



US 20040182315A1

(19) **United States**

(12) **Patent Application Publication**

Laflamme, JR. et al.

(10) **Pub. No.: US 2004/0182315 A1**

(43) **Pub. Date: Sep. 23, 2004**

(54) **REDUCED MAINTENANCE CHEMICAL OXIDE REMOVAL (COR) PROCESSING SYSTEM**

(75) Inventors: **Arthur H. Laflamme JR.**, Rowley, MA (US); **Thomas Hamelin**, Georgetown, MA (US); **Jay Wallace**, Danvers, MA (US)

Correspondence Address:
PILLSBURY WINTHROP, LLP
P.O. BOX 10500
MCLEAN, VA 22102 (US)

(73) Assignee: **Tokyo Electron Limited**, Tokyo (JP)

(21) Appl. No.: **10/736,991**

(22) Filed: **Dec. 17, 2003**

Related U.S. Application Data


(60) Provisional application No. 60/454,597, filed on Mar. 17, 2003. Provisional application No. 60/454,642, filed on Mar. 17, 2003. Provisional application No. 60/454,641, filed on Mar. 17, 2003. Provisional application No. 60/454,644, filed on Mar. 17, 2003.

Publication Classification

(51) **Int. Cl.⁷** **C23C 16/00**
(52) **U.S. Cl.** **118/715**

(57) **ABSTRACT**

A chemical oxide removal (COR) processing system is presented, wherein the COR processing system includes a first treatment chamber and a second treatment chamber. The first treatment chamber comprises a chemical treatment chamber that provides a temperature controlled chamber having a protective barrier. The second treatment chamber comprises a heat treatment chamber that provides a temperature-controlled chamber having a protective barrier.






FIG. 1




FIG. 2




FIG. 3




FIG. 4




FIG. 5




FIG. 6




FIG. 7




FIG. 8A




FIG. 8B




FIG. 9

REDUCED MAINTENANCE CHEMICAL OXIDE REMOVAL (COR) PROCESSING SYSTEM

CROSS-REFERENCE TO RELATED APPLICATIONS

[0001] This application is related to pending U.S. Patent Application Serial No. 60/454,597, entitled "Processing System and Method For Treating a Substrate", Attorney docket no. 071469/0301073, filed on Mar. 17, 2003; pending U.S. Patent Application Serial No. 60/454,642, entitled "Processing System and Method For Chemically Treating a Substrate", Attorney docket no. 071469/0301087, filed on Mar. 17, 2003; pending U.S. Patent Application Serial No. 60/454,641, entitled "Processing System and Method For Thermally Treating a Substrate", Attorney docket no. 071469/0301088, filed on Mar. 17, 2003; and pending U.S. Patent Application Serial No. 60/454,644, entitled "Method and Apparatus For Thermally Insulating Adjacent Temperature Controlled Chambers", Attorney docket no. 071469/0292055, filed on Mar. 17, 2003. The entire contents of all of those applications are herein incorporated by reference in their entirety.

FIELD OF THE INVENTION

[0002] The present invention relates to a system and method for processing a substrate, and more particularly to a system and method for protecting chemical and thermal treatment chambers.

BACKGROUND OF THE INVENTION

[0003] During semiconductor processing, a dry plasma etch process can be utilized to remove or etch material along fine lines, within vias, or contacts patterned on a silicon substrate. The plasma etch process generally involves positioning a semiconductor substrate with an overlying patterned, protective layer, for example a photoresist layer, in a processing chamber. Once the substrate is positioned within the chamber, an ionizable, dissociative gas mixture is introduced within the chamber at a pre-specified flow rate, while a vacuum pump is throttled to achieve an ambient process pressure. Thereafter, a plasma is formed when a fraction of the gas species present are ionized by electrons heated via the transfer of radio frequency (RF) power either inductively or capacitively, or microwave power using, for example, electron cyclotron resonance (ECR). Moreover, the heated electrons serve to dissociate some species of the ambient gas species and create reactant specie(s) suitable for the exposed surface etch chemistry. Once the plasma is formed, selected surfaces of the substrate are etched by the plasma. The process is adjusted to achieve appropriate conditions, including an appropriate concentration of desirable reactant and ion populations to etch various features (e.g., trenches, vias, contacts, gates, etc.) in the selected regions of the substrate. Such substrate materials where etching is required include silicon dioxide (SiO₂), low-k dielectric materials, poly-silicon, and silicon nitride.

[0004] During material processing, etching such features generally comprises the transfer of a pattern formed within a mask layer to the underlying film within which the respective features are formed. The mask can, for example, comprise a light-sensitive material such as (negative or positive) photo-resist, multiple layers including such layers

as photo-resist and an anti-reflective coating (ARC), or a hard mask formed from the transfer of a pattern in a first layer, such as photo-resist, to the underlying hard mask layer.

SUMMARY OF THE INVENTION

[0005] The present invention relates to a system and method for protecting a chemical treatment chamber and/or heat treatment chamber.

[0006] In one aspect of the invention, a processing system is described for performing material removal on a substrate comprising a first treatment system and a second treatment system, wherein the first and second treatment systems are coupled to one another. The first treatment system comprises a chemical treatment system, and a protective barrier formed on at least one component of the chemical treatment system. The second treatment system comprises a thermal treatment system and a protective barrier formed on at least one component of the thermal treatment system.

BRIEF DESCRIPTION OF THE DRAWINGS

[0007] In the drawings:

[0008] **FIG. 1** illustrates a schematic representation of a processing system according to an embodiment of the present invention;

[0009] **FIG. 2** shows a schematic cross-sectional view of a processing system according to an embodiment of the present invention;

[0010] **FIG. 3** shows a schematic cross-sectional view of a chemical treatment system according to an embodiment of the present invention;

[0011] **FIG. 4** shows a schematic perspective view of a chemical treatment system according to another embodiment of the present invention;

[0012] **FIG. 5** shows a schematic cross-sectional view of a thermal treatment system according to an embodiment of the present invention;

[0013] **FIG. 6** shows a schematic perspective view of a thermal treatment system according to another embodiment of the present invention;

[0014] **FIG. 7** illustrates a schematic cross-sectional view of a substrate holder according to an embodiment of the present invention;

[0015] **FIG. 8A** illustrates a schematic cross-sectional view of a gas distribution system according to another embodiment of the present invention;

[0016] **FIG. 8B** presents an expanded view of the gas distribution system shown in **FIG. 8A** according to an embodiment of the present invention; and

[0017] **FIG. 9** shows a substrate lifter assembly according to an embodiment of the present invention.

DETAILED DESCRIPTION OF SEVERAL EMBODIMENTS

[0018] In material processing methodologies, pattern etching comprises the application of a thin layer of light-sensitive material, such as photoresist, to an upper surface of

a substrate, that is subsequently patterned in order to provide a mask for transferring this pattern to the underlying thin film during etching. The patterning of the light-sensitive material generally involves exposure of the light-sensitive material by a radiation source through a reticle (and associated optics) using, for example, a micro-lithography system, followed by the removal of the irradiated regions of the light-sensitive material (as in the case of positive photoresist), or non-irradiated regions (as in the case of negative resist) using a developing solvent.

[0019] Additionally, multi-layer and hard masks can be implemented for etching features. For example, when etching features using a hard mask, the mask pattern in the light-sensitive layer is transferred to the hard mask layer using a separate etch step preceding the main etch step. The hard mask can, for example, be selected from several materials for silicon processing including silicon dioxide (SiO_2), silicon nitride (Si_3N_4), and carbon, for example.

[0020] In order to reduce the feature size formed, the hard mask can be trimmed laterally using, for example, a two-step process involving a chemical treatment of the exposed surfaces of the hard mask layer in order to alter the surface chemistry of the hard mask layer, and a thermal treatment of the exposed surfaces of the hard mask layer in order to desorb the altered surface chemistry.

[0021] FIG. 1 illustrates a schematic representation of a processing system according to an embodiment of the present invention. In the illustrated embodiment shown in FIG. 1, a processing system 1 for processing a substrate using, for example, mask layer trimming is shown. Processing system 1 can comprise a first treatment system 10, and a second treatment system 20 coupled to the first treatment system 10. For example, the first treatment system 10 can comprise a thermal treatment system, and the second treatment system 20 can comprise a chemical treatment system. Also, as illustrated in FIG. 1, a transfer system 30 can be coupled to the first treatment system 10 in order to transfer substrates into and out of the first treatment system 10 and the second treatment system 20, and exchange substrates with a multi-element manufacturing system 40.

[0022] The first and second treatment systems 10, 20, and the transfer system 30 can, for example, comprise a processing element coupled to the multi-element manufacturing system 40. The multi-element manufacturing system 40 can permit the transfer of substrates to and from processing elements including such devices as etch systems, deposition systems, coating systems, patterning systems, metrology systems, etc. In order to isolate the processes occurring in the first and second systems, an isolation assembly 50 can be utilized to couple each system. For instance, the isolation assembly 50 can comprise at least one of a thermal insulation assembly to provide thermal isolation, and a gate valve assembly to provide vacuum isolation. In alternate embodiments, treatment systems 10 and 20, and transfer system 30 can be placed in any sequence.

[0023] In addition, a controller 60 can be coupled to the first treatment system 10, the second treatment system 20, and the transfer system 30. For example, controller 60 can be used to control the first treatment system 10, the second treatment system 20, and the transfer system 30. Also, controller 60 can be coupled to a control element (not shown) in the multi-element manufacturing system 40.

[0024] Alternately, the first treatment system 10, the second treatment system 20, and the transfer system 30 can be configured differently. For example, a stacked arrangement or a side-by-side arrangement can be used.

[0025] In general, at least one of the first treatment system 10 and the second treatment system 20 of the processing system 1 depicted in FIG. 1 comprises at least two transfer openings to permit the passage of the substrate therethrough. For example, as depicted in FIG. 1, the first treatment system 10 comprises two transfer openings, the first transfer opening permits the passage of the substrate between the first treatment system 10 and the transfer system 30 and the second transfer opening permits the passage of the substrate between the first treatment system 10 and the second treatment system 20. Alternately, each treatment system can comprise at least one transfer opening to permit the passage of the substrate therethrough.

[0026] FIG. 2 shows a schematic cross-sectional view of a processing system according to an embodiment of the present invention. In the illustrated embodiment, a processing system 200 for performing chemical treatment and thermal treatment of a substrate is shown. Processing system 200 can comprise a thermal treatment system 210, and a chemical treatment system 220 coupled to the thermal treatment system 210. The thermal treatment system 210 can comprise a thermal treatment chamber 211, which can be temperature-controlled. The chemical treatment system 220 can comprise a chemical treatment chamber 221, which can be temperature-controlled. The thermal treatment chamber 211 and the chemical treatment chamber 221 can be thermally insulated from one another using a thermal insulation assembly 230, and vacuum isolated from one another using a gate valve assembly 296, to be described in greater detail below.

[0027] FIG. 3 shows a schematic cross-sectional view of a chemical treatment system according to an embodiment of the present invention. As illustrated in FIGS. 2 and 3, the chemical treatment system 220 can further comprise a temperature controlled substrate holder 240 configured to be substantially thermally isolated from the chemical treatment chamber 221 and configured to support a substrate 242 and a centering ring 243. The centering ring 243 can be made of polytetrafluoroethylene (PTFE) and/or tetrafluoroethylene (TFE). Also, substrate holder 240 can comprise a protective barrier 241 formed on one or more exposed surfaces of the substrate holder 240. In one embodiment, the protective barrier 241 can be created by anodizing a metal, and impregnating the anodized surface with PTFE and/or TFE. For example, a protective barrier can be formed by hard anodizing aluminum or hard anodizing an aluminum alloy and impregnating the hard-anodized surface with TFE and/or PTFE. In an alternate embodiment, protective barrier 241 is not required.

[0028] In an alternate embodiment of the present invention, the protective barrier 241 can comprise at least one of Al_2O_3 , Yttria (Y_2O_3), Sc_2O_3 , Sc_2F_3 , YF_3 , La_2O_3 , CeO_2 , Eu_2O_3 , and DyO_3 . In additional embodiments of the present invention, the protective barrier 222 can comprise at least one of a column-III element (column III of periodic table) and a Lanthanoid element. In another embodiment of the present invention, the column-III element can comprise at least one of Yttrium, Scandium, and Lanthanum. In another

embodiment of the present invention, the Lanthanum element can comprise at least one of Cerium, Dysprosium, and Europium.

[0029] In an embodiment of the present invention, the protective barrier 241 can have a minimum thickness, wherein the minimum thickness can be specified as constant across at least one of the interior surfaces. In another embodiment, the minimum thickness can be variable across the interior surfaces. Alternately, the minimum thickness can be constant over a first portion of a surface and variable over a second portion of the surface. For example, a variable thickness can occur on a curved surface, on a corner, or in a hole. For example, the minimum thickness can range from about 0.5 microns to about 500 microns. Alternatively; the minimum thickness can range from about 100 microns to about 200 microns; or the minimum thickness can be at least about 120 microns.

[0030] Furthermore, substrate holder 240 can comprise a protective barrier 245 formed on the top surface of the substrate holder 240. Protective barrier 245 can be made of a material selected from the same range of materials and can have the same thickness as was described for protective barrier 241. Alternatively protective barrier 245 is not required.

[0031] Also, the chemical treatment system 220 can further comprise a vacuum pumping system 250 coupled to the chemical treatment chamber 221 to control the pressure in the chemical treatment chamber 221, and an upper assembly 260 that can comprise a gas distribution system for introducing a process gas into a process space 262 within the chemical treatment chamber 221.

[0032] In addition, chemical treatment chamber 221 can comprise a protective barrier 222 formed on one or more interior surfaces of the chemical treatment chamber 221. Protective barrier 222 can be made of a material selected from the same range of materials and can have the same thickness as was described for protective barrier 241. Alternatively protective barrier 222 is not required.

[0033] Furthermore, a protective barrier 261 can be formed on one or more interior surfaces of the upper assembly 260. Protective barrier 261 can be made of a material selected from the same range of materials and can have the same thickness as was described for protective barrier 241. Alternatively protective barrier 261 is not required.

[0034] The present invention may include a multi-step process that can include, for example, preparing one or more surfaces to receive the protective barrier, and then forming the protective barrier on those surfaces.

[0035] As illustrated in FIGS. 2 and 5, the thermal treatment system 210 can further comprise a temperature controlled substrate holder 270 mounted within the thermal treatment chamber 211 and configured to be substantially thermally insulated from the thermal treatment chamber 211 and configured to support a substrate 242', a vacuum pumping system 280 to evacuate the thermal treatment chamber 211, a substrate lifter assembly 290, and a drive system 530 coupled to the thermal treatment chamber 211. Lifter assembly 290 can vertically translate the substrate 242" between a holding plane (solid lines) and the substrate holder 270

(dashed lines), or a transfer plane located therebetween. The thermal treatment chamber 211 can further comprise an upper assembly 284.

[0036] In addition, thermal treatment chamber 211 can comprise a protective barrier 212 formed on one or more interior surfaces of the thermal treatment chamber 211. Protective barrier 212 can be made of a material selected from the same range of materials and can have the same thickness as was described for protective barrier 241. Alternatively protective barrier 212 is not required.

[0037] Additionally, the thermal treatment chamber 211, chemical treatment chamber 221, and thermal insulation assembly 230 define a common opening 294 through which a substrate can be transferred. During processing, the common opening 294 can be sealed closed using a gate valve assembly 296 in order to permit independent processing in the two chambers 211, 221.

[0038] Furthermore, a transfer opening 298 can be formed in the thermal treatment chamber 211 in order to permit substrate exchanges with a transfer system as illustrated in FIG. 1. A second thermal insulation assembly 231 can be implemented to thermally insulate the thermal treatment chamber 221 from a transfer system (not shown). Although the opening 298 is illustrated as part of the thermal treatment chamber 211 (consistent with FIG. 1), the transfer opening 298 can be formed in the chemical treatment chamber 221 and not the thermal treatment chamber 211 (reverse chamber positions as shown in FIG. 1).

[0039] Also, exposed surfaces of the gate valve assembly 296, the common opening 294, and/or the transfer opening 298 can be provided with a protective barrier (not shown). The protective barrier can be made of a material selected from the same range of materials and can have the same thickness as was described for protective barrier 241. Alternatively the protective barrier is not required.

[0040] As illustrated in FIGS. 2 and 3, the chemical treatment system 220 can comprise a substrate holder 240, and a substrate holder assembly 244 in order to provide several operational functions for thermally controlling and processing substrate 242. The substrate holder 240 and substrate holder assembly 244 can comprise an electrostatic clamping system (or mechanical clamping system) in order to electrically (or mechanically) clamp substrate 242 to the substrate holder 240. For example, the clamping system can comprise a top surface comprising PTFE and/or TFE.

[0041] Furthermore, substrate holder 240 can, for example, further include a cooling system having a recirculating coolant flow that receives heat from substrate holder 240 and transfers heat to a heat exchanger system (not shown), or when heating, transfers heat from the heat exchanger system. Moreover, a heat transfer gas can, for example, be delivered to the backside of substrate 242 via a backside gas system to improve the gas-gap thermal conductance between substrate 242 and substrate holder 240. For instance, the heat transfer gas supplied to the back-side of substrate 242 can comprise an inert gas such as helium, argon, xenon, krypton, a process gas such as CF₄, C₄F₈, C₅F₈, C₄F₆, etc., or other gas such as oxygen, nitrogen, or hydrogen. Such a system can be utilized when temperature control of the substrate is required at elevated or reduced temperatures. For example, the backside gas system can

comprise a multi-zone gas distribution system such as a two-zone (center-edge) system, wherein the backside gas gap pressure can be independently varied between the center and the edge of substrate 242. In other embodiments, heating/cooling elements, such as resistive heating elements, or thermo-electric heaters/coolers can be included in the substrate holder 240, as well as the chamber wall of the chemical treatment chamber 221.

[0042] FIG. 7 illustrates an embodiment of a temperature controlled substrate holder 300 which performs several of the above-identified functions. Substrate holder 300 can comprise a chamber mating component 310 coupled to a lower wall of the chemical treatment chamber 221, an insulating component 312 coupled to the chamber mating component 310, and a temperature control component 314 coupled to the insulating component 312. The chamber mating and temperature control components 310, 314 can be fabricated from an electrically and thermally conducting material such as aluminum, stainless steel, nickel, etc. The insulating component 312 can be fabricated from a thermally-resistant material having a relatively lower thermal conductivity such as quartz, alumina, TFE, PTFE, etc.

[0043] In addition, chamber mating and temperature control components 310, 314 can comprise protective barriers 311, 315 formed on one or more exterior surfaces thereof. Also, insulating component 312 can comprise a protective barrier 313 formed on one or more exterior surfaces thereof. Protective barriers 311, 313 and 315 can each be made of a material selected from the same range of materials and can have the same thickness as was described for protective barrier 241. Alternatively one or more of protective barriers 311, 313 and 315 is not required.

[0044] The temperature control component 314 can comprise temperature control elements such as cooling channels, heating channels, resistive heating elements, or thermo-electric elements. For example, as illustrated in FIG. 7, the temperature control component 314 can comprise a coolant channel 320 having a coolant inlet 322 and a coolant outlet 324. The coolant channel 320 can, for example, be a spiral passage within the temperature control component 314 that permits a flow of coolant, such as water, Fluorinert, Galden HT-135, etc., in order to provide conductive-convective cooling of the temperature control component 314. Alternatively, the temperature control component 314 can comprise an array of thermo-electric elements capable of heating or cooling a substrate depending upon the direction of electrical current flow through the respective elements. An exemplary thermoelectric element is one commercially available from Advanced Thermoelectric, Model ST-127-1.4-8.5M (a 40 mm by 40 mm by 3.4 mm thermoelectric device capable of a maximum heat transfer power of 72 W).

[0045] Additionally, the substrate holder 300 can further comprise an electrostatic clamp (ESC) 328 comprising a ceramic layer 330, a clamping electrode 332 embedded therein, and a high-voltage (HV) DC voltage supply 334 coupled to the clamping electrode 332 using an electrical connection 336. The ESC 328 can, for example, be monopolar, or bi-polar. The design and implementation of such a clamp is well known to those skilled in the art of electrostatic clamping systems. In one embodiment, a protective barrier 243 can be formed on the upper surface of the substrate holder. Protective barrier 243 can be made of a

material selected from the same range of materials and can have the same thickness as was described for protective barrier 241. Alternatively protective barrier 243 is not required.

[0046] Additionally, the substrate holder 300 can further comprise a back-side gas supply system 340 for supplying a heat transfer gas, such as an inert gas including helium, argon, xenon, krypton, a process gas including CF_4 , C_4F_8 , C_5F_8 , C_4F_6 , etc., or other gas including oxygen, nitrogen, or hydrogen, to the backside of substrate 242 through at least one gas supply line 342. The backside gas supply system 340 can be a multi-zone supply system such as a two-zone (center-edge) system, wherein the backside pressure can be varied radially from the center to edge.

[0047] The insulating component 312 can further comprise a thermal insulation gap 350 in order to provide additional thermal insulation between the temperature control component 314 and the underlying mating component 310. The thermal insulation gap 350 can be evacuated using a pumping system (not shown) or a vacuum line as part of vacuum pumping system 250, and/or coupled to a gas supply (not shown) in order to vary its thermal conductivity. The gas supply can, for example, be the backside gas supply 340 utilized to couple heat transfer gas to the backside of the substrate 242.

[0048] The mating component 310 can further comprise a lift pin assembly 360 capable of raising and lowering three or more lift pins 362 in order to vertically translate substrate 242 to and from an upper surface of the substrate holder 300 and a transfer plane in the processing system.

[0049] Each component 310, 312, and 314 can further comprise fastening devices (such as bolts and tapped holes) in order to affix one component to another, and to affix the substrate holder 300 to the chemical treatment chamber 221. Furthermore, each component 310, 312, and 314 facilitates the passage of the above-described utilities to the respective component, and vacuum seals, such as elastomer O-rings, are utilized where necessary to preserve the vacuum integrity of the processing system.

[0050] The temperature of the temperature-controlled substrate holder 240 can be monitored using a temperature-sensing device 344 such as a thermocouple (e.g. a K-type thermocouple, Pt sensor, etc.). Furthermore, a controller can utilize the temperature measurement as feedback to the substrate holder assembly 244 in order to control the temperature of substrate holder 240. For example, at least one of a fluid flow rate, fluid temperature, heat transfer gas type, heat transfer gas pressure, clamping force, resistive heater element current or voltage, thermoelectric device current or polarity, etc. can be adjusted in order to affect a change in the temperature of substrate holder 240.

[0051] Referring again to FIGS. 2 and 3, chemical treatment system 220 can comprise an upper assembly 260 having a gas distribution system.

[0052] In the embodiment shown in FIGS. 8A and 8B (expanded view of FIG. 8A), a gas distribution system 420 for distributing a process gas, which can comprise at least two gases, comprises a gas distribution assembly 424, a first gas distribution plate 430 coupled to the gas distribution assembly 424 and configured to couple a first gas to the process space of chemical treatment chamber 221, and a

second gas distribution plate **432** coupled to the first gas distribution plate **430** and configured to couple a second gas to the process space of chemical treatment chamber **221**. The first gas distribution plate **430**, when coupled to the gas distribution assembly **424**, forms a first gas distribution plenum **440**. Additionally, the second gas distribution plate **432**, when coupled to the first gas distribution plate **430** forms a second gas distribution plenum **442**. Although not shown, gas distribution plenums **440**, **442** can comprise one or more gas distribution baffle plates. The second gas distribution plate **432** can further comprise a first array of one or more orifices **444** coupled to and coincident with an array of one or more passages **446** formed within the first gas distribution plate **430**, and a second array of one or more orifices **448**. The first array of one or more orifices **444**, in conjunction with the array of one or more passages **446**, are configured to distribute the first gas from the first gas distribution plenum **440** to the process space of chemical treatment chamber **221**. The second array of one or more orifices **448** is configured to distribute the second gas from the second gas distribution plenum **442** to the process space of chemical treatment chamber **221**. The process gas can, for example, comprise NH_3 , HF, H_2 , O_2 , CO, CO_2 , Ar, He, etc. Each orifice **444**, **448** has a diameter and a length, wherein the diameter can range from about 0.1 mm to about 10 cm, and the length can range from about 0.5 mm to about 5 cm. In addition, each orifice can have a protective barrier **261** on one or more surfaces exposed to the processing space. Protective barrier **261** can be made of a material selected from the same range of materials and can have the same thickness as was described for protective barrier **241**. Alternatively protective barrier **261** is not required. As a result of this arrangement, the first gas and the second gas are independently introduced to the process space without any interaction except in the process space.

[0053] Referring again to FIGS. 2 and 3, chemical treatment system **220** can further comprise a temperature controlled chemical treatment chamber **221** that is maintained at an elevated temperature. For example, a wall temperature control element **266** can be coupled to a wall temperature control unit **268**, and the wall temperature control element **266** can be configured to couple to the chemical treatment chamber **221**. The temperature control element can, for example, comprise a resistive heater element and/or a cooling element. The temperature of the chemical treatment chamber **221** can be monitored using a temperature-sensing device such as a thermocouple (e.g. a K-type thermocouple, Pt sensor, etc.). Furthermore, a controller can utilize the temperature measurement as feedback to the wall temperature control unit **268** in order to control the temperature of the chemical treatment chamber **221**.

[0054] Referring again to FIG. 3, chemical treatment system **220** can further comprise an upper assembly **260** that can include a temperature controlled gas distribution system that can be used to maintain the upper assembly and/or the process gas at a selected temperature. For example, a temperature control element **267** can be coupled to a gas distribution system temperature control unit **269**, and the temperature control element **267** can be configured to be coupled to the gas distribution system **260**. The temperature control element can, for example, comprise a resistive heater element and/or cooling element. The temperature of the upper assembly and/or process gas can be monitored using a temperature-sensing device such as a thermocouple (e.g. a

K-type thermocouple, Pt sensor, etc.). Furthermore, a controller can utilize the temperature measurement as feedback to the gas distribution system temperature control unit **269** in order to control the temperature of the upper assembly and/or process gas.

[0055] Referring still to FIGS. 2 and 3, vacuum pumping system **250** can comprise a vacuum pump **252** and a gate valve **254** for throttling the chamber pressure. Vacuum pump **252** can, for example, include a turbo-molecular vacuum pump (TMP) capable of a pumping speed up to 5000 liters per second (and greater). For example, the TMP can be a Seiko STP-A803 vacuum pump, or an Ebara ET1301W vacuum pump. TMPs are useful for low pressure processing, typically less than about 50 mTorr. For high pressure (i.e., greater than about 100 mTorr) or low throughput processing (i.e., no gas flow), a mechanical booster pump and dry roughing pump can be used.

[0056] Referring again to FIG. 3, chemical treatment system **220** can further comprise a controller **235** having a microprocessor, memory, and a digital I/O port capable of generating control voltages sufficient to communicate and activate inputs to chemical treatment system **220** as well as monitor outputs from chemical treatment system **220** such as temperature and pressure sensing devices. Moreover, controller **235** can be coupled to and can exchange information with substrate holder assembly **244**, gas distribution system **260**, vacuum pumping system **250**, gate valve assembly **296**, wall temperature control unit **268**, and gas distribution system temperature control unit **269**. For example, a program stored in the memory can be utilized to activate the inputs to the aforementioned components of chemical treatment system **220** according to a process recipe. One example of controller **235** is a DELL PRECISION WORKSTATION 610™, available from Dell Corporation, Austin, Tex.

[0057] In one example, FIG. 4 presents a chemical treatment system **1220** further comprising a lid **1222** with a handle **1223**, at least one clasp **1224**, and at least one hinge **1227**, an optical viewport **1225**, and at least one pressure sensing device **1226**.

[0058] Optical viewport **1225** can comprise an optical window (not shown), and an optical window flange (not shown) can couple the optical window to the chamber wall. Optical monitoring system **202** can permit monitoring of optical emission from the processing space through optical viewport **1225**. For example, a photodiode, a photomultiplier tube, a CCD, CID, or other solid state detector can be used. However, other optical devices capable of analyzing optical emissions, can be used as well. The monitoring system **202** can provide information to controller in order to adjust chamber conditions before, during, or after processing. In an alternate embodiment, optical monitoring system **202** can also include a light source, such as a laser.

[0059] Monitoring system component status using an optical monitoring system can include determining if the intensity level of an optical signal reflected from a system component exceeds a threshold value, arriving at a determination of whether the system component needs to be cleaned and/or replaced, and based on the determination, either continuing with the process or stopping the process.

[0060] For example, the status of a system component can be determined during a plasma process, by monitoring

optical emission from a material deposited on a surface of a system component. One possible method for determining the status of contamination material on a system component is to use optical emission spectroscopy (OES) to monitor a wavelength range where one or more of the material's reflectivity characteristics change. During processing, a material can coat a system component and the thickness of the material can be determined by monitoring the optical characteristics of the deposited material, and these optical characteristics can be monitored during the plasma process. When an optical characteristic crosses a specified threshold value, a determination can be made whether or not to clean the system component, and based on the determination, the process can be continued or stopped.

[0061] As described in FIGS. 2 and 5, the thermal treatment system 210 can further comprise a temperature controlled substrate holder 270. The substrate holder 270 comprises a pedestal 272 thermally insulated from the thermal treatment chamber 211 using a thermal barrier 274. For example, the substrate holder 270 can be fabricated from aluminum, stainless steel, or nickel, and the thermal barrier 274 can be fabricated from a thermal insulator such as PTFE, TFE, alumina, or quartz. The substrate holder 270 can further comprise a temperature control element 276 embedded therein and a substrate holder temperature control unit 278 coupled thereto. The temperature control element 276 can, for example, comprise a resistive heater element and/or cooling element.

[0062] The temperature of the substrate holder 270 can be monitored using a temperature-sensing device such as a thermocouple (e.g. a K-type thermocouple) or an optical fiber thermometer. Furthermore, a controller 275 can utilize the temperature measurement as feedback to the substrate holder temperature control unit 278 in order to control the temperature of the substrate holder 270.

[0063] Referring again to FIG. 5, thermal treatment system 210 can further comprise a temperature controlled thermal treatment chamber 211 that is maintained at a selected temperature. For example, a thermal wall control element 283 can be coupled to a thermal wall temperature control unit 281, and the thermal wall control element 283 can be coupled to the thermal treatment chamber 211. The control element can, for example, comprise a resistive heater element such as a tungsten, nickel-chromium alloy, aluminum-iron alloy, or aluminum nitride filament. Alternatively, or in addition, cooling elements may be employed in thermal treatment chamber 211. The temperature of the thermal treatment chamber 211 can be monitored using a temperature-sensing device such as a thermocouple (e.g. a K-type thermocouple, Pt sensor, etc.). Furthermore, controller 275 can utilize the temperature measurement as feedback to the thermal wall temperature control unit 281 in order to control the temperature of the thermal treatment chamber 211.

[0064] Referring again to FIG. 5, thermal treatment system 210 can further comprise a temperature controlled upper assembly 284 that can be maintained at a selected temperature. For example, an upper assembly temperature control element 285 can be coupled to an upper assembly temperature control unit 286, and the upper assembly temperature control element 285 can be coupled to the upper assembly 284. The temperature control element can, for example, comprise a resistive heater element such as a tungsten,

nickel-chromium alloy, aluminum-iron alloy, or aluminum nitride filament. The temperature of the upper assembly 284 can be monitored using a temperature-sensing device such as a thermocouple (e.g. a K-type thermocouple, Pt sensor, etc.). Furthermore, controller 275 can utilize the temperature measurement as feedback to the upper assembly temperature control unit 286 in order to control the temperature of the upper assembly 284. Upper assembly 284 may additionally or alternatively include a cooling element.

[0065] Referring again to FIGS. 2 and 5, thermal treatment system 210 can further comprise a substrate lifter assembly 290 and drive system 530. Substrate lifter assembly 290 can be configured to lower a substrate 242' to an upper surface of the substrate holder 270, as well as raise a substrate 242" from an upper surface of the substrate holder 270 to a holding plane, or a transfer plane therebetween. At the transfer plane, substrate 242" can be exchanged with a transfer system utilized to transfer substrates into and out of the chemical and thermal treatment chambers 221, 211. At the holding plane, substrate 242" can be cooled while another substrate is exchanged between the transfer system and the chemical and thermal treatment chambers 221, 211.

[0066] As shown in FIG. 9, the substrate lifter assembly 290 can comprise a blade 500 having three or more tabs 510, a flange 520 for coupling the substrate lifter assembly 290 to the thermal treatment chamber 211, and a drive system 530 for permitting vertical translation of the blade 500 within the thermal treatment chamber 211. The tabs 510 are configured to grasp substrate 242" in a raised position, and to recess within receiving cavities 540 (FIG. 5) formed within the substrate holder 270 when in a lowered position. The drive system 530 can, for example, be a pneumatic drive system designed to meet various specifications including cylinder stroke length, cylinder stroke speed, position accuracy, non-rotation accuracy, etc., the design of which is known to those skilled in the art of pneumatic drive system design.

[0067] Furthermore, a protective barrier 512 can be formed on one or more surfaces of the blade 500. Protective barrier 512 can be made of a material selected from the same range of materials and can have the same thickness as was described for protective barrier 241. Alternatively protective barrier 512 is not required.

[0068] Referring still to FIGS. 2 and 5, thermal treatment system 210 can further comprise a vacuum pumping system 280. Vacuum pumping system 280 can, for example, comprise a vacuum pump, and a throttle valve such as a gate valve or butterfly valve. The vacuum pump can, for example, include a turbo-molecular vacuum pump (TMP) capable of a pumping speed up to 5000 liters per second (and greater). TMPs are useful for low pressure processing, typically less than about 50 mTorr. For high pressure processing (i.e., greater than about 100 mTorr), a mechanical booster pump and dry roughing pump can be used.

[0069] Referring again to FIG. 5, thermal treatment system 210 can further comprise a controller 275 having a microprocessor, memory, and a digital I/O port capable of generating control voltages sufficient to communicate and activate inputs to thermal treatment system 210 as well as monitor outputs from thermal treatment system 210. Moreover, controller 275 can be coupled to and can exchange information with substrate holder temperature control unit 278, upper assembly temperature control unit 286, upper

assembly **284**, thermal wall temperature control unit **281**, vacuum pumping system **280**, and substrate lifter assembly **290**. For example, a program stored in the memory can be utilized to activate the inputs to the aforementioned components of thermal treatment system **210** according to a process recipe. One example of controller **275** is a DELL PRECISION WORKSTATION 610™, available from Dell Corporation, Austin, Tex.

[0070] In an alternate embodiment, controllers **235** and **275** can be the same controller.

[0071] As one example, FIG. 6 presents a thermal treatment system **2210** further comprising a lid **2212** with a handle **2213** and at least one hinge **2214**, an optical viewport **2215**, at least one pressure-sensing device **2216**, at least one alignment device **2235**, and at least one fastening device **2236**. Additionally, the thermal treatment system **2210** can further comprise a substrate detection system **2217** in order to identify whether a substrate is located in the holding plane. The substrate detection system can, for example, comprise a Keyence digital laser sensor.

[0072] In an example, the processing system **200**, as depicted in FIG. 2, can be a chemical oxide removal (COR) system for trimming an oxide hard mask. The processing system **200** can comprise chemical treatment system **220** for chemically treating exposed surface layers, such as oxide surface layers, on a substrate, whereby adsorption of the process chemistry on the exposed surfaces affects chemical alteration of the surface layers. Additionally, the processing system **200** can comprise thermal treatment system **210** for thermally treating the substrate, whereby the substrate temperature is elevated in order to desorb (or evaporate) the chemically altered exposed surface layers on the substrate.

[0073] In the chemical treatment system **220**, the process space **262** (see FIG. 2) is evacuated, and a process gas comprising HF and NH₃ is introduced. The processing pressure can range from about 1 to about 100 mTorr, or alternatively, from about 2 to about 25 mTorr. The process gas flow rates can range from about 1 to about 200 sccm for each specie, or alternatively, from about 10 to about 100 sccm. Although the vacuum pumping system **250** is shown in FIGS. 2 and 3 to access the chemical treatment chamber **221** from the side, a uniform (three-dimensional) pressure field can be achieved. Table I illustrates the dependence of the pressure uniformity at the substrate surface as a function of processing pressure and the spacing between the gas distribution system **260** and the upper surface of substrate **242**.

TABLE I

(%)	h (spacing)				
	50 mm	62	75	100	200
Pressure					
20 mTorr	0.6	NA	NA	NA	NA
9	NA	NA	0.75	0.42	NA
7	3.1	1.6	1.2	NA	NA
4	5.9	2.8	NA	NA	NA
3	NA	3.5	3.1	1.7	0.33

[0074] Additionally, the chemical treatment chamber **221** can be heated to a temperature ranging from about 30° to about 100° C. For example, the temperature can be about

40° C. Additionally, the gas distribution system can be heated to a temperature ranging from about 40° to about 100° C. For example, the temperature can be about 50° C. The substrate can be maintained at a temperature ranging from about 10° to about 50° C. For example, the substrate temperature can be about 20° C.

[0075] In the thermal treatment system **210**, the thermal treatment chamber **211** can be heated to a temperature ranging from about 50° to about 100° C. For example, the temperature can be about 80° C. Additionally, the upper assembly can be heated to a temperature ranging from about 50° to about 100° C. For example, the temperature can be about 80° C. The substrate can be heated to a temperature in excess of about 100° C. For example, the temperature can range from about 100° to about 200° C. Alternatively, the temperature can be about 135° C.

[0076] The chemical treatment and thermal treatment described herein can produce an etch amount of an exposed oxide surface layer in excess of about 10 nm per 60 seconds of chemical treatment for thermal oxide, an etch amount of the exposed oxide surface layer in excess of about 25 nm per 180 seconds of chemical treatment for thermal oxide, and an etch amount of the exposed oxide surface layer in excess of about 10 nm per 180 seconds of chemical treatment of ozone TEOS. The treatments can also produce an etch variation across the substrate of less than about 2.5%.

[0077] Although only certain embodiments of this invention have been described in detail above, those skilled in the art will readily appreciate that many modifications are possible in the embodiments without materially departing from the novel teachings and advantages of this invention. Accordingly, all such modifications are intended to be included within the scope of this invention.

What is claimed is:

1. A reduced maintenance processing system for treating a substrate comprising:
 - a chemical treatment system for chemically altering exposed surface layers on the substrate comprising a temperature controlled chemical treatment chamber having a protective barrier formed on at least a portion of an interior surface;
 - a thermal treatment system for thermally treating the chemically altered surface layers on the substrate, the thermal treatment system comprising a temperature controlled thermal treatment chamber having a protective barrier formed on at least a portion of an interior surface; and
 - a thermal insulation assembly coupled to the thermal treatment system and the chemical treatment system.
2. The processing system as claimed in claim 1, wherein the thermal insulation assembly comprises a protective barrier on at least one exposed surface.
3. The processing system as claimed in claim 1, wherein:
 - the chemical treatment system further comprises a temperature controlled substrate holder mounted within the chemical treatment chamber and having a protective barrier formed on at least a portion of an exposed surface, a vacuum pumping system coupled to the chemical treatment chamber, and a gas distribution plate comprising a plurality of gas injection orifices and

having a protective barrier formed on at least a portion of an exposed surface of the gas distribution plate and at least a portion of an exposed surface of each orifice, wherein the gas distribution plate is coupled to a temperature controlled gas distribution system for introducing a process gas into the chemical treatment chamber;

the thermal treatment system further comprises a temperature controlled substrate holder mounted within the thermal treatment chamber and having a protective barrier formed on at least a portion of an exposed surface, and a vacuum pumping system coupled to the thermal treatment chamber; and

the processing system further comprises a control system coupled to the chemical treatment system and the thermal treatment system, and configured to control at least one of a chemical treatment chamber temperature, a chemical treatment gas distribution system temperature, a chemical treatment substrate holder temperature, a chemical treatment substrate temperature, a chemical treatment processing pressure, a chemical treatment gas flow rate, a thermal treatment chamber temperature, a thermal treatment substrate holder temperature, a thermal treatment substrate temperature, a thermal treatment processing pressure, and a thermal treatment gas flow rate.

4. The processing system as claimed in claim 1, wherein the protective barrier on the interior surface of the chemical treatment chamber comprises an anodized metal impregnated with PTFE and/or TFE.

5. The processing system as claimed in claim 4, wherein the protective barrier on the interior surface of the chemical treatment chamber comprises a hard anodized metal impregnated with TFE and/or PTFE.

6. The processing system as claimed in claim 4, wherein the metal comprises at least one of aluminum and an aluminum alloy.

7. The processing system as claimed in claim 1, wherein the protective barrier on the interior surface of the chemical treatment chamber comprises at least one of Al_2O_3 , Y_2O_3 , Sc_2O_3 , Sc_2F_3 , YF_3 , La_2O_3 , CeO_2 , Eu_2O_3 , and DyO_3 .

8. The processing system as claimed in claim 1, wherein the chemical treatment system further comprises a temperature controlled substrate holder having a protective barrier formed on at least a portion thereof, the protective barrier on the temperature controlled substrate holder mounted within the chemical treatment chamber comprising an anodized metal impregnated with PTFE and/or TFE.

9. The processing system as claimed in claim 1, wherein the chemical treatment system further comprises a temperature controlled substrate holder having a protective barrier formed on at least a portion thereof, the protective barrier on the temperature controlled substrate holder mounted within the chemical treatment chamber comprising at least one of Al_2O_3 , Y_2O_3 , Sc_2O_3 , Sc_2F_3 , YF_3 , La_2O_3 , CeO_2 , Eu_2O_3 , and DyO_3 .

10. The processing system as claimed in claim 1, wherein the chemical treatment system further comprises a gas distribution plate comprising a plurality of gas injection orifices and having a protective barrier formed on at least a portion of an exposed surface of the gas distribution plate and at least a portion of an exposed surface of each orifice, wherein the gas distribution plate is coupled to a temperature

controlled gas distribution system for introducing a process gas into the chemical treatment chamber, the protective barrier on the gas distribution plate and the protective barrier on each orifice comprises an anodized metal impregnated with PTFE and/or TFE.

11. The processing system as claimed in claim 10, wherein the protective barrier on the exposed surface of the gas distribution plate and the protective barrier on the exposed surface of each orifice comprises a hard anodized metal impregnated with TFE and/or PTFE.

12. The processing system as claimed in claim 10, wherein the metal comprises at least one of aluminum and an aluminum alloy

13. The processing system as claimed in claim 1, wherein the chemical treatment system further comprises a gas distribution plate comprising a plurality of gas injection orifices and having a protective barrier formed on at least a portion of an exposed surface of the gas distribution plate and at least a portion of an exposed surface of each orifice, wherein the gas distribution plate is coupled to a temperature controlled gas distribution system for introducing a process gas into the chemical treatment chamber, the protective barrier on the exposed surface of the gas distribution plate and the protective barrier on the exposed surface of each orifice comprises at least one of Al_2O_3 , Y_2O_3 , Sc_2O_3 , Sc_2F_3 , YF_3 , La_2O_3 , CeO_2 , Eu_2O_3 , and DyO_3 .

14. The processing system as claimed in claim 1, wherein the protective barrier on the interior surface of temperature controlled thermal treatment chamber comprises an anodized metal impregnated with PTFE and/or TFE.

15. The processing system as claimed in claim 14, wherein the protective barrier on the interior surface of the temperature controlled thermal treatment chamber comprises a hard anodized metal impregnated with TFE and/or PTFE.

16. The processing system as claimed in claim 14, wherein the metal comprises at least one of aluminum and an aluminum alloy.

17. The processing system as claimed in claim 1, wherein the protective barrier on the interior surface of temperature controlled thermal treatment chamber comprises at least one of Al_2O_3 , Y_2O_3 , Sc_2O_3 , Sc_2F_3 , YF_3 , La_2O_3 , CeO_2 , Eu_2O_3 , and DyO_3 .

18. The processing system as claimed in claim 1, wherein the thermal treatment system further comprises a temperature controlled substrate holder mounted within the thermal treatment chamber and having a protective barrier formed on at least a portion of an exposed surface, the protective barrier on the exposed surface of the temperature controlled substrate holder mounted within the temperature controlled thermal treatment chamber comprises an anodized metal impregnated with PTFE and/or TFE.

19. The processing system as claimed in claim 1, wherein the thermal treatment system further comprises a temperature controlled substrate holder mounted within the thermal treatment chamber and having a protective barrier formed on at least a portion of an exposed surface, the protective barrier on the exposed surface of the temperature controlled substrate holder mounted within the temperature controlled thermal treatment chamber comprises at least one of Al_2O_3 , Y_2O_3 , Sc_2O_3 , Sc_2F_3 , YF_3 , La_2O_3 , CeO_2 , Eu_2O_3 , and DyO_3 .

20. The processing system as claimed in claim 1, wherein the thermal insulation assembly comprises a gate valve

assembly, wherein a protective barrier is formed on at least a portion of an exposed surface of the gate valve assembly.

21. The processing system as claimed in claim 20, wherein the protective barrier on the exposed surface of the gate valve assembly comprises an anodized metal impregnated with PTFE and/or TFE.

22. The processing system as claimed in claim 20, wherein the protective barrier on the exposed surface of the gate valve assembly comprises at least one of Al₂O₃, Y₂O₃, Sc₂O₃, Sc₂F₃, YF₃, La₂O₃, CeO₂, Eu₂O₃, and DyO₃.

23. The processing system as claimed in claim 10, wherein the process gas comprises a first gas and a second gas.

24. The processing system as claimed in claim 23, wherein the first gas comprises at least one of NH₃, HF, H₂, O₂, CO, CO₂, Ar, He, and N₂.

25. The processing system as claimed in claim 23, wherein the second gas comprises at least one of NH₃, HF, H₂, O₂, CO, CO₂, Ar, He, and N₂.

26. The processing system as claimed in claim 23, wherein the plurality of orifices comprises a first array of orifices for coupling the first gas to the process space and a second array of orifices for coupling the second gas to the process space.

27. The processing system as claimed in claim 1, wherein the thermal treatment system further comprises a substrate lifter assembly coupled to the thermal treatment chamber for vertically translating the substrate between a transfer plane and the substrate holder.

28. The processing system as claimed in claim 27, wherein the substrate lifter assembly comprises a blade having three or more tabs for receiving the substrate and having a protective barrier formed on at least a portion of an exposed surface, and a drive system for vertically translating the substrate between the substrate holder and a transfer plane.

29. The processing system as claimed in claim 28, wherein the protective barrier on the at least one exposed surface of the blade comprises an anodized metal impregnated with PTFE and/or TFE.

30. The processing system as claimed in claim 28, wherein the protective barrier on the at least one exposed surface of the blade comprises at least one of Al₂O₃, Y₂O₃, Sc₂O₃, Sc₂F₃, YF₃, La₂O₃, CeO₂, Eu₂O₃, and DyO₃.

31. A chemical treatment system for chemically altering exposed surface layers on the substrate comprising:

- a temperature controlled chemical treatment chamber having a protective barrier formed on at least a portion of an interior surface;
- a temperature controlled substrate holder mounted within the chemical treatment chamber;
- a vacuum pumping system coupled to the chemical treatment chamber; and
- a gas distribution plate comprising a plurality of gas injection orifices, the gas distribution plate being coupled to a temperature controlled gas distribution system for introducing a process gas into the chemical treatment chamber.

32. The chemical treatment system as claimed in claim 31, wherein the protective barrier on the interior surface of the

chemical treatment chamber comprises an anodized metal impregnated with PTFE and/or TFE.

33. The chemical treatment system as claimed in claim 32, wherein the protective barrier on the interior surface of the chemical treatment chamber comprises a hard anodized metal impregnated with TFE and/or PTFE.

34. The processing system as claimed in claim 32, wherein the metal comprises at least one of aluminum and an aluminum alloy.

35. The processing system as claimed in claim 31, wherein the protective barrier on the interior surface of the chemical treatment chamber comprises at least one of Al₂O₃, Y₂O₃, Sc₂O₃, Sc₂F₃, YF₃, La₂O₃, CeO₂, Eu₂O₃, and DyO₃.

36. The chemical treatment system of claim 31, wherein the substrate holder has a protective barrier formed on at least a portion of an exposed surface.

37. The chemical treatment system of claim 31, wherein a protective barrier is formed on at least a portion of an exposed surface of the gas distribution plate and on at least a portion of an exposed surface of each orifice.

38. A thermal treatment system for thermally treating the chemically altered surface layers on the substrate, the thermal treatment system comprising:

- a temperature controlled thermal treatment chamber having a protective barrier formed on at least a portion of an interior surface;
- a temperature controlled substrate holder mounted within the thermal treatment chamber;
- a vacuum pumping system coupled to the thermal treatment chamber; and
- a temperature controlled upper assembly coupled to the thermal treatment chamber.

39. The thermal treatment system as claimed in claim 38, wherein the protective barrier on the interior surface of the thermal treatment chamber comprises an anodized metal impregnated with PTFE and/or TFE.

40. The thermal treatment system as claimed in claim 39, wherein the protective barrier on the interior surface of the thermal treatment chamber comprises a hard anodized metal impregnated with TFE and/or PTFE.

41. The thermal treatment system as claimed in claim 39, wherein the metal comprises at least one of aluminum and an aluminum alloy.

42. The thermal treatment system as claimed in claim 38, wherein the protective barrier on the interior surface of the thermal treatment chamber comprises at least one of Al₂O₃, Y₂O₃, Sc₂O₃, Sc₂F₃, YF₃, La₂O₃, CeO₂, Eu₂O₃, and DyO₃.

43. The thermal treatment system as claimed in claim 38, wherein the substrate holder has a protective barrier formed on at least one exposed surface.

44. A method for treating a processing chamber, comprising:

- anodizing at least a portion of an interior surface of the processing chamber; and
- impregnating the anodized surface with PTFE and/or TFE, thereby creating a protective barrier.