

(19) World Intellectual Property
Organization
International Bureau



(43) International Publication Date
3 June 2004 (03.06.2004)

PCT

(10) International Publication Number
WO 2004/045362 A2

(51) International Patent Classification⁷: **A47L 23/00**

(74) Agents: **WELLS, William, K.** et al.; Kenyon & Kenyon,
1500 K Street, N.W., Suite 700, Washington, DC 20005
(US).

(21) International Application Number:
PCT/US2002/024875

(22) International Filing Date: 6 August 2002 (06.08.2002)

(25) Filing Language: English

(26) Publication Language: English

(30) Priority Data:
09/928,429 14 August 2001 (14.08.2001) US

(71) Applicant: **TECH MATS LLC.** [US/US]; 2840 Hersh-
berger Road, Suite A, Roanoke, VA 24017 (US).

(72) Inventors: **BLUM, Ronald, D.**; 5320 Silver Fox Road,
Roanoke, VA 24014 (US). **THIBODEAU, Joseph,**
A.; 2523 Rosalind Avenue, Roanoke, VA 24014 (US).
KOKONASKI, William; 1807 44th Court, N.W., Gig
Harbour, WA 98335 (US). **GENTILUOMO, Andrew**;
6517 Brookhaven Court, Roanoke, VA 24018 (US). **JOR-**
DAN, Robert; 1305 Currituck Drive, Raleigh, NC 27609
(US).

(81) Designated States (*national*): AE, AG, AL, AM, AT, AU,
AZ, BA, BB, BG, BR, BY, BZ, CA, CH, CN, CO, CR, CU,
CZ, DE, DK, DM, DZ, EC, EE, ES, FI, GB, GD, GE, GH,
GM, HR, HU, ID, IL, IN, IS, JP, KE, KG, KP, KR, KZ, LC,
LK, LR, LS, LT, LU, LV, MA, MD, MG, MK, MN, MW,
MX, MZ, NO, NZ, OM, PH, PL, PT, RO, RU, SD, SE, SG,
SI, SK, SL, TJ, TM, TN, TR, TT, TZ, UA, UG, UZ, VN,
YU, ZA, ZM, ZW.

(84) Designated States (*regional*): ARIPO patent (GH, GM,
KE, LS, MW, MZ, SD, SL, SZ, TZ, UG, ZM, ZW),
Eurasian patent (AM, AZ, BY, KG, KZ, MD, RU, TJ, TM),
European patent (AT, BE, BG, CH, CY, CZ, DE, DK, EE,
ES, FI, FR, GB, GR, IE, IT, LU, MC, NL, PT, SE, SK,
TR), OAPI patent (BF, BJ, CF, CG, CI, CM, GA, GN, GQ,
GW, ML, MR, NE, SN, TD, TG).

Published:

— *without international search report and to be republished
upon receipt of that report*

*For two-letter codes and other abbreviations, refer to the "Guid-
ance Notes on Codes and Abbreviations" appearing at the begin-
ning of each regular issue of the PCT Gazette.*

(54) Title: ADVANCED FLOOR MAT

(57) Abstract: An advanced floor mat is disclosed. In an embodiment of the present invention, the floor mat includes a cleanable portion. The floor mat may also include a water dissipation component, a water absorbing component, a cushioning component, customized graphics, a transparent cleanable portion, a tacky surface on the cleanable portion, an antibacterial composition, an anti-fungal composition, and a fragrance. The cleanable portion may be erodible and may include a plurality of cleanable reusable layers. If a tacky surface is included in the floor mat, an anti-slip feature may be associated with the tacky surface to help prevent slipping on a possibly wet tacky surface. Additionally, a sensor system may be included in the floor mat to assist a user in identifying when the floor mat may require cleaning.



WO 2004/045362 A2

ADVANCED FLOOR MAT

This application is a continuation-in-part of international application no. PCT/US00/30206, filed November 2, 2000, which is a continuation-in-part of U.S. application no. 09/553,234, filed April 19, 2000 and issued May 24, 2001 as U.S. patent no. 6,233,776. Application no. 09/553,234 is a continuation-in-part of U.S. application no. 09/418,752, filed October 15, 1999, which is a continuation-in-part of U.S. application no. 09/304,051, filed May 4, 1999 and issued April 24, 2001 as U.S. patent no. 6,219,876.

Background and Discussion of the Invention

The present invention relates to a floor mat having features that make it more desirable for home, commercial and other uses. More specifically, the invention provides a floor mat that includes a cleanable portion, and may also include a water dissipation component, a water absorbing component, a cushioning component, customized graphics, a transparent cleanable portion, a tacky surface on the cleanable portion, an antibacterial composition, an antifungal composition, and a fragrance. The cleanable portion may be erodible and may include a plurality of cleanable reusable layers. If a tacky surface is included in the floor mat, an anti-slip feature may be associated with the tacky surface to help prevent slipping on a possibly wet tacky surface. Additionally, a sensor system may be included in the floor mat to assist a user in identifying when the floor mat may require cleaning.

Floor mats are known for cleaning the soles of a person's shoes who is about to enter a particular area or room. One problem with floor mats in general is how to keep the floor mat sufficiently clean such that it may perform its function of cleaning the person's shoes when, by its very nature, it is purposefully dirtied when performing its

function.

Known floor mats may be comprised of a single, unitary piece of material. Whereas these single structure floor mats may be kept clean by, for example, washing the floor mat, it may be required that the entire floor mat be removed from its location
5 for washing and thus, the floor mat is not available where desired while the entire mat is being cleaned. Alternatively, even if the mat can be cleaned in-place, which may not be a possibility if it is located in, for example, a carpeted area, it may be inconvenient to clean the mat in-place.

U.S. Patent Number 3,785,102 to Amos discloses a throw-away pad comprising
10 a plurality of stacked disposable sheets where, when a particular sheet is dirtied, the dirty sheet is removed and disposed of. The next sheet that is exposed after the dirty sheet is discarded is clean and thus, a clean surface is again available. However, there may be problems with comprising the floor mat of disposable sheets. Disposing of each dirty sheet may be uneconomical since each sheet is discarded after it becomes dirty.
15 Additionally, after some finite number of sheets are disposed of, no sheets will remain and thus no effective cleaning surface is available.

U.S. Patent Number 3,785,102 to Amos also discloses that an adhesive can be provided on each sheet's top surface to improve its ability to remove dirt from a person's shoes. However, again, these sheets are not cleanable and therefore are not
20 reusable.

U.S. Patent Number 3,717,897 to Amos et al. discloses a pad for cleaning shoes and wheels. The pad includes a thin water-washable adhesive covering its upper surface for removing dirt from shoes and wheels. Whereas the '897 patent discloses a pad with a water-washable adhesive upper surface, the pad is not known for use in
25 domestic or office-type applications. As stated in the '897 patent, the pad is placed at an entrance doorway leading into a clean room.

Tacky floor mats are by far more popular for utilization in indoor environments that are far removed from exterior outside entrances, such as for clean rooms that are well-within the interior of the building in which they are used, e.g., hospital rooms,
30 computer chip manufacturing spaces, and gymnasiums. Thus, tacky floor mats are not known for use in areas that are adjacent to entrances that lead from the outdoor

environment for cleaning the soles of a person's shoes prior to entry into the interior of a building, such as for example in an entry foyer or on an outdoor porch.

Tacky floor mats are not known for use in domestic or office-type applications, e.g., home or business office use, because of several known deficiencies. One of these
5 deficiencies is that their tacky surface will not be as effective if it becomes wet. Therefore, if the tacky surface floor mat was utilized in an outdoor environment, such as the outdoor porch mentioned above, or in an indoor environment that is adjacent to or near an outdoor entrance, such as an entry foyer of a home or business, for cleaning a person's shoes prior to further entering the home or business, the mat is likely to
10 become wet and therefore not effective. The mat could become wet from, for example, the moisture in the atmosphere or from moisture carried on the soles of the person's shoes who steps on the mat. Additionally, if the tacky surface becomes wet it may become slippery and thus cause a hazard for the person who steps on it.

Additional deficiencies with using known tacky floor mats for home or office-
15 type applications as discussed above is their likelihood of becoming trip hazards and their lack of aesthetic appeal. In the '897 patent, because the pad is designed for use in clean room environments, it is adhesively adhered to the passageway floor in front of the entrance doorway. This may be satisfactory for retaining the mat in-place in clean room-type of applications, however, if it was attempted to use the '897 pad on a
20 carpeted floor, the pad would not properly adhere to the carpet and thus a trip hazard would be present. This could result in significant liability issues. The '897 pad does not have sufficient mass for it to remain in-place without utilizing an adhesive. Regarding aesthetics, because tacky floor mats are known only for their functional characteristics, and thus for use only in "clean room"-type applications, they are not
25 aesthetically pleasing. Therefore, for at least the above reasons, tacky floor mats are not known for use in home or office-type applications.

Additional drawbacks with known floor mats exist that are directed to issues of customization for a particular purchaser and a lack of additional cleaning properties. A floor mat may be the first object that a visitor to a particular home or business
30 encounters. As such, the owner of the home or business may want to utilize the floor mat to graphically convey an initial greeting or message to the visitor. Whereas floor

mats are known that may include a greeting on them, it is not currently known to allow for a particular purchaser to customize the displayed graphic so that the message is tailored to convey a particular message desired by the purchaser. For example, on Halloween the purchaser may want the floor mat to display a "Happy Halloween" message. In another situation, the purchaser may want to greet a particular visitor with a message such as "Hello, Joe". Currently, it is not known to provide a floor mat where an individual can customize the floor mat to display a particular message that they want to convey and in certain circumstances even change the floor mat's message they want to convey.

Such customization of a floor mat may relate to choice of features such as colors, materials, constituent components and the like. Such choices may depend, for example, on whether a floor mat is intended for indoor or outdoor use. A floor mat that is user-configurable in terms of such features as color, components, and the like could fulfill unmet consumer needs by, for example, allowing consumers to choose floor mat materials adapted to regional climate or to personal preference in home décor.

An additional problem with known floor mats, as mentioned above, is that they are limited in their ability to clean the soles of a person's shoes. Whereas known floor mats may be capable of removing dirt particles from the shoe's soles, they are not able to disinfect the soles nor provide a scent to the soles to assist in masking any unpleasant odors that may be associated with the shoes.

An additional drawback with known floor mats, even if they are cleanable, is that they do not assist a user in determining when the floor mat may require cleaning. Generally, the owner or custodian of the floor mat does not continuously or regularly monitor the condition of the floor mat with respect to cleanliness. Therefore, the floor mat could require cleaning, and because the owner is not consciously monitoring the condition of the floor mat, there could be a significant period of time before the owner realizes that the floor mat requires cleaning. Therefore, it would be desirable to assist the owner/custodian of the floor mat in determining when the floor mat requires cleaning.

Therefore, it would be desirable to provide an advanced floor mat that could address deficiencies that exist with currently known floor mats. The advanced floor mat

of the present invention overcomes deficiencies in the prior art and may include a base portion which incorporates a cleanable portion that is adapted to be removably received within the floor mat. The floor mat may also include features such as a water dissipation capability, a water absorbing capability, a cushioning capability, customized
5 graphics, a transparent portion, a tacky surface on the cleanable portion, an antibacterial composition, an antifungal composition, and a fragrance. The cleanable portion may include the features of being erodible and containing a plurality of cleanable reusable layers. If a tacky surface is included in the floor mat, an anti-slip feature may be associated with the tacky surface to help prevent slipping on a possibly wet tacky
10 surface. Additionally, a sensor system may be included in the floor mat to assist a user in identifying when the floor mat may require cleaning. An advanced floor mat according to the present invention may further be user-configurable with such features as color, materials, components, and the like. Other features will be apparent from the detailed description which follows.

15

Brief Description of the Drawings

The various features of the invention will best be appreciated by simultaneous reference to the description which follows and the accompanying drawings, in which:

Fig. 1 is a perspective view of a floor mat in accordance with an embodiment
20 of the present invention;

Fig. 2 is an exploded perspective view of the floor mat of Fig. 1;

Fig. 3 is an exploded side view of an alternative embodiment of the floor mat of the present invention;

Fig. 4 is an exploded side view of an alternative embodiment of the floor mat
25 of the present invention;

Fig. 5 illustrates a third alternative embodiment for a tacky insert portion with an anti-slip feature for the floor mat of the present invention;

Fig. 6 illustrates a fourth alternative embodiment for a tacky insert portion with an anti-slip feature for the floor mat of the present invention;

30 Fig. 7 is a side view of the embodiment for the tacky insert portion with an anti-slip feature of Fig. 6;

Fig. 8 is a perspective view of a fifth embodiment for a tacky insert portion with an anti-slip feature for the floor mat of the present invention;

Fig. 9 illustrates a sixth alternative embodiment for a tacky insert portion with an anti-slip feature for the floor mat of the present invention;

5 Fig. 10 illustrates the tacky insert portion with an anti-slip feature of Fig. 9 in conjunction with an alternative embodiment for the base portion;

Fig. 11 illustrates a seventh alternative embodiment for a tacky insert portion with an anti-slip feature and a water dissipating capability for the floor mat of the present invention;

10 Fig. 12 illustrates an alternative embodiment for a tacky insert portion and base portion with a water dissipating capability for the floor mat of the present invention;

Fig. 13 illustrates a sensor system that may be utilized in an embodiment of the present invention;

15 Fig. 14 is an embodiment for a floor mat where the tacky portion and the non-tacky portion are separable;

Fig. 15 is a perspective view of an embodiment of the floor mat of the present invention as being used in one step of a process for utilizing the floor mat;

Fig. 16 is a perspective view of the floor mat of Fig. 15 as being used in a second step of a process for utilizing the floor mat;

20 Fig. 17 illustrates an alternative embodiment for a floor mat in accordance with the present invention that includes interchangeable base portions;

Fig. 18 illustrates an alternative embodiment for a floor mat in accordance with the present invention that includes single sheets for the cleanable portion;

25 Fig. 19 illustrates a roll of sheets that may be utilized with the embodiment of Fig. 18;

Fig. 20 illustrates a storage container that may be utilized with the roll of sheets of Fig. 19;

Fig. 21 illustrates an alternative embodiment for a floor mat in accordance with the present invention that includes a scraper movable on tracks;

30 Fig. 22 illustrates an alternative embodiment for a floor mat in accordance with the present invention that includes a scraper movable on tracks;

Figs. 23A-23F, 24A-24F, and 25A-25E illustrate embodiments of components which may be assembled into a floor mat in accordance with the present invention;

Fig. 26 illustrates an embodiment of a floor mat in accordance with the present invention wherein at least two separate tacky sections are provided within a non-tacky
5 region; and

Fig. 27 illustrates an embodiment of a floor mat in accordance with the present invention wherein a surface for cleaning a person's shoes consists solely of a tacky material having apertures for anti-slip features.

10 **Detailed Description**

Figure 1 illustrates a first embodiment for a floor mat 100 in accordance with the principles of the present invention. As can be seen in Figure 1, floor mat 100 includes a base portion 200 and a cleanable insert portion 300. As will be further described later in this specification, in this embodiment, cleanable portion 300 is
15 received within base portion 200 and is removable from base portion 200.

Figure 2 illustrates an exploded, perspective view of the floor mat of Figure 1. As can be seen in Figure 2, base portion 200 is formed as a generally flat, planar member and defines a recess 210 within the top surface of base portion 200. Base portion 200 provides sufficient weight and mass for supporting cleanable insert portion
20 300 and maintaining the floor mat's positioning on the surface on which it is placed. Base portion 200 may include, as will be discussed below, a water dissipation capability, a water absorption capability, and a cushioning capability and may be comprised of materials such as polyurethane, polyisoprene and other cross-linked elastomeric materials, such as nylon-6, molded or woven to form a porous structure.
25 Recess 210 can be configured in any of a variety of geometric configurations, however, in the present embodiment, recess 210 is configured in a rectangular shape. Recess 210 has a length L_1 and a width W_1 . The depth of recess 210 is such that it is able to receive within it cleanable insert portion 300 such that when cleanable insert portion 300 is received within recess 210, the top surface of cleanable insert portion 300 lies generally
30 in the same plane as the top surface of base portion 200.

The top surface of base portion 200 may be colored with any color depending

upon the desires of a particular purchaser, however, it is preferable that a color be utilized that will minimize the visibility of any dirt that is accumulated by base portion 200. For example, it may be desirable that darker colors be utilized for the top surface of base portion 200 rather than lighter colors. However, again, any particular color may
5 be utilized for base portion 200, and particularly the top surface of base portion 200, depending upon the particular desires of an individual. Additionally, the base portion 200 may be either translucent or opaque.

As can be seen in Figure 2, the surface of base portion 200 which defines the bottom of recess 210 may include graphics 220 on that surface. In the illustrated
10 embodiment, the graphics include pictorial representations of flowers and a text message which spells out the word "WELCOME". The present invention is not limited to any particular graphic within recess 210 and the present invention may include any of a variety of different forms of graphics.

Graphics 220 may be modified, and thus customized, by an individual after the
15 floor mat has been purchased by the owner. The owner may customize the mat at their home or office and, thus, a graphic that may be appropriate for a particular situation may be modified by the individual for display in another situation. For example, the graphic may display a message stating "Happy Halloween" for Halloween and may be modified to display "Happy Holidays" during the winter holiday season. Thus, as can be
20 understood, the graphics are modifiable by a user and thus, may be customized for the particular desires of a particular user.

As stated above, the present invention is not limited to any particular form for graphics 220. The graphics 220 can be customized by a user to include any of a variety of different colors, pictures, messages, or other representations that the user may want
25 to display. In addition, the visible intensity of a color(s) can be modified. For example, a color that glows at night could be included in graphics 220 for an occasion such as Halloween.

Any of a variety of different types of structures or methods may be practiced in the present invention for modifying graphics 220 of floor mat 100 and the present
30 invention is not limited to any particular methodology or structure for modifying graphics 220. Additionally, all of the various embodiments contemplated for providing

a modifiable graphic display in the floor mat of the present invention can be incorporated in either, or both, of the base portion or the insert portion. For example, the graphics may consist of pre-formed messages or art forms which may be adhered to either the surface which defines the bottom of recess 210, such as by using an adhesive
5 or fastener assembly, e.g., a hook and loop assembly, or to the underside of insert portion 300 such that, when insert portion 300 is placed within base portion 200, the graphics would be visible through a transparent insert portion.

Alternatively, a variety of different graphics may be stored within floor mat 100 such that a user is able to selectively uncover a particular graphic for display while the
10 other available graphics remain covered within floor mat 100. This type of selectability is known in other mediums where selectivity between a variety of different graphics within a common display panel is desired. For example, advertising bulletin boards at sporting events are able to selectively display a first particular message during a first particular period of time and display a second message during a second period of time
15 on the same bulletin board.

A third possible alternative is to provide a modifiable display on the floor mat. The display surface can be associated with either the base portion or the insert portion, e.g., on either the bottom surface of recess 210 or attached to the bottom of insert portion 300. A display could be included on the front of the floor mat, on the back of
20 the mat such that it is viewable through a transparent portion of the mat, embedded in the mat, attached to the mat, or integrally formed in the mat. For example, the display could be comprised of a small, thin box of graphics that could attach to a tacky portion and/or a base portion or any other component part of the floor mat. However it is associated with the floor mat, a user may design and display their customized graphic
25 and may subsequently modify that graphic such that it is replaced with another graphic. A display surface such as an erasable writing board could be utilized for this purpose.

It is also contemplated that a modifiable electronic display surface could be provided, such as, for example, a liquid crystal display. The display could be connected to a computer and a computer generated image could be displayed on the display. Thus,
30 the image displayed on the display could be modified by generating a different computer image and displaying that computer image on the display. The display could be

associated with base portion 200, such as included within recess 210, or could be included on a bottom surface, facing upward, of insert portion 300. Alternatively, the display could be integrally formed with either of the base portion or the insert portion. The modifiable display could utilize a plurality of different graphics that can be
5 displayed in any of a variety of manners on the display: For example, the graphics could be displayed in a generally fixed position on the display or could scroll across the display, with both exemplary methodologies displaying multiple graphics either individually or in combination.

Other alternatives for modifying the graphics 220 of floor mat 100 include using
10 light emitting polymers to create, and thus change, graphics 220. The light emitting polymers can be either applied to, attached to, or woven into the floor mat. The light emitting polymers may be utilized on any portion of floor mat 100, for example, on either the base portion or the insert portion, or on any other portion of the different embodiments for the floor mat. Light emitting polymers are known and described in
15 U.S. Patents 5,945,502, 5,869,350, and 5,571,626, which are incorporated herein by reference in their entirety.

Other options for a display are to use electronic ink or electric paper. Electric paper is available from Xerox and is described in U.S. Patents 5,723,204, 5,604,027, 4,126,854, and 4,143,103, which are incorporated herein by reference in their entirety.
20 Electric paper employs thousands of tiny, electrically charged beads, called Gyrricon, each about the width of a human hair, to create pixels. The two-tone beads are embedded inside a liquid-filled plastic sheeting that forms the surface of the paper. Each bead, half-black, half-white, gyrates in response to an electric field. Whether the beads are black- or white-side up determines the image. Because there's no need to
25 refresh the image, and because the screen isn't backlit, electric paper uses only a fraction of the power used by conventional electronic displays. Electromagnetic styluses and printer-like devices can be used for getting images onto the paper.

Electronic ink is available from E Ink Corp., at 45 Spinelli Pl., Cambridge, MA 02138. Electronic ink uses a microencapsulated micromechanical display system. Tiny
30 microcapsules are captured between two sheets of plastic to create pixels. Alternatively, the capsules may be sprayed on a surface. The result is a flexible display material. The

tiny capsules are transparent and contain a mixture of dark ink and white paint chips. An electric charge is passed through the capsules. Depending on the electrostatic charge, the paint chips float at the top or rest on the bottom of each capsule. When the paint chips float at the top, the surface appears white. When they rest at the bottom, and
5 thus under the ink, the surface appears black. Each of the two states is stable: black or white. A transparent electromagnetic grid laid over the sheet's surface controls the shape of the image. The display may be wirelessly connected to, for example, a computer and thus, the World Wide Web by utilizing, for example, a Motorola paging system. Text on all displays, if multiple displays are used, can be changed at once by
10 a single editor, through a Web page.

Again, a display, which could utilize any of the methods discussed above for modifying the display, could be associated with any portion of the floor mat, such as base portion 200 within recess 210 or on a bottom surface, facing upward, of insert portion 300. Alternatively, the display could be integrally formed with either of the
15 base portion or the insert portion. The display could be utilized in any of the embodiments disclosed herein for the floor mat of the present invention, including a floor mat that includes a tacky surface and a non-tacky floor mat embodiment.

In further describing base portion 200, as mentioned above, base portion 200 may also include both a water dissipation component and a cushioning component. The
20 water dissipation component provides for transferring moisture from the soles of a person's shoes that is standing on floor mat 100 to reduce the degree of moisture transferred to cleanable insert portion 300 and the cushioning component provides for conforming the floor mat 100 to the shape of the person's soles such that a greater amount of the debris on the person's soles may be removed by floor mat 100. The
25 present invention is not limited to any particular structure or material for the water dissipation component and the cushioning component. For example, the water dissipation component may be comprised of any of a wide variety of known materials, such as polyamides, vinylics, and polyisoprene. It is desirable, but not required, that the water dissipation component dissipate or move the water and not retain the water. Thus,
30 porous materials, and not hydrophilic materials, are desired. The cushioning component may be comprised of any of a variety of cushioning components to include, for example,

foam rubber.

Figure 2 also further illustrates cleanable insert portion 300. As can be seen, cleanable insert portion 300 has a geometric shape which is complementary in size and form to the recess 210 that is formed within base portion 200. As such, cleanable insert
5 portion 300 is able to be received securely within recess 210. Thus, cleanable insert portion 300 has a length L_2 which is just slightly smaller than the length L_1 of recess 210. Likewise, cleanable insert portion 300 has a width W_2 which is also just slightly smaller than width W_1 of recess 210.

On the bottom side 310 of cleanable insert portion 300, i.e., that surface which
10 contacts the surface which defines the bottom of recess 210, an attachment mechanism may be provided such that cleanable insert portion 300 may be removably attached to base portion 200 within recess 210. Any of a variety of different attachment mechanisms may be provided on the bottom surface of cleanable insert portion 300 to include, for example, a hook and loop fastener assembly or an adhesive. Regardless of
15 the particular securement mechanism used to removably attach cleanable insert portion 300 to base portion 200, in this embodiment, cleanable insert portion 300 may be removed from base portion 200 such that it may be cleaned by a user and, after cleaning, be reinserted within recess 210 such that a clean surface is now provided for floor mat 100.

20 As stated above, cleanable insert portion 300 may be formed from a transparent material such as hydrophilic aliphatic acrylic polymers and copolymers incorporating acrylic acid, hydroxy ethyl methacrylate, and glycerin monomethacrylate. Forming cleanable insert portion 300 of a transparent material would allow an individual to view the customized graphics that may be provided within floor mat 100, as discussed
25 previously. Alternatively, the insert portion 300 could be opaque.

Additionally, the top side of cleanable insert portion 300 may include a tacky surface. The tacky surface would provide for assisting in removing debris from the soles of a person's shoes that is standing on cleanable insert portion 300. When the top tacky surface of cleanable insert portion 300 is dirtied to such an extent that the user
30 desires to clean insert portion 300, in this embodiment, the user removes insert portion 300 from base portion 200 and cleans insert portion 300 to remove the accumulated

debris. The insert portion 300 is then reinserted into base portion 200.

The tacky surface that is provided on the top side of cleanable insert portion 300 could be comprised of any of a variety of materials, such as polyvinyl chlorides combined with a suitable plasticizer, plasticized neoprene, polysulfides, and
5 polyurethanes. Additionally, acrylics, such as butyl acrylate and many of its homologues, may be utilized. Again, the present invention is not limited to any particular material. The tacky surface may be formed, generally, from any adhesive material. The only consideration, in this embodiment, is that the surface should maintain its tacky characteristic even after repeated cleaning cycles.

10 The present invention is not limited to any particular methodology for cleaning insert portion 300. Insert portion 300 may be cleaned by any of a variety of methods depending upon a particular material composition for insert portion 300. For example, insert portion 300 may be cleaned by placing insert portion within a washing machine and washing insert portion 300 or insert portion 300 may be cleaned by scrubbing insert
15 portion 300 with a scrub brush and soap and water or with a cleaning agent such as "Spic 'N Span".

Additionally, the insert portion 300 could be cleaned by utilizing a roller that also includes a tacky surface around the circumference of the roller. The tacky surface of the roller is comprised of a stronger adhesive than that of the tacky insert portion such
20 that, as the tacky surface of the roller is rolled over the tacky surface of the insert portion, any dirt and debris on the tacky insert portion will be drawn off of the tacky insert portion and will adhere to the roller. In this manner, a roller with a tacky surface could be utilized to clean the tacky insert portion.

Again, however, the present invention is not limited to any particular
25 methodology or cleaning agent for cleaning insert portion 300 and any cleaning methodology or agent compatible with the composition of insert portion 300 is contemplated.

Floor mat 100 may also include additional features for assisting in the cleaning of the soles of a person standing on floor mat 100. For example, base portion 200
30 and/or insert portion 300 may include an antibacterial composition and an antifungal composition. Antibacterial compositions such as anthraquinone derivatives of

polyethylene glycol mono- and di-methacrylate could be utilized. Thus, floor mat 100 would be bactericidal. The antibacterial feature would be particularly desirable because the floor mat would be able to both clean structural debris from the soles of the person's shoes and remove any potentially harmful bacteria from the person's soles as well.

5 Additionally, in order to further provide for a desirable sole surface prior to entering a particular area, floor mat 100 could also be provided with a fragrance. Flavones such as tricyclic molecules with aromatic substitution or organic ethers, e.g., liminolic acid, could be utilized. The fragrance is transferred from floor mat 100 to the soles of the person's shoes such that any undesirable odors are favorably masked by the
10 fragrance.

 The present invention is not only limited to utilizing an antibacterial composition, an antifungal composition, and/or a fragrance in floor mat 100. Rather, floor mat 100 could also incorporate a variety of other substances that would assist in cleaning the soles of a person's shoes.

15 Any variety of structures or methods could be utilized for associating an antibacterial composition, an antifungal composition, a fragrance, or any other composition, with floor mat 100. The substances could be applied as releasable, or dissipatable, coatings to floor mat 100 or could be releasably embedded as, for example, pellets within the structure of floor mat 100 such that as pressure is applied to floor mat
20 100 the substances are dispensed to the soles of the person's shoes.

 Figure 3 illustrates an alternative embodiment for floor mat 100. In Figure 3, it is illustrated that base portion 200 may include separate layers for a water dissipation component 230 and a cushioning component 240. Water dissipation component 230, in this embodiment, is disposed on a top side of the cushioning component 240.
25 However, the present invention is not limited to this particular embodiment for water dissipation component 230 and cushioning component 240. For example, a single hybrid structure could be utilized for base portion 200 that would include the material properties to provide for both water dissipation and conforming structure.

 Alternatively, Figure 4 illustrates that the floor mat may include both a water
30 dissipation component, or wicking layer, and a water absorption layer. In Figure 4, floor mat 400 includes wicking layer 410 and water absorption layer 420. The wicking layer

410 could be comprised of polypropylene or olefins, or any other suitable material that has the properties of moving the water from the surface of floor mat 400. The water absorption layer 420 is disposed underneath the wicking layer 410 and absorbs any water that passes through the wicking layer 410. The water absorption layer 420 could
5 be periodically removed and dried, such as by example only, in a drying machine.

Of course, a wicking layer 410 may be used either with or without a water absorption layer 420 and a cushioning layer, as described previously in other embodiments, and the water absorption layer 420 could be used with or without a wicking layer 410 and a cushioning layer. Additionally, both the wicking layer and/or
10 the absorption layer and/or the cushioning layer could be used with or without a tacky portion.

Returning to Figure 3, Figure 3 also illustrates an alternative embodiment for insert portion 300. Whereas the previously disclosed embodiment for insert portion 300 was discussed as a single structural member that could include a tacky surface on a top
15 side thereof, the embodiment of Figure 3 for insert portion 300 is comprised of a plurality of layers. As can be seen, layers 301-305, comprise insert portion 300. Each of the layers may include a tacky surface on a top side thereof, as was described previously for insert portion 300. In use, a top-most layer, e.g., layer 301, may be removed from its adjacent lower layer, e.g., layer 302, and may be independently
20 cleaned. After cleaning, the layer may be reinstalled within recess 210 on top of the exposed layer of insert portion 300. In this manner, insert portion 300 may be cleaned by removing a top-most layer, cleaning that layer, and reinstalling that layer within recess 210. Whereas each layer is described as being independently cleanable, it is not required that each individual layer be cleanable. Each layer may be formed of materials
25 as described previously when discussing the embodiment of Figures 1 and 2 for the insert portion.

Other alternative embodiments for insert portion 300 are contemplated. For example, whereas the previously disclosed embodiments discussed insert portion 300 as being comprised of one or more layers with a tacky surface on a top side of the
30 layer(s), it is not required that insert portion 300 be formed with only a tacky surface on a top side thereof. More specifically, an alternative embodiment for insert portion 300

could include forming insert portion 300 as a single structural member from a material which is tacky in composition throughout the entire cross-section of the material. A material such as a blend of a noncross-linked hydrophilic thermoplastic, preferably a polyethylene glycol diacrylate with n not exceeding 15, and a hydrophobic material, such as a polyvinyl neoprene chloride, could be utilized for the insert portion of this embodiment. By forming insert portion 300 from a uniform, tacky material, the insert portion 300 does not necessarily have to be removed from recess 210 of base portion 200 to be cleaned. Insert portion 300 could be cleaned in this alternative embodiment by eroding the top surface of the insert portion as a result of use of the insert portion. Thus, by providing an erodible insert portion, the insert portion may be cleaned by the erosion of its top surface as the insert portion is used within floor mat 100.

As insert portion 300 erodes, the exposed surface of insert portion 300 continues to be tacky in composition because of its uniform cross-section. As the exposed tacky surface erodes, the dirt captured by the exposed tacky surface will dissipate as a result of the erosion and thus, the erosion of the insert portion itself provides for a cleanable insert portion.

Alternatively, even with a uniform cross-section of a tacky substance for insert portion 300, the user may remove insert portion 300 from recess 210 and separately clean insert portion 300. Thus, the user is not required to rely solely on the erodible characteristic of insert portion 300 for cleaning of insert portion 300; rather, the user may utilize the erodible cleaning feature of the insert portion in combination with a separate cleaning step of removing the insert portion from the base portion and independently cleaning the insert portion.

As discussed above, insert portion 300 may be comprised of a variety of materials, including materials such as tacky plastics, paper, or adhesives that can be cleanable and may or may not be erodible and reusable. If paper is utilized, the insert portion may be formed as a single structural member or as a plurality of layers, as discussed previously. Additionally, the paper may include a tacky surface on a top-side thereof. The paper may be translucent, opaque, or colored, and may include a graphic display thereon.

As discussed earlier, it is desirable, but not required, that the floor mat contain

a water dissipation and/or absorption capability. This capability is desired to help prevent the tacky surface of the insert portion from becoming excessively wet and, thus, slippery. Whereas it has been discussed that, in order to help prevent a user from slipping on the tacky surface of the insert portion, a water dissipation and/or absorbing capability could be included in the floor mat to reduce the degree of moisture on the tacky surface, this is not the only structure contemplated for preventing the tacky insert portion from becoming slippery. Alternatively, the tacky insert portion itself could be formed to help prevent slipping. Figures 5-12 illustrate alternative embodiments for tacky insert portion 300. Figure 5 illustrates tacky insert portion 300 as including a grid pattern 320 of channels 322 that could be comprised of a non-tacky material. The channels could be either raised from the surface of insert portion 300 or could lie coplanar with the top surface of the insert portion. By forming the channels of a non-tacky material, even if the tacky material of insert portion 300 became wet, a user would be assisted in not slipping on the slippery, wet tacky surface of the insert portion by the presence of the non-tacky surfaces which do not become slippery when wet.

Figures 6 and 7 illustrate another alternative embodiment for tacky insert portion 300 which includes anti-slip particles 324, e.g., silicon or sand particles, which extend above the top surface 330 of the tacky insert portion. It is desirable that the anti-slip particles be comprised of a material that does not become slippery when wet and that they be exposed from the tacky surface, however, it is not required. Even if the anti-slip particles are embedded within the tacky surface, their extension above the top surface 330 of the tacky insert portion will provide a physical frictional restraint against slipping for the soles of a person's shoes who is standing on the floor mat.

Whereas Figure 5 illustrates tacky insert portion 300 as including a grid pattern 320 of channels 322 that could be comprised of a non-tacky material and Figures 6 and 7 illustrate another alternative embodiment for tacky insert portion 300 which includes anti-slip particles 324 which extend above the top surface 330 of the tacky insert portion, it is not required that these two alternative embodiments contain features that are mutually exclusive. For example, it is contemplated that tacky insert portion 300 could include both a grid pattern of non-tacky channels and anti-slip particles, which is not illustrated specifically in the Figures but which can be easily understood.

Another alternative for providing a slip-resistant tacky portion is to include a plurality of anti-slip members, or treads or nipples, that extend up through and slightly above the surface of the tacky portion. As can be seen in Figure 8, in this embodiment, tacky portion 300 is inserted within a base portion, which may be a water absorbent border 500, and includes a plurality of apertures 342 within it. Each of a plurality of treads 344, which may extend upward from a base disposed underneath tacky portion 300, extend up through one of the plurality of apertures 342. A top-most end of each tread extends above a top-most surface 340 of tacky portion 300. As a person steps onto tacky portion 300, the quantity and positioning of the treads 344 is such that the tacky portion is able to remove debris from the person's shoes and the treads 344, at least one of which is stepped upon by the person, prevents slipping of the person on the tacky portion 300 should the tacky portion 300 become slippery when wet. The treads 344 may compress when stepped upon such that the top-most end of the tread is co-planar with the top-most surface 340 of the tacky portion 300. In this manner, the tread will contact the person's shoes to prevent slipping but yet not hinder contact between the person's shoes and the tacky surface of the mat, which enhances the cleaning of the person's shoes. Therefore, there is a relationship between the distance that the tread extends above the top-most surface of the tacky portion and the compressibility of the tread; a relationship which provides the functionality discussed above.

The treads may be configured in any shape and size. Additionally, the treads may be comprised of any material which is slip-resistant when wet, such as, for example, rubber or plastics. The treads may include grooves within them to further assist in preventing a person from slipping on the tacky portion.

Figures 9 and 10 illustrate additional alternative embodiments for both the tacky insert portion 300 and the base portion 200 that help to prevent slipping on a potentially wet tacky portion. As can be seen in Figure 9, and as discussed previously, tacky insert portion 300 is comprised of a plurality of layers 301, 302, and 303. Whereas only three layers are illustrated, it can be understood that any number of layers can be utilized in the present invention. As can be seen, tacky layers 301-303 each contain a plurality of integrally formed raised portions 300A. These raised portions can help to prevent a person from slipping on the tacky portion by providing increased friction between the

top surface of the tacky layer, due to the raised portions, and the person's shoes. Thus, these raised portions can substantially reduce the potential for slipping on the tacky portion if it becomes wet.

The raised portion 300A can be formed in each layer in a variety of ways and the present invention is not limited to any particular method. One method for forming the raised portions is to assemble the layers into a pad of layers and then insert the entire pad into a machine press. One face of the press is flat and the other face, i.e., that face that is facing the non-tacky, or underside, of the layers, contains an array of bosses or bumps. When the pad is pressed in the machine press, all of the tacky layers become embossed with the pattern on the press face, causing the raised portions, or embossed portions, in each tacky layer of the pad. Thus, each embossed portion is integrally formed in each layer and is comprised of an indentation on the underside, or non-tacky side, of each layer and a raised portion on the upperside, or tacky side, of each layer.

As can be understood, in the method as described above for forming the raised portions, the raised portions of each layer are aligned with the raised portions of each other layer. It is desirable, but not required, that the raised portions of each layer are aligned so that their shape may be easily maintained when the layers are stacked one upon another.

As can be seen in Figure 10, base portion 200 may also be formed to be complementary to the embossed layers. The surface 200A that defines a bottom of the recess of base portion 200, which receives within it the tacky layers 300, can be formed with raised portions 200B. These raised portions are positioned so that they are aligned with the raised portions in the tacky layers. Thus, the raised portions 200B on surface 200A are positioned within the indentations in the lower-most tacky layer when the layers are inserted into the recess in the base portion. As can be understood, these raised portions help to retain and maintain the raised portions in the tacky layer(s), particularly when only the lower-most layer(s) remain in the floor mat. However, it is not required that the base portion be formed with raised portions in practicing the present invention. The layers may be formed with raised portions whether or not the base portion includes complementary raised portions.

In another alternative embodiment for a tacky portion, the tacky portion could

also include a water dissipating capability. The tacky portion could be comprised of a hydrophobic porous structure which would assist in dissipating water from the surface of the tacky portion.

Figures 11 and 12 illustrate alternative embodiments for the floor mat of the present invention that provide a water dissipating capability for the tacky portion. As will be discussed, the embodiment of Figure 11 also helps to prevent a person from slipping on a potentially wet tacky portion.

Figure 11 illustrates an embodiment for tacky portion 300 where the tacky layers 301 and 302 of the tacky portion define a plurality of apertures 300C therein. The apertures of each layer are aligned with the apertures of each other layer. Thus, because of the aligned apertures in the layers, the tacky portion is able to drain surface water from the top-most surface of the tacky portion, or from the soles of a person's shoes that is standing on the tacky portion, through the apertures and to the base portion, within which the layers may be positioned. The base portion, as discussed previously, may include a water dissipation component and/or a water absorbing component which would move and/or absorb the surface water drained from the tacky portion through the apertures.

The apertures would also provide for helping to prevent slipping on a wet surface of the layers, not only by draining surface water from the surface, but by also providing for enhanced frictional contact between the shoes of the person stepping on the layer and the layer itself. The apertures provide for discontinuities in the surface of the layer which would enhance the frictional contact between the person's shoes and the layer. The edges of the surface of the layer which define the apertures would provide for this enhanced contact. The person's shoes would engage with the edges, thus enhancing frictional contact for the shoes. Additionally, the apertures would act as a suction on the bottoms of the person's shoes, e.g., like suction cups. This suction caused by the apertures on the person's shoes would also help to prevent slippage on the surface of the layer.

Figure 12 illustrates another embodiment for the floor mat of the present invention that also provides a water dissipating capability for the tacky portion. As can be seen, tacky portion 300 includes layers 301 and 302. Base portion 200 defines a

recess where layers 301 and 302 are disposed within the recess. A surface of the base portion that defines a bottom of the recess includes a raised portion 200C at or near a center position within the recess. Thus, the raised portion 200C of the base portion forms a raised portion in each of the layers. As can be understood, the raised portion
5 formed in the layers acts to dissipate surface water on the layers from the layers. The surface water will drain off of the layers under the force of gravity due to the raised portion.

Again, any number of layers may be included in tacky portion 300 in the embodiments of Figures 11 and 12.

10 It is also contemplated that a water absorbing powder, such as a talcum powder, could be provided in the present invention. The powder could either be integrated into the floor mat or be separately associated with the floor mat. The talcum powder would remove moisture from the soles of a person's shoes when the person stepped into the powder and the tacky insert portion could then remove the powder from the person's
15 soles, in addition to any dirt on the soles, when the person next steps on the tacky insert portion.

The present invention also provides an apparatus and method for determining when the tacky portion, or a layer in the tacky portion, should be removed for cleaning. Since the tacky portion assists in removing dirt from the soles of the person's shoes that
20 steps on the tacky portion, the tacky portion, or a layer thereof, will become dirty after some number of persons step on the it, assuming that any particular person's shoes are not exceptionally dirty. Therefore, it would be desirable to assist a person in deciding when to remove a dirty tacky portion for cleaning. Again, as discussed above, this determination can be made after a certain number of persons step on the mat. Thus, an
25 embodiment of the present invention as illustrated in Figure 13 includes a sensor system 700 that detects the presence of a person on the floor mat 100. The sensor system 700 may detect the presence of a person on base portion 200 and/or tacky portion 300. Since it is assumed that a person who steps on base portion 200 will also step on tacky portion 300, sensing the person's presence on either portion is sufficient for practicing the
30 present invention.

Sensor system 700 includes a sensor 710 and a display device 720, e.g., an LED,

coupled to sensor 710 and disposed on mat 100 such that it can be viewed. A power source, such as a battery, may be included on an underside of the floor mat. As mentioned above, sensor 710 senses the presence of a person on mat 100, e.g., in this embodiment on tacky portion 300. The sensor can detect the person's presence by
5 utilizing any of a variety of apparatuses and methods and can include sensing the pressure applied to the mat by the weight of the person standing on the mat or by sensing the motion across the surface of the mat by the movements of the person. Thus, pressure sensors and motion detectors may be utilized in the present invention. Sensor system 700 also determines the number of persons that have stepped on the mat 100 by
10 counting the number of sensed presences. After the number of presences equals a defined number of presences, a signal is provided to display device 720, e.g., illuminating the LED, which indicates that the tacky portion should be removed for cleaning. The present invention is not limited to removing the tacky portion at any particular number of sensed presences and the number may be adjusted based on the
15 particular environmental conditions in which the mat is utilized. Of course, as can be understood, after the dirty tacky portion or layer is removed and/or cleaned the sensor system can be reset to begin counting the total number of presences on the newly cleaned or exposed layer.

Alarm device 720 can provide either a visual, audible, or vibratory signal and
20 the present invention is not limited to providing any particular type of signal. For example, a visual signal could consist of a light that is illuminated when the floor mat should be cleaned and that is not illuminated when the floor mat does not require cleaning. Alternatively, the light could be continuously illuminated in one of a plurality of different colors, with each color signifying a different state of cleanliness for the floor
25 mat. For example, a green light could signify that the mat does not need cleaning. A yellow light could indicate the mat is reaching a state of dirtiness that will soon require cleaning. A red light, which could blink on and off, could signify that it is time to clean the floor mat.

The sensor system of the present invention may be utilized with any of the
30 embodiments disclosed for the cleanable portion, which may or may not be an insert and may or may not include layers and a tacky surface(s), and the base portion.

Whereas cleanable portion 300 has been discussed as an insert portion, it is not required that cleanable portion 300 be inserted into floor mat 100. There exists many alternative possibilities for associating cleanable portion 300 with floor mat 100. For example, cleanable portion 300 could be placed on top of base portion 200 or could be
5 positioned adjacent to base portion 200. The present invention is not limited to inserting any of the embodiments for cleanable portion 300 within base portion 200.

For example, Figure 14 illustrates a tacky portion 300 and a non-tacky portion 200, which may include a water dissipation component, a water absorbing component, and a cushioning component, as discussed previously, that are separable. As can be
10 seen in Figure 14, tacky portion 300 may be bordered within a border 500, which may be water absorbent, water dissipative, and include a cushioning component, and may include a plurality of apertures 342 and treads 344 within it. Tacky portion 300 can include any of the embodiments previously discussed. An attachment layer 600 is positioned on an underside of both border 500 of tacky portion 300 and non-tacky
15 portion 200. The border 500 and/or non-tacky portion 200 may be releasably attached to attachment layer 600. Thus, through attachment layer 600, border 500, and therefore tacky portion 300, and non-tacky portion 200 are releasably attachable to each other. In this manner, it is possible to, for example, position non-tacky portion 200 outside of a person's home on the front porch and tacky portion 300 within the person's home.

20 Attachment layer 600 can be any of a variety of materials. All that is required is that the attachment layer be able to releasably join one portion of the floor mat to a second portion of the floor mat. For example, a hook and loop fastener assembly, e.g., Velcro®, can be used with one portion of the assembly on the attachment layer and the other portion on the underside of the first portion of the floor mat and the second portion
25 of the floor mat. Alternatively, an adhesive can be utilized to releasably join the two portions of the floor mat to the attachment layer. Additionally, snaps, including any type of male/female connector, may be used to join the two portions to the attachment layer.

Figure 15 illustrates a first process step in utilizing an embodiment of the floor
30 mat 100 of the present invention. As was described previously, an embodiment of floor mat 100 includes a base portion 200 and an insert portion 300. As can be seen in Figure

15, and as was also discussed previously, a different graphic display 220 is present in the embodiment of Figure 15 than was illustrated in the embodiment of Figures 1 and 2. Thus, Figure 15 displays a "Hello" message with "smiley face" representations in the graphic 220.

5 As can be seen in Figure 15, in utilizing an embodiment of the present invention, a user would first step upon base portion 200. As discussed earlier, base portion 200 may include a water dissipating and/or absorbing component and is thus able to assist in removing any moisture from the soles of the person's shoes. As was also discussed earlier, because base portion 200, in one embodiment, also includes a cushioning
10 component, base portion 200 conforms to the person's soles when the person steps upon base portion 200. Whereas not illustrated in Figure 15, as discussed previously, an antibacterial composition, an antifungal composition, a fragrance, or any other cleaning substance may also be associated with floor mat 100 and applied to the soles of the person's shoes when the person applies pressure to floor mat 100.

15 As can be seen in Figure 16, the second process step in utilizing the present invention includes the person stepping onto insert portion 300 of floor mat 100. As discussed previously, insert portion 300 may include a tacky surface on a top side thereof for assisting in removing debris from the soles of the person's shoes. Additionally, antibacterial compositions, antifungal compositions, fragrances, or other
20 cleaning compositions may also be included within insert portion 300 for dispensing to the soles of the person's shoes.

After the person steps onto insert portion 300, the user then steps off of floor mat 100. As described previously, floor mat 100 may be cleaned after an accumulation of dirt on insert portion 300 by any of the methods described previously. Insert portion
25 300 may be removed from base portion 200 and cleaned, a layer may be removed from insert portion 300 to be cleaned or discarded, or insert portion 300 may be cleaned through erosion of insert portion 300. The present invention is not limited to any particular methodology for cleaning insert portion 300 of floor mat 100.

Figures 17-22 illustrate further alternative embodiments for the floor mat of the
30 present invention. As can be seen in Figure 17, in this embodiment for the floor mat, floor mat 1700 includes a cleanable portion 1710 and a plurality of base portions

1720A-D. As can be seen, cleanable portion 1710 is positioned within one of base portions 1720A-D. In this manner, the floor mat 1700 can be customized for a particular user by interchanging the cleanable portion 1710 with one of a variety of base portions 1720A-D. The base portions 1720A-D can be formed in any of a variety of physical configurations and can include any of a variety of themes, graphics, or colors. Thus, a common cleanable portion 1710 may be utilized with a variety of base portions 1720A-D.

Figures 18-20 illustrate another alternative embodiment for a floor mat 1800 in accordance with the principles of the present invention. As can be seen in Figure 18, floor mat 1800 also includes a cleanable portion 1810 and a base portion 1820. As discussed previously, cleanable portion 1810 is received within base portion 1820. In this embodiment, cleanable portion 1810 is comprised of a single sheet 1810A. The single sheet 1810A may be tacky on a top-side thereof and may include apertures therein to receive anti-slip nipples though it, as was also discussed previously. The single sheet 1810A, in this embodiment, may be removed and replaced with another sheet when dirty.

Figure 19 illustrates that a plurality of sheets 1810B-D, may be attached to each other and rolled into a roll 1830 of sheets. The sheets can be joined to each other at a perforated joint to provide for ease in separating a sheet from the roll of sheets. As can be understood, a sheet may be separated from the roll of remaining sheets and may be then inserted into base portion 1820.

Figure 20 illustrates that the roll of sheets 1830 may be stored in a storage device 1840, such as, for example, by mounting the roll of sheets 1830 on a cabinet door, which may be located in proximity to the floor mat. In this manner, replacements sheets are easily organized and stored for use.

Alternatively, instead of organizing the sheets in a roll and storing the roll in a cabinet, the sheets could be folder one upon another such that they form a flat package. The package of sheets could then be stored underneath of the floor mat 1800 where individual sheets could be removed from the package and from under the floor mat, when needed, similar to the way a Kleenex® tissue is dispensed.

Figure 21 illustrates another alternative embodiment for a floor mat in

accordance with the present invention. Floor mat 2100 also includes a cleanable/scrapable portion 2110 and a base portion 2120. In this embodiment, cleanable portion 2110 is formed, as discussed previously in this application, as a single structural member from a material which is tacky in composition throughout the entire cross-section of the material. As was also discussed previously, by forming portion 2110 from a uniform, tacky material, the portion 2110 does not necessarily have to be removed from the base portion 2120 to be cleaned. However, in the embodiment previously discussed, the cleanable portion 2110 could be cleaned by eroding the top surface of the insert portion as a result of use of the insert portion. In the embodiment of Figure 21, the cleanable portion is cleaned by scraping off a top surface of approximately 2-3 microns from the cleanable portion 2110 by utilizing a scraper 2130.

Scraper 2130 can include any of a variety of structures, however, all that is required is that the scraper be capable of removing a top surface from cleanable portion 2110. For example, any type of scraping surface can be utilized in scraper 2130, such as, for example, a dull knife, a razor, or a plane.

Scraper 2130 is movable on tracks 2140, 2145. Tracks 2140, 2145 are adjacent to cleanable portion 2110 and base portion 2120. Scraper 2130 may include wheels or other structures, e.g., pins, which are received within complementary structures, e.g., grooves, in tracks 2140, 2145. Thus, scraper 2130 is movable across cleanable portion 2110 on tracks 2140, 2145. The scraper 2130 may only include a scraping surface on the portion of scraper 2130 that is movable across cleanable portion 2110. Additionally, it is not required that two tracks be utilized. The scraper could be movable within a single track.

Scraper 2130 may be moved by any of a variety of methods, including using the foot of a user to engage with the scraper to move the scraper on the tracks.

Floor mat 2100 also includes a catch basin 2150 that may be included at one or both ends of tracks 2140, 2145. Catch basin(s) 2150 includes a recess into which is deposited the shavings from cleanable portion 2110 after scraper 2130 scrapes the cleanable portion. Scraper 2130 moves the shavings off of the cleanable portion and into the catch basin 2150. The shavings from the cleanable portion deposited into the catch basin may be removed from the catch basin in any of a variety of ways, including,

for example, by vacuuming the shavings from the catch basin or removing a detachable catch basin, throwing away the contents from the catch basin, and reinstalling the catch basin.

As can be understood, as the cleanable portion is shaved, the scraper is
5 commensurately lowered on tracks 2140, 2145 such that the surface of the scraper that engages with the cleanable portion remains engaged with the cleanable portion. As such, for example, the scraper may be mounted on a ratchet mechanism such that, as the scraper is moved across a complete width of the floor mat, the scraper actuates the ratchet such that the ratchet lowers the scraper. Alternatively, the scraper could remain
10 in the same relative position with respect to the tracks and the tracks could be ratcheted lower with respect to the base portion and cleanable portion. Additionally, the blade surface of the scraper could be lowered with respect to the scraper's structure such that the blade is moved relative to the cleanable portion and the base portion but the scraper remains in the same relative position with respect to the tracks and the cleanable portion
15 and the base portion.

Additionally, it is not required that a base portion be utilized in the embodiment for floor mat 2100. The cleanable portion alone can be utilized with the tracks adjacent the cleanable portion and the scraper movable on the tracks. A catch basin(s) could still be utilized. As such, Figure 22 illustrates an embodiment for floor mat 2200 that
20 includes a cleanable portion 2210 without use of a base portion. Cleanable portion 2210 is adjacent to tracks 2240, 2245. Scraper 2230 is movable on tracks 2240, 2245. A catch basin 2250 may be included at one or both ends of tracks 2240, 2245.

Thus, as described previously, the floor mat of the present invention includes features as described below. It should be noted that the below-listed features are not all-
25 inclusive of the features of the floor mat of the present invention. This specification in its entirety discloses all of the features of the floor mat of the present invention.

As described previously, in an embodiment, the floor mat includes a tacky surface having a top exposed surface with a surface area and a substantially non-paper anti-slip component disposed within the surface area of the top exposed surface of the
30 tacky surface to prevent slipping on the tacky surface when wet. Thus, the anti-slip component is in operable association with the top exposed surface of the tacky surface

to reduce slippage of a person on the top exposed surface who steps on the top exposed surface when the top exposed surface is wet. The anti-slip component may be integrally included in the top exposed surface.

The anti-slip component may include a plurality of channels as can be seen in
5 Figure 5 which are comprised of a non-tacky material where the plurality of channels is extendible from the top surface of the tacky surface in response to a person stepping on the tacky surface. Alternatively, the floor mat may include an anti-slip component that is extendible from the top surface of the tacky surface in the absence of a person standing on the tacky surface, such as the treads described previously. Thus, the treads
10 may be elongated members that have a length extending across the top exposed surface of the tacky surface which is substantially greater than a height that the treads extend above the top exposed surface of the tacky surface.

Additionally, the anti-slip component may be the apertures illustrated in Figure 11.

15 The various embodiments for an anti-slip component may be comprised of a non-tacky material, e.g., non-tacky members, and a water resistant material. Thus, the anti-slip components may be water resistant. The anti-slip components may also be comprised of a material such that they remain functional to prevent slipping on the tacky surface after a plurality of uses. As such, the anti-slip component may be comprised of
20 a sufficiently rigid material such that a configuration of the anti-slip component is substantially maintained after being stepped on a plurality of times by a person and may be comprised of a material having a composition which is substantially maintained after having been stepped on a plurality of times by the person.

As was also described previously, in an embodiment, the floor mat includes a
25 base portion having a non-tacky exposed top surface area 250 or contacting the soles of a person's shoes thereon and a tacky portion associated with the non-tacky exposed top surface area of the base portion and having a tacky exposed top surface area 350 for contacting the soles of the shoes thereon. As can be seen at least in Figure 1, the base portion non-tacky exposed top surface area 250 is at least as large as the tacky portion
30 tacky exposed top surface area 350.

The floor mat's base portion may include a cushioning component such that

when the person's shoes applies pressure to the base portion and the tacky portion, both the base portion and the tacky portion conform to a topography of a bottom of the person's shoes. The tacky portion may also include a tacky surface on a bottom side of the tacky portion.

5 In various embodiments, the base portion may circumscribe the tacky portion, as can be seen in Figure 1, or may be located adjacent to the tacky portion, as can be seen in Figure 14.

 As can also be seen in at least Figure 1, the floor mat has a base portion that has a continuous non-tacky exposed top surface area 250 for contacting the soles of a
10 person's shoes thereon and a tacky portion having a tacky exposed top surface area 350 for contacting the soles of the shoes thereon. As can be seen also in Figures 15 and 16, the non-tacky exposed top surface area of the base portion and the tacky exposed top surface area of the tacky portion are both of a size such that an entire sole of an adult-sized shoe is receivable thereon. The continuous non-tacky exposed top surface area
15 250 of the base portion has a first side area 252 disposed on a first side 352 of the tacky exposed top surface area of the tacky portion and a second side area 254 disposed on a second, opposing side 354 of the tacky exposed top surface area of the tacky portion. The first side area of the continuous non-tacky exposed top surface area of the base portion is larger than the second side area of the continuous non-tacky exposed top
20 surface area of the base portion.

 Figures 23A-27F, discussed in the following, illustrate embodiments of a user-configurable floor mat assembly which allows consumers to, for example, choose features suitable for a particular application of the floor mat. The user-configurable features may include a selection of alternative constituent components of the floor mat,
25 the colors and textures of the components and what materials the components are fabricated from. As noted earlier, factors influencing a particular configuration selected for a floor mat may include whether the floor mat is intended for indoor or outdoor use, regional climate, personal preference in home décor, and the like. For the convenience of the consumer, the user-configurable floor mats could be provided in kits that could
30 be ordered from a catalog, for example, or over the Internet.

Turning first to Figure 23A, a floor mat frame 2300 is shown which includes anti-slip components 2320 embodied as, for example, treads or ribs made of a pliable, water-resistant material such as rubber or plastic. The anti-slip components 2320 are provided on backing material of the frame, in an area of the frame 2310 for receiving
5 a tacky insert as described in greater detail below. Spaces (regions empty of material) 2330 may be formed in the backing material of the frame to reduce material cost, especially in cases where, for example, the mat frame is manufactured by injection molding.

Around the perimeter of the mat frame, a channel 2340 is formed integrally with
10 the backing material, and configured to receive a non-tacky insert, described in greater detail below. As shown in cross-sectional view 23A1-23A1, in one embodiment the channel 2340 tapers toward one end and forms a gap 2351 for receiving the non-tacky insert, which may also have a tapered shape adjacent to an edge thereof. The material of the floor mat frame 2300 may be made flexible, but still relatively stiff in the channel
15 2340, and the gap 2351 may be sized to be slightly smaller than the thickest portion of the non-tacky insert. Thus, the channel 2340 cooperates with the non-tacky insert to secure it in place.

An embodiment of channel 2340 in cross-sectional view 23A2-23A2 illustrates a plurality of teeth 2356 on an upper inner surface of the channel, and a plurality of
20 teeth 2357 on a lower inner surface of the channel. Depending on a type of water absorbing/water wicking material used for the non-tacky insert and the natural adhesion characteristics of the frame material used, a range of textures of inner surfaces of the channel may be used. The range may include a completely smooth texture, as illustrated in cross-sectional view 23A1-23A1, and progressively rougher textures, including a
25 substantially serrated texture as illustrated by the teeth of cross-sectional view 23A2-23A2. The teeth 2356, 2357 provide additional grip on a non-tacky insert that is placed into the floor mat frame, by engaging the non-tacky insert edge when extended within the channel.

Figure 23B illustrates an embodiment of a non-tacky insert 2370, which is sized
30 to fit into the floor mat frame 2300 described with reference to Figure 23A. The non-tacky insert is in contact with backing material of the frame when inserted therein.

Edges of the non-tacky insert define a space 2375 for exposing the area 2310 on the frame backing material for receiving a tacky insert. The non-tacky insert 2370 may have properties of components of the base portion 200 described earlier. For example, the non-tacky insert may have any combination of water-absorbing properties, water-
5 dissipating properties, water-wicking properties, cushioning properties, antibacterial properties, antifungal properties, a fragrance, graphics and the like as described above in connection with base portion 200. The non-tacky insert may, for example, be a carpet.

The non-tacky insert could be formed with a template designed to provide
10 dimensions for assuring that the non-tacky insert 2370 fits snugly and securely into the floor mat frame 2300. Templates could be designed to account for different material thicknesses of non-tacky inserts, for example if the non-tacky inserts were embodied as carpets. A thinner carpet might need to be sized slightly larger than a thicker carpet, so that the carpet material extends far enough into the channel 2340 to allow for a snug
15 fit.

Figure 23C illustrates the floor mat frame 2300 with non-tacky insert 2370 in place and secured into the channel 2340 of the floor mat frame. Depending upon the natural adhesive characteristics of contact surfaces of the frame and the non-tacky insert 2370, it could be helpful to apply a small amount of adhesive between contact surfaces
20 of the non-tacky insert and the floor mat frame to aid in keeping the non-tacky insert from moving around within the frame. The non tacky insert could be further secured into the frame by also adding adhesive inside the channel area as opposed to simply relying on the clamping forces.

Figure 23D also illustrates the floor mat frame 2300 with a non-tacky insert
25 2370 in place, but further shows a tacky insert 2335 configured to be received in area 2310 of the floor mat frame not covered by the non-tacky insert. The tacky insert 2335 may have properties of the tacky insert 300 described earlier. For example, the tacky insert may have any combination of tackiness properties, cleanability properties, erodibility properties, antibacterial properties, antifungal properties, a fragrance,
30 graphics and the like as described above in connection with insert 300. In particular, the tacky insert 2335 may comprise a plurality of tacky sheets, each having a pull tab

2350 for enabling the sheet to be separated and removed from the other tacky sheets. A topmost sheet may be removed, for example, once it is too soiled to be effective. Apertures 2345 may be formed in the tacky insert 2335 to receive anti-slip components 2320 and allow anti-slip components 2320 to extend through the apertures beyond a top
5 surface of the tacky insert, when the tacky insert is placed onto the area 2310 of the floor mat frame 2300.

The anti-slip components 2320 may have properties of treads 344 described above. For example, the anti-slip components 2320 may be deformable and arranged in number and location such that the tacky insert is able to remove debris from a
10 person's shoe when contacted by the shoe, and prevent slipping of the person on the tacky insert should the tacky insert become slippery when wet.

The tacky insert 2335 may be held in place with, for example, adhesive or double backed tape, designed to have sufficient adhesion to keep the tacky insert in place when the tacky insert is stepped on, but weak enough to be relatively easy to
15 replace once all the tacky sheets are used, and the tacky insert needs to be replaced.

Figure 23E illustrates the floor mat components described in Figures 23A to 23D wherein the non-tacky insert 2370 is embodied as carpet. Cross-sectional view 23E-23E illustrates an embodiment wherein the carpet is a pile-type carpet 2377. While a pile-type carpet is shown, other carpets types could be used, such as, by way of example
20 only, woven or braided carpets.

Figure 23F illustrates the floor mat components described in Figures 23A to 23D wherein the non-tacky insert 2370 is embodied as a mat constructed from a pliable, water-resistant material such as rubber or plastic.. Cross-sectional view 23F- 23F illustrates protrusions or nubs 2379 made of, for example, rubber, which may provide
25 both a water wicking function and some degree of anti-slip function.

Figures 24A-24D illustrate another embodiment of the present invention. In contrast to the embodiments shown in Figures 23A-23D, wherein a channel along the perimeter of a floor mat frame for receiving a non-tacky insert is integral with the floor mat frame, in the embodiments shown in Figures 24A-24D, a floor mat frame comprises
30 distinct and separable sections.

For example, as shown Figure 24A, a plurality of components 2400 may be used

to form an outer perimeter of the floor mat frame. The perimeter components comprise three sections 2410, for forming three sides of the frame perimeter, and a section 2411 having a cut-out area 2412 for forming a fourth side of the perimeter. Holes 2415 formed in ends of the perimeter sections 2410, 2411 enable fastening the perimeter sections to each other and to other components of the floor mat with, for example, snaps, grommets, or screws. Such fastening techniques are well known in the art, and, therefore, are not detailed here.

Cross-sectional view 24A1-24A1 illustrates a cross section of each perimeter section 2410. The perimeter sections form a channel 2440 configured to receive a non-tacky insert and a frame backing section, described in greater detail below.

An embodiment of the perimeter sections wherein channel 2440 includes teeth, along lines described above in connection with cross-sectional view 23A2-23A2, is illustrated in cross-sectional view 24A2-24A2.

As noted above, a perimeter section 2411 having a cut-out area 2412 is used for forming a side of the frame perimeter associated with a tacky insert. The cut-out area 2412 is configured to receive an end portion of a tacky insert, allowing the tacky insert to extend at least as far as an outer edge of the floor mat perimeter, when the tacky insert is placed in a floor mat assembled from components illustrated in Figures 24A-24D.

As further shown in Figure 24A, components of a floor mat frame according to the present embodiment further comprise corner sections 2420 having holes 2425 formed therein to enable assembling components of the floor mat with fasteners such as snaps, grommets, or screws. In cross section, corner sections 2420 may be similar to the perimeter sections 2410, 2411 as shown in views 24A1-24A1 and 24A2-24A2 of Fig. 24A. Assembling components of the floor mat using corner sections 2420 is described in greater detail below.

Figure 24B illustrates a floor mat frame backing section 2450 having holes 2455 formed adjacent to corners thereof. The backing section includes anti-slip components 2320. Figure 24B further illustrates a non-tacky insert 2370 including holes 2475 formed adjacent to corners thereof, and which is sized to fit in a floor mat frame assembled from components described above. The non-tacky insert could, for example,

be selected by an end user and cut with a template to the correct geometry to fit into an assembled floor mat frame, or could be ordered from a manufacturer pre-cut and selected from available materials identified in, for example, a catalog or a website on the Internet.

5 Figure 24C illustrates an assembly of components described in Figures 24A and 24B. The assembly is shown with the non-tacky insert 2370 in place within the perimeter sections and backed by the backing section 2450, and wherein the assembly is fastened together adjacent to corners thereof with fasteners 2425. Cross-sectional view 24C-24C illustrates details of connections which may be formed in assembling the
10 components. A gap 2460 in corner sections 2420 may be large enough to receive perimeter sections 2410 and 2411, non-tacky insert 2370, and backing section 2450. The non-tacky insert 2370 and backing section 2450 may be received within perimeter section 2411, and perimeter section 2411 may be received within perimeter section 2410. Alternatively, the non-tacky insert 2370 and backing section 2450 may be
15 received within perimeter section 2410, and perimeter section 2410 may be received within perimeter section 2411 (not shown). Such nesting techniques are widely used in the art, and are not detailed further here.

 An upper portion 2465 of a fastener 2425 extends through holes, described above, formed in each of the nested components, as illustrated in cross-sectional view
20 24C-24C. The upper portion of the fastener is connected to a lower portion 2470 of the fastener 2425 to lock the assembly together adjacent to corners thereof. The lower portion 2470 of the fasteners may be countersunk into the corner sections 2420 so that the mat sits flush against the floor. Depending upon the natural adhesive characteristics of the backing section 2450 and non-tacky insert 2370, it could be helpful to use a
25 small amount of adhesive between contact surfaces of the backing section and the non-tacky insert, to aid in keeping the non-tacky insert from moving around relative to the backing section and other components of the floor mat frame.

 Figure 24D illustrates a tacky insert 2335 configured to be received into the assembly of components shown in Figure 24C. The tacky insert is received within an
30 area 2310 of the assembly not covered by the non-tacky insert. An end portion of the tacky insert is received within cut-out area 2412 of perimeter section 2411.

Figures 24E-24F each illustrate an assembly of components described in Figures 24A to 24D, along the lines discussed above in connection with Figures 23E-23F.

Figure 25A illustrates yet another embodiment of components that may be assembled into a floor mat frame configured to receive a non-tacky insert and a tacky insert. A plurality of components 2500 may be used to form an outer perimeter of the floor mat frame. The perimeter components comprise three sections 2410, for forming three sides of the frame perimeter, and two sections 2530 for arranging along a fourth side of the perimeter as described in greater detail below. Holes 2415 are formed in ends of the perimeter sections 2410, and holes 2520 are formed in perimeter sections 2530 to enable fastening the perimeter sections to each other and to other components of the floor mat, along the lines described above. As illustrated in cross-sectional view 25A1-25A1, the perimeter sections 2410 form a channel 2440 configured to receive a non-tacky insert. As illustrated in cross-sectional view 25A2-25A2, the perimeter sections may include teeth. Also shown in view 25A2-25A2 is a slip resistant foot 2590, which may be applied to a bottom surface of the perimeter sections for contacting a floor, to provide additional slip resistance. The slip resistant foot may, for example, be made of latex or rubber.

Components of the floor mat frame further comprise corner sections 2420 having holes 2425 formed therein to enable assembling components of the floor mat with fasteners

In contrast to earlier described embodiments, in the present embodiment a frame backing section 2550 including anti-slip components 2320 may not extend across the space bounded by the outer frame perimeter. Rather, to economize on material, the frame backing section 2550 is smaller than in the earlier described embodiments, and is configured to be received within a U-shaped section 2520 as further illustrated in Figure 25A. The U-shaped section 2520 includes holes 2510 adjacent to ends thereof for enabling the U-shaped section to be connected to other components of a floor mat frame assembly as described in greater detail below.

Cross-sectional view 25A3-25A3 illustrates that the U-shaped section 2520 may comprise opposing channels 2572 and 2573. In a channel 2572 for engaging the frame backing section 2550, upper and lower inner surfaces for contacting the backing

section are smooth, while upper and lower inner surfaces of a channel 2573 for engaging a non-tacky insert have teeth to provide additional gripping force. A slip-resistant foot 2574 may be applied to a bottom surface of the U-shaped section for contacting a floor, to provide skid resistance between the floor and the mat assembly.

- 5 The slip resistant foot may, for example, be made of latex or rubber.

Figure 25B illustrates a non-tacky insert 2370 having holes 2475 formed adjacent to corners thereof, and sized to fit in a floor mat frame assembled from components described above. A space 2375 is provided for exposing the backing section 2550 when the floor mat components are assembled. Since in this embodiment
10 the non-tacky insert is not in contact with a frame backing material, a bottom surface of the non-tacky insert may be provided with an anti-slip coating such as latex, acrylic or rubber, to reduce slippage of the assembled floor mat when it is in contact with a floor.

Figure 25C illustrates an assembly of components described in Figures 25A
15 and 25B. The assembly is shown with the non-tacky insert 2370 in place within the perimeter sections 2410. Perimeter sections 2410, corner sections 2420 and the non-tacky insert 2370 are connected to each other by fasteners 2425 along the lines described above in connection with Figure 24C. Similarly, perimeter sections 2410, corner sections 2420, the non-tacky insert 2370 and perimeter sections 2530 are connected to
20 each other by fasteners 2425 along the lines described above in connection with Figure 24C. Perimeter sections 2530 are further connected to the U-shaped section 2520 and the backing section 2550 by fasteners 2425. The U-shaped section engages the backing section via a channel 2572, and engages the non-tacky section via a channel 2573 as described above.

- 25 Figures 25D-25E each illustrate an assembly of components described in Figures 24A to 25C, along the lines discussed above in connection with Figures 23E-23F.

Means for assembling floor mat components are not limited to hole-and-fastener-type arrangements as described above, merely by way of example and illustration. Other known connecting arrangements are readily contemplated, such as
30 tongue-and-groove-type connections or snap-together mating parts, or combinations of different known types of connecting arrangements.

Figure 26 illustrates another alternative embodiment of a floor mat according to the invention. A floor mat 2600 according to this embodiment comprises at least two non-tacky areas 2610 and 2630 adjacent to tacky sections 2650 and 2640, respectively. A non-tacky area 2620 extends between tacky sections 2650 and 2640, separating the
5 tacky sections. Each of tacky sections 2650 and 2640, and non-tacky areas 2610, 2620 and 2630 may be dimensioned to receive at least one adult-sized shoe thereon. The tacky sections may include apertures for anti-slip components 2320. The floor mat is configured to be received within a frame 2660.

Non-tacky areas according to this embodiment may have the properties of the
10 non-tacky insert 2370 described above. A person using the mat shown in Figure 26 could, for example, first remove moisture from his or her shoes by wiping his or her shoes on a non-tacky area to either side of tacky sections 2640 and 2650. By, for example, using the section 2620 between the tacky sections, along with either section 2630 or 2610, a user of the mat could reduce the distance he or she must straddle to
15 avoid contacting a tacky section.

Once the user had removed moisture from his or her shoes, he or she could then step onto either or both of the tacky sections 2640 and 2650 to further clean his or her shoes.

Figure 27 illustrates an embodiment of a floor mat wherein a surface for
20 cleaning a person's shoes consists solely of a tacky material 2730 having apertures for anti-slip components 2320. A frame 2710 engages edges of the surface. The tacky material 2730 may have properties of the tacky insert 2335 described above. The tacky material may comprise a plurality of tacky sheets, each having a pull tab 2350 for enabling the sheet to be separated and removed from the other tacky sheets.

25 Embodiments of a user-configurable floor mat as described above could be made from pliable, water-resistant materials such as rubber or plastic, and, by way of example only, could be injection molded. The embodiments described above could be extruded to further reduce the cost of manufacturing.

Further, as noted earlier, floor mat components could be made available in kits
30 that could be ordered from manufacturers. A selection of colors and materials for the components could be made available. Components for assembling a complete floor mat

could be ordered in a single package, or individual components could be ordered separately to replace used or damaged components, for example. Thus, unitary frames such as described in connection with Figures 23A-23F, frames assembled from separate components such as described in connection with Figures 24A-24F and 25A-25F, non-
5 tacky inserts and tacky inserts could each be sold separately. Further, individual frame components, such as perimeter sections or backing sections could each be sold separately.

All of the disclosed embodiments are illustrative of the various ways in which the present invention may be practiced. Additionally, any of the disclosed embodiments for
10 the base portion and the cleanable portion, and thus all of the features associated with these components, may be combined in any embodiment of the present invention and the present invention is not limited to only the particular combined embodiments disclosed. Other embodiments can be implemented by those skilled in the art without departing from the spirit and scope of the present invention.

What Is Claimed Is:

1. A floor mat assembly comprising:
a floor mat frame;
a non-tacky insert configured to be received within said frame; and
a tacky insert configured to be received within said frame.
2. The floor mat assembly of claim 1, wherein said frame comprises a perimeter forming a channel for receiving said non-tacky insert.
3. The floor mat assembly of claim 2, wherein said channel includes teeth.
4. The floor mat assembly of claim 1, wherein said frame includes a backing material for backing said non-tacky insert.
5. The floor mat assembly of claim 4, wherein said backing material includes spaces therein.
6. The floor mat assembly of claim 1, wherein said frame includes an area comprising anti-slip components.
7. The floor mat assembly of claim 6, wherein said tacky insert comprises apertures for receiving said anti-slip components.
8. The floor mat assembly of claim 1, wherein said tacky insert comprises a plurality of tacky sheets.
9. A floor mat assembly, comprising a plurality of components which may be assembled to receive a non-tacky insert and a tacky insert.
10. The floor mat assembly of claim 9, further comprising a non-tacky insert configured to be received within said assembled components.

11. The floor mat assembly of claim 9, further comprising a tacky insert configured to be received within said assembled components.
12. The floor mat assembly of claim 9, wherein said plurality of components comprises perimeter sections for forming a perimeter of said assembled components and receiving said non-tacky insert.
13. The floor mat assembly of claim 12, wherein at least one of said perimeter sections comprises a recess for receiving an end portion of said tacky insert.
14. The floor mat assembly of claim 9, wherein said plurality of components comprises a backing section for backing said non-tacky insert.
15. The floor mat assembly of claim 14, wherein said backing section comprises anti-slip components.
16. The floor mat assembly of claim 15, wherein said tacky insert comprises apertures for receiving said anti-slip components.
17. The floor mat assembly of claim 9, wherein said plurality of components comprises corner sections for connecting others of said components.
18. The floor mat assembly of claim 9, wherein said plurality of components comprises a U-shaped section configured to receive a backing section for said tacky insert.
19. The floor mat assembly of claim 18, wherein said U-shaped section comprises opposing channels, one of said opposing channels being configured to receive said backing section, and the other of said opposing channels being configured to receive said non-tacky insert.

20. The floor mat assembly of claim 19, wherein said channel configured to receive said non-tacky insert comprises teeth.
21. A floor mat assembly, comprising:
a plurality of perimeter sections;
a backing section connectable to said perimeter sections;
a plurality of corner sections connectable to said perimeter sections and backing section;
a non-tacky insert configured to be received within said perimeter sections; and
a tacky insert configured to be received on a area of said backing section.
22. A floor mat assembly, comprising:
a plurality of perimeter sections;
a U-shaped section connectable to said perimeter sections;
a backing section connectable to said U-shaped section;
a plurality of corner sections connectable to said perimeter sections;
a non-tacky insert configured to be received within said perimeter sections; and
a tacky insert configured to be received within said U-shaped section.
23. A floor mat comprising:
at least two tacky areas separated by an inner non-tacky area, each of said tacky areas being adjacent on an inner side thereof to said inner non-tacky area, and on an outer side thereof to an outer non-tacky area.
24. The floor mat of claim 23, wherein each of said tacky and non-tacky areas is sized to receive at least one adult shoe.
25. A floor mat comprising a surface for cleaning a person's shoes, wherein the surface consists solely of a tacky material comprising apertures for anti-slip features.

26. The floor mat of claim 25, wherein the tacky material comprises a plurality of tacky sheets.
27. The floor mat of claim 26, wherein each of said tacky sheets comprises a pull-tab for separating said each sheet from said plurality.
28. A method for commercially distributing user-configurable floor mats, comprising:
- providing a plurality of components which may be assembled into a floor mat, wherein a user may select from among said plurality of components to assemble at least one of a plurality of distinct floor mat configurations; and
 - distributing selected components to said user.
29. The method of claim 28, wherein said user may select from among a plurality of colors for said components.
30. The method of claim 28, wherein said user may select from among a plurality of materials of said components.
31. The method of claim 28, wherein said user may select from among a plurality of textures of said components.
32. The method of claim 28, wherein said plurality of components is listed in a public catalog.
33. The method of claim 32, wherein said public catalog is accessible via the Internet.
34. A floor mat assembly comprising separate components which may be assembled by a user, said separate components comprising a carpet section and a tacky section.

35. The floor mat assembly of claim 34, wherein said tacky section comprises a plurality of separable tacky sheets.

36. A floor mat assembly comprising a non-tacky portion and a separate receiving portion attachable to said non-tacky portion, said receiving portion being configured to receive a tacky insert.

37. The floor mat of claim 34, wherein said non-tacky portion is a carpet.

38. A method of producing and marketing a floor mat assembly, comprising:

manufacturing said floor mat assembly as separable components which may be assembled by an end user, said separable components comprising a carpet section and a tacky section; and

providing said separable components to an end user for assembly by said end user.

1/30




FIG. 1

2/30




FIG. 2

3/30




FIG.3

4/30




FIG. 4

5/30




FIG. 5




FIG. 6




FIG. 7

6/30






FIG. 8

7/30



8/30




FIG. 11




FIG. 12

9/30




FIG. 13

10/30




FIG. 14

11/30




FIG. 15

12/30




FIG. 16

13/30




FIG. 17




FIG. 18




FIG. 19

15/30




FIG. 20

16/30




FIG. 21








FIG. 22

17/30





19/30




FIG. 23E

20/30




FIG. 23F

21/30




FIG. 24A




FIG. 24B

22/30




FIG. 24C

23/30




FIG. 24D

24/30




FIG. 24E

25/30




FIG. 24F

26/30




FIG. 25A




FIG. 25B




FIG. 25C

28/30




FIG. 25D

29/30




FIG. 25E




FIG. 26




FIG. 27