



- (51) International Patent Classification:
A43B 23/02 (2006.01) A43B 1/00 (2006.01)
- (21) International Application Number:
PCT/US2012/039589
- (22) International Filing Date:
25 May 2012 (25.05.2012)
- (25) Filing Language: English
- (26) Publication Language: English
- (30) Priority Data:
61/460,776 27 May 2011 (27.05.2011) US
13/467,499 9 May 2012 (09.05.2012) US
- (71) Applicant (for all designated States except US): **NIKE INTERNATIONAL LTD.** [GB/US]; One Bowerman Drive, Beaverton, Oregon 97005 (US).
- (72) Inventors; and
- (75) Inventors/Applicants (for US only): **SHAFFER, Benjamin A.** [US/US]; c/o Nike, Inc., One Bowerman Drive, Beaverton, Oregon 97005 (US). **HOFFER, Kevin W.** [US/US]; c/o Nike, Inc., One Bowerman Drive, Beaverton, Oregon 97005 (US). **LE, Tony H.** [US/US]; c/o Nike, Inc., One Bowerman Drive, Beaverton, Oregon 97005 (US). **KANG, YunMi** [KR/KR]; c/o Nike, Inc., One Bowerman Drive, Beaverton, Oregon 97005 (US).
- (74) Agent: **RAUCHHOLZ, William F.**; Banner & Witcoff, Ltd., 1100 13th Street NW, Suite 1200, Washington, District of Columbia 20005-4051 (US).

- (81) Designated States (unless otherwise indicated, for every kind of national protection available): AE, AG, AL, AM, AO, AT, AU, AZ, BA, BB, BG, BH, BR, BW, BY, BZ, CA, CH, CL, CN, CO, CR, CU, CZ, DE, DK, DM, DO, DZ, EC, EE, EG, ES, FI, GB, GD, GE, GH, GM, GT, HN, HR, HU, ID, IL, IN, IS, JP, KE, KG, KM, KN, KP, KR, KZ, LA, LC, LK, LR, LS, LT, LU, LY, MA, MD, ME, MG, MK, MN, MW, MX, MY, MZ, NA, NG, NI, NO, NZ, OM, PE, PG, PH, PL, PT, QA, RO, RS, RU, RW, SC, SD, SE, SG, SK, SL, SM, ST, SV, SY, TH, TJ, TM, TN, TR, TT, TZ, UA, UG, US, UZ, VC, VN, ZA, ZM, ZW.
- (84) Designated States (unless otherwise indicated, for every kind of regional protection available): ARIPO (BW, GH, GM, KE, LR, LS, MW, MZ, NA, RW, SD, SL, SZ, TZ, UG, ZM, ZW), Eurasian (AM, AZ, BY, KG, KZ, RU, TJ, TM), European (AL, AT, BE, BG, CH, CY, CZ, DE, DK, EE, ES, FI, FR, GB, GR, HR, HU, IE, IS, IT, LT, LU, LV, MC, MK, MT, NL, NO, PL, PT, RO, RS, SE, SI, SK, SM, TR), OAPI (BF, BJ, CF, CG, CI, CM, GA, GN, GQ, GW, ML, MR, NE, SN, TD, TG).

Published:

- with international search report (Art. 21(3))
- before the expiration of the time limit for amending the claims and to be republished in the event of receipt of amendments (Rule 48.2(h))

(54) Title: SHOE WITH COMPOSITE UPPER AND METHOD OF MAKING THE SAME




FIG. 19

(57) Abstract: Uppers for article of footwear may include one or more skin layers attached to a base layer, wherein at least one of the skin layers is at least partially transparent or translucent. The transparent or translucent skin layer may be applied over other elements of the upper (e.g., other skin layers, base layers, reinforcing layers, etc.) to provide interesting color change options and color palettes for the upper. Additional aspects of this invention relate to production of curved tongue composite structures and/or footwear having a bonded (hot melt) side seam for forming the upper (and optionally do not include a rear heel seam).



SHOE WITH COMPOSITE UPPER AND METHOD OF MAKING THE SAME

CROSS-REFERENCE TO RELATED APPLICATIONS

[01] This application is a non-provisional application based on U.S. Provisional Patent Appln. No. 61/460,776, filed May 27, 2011 and entitled “Shoe with Composite Upper and Method of Making Same.” This prior provisional application is entirely incorporated herein by reference. This application also claims priority benefits based on U.S. Patent Appln. No. 13/467,499 filed May 9, 2012 and entitled “Shoe with Composite Upper and Method of Making the Same,” which application also is entirely incorporated herein by reference. Additionally, aspects of the inventions described in this patent application may relate to or be useful with, at least in part, the technology described in: (a) U.S. Patent Application No. 13/029,502, titled “Shoe with Composite Upper and Foam Element and Method of Making Same” and filed February 17, 2011, (b) U.S. Patent Application No. 12/603,494, titled “Composite Shoe Upper and Method of Making Same” and filed October 21, 2009, and (c) U.S. Patent Application No. 12/603,498, also titled “Composite Shoe Upper and Method of Making Same” and filed October 21, 2009. Each of these prior applications is entirely incorporated by reference herein.

BACKGROUND

[02] The design of many types of footwear is often driven by conflicting considerations. As but one example, it is normally desirable for an athletic shoe to have a construction that supports and protects a wearer's foot during a particular athletic endeavor. However, “breathability” is also a desirable quality for many types of athletic shoes. Specifically, air flow from the outside to a shoe interior can help relieve the effects of heat and perspiration that typically build up around a foot during sporting activities. Unfortunately, many materials that provide good support and foot protection can block air and moisture flow. Conversely, many materials that facilitate air and moisture flow provide little support or protection to the wearer's foot.

[03] One solution is to fabricate a shoe in which some portions are formed from supportive/protective materials and some portions are formed from breathable materials. However, this can increase the complexity of the fabrication process and increase cost. Moreover, footwear design (including athletic footwear design) is also driven by aesthetics.

A complex production process developed to fabricate a complex shoe can potentially limit a manufacturer's ability to vary that shoe's design to achieve different aesthetic effects.

SUMMARY

[04] This Summary is provided to introduce a selection of concepts in a simplified form that are further described below in the Detailed Description. This Summary is not intended to identify key features or essential features of the invention.

[05] In at least some embodiments, a shoe has an upper that includes a bonded mesh composite panel. The panel may include a substrate layer formed from synthetic leather or another material chosen to provide support and protection to the foot of a wearer, but that can include ventilation openings. The panel further may include a mesh layer that is bonded to the substrate layer and spans one or more of the ventilation openings. One or more panels of thermoplastic polyurethane (TPU) or other desired material can also be included in certain regions so as to create skin layers that provide abrasion protection for the mesh layer and/or to achieve different aesthetic effects.

[06] A bonded mesh composite panel for an upper is in some embodiments fabricated by first arranging panels of substrate, mesh and skin layer materials into an assembly corresponding to the locations of those panels in a completed upper. The assembly may also include separate layers of hot melt bonding material interposed between the substrate, mesh and skin layers, and/or a bonding material may be a component of a substrate, mesh and/or skin layer material. The assembly is then pressed at an elevated temperature so as to melt the bonding material and/or the skin layers and bond the elements together. Before the pressed assembly completely cools, it may be pressed a second time in an unheated press. A heat-conductive compressible pad can be used in the pressing process to create a surface effect in the skin layers that reveals a pattern of an underlying mesh layer (or other layer).

[07] In some embodiments, a bonded mesh composite panel is used to form a three-dimensional upper shell that includes extensions used for double-lasting and/or to otherwise provide a shelf to support foam padding. The foam padding may be, e.g., a foam midsole. The extensions of the upper shell may be located in a lower portion of the shell and may be bonded to the foam midsole in a heel, midfoot and/or forefoot regions.

[08] Additional aspects of this invention relate to uppers for article of footwear (and blanks for making such uppers). These uppers may include, for example: (a) a base layer (including one or more separate pieces); (b) a first skin layer (in one or more separate pieces) partially covering the base layer; and (c) a second skin layer (in one or more separate pieces) partially covering the base layer. The skin layers may be overlapped in varying manners such that in a single upper: (a) at a first portion of the upper, the first skin layer directly contacts the base layer and is covered by the second skin layer and (b) at a second portion of the upper, the second skin layer directly contacts the base layer and is covered by the first skin layer. The base layer may include a mesh material layer and/or a support layer (such as a synthetic leather, a thermoplastic polyurethane, etc.).

[09] Another potential aspect of this invention relates to uppers for articles of footwear (and blanks for making such uppers) that may include, for example: (a) a base layer; (b) a first skin layer partially covering the base layer, wherein the first skin layer has a first color; and (c) a second skin layer partially covering the base layer, wherein the second skin layer has a second color and is at least partially transparent or translucent. In such upper constructions, at a first portion of the upper, the first skin layer may directly contact the base layer and may be covered by the second skin layer such that a color appearance at the first portion of the upper constitutes a blend of the first color and the second color. If desired, in at least some examples of this invention, the color of the first skin layer may be different from that of the second skin layer. Also, if desired, the first skin layer may be at least partially transparent or translucent. These differently colored skin layers also may be layered in varying manners on a single upper construction as generally described above.

[10] Still another aspect of this invention relating to uppers (or blanks for making them) may include, for example: (a) a base layer having a first color; (b) a support layer (e.g., a mesh layer, a synthetic leather layer, a TPU, a skin layer, an eyelet reinforcing element, a toe reinforcing element, a heel reinforcing element, a decorative element, another support element, etc.) provided at least partially on the base layer, wherein the support layer has a second color; and (c) a first skin layer partially covering the base layer and the support layer, wherein the first skin layer has a third color and is at least partially transparent or translucent. This example upper may have: (a) a first color appearance at a first portion where the first skin layer is absent, (b) a second color appearance different from the first color appearance at a second portion where the first skin layer covers the base layer and the support layer is

absent, and (c) a third color appearance different from the first and second color appearances at a third portion where the first skin layer covers the support layer.

[11] Another aspect of uppers in accordance with at least some examples of this invention (and the blanks for making such uppers) may include: (a) a base layer (made from one or more separate pieces); (b) a first skin layer portion applied to the base layer, wherein the first skin layer portion includes a first engagement edge; and (c) a second skin layer portion applied to the base layer, wherein the second skin layer portion includes a second engagement edge. The second engagement edge may be provided on a piece of the base layer that is a unitary, one piece construction with a portion of the base layer that extends around a rear heel area of the upper (if desired, the base layer may be made from multiple pieces such that the first skin layer portion is on a first piece of the base layer and the second skin layer portion is on a second, separate piece of the base layer). The first skin layer portion and the second skin layer portion may be engaged together at a bonded joint (e.g., by hot melt bonding) provided at an overlap of the first engagement edge and the second engagement edge, wherein the bonded joint is located along a medial midfoot side region of the upper. Alternatively, if desired, the bonded joint could be located at a lateral midfoot side region of the upper. Uppers in accordance with this aspect of the invention need not include a seam in the rear heel area.

[12] Another example aspect of this invention relates to tongue members for articles of footwear. Such tongue members may include, for example: (a) an interior layer made from an interior layer panel having a first width in a medial side to lateral side direction; (b) an exterior layer made from an exterior layer panel having a second width in the medial side to lateral side direction, wherein the first width is less than the second width; and, optionally, (c) an intermediate layer between the interior layer panel and the exterior layer panel. The interior layer panel and the exterior layer panel may be bonded to one another using a curved platen or other curved support surface and formed as a curved composite tongue member (e.g., by hot melt bonding).

[13] Finally, additional aspects of this invention will relate to shoes including the uppers and/or other components described above (e.g., by engaging the upper with a sole structure (e.g., a midsole, an outsole, etc.)), as well as to methods of making the uppers, shoes, and/or other components.

BRIEF DESCRIPTION OF THE DRAWINGS

[14] Some embodiments are illustrated by way of example, and not by way of limitation, in the figures of the accompanying drawings and in which like reference numerals refer to similar elements.

[15] FIGS. 1A and 1B are, respectively, lateral and medial views of a shoe according to some embodiments.

[16] FIG. 1C is an enlarged view of the area indicated in FIG. 1A showing an aspect of the mesh composite in the embodiment of FIGS. 1A and 1B.

[17] FIG. 2 is a partially schematic diagram showing creation of a multilayer mesh composite according to some embodiments.

[18] FIG. 3 is a partially schematic cross-sectional view from the location indicated in FIG. 1A showing the structure of a mesh composite according to some embodiments.

[19] FIGS. 4A1 through 4L show operations in a process, according to at least some embodiments, to fabricate a unibody upper panel for the shoe of FIGS. 1A and 1B.

[20] FIGS. 5A through 5G show additional operations in a process, according to at least some embodiments, to fabricate an upper for the shoe of FIGS. 1A and 1B.

[21] FIGS. 6A and 6B show examples of composite upper portions, according to some additional embodiments, that include an additional layer for reinforcement, support and/or padding.

[22] FIG. 7 shows a toe cap extension in a shoe according to some embodiments.

[23] FIG. 8 shows a layer of skin material used to reinforce a transition from a mesh composite portion of a shell to another portion according to some embodiments.

[24] FIGS. 9A through 9C show an assembly jig that can be used in fabrication methods according to some embodiments.

[25] FIGS. 10A through 10E show assembly of panel elements for a unibody upper shell according to another embodiment.

[26] FIG. 11 shows a bonded composite panel formed from the panels assembled in FIGS. 10A through 10E.

[27] FIG. 12 shows the bonded composite panel of FIG. 11 after trimming.

[28] FIG. 13 shows an inner face of the trimmed, bonded composite panel of FIG. 12.

[29] FIG. 14 shows a three-dimensional upper shell formed from the trimmed, bonded composite panel of FIG. 12 and placed onto a last.

[30] FIGS. 15A and 15B show attachment of the three-dimensional upper shell from FIG. 14 to a foam midsole.

[31] FIG. 16 shows a completed shoe that includes the upper shell and attached foam midsole from FIG. 15B.

[32] FIGS. 17A through 17E illustrate example parts that may be incorporated into an upper construction in accordance with another example of this invention.

[33] FIGS. 18A through 18E illustrate example steps for making the example upper construction shown in FIGS. 17A through 17E.

[34] FIG. 19 is provided as an aid to explain various features of this example upper construction according to the invention.

DETAILED DESCRIPTION

[35] At least some embodiments include an athletic shoe or other type of footwear in which an upper has a panel formed from a bonded mesh composite. The mesh composite includes an inner substrate layer that provides support and protection in appropriate regions based on activities for which the shoe is intended. The substrate layer can also include one or more openings for ventilation, weight reduction or other purposes. The mesh composite

further includes a mesh layer that is bonded to the substrate layer and located on the outer side of the substrate in the finished shoe. This construction offers several advantages. For example, the mesh can reinforce the substrate and help retain individual portions of the substrate in a desired arrangement, thereby permitting larger ventilation holes in the substrate. Moreover, covering those ventilation holes and surrounding substrate regions with a mesh can avoid edges that might separate as the shoe wears. A “skin” layer may cover the mesh layer in one or more areas to provide additional durability and/or for decorative purposes. In some embodiments, all or substantially all of the upper is formed from a mesh composite panel that extends around the heel counter region. In other embodiments, the upper may have a mesh composite panel in a front portion that is bonded or otherwise attached to a separate panel that forms a rear portion of the upper.

Definitions

[36] To assist and clarify the subsequent description of various embodiments, various terms are defined herein. Unless otherwise indicated, the following definitions apply throughout this specification (including the claims). The “interior” of a shoe refers to space that is occupied by a wearer’s foot when the shoe is worn. The “inner side” of a panel or other shoe element refers to the face of that panel or element that is (or will be) oriented toward the shoe interior in a completed shoe. The “outer side” of an element refers to the face of that element that is (or will be) oriented away from the shoe interior in the completed shoe. In some cases, the inner side of an element may have other elements between that inner side and the interior in the completed shoe. Similarly, an outer side of an element may have other elements between that outer side and the space external to the completed shoe.

[37] A “bonded” composite element is an element that includes substituent elements (e.g., panels of textile or other materials) that are bonded to one another. Bonding includes bonding through use of glue or other adhesives, through melting and subsequent solidification of a bonding material, and/or through melting and subsequent solidification of a substituent element, but excludes stitching, stapling or similar types of mechanical attachment. Although a bonded composite element may include stitching or other types of mechanical attachment (e.g., to attach the bonded composite element to another element, to shape the bonded composite element), the bonded composite does not rely on that stitching or

other mechanical attachment to structurally connect the substituent elements of the bonded composite.

[38] Certain regions of an upper are defined by reference to the anatomical structures of a human foot wearing a shoe that is properly sized for that foot. One or more of the below-defined regions may overlap. The “forefoot” region of an upper is the portion of the upper that will generally cover the metatarsal and phalangeal bones of the wearer’s foot, and which will extend beyond the wearer’s toes to the frontmost portion of the upper. The “midfoot” region of an upper is the portion of the upper that will generally cover the cuboid, navicular, medial cuneiform, intermediate cuneiform and lateral cuneiform bones of the wearer’s foot. The “hindfoot” region of an upper extends from the midfoot region to the rearmost portion of the upper and covers the wearer heel. The hindfoot region covers the sides of the calcaneus bone of a wearer and may, depending on a particular shoe configuration, cover some or all of the wearer’s talus bone (ankle).

[39] The “top forefoot” and “top midfoot” regions of an upper will generally cover the upper surfaces of a wearer’s forefoot and midfoot bones described above. The “toe” of the upper is the portion that will generally cover the tops and fronts of the toes and that extends from the top forefoot region to the lowest edge of the upper in the direction of the sole. The “lateral forefoot” region extends between the top forefoot and the lowest edge of the upper in the direction of the sole and between the toe and lateral midfoot regions. The “lateral midfoot” region extends between the top midfoot region and the lowest edge of the upper in the direction of the sole and between the lateral forefoot and hindfoot regions. In a similar manner, the “medial forefoot” region extends between the top forefoot region and the lowest edge of the upper in the direction of the sole and between the toe and medial midfoot regions, the “medial midfoot” region extends between the top midfoot region and the lowest edge of the upper in the direction of the sole and between the medial forefoot and hindfoot regions. The “topfoot region” includes the top forefoot and top midfoot regions. The “lateral side” region includes the lateral forefoot and lateral midfoot regions. The “medial side” region includes the medial forefoot and medial midfoot regions.

Shoe With Mesh Composite Upper Panel

[40] FIG. 1A is lateral view of a shoe 10 according to at least some embodiments. FIG. 1B is a medial view of shoe 10. In the embodiment of FIGS. 1A and 1B, the upper 11 of shoe 10 includes a bonded mesh composite panel 16 and a foxing panel 17. Additional details of mesh composite panel 16 and its construction, as well the attachment of mesh composite panel 16 to foxing panel 17, are provided below in connection with FIGS. 1C and 4A1-4K.

[41] In the embodiment of shoe 10, mesh composite panel 16 generally covers the toe region, the top, lateral and medial forefoot regions, the top, lateral and medial midfoot regions, and portions of the hindfoot region. The foxing panel 17 covers the remainder of the hindfoot region. As explained in more detail below, shoe 10 of FIGS. 1A and 1B is merely one example of footwear according to various embodiments. In other embodiments, a mesh composite front portion of an upper panel may be joined to a non-mesh-composite rear portion at different locations and/or along joints having different configurations. In still other embodiments (e.g., an embodiment such as is described in connection with FIGS. 10A-16), an entire upper shell is formed from a mesh composite that includes a contiguous substrate element that completely surrounds a wearer foot in a completed shoe

[42] FIG. 1C is an enlarged view of the area indicated in FIG. 1A showing the details of a portion of mesh composite panel 16 in the embodiment of shoe 10. A layer 28 of mesh material is bonded to a layer 27 of substrate material in a manner described below. For illustrative purposes, a portion of the mesh layer 28 below broken line 30 has been removed in FIG. 1C to further expose substrate layer 27. For convenience and to avoid obscuring the drawings with excessive detail, the mesh material of layer 28 (and of mesh layers in some other embodiments) is shown in the various drawing figures as a simple and relatively coarse grid pattern with a diagonal orientation. Actual materials used for mesh layer 28 (or for mesh layers in other embodiments), examples of which are provided below, may have a more complex and/or finer weave structure. A panel 36a of skin material is in turn bonded to mesh layer 28 and/or to substrate layer 27 to form a skin layer. As is also discussed in more detail below, the layer of skin material may conform to the mesh material of layer 28 so as to reveal a surface texture having a contour corresponding to that of the mesh material. For simplicity, a view of this conformance perpendicular to a skin layer is represented in the drawings as a partially broken version of the grid pattern used for mesh layer 28.

[43] Returning to FIGS. 1A and 1B, the substrate material of layer 27 extends across all of mesh composite panel 16 except for a tongue opening 26, lateral ventilation holes 31 and 32, medial ventilation hole 33, and top forefoot ventilation hole 34. Other embodiments have an inner substrate material layer that includes more or fewer holes, and/or holes of different shapes and/or in different locations. As is further explained below in connection with FIGS. 4A1-4K, the mesh material of layer 28 is bonded to substrate layer 27 over most of panel 16 in the embodiment of FIGS. 1A and 1B, although this may not be the case in other embodiments.

[44] The embodiment of FIGS. 1A and 1B also includes skin layers formed by panels 36a, 36b, 36c and 36d. The skin material of panels 36b and 36c similarly conforms to the mesh material of layer 28 so as to reveal a surface texture corresponding to the mesh. The mesh material underlying panel 36d is compressed so as to provide a smooth texture on the external surface of panel 36d, as is also described more fully below.

[45] Because mesh layer 28 is directly bonded to substrate layer 27, the combined strength of the mesh and substrate materials obviates the need for another material on the outside surface of upper 11 to provide tensile strength. This permits upper 11 to be much lighter than is possible using various conventional shoe construction techniques. Panels of skin material (which are relatively lightweight) can be included in certain areas of an upper where abrasion protection is helpful.

[46] Ventilation holes 31, 32, 33 and 34 in substrate layer 27 allow air to flow through perforations of the mesh material of layer 28. This air flow helps to cool and dry the foot of a wearer of shoe 10. In some embodiments, there are no additional material layers separating substrate layer 27 and the foot of a wearer (or the socked foot of a wearer) in the regions around one or more of holes 31, 32, 33 and 34, and air can directly reach the interior of shoe 10. In other embodiments, upper 11 of shoe 10 may include an additional lining (e.g., a "bootie") between substrate layer 27 and a wearer's foot. In such embodiments, air cannot directly reach the wearer's foot through holes 31, 32, 33 and 34, but ventilation is still improved relative to many conventional constructions, as materials used for a bootie or other liner are typically porous and significantly more breathable than materials used for substrate layer 27.

[47] The number, size and location of ventilation holes will vary in different embodiments. In some embodiments, an upper may include ventilation holes as small as (or smaller than) 2 mm in diameter, while in other embodiments, the ventilation holes may be quite large and cover a substantial portion of the upper. In some embodiments, minimum spacing between some ventilation holes can be based on the minimum area needed to effectively bond the mesh and substrate layer materials used for a particular embodiment.

[48] The material of skin layer panels 36a, 36b, 36c and 36d provides abrasion protection for mesh layer 28. A skin material panel can also be added for decorative purposes. For example, skin material elements can include one or more additional elements such as element 36d in the shape of a logo or other identifier of the manufacturer of shoe 10. Although much of skin layer panels 36a-36d are overlaid on the mesh material of layer 28, some portions of skin layer panels are directly bonded to substrate layer 27 without an interposing layer of mesh material. For example, and as described in more detail below in connection with FIGS. 4A1-4K, skin layer panels 36a-36c cover some portions of substrate layer 27 over which mesh layer 28 does not extend. Moreover, and as also described in more detail below, a portion of skin layer panel 36a overlays (and is bonded to) foxing panel 17. In some cases, an interposing mesh layer is omitted for structural purposes. An interposing mesh layer could also be omitted for decorative reasons.

[49] Shoe 10 includes a foamed ankle collar 141, a heel counter (not shown) and a tongue 41. Tongue 41 may be stitched or otherwise bonded to the inside of upper 11. Attachment of collar 141 is described below. Upper 11 may be bonded to a midsole 42 in any of various manners. In some embodiments, upper 11 is slip lasted and attached to a strobel layer, with that strobel layer then bonded to an upper face of midsole 42. Other types of constructions are used in other embodiments to attach upper 11 to a midsole or other sole component. One example of such a construction is discussed below in connection with FIGS. 15A and 15B.

[50] As can also be seen in FIGS. 1A and 1B, the pattern of the mesh material of layer 28 (represented in FIGS. 1A through 1C as a coarse diagonal grid) is exposed over a substantial portion of composite panel 16. In particular, that mesh material is directly visible in regions of panel 16 not covered by one of skin layer panels 36a-36d. In much of the areas covered by skin layer panels, however, the pattern of the underlying mesh material is still visible because of the skin layer conformance to that mesh. In some embodiments, the pattern of the mesh

material in the mesh layer is visible over a substantial portion (or even most) of the surface of the mesh composite panel in the finished shoe. This pattern may be visible directly in areas where the mesh is exposed (e.g., over openings 31, 32, 33 and 34 and in the regions surrounding those openings) or as a contour of a skin layer panel (e.g., the portion of panel 36a shown in FIG. 1C). In some embodiments, the percentage of exposed mesh will depend on the purpose of the shoe.

[51] Shoe 10 of FIGS. 1A and 1B is merely one example of a shoe having a multilayer bonded mesh composite upper panel according to certain embodiments. Additional embodiments include other styles of shoes, shoes with different types of midsole/outsole combinations, shoes with different patterns of substrate material holes, and shoes with different skin material configurations and arrangements. Still other embodiments include shoes with additional layers and/or layers of additional types of materials.

[52] FIG. 2 is a partially schematic diagram showing creation of multilayer bonded mesh composite panel 16. Substrate layer 27, mesh layer 28, and skin layer panels 36a-36d are assembled in a manner described below. For purposes of explanation, substrate layer 27 is shown in cross-sectional views with fine stippling, skin panels are shown with coarse stippling, and mesh layer 28 is shown with cross-hatching. The open areas between the cross-hatched portions of mesh layer 28 correspond to mesh material openings. Interposed between mesh layer 28 and substrate layer 27 is a layer 39 of hot melt bonding material (shown with small black dots). Another layer 40 of hot melt bonding material is placed between mesh layer 28 and skin layer panels 36a-36d. After the layers are tacked together, the assembly is covered with a heat conductive silicone pad 44 and put into a heated press 45, with the skin material panels 36a-36d facing silicone pad 44. Heat and pressure are then applied to activate the bonding material and/or to cause the skin material to reach its melting point. As a result, the bonding material in layers 39 and 40 bonds substrate layer 27 to mesh layer 28 and mesh layer 28 to skin layer panels 36a-36d, the skin material of panels 36a-36d begins to conform (and further bond) to the mesh material of layer 28, and the various layers bond to become a one-piece panel. In some instances, the bonding material in layers 39 and 40 (or otherwise applied) may pass through openings in the mesh 28 to reach one another. After that heated pressing, the layers are then pressed again in a separate cool press (not shown). Additional details of the pressing operations are provided below.

[53] In some embodiments, a separate panel of hot melt bonding material may not be placed between a skin layer panel and a mesh or substrate layer panel. Instead, the skin layer panel is bonded to the other layer(s) solely through the melting of the skin layer panel so as to fuse the skin layer to one or more other layers. Similarly, inserting a separate panel of hot melt bonding material between a substrate material panel and a mesh material panel is unnecessary in some embodiments. In certain embodiments, for example, a substrate layer 27 may comprise a laminate that includes a first material layer (e.g., artificial leather) and a second material layer (e.g., thermoplastic polyurethane) prelaminated to a face of the first material layer by the substrate material manufacturer. Panels of that two layer substrate material can then be cut to shape by a shoe manufacturer and used as substrate layer 27. In such an embodiment, the second material layer would be oriented to face mesh layer 28 and would melt during pressing so as to fuse to mesh layer 28 (and to the skin layer(s)), and the separate layer of bonding material 39 could be omitted. Indeed, some embodiments may not require any separate bonding material layers, and could rely on melting of the skin and/or substrate layers themselves to achieve bonding. As another alternative, large sections of mesh, substrate or skin material could have a separate hot melt bonding material (e.g., such as would be used for layer 39 or 40) pre-applied (e.g., by the material supplier or in a preprocessing step by a shoe manufacturer) prior to cutting of individual upper panels from the large material sections. Combinations of these techniques could also be used.

[54] FIG. 3 is a partially schematic cross-sectional view from the location indicated in FIG. 1A showing the structure of mesh composite panel 16 after hot and cold pressings. For purposes of illustration, three different regions are labeled in FIG. 3. Region A corresponds to the location of the mesh composite panel 16 where hole 32 in substrate layer 27 is located. Because no other material layers are present in region A, the mesh material of layer 28 is not bonded to another material in this region. If upper 11 includes a liner (i.e., on the inner side of substrate layer 27), such as is shown in FIG. 3 with a broken line, the mesh material of layer 28 is in at least some embodiments not bonded to that liner in the region of holes in substrate layer 27. In some embodiments, however, a liner may be stitched to mesh layer 28 and/or other portions of upper shell 11 in some locations and/or bonded to the inside surface of substrate layer 27 at some locations.

[55] Region B in FIG. 3 corresponds to a location of mesh composite panel 16 where no skin material panel is present. Region C corresponds to a location where substrate layer 27,

mesh layer 28 and skin layer panel element 36a are present. In regions B and C, and throughout mesh composite panel 16, the substrate material of layer 27 and the mesh material of layer 28 are bonded together at all surfaces where those two materials are in contact. Similarly, skin layer element 36a and the substrate material of layer 27 are bonded together at all surfaces where those materials contact, as are panel 36a and the mesh material of layer 28. Other skin material panels are similarly bonded to the substrate material of layer 27 and the mesh material of layer 28. Bonding substrate and mesh materials, and/or skin materials, effectively fuses the materials together so as to create a material that is stronger than the individual components.

[56] As also seen in region C, the skin material of panel 36a conforms to the mesh material of layer 28 so that a contour of the mesh material pattern is revealed through panel 36a. Other skin material panels that overlay mesh layer 28 similarly may conform to the mesh material. In this manner, upper 11 can have a more continuous appearance than might otherwise be possible. By providing layers of skin material that have a texture revealing an underlying mesh material, a potential purchaser of shoe 10 is also made aware of the structure of shoe 10. Moreover, it is believed that the conformal nature of the contact between a skin material panel and underlying mesh and substrate layer materials helps to increase the bonded surface areas and overall material strength.

[57] As indicated above, the substrate material of layer 27 provides support and protection for the foot of a wearer of shoe 10. In at least some embodiments, the substrate material is (or includes) a synthetic leather or another material that is sufficiently durable to protect a foot in regions where the upper is likely to contact external objects and/or where foot support is needed, but sufficiently flexible to provide comfort.

[58] Many different substrate materials can be used. In some embodiments, substrate materials are selected so as to provide support for the lamination package (i.e., the stack of substrate, mesh and other materials assembled to create an upper) and to adequately bond to the mesh material. To achieve such goals, substrate materials can be chosen so as to have limited stretch, to bond well and be chemically compatible with TPU hot melt, to have a continuous (i.e., non-mesh) surface so as to provide more bonding surface area, and to be cuttable with clean edges in mass production. Table 1 lists examples of substrate materials that can be used in at least some embodiments; other materials could also be used.

Table 1

<u>Material Type/Description</u>	<u>Example Commercially-Available Product</u>
EPM synthetic suede 0.5 - 1.0 mm thick	CLARINO TIRRENINA NUBUCK (Kuraray America, Inc., New York, NY)
regular density synthetic leather	SOFT-R 1.1 mm (Nan Ya Plastics Corporation, Taiwan)
microfiber synthetic leather	THUNDER II, 1.4 mm (Nan Ya Plastics Corporation, Taiwan)
EPM synthetic leather with 50% rePET in high density substrate	KANGA ENV 1.3 mm or 1.5 mm (Nan Ya Plastics Corporation, Taiwan)
buffed high density synthetic leather	KITE BUFF 0.9 mm (Daewoo International Corporation, Pusan, Korea)
poly/nylon nonwoven	EVO80 WS (Freudenberg & Co., Weinheim, Germany)
perfed microfiber polyester textile	LJ-M11K (Gold Long John International Co, Taiwan)
polyester textile package	POLYPAG PLUS MULTI (You Young Co., Ltd. , Korea)
polyester textile package	JEKYLL PLUS MULTI (You Young Co., Ltd., Korea)
TPU coated synthetic leather	A806/A807 (Chaei Hsin Enterprise Co., Ltd., Taiwan)

[59] The mesh material of layer 28 reinforces upper 11 by augmenting the strength of the substrate material where the two materials are bonded, thereby allowing use of thinner substrate material elements. Incorporation of mesh material into an upper further allows elimination of substrate material in areas where the full protection and support of the substrate material is not as important, thus permitting further reduction in substrate material and overall shoe weight. The mesh material of layer 28 also allows air to flow through openings in substrate layer 27 to help cool and dry the foot of a wearer.

[60] In at least some embodiments, the mesh material of layer 28 is a single layer warped knit with an open structure (or other type of woven material) and is formed from nylon, polyester, nylon/polyester blends, recycled polyethylene terephthalate (rePET), or other material. In certain embodiments, the mesh material has more than 50% open area (e.g., more than 50% of the material surface area comprises open space through which air can freely flow from one side to the other). In some embodiments, SPANDEX (or other

stretchable meshes) and spacer meshes (meshes with filler yarn) are undesirable. Table 2 lists examples of the mesh material in at least some embodiments; other materials could also be used.

Table 2

<u>Material Type/Description</u>	<u>Example Commercially-Available Product</u>
100% PET	E-minicell mesh 420D single mesh (Daewoo International Corporation, Pusan, Korea)
mesh	BULLHEAD mesh (Formosa Ting Sho Co., Ltd., Taiwan)
35% rePET mesh	TENOR mesh (Joonang Textile Co., Ltd., Korea)
38.6% rePET mesh	AIR TING mesh (Mogae Textile Co., Ltd., Busan, Korea)
34% nylon 200D/84F, 66% polyester 300D/168F	TLE8B001 DUONET (Tiong Liong Industrial Co., Ltd., Taiwan)
32% polyester 100D/36F, 68% polyester 300D/168F	TLD9B018 BLOCKBUSTER (Tiong Liong Industrial Co., Ltd., Taiwan)
50% rePET mesh	MATRIX mesh (You Young Co., Ltd., Korea)
30% rePET mesh	MONO RIB mesh (Dong Jin International Corporation, DaeGu, Korea)
30% rePET mesh	thermoplastic mesh 6 (Duck San Co., Korea)
30% rePET mesh	Egg mesh (You Young Co., Ltd., Korea)
Love Look	Formosa Ting Sho Co., Ltd., Taiwan

[61] The skin material for panels 36a-36d reinforces the mesh and substrate materials, protects the mesh material layer in certain areas (e.g., provides abrasion resistance), and/or provides a decorative surface on upper 11. In at least some embodiments, the skin material is a thermoplastic polyurethane (TPU) or other appropriate material. In certain embodiments, the skin material is a multilayer material having an outer heat-resistant layer for abrasion resistance and an inner layer for hot melt bonding. For example, the outer layer can be thermoset polyurethane (PU) or a TPU with a high melt temperature, and the inner layer can be a TPU having a lower melt temperature suitable for hot melt bonding and production temperatures. Table 3 lists examples of materials that can be used for the skin material in at least some embodiments; other materials could also be used.

Table 3

<u>Material Type/Description</u>	<u>Example Commercially-Available Product</u>
0.4 mm thermoset polyurethane (PU) film	UT900 (San Fang Chemical Industry Co., Ltd., Taiwan)
TPU film	FW film (Daewon Chemical Company, Ltd., Korea)
Dual (H/L) TPU film having 0.1 mm high melting temp. aliphatic film layer and 0.2 mm low melting temp. aromatic polyester film FS8080 layer	FD26K series (Ding Zing Chemical Products Co., Ltd., Taiwan)
0.3 mm film having 0.1 mm PU layer and 0.2 mm TPU hot melt layer	SKN300 (Teijin, Okahata, Japan)
0.35 mm PU coated hot melt film	HH Million AB (Daewoo International, Busan, Korea)

[62] In at least some embodiments, and as shown schematically in FIG. 2, various layers of material are bonded by interposing a separate layer of hot melt bonding material between those materials and then activating that bonding material in a heated press. In at least some embodiments, the hot melt bonding material generally has a pre-activation consistency of a fine fibrous mat that is similar in thickness (and appearance) to a fine spider web. This allows the activated bonding material to fully cover contacting surfaces without excess buildup of hardened bonding material. In some embodiments, hot melt bonding material mats can be laid onto sheets of mesh and skin material, with the sheets then rolled and provided to a shoe manufacturer. The manufacturer can then unroll the mesh and bonding material combination (or the skin and bonding material combination) and cut appropriate shapes for an upper in a single die-cutting operation.

[63] In at least some embodiments, a TPU hot melt bonding material could have a melt temperature between 80°C and approximately 120°C and be polyester-based. Table 4 lists examples of hot melt bonding materials that can be used in at least some embodiments; other hot melt bonding materials could also be used.

Table 4

<u>Material Type/Description</u>	<u>Example Commercially-Available Product</u>
----------------------------------	---

hot melt film	F1500 (Duck San Co. Ltd, Seoul, Korea)
polyurethane/polyester base hot melt film	FS8080 (Ding Zing Chemical Products Co., Ltd., Taiwan)
hot melt film	FS4252X3 (Ding Zing Chemical Products Co., Ltd., Taiwan)
hot melt film	NASA 600 (Sambu, Korea)
hot melt film	Meltlace Web 100E (Dongsung Adhesives division Henkel AG & Co. KGaA)
polyether film (.05 mm to 2 mm thickness)	FT1029 (Ding Zing Chemical Products Co., Ltd., Taiwan)

The final material in Table 4 (polyether film) may be desirable, e.g., in certain embodiments in which high humidity is a concern.

Fabrication of an Upper Shell Having a Mesh Composite Portion

[64] According to at least some embodiments, a bonded mesh composite panel of an upper is created by assembling individual panels of material for the various layers in a flat configuration. If the upper is to include additional portions (e.g., a rear portion such as panel 17 of shoe 10), additional material elements can be included as part of the assembly process. The panels and other elements are assembled so as to have an arrangement in which the relative locations of the panels and elements correspond to the locations those panels and elements will have in the completed shoe. After assembling the individual panels and/or other elements into the proper arrangement and tacking the assembly at several locations, the assembly undergoes a series of pressing operations to bond the assembled elements. These operations create a flat, one-piece unibody upper shell that can contain many or all elements to be included in the finished upper. Edges of the unibody upper shell can then be joined to create a three-dimensional upper body ready for further finishing and attachment to a midsole.

[65] FIGS. 4A1 through 4K show a process, according to at least some embodiments, for fabricating the mesh composite panel 16 for shoe 10 of FIGS. 1A and 1B. In step 1 shown in FIGS. 4A1 and 4A2, foxing panel 17 is attached to an assembly jig 100. FIG. 4A2 is a side view of jig 100 and foxing panel 17, from the position noted in FIG. 4A1, that is included to further show the use of jig 100. Each of pins 101a-101q in jig 100 extends upward and is

used to position one or more upper elements. For example, and as shown for panel 17, pins 101a, 101b and 101e correspond to holes 102a, 102b and 102e in foxing panel 17. Panel 17 is positioned on jig 100 by respectively placing holes 102a, 102b and 102e over pins 101a, 101b and 101e and pushing panel 17 onto jig 100. The side of foxing panel 17 facing upward at the completion of step 1 will face outward and away from the interior of a completed shoe 10. Hole 102a of panel 17 is in a small extension tab 99 that extends away from an edge 98 of panel 17. Extension tab 99 (and similar extension tabs on other elements) will be trimmed away during a later stage of fabrication.

[66] Other elements of upper 11 are positioned on jig 100 in a similar manner. In step 2 (FIG. 4B), for example, a panel 53 of hot melt bonding material is placed adjacent an edge 54 of foxing panel 17. Bonding material panel 53 will be used to bond foxing panel 17 to a panel of substrate material that will become substrate layer 27 of mesh composite panel 16. In other embodiments, foxing panel 17 can be attached in a different manner (e.g., by relying on the melting of a laminated layer of foxing panel 17, by using a brushed-on liquid adhesive) and/or at a different stage of constructing an upper shell.

[67] In step 3 (FIG. 4C), a panel of material for substrate layer 27 is attached to assembly jig 100 by pushing holes 104b through 104q in the substrate material panel over pins 101b through 101q, respectively. Holes 104b-104d, 104f and 104p are contained in extension tabs that will be trimmed away in a subsequent fabrication step. As seen in FIG. 4C, the panel of layer 27 includes opening 34 that will ultimately be located in the top forefoot region of upper 11 (see FIGS. 1A and 1B). Also seen in FIG. 4C are openings 31 and 32 that will ultimately be located laterally on upper 11 (FIG. 1A) and opening 33 that will ultimately be located medially on upper 11 (FIG. 1B). In some embodiments, holes 31, 32, 33 and 34 are cut when the substrate layer panel is die-cut from a larger piece of material. Tongue opening 26 (FIGS. 1A and 1B) will be cut after assembly and pressing. In other embodiments, tongue opening 26 can also be cut from the substrate material panel when that panel is die cut. The side of the layer 27 panel that is exposed at the completion of step 3 will face outward and away from the interior of a completed shoe 10.

[68] In step 4 (FIG. 4D), eye stay reinforcement 56 is attached to jig 100 by pushing holes 108g, 108h, 108i and 108o over pins 101g, 101h, 101i and 101o, respectively. Eye stay reinforcement 57 is similarly attached by pushing holes 109j, 109k and 109l over holes 101j,

101k and 101l, respectively. In at least some embodiments, reinforcements 56 and 57 are added to provide reinforced locations for shoe lace eyelets. In other embodiments, eye stay reinforcements may be omitted or may have different configurations. Panels of unactivated hot melt bonding material can also be interposed between reinforcements 56 and 57 and substrate layer 27.

[69] Other types of reinforcements can be placed in other areas of a shoe upper in a manner similar to that used for eye stay reinforcements 56 and 57. In some embodiments, for example, additional reinforcement could be placed over the area of the substrate layer panel that will be located in the toe region of a completed upper. In another embodiment, reinforcement materials could be placed over the portions of the substrate layer panel that will be located at the lateral and medial sides of a completed shoe, with those reinforcement materials forming reinforcing strap attachment points in a finished upper.

[70] In step 5 (FIG. 4E), a panel of mesh material to form layer 28 is attached to jig 100 by pushing holes 119b, 119c, 119d, 119e, 119p and 119q over pins 101b, 101c, 101d, 101e, 101p and 101q, respectively. Holes 119b-119d and 119p are contained in extension tabs that will be trimmed away in a subsequent fabrication step. The side of the layer 28 mesh material panel that is exposed at the completion of step 5 will face outward and away from the interior of a completed shoe 10. A layer of unactivated hot melt bonding material is included between the mesh layer 28 panel and the substrate layer 27 panel. In some embodiments, a roll of the mesh material used for the panel of layer 28 is received from a vendor with a layer of hot melt bonding material pre-applied to one side. In such embodiments, the mesh material panel for layer 28 is placed onto jig 100 with the bonding material side facing down (i.e., toward substrate layer 27). In other embodiments, a separate layer of hot melt bonding material having the same shape as the layer 28 mesh material panel is placed over substrate layer 27 at the conclusion of step 1, and only a plain mesh material panel is added in step 5. In still other embodiments, a separate panel of hot melt bonding material between panels 27 and 28 is obviated through use of a substrate material having a prelaminated layer formed from a meltable material such as TPU.

[71] As seen in FIG. 4E, the mesh layer 28 panel does not completely cover the substrate layer 27 panel. For example, a region 110 of the substrate material panel (corresponding to the toe and lateral side forefoot regions of an upper in a completed shoe 10) is not overlapped

by the mesh material panel. In this manner, a smooth surface of upper 11 can be provided for subsequent bonding to a toe cap or other external feature. A region 111 of the substrate layer 27 panel is similarly not covered by mesh material so as to provide a smoother interface between the substrate layer and reinforcements 56 and 57. Unlike material used for skin layers, reinforcements 56 and 57 are formed from a thicker material (e.g., nylon) that will not conform as readily to mesh layer 28 at the temperatures used in the pressing process. Although region 112 of substrate layer 27 corresponds to a region that will subsequently be covered by skin material panel 36d in such a manner so as not reveal an underlying mesh material layer, mesh layer 28 covers region 112 so that the added strength of the mesh material can be present in the portion of upper 11 to which region 112 will correspond in a completed shoe 10.

[72] In step 6 (FIG. 4F), skin material panel 36c is attached to jig 100 by pushing holes 114c, 114d, 114f, 114j and 114p over pins 101c, 101d, 101f, 101j and 101p, respectively. Holes 114c, 114d, 114f and 114p are contained in extension tabs that will be trimmed away in a subsequent fabrication step. Panel 36c will form the skin material covering, e.g., the toe, medial forefoot and lateral forefoot regions on a completed shoe 10 (see FIGS. 1A and 1B). The side of panel 36c that is exposed at the completion of step 6 will face outward and away from the interior of a completed shoe 10. In some embodiments, a roll of the material used for panel 36c and/or other skin material panels is also received from a vendor with a layer of unactivated hot melt bonding material pre-applied to one side. In other embodiments, a separate layer of hot melt bonding material having the same shape as skin material panel 36c is placed between skin material panel 36c and previously positioned layers as part of step 6. In still other embodiments, one or more skin material panels are bonded to other layers by melting of the skin material during a hot pressing operation (described below) and subsequent solidification during cooling, and no separate bonding material is interposed between those skin material panels and other inwardly-located layers. As also seen by comparing FIGS. 4E and 4F, skin material panel 36c is assembled so as to be located over substrate layer 27 in region 110 where mesh material is not present.

[73] In some embodiments, extra and/or higher strength bonding material and/or additional adhesives may be included in portions of a composite panel that will correspond to a toe region and/or to other forward regions of an upper of a completed shoe. This additional

bonding may be desirable in embodiments where toe portions of an upper may experience significant stresses during various manufacturing operations (e.g., toe forming, lasting).

[74] In step 7 (FIG. 4G), skin material panel 36b is attached to jig 100 by pushing holes 113g, 113h, 113i, 113j, 113k, 113l, 113n and 113o over pins 101g, 101h, 101i, 101j, 101k, 101l, 101n and 101o, respectively. The outer edges of panel 36b will face away from the interior of a completed shoe 10, and the remainder of panel 36b (together with portions of the underlying substrate material panel and mesh material panel) will be removed to create tongue opening 26. As with panel 36c in step 6, panel 36b is placed onto jig 100 with the outer side facing up, and a layer of hot melt bonding material is interposed between panel 36b and underlying elements.

[75] Panel 36a of skin layer material is placed onto jig 100 in step 8 (FIG. 4H) by pushing holes 115a, 115b, 115e, 115m, 115n and 115o over pins 101a, 101b, 101e, 101m, 101n and 101o, respectively. Holes 115a, 115b and 115n are contained in extension tabs that will be trimmed away in a subsequent fabrication step. Panel 36a will form the skin material layer covering portions of the lateral midfoot and hindfoot regions on a completed shoe 10. As with panel 36c in step 6, a layer of hot melt bonding material can be interposed between panel 36a and underlying elements. The result at the conclusion of step 8 is a panel assembly 116 of upper elements that will ultimately become an upper shell that includes mesh composite panel 16 bonded to foxing panel 17.

[76] In step 9 (FIG. 4I), elements of assembly 116 are tacked together by partially activating the hot melt bonding material layers in isolated locations. This partial activation can be performed in some embodiments using high frequency (HF) welding. For purposes of illustration, the resultant tacking is shown schematically in FIG. 4I as a series of dots distributed over the surface of the assembled elements that will form mesh composite panel 16. In practice, the actual locations at which heat is applied for tacking purposes may vary. Tack welding in step 9 can be performed using a handheld heat gun, or by briefly inserting jig 100 with assembly 116 into a press having a plate configured to accommodate pins 101a through 101q. In at least some such embodiments, the press conditions for the tacking step will depend on the particular hot melt selected, but will typically be between about 115°C and about 125°C, with pressing for approximately 30 to 35 seconds at approximately 2 to 6 kg/cm² of surface pressure.

[77] The tacking of step 9 results in a partial bonding so that the individual elements of assembly 116 will remain in an assembled condition when assembly 116 is removed from jig 100. In step 10 (FIG. 4J), tacked assembly 116 is heat pressed so as to fully bond the individual elements together. In particular, tacked assembly 116 is removed from jig 100 and placed onto heat-transferring silicone pad 120. Assembly 116 is turned upside down so that the side facing upward at the conclusion of steps 8 and 9 is positioned to face downward toward pad 120. After a sheet of release paper 121 is placed over assembly 116, heated platens 122 and 123 are brought together and pressure applied to compress assembly 116. For simplicity, only the outer edges of release paper 121 are shown in FIG. 4J. In other embodiments, panel assembly 116 may be placed so that the inner side is facing lower platen 122, with release paper 121 inserted between the inner side of assembly 116 and platen 122, and with pad 120 between the outer side of assembly 116 and upper platen 123.

[78] In at least some embodiments, silicone pad 120 is first preheated to 110°C prior to the pressing operation of step 10. Typical process parameters for the hot pressing operation of step 10 are upper and lower press platen temperatures of 120°C, press pressure of approximately 20 kg/cm², and press time of 30 to 40 seconds. However, the process parameters for a particular shoe upper will depend on the combination of materials and on the panel arrangement applicable to that upper. In some embodiments, the press time for step 10 can be determined by assembling panels for a particular upper design into a test panel assembly, with thermocouple temperature probes inserted at one or more locations within the test panel assembly. The test panel assembly is then pressed between 120°C press platens until the temperature probes indicate that the internal assembly temperature has reached a desired melting point for the skin materials in the test panel assembly. If desired, the press time can be adjusted upward or downward by adjusting the press platen temperature. The desired melting point temperature for a particular skin material can be determined by using differential scanning calorimetry (50°C/min. scan rate) to find the temperature associated with the maximum heat transfer for that skin material. Press pressure can be adjusted upward if there is insufficient bonding between layers in one or more test panel assemblies or adjusted downward if there is excessive (and undesired) “flattening” of surface features.

[79] After the heated pressing of step 10, assembly 116 is “cold” pressed between room temperature press platens to continue to the bonding process and to enable melted TPU to set while under pressure so as to improve bonding. As used herein, “room temperature” is a

temperature between approximately 20°C and approximately 30°C. By cold pressing assembly 116 immediately after the heated pressing of step 10, individual elements are held in contact while the hot melt bonding material and skin layers solidify, thereby preventing materials rebounding from one another after the initial heated pressing. Without a subsequent cold pressing, for example, a skin layer element in at least some embodiments will not conform to an underlying mesh layer so as to show the mesh pattern on the outer side of the skin layer.

[80] FIG. 4K shows cold pressing in step 11, which immediately follows step 10. After assembly 116 is removed from heated press platens 122 and 123 (FIG. 4J) and release paper 121 is taken off, assembly 116 is placed on silicone pad 129 between cold platens 130 and 131. A different silicone pad can be used in step 11 so as to avoid residual heat remaining in pad 120 at the completion of step 10. The same face of assembly 116 that faced silicone pad 120 in step 10 faces silicone pad 129 in step 11. In at least some embodiments, platen 130 and/or 131 may include internal water lines or another mechanism to maintain the platens at a desired temperature. Assembly 116 is then pressed between platens 130 and 131. Typical process parameters for the cold pressing operation of step 11 are room temperature (e.g., 25°C) upper and lower press platens, press pressure of approximately 30 kg/cm², and press time of approximately 30 seconds.

[81] Heat-conductive silicone pads 120 and 129 used in steps 10 and 11, respectively, are at least partially compressible and conformable to the surface features of panel assembly 116. This permits compression of the panel assembly to bond the various layers without overly flattening the surface features. This also allows formation of a profile, such as is shown in region C of FIG. 3, in which skin material conforms to an underlying layer of mesh material so as to reveal contours of that mesh material. In at least some embodiments, each of silicone pads 120 and 129 has a Shore-A hardness of between 15 to 30 and a thermal conductivity of approximately 0.3 Watts. However, pads with different thermal conductivities can be used by adjusting press platen temperatures to achieve a desired internal temperature in the pressed materials.

[82] At the completion of step 11, tacked assembly 116 has been transformed into a fused unibody shell that includes mesh composite panel 16 and foxing panel 17. FIG. 5A shows fused unibody upper shell 116 that results from the completion of steps 1 through 11 of FIGS.

4A1-4K, and that is ready for finishing operations. Edges 133, 134 and 135 are marked in FIG. 5A and will be further discussed below. In step 12 (FIG. 5B), tongue opening 26 is cut, extension tabs on the outer edges of composite panel 16 are trimmed away, and lacing eyelets are punched. In step 13, (FIG. 5C), skin layer element 36d is applied by hot pressing combined with HF welding, but without a cold pressing step, so that skin layer element 36d will have a different texture than other portions of upper 10. In particular, a tool (not shown) having the shape of element 36d is applied to unibody upper shell 116 on the location where panel 36d is to be placed. HF welding heat is then applied through that tool to flatten the region of the mesh material in layer 28 under the tool. Element 36d is then placed in the flattened region with an interposed layer of hot melt bonding material and HF welded in place using a heating element (e.g., formed from copper, brass, aluminum or other conductive material) in the shape of the desired melt pattern at a temperature, pressure and time appropriate for the materials in use. In some embodiments, element 36d may be in the shape of a logo or other indicia that is associated with a manufacturer of the shoe, and a different texture for element 36d may be desired to offset the logo from other portions of the shoe upper or for some other aesthetic purpose. In embodiments where a different texture for element 36d is not desired, skin layer element 36d can be added in a step inserted somewhere between steps 5 and 9 in the process flow of FIGS. 4A-4K, and then heat- and cold-pressed with other elements when forming upper unibody shell 116.

[83] In step 14 (FIG. 5D), a foam element 140 with attached collar element 141 is placed onto a second jig 151 by inserting holes 152a through 152i over corresponding pins 153a through 153i on jig 151. Collar element 141 forms a lip that overhangs an upper edge of foam element 140. In some embodiments, collar element 141 can be formed from a folded-over section of material having an inverted “U” cross-section, with one leg of that “U” attached to the inside upper edge of foam element 140 and the other leg overhanging foam element 140 on the outside of that upper edge. Materials for foam element 140 can include open cell PU foam, and materials for collar element 141 can include synthetic suede. In step 15 (FIG. 5E), edge 134 of unibody upper shell 116 (see FIG. 5A) is inserted under the lip of collar element 141. In step 16 (FIG. 5F), a copper HF welding tool (not shown) having a shape corresponding to collar element 141 (or to a portion of collar element 141) is pressed onto collar element 141 and heat applied (at a temperature, pressure and time appropriate for

the materials in use), thereby bonding shell 116, foam element 140 and collar element 141 along the HF weld 153.

[84] In step 17 (FIG. 5G), regions of unibody upper shell 116 adjacent edges 133 and 135 (see FIG. 5A) are joined to transform shell 116 into a three-dimensional upper shape. Prior to step 17, extension tabs on collar 141 and excess portions of foam element 140 are trimmed. As part of step 17, the portion of panel 16 that includes edge 135 is placed into a jig 160 having rails 161 and 162 that conform to the shape of panel 16 along edges adjacent to edge 135 and that hold shell 116 in place. The remainder of shell 116 (with attached foam element 140 and collar 141) is then wrapped under and around the reverse side of jig 160 so as to place edge 133 over edge 135. An HF welding tool (e.g., formed from copper or other conductive material) having a shape corresponding to the overlapped portions adjacent edges 133 and 135 is pressed onto folded-over panel 17 and heat applied (at a temperature, pressure and time appropriate for the materials in use), thereby bonding regions of shell 116 adjacent edges 133 and 135 along the HF weld 163.

[85] After completion of step 17, the three-dimensional shell 116 (with attached collar 141 and foam element 140) may undergo additional finishing prior to bonding to midsole 42 (FIGS. 1A and 1B). In some embodiments, the toe portion of mesh composite panel 16 is heated and applied to a shaping form so as to obtain a desired toe region shape. In some embodiments, the toe portion of the three-dimensional shell is heated to approximately 80°C for approximately 20 seconds. The heated toe portion is then pressed onto a shaping die to obtain the proper toe shape, with vamp gathering then performed during a cooling step at approximately -4°C for approximately 30 seconds. A plastic counter may be inserted between foxing panel 17 and foam 140 in the heel region and stitched or otherwise fastened in place. The tongue and/or a bootie or other type of liner is attached, and upper 11 is completed by stitching a strobel in place around the lower edges of the upper panel while the upper is on a last.

[86] Operations similar to those described above can be used to create a tongue for attachment to shell 116. In particular, a tongue can also be formed by positioning one or more layers on jig, tacking those layers together, and then hot and cold pressing those layers to form a mesh composite panel in the shape of a tongue. The mesh composite of the tongue can have similar materials as are described above (e.g., a substrate, mesh and skin layers) or

other combinations of materials. For example, a tongue composite panel can be formed to include a curved composite panel shaped to conform to the top of a wearer's foot and/or to include a padded element that is molded into a desired shape on the outer (or inner) side of the tongue composite. Elements for such a tongue composite could include, for example, a textile layer and a moldable foam padding layer. Instead of using a set of flat press platens such as is shown in FIGS. 4J and 4K, a pair of curved platens can be used to achieve the desired curvature for the tongue. One of those curved platens could further include a mold cavity that is used to form the padded element into the desired shape.

[87] FIG. 4L shows an example of molding a tongue composite member in accordance with at least some examples of this invention as described above. A bottom curved platen 170 may be provided, e.g., with pins and other features of the types described above, and a substrate layer 172 (e.g., of the types described above for substrate layer 27) can be engaged with the bottom curved platen 170 via pins. The substrate layer 172 may have one or more openings (as shown in Fig. 4L), or it may be a complete layer. If desired, one or more intermediate layers 174 may be layered over the substrate layer 172, e.g., made of a soft material, such as one or more layers of a spacer mesh, a foam material, a quilted or pillowed material, textile, fabric, etc. (e.g., a material that could feel comfortable to the wearer's foot through the opening in the substrate layer 172, in this example). Finally, an outer skin layer 176 (e.g., of the skin layer types described above) may be provided on top of the intermediate layer(s) 174. Optionally, this outer skin layer 176 also could have one or more openings.

[88] Hot melt materials may be provided as separate layers and/or provided as part of the outer skin layer 176, the intermediate layer(s) 174, and/or the substrate layer 172, e.g., in the manners described above. Because each of these layers 172, 174, and 176 may be flexible and pliable (e.g., made of fabrics, textiles, thin substrates, etc.), they can conform to the curved shape of the platens 170 and/or 178. At least one of the layers 172, 174, and/or 176 may be made from a shape retaining material so that the overall composite tongue will maintain a curved shape after the pressing step(s). The overall width(s) of the various layers (in the W direction in Fig. 4L) may increase in the bottom-to-top direction such that substrate layer 172 is somewhat narrower than skin layer 176 in the width W direction (the intermediate layer(s) 174, if any, may have an intermediate thickness between the upper and lower skin layers). In this manner, when the composite tongue member is formed by pressing the tongue assembly between curved platens 170 and 178 (e.g., in the various manners and/or

under the various conditions described above), the top, intermediate, and bottom panels will shape smoothly in a curved manner in the W direction without excessive bunching or pillowing of the lower layers and/or without excessive stress and strain on the outer layers.

[89] If desired, the hot melt material need not bond with intermediate layer(s) 174. Rather, if desired, the intermediate layer(s) 174 may be simply held in place by the bonding of the substrate layer 172 and the skin layer 176. Optionally, if desired, along the edges of the composite tongue assembly, hot melt material may pass through the material of the intermediate layer(s) 174 to reach the opposite side and bond on the opposite side (e.g., to bond the substrate layer 172 to the skin layer 176 and pin the intermediate layer(s) 174 in between). Alternatively, the hot melt material also may bond to the intermediate layer(s) 174.

[90] The composite tongue member may be incorporated into an upper structure in any desired manner and/or at any desired time in the overall construction process without departing from this invention. For example, the composite tongue member may be separately formed and engaged with the upper in any desired manner, such as by stitching, adhesives, hot melt fusion (using heat and pressure), HF welding, mechanical connectors, etc., including in manners conventionally known and used in the art. As other examples, if desired, some or all portions of the composite tongue member can be integrally formed with one of the layers of the remainder of the upper or engaged with one of the layers of the remainder of the upper, e.g., during the processes described above in conjunction with Figs. 4A1 through 4K. Other ways of engaging the tongue member with the upper also may be used without departing from this invention.

Additional Embodiments

[91] Shoe 10 and the fabrication operations described above are merely examples of shoes and fabrication processes according to various embodiments. As indicated above, the shape and arrangement of a substrate layer, mesh layer and/or skin layer can vary in different embodiments, as can the number, size and arrangement of ventilation openings in a substrate. Moreover, different types of substrate materials, mesh materials and/or skin materials could be employed for different shoe types. For example, a running shoe may utilize a mesh material that is lighter and/or has a different weave pattern than a mesh material used for a

basketball shoe. Indeed, a single shoe could include more than one type substrate material and/or more than one type of mesh material and/or more than one type of skin material. In some embodiments, a skin layer might be omitted.

[92] Certain embodiments may incorporate more than one type of mesh material in a single upper in various ways. For example, an upper according to some such embodiments may have a first type of mesh material in one portion of the upper and a second type of mesh material in a different portion. The first type of mesh may be of lighter weight and have larger openings so as to increase ventilation, and may be placed in locations that will correspond to portions of an upper that will be subject to less severe forces. The second type of mesh material may have a denser weave and/or be formed from a higher strength material, and may be placed in locations that will correspond to portions of an upper that will be subject to more severe forces. More than two types of mesh material can be used in an upper, and different mesh material types can be combined for other reasons (e.g., to achieve a desired aesthetic, to reduce unit cost, etc.).

[93] Some embodiments can include uppers in which there may be multiple mesh layers. In some cases, one mesh material panel may overlap another mesh material panel in an area where extra reinforcement is desired. In still other cases, separate mesh material panels may not overlap one another, and may be located at different layers of an upper. For example, a first panel of mesh material could be overlaid on a substrate material layer, a second panel of substrate material (or other type of material) overlaid onto a portion of the first panel, and a third panel of mesh material overlaid so as to overlap a portion of the second panel. In some embodiments, mesh material panels may be located at the same layer but not overlap one another.

[94] Additional types of materials can be added to an upper shell in additional embodiments. Such additional materials can be included so as to form an outrigger, a shank, a heel cup, a toe cap, etc. For example, a panel of rigid nylon or other polymer could be included in the toe region of a composite panel and shaped as part of the toe shaping process described above. As another example, a counter panel formed from nylon or other type(s) of polymer could be included, during the process of assembling upper panels on an assembly jig, in a location that corresponds to the sides and rear of a wearer's heel in a completed shoe.

Those counter panels can then be hot melt bonded to the inner side of panel 17 during the pressing operations.

[95] FIGS. 6A and 6B show examples of composite upper panel portions, according to some additional embodiments, that include an additional layer for reinforcement, support and/or padding, dimensional stability, etc.. In FIG. 6A, a layer 201 of additional material is interposed between a layer 28' of mesh material and a layer 36' of skin material. The material of layer 201 is bonded to the skin material of layer 36' and to the layer of mesh material 28' with interposed layers of hot melt bonding material (not shown). In FIG. 6B, a layer 202 of additional material is located on an inner side of a substrate layer 27'' and bonded to that substrate layer with an interposed layer of hot melt bonding material (not shown). Material in layer 201 or in layer 202 could be the same material used in a substrate layer, could be a foam padding material, could be a plastic material that is rigid or semi-rigid, could be a rubber-like material, or could be a different type of material. Also shown in FIG. 6B are a mesh material layer 28'' and a skin material layer 36''. Examples of other materials that could be used for layer 201 or 202 to provide reinforcement and/or support include (but are not limited to) materials previously described herein and combinations thereof. Other materials that permit sufficient inter-layer bonding, have limited stretch and have appropriate heat-setting properties can also be used. Multiple layers of additional materials such as are shown for layers 201 and 202 and/or combinations of materials (e.g., a foam panel and a rubber panel) could be employed. A composite panel having a construction such as indicated in FIGS. 6A and 6B, as well as other types of composite panels having added reinforcement/support materials, can be fabricated using assembly, tacking and hot/cold pressing operations similar to those described herein.

[96] In some embodiments, an upper shell formed according to the above described steps can include extensions in one or more panels (e.g., panel 17 of FIGS. 4A1 et seq.) near regions that will correspond to the heel of a wearer. After completion of step 17 (FIG. 5G), the extensions can then be wrapped around the bottom of the heel region to form a double-lasted heel cup.

[97] In certain embodiments, additional panels and/or panels having extensions can be included in a panel assembly so as to form a carrier layer for foam inserts. For example, such extensions can be included in regions of substrate material panels, foxing panels or other

panels that can be wrapped under the bottom of a three-dimensional upper (after step 17 of FIG. 5G) so as to form a shelf for inclusion of foam padding that will cushion the bottom of a wearer's foot. Various types of foam materials can be used in these and other embodiments, including but not limited to foam materials as described in commonly-owned U.S. Patent No. 7,941,938 and incorporated by reference herein. One example of a shoe comprising a double-lasting upper that forms a shelf for foam padding is described below in connection with FIGS. 10A through 16.

[98] In some embodiments, and as shown in FIG. 7, a sole can include a toe cap extension 203. As indicated above, mesh material 28 can be omitted from the composite portion of a panel that corresponds to the region over which toe cap 203 will be located, thereby providing a smooth surface onto which toe cap 203 could be bonded. Alternatively (or additionally), a reinforcing stitch 204 can be included to secure toe cap 203 in place. In still other embodiments, a toe cap can be formed by adding an additional layer of substrate material, a relatively thick layer of abrasion resistant plastic (e.g., polyurethane), or other material in the region that will correspond to the toe of the finished upper. In some such embodiments, mesh material is omitted in the toe region similar to the embodiment described in connection with FIGS. 4A1 through 5G, while in other embodiments the mesh material may extend over the entire toe region. In a similar manner, an additional layer of substrate material, a relatively thick layer of abrasion resistant plastic (e.g., polyurethane), a shock absorbing material (e.g., Phylon (compressed ethylene vinyl acetate foam)) or other material can be included in regions of an upper that will correspond to the lower heel and/or edges of a wearer foot in a finished shoe.

[99] In at least some embodiments mesh material can also be omitted from portions of a composite panel that correspond to the regions where the upper will join a midsole. In this manner, a smoother transition from upper to midsole or other tooling can be achieved. Alternatively, a layer of foam or other moderator can be interposed between the lower edge of an upper and a midsole.

[100] In some embodiments, a substrate material panel can be pre-processed so as to create an indentation in the form of a product name, a logo, or other shape. A skin layer material panel is then placed over the substrate material panel so as to completely cover the indentation and can be melted during the hot pressing operation so as to flow into and

completely cover the indentation. The indentation can be created during a pre-processing operation using an HF welding tool having the desired shape, using laser cutting, or by other desired method. In certain embodiments, the skin layer panel used to cover the indentation may be thinner than skin layer panels used in other portions of an upper so as to create crisper and more defined edges of the covered indentation. Indentations can similarly be added to substrate material panels for other purposes. For example, indentations can be created to locate and/or accommodate harder materials used for reinforcement and protection in certain regions (e.g., for eye stay reinforcement, for heel counters, etc.). As another example, indentations can be created to locate and/or accommodate padding layers.

[101] In certain embodiments, and as shown in FIG. 8, a layer of skin material is used to reinforce the transition from the mesh composite portion of a shell to another portion. FIG. 8 is a cross-section taken from the location shown in FIG. 1A. As seen in FIG. 8, the skin material of panel 36a extends over foxing panel 17.

[102] In some embodiments, malleolus padding can be included in the region of the upper that will correspond to the portion of the wearer foot near the ankle. In some such embodiments, indentations are formed in the portions of foxing panel 17 (see FIGS. 4A1 et seq.) that will correspond to the regions around the wearer ankles. These indentations can be formed, after step 11 of FIG. 4K, using an HF welding element in the shape of the desired padding. That element is applied to the inner side of panel 17, in the area that will correspond to the desired padding location, so as to create a pocket to contain the padding. Application of the HF element will also deform the outer side of foxing panel 17 in the shape of the padding element, thereby allowing the padding presence to be visible in the finished upper. After creation of the padding pocket, the padding elements can be glued in place in the pockets, and an inner lining element of artificial suede applied over the inner side of the foxing panel to cover the padding elements. In some such embodiments, the padding element 140 (and steps 14-16 of FIGS. 5D through 5F) may be omitted.

[103] Various modifications can also be made to the above-described fabrication process in other embodiments. For example, different types of jigs or jig configurations can be used. In some embodiments, a jig with retractable pins can be employed to eliminate the need for a tacking operation (such as step 9 described above in connection with FIG. 4I). In some such embodiments, a heat-conductive jig with retractable pins is used to assemble elements of a

shell and then placed face up onto a press having a heat-conductive silicone pad on an upper platen. Techniques other than pins can also be used to hold shell elements during assembly (e.g., a vacuum table, a static charge system, etc.).

[104] In some embodiments, a dual pan assembly jig can be employed so as to avoid a tacking step. FIGS. 9A through 9C show use of a dual pan jig 450 according to some such embodiments. Jig 450 includes a lower pan 452 and an upper pan 453. Upper pan 453 includes a planar work surface 455 surrounded by a raised rim 456. Surface 455 includes a collection of through-holes, which holes are not visible in FIG. 9A, but which have locations corresponding to pins 454. Surface 455 may also have a non-stick coating. Pins 454, which are used to locate material panels of a panel assembly 316, are affixed to lower pan 452 and protrude through the holes in surface 455. So as to avoid confusing the drawings, all of pins 454 are not labeled. Lower pan 452 can be clipped or otherwise affixed to a planar work stand 451, with work stand 451 bolted or otherwise attached to a bench or other work location. For simplicity, panel assembly 316 is only shown generally in FIG. 9A. However, assembly 316 could be identical to assembly 116 described above (with pins 454 having relative locations identical to those of pins 101a-101q described above). The details of a panel assembly and pin layout will depend on a specific shoe design. In some embodiments, after a panel assembly layout pattern is developed for a specific upper, pins 454 are welded, soldered or braised to lower pan 452 in an appropriate pattern, and corresponding holes drilled in upper pan 453.

[105] Material panels of assembly 316 are placed in their proper locations on pins 454 in a manner similar to that described above in connection with FIGS. 4A1 through 4H, with the locations for individual panels identified by different groups of pins 454. If surface 455 does not have a non-stick coating, a layer of release paper can be placed onto surface 455 before placing panels of assembly 316. Instead of tacking the panels together as described in connection with FIG. 4I, a silicone pad 420 is placed over panel assembly 316 (FIG. 9B). Panel 420 is similar to panel 120 described above. Panel 420 has a shape that fits within rim 456 and is sufficiently thick to extend above rim 456.

[106] While pad 420 rests over panel assembly 316, and as shown in FIG. 9C, upper pan 453 is pulled up and away from lower pan 452. Because pins 454 (FIG. 9A) are attached to lower pan 452, those pins remain on pan 452 as upper pan 453 is moved away. The weight

of pad 420 on assembly 316 maintains the positions of the individual panels of assembly 316 on surface 455 of pan 453, and thus a tacking operation can be omitted. Upper pan 453 (with assembly 316 and pad 420) can then be placed between heated press platens and hot pressing performed. In some embodiments, hot pressing time and/or press platen temperatures can be increased to account for heat absorption by pan 453. Pad 420 can be preheated prior to placement on upper pan 453. After hot pressing of assembly 316 in pan 453, assembly 316 can be removed from pan 453 and cold pressing performed, as described in connection with FIG. 4K, with a separate room temperature pad similar to pad 129 described above.

[107] In some embodiments, an assembly process using jig 450 can be modified so that some or all of the assembled panels are slightly tacky. This tackiness could prevent panels from slipping if pad 420 is moved after placement onto pan 453, but would allow removal and repositioning of panels during the assembly process. Panel tackiness can be achieved, e.g., by including small amounts of uncured bonding material on some panels. In still other embodiments, panel tackiness can be achieved by including heating elements on lower pan 452 that raise the temperature of pan 453 enough begin the melting of hot melt bonding materials in a panel assembly (and to at least partially preheat upper pan 453 before the hot pressing operation).

[108] The order of at least some steps can also be varied in some embodiments. In some embodiments, a tool used in an HF welding process (e.g., step 16 described above in connection with FIG. 5F) can include surface protrusions that emboss a manufacturer's logo or other indicia in the welded region.

[109] As indicated above, some embodiments include upper shells that have extensions used for double-lasting and/or to provide a shelf to support foam padding. FIGS. 10A through 10E show assembly of individual material panels that will be used to create a one-piece, unibody upper shell for such an embodiment.

[110] In FIG. 10A, a first panel 501 of substrate material is positioned on an assembly jig (not shown). For convenience, locating holes (such as holes 104b-104q in FIG. 4C) and locating hole extension tabs are not shown in FIGS. 10A-10E. However, the presence of such holes (and tabs, in some embodiments) is understood. For example, the assembly operations of FIGS. 10A through 10E can be carried out using an assembly jig such as jig 100

and the techniques described in connection with jig 100. Alternatively, the assembly operations of FIGS. 10A through 10E could be carried out using a dual-pan assembly jig such as jig 450 and the techniques described in connection with jig 450. Other jigs and techniques could also be used.

[111] Panel 501 will form the inner layer of the upper shell being fabricated. Panel 501 can be formed, e.g., from a synthetic leather or other material from Table 1. Face 502 of panel 501 is visible in FIG. 10A. Face 502 will be the outer face of panel 501 in a completed shoe (i.e., face 502 will be oriented away from the shoe interior). In some embodiments, panel 501 may include a laminated layer of TPU or other heat-activatable bonding material on face 502. Unlike substrate panel 27 (FIG. 4C) described in connection with a previous embodiment, panel 501 will extend completely around a wearer foot in the completed shoe. For example, and as will be seen more clearly in connection with FIGS. 12-14, the flat unibody upper shell of which panel 501 will form a part does not include a separate foxing panel in the hindfoot region. Instead, panel 501 is a contiguous piece of substrate material. In a completed upper shell (and in the upper of the completed shoe including that shell), panel 501 includes portions located in lateral forefoot, lateral midfoot, top forefoot, medial forefoot, medial midfoot and hindfoot regions of the upper. The toe region of panel 501 includes a cutout 505 that will accommodate a toe cap.

[112] As previously discussed, a wide variety of ventilation openings can be included in upper shells according to various embodiments. For example, instead of relatively large ventilation openings such as holes 31-34 in upper 11 of shoe 10 (see, e.g., FIGS. 1A, 1B and 4C), panel 501 includes a plurality of smaller ventilation holes 503. As another example, other embodiments could include large ventilation openings or a combination of large and small ventilation openings. Similarly, one or more ventilation openings in top forefoot region 504 could be included.

[113] In FIG. 10B, two mesh material panels 520 and 521 are placed onto substrate panel 501 so as to cover the ventilation holes 503 and the areas of panel 501 that surround holes 503. Panels 520 and 521 can, e.g., be cut from one of the materials identified in connection with Table 2 or otherwise identified as a possible mesh material in connection with other embodiments. In some embodiments (e.g., where panel 501 does not include a layer of TPU

or other bonding material on face 502), a separate layer of hot melt bonding material can be interposed between substrate panel 501 and each of mesh material panels 520 and 521.

[114] In FIG. 10C, a first skin material panel 524 is placed over mesh panels 520 and 521 and the region in between panels 520 and 521. Panel 524 also extends over much of the forefoot region of substrate panel 501. Panel 524, e.g., can be cut from a sheet of one of the possible skin materials previously mentioned in connection with other embodiments. In some embodiments, that material may include a first layer formed from a TPU with a lower melting point and a second layer formed from a higher melting point TPU or from PU, with the first layer oriented toward face 502 of panel 501.

[115] In FIG. 10D, reinforcement panels 527 and 528 are put into place. Panels 527 and 528 are in some embodiments cut from the same synthetic leather material used for panel 501. In other embodiments, panels 527 and 528 may be cut from materials that differ from the material of panel 501 (e.g., a different type of synthetic leather). Panels 527 and 528 need not be cut from the same type of material. For example, panel 527 could be cut from a first material and panel 528 could be cut from a second material, with that first material being different from that second material.

[116] In the completed shoe, panel 528 will surround the rear of the wearer foot and includes an extension 506 that will extend over the lateral side of a wearer midfoot. Panel 528 further includes medial extension 507 that will surround an ankle opening on a medial side and a lateral extension 508 that will surround an ankle opening on a lateral side. Extensions 507 and 508 respectively include cutouts 509 and 510 that will ultimately create decorative contours in the exposed surface of a completed upper. Additional cutouts could be included in either or both of extensions 507 and 508 and/or in other portions of panel 528.

[117] Panel 527 will extend over the arch region of a wearer foot in a completed shoe. Panels 529 and 530, which may be formed from nylon or other material, will serve as eye stay reinforcements in the completed shoe. The material(s) from which panels 527 and 528 are cut may include a laminated layer of TPU or other heat-activatable bonding material, which layer may then be oriented inward (e.g., toward face 502 of panel 501). A separate layer of hot-melt bonding material can be placed between skin panel 524 and each of eye stay reinforcement panels 529 and 530.

[118] In FIG. 10E, three additional skin material panels 532-534 have been placed into position. As with panel 524, panels 532-534 can, e.g., be cut from a sheet of one of the possible skin materials previously mentioned in connection with other embodiments. As indicated above, that skin material can include a first layer formed from a TPU with a lower melting point and a second layer formed from a higher melting point TPU or from PU. The first layer of panels 532-533 could then be oriented inward, i.e., facing previously-placed panels. Panels 532-534 need not be cut from the same type of skin material. For example, panel 532 could cut from a first skin material, panel 533 cut from a second skin material, and panel 534 cut from a third skin material, with each of those first, second and third skin materials being different from one another.

[119] The assembly of panels from FIG. 10E is then subjected to hot and cold pressing as described above in connection with previous embodiments. At conclusion of these pressing steps, the panel assembly from FIG. 10E is converted into a bonded composite panel 540 as shown in FIG. 11. As in previously-described embodiments, these pressing operations cause skin panels 532-534 conform to underlying elements. As a result, outlines 551 and 552 of panels 527 and 528, respectively, are visible in skin panels 534 and 532, respectively. In a similar manner, the outlines 553 and 554 of eye stay reinforcing elements 529 and 530 are visible in skin panel 533. The patterns of mesh panels 520 and 521 are partially visible in regions 559 and 560 of skin panel 524.

[120] FIG. 12 shows composite panel 540 after trimming. In particular, peripheral edges of panel 540 have been trimmed in multiple locations so as to provide an even edge and to remove excess material. A tongue opening 565 has been cut, and material has been removed so as to free the top and forward edges of lateral ankle tab 566. Lace eyelets 567 have been punched through panel 540 along the edges of tongue opening 565. Additional eyelets 568 have been punched through lateral ankle tab 566 and medial ankle tab 570.

[121] FIG. 13 shows the inner face 600 of substrate panel 501 (and of trimmed composite panel 540). Regions 601a-601k on inner face 600 are respectively located adjacent to corresponding peripheral edge portions 602a-602k. In a three-dimensional upper shell formed from shell 540, and as seen in connection with FIG. 15A, regions 601a-601k will be part of extensions in a lower portion of that shell. As described below in connection with

FIGS. 15A and 15B, the extension regions 601a-601k are bonded to a lower surface of a foam midsole in a later step.

[122] Also marked in FIG. 13 is a region 571 of inner face 600. In the next step of forming an upper that will include panel 540, region 571 is bonded to region 572 on the outer face of panel 540 (FIG. 12). In particular, and in the embodiments described in connection with FIGS. 10A-16, trimmed panel 540 is a flat, unibody upper shell. Unlike certain previously-described embodiments, this flat unibody upper shell does not include a separate foxing panel in the hindfoot region. Regions 571 and 572 can be bonded by interposing hot melt bonding material between regions 571 and 572, by placing those regions into contact with one another, and by then applying pressure and heat. A jig similar to jig 160 (FIG. 5G) could be used.

[123] In some embodiments, an ankle collar and/or padding can be added to panel 540 after trimming, but prior to bonding regions 571 and 572. The ankle collar (which could be located along edge 575 of panel 540) and the padding (which could be part of the ankle collar and/or located on the inside face of panel 540 below edge 575) could be added using techniques described in connection with previous embodiments.

[124] FIG. 14 shows panel 540 after regions 571 and 572 have been bonded so as to convert panel 540 from a flat, unibody upper shell into a three-dimensional upper shell 540'. FIG. 14 further shows shell 540' placed onto a last L. Only a toe portion of last L and a last supporting bracket B are visible in FIG. 14. For simplicity, FIG. 14 does not show an ankle collar or features that could have been added in the hindfoot region of the shell 540' prior to placing of shell 540' onto last L. In some embodiments, shell 540' may undergo additional finishing prior to placement onto last L. For example, shell 540' could be heated and applied to a shaping form so as to obtain a desired shape in certain regions.

[125] Also shown in FIG. 14 is a foam midsole 610. The top side of midsole 610 is shown in FIG. 14. Stated differently, the side of midsole 14 seen in FIG. 14 will face toward a wearer foot in a completed shoe. In the embodiment of FIGS. 10A-16, midsole 610 is formed from one or more foam materials such as are described in the aforementioned U.S. Patent No. 7,941,938. Midsole 610 includes a top surface 611 that is approximately

contoured to conform to a wearer foot, as well as an edge wall 612 extends above surface 611 and that surrounds the sides of a wearer foot to provide sideways support.

[126] As part of assembling the shoe that will include shell 540' and midsole 610, midsole 610 is placed into shell 540' so that surface 611 contacts last L. This is represented by an arrow in FIG. 14. FIG. 15A shows midsole 610 after placement into shell 540' and onto last L. In FIG. 15A, the bottom surface 615 of midsole 610 is visible. The lower portions of shell 540' (including regions 601a-601k of inner face 600 and corresponding peripheral edge portions 602a-602k) extend beyond bottom surface 615. These extension portions of shell 540' form a skirt that extends out of the plane of FIG. 15A.

[127] In a subsequent fabrication step, the extension portions of shell 540' are folded over and bonded to surface 615. In particular, an adhesive is applied to regions 601a-601k of inner face 600. A fabricator then sequentially pulls on lower portions of shell 540' so as to stretch shell 540' tightly against last L and, while maintaining tension on shell 540', presses those pulled lower portions against surface 615 so as to bond each of regions 601a-601k to surface 615.

[128] FIG. 15B shows midsole 610 after the lower portions of shell 540' have been bonded to surface 615. Regions 601b through 601j become part of a shelf that supports midsole 610, and is located in a heel region. Regions 601b through 601j also form a double-lasted heel cup. Region 601a becomes part of the shelf supporting midsole 610 and is located in medial mid- and forefoot regions. Region 601k becomes part of the shelf supporting midsole 610 and is located in lateral mid- and forefoot regions.

[129] In other embodiments, extension portions of an upper shell may not form a support shelf located in heel, medial mid- and forefoot, and lateral mid- and forefoot regions. For example, a shell in some embodiments may only include extensions that form a support shelf located in a heel region. As another example, a shell in other embodiments may only include extensions that form a support shelf located in heel and midfoot regions.

[130] Ridge 616 extends above surface 615 and is used to position additional sole structure elements in subsequent steps. Ridge 616 also compensates for the thickness of the shell 540' portions bonded to surface 615. In particular, ridge 616 provides additional support in the

central portion of the midsole 610 bottom surface that lack the presence of folded over shell 540' portions.

[131] FIG. 16 shows a shoe 700 that includes shell 540' and bonded midsole 610 from FIG. 15B. In subsequent fabrication operations, a toe cap 630 is attached by adhesively bonding the outer edges of shell 540' near cutout 505 to inner edges of toe cap 630. A support plate 631 and outsole 632 are also attached. A tongue is attached to the interior of shell 540', and an insole may be inserted. A bootie or other liner may also be attached, which liner may be a part of the tongue and attached as part of tongue attachment, and which liner may contain the insole. FIG. 16 also shows an ankle collar 635 that has been added to shell 540'.

[132] In other embodiments that include upper shells with extensions used for double-lasting and/or to otherwise provide a shelf to support foam padding, numerous variations are possible. For example, fewer or more reinforcing panels can be used. The thicknesses, shapes, arrangements and other aspects of such reinforcing panels can be varied. Decorative features similar to those resulting from cutouts 509 and 510 can be achieved in additional ways. As but one example, a reinforcing panel can have reduced thickness in a certain area instead of a slot cut all the way through the panel. As another example, a small piece of material (e.g., in the shape of a logo) could be placed on an outer surface of a reinforcing panel so as to create an outline when skin material is later bonded to the reinforcing panel.

[133] FIGS. 17A through 17E illustrate example components that may be incorporated into another example composite upper in accordance with some aspects of this invention. FIG. 17A illustrates the substrate or base layer 800 for this example upper construction. This substrate layer 800 may be made of any desired materials without departing from this invention, including the various materials described for substrate layer 27 above. As a more specific example, the substrate layer 800 may be a 0.35 mm polyurethane hot met film material called HM Millon (a 0.15 mm polyurethane skin and a 0.2 mm hot melt layer). While any number of pieces may be provided for substrate layer 800 without departing from this invention, this example substrate layer 800 includes four separate parts, namely, rear foot and medial side part 800a, lateral side and forefoot part 800b, medial forefoot part 800c, and toe part 800d. These example parts 800a through 800d each have openings 802 defined through them, but this is not a requirement (e.g., the openings 802 can be positioned and used to provide desired features to the upper at specific areas, such as support, breathability,

aesthetics, etc.). Area 804 is an open area at the vamp or instep area of the upper, located between parts 800b, 800c, and 800d, which will correspond to the open tongue area of the upper in the final construction. Any desired configurations and arrangements of the parts and/or openings may be provided. Notably, the substrate parts 800a through 800d have holes 806 for mounting the substrate layer 800 on pins in the manner described above (not all pin mounting holes are labeled in FIG. 17A).

[134] FIG. 17B illustrates an example mesh layer 810 that may be used in this example composite upper construction. While a single mesh layer component part is shown in FIG. 17B, the mesh layer 810 may be made from any desired number of separate parts without departing from this invention. Mesh layer 810 may be made of any desired materials, with any desired mesh opening size(s), without departing from this invention, including the various materials and mesh sizes described for layer 28 above. Notably, the mesh layer 810 includes holes 812 for mounting the mesh layer 810 on pins in the manner described above (not all pin mounting holes are labeled in FIG. 17B).

[135] In the example construction shown in FIGS. 17A through 19, the exterior of the upper may include multiple skin layers, in at least some areas. In some examples, at least some of these skin layers may be transparent, transparent to certain wavelengths of light (e.g., to appear colored), or translucent (optionally, with some color component). FIG. 17C illustrates a first skin layer 820, which may be made of one or more separate parts (three parts 820a, 820b, and 820c are shown in the example of FIG. 17C). The parts 820a, 820b, and 820c may be joined together at overlapping joints shown at 820d (during the pressing steps to be described below, at another appropriate time, etc.). The first skin layer 820 may be made of a first color material, which may be transparent (to at least some wavelengths) or translucent (e.g., allows light to pass in a diffused manner). As a more specific example, the translucent skin layer 820 may be a 0.3 mm polyurethane hot met film material called HM Millon TR (0.1 mm polyurethane skin and a 0.2 mm hot melt layer). The example parts 820a through 820c each have openings 822 defined through them, but this is not a requirement (e.g., the openings 822 can be positioned and used to provide desired features to the upper, such as support, breathability, aesthetics, abrasion resistance, etc.). Any desired configurations and arrangements of the skin parts and/or openings may be provided in skin layer 820. Notably, the skin layer parts 820a through 820c have holes 826 for mounting the skin layer 820 on pins in the manner described above (not all pin mounting holes are labeled in FIG. 17C).

[136] This example upper construction includes another skin layer 830, an example of which is shown in FIG. 17D. This example second skin layer 830 is made from two separate parts 830a and 830b, which are joined at an overlapping joint shown at 830c (during the pressing steps to be described below, at another appropriate time, etc.). The second skin layer 830 may be made of a second color material that optionally differs from the color of the first skin layer 820. The second skin layer 830 may be transparent (to at least some wavelengths) or translucent (e.g., allows light to pass in a diffused manner). As a more specific example, the translucent skin layer 830 may be a 0.3 mm polyurethane hot met film material called HM Millon TR (0.1 mm polyurethane skin and a 0.2 mm hot melt layer). The example part 830b has openings 832 defined through it, but this is not a requirement (e.g., the openings 832 can be positioned and used to provide desired features to the upper, such as support, breathability, aesthetics, abrasion resistance, etc.). If desired, part 830a also could have one or more openings. Any desired configurations and arrangements of the skin parts and/or openings may be provided in skin layer 830. Notably, the skin layer parts 830a and 830b have holes 836 for mounting the skin layer 830 on pins in the manner described above (not all pin mounting holes are labeled in FIG. 17D).

[137] FIG. 17E illustrates additional structures that may be included in a composite upper in accordance with this example of the invention. As shown in FIG. 17E, the additional structures may include, for example, a rear heel support or reinforcing element 840, one or more lace engaging eye stay support or reinforcing elements 842 (if desired, one eye stay support or reinforcing element 842 may include openings for more than one lace engaging eye stay), and a toe support or reinforcing element 844. These additional structures may be made of any desired materials without departing from this invention, including plastics, polymers, rubbers, foams, metals, and the like. The additional structures may be made of materials that will bond to the hot melt material, or they may simply be contained between two layers of material that are hot melted together without the material of the additional structure bonding to the hot melt. As another example, if desired, additional structures could be provided to incorporate soft comfort elements, additional padding, or the like, around the upper structure. Additional structures may be provided in the overall upper construction for any desired reason(s) without departing from this invention, and they may be provided in any desired manners, including in the manners described above.

[138] While building this upper structure may be similar to the processes and steps described above in conjunction with FIGS. 4A1 through 4K, various example features of this embodiment of the invention will be described in more detail below in conjunction with FIGS. 18A through 18E. First, as shown in FIG. 18A, the substrate layer 800 (in one or more separate pieces) is engaged with pins on a flat support base 850 (like assembly jig 100 above), e.g., via pins through the holes 802. This substrate layer 800 will form the inside most layer of this example upper when completed, and the exposed surface shown in FIG. 18A will be located outside the interior chamber of the shoe. Next, as shown in FIG. 18B, the mesh layer 810 is applied to the support base 850. While not absolutely necessary, in this example construction, the mesh layer 810 completely overlies the substrate layer 800. Therefore, the substrate layer 800 and its openings 802 are shown in broken lines in FIG. 18B (because the mesh layer 810 covers these openings 802). Not all of the openings 802 are labeled in FIG. 18B.

[139] While the next steps are shown separately, the various parts of the first skin layer 820, the second skin layer 830 (and any additional skin layers, when present), and/or the additional structures 840, 842, and 844 may be applied to the support base 850 in any desired order, e.g., depending on the desired aesthetics or other properties (as will be explained in more detail below). FIG. 18C first shows the additional support structures 840, 842, and 844 applied over the mesh layer 810. FIG. 18D shows the first skin layer 820 applied to the support base 850 (the first skin layer 820 includes cross hatching running from the upper left to the lower right direction), and FIG. 18E shows the second skin layer 830 applied to the support base 850 (the second skin layer 830 includes cross hatching running from the upper right to the lower left direction). The first skin layer 820 may cover some portions of the mesh layer 810 (and other structures), the second skin layer 830 may cover some portions of the mesh layer 810 (and other structures), and the mesh layer 810 may remain exposed in at least some areas. Once all component parts of the upper are placed on the support base 850, the parts may be joined together using heat and/or pressure, and then formed into an upper and an overall shoe, e.g., in the various manners described above.

[140] FIG. 18E shows some additional interesting features of this aspect of the invention. If desired, as shown in FIG. 18E, the two skin layers 820 and 830 may overlap one another (shown by the criss-cross hatched areas in FIG. 18E). While providing additional support and/or abrasion resistance, this overlapping feature may provide other potentially interesting

characteristics as well. As noted above, the skin layers 820 and 830 may be transparent to at least some wavelengths of light or translucent, and they may have different colors. Thus, at the overlapped areas of the two skins 820 and 830, another color may appear (i.e., a color combination of the two skin layers 820 and 830). As a more specific example, if skin layer 820 is yellow and skin layer 830 is blue, the areas at which these two skin layers 820 and 830 overlap will have a green color. Any desired color combinations may be used without departing from this invention. Also, at areas where one portion of a skin layer overlaps with itself (e.g., at joint areas 820d and 830c), a deeper and richer color of the skin layer may appear. These features provide a wide color palette and interesting design options for manufacturers and allow generation of an interesting aesthetic appearance.

[141] The skin layers 820 and 830 and/or the other structures 840, 842, and 844 need not always be layered on the mesh layer 810 in the same order. For example, in some areas of the upper, skin layer 820 may be outside of skin layer 830, while in other areas of the upper, the skin layer 820 may be inside (beneath) skin layer 830. Changes in the layering order can be accomplished as the various skin layers 820 and 830 and/or other structures (e.g., structures 840, 842, and 844) are placed on the support base 850. Skin layers 820 and 830 may be layered in different manners as they are placed on the support base 850 (e.g., through their pin holes), e.g., by weaving portions of one skin layer 820 or 830 through the openings provided in the other skin layer. Also, when the skin layer is made of different parts (as shown in FIGS. 17C and 17D), the various parts may be placed on the support base 850 in different orders to allow for different layering orders.

[142] FIG. 19 helps illustrate potential differences in the layering on a single upper construction. FIG. 19 includes stars at various areas of the upper construction of FIG. 18E. The table below provides the layering arrangement of the upper construction at the starred locations, moving from the inside (or bottom) to the top (exposed surface).

Table 5 – Layering of Upper at Various Locations

Star Identifier	Layer Construction from Shoe Interior to Exterior
A	810 ¹
B	800 ² , 810, 830 ³ , 820 ⁴

C	800, 810
D	800, 810, 840 ⁵ , 830
E	800, 810, 830
F	800, 810, 830, 820, 820 (this is the location of the overlap joint 820d between parts 820a and 820b of skin layer 820)
G	800, 810, 820
H	800, 810, 830, 820
I	800, 810, 820, 830
J	800, 810, 820, 830
K	800, 810, 830, 820
L	800, 810, 830b, 842 ⁶ , 830a
M	800, 810, 830, 842, 820
N	800, 810, 820, 844 ⁷ , 830
O	800, 810, 830, 820b, 820c (this is the location of the overlap joint 820d between parts 820b and 820c of skin layer 820)
P	800, 810, 820, 830
Q	800, 810, 830, 820

¹ Reference No. 810 refers to the mesh layer 810 discussed above.

² Reference No. 800 refers to the substrate layer 800 discussed above.

³ Reference No. 830 refers to the skin layer 830 discussed above.

⁴ Reference No. 820 refers to the skin layer 820 discussed above.

⁵ Reference No. 840 refers to the heel support element 840 discussed above.

⁶ Reference No. 842 refers to the eye support elements 842 discussed above.

⁷ Reference No. 844 refers to the toe support element 844 discussed above.

[143] As evident from a comparison of various closely positioned points (e.g., points H, I, J, and K, or points P and Q), the layering of component parts within a single upper can easily be changed, e.g., to provide a somewhat different look at different areas, to better avoid snagging and delaminating a layer, to otherwise provide different properties to the upper, etc.

[144] If desired, some color blending features may be provided in other ways as well. For example, even if only one skin layer is at least partially transparent or translucent (and colored), the overlapping of that skin layer on other skin layers or other colored areas of the upper will provide color blending and color change areas on the upper, at least in areas of the upper where the colored transparent or translucent skin layer overlays other layers of the shoe, including other layers that may or may not be at least partially transparent or translucent. Therefore, it is not a requirement of the invention that both skin layers have transparent or translucent qualities. In fact, a single skin area that is at least partially transparent or translucent can provide interesting aesthetics and color change areas on the upper, at least in some example constructions according to this invention.

[145] The example upper construction of FIG. 18E (as well as others described above) provides another feature of interest. As shown, the upper blank is not symmetric. Rather, as shown in FIG. 18E, the one side 852 of the upper blank stops about the midfoot area while the other side 854 of the upper blank includes a much longer structure (which will correspond to the heel and a portion of the rear, medial side of the shoe in the final construction). Thus, when the final upper is constructed (as described above), the free end of side 854 will bend around to form the heel, and edge 856 will join with edge 858, e.g., at an overlapping joint, to make the flat upper blank into more of a three dimensional shape (e.g., prior to lasting). The edges 856 and 858 may be joined in any desired manner without departing from this invention, e.g., using hot melt materials (with heat and pressure, e.g., by overlapping skin material 820a at edge 856 on edge 858 of skin material 820c), via sewn seams or stitching, via HF or RF welding, via mechanical connectors, etc. In this manner, the mesh layer 810 and all components of the upper are engaged at the medial side of the upper (e.g., at the medial heel or medial midfoot area), and a rear heel seam is avoided.

[146] In this illustrated example, as noted above, edges 856 and 858 are joined together on the medial side of the shoe. This medial side engagement alleviates stress in the tongue opening area of the shoe and provides a smoother construction in the tongue area (e.g., less binding, billowing, etc.) and a more aesthetically pleasing construction as compared to more symmetric upper blanks that are engaged together in the rear heel area of the shoe. The engagement at the rear heel area of the shoe tends to pull on the sides of the tongue opening and causes an uneven stress and appearance.

[147] A bonded mesh composite panel used in an upper of a shoe such as that of FIGS. 1A and 1B (or of FIG. 16 or FIG. 18E) offers numerous advantages. The composite panel includes substrate material in regions where support and protection for the wearer's foot is helpful, but can include relatively large openings in other areas. These openings help to reduce weight and to facilitate ventilation of the shoe interior. The mesh material provides tensile strength to bridge openings in the substrate layer and to augment the strength of the substrate layer in other areas. By bonding the mesh layer to the substrate layer over a wide area, seams along edges of the substrate ventilation openings can be avoided, thereby reducing the likelihood of tearing or separation along those ventilation hole edges. The skin layers can be used to provide abrasion resistance in various areas and/or to achieve desired aesthetic effects.

[148] The above described fabrication processes for creating a bonded mesh composite panel also offer numerous advantages. Using the above-described processes, a relatively complex composite can be quickly formed in a simple manner using relatively simple equipment. Moreover, the above-described processes can also facilitate inexpensive changes to a composite panel design (for either functional or aesthetic reasons) without requiring substantial expensive re-tooling.

[149] The foregoing description of embodiments has been presented for purposes of illustration and description. The foregoing description is not intended to be exhaustive or to limit embodiments of the present invention to the precise form disclosed, and modifications and variations are possible in light of the above teachings or may be acquired from practice of various embodiments. As but one example, techniques such as are described herein can be used to fabricate articles other than footwear uppers. The embodiments discussed herein were chosen and described in order to explain the principles and the nature of various embodiments and their practical application to enable one skilled in the art to utilize the present invention in various embodiments and with various modifications as are suited to the particular use contemplated. Any and all permutations of features from above-described embodiments are the within the scope of the invention.

CLAIMS:

1. An upper for an article of footwear, comprising:
a base layer;
a first skin layer partially covering the base layer, wherein the first skin layer has a first color; and
a second skin layer partially covering the base layer, wherein the second skin layer has a second color and is at least partially transparent or translucent, and wherein at a first portion of the upper, the first skin layer directly contacts the base layer and is covered by the second skin layer such that a first color appearance at the first portion of the upper includes a blend of the first color and the second color.
2. An upper according to claim 1, wherein the first color differs from the second color.
3. An upper according to claim 1, wherein the first skin layer is at least partially transparent or translucent.
4. An upper according to claim 3, wherein at a second portion of the upper, the second skin layer directly contacts the base layer and is covered by the first skin layer.
5. An upper according to claim 4, wherein in addition to the first color appearance at the first portion where the first skin layer is covered by the second skin layer, the upper includes: (a) the first color appearance at the second portion where the second skin layer is covered by the first skin layer, (b) a third color appearance at a third portion where the first skin layer is present and the first and second skin layers do not overlap, and (c) a fourth color appearance at a fourth portion where the second skin layer is present and the first and second skin layers do not overlap.
6. An upper according to claim 1, wherein at a second portion of the upper, the second skin layer directly contacts the base layer and is covered by the first skin layer.
7. An upper according to claim 1, wherein the upper has a second color appearance at a second portion where the first skin layer is present and the first and second skin layers do not overlap.
8. An upper according to claim 1, wherein the base layer includes a mesh layer.
9. An upper according to claim 1, wherein the base layer includes a support layer and a mesh layer at least partially overlaying the support layer, wherein the first skin layer

directly contacts the mesh layer at the first portion of the upper and the second skin layer directly contacts the mesh layer at a second portion of the upper.

10. An upper according to claim 1, wherein the base layer includes a thermoplastic polyurethane material.

11. An upper according to claim 1, wherein the base layer includes a synthetic leather material.

12. An upper according to claim 1, further comprising:
a reinforcement component located between the base layer and at least one of the first skin layer or the second skin layer.

13. An upper according to claim 12, wherein the reinforcement component is located along an instep opening to provide reinforcement for one or more lace eye stays.

14. An upper according to claim 12, wherein the reinforcement component is located at a toe area of the upper.

15. An upper according to claim 12, wherein the reinforcement component is located at a rear heel area of the upper.

16. An upper according to claim 1, further comprising:
a first reinforcement component located between the base layer and at least one of the first skin layer or the second skin layer, wherein the first reinforcement component is located along a first side of an instep opening to provide reinforcement for one or more lace eye stays on the first side of the instep opening; and

a second reinforcement component located between the base layer and at least one of the first skin layer or the second skin layer, wherein the second reinforcement component is located along a second side of the instep opening to provide reinforcement for one or more lace eye stays on the second side of the instep opening.

17. An upper according to claim 1, wherein the first skin layer is fuse bonded to the base layer.

18. An upper according to claim 1, wherein the first and second skin layers are fuse bonded to the base layer.

19. An upper according to claim 1, wherein the first and second skin layers are fuse bonded to one another and to the base layer.

20. An upper for an article of footwear, comprising:
a base layer, wherein the base layer has a first color;
an intermediate layer provided at least partially on the base layer, wherein the intermediate layer has a second color; and
a first skin layer partially covering the base layer and the intermediate layer, wherein the first skin layer has a third color and is at least partially transparent or translucent, and wherein the upper includes: (a) a first color appearance at a first portion where the first skin layer is absent, (b) a second color appearance different from the first color appearance at a second portion where the first skin layer covers the base layer and the intermediate layer is absent, and (c) a third color appearance different from the first and second color appearances at a third portion where the first skin layer covers the intermediate layer.
21. An upper according to claim 20, wherein the intermediate layer is a second skin layer.
22. An upper according to claim 21, wherein the second skin layer is at least partially transparent or translucent.
23. An upper according to claim 20, wherein the intermediate layer includes an eye stay reinforcing element.
24. An upper according to claim 20, wherein the intermediate layer includes a toe reinforcing element.
25. An upper according to claim 20, wherein the intermediate layer includes a heel reinforcing element.
26. An upper according to claim 20, wherein the first skin layer is fuse bonded to the base layer.
27. An upper according to claim 20, wherein the first skin layer is fuse bonded to the base layer and the intermediate layer.
28. An article of footwear, comprising:
an upper according to any one of claims 1-27; and
a sole structure engaged with the upper.
29. A method for making an upper for an article of footwear, comprising:
engaging a first skin layer with a base layer to at least partially cover the base layer, wherein the first skin layer has a first color; and

engaging a second skin layer with the base layer to at least partially cover the base layer, wherein the second skin layer has a second color and is at least partially transparent or translucent, and wherein at a first portion of the upper, the first skin layer directly contacts the base layer and is covered by the second skin layer such that a first color appearance at the first portion of the upper includes a blend of the first color and the second color.

30. A method according to claim 29, wherein the first color differs from the second color.

31. A method according to claim 29, wherein the first skin layer is at least partially transparent or translucent.

32. A method according to claim 31, wherein at a second portion of the upper, the second skin layer directly contacts the base layer and is covered by the first skin layer.

33. A method according to claim 32, wherein in addition to the first color appearance at the first portion where the first skin layer is covered by the second skin layer, the upper includes: (a) the first color appearance at the second portion where the second skin layer is covered by the first skin layer, (b) a third color appearance at a third portion where the first skin layer is present and the first and second skin layers do not overlap, and (c) a fourth color appearance at a fourth portion where the second skin layer is present and the first and second skin layers do not overlap.

34. A method according to claim 29, wherein at a second portion of the upper, the second skin layer directly contacts the base layer and is covered by the first skin layer.

35. A method according to claim 29, wherein the upper has a second color appearance at a second portion where the first skin layer is present and the first and second skin layers do not overlap.

36. A method according to claim 29, wherein the base layer includes a mesh layer.

37. A method according to claim 29, wherein the base layer includes a support layer and a mesh layer at least partially overlaying the support layer, wherein the first skin layer directly contacts the mesh layer at the first portion of the upper and the second skin layer directly contacts the mesh layer at a second portion of the upper.

38. A method according to claim 29, further comprising:

providing a reinforcement component between the base layer and at least one of the first skin layer or the second skin layer.

39. A method according to claim 38, wherein the reinforcement component is located along an instep opening to provide reinforcement for one or more lace eye stays.

40. A method according to claim 38, wherein the reinforcement component is located at a toe area of the upper.

41. A method according to claim 38, wherein the reinforcement component is located at a rear heel area of the upper.

42. A method according to claim 29, further comprising:

providing a first reinforcement component between the base layer and at least one of the first skin layer or the second skin layer, wherein the first reinforcement component is located along a first side of an instep opening to provide reinforcement for one or more lace eye stays on the first side of the instep opening; and

providing a second reinforcement component between the base layer and at least one of the first skin layer or the second skin layer, wherein the second reinforcement component is located along a second side of the instep opening to provide reinforcement for one or more lace eye stays on the second side of the instep opening.

43. A method according to claim 29, wherein the step of engaging the first skin layer with the base layer includes applying heat and pressure to the first skin layer and the base layer to fuse bond the first skin layer to the base layer.

44. A method according to claim 29, wherein the steps of engaging the first and second skin layers with the base layer include applying heat and pressure to fuse bond the first and second skin layers to the base layer.

45. A method according to claim 44, wherein the steps of engaging the first and second skin layers with the base layer occur simultaneously.

46. A method of making an upper for an article of footwear, comprising:

engaging an intermediate layer with a base layer, wherein the base layer has a first color and the intermediate layer has a second color; and

engaging a first skin layer with the base layer so as to partially cover the base layer and the intermediate layer, wherein the first skin layer has a third color and is at least partially transparent or translucent, and wherein the upper includes: (a) a first color appearance at a first portion where the first skin layer is absent, (b) a second color appearance different from the first color appearance at a second portion where the first skin layer covers the base layer

and the intermediate layer is absent, and (c) a third color appearance different from the first and second color appearances at a third portion where the first skin layer covers the intermediate layer.

47. A method according to claim 46, wherein the intermediate layer is a second skin layer.

48. A method according to claim 47, wherein the second skin layer is at least partially transparent or translucent.

49. A method according to claim 46, wherein the intermediate layer includes an eye stay reinforcing element.

50. A method according to claim 46, wherein the intermediate layer includes a toe reinforcing element.

51. A method according to claim 46, wherein the intermediate layer includes a heel reinforcing element.

52. A method according to claim 46, wherein the step of engaging the first skin layer with the base layer includes applying heat and pressure to the first skin layer and the base layer to fuse bond the first skin layer to the base layer.

53. A method according to claim 46, wherein the steps of engaging the intermediate layer and the first skin layer with the base layer include applying heat and pressure to fuse bond the first skin layer to the base layer.

54. A method according to claim 46, wherein the steps of engaging the intermediate layer and the first skin layer with the base layer include applying heat and pressure to fuse bond the first skin layer and the intermediate layer to the base layer.

55. A method according to claim 46, wherein the steps of engaging the intermediate layer and the first skin layer with the base layer occur simultaneously.

56. A method of making an article of footwear, comprising:
producing an upper according to any one of claims 29-55; and
engaging a sole structure with the upper.

57. A method of making an article of footwear, comprising:
providing an upper having a structure according to any one of claims 1-27; and
engaging a sole structure with the upper.




FIG. 1A

2/51




FIG. 1B

3/51




FIG. 1C




FIG. 2

4/51




FIG. 3





Fig. 4



42
5
6






FIG. 4B



20


4025



Q

10/51

Steps



46







FIG. 4F

7335



24





15/51




FIG. 4J

16/51




FIG. 4K

17/51




FIG. 4L




FIG. 5A





FIG. 5B



21/51

STEP 14





FIG. 5D



56

STEP 16




FIG. 5F

24/51

STEP 17




FIG. 5G

25/51




FIG. 6A




FIG. 6B

26/51




FIG. 7




FIG. 8




FIG. 9A




FIG. 9B




FIG. 9C

30/51




FIG. 10A




FIG. 10B




FIG. 10C




FIG. 10D




FIG. 10E





FIG. 11

36/51



25

37/51




FIG. 13

38/51




FIG. 14

39/51




FIG. 15A




FIG. 15B

40/51




FIG. 16

41/51




FIG. 17A




FIG. 17B




FIG. 17C




FIG. 17D




FIG. 17E




FIG. 18A




FIG. 18B




FIG. 18C

49/51




FIG. 18D




FIG. 18E

51/51




FIG. 19

INTERNATIONAL SEARCH REPORT

International application No
PCT/US2012/039589

A. CLASSIFICATION OF SUBJECT MATTER
INV. A43B23/02 A43B1/00
ADD.

According to International Patent Classification (IPC) or to both national classification and IPC

B. FIELDS SEARCHED

Minimum documentation searched (classification system followed by classification symbols)
A43B

Documentation searched other than minimum documentation to the extent that such documents are included in the fields searched

Electronic data base consulted during the international search (name of data base and, where practicable, search terms used)

EP0-Internal, WPI Data

C. DOCUMENTS CONSIDERED TO BE RELEVANT

Category*	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
X	EP 2 084 981 A1 (INNOVATEC MICROFIBRE TECHNOLOG [DE] INNOVATEC MICROFIBRE TECHNOLOGY GM) 5 August 2009 (2009-08-05) paragraphs [0009], [0016]; claim 4 -----	1-57
X	DE 452 156 C (MUELLER JOSEF) 4 November 1927 (1927-11-04) claims -----	1-57
A	EP 2 250 914 A1 (SPORT MASKA INC [CA]) 17 November 2010 (2010-11-17) claims; figures -----	1-57



Further documents are listed in the continuation of Box C.



See patent family annex.

* Special categories of cited documents :

"A" document defining the general state of the art which is not considered to be of particular relevance

"E" earlier application or patent but published on or after the international filing date

"L" document which may throw doubts on priority claim(s) or which is cited to establish the publication date of another citation or other special reason (as specified)

"O" document referring to an oral disclosure, use, exhibition or other means

"P" document published prior to the international filing date but later than the priority date claimed

"T" later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the invention

"X" document of particular relevance; the claimed invention cannot be considered novel or cannot be considered to involve an inventive step when the document is taken alone

"Y" document of particular relevance; the claimed invention cannot be considered to involve an inventive step when the document is combined with one or more other such documents, such combination being obvious to a person skilled in the art

"&" document member of the same patent family

Date of the actual completion of the international search

12 September 2012

Date of mailing of the international search report

21/09/2012

Name and mailing address of the ISA/

European Patent Office, P.B. 5818 Patentlaan 2
NL - 2280 HV Rijswijk
Tel. (+31-70) 340-2040,
Fax: (+31-70) 340-3016

Authorized officer

Claudel, Benoît

INTERNATIONAL SEARCH REPORT

Information on patent family members

International application No

PCT/US2012/039589

Patent document cited in search report		Publication date	Patent family member(s)	Publication date
EP 2084981	A1	05-08-2009	AT 536111 T	15-12-2011
			DE 102008006623 A1	30-07-2009
			EP 2084981 A1	05-08-2009

DE 452156	C	04-11-1927	NONE	

EP 2250914	A1	17-11-2010	CA 2703363 A1	12-11-2010
			EP 2250914 A1	17-11-2010
			US 2011016752 A1	27-01-2011
