




(86) Date de dépôt PCT/PCT Filing Date: 2001/07/24
(87) Date publication PCT/PCT Publication Date: 2002/01/31
(45) Date de délivrance/Issue Date: 2008/01/29
(85) Entrée phase nationale/National Entry: 2003/01/21
(86) N° demande PCT/PCT Application No.: US 2001/023235
(87) N° publication PCT/PCT Publication No.: 2002/007799
(30) Priorités/Priorities: 2000/07/24 (US60/220,247);
2000/11/29 (US09/725,828)

(51) Cl.Int./Int.Cl. *A61M 3/02* (2006.01),
A61M 35/00 (2006.01), *B05B 11/04* (2006.01)
(72) Inventeur/Inventor:
RUCINSKI, PAUL J., US
(73) Propriétaire/Owner:
INNOVATION TECHNOLOGIES, INC., US
(74) Agent: MACRAE & CO.

(54) Titre : NOUVEAU DISPOSITIF ET PROCEDE D'IRRIGATION D'UNE PLAIE
(54) Title: NOVEL WOUND IRRIGATION DEVICE AND METHOD



(57) Abrégé/Abstract:

The subject invention pertains to a method and device for irrigation of a wound, said device comprising a reservoir housing containing a wound irrigation solution and a discharge means attachable thereto, said discharge means having at least one port therethrough wherein said port, or ports forms a nozzle for directing a pressurized dispersed stream of said solution.

(12) INTERNATIONAL APPLICATION PUBLISHED UNDER THE PATENT COOPERATION TREATY (PCT)

(19) World Intellectual Property Organization
International Bureau



(43) International Publication Date
31 January 2002 (31.01.2002)


PCT

(10) International Publication Number
WO 02/007799 A3


- (51) International Patent Classification⁷: A61M 3/02, 35/00, A61J 1/00, B05B 11/04
- (72) Inventor; and
(75) Inventor/Applicant (*for US only*): RUCINSKI, Paul, J. [/]; 4037 S.W. 93rd Drive, Gainesville, FL 32608 (US).
- (21) International Application Number: PCT/US01/23235
- (74) Agents: SALIWANCHIK, David, R. et al.; Saliwanchik, Lloyd & Saliwanchik, Suite A-1, 2421 N.W. 41st Street, Gainesville, FL 32606-6669 (US).
- (22) International Filing Date: 24 July 2001 (24.07.2001)
- (25) Filing Language: English
- (81) Designated States (*national*): AE, AG, AL, AM, AT, AU, AZ, BA, BB, BG, BR, BY, BZ, CA, CH, CN, CO, CR, CU, CZ, DE, DK, DM, DZ, EC, EE, ES, FI, GB, GD, GE, GH, GM, HR, HU, ID, IL, IN, IS, JP, KE, KG, KP, KR, KZ, LC, LK, LR, LS, LT, LU, LV, MA, MD, MG, MK, MN, MW, MX, MZ, NO, NZ, PL, PT, RO, RU, SD, SE, SG, SI, SK, SL, TJ, TM, TR, TT, TZ, UA, UG, US, UZ, VN, YU, ZA, ZW.
- (26) Publication Language: English
- (30) Priority Data:
60/220,247 24 July 2000 (24.07.2000) US
09/725,828 29 November 2000 (29.11.2000) US
- (71) Applicant (*for all designated States except US*): INNOVATION TECHNOLOGIES, INC. [US/US]; 4037 S.W. 93rd Drive, Gainesville, FL 32608 (US).
- (84) Designated States (*regional*): ARIPO patent (GH, GM, KE, LS, MW, MZ, SD, SL, SZ, TZ, UG, ZW), Eurasian

[Continued on next page]

(54) Title: NOVEL WOUND IRRIGATION DEVICE AND METHOD



(57) Abstract: The subject invention pertains to a method and device for irrigation of a wound, said device comprising a reservoir housing containing a wound irrigation solution and a discharge means attachable thereto, said discharge means having at least one port therethrough wherein said port, or ports forms a nozzle for directing a pressurized dispersed stream of said solution.



WO 02/007799 A3

WO 02/007799 A3

patent (AM, AZ, BY, KG, KZ, MD, RU, TJ, TM), European patent (AT, BE, CH, CY, DE, DK, ES, FI, FR, GB, GR, IE, IT, LU, MC, NL, PT, SE, TR), OAPI patent (BF, BJ, CF, CG, CI, CM, GA, GN, GQ, GW, ML, MR, NE, SN, TD, TG).

Published:

- *with international search report*
- *before the expiration of the time limit for amending the claims and to be republished in the event of receipt of amendments*

(88) Date of publication of the international search report:
29 August 2002

For two-letter codes and other abbreviations, refer to the "Guidance Notes on Codes and Abbreviations" appearing at the beginning of each regular issue of the PCT Gazette.

DESCRIPTIONNOVEL WOUND IRRIGATION DEVICE AND METHOD

5

Background of the Invention

In the management and treatment of a wound (defined herein to mean any injury or opening in tissue) there are three primary objectives: (1) prevention of infection, (2) preservation and/or restoration of function, and (3) preservation and/or restoration of cosmetic appearance. The most important of these objectives is the prevention of infection. Success in the prevention of infection directly affects the healing process and the degree to which the other two objectives, function and cosmetic appearance, can be preserved and/or restored.

In the case of wounds, the presence of bacteria is the single cause of infection. It is known that the number of bacteria, rather than bacterial type, is a critical determinant of whether a wound becomes infected. Experimental evidence suggests that a critical level of bacteria is approximately 10^5 organisms per gram of tissue. Below this level, wounds heal; at levels greater than 10^5 bacteria per gram of tissue, wounds often become infected. All traumatic wounds are contaminated by the time the wound is presented to a medical care facility for treatment (Dire, Daniel I. [1990] "A comparison of Wound Irrigation Solutions Used in the Emergency Department," *Annals of Emergency Medicine* 19(6):704-708). Dirty wounds, or those which have not been treated within six hours, are likely to be contaminated with bacteria at levels which are higher than the critical level. Reducing the number of bacteria in and around the wound is a recognized and accepted means for avoiding infection and expediting wound healing.

Different procedures of wound management have been developed to help decrease the level of bacteria present in a wound, *i.e.*, reduce the incidence of infection. The cleansing of a wound and the site surrounding the wound to remove blood clots, debris, dirt, or other foreign materials which can introduce contaminants, including pathogenic microorganisms, is critical in reducing levels of bacteria in and around the wound. There are numerous wound cleansing procedures presently used by healthcare professionals such as debridement, excision and irrigation. See, for example, Sinkinson, Craig Alan, ed. (1989) "Maximizing A Wound's Potential For Healing," *Emergency Medicine Reports* 10(11):83-89; Lammers, Richard L. (1991) "Soft Tissue Procedures: Principles of Wound Management," in *Clinical Procedures in Emergency Medicine*, Roberts and Hedges, eds., 2nd Ed., W.B. Saunders Company, pp. 515-521; Cracroft, Davis (1987) "Minor Lacerations and Abrasions," *Emergency Medicine: A Comprehensive Review*, Kravis and Warner, eds., 2nd cd., Aspen Publishing Co., pp. 107-110;

and Mulliken, John B. (1989) "Management of Wounds," in *Emergency Medicine*, May ed., John Wiley & Sons, pp. 283-286.

Irrigation is the most commonly used procedure for cleansing of open contaminated wounds.

5 Irrigation involves the application of sterile solutions or fluids to wounds to remove loose devitalized tissue, bacterial inoculum, blood clots, loose debris, and foreign bodies proximate to and within the depths of the wound. The two critical components of any effective wound irrigation method and/or device are: (1) the application of an adequate volume of sterile irrigation solution to the wound, and (2) the use of sufficient pressure applied in an effective
10 dispersal pattern in the delivery of the solution to effectively remove contaminants. Regarding volume, the amount of irrigation solution required will depend upon the type of wound and the level of contamination. Injuries which can introduce a high amount of bacteria into a wound (such as puncture wounds and bites) may require 1 liter or more of irrigation solution. See Mulliken, 1989. Regarding pressure, it has been demonstrated that stream pressure of a
15 minimum of 4 pounds per square inch (psi) (and, preferably, 7 psi) is required to effectively flush or remove contaminants from a wound. See, for example, Rodeheaver GT. Wound Cleaning, Wound Irrigation, Wound Disinfection, In: Krasner D., Kane D. Chronic Wound Care. 2nd ed. Wayne, P.A.: Health Management Publications; 1997, pp 97-108; and Bergstrom N., Bennett, M.A., Carlson, C.E. *et al.* Treatment of Pressure Ulcers. Clinical Guideline No. 15. AHCPR Publication No. 95-0652. Rockville, MD. Department of Health and Human Services. Public Health Services, Agency of Health Care Policy and Research; December 1994. Irrigation pressure in excess of desired limits (e.g., 25 psi or greater) may actually drive bacteria and particulate matter deeper into the wound and thereby defeat the purpose of the irrigation process. High-pressure irrigation may also cause damage to healthy tissue and impede the tissue's
20 defenses and retard healing. Thus, effective wound irrigation requires the use and application of adequate volumes of irrigation solution delivered to the wound in an effective dispersal pattern at appropriate pressures.

 Bulb syringes or gravity flow irrigation devices deliver fluid at low pressures and as such are ineffective in ridding wounds of small particulate matter or in sufficiently reducing
30 wound bacterial counts. Irrigation by bulb syringe exerts a pressure of about 0.05 psi, which does not reduce the number of bacteria or particulate contaminants enough to prevent infection. The flow rate of irrigation fluid delivered through intravenous (IV) tubing can be enhanced by inflation of a blood pressure cuff around a collapsible plastic IV bag. This method is cumbersome and provides considerably less irrigation pressure than can be delivered by a
35 plunger-type syringe.

The plunger-type syringe is the most common irrigation device currently used. Its use involves filling the barrel of the syringe with sterile irrigation solution and depressing the plunger to generate and apply a single pressurized stream of solution in and around the wound to dislodge and rinse away contaminants. This device has two notable disadvantages: (1) an
5 extremely limited reservoir of irrigation fluid (typically a syringe with a 35 cc-capacity barrel), and (2) it is limited to dispersal and application of a single concentrated stream of solution to the wound. Consequently, in most cases, the syringe must be repeatedly refilled in order to apply sufficient quantities of irrigation solution to a wound. This is time-consuming and cumbersome to do while attempting to maintain a sterile field. In an attempt to address this
10 limitation, a device has been developed that involves a system consisting of a syringe and IV tubing with a valve system that attaches to a bottle of saline to provide a ready means of refilling the syringe barrel. (Travenol^{*} pressure irrigation set, code no. 2D2113, or irriget, Ackrad Laboratories, Garwood, NJ). Additionally, U.S. Patent No. 4,357,937 describes a disposable, manually operable medical irrigation device which is adapted for providing selective volume
15 and stream intensity in liquid flow from a plurality of syringes. These devices do not adequately address the disadvantages of using syringes for irrigation as discussed above and are not commonly used in clinical practice due to their complexity of use and cost.

The amount of hydraulic pressure that can be delivered with a plunger-type syringe varies with the force exerted on the plunger of the syringe and with the internal diameter of the
20 attached needle. Plunger-type syringe devices that deliver moderate pressure employ either a 19 gauge needle attached to a 35 cc syringe, which creates hydraulic pressure in the range of 7-8 psi, or a 30 ml syringe fitted with a 19 gauge needle which typically creates about 7 psi irrigation pressure. A 22 gauge needle attached to a 12 cc syringe, delivers a pressure of about 13 psi. Such pressures have been proven effective in wound irrigation, but, as stated above, such devices
25 apply only a single stream of solution to the wound. In addition, these described devices hold less than adequate volumes of irrigation solution and therefore require repeated refilling which is time consuming and cumbersome.

U.S. Patent No. 5,071,104 describes a wound irrigation apparatus and process for cleansing wounds which includes a pressure bladder, e.g., a blood pressure cuff, disposed
30 proximate a reservoir holding a cleaning solution. The device in the '104 patent also includes a flexible tubular conduit for transmitting the solution from the reservoir to a single nozzle. The conduit and reservoir form a two-part system which is time consuming to set up, inconvenient to use, and costly.

U.S. Patent No. 5,133,701 describes a disposable pressurized wound irrigation device
35 which has a pressurized chamber for providing a force upon the reservoir such that a single
*Trade-mark

liquid stream of cleansing solution is expelled from the device at a constant pressure. A propellant is used in evacuating the cleanser contents of the device. This invention requires a propellant and involves a relatively elaborate manufacturing and filling process which is labor intensive and requires specialized machinery. This device is also inconvenient to use and costly.

5 The subject invention successfully addresses the above described disadvantages associated with the previously known devices and methods, and provides certain attributes and advantages which have not been realized by these known devices.

Brief Summary of the Invention

10 The subject invention concerns a novel and inexpensive method and device for convenient and effective manual wound irrigation. In one embodiment the subject invention provides a discharge means for a standard reservoir housing containing an adequate volume of irrigation solution wherein the discharge means has a plurality of nozzles through which the irrigation solution can pass. In a preferred embodiment the reservoir housing, upon which the
15 discharge means is affixed, is compressible or squeezable (*e.g.*, plastic bottles in which the saline solutions are presently available). The medical or health care professional or other person using the subject device and providing wound irrigation therapy can compress the reservoir housing to force the irrigation solution through the nozzles under sufficient pressure to dislodge dirt, debris, or other particles, including microorganisms, *e.g.*, pathogenic bacteria.

20 In another embodiment, elongated ports are used to achieve the desired dispersal of the stream of irrigation solution.

 The object of the subject invention is to provide an easy to use, economical wound irrigation method and device which are capable of delivering adequate volumes of irrigation solution (without refilling the reservoir) in a dispersed stream under sufficient pressure to
25 effectively cleanse the wound thereby reducing the incidence of infection.

 The subject invention would allow the medical professional to, without assistance, easily direct and control the application of irrigation solution with one hand, leaving the other hand free for other activities such as separation of the wound to further facilitate irrigation.

Brief Summary of the Figures

30 **Figure 1** shows the subject wound irrigation device which includes a compressible reservoir housing, and a discharge means which has a plurality of ports which form nozzles for directing pressurized streams or a shower of irrigation solution to the wound.

Figure 2 shows a sectional view of a discharge means illustrating the cone shaped
35 design of the ports forming the nozzles which direct a pressurized stream of irrigation solution.

Figure 3 shows an embodiment of the subject reservoir housing having incorporated therein an inlet port for supplying pressurized gas from a source to the reservoir.

Figure 4 shows the embodiment of the device comprising a discharge means and reservoir housing, which includes a back-splash protective shield component.

5 **Figure 5** shows an alternative embodiment of the subject wound irrigation device comprising an adjustable discharge means.

Figure 6 shows a perspective view of an adjustable discharge means.

Figure 7a shows a top perspective view of an adjustable nozzle with splash guard.

Figure 7b shows a bottom perspective view of an adjustable nozzle with splash guard.

10 **Figure 8** shows a perspective view of an outer seal.

Figure 9a shows a cross-sectional view of the adjustable discharge in a first position.

Figure 9b shows a cross-sectional view of the adjustable discharge in a first position.

Figure 10 shows a preferred embodiment of the subject wound irrigation device comprising a flat disc discharge means.

15 **Figure 11** shows a perspective view of a flat disc discharge means.

Figure 12 shows a top view of a flat disc discharge means

Figure 13 shows a perspective view of an end cap.

Figure 14 shows a perspective view of the end cap with splash guard.

20 **Figure 15** shows a perspective view of the end cap with splash guard and protective membrane.

Figure 16 shows a cross-sectional view of the flat discharge means secured to the reservoir housing.

Figure 17 shows an embodiment of the subject wound irrigation device with a protective cover.

25 **Figure 18** shows a preferred embodiment of the subject wound irrigation device.

Figure 19 shows a preferred embodiment of the subject wound irrigation device discharging fluid.

Detailed Description of the Invention

30 The subject invention is a novel, convenient, inexpensive, and effective device which comprises, in a preferred embodiment, a reservoir housing and a discharge means for irrigation of a wound. The subject invention also includes a method of use for the device. The materials and methods of the subject invention make it possible, for the first time, to conveniently and easily apply a stream of wound irrigation fluid to a wound with the stream having an appropriate
35 volume, pressure, and dispersal pattern. Unlike previous attempts to provide wound irrigation

devices, the current invention is particularly advantageous in its simplicity and its ability to provide a physician with excellent control over the irrigation process. Under optimal circumstances, the devices and methods of the subject invention will be utilized by trained emergency technicians; however, because of the simplicity and convenience of the subject invention, it can be used to greatly enhance the effectiveness of wound irrigation regardless of the training level of the person performing the irrigation.

The subject invention is perhaps best understood by reference to the accompanying figures. Figure 1 shows an embodiment of the subject invention wherein the device comprises a squeezable reservoir housing having a wall 1 which forms a reservoir which can contain therein a wound-cleaning material. The reservoir can preferably hold a liquid solution (*e.g.*, sterile saline) as the wound cleansing solution for irrigating, and thereby removing particles or other contaminants from, a wound. The reservoir housing has a mouth or opening which communicates the reservoir to the outside of the housing. Disposed over the reservoir housing opening, and affixed to the reservoir housing is a discharge means 2. In one embodiment, the discharge means has a plurality of ports 3, each port forming a circular nozzle whereby the irrigation solution in the reservoir passes through in a pressurized and directional manner. As described herein, other embodiments of the subject invention utilize slits or combinations of slits and circular ports to achieve the advantageous fluid dispersion which is critical to the subject invention. As used herein, the term nozzle refers to either circular ports or elongated ports such as slits. As described herein, a critical feature of the subject invention is the unique use of these nozzles to easily and conveniently achieve a stream of irrigation solution having the appropriate volume, pressure and dispersal pattern to obtain effective wound irrigation which can greatly enhance the safe and speedy recovery from wounds.

As used herein, reference to a "dispersed" stream of solution means that the area from which the stream emanates, or the area which it contacts, is larger than that which can be achieved using a syringe. In one embodiment, the dispersed stream can be achieved using multiple ports. The ports can be presented in a variety of patterns such as a circular pattern. Alternatively, the dispersed stream can be achieved using an elongated port, such as a slit. The use of slits can also take advantage of a variety of patterns including slits which form arcs or slits which cross to form an "X" shape or asterisk shape. Combination of slits and circular ports can also be used.

A removable protective shield 4, which is disposable or reattachable can be included, if desired, to cap and protect the discharge means and the contents of the reservoir housing.

The discharge means is a particularly advantageous embodiment of the invention. The discharge means can be affixed to the reservoir housing. The discharge means can be, for

example, a flat or domed disc of approximately the same size as the opening of the reservoir housing. In one embodiment, the discharge means can have a plurality of ports therethrough, each port forming a separate nozzle which allows the contents of the reservoir to pass directly through during use of the invention. Each of the ports can be of any desirable size, preferably less than one-eighth inch in diameter and having a size between about a 10 gauge hypodermic needle and about a 30 gauge needle, and most preferably having a size ranging from that of a 16 gauge needle to a 25 gauge needle. Each of the nozzle-forming ports can be the same size or the ports can be different sizes and shapes. The different sizes of ports allow for the liquid to be expelled from the discharge means at different pressures. For example, the 16 gauge port allows for a stream having about 6 psi pressure when the device is squeezed by the normal adult; the 25 gauge port provides a pressure of up to about 20 psi from each nozzle.

In a preferred embodiment, each port is cone-shaped, forming a nozzle traversing the discharge means. The nozzle has a larger diameter on the inner face of the discharge means and a smaller diameter on the outside face of the discharge means. This embodiment of cone-shaped ports is shown as 5 in Figure 2. In one embodiment, the wall of the cone-shaped nozzle is formed at an angle of about 60 degrees from the perpendicular. Advantageously, the cone shape of each nozzle allows for hydrostatic pressure to keep the nozzle filled with liquid thus lubricating the surface of the device in the unlikely event that the wound is inadvertently contacted with the discharge means during the irrigation process. Alternatively, the ports can be cylindrical instead of cone shaped.

The nozzles can also be formed in different configurations in order to optimize the irrigation action for particularly desired results. For example, one nozzle design comprises a 19 gauge (needle size) central nozzle surrounded by a circularly disposed row wherein the circle formed by the row of nozzles has a diameter of about 1 cm. The circularly disposed row consists of about eight (8) nozzles in one embodiment of the invention, which are spaced evenly apart from one another. At least two, and preferably four, of these nozzles, alternately configured, are formed in such a way that the stream of liquid expelled from the discharge means is directed at an angle of 45-85 degrees from the surface of the discharge means. The angle of these ports is preferably between 75 degrees and 85 degrees and is most preferably about 82 degrees from the surface of the discharge means. The remainder of the nozzles, including the center nozzle, direct a stream at about a 90-degree angle from the top surface. The preferred configuration allows the stream from each of the nozzles angled at 82 degrees to intersect with the stream from the center nozzle at about 25 cm from the outer surface of the discharge means.

In another embodiment, the discharge means can include decreased nozzle size which can generate a greater stream pressure (22 gauge needle size). This embodiment preferably

includes at least one additional circularly disposed row either outside or inside the circularly disposed row as described for the embodiment above. The circularly disposed rows form nozzles which are disposed in a configuration of concentric rings. An additional circularly disposed row of nozzles can increase the volume of irrigation solution used in the irrigation process. Alternatively, increasing the diameter of the nozzles can allow greater volume of irrigation solution to be directed at the wound. Preferably, the additional circularly disposed row is an outer row which comprises eight (8) additional nozzles approximately 1 cm outward, radially, from the center nozzle. The number of nozzles can vary from as little as 2 to as many as 24 or more as desired. Most preferably at least two, and typically four, of the nozzles in the outer row, in an alternating basis, would direct a stream of the solution contained therein at an angle of about 75 to 85 degrees when discharged by pressure created by squeezing of the bottle. As would be appreciated by one skilled in the art having the benefit of this disclosure, elongated ports (slits) can be used to achieve essentially the same dispersal pattern as that which is produced using the holes as discussed herein.

One embodiment of the subject invention also includes a removable or partially detachable protective shield, which is placed over the discharge means to protect the ports and contents of the reservoir from contamination or premature discharge or leakage. The protective shield can comprise a screw-cap which threadably engages the neck of a discharge means, a snap-on cap which is detachably affixed to the discharge means or neck of the reservoir housing using a latch, hook, or other locking or connecting means, or a hinged cover commonly referred to as a "flip-top" cap. The hinged cover can be permanently affixed to the discharge means or can be part of a threadably engaged screw-cap or protective shield.

A second type of protective shield can also be provided as a component of the subject device. This second type of protective shield is a "back-splash" protective shield wherein the back-splash protective shield is detachably or permanently affixed to the device, preferably between the discharge means and the compressible reservoir housing. The back-splash protective shield protects the health care professional from back-splash of human and or animal body fluids which are mixed with and splashed from the wound when the wound is contacted by the discharged irrigation solution.

The wall of the reservoir housing can be made or molded from any material which is preferably rigid enough to stand upright when the reservoir is filled with irrigation solution. In a typical embodiment, the reservoir housing is formed by a molded plastic which is pliable enough so that the wall of the reservoir housing can be squeezed or compressed by hand to exert pressure on the contents of the reservoir. Other materials can also be used for the reservoir housing walls, including rubber, laminated or plastic-lined paper, a composite material, or the

like, as would be readily understood in the art. These materials are commercially available. The preferred embodiment comprises a plastic material which is pliable enough to squeeze by hand and which also has resilience properties to return to its original shape when no longer compressed or squeezed.

5 The horizontal cross-sectional shape of the reservoir housing can be square, rectangular, cylindrical, or other geometric shapes as desired or as already available. The walls can be tapering toward one end or the other. Alternatively, other shapes can be made for the reservoir housing according to and adapted for a particular use. For example, part of the reservoir housing wall can be slightly rounded as in a general hourglass shape or can be molded according to
10 ergonomic consideration for easily fitting a hand or otherwise facilitating handling or compressing the reservoir housing. The reservoir formed by the housing of the subject invention can typically hold a volume of about 100 ml to 1000 ml, preferably about 250 ml to about 750 ml and most preferably about 500 ml.

 Further, in a preferred embodiment, the reservoir housing comprises at one end a mouth
15 and a neck portion formed at the mouth end. The neck portion of the reservoir housing is generally at least slightly smaller in diameter than the diameter or diagonal measurement of the reservoir housing. The neck of the reservoir housing forms a connecting means, *e.g.*, threads, for affixing the discharge means thereto. The reservoir housing neck is preferably integrally molded with the reservoir housing, but can be formed or molded separately and affixed to the
20 mouth end of the reservoir housing. The material used for the neck portion of the reservoir housing can be the same as the material used to make the reservoir housing cylinder.

 Alternatively, the neck portion can be a different material, for example, a more rigid or sturdy material than the compressible material forming the reservoir housing wall. For example, the material used to make the neck portion can be a metal or a hard plastic, or the like.

25 The neck portion can be formed having threads, or latches, or other connecting means for affixing the discharge means thereto. The connecting means can be on the outer face of the neck portion, forming a male connecting end, or can be on the inner face forming a female connecting end of the neck portion.

 The discharge means can have connecting means complementary and attachable to the
30 neck portion. In a preferred embodiment, the neck portion and discharge means can have threads or grooves so that the discharge means can be detachably and/or threadably engaged to the neck portion of the reservoir housing. This screw-top design can be made to be adaptable to available irrigation solution bottles. Thus, the discharge means of the subject invention is interchangeable, when desired, with the screw-cap which is provided with an irrigation solution
35 bottle as are available. The screw-top design provides the user with the option of using the

reservoir housing with the nozzle-forming ports or to threadably remove the discharge means and pour out or change the irrigation solution.

Another embodiment of the discharge means includes a stopper which can be forced or wedged into the mouth of a reservoir housing. The stopper can have a flange which facilitates positioning of the stopper by preventing its insertion completely through the opening of the reservoir housing and into the reservoir. In another embodiment, the discharge means can be affixed directly to the reservoir housing or neck portion of the reservoir housing so that the discharge means fits flush with the mouth of the reservoir housing. This flush-fitting embodiment of the discharge means is formed as an integral part of the reservoir housing wherein the discharge means is molded with, or heat-sealed to, the reservoir housing. An alternative embodiment is a flush-fitting discharge means which is held in place over the mouth of the reservoir housing with a connecting ring threadably engaging the threaded neck of the reservoir housing. The discharge means is held in place by having a rib or groove which corresponds to and engages a groove or flange on the threaded connecting ring.

Another embodiment of the subject invention includes a reservoir housing comprising an inlet port and fitting for attaching a flexible tubing for delivery of pressurized gas to the reservoir. A pressurized irrigation reservoir would employ an embodiment of a squeezable reservoir housing that can be attached to an outside pressure source. Pressure sources generally available in hospitals, emergency rooms, and other medical clinics or facilities provide a pressure of 0-55 pounds per square inch (PSI). The reservoir would attach via a flexible tube to the pressure source connector and to the fitting provided on the reservoir housing of the subject device. Supplying to the reservoir an outside source of pressurized gas would permit the medical professional to discharge the irrigation solution obtained in the reservoir at a constant pressure. A valve can also be incorporated into the inlet port fitting, the reservoir housing, and/or the discharge means to stop the flow of air pressurizing the reservoir or to stop the flow of irrigation solution discharged from the discharged means. This permits interruption of the wound irrigation process, and thus control, by the user as desired. Alternatively, the reservoir could itself be pressurized so that no external pressure source is necessary. In this embodiment, the reservoir could be manufactured to contain a pressurized gas to expel the irrigation fluid with the desired force. The pressurized gas could be separated from the fluid by, for example, a diaphragm.

In an alternative embodiment, as shown in Figures 5-9, the subject invention can include an adjustable discharge means 10, which permits the irrigation solution to be discharged at various rates. As shown in Figure 5, the subject invention comprises a compressible reservoir housing 40, having a wall which forms a reservoir, which can contain therein wound-cleaning

material. The reservoir can preferably hold a liquid solution as the wound-cleaning solution for irrigating and thereby removing particles or other contaminants from a wound. The reservoir housing 40 has a mouth opening which communicates the reservoir to the outside of the housing. Disposed over the reservoir housing 40, and removably attached to the reservoir housing's neck 42, can be an adjustable discharge means 10. The adjustable discharge means 10 comprises a valve cap 11 and a valve head 22, where the valve head 22 is threadably affixed to the valve cap 11. The valve cap 11, as shown in Figure 6, comprises an inner air inlet 12 and an inner water outlet 14, where the inner water outlet 14 substantially surrounds the inner air inlet 12, and the inner air inlet 12 and the inner water outlet 14 are separate sections of the valve cap 11. The subject invention can further comprises an air hose 44 connected to the inner air inlet 12, through the base of the valve cap 11. A ball valve 46 is located at the base of the air hose 44. When the valve cap 11 is affixed to the neck 42 of the reservoir housing 40, the air hose 44 is passed through the reservoir housing opening, with the ball valve 46 being positioned near the bottom interior surface of the reservoir. The outer surface of the valve cap 11 comprises positioning threads 18 for engaging the valve head 22.

The valve head 22, as shown in Figures 7a and 7b, comprises an outer air inlet 24 and an outer water outlet 26. The outer air inlet 24 comprises a centrally located circular port. The outer water outlet 26 comprises a plurality of circular ports surrounding the outer air inlet 24. The outer air inlet 24 and the outer water outlet 26 are separate sections of the valve head 22. The inner surface of the valve head comprises positioning threads 19 for engaging the valve cap 11.

The adjustable discharge means 10 is formed by threadably affixing the valve head 22 onto the valve cap 11, thereby engaging the positioning threads 18 and 19. The inner air inlet 12 and the outer air inlet 24 combine to form the air inlet 50, and the inner water outlet 14 and the outer water outlet 26 combine to form the water outlet 52. The air inlet 50 and the water outlet 52 are separate sections of the adjustable discharge means 10. The rate of discharge of the irrigation solution can be changed by using the positioning threads 18 and 19 to rotate the valve head 22 on the valve cap 11. Additionally, a pair of o-rings 38 can be used to form a seal between the valve head 22 and the valve cap 11.

In a further embodiment, a splash guard 28 is attached to the valve head 22, where the splash guard 28 is hemispherical in shape. The splash guard 28 can be covered with a tear away protective cap 34.

In another embodiment, as shown in Figures 10 - 19, the subject invention comprises a contoured squeezable reservoir housing 60 having a wall which forms a reservoir which can contain therein a wound-cleaning material. The reservoir can preferably

hold a liquid solution (*e.g.*, sterile saline) as the wound cleansing solution for irrigating, and thereby remove particles or other contaminants from a wound. The reservoir housing 60 has a mouth or opening 62 which communicates the reservoir to the outside of the housing 60. Disposed over the opening 62 of the reservoir housing 60 is a discharge means 70. The
 5 discharge means 70 comprises a flat disc 72 having plurality ports 74 there through. Each of the ports 74 forms a separate nozzle which allows the contents of the reservoir to pass directly through during use of the subject invention.

In one embodiment, the ports 74 are of a sufficient diameter such that a syringed polypropylene hub can be inserted into the individual ports 74. Additionally, the ports 74 can
 10 be angled, such that the discharged streams intersect above the center of the discharge means 70.

In a preferred embodiment, the discharge means 70 comprises four ports 74. Additionally, to discharge the irrigation solution at appropriate pressure, the diameter of the ports 74 can be less or equal to about 0.04 in.

Disposed over the reservoir housing 60, and removably and threadably attached to the
 15 neck 64 of the reservoir housing 60, can be an end cap 80. The end cap 80 secures the flat disc 72 over the opening 62 in the reservoir housing 60, whereby the groove 76 located on the outer edge of the flat disc 72 engages a flange in the connecting ring 82 on the end cap 80. The end cap 80 further comprises a thin membrane 84, which covers and seals the discharge means 70, protecting the ports 74 and contents of the reservoir from contamination or premature discharge
 20 or leakage. To expose the discharge means 70, the thin membrane 84 is removed. The membrane 84 can be removed by, for example, means of a pull tab 86, which when pulled, peels the thin membrane 84 from the end cap 80, exposing the discharge means 70. Additionally, an o-ring can be used to form a seal between the reservoir neck 64 and the end cap 80.

In a further embodiment, a splash guard 90 is attached to the end cap 80. In one
 25 embodiment, the splash guard 90 is hemi-spherical in shape. Additionally, a protective cap 92 can be removably affixed to the splash guard 90, whereby the protective cap 92 protects the splash guard 90 from contamination. The protective cap 92 is removed by removing the pull seal 94.

In a method of use, the protective cap 92 is first removed from the splash guard 90 by
 30 breaking the pull seal 94, exposing the end cap 80. The discharge means 70 is exposed by pulling the pull tab 86 thereby removing the thin membrane 84 from the end cap 80. The discharge means 70 is directed towards the wound, and the reservoir housing 60 is compressed, discharging the irrigation solution through the discharge means 70. The solution can be discharged at a range of pressures of about 4 - 15 lbs/in², with a preferred pressure of about 7 psi.
 35 High pressures are pressures in excess of about 8 lbs/in².

The irrigation solution used can be water, saline, or a balanced salt solution. The solution is preferably sterile and at the discretion of the user or manufacturer of the irrigation solution can additionally comprise an antibacterial and/or antifungal component. The device can be sterilized by known sterilization techniques, including boiling, autoclaving, gas sterilization and the like, either separately or together with the reservoir housing.

Buffered Ringer's solution or commercially available balanced salt solution (e.g., Tis-U-Sol or Physio-Sol) are physiologically compatible and are commonly used in wound irrigation procedures.

The antiseptic agents most commonly used in wound care at present include:

Povidone-iodine solution (Betadine^{*} preparation)-iodine added to the carrier polyvinylpyrrolidone (PVP), a water-soluble organic complex; this combination is called an iodophor. Standard solutions of Betadine preparation are 10 per cent.

Povidone-iodine surgical scrub (Betadine scrub)-the iodophor PVP-I and an anionic detergent (pH 4.5).

pHisoHex^{*}-an emulsion of an anionic detergent, entsulfon, lanolin cholesterol, petrolatum, and hexachlorophene (pH 5.5).

Hi-Bi-clens^{*}-chlorhexidine gluconate plus a sudsing base (pH 5.1 to 6.5).

Tincture of green soap-potassium oleate, isopropanol, potassium coconut oil, soap.

Dakin's solution 0.2 per cent solution hypochlorite solution.

Hydrogen peroxide-an oxidizing agent.

Benzalkonium chloride (Zephiran)^{*}-a quaternary ammonium compound that works as a cationic surface active agent.

Nonionic surfactants-Pluronic F-68 (Shur-Clens)^{*} and Poloxamer-188 (Pharma Clens)^{*}-agents that have no antimicrobial activity (pH 7.1).

From the description of the device herein above, a method of using the subject device would readily be understood and adaptable by those persons having ordinary skill in the art. The reservoir housing is filled with a desired irrigation solution. The irrigation solution is sterilized before or after filling. The reservoir housing and contents can be stored in a sterile environment, e.g., sterile packaging which is opened immediately prior to use. In a preferred use, the protective shield is removed, then the reservoir housing can be directed towards the wound and squeezed or compressed to expel or discharge the solution in the desired direction, and at the desired pressure to effect irrigation of a wound to remove contaminants or debris. See also the Example, provided below.

It would also be understood that the described discharge means can be packaged separately from the reservoir housing. The discharge means is packaged in a sterile

*Trade-mark

environment. In a preferred use of the embodiment wherein the discharge means is provided separately from the reservoir housing, the cap of a readily available, squeezable irrigation bottle containing a sterile irrigation solution, *e.g.*, normal saline, is replaced with the subject discharge means. The bottle, now having the subject discharge means attached or engaged thereto, can be used as described herein.

Significantly, it is known that more force is required to rid the wound of particles with a small surface area (*e.g.*, bacteria) than to remove particles with a large surface area (*e.g.*, dirt, sand, or vegetation). Minimum recommended volumes of irrigation solution vary, but for a moderately sized potentially contaminated wound, for example a laceration 3-6 cm long and less than 2 cm deep, 200 to 300 ml should be used. Greater volumes, on the order of one to two liters, may be required for larger or heavily contaminated wounds. Irrigation should continue at least until all visible, loose particulate matter has been removed.

Following is an example which illustrates procedures, including the best mode, for practicing the invention. This example should not be construed as limiting. All percentages are by weight and all solvent mixture proportions are by volume unless otherwise noted.

Example 1 — Methods of Wound Irrigation

When a patient presents a wound to a medical or other health care professional skilled in the art, that medical professional assesses the extent of the injury sustained by the patient, including all other life threatening injuries. Appropriate action regarding these life threatening injuries is performed and a history is recorded. All wounds are covered to minimize further contamination until the actual repair process begins.

For examination of the wound, it is assumed that a medical professional would have performed a detailed evaluation of the extent of tissue injury, including but not limited to: anatomical area considerations, depth of the wound, type of injury, *e.g.*, crush injury, puncture wound, bites, missiles, cuts with sharp objects, or the like. Included in this examination would be a determination of the type(s) of contamination, time elapsed between the occurrence of the injury to presentation, gross contamination of a wound, and other medical factors associated with an increase incidence of infection (for example, diabetics, AIDS patients, and chemotherapeutics patients).

The wound and surrounding tissue, at the option of the health care professional, could be anesthetized using topical, local, or general anesthetics before the wound-cleansing method begins.

In one embodiment, the subject device has a discharge means affixed to a reservoir housing as described with a protective shield covering the discharge means. The health care

professional using the subject device would remove the protective shield to expose the discharge means. The subject device can be held in either hand as preferred by the user. Normally, it would be held in the dominate hand in a bottle-holding fashion. This allows the medical care professional to gently open the wound if needed, with the opposite hand, preferably protected
5 by a sterile glove, to expose the depths of the wound.

Once the depths of the wound have been exposed, the end of the reservoir housing having the discharge means affixed thereto is directed towards the wound. Manual or mechanically produced pressure is applied to the reservoir housing to expel the irrigation solution through the nozzles of the discharge means. The wound should be irrigated in this
10 fashion until all visible evidence of contamination has been removed. A potentially contaminated wound of any size should be irrigated with a minimum of 200-300 ml of irrigation solution. Heavily contaminated or larger wounds may require 2-3 liters of irrigation solution. The health care professional could vary the angle of the discharged irrigation solution from the discharge means in reference to the wound to further assist with the dislodgement of
15 contaminants. This variation in the angle will also decrease or increase the amount of back-splash. Thus it would be important to irrigate in a manner that decreases the back-splash. Minimizing back-splash is achieved by irrigation at acute angles to the plane of the wound.

Following an initial irrigation of the wound, a re-examination of the wound should be undertaken. The wound should be explored to its base to ascertain that no visible foreign bodies
20 or contaminants remain. If foreign bodies or contaminants are found, the irrigation process should be repeated followed by a re-examination. This may continue for several cycles.

Once irrigation has been completed, *i.e.*, no visible contaminants remain, the wound would be repaired in a standard accepted fashion.

25 It should be understood that the example and embodiment described herein is for illustrative purposes only and that various modifications or changes in light thereof will be suggested to persons skilled in the art and are to be included within the spirit and purview of this application and the scope of the appended claims.

CLAIMS

1. A wound irrigation device comprising a reservoir housing containing a wound irrigation solution and a discharge means;

wherein said discharge means is removably attached to said reservoir housing such that said discharge means directs a pressurized stream of said wound irrigation solution when said reservoir housing is pressurized;

wherein said discharge means comprises a flat disc;

wherein said flat disc comprises a plurality of ports;

wherein said reservoir housing comprises a threaded neck and an opening;

wherein said flat disc is positioned over said opening;

wherein said flat disc is affixed over said opening with a threaded end cap comprising a connection ring which engages said flat disc such that said ports are uncovered; and

wherein said threaded end cap further comprises a removable protective membrane which protects said ports and said wound irrigation solution from contamination.

2. A wound irrigation device comprising a reservoir housing containing a wound irrigation solution and a discharge means;

wherein said discharge means is removably attached to said reservoir housing such that said discharge means directs a pressurized stream of said wound irrigation solution when said reservoir housing is pressurized;

wherein said discharge means comprises a flat disc;

wherein said flat disc comprises a plurality of ports;

wherein said ports form nozzles that extend beyond the plane of the flat disc;

wherein said reservoir housing comprises a threaded neck and an opening;

wherein said flat disc is positioned over said opening; and

wherein said device further comprises a splash guard.

3. The wound irrigation device according to Claim 1 wherein said plurality of ports discharge a plurality of pressurized streams of the wound irrigation solution at an angle, such that said pressurized streams intersect over a center of said discharge means.

4. The wound irrigation device according to Claim 1, 2 or 3 wherein said discharge means comprises four ports.

5. The wound irrigation device according to Claim 1, 2, 3 or 4 wherein each of said ports has a diameter of about 0.04 inches.
6. The wound irrigation device according to Claim 1 wherein said protective membrane comprises a pull tab, such that said protective membrane is removed by pulling said pull tab.
- 5 7. The wound irrigation device according to Claim 1 further comprising a splash guard.
8. The wound irrigation device according to Claim 7 wherein said splash guard is hemi-spherical.
9. The wound irrigation device according to Claim 8 wherein said splash guard comprises a removable protective cap.
- 10 10. The wound irrigation device according to any one of Claims 1 to 9 wherein said discharge means is an adjustable discharge means, whereby said adjustable discharge means permits adjustment of the rate of discharge of said irrigation solution.
11. The wound irrigation device according to Claim 10 wherein said adjustable discharge means comprises a valve cap and a valve head, wherein said valve cap is removably affixed to said reservoir housing and said valve head is threadably affixed to said valve cap.
- 15 12. The wound irrigation device according to Claim 11 wherein said valve cap comprises an inner air inlet and an inner water outlet, wherein said inner water outlet substantially surrounds said inner air inlet.
13. The wound irrigation device according to Claim 12 wherein said valve head comprises an outer air inlet and an outer water outlet, wherein said outer water outlet substantially surrounds said water air inlet.
- 20 14. The wound irrigation device according to Claim 13 wherein said outer air inlet comprises a circular port.

15. The wound irrigation device according to Claim 13 wherein said outer water outlet comprises a plurality of circular ports.

16. The wound irrigation device according to Claim 13 wherein said inner air inlet and said outer air inlet combine to form an air inlet, and said inner water outlet and said outer water outlet
5 combine to form a water outlet.

17. The wound irrigation device according to Claim 16 further comprising an air hose, wherein said air hose comprises a proximal end and a distal end, wherein said proximal end of said air hose is affixed to said inner air outlet and said distal end of said air hose is located near a bottom inner surface of said reservoir housing.

10 18. The wound irrigation device according to Claim 17 wherein said distal end of said air hose comprises a ball valve.

19. Use of a wound irrigation device according to any one of Claims 1 to 18 to irrigate a wound.

1/19




FIG. 1

2/6




FIG. 2

3/19




FIG. 3

4/19




FIG. 4




FIG. 5

6/19




FIG. 6

7/19

FIG. 7A





FIG. 7B



8/19




FIG. 8

9/19




FIG. 9A

10/19




FIG. 9B

11/19




FIG. 10

12/19




FIG. 11




FIG. 12

14/19




FIG. 14




FIG. 13

15/19




FIG. 15

16/19




FIG.16

17/19




FIG. 17

18/19




FIG. 18

19/19




FIG. 19

