




(86) Date de dépôt PCT/PCT Filing Date: 2007/03/13
(87) Date publication PCT/PCT Publication Date: 2007/09/20
(85) Entrée phase nationale/National Entry: 2008/09/05
(86) N° demande PCT/PCT Application No.: US 2007/006412
(87) N° publication PCT/PCT Publication No.: 2007/106525
(30) Priorité/Priority: 2006/03/13 (US60/782,172)

(51) Cl.Int./Int.Cl. *C07D 211/26* (2006.01),
A61K 31/445 (2006.01), *A61K 31/4523* (2006.01),
A61P 11/00 (2006.01), *A61P 19/02* (2006.01),
A61P 9/14 (2006.01), *C07C 275/26* (2006.01),
C07C 275/28 (2006.01), *C07D 209/08* (2006.01),
C07D 211/58 (2006.01), *C07D 211/96* (2006.01),
C07D 213/40 (2006.01), ...
(71) Demandeurs/Applicants:
THE REGENTS OF THE UNIVERSITY OF CALIFORNIA,
US;
ARETE THERAPEUTICS, US
(72) Inventeurs/Inventors:
HAMMOCK, BRUCE D., US; ...

(54) Titre : INHIBITEURS D'UREE A CONFORMATION RESTREINTE D'EPOXYDE HYDROLASE SOLUBLE
(54) Title: PIPERIDINYL, INDOLYL, PIRINIDYL, MORPHOLINYL AND BENZIMIDAZOLYL UREA DERIVATIVES AS
INHIBITORS OF SOLUBLE EPOXIDE HYDROLASE FOR THE TREATMENT OF HYPERTENSION,
INFLAMMATIONS AND OTHER DISEASES



(57) **Abrégé/Abstract:**

Compounds of the formula (I); wherein R^1 is a member selected from the group consisting of C_1 - C_8 alkyl, aryl C_0 - C_8 alkyl, C_3 - C_{12} cycloalkyl and heterocyclyl, Y^1 is selected from the group consisting of a bond, $C(R^5)_2$, NR^5 and O; Y^2 is selected from the group consisting of a bond, NR^5 and O; each R^2 , R^3 and R^5 is independently selected from the group consisting of H, alkyl and COR^6 ; A is heterocyclyl, optionally substituted with from 1 to 2 R^7 substituents; L is selected from the group consisting of a direct bond, C_1 - C_{12} alkylene, C_1 - C_{12} heteroalkylene, C_3 - C_6 cycloalkylene, arylene, heteroarylene, -CO-, -SO_{in}- and -Se-; R^4 is selected from the group consisting of H, C_1 C_8 alkyl, C_2 - C_6 alkenyl, C_2 - C_6 alkynyl, C_1 - C_8 heteroalkyl, aryl C_0 - C_8 alkyl, C_3 C_{12} cycloalkyl and heterocyclyl, are claimed. The compounds are inhibitors of the soluble epoxide hydrolase (sEH) and useful for the treatment of hypertension, inflammation, adult respiratory distress syndrome; diabetic complications; end stage renal disease; Raynaud syndrome and arthritis.

(51) Cl.Int./Int.Cl. (suite/continued) *C07D 295/20* (2006.01), *C07D 401/06* (2006.01), *C07D 487/18* (2006.01)

(72) Inventeurs(suite)/Inventors(continued): JONES, PAUL D., US; MORISSEAU, CHRISTOPHE, US;
HUANG, HUAZHANG, US; TSAI, HSING-JU, US; GLESS, RICHARD JR., US

(74) Agent: FETHERSTONHAUGH & CO.

(12) INTERNATIONAL APPLICATION PUBLISHED UNDER THE PATENT COOPERATION TREATY (PCT)

(19) World Intellectual Property Organization
International Bureau



(43) International Publication Date
20 September 2007 (20.09.2007)

PCT

(10) International Publication Number
WO 2007/106525 A1

(51) International Patent Classification:

C07D 211/26 (2006.01) *A61K 31/445* (2006.01)
C07D 209/08 (2006.01) *A61K 31/4523* (2006.01)
C07D 211/58 (2006.01) *A61P 9/14* (2006.01)
C07D 211/96 (2006.01) *A61P 11/00* (2006.01)
C07D 213/40 (2006.01) *A61P 19/02* (2006.01)
C07D 401/06 (2006.01) *C07D 487/18* (2006.01)
C07C 275/26 (2006.01) *C07D 295/20* (2006.01)
C07C 275/28 (2006.01)

Richard, Jr. [US/US]; 3912 Trust Way, Hayward, California 94545 (US).

(21) International Application Number:

PCT/US2007/006412

(22) International Filing Date: 13 March 2007 (13.03.2007)

(25) Filing Language: English

(26) Publication Language: English

(30) Priority Data:

60/782,172 13 March 2006 (13.03.2006) US

(71) Applicants (for all designated States except US): **THE REGENTS OF THE UNIVERSITY OF CALIFORNIA** [US/US]; 1111 Franklin Street, 12th Floor, Oakland, California 94607-5200 (US). **ARÊTE THERAPEUTICS** [US/US]; 3912 Trust Way, Hayward, California 94545 (US).

(72) Inventors; and

(75) Inventors/Applicants (for US only): **HAMMOCK, Bruce D.** [US/US]; 3134 Chesapeake Bay Avenue, Davis, California 95616 (US). **JONES, Paul D.** [US/US]; 120 Ravine Drive, Apt. 63B, Matawan, New Jersey 07747 (US). **MORISSEAU, Christophe** [FR/US]; 3376 Bonaire Road, West Sacramento, California 95691 (US). **HUANG, Huazhang** [CN/US]; 520 Alvarado Ave., Apt. 206, Davis, California 95616 (US). **TSAI, Hsing-Ju** [—/US]; 178 La Rue Road, #142, Davis, California 95616 (US). **GLESS,**

(74) Agents: **HOPKINS, Mark H.** et al.; Townsend and Townsend and Crew LLP, Two Embarcadero Center, 8th Floor, San Francisco, CA 94111 (US).

(81) Designated States (unless otherwise indicated, for every kind of national protection available): AE, AG, AL, AM, AT, AU, AZ, BA, BB, BG, BR, BW, BY, BZ, CA, CH, CN, CO, CR, CU, CZ, DE, DK, DM, DZ, EC, EE, EG, ES, FI, GB, GD, GE, GH, GM, GT, HN, HR, HU, ID, IL, IN, IS, JP, KE, KG, KM, KN, KP, KR, KZ, LA, LC, LK, LR, LS, LT, LU, LY, MA, MD, MG, MK, MN, MW, MX, MY, MZ, NA, NG, NI, NO, NZ, OM, PG, PH, PL, PT, RO, RS, RU, SC, SD, SE, SG, SK, SL, SM, SV, SY, TJ, TM, TN, TR, TT, TZ, UA, UG, US, UZ, VC, VN, ZA, ZM, ZW.

(84) Designated States (unless otherwise indicated, for every kind of regional protection available): ARIPO (BW, GH, GM, KE, LS, MW, MZ, NA, SD, SL, SZ, TZ, UG, ZM, ZW), Eurasian (AM, AZ, BY, KG, KZ, MD, RU, TJ, TM), European (AT, BE, BG, CH, CY, CZ, DE, DK, EE, ES, FI, FR, GB, GR, HU, IE, IS, IT, LT, LU, LV, MC, MT, NL, PL, PT, RO, SE, SI, SK, TR), OAPI (BF, BJ, CF, CG, CI, CM, GA, GN, GQ, GW, ML, MR, NE, SN, TD, TG).

Declaration under Rule 4.17:


— of inventorship (Rule 4.17(iv))

Published:

— with international search report
— before the expiration of the time limit for amending the claims and to be republished in the event of receipt of amendments

For two-letter codes and other abbreviations, refer to the "Guidance Notes on Codes and Abbreviations" appearing at the beginning of each regular issue of the PCT Gazette.

(54) Title: PIPERIDINYL, INDOLYL, PIRINIDYL, MORPHOLINYL AND BENZIMIDAZOLYL UREA DERIVATIVES AS INHIBITORS OF SOLUBLE EPOXIDE HYDROLASE FOR THE TREATMENT OF HYPERTENSION, INFLAMMATIONS AND OTHER DISEASES



(57) Abstract: Compounds of the formula (I); wherein R^1 is a member selected from the group consisting of C_1 - C_8 alkyl, aryl C_0 - C_8 alkyl, C_3 - C_{12} cycloalkyl and heterocyclyl, Y^1 is selected from the group consisting of a bond, $\text{C}(\text{R}^5)_2$, NR^5 and O; Y^2 is selected from the group consisting of a bond, NR^5 and O; each R^2 , R^3 and R^5 is independently selected from the group consisting of H, alkyl and COR^6 ; A is heterocyclyl, optionally substituted with from 1 to 2 R^7 substituents; L is selected from the group consisting of a direct bond, C_1 - C_{12} alkylene, C_1 - C_{12} heteroalkylene, C_3 - C_6 cycloalkylene, arylene, heteroarylene, $-\text{CO}-$, $-\text{SO}_{\text{in}}-$ and $-\text{Se}-$; R^4 is selected from the group consisting of H, C_1 - C_8 alkyl, C_2 - C_6 alkenyl, C_2 - C_6 alkynyl, C_1 - C_8 heteroalkyl, aryl C_0 - C_8 alkyl, C_3 - C_{12} cycloalkyl and heterocyclyl, are claimed. The compounds are inhibitors of the soluble epoxide hydrolase (sEH) and useful for the treatment of hypertension, inflammation, adult respiratory distress syndrome; diabetic complications; end stage renal disease; Raynaud syndrome and arthritis.

WO 2007/106525 A1

PIPERIDINYL, INDOLYL, PIRINIDYL, MORPHOLINYL AND BENZIMIDAZOLYL UREA DERIVATIVES AS INHIBITORS OF SOLUBLE EPOXIDE HYDROLASE FOR THE TREATMENT OF HYPERTENSION, INFLAMMATIONS AND OTHER DISEASES.

CROSS-REFERENCES TO RELATED APPLICATIONS

[0001] This application claims the benefit of U.S. Provisional Patent Application No. 60/782,172, filed March 13, 2006, which is incorporated by reference herein in its entirety.

STATEMENT AS TO RIGHTS TO INVENTIONS MADE UNDER FEDERALLY SPONSORED RESEARCH OR DEVELOPMENT

[0002] The U.S. Government has certain rights to the invention pursuant to contract ES02710 & HL078096 awarded by the National Institutes of Health.

BACKGROUND OF THE INVENTION

[0003] Epoxide hydrolases (EHs, EC 3.3.2.3) catalyze the hydrolysis of epoxides or arene oxides to their corresponding diols by the addition of water (see, Oesch, F., et al., *Xenobiotica* **1973**, 3, 305-340). Some EHs play an important role in the metabolism of a variety of compounds including hormones, chemotherapeutic drugs, carcinogens, environmental pollutants, mycotoxins, and other harmful foreign compounds.

[0004] There are two well-studied EHs, microsomal epoxide hydrolase (mEH) and soluble epoxide hydrolase (sEH). These enzymes are very distantly related, have different subcellular localization, and have different but partially overlapping substrate selectivities. The soluble and microsomal EH forms are known to complement each other in degrading some plant natural products (see, Hammock, B.D., et al., *COMPREHENSIVE TOXICOLOGY*. Oxford: Pergamon Press **1977**, 283-305 and Fretland, A.J., et al., *Chem. Biol. Interact* **2000**, 129, 41-59).

[0005] The major role of the sEH is in the metabolism of lipid epoxides including the metabolism of arachidonic acid (see, Zeldin, D.C., et al., *J. Biol. Chem.* **1993**, 268, 6402-6407), linoleic acid (see, Moghaddam, M.F., et al., *Nat. Med.* **1997**, 3, 562-567) acid, some of which are endogenous chemical mediators (see, Carroll, M.A., et al., *Thorax* **2000**, 55, S13-16). Epoxides of arachidonic acid (epoxyeicosatrienoic acids or EETs) and other lipid epoxides and diols are known effectors of blood pressure (see, Capdevila, J.H., et al., *J. Lipid. Res.* **2000**, 41, 163-181), and modulators of vascular permeability (see, Oltman, C.L., et al.,

Circ Res. **1998**, 83, 932-939). The vasodilatory properties of EETs are associated with an increased open-state probability of calcium-activated potassium channels leading to hyperpolarization of the vascular smooth muscle (see Fisslthaler, B., et al., *Nature* **1999**, 401, 493-497). Hydrolysis of the arachidonate epoxides by sEH diminishes this activity (see, Capdevila, J.H., et al., *J. Lipid. Res.* **2000**, 41, 163-181). sEH hydrolysis of EETs also regulates their incorporation into coronary endothelial phospholipids, suggesting a regulation of endothelial function by sEH (see, Weintraub, N.L., et al., *Am. J. Physiol.* **1992**, 277, H2098-2108). It has recently been shown that treatment of spontaneous hypertensive rats (SHRs) with selective sEH inhibitors significantly reduces their blood pressure (see, Yu, Z., et al., *Circ. Res.* **2000**, 87, 992-998). In addition, it was claimed that male knockout sEH mice have significantly lower blood pressure than wild-type mice (see Sinal, C.J., et al., *J. Biol. Chem.* **2000**, 275, 40504-405010), however subsequent studies demonstrated with back breeding into C57b mice that 20-HETE levels increased compensating for the increase in plasma EETs (see, Luria, A. et al., *J. Biol. Chem.* **2007**, 282:2891-2898).

[0006] The EETs have also demonstrated anti-inflammatory properties in endothelial cells (see, Node, K., et al., *Science* **1999**, 285, 1276-1279 and Campbell, W.B. *Trends Pharmacol. Sci.* **2000**, 21, 125-127). In contrast, diols derived from epoxy-linoleate (leukotoxin) perturb membrane permeability and calcium homeostasis (see, Moghaddam, M.F., et al., *Nat. Med.* **1997**, 3, 562-567), which results in inflammation that is modulated by nitric oxide synthase and endothelin-1 (see, Ishizaki, T., et al., *Am. J. Physiol.* **1995**, 269, L65-70 and Ishizaki, T., et al., *J. Appl. Physiol.* **1995**, 79, 1106-1611). Micromolar concentrations of leukotoxin reported in association with inflammation and hypoxia (see, Dudda, A., et al., *Chem. Phys. Lipids* **1996**, 82, 39-51), depress mitochondrial respiration *in vitro* (see, Sakai, T., et al., *Am. J. Physiol.* **1995**, 269, L326-331), and cause mammalian cardiopulmonary toxicity *in vivo* (see, Ishizaki, T., et al., *Am. J. Physiol.* **1995**, 269, L65-70; Fukushima, A., et al., *Cardiovasc. Res.* **1988**, 22, 213-218; and Ishizaki, T., et al., *Am. J. Physiol.* **1995**, 268, L123-128). Leukotoxin toxicity presents symptoms suggestive of multiple organ failure and acute respiratory distress syndrome (ARDS) (see, Ozawa, T. et al., *Am. Rev. Respir. Dis.* **1988**, 137, 535-540). In both cellular and organismal models, leukotoxin-mediated toxicity is dependent upon epoxide hydrolysis (see, Moghaddam, M.F., et al., *Nat. Med.* **1997**, 3, 562-567; Morisseau, C., et al., *Proc. Natl. Acad. Sci. USA* **1999**, 96, 8849-8854; and Zheng, J., et al., *Am. J. Respir. Cell Mol. Biol.* **2001**, 25, 434-438), suggesting a role for sEH in the regulation of inflammation and vascular permeability. The bioactivity of these epoxy-fatty


acids suggests that inhibition of *vicinal*-dihydroxy-lipid biosynthesis may have therapeutic value, making sEH a promising pharmacological target.

[0007] Recently, 1,3-disubstituted ureas, carbamates, and amides have been reported as new potent and stable inhibitors of sEH *See*, U.S. Patent No. 6,150,415. Compounds **192** and **686** are representative structures for this type of inhibitors (**Figure 1**, therein). These compounds are competitive tight-binding inhibitors with nanomolar K_i values that interact stoichiometrically with purified recombinant sEH (see, Morisseau, C., et al., *Proc. Natl. Acad. Sci. USA* **1999**, *96*, 8849-8854). Based on the X-ray crystal structure, the urea inhibitors were shown to establish hydrogen bonds and to form salt bridges between the urea function of the inhibitor and residues of the sEH active site, mimicking features encountered in the reaction coordinate of epoxide ring opening by this enzyme (see, Argiriadi, M.A., et al., *Proc. Natl. Acad. Sci. USA* **1999**, *96*, 10637-10642 and Argiriadi, M.A., et al., *J. Biol. Chem.* **2000**, *275*, 15265-15270). These inhibitors efficiently reduced epoxide hydrolysis in several *in vitro* and *in vivo* models (see, Yu, Z., et al., *Circ. Res.* **2000**, *87*, 992-998; Morisseau, C., et al., *Proc. Natl. Acad. Sci. USA* **1999**, *96*, 8849-8854; and Newman, J.W., et al., *Environ. Health Perspect.* **2001**, *109*, 61-66). Despite the high activity associated with these inhibitors, there exists a need for compounds possessing similar or increased activities, preferably with improved solubility and/or pharmacokinetic properties to facilitate formulation and delivery.

[0008] The present invention provides such compounds along with methods for their use and compositions that contain them.

BRIEF SUMMARY OF THE INVENTION

[0009] In one aspect, the present invention provides a method for inhibiting a soluble epoxide hydrolase, comprising contacting the soluble epoxide hydrolase with an inhibiting amount of a compound having the formula (I):



(I).

[0010] The symbol R^1 is a member selected from the group consisting of C_1 - C_8 alkyl, aryl C_0 - C_8 alkyl, C_3 - C_{12} cycloalkyl and heterocyclyl, each of which is optionally substituted. In

one embodiment, each C₁-C₈alkyl, arylC₀-C₈alkyl, C₃-C₁₂cycloalkyl and heterocyclyl is optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C₁-C₈alkyl, C₁-C₈heteroalkyl, aryl, and heteroaryl; wherein said cyclic portions are monocyclic or polycyclic. In one embodiment, the 1 to 2 substituents are each independently selected from the group consisting of C₁-C₈alkyl and C₁-C₈alkoxy. In one embodiment, the 1 to 2 substituents are each independently selected from the group consisting of C₁-C₈haloalkyl and C₁-C₈haloalkoxy.

[0011] The symbol Y¹ is selected from the group consisting of a bond, C(R⁵)₂, NR⁵ and O.

[0012] The symbol Y² is selected from the group consisting of a bond, NR⁵ and O.

[0013] Each symbol R², R³ and R⁵ is independently selected from the group consisting of H, C₁-C₈alkyl and COR⁶.

[0014] The symbol A is heterocyclyl, optionally substituted with from 1 to 2 R⁷ substituents.

[0015] The symbol L is selected from the group consisting of a direct bond, C₁-C₁₂alkylene, C₁-C₁₂heteroalkylene, C₃-C₆cycloalkylene, arylene, heteroarylene, -CO-, -SO_m- and -Se-.

[0016] The symbol R⁴ is selected from the group consisting of H, C₁-C₈alkyl, C₂-C₆alkenyl, C₂-C₆alkynyl, C₁-C₈heteroalkyl, arylC₀-C₈alkyl, C₃-C₁₂cycloalkyl and heterocyclyl, each of which is optionally substituted. In one embodiment, each C₁-C₈alkyl, C₂-C₆alkenyl, C₂-C₆alkynyl, C₁-C₈heteroalkyl, arylC₀-C₈alkyl, C₃-C₁₂cycloalkyl and heterocyclyl group is optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C₁-C₈alkyl, halo, C₁-C₈heteroalkyl, arylC₀-C₈alkyl, COR⁶, S(O)_mR⁶ and heteroaryl. In one embodiment, R⁴ is selected from the group consisting of C₁-C₈alkyl and C₁-C₈alkoxy. In one embodiment, R⁴ is selected from the group consisting of C₁-C₈haloalkyl and C₁-C₈haloalkoxy.

[0017] Each symbol R⁶ is independently selected from the group consisting of H, C₁-C₈alkyl, OH, C₁-C₈alkoxy and amino.

[0018] Each symbol R⁷ is selected from the group consisting of halo, nitro, C₁-C₈alkyl, C₁-C₈alkylamino, hydroxyC₁-C₈alkyl, haloC₁-C₈alkyl, carboxyl, hydroxyl, C₁-C₈alkoxy, C₁-C₈alkoxyC₁-C₈alkoxy, haloC₁-C₈alkoxy, thioC₁-C₈alkyl, aryl, aryloxy, C₃-C₈cycloalkyl, C₃-

C₈cycloalkyl C₁-C₈alkyl, heteroaryl, arylC₁-C₈alkyl, heteroarylC₁-C₈alkyl, C₂-C₈alkenyl containing 1 to 2 double bonds, C₂-C₈alkynyl containing 1 to 2 triple bonds, C₄-C₈alk(en)(yn)yl groups, cyano, formyl, C₁-C₈alkylcarbonyl, arylcarbonyl, heteroarylcarbonyl, C₁-C₈alkoxycarbonyl, aryloxy carbonyl, aminocarbonyl, C₁-C₈alkylaminocarbonyl, C₁-C₈dialkylaminocarbonyl, arylaminocarbonyl, diarylaminocarbonyl, arylC₁-C₈alkylaminocarbonyl, haloC₁-C₈alkoxy, C₂-C₈alkenyloxy, C₂-C₈alkynyloxy, arylC₁-C₈alkoxy, aminoC₁-C₈alkyl, C₁-C₈alkylaminoC₁-C₈alkyl, C₁-C₈dialkylaminoC₁-C₈alkyl, arylaminoC₁-C₈alkyl, amino, C₁-C₈dialkylamino, arylamino, arylC₁-C₈alkylamino, C₁-C₈alkylcarbonylamino, arylcarbonylamino, azido, mercapto, C₁-C₈alkylthio, arylthio, haloC₁-C₈alkylthio, thiocyano, isothiocyano, C₁-C₈alkylsulfinyl, C₁-C₈alkylsulfonyl, arylsulfinyl, arylsulfonyl, aminosulfonyl, C₁-C₈alkylaminosulfonyl, C₁-C₈dialkylaminosulfonyl and arylaminosulfonyl.

[0019] The subscript n is an integer of 0 to 1.

[0020] The subscript m is an integer of from 0 to 2.

[0021] The compounds include all pharmaceutically acceptable derivatives thereof, such as salts, prodrugs, soft drugs, solvates and hydrates.

[0022] In a related aspect, the present invention provides methods of treating diseases modulated by soluble epoxide hydrolases, the method comprising administering to a subject in need of such treatment an effective amount of a compound having a formula selected from formula (I), above. In one aspect, the effective amount is a therapeutically effective amount.

[0023] In other aspects, the present invention provides methods of reducing renal deterioration in a subject, the method comprising administering to the subject an effective amount of a compound of formula (I), above.

[0024] In a related aspect, the present invention provides methods method for inhibiting progression of nephropathy in a subject, the method comprising administering to the subject an effective amount of a compound of formula (I), above.

[0025] In another aspect, the present invention provides for reducing blood pressure in a subject, the method comprising administering to the subject an effective amount of a compound of formula (I), above.

[0026] In a related aspect, the present invention provides methods of inhibiting the proliferation of vascular smooth muscle cells in a subject, the method comprising administering to the subject an effective amount of a compound of formula (I), above.

[0027] In another aspect, the present invention provides methods of inhibiting the progression of an obstructive pulmonary disease, an interstitial lung disease, or asthma in a subject, the method comprising administering to the subject an effective amount of a compound of formula (I), above. The obstructive pulmonary disease can be, for example, chronic obstructive pulmonary disease ("COPD"), emphysema, or chronic bronchitis. The interstitial lung disease can be, for example, idiopathic pulmonary fibrosis, or one associated with occupational exposure to a dust.

[0028] In yet another aspect, the present invention provides compounds having a formula (I) above, as well as pharmaceutical compositions containing one or more of the subject compounds.

BRIEF DESCRIPTION OF THE DRAWINGS

[0029] **Figure 1.** Pharmacokinetic profile of compounds with piperidine substitutions given as a single oral dose of 0.3 mg/kg.

[0030] **Figure 2.** Pharmacokinetic profile of compounds **1153**, **1155** and **1645**. Compounds were administered orally to canines at 0.3 mg/kg.

[0031] **Figure 3.** Pharmacokinetic profile of compound **1153** following single oral administration 0.1 and 0.3 mg/kg orally.

[0032] **Figure 4.** Pharmacokinetic profile of compound **1153** and other compounds following single oral administration 0.3 mg/kg of canine model.

[0033] **Figure 5.** Exposure of selected compounds as a function of inverse potency.

DETAILED DESCRIPTION OF THE INVENTION

[0034] **Abbreviations and Definitions:**

[0035] "cis-Epoxyeicosatrienoic acids" ("EETs") are biomediators synthesized by cytochrome P450 epoxygenases.

[0036] "Epoxide hydrolases" ("EH;" EC 3.3.2.3) are enzymes in the alpha / beta hydrolase fold family that add water to 3 membered cyclic ethers termed epoxides.

[0037] "Soluble epoxide hydrolase" ("sEH") is an enzyme which in endothelial, smooth muscle and other cell types converts EETs to dihydroxy derivatives called dihydroxyeicosatrienoic acids ("DHETs"). The cloning and sequence of the murine sEH is set forth in Grant et al., *J. Biol. Chem.* 268(23):17628-17633 (1993). The cloning, sequence, and accession numbers of the human sEH sequence are set forth in Beetham et al., *Arch. Biochem. Biophys.* 305(1):197-201 (1993). The amino acid sequence of human sEH is also set forth as SEQ ID NO:2 of U.S. Patent No. 5,445,956; the nucleic acid sequence encoding the human sEH is set forth as nucleotides 42-1703 of SEQ ID NO:1 of that patent. The evolution and nomenclature of the gene is discussed in Beetham et al., *DNA Cell Biol.* 14(1):61-71 (1995). Soluble epoxide hydrolase represents a single highly conserved gene product with over 90% homology between rodent and human (Arand et al., *FEBS Lett.*, 338:251-256 (1994)).

[0038] The terms "treat", "treating" and "treatment" refer to any method of alleviating or abrogating a disease or its attendant symptoms.

[0039] The term "therapeutically effective amount" refers to that amount of the compound being administered sufficient to prevent or decrease the development of one or more of the symptoms of the disease, condition or disorder being treated.

[0040] The term "modulate" refers to the ability of a compound to increase or decrease the function, or activity, of the associated activity (e.g., soluble epoxide hydrolase).

"Modulation", as used herein in its various forms, is meant to include antagonism and partial antagonism of the activity associated with sEH. Inhibitors of sEH are compounds that, e.g., bind to, partially or totally block the enzyme's activity.

[0041] The term "compound" as used herein is intended to encompass not only the specified molecular entity but also its pharmaceutically acceptable, pharmacologically active derivatives, including, but not limited to, salts, prodrug conjugates such as esters and amides, metabolites, hydrates, solvates and the like.

[0042] The term "composition" as used herein is intended to encompass a product comprising the specified ingredients in the specified amounts, as well as any product which results, directly or indirectly, from combination of the specified ingredients in the specified

amounts. By "pharmaceutically acceptable" it is meant the carrier, diluent or excipient must be compatible with the other ingredients of the formulation and not deleterious to the recipient thereof.

[0043] The "subject" is defined herein to include animals such as mammals, including, but not limited to, primates (*e.g.*, humans), cows, sheep, goats, horses, dogs, cats, rabbits, rats, mice and the like. In some embodiments, the subject is a human.

[0044] As used herein, the term "sEH-mediated disease or condition" and the like refers to a disease or condition characterized by less than or greater than normal, sEH activity. A sEH-mediated disease or condition is one in which modulation of sEH results in some effect on the underlying condition or disease (*e.g.*, a sEH inhibitor or antagonist results in some improvement in patient well-being in at least some patients).

[0045] "Parenchyma" refers to the tissue characteristic of an organ, as distinguished from associated connective or supporting tissues.

[0046] "Chronic Obstructive Pulmonary Disease" or "COPD" is also sometimes known as "chronic obstructive airway disease", "chronic obstructive lung disease", and "chronic airways disease." COPD is generally defined as a disorder characterized by reduced maximal expiratory flow and slow forced emptying of the lungs. COPD is considered to encompass two related conditions, emphysema and chronic bronchitis. COPD can be diagnosed by the general practitioner using art recognized techniques, such as the patient's forced vital capacity ("FVC"), the maximum volume of air that can be forcibly expelled after a maximal inhalation. In the offices of general practitioners, the FVC is typically approximated by a 6 second maximal exhalation through a spirometer. The definition, diagnosis and treatment of COPD, emphysema, and chronic bronchitis are well known in the art and discussed in detail by, for example, Honig and Ingram, in *Harrison's Principles of Internal Medicine*, (Fauci et al., Eds.), 14th Ed., 1998, McGraw-Hill, New York, pp. 1451-1460 (hereafter, "*Harrison's Principles of Internal Medicine*").

[0047] "Emphysema" is a disease of the lungs characterized by permanent destructive enlargement of the airspaces distal to the terminal bronchioles without obvious fibrosis.

[0048] "Chronic bronchitis" is a disease of the lungs characterized by chronic bronchial secretions which last for most days of a month, for three months a year, for two years.

[0049] As the names imply, "obstructive pulmonary disease" and "obstructive lung disease" refer to obstructive diseases, as opposed to restrictive diseases. These diseases particularly include COPD, bronchial asthma and small airway disease.

[0050] "Small airway disease." There is a distinct minority of patients whose airflow obstruction is due, solely or predominantly to involvement of the small airways. These are defined as airways less than 2 mm in diameter and correspond to small cartilaginous bronchi, terminal bronchioles and respiratory bronchioles. Small airway disease (SAD) represents luminal obstruction by inflammatory and fibrotic changes that increase airway resistance. The obstruction may be transient or permanent.

[0051] The "interstitial lung diseases (ILDs)" are a group of conditions involving the alveolar walls, perialveolar tissues, and contiguous supporting structures. As discussed on the website of the American Lung Association, the tissue between the air sacs of the lung is the interstitium, and this is the tissue affected by fibrosis in the disease. Persons with the disease have difficulty breathing in because of the stiffness of the lung tissue but, in contrast to persons with obstructive lung disease, have no difficulty breathing out. The definition, diagnosis and treatment of interstitial lung diseases are well known in the art and discussed in detail by, for example, Reynolds, H.Y., in Harrison's Principles of Internal Medicine, *supra*, at pp. 1460-1466. Reynolds notes that, while ILDs have various initiating events, the immunopathological responses of lung tissue are limited and the ILDs therefore have common features.

[0052] "Idiopathic pulmonary fibrosis," or "IPF," is considered the prototype ILD. Although it is idiopathic in that the cause is not known, Reynolds, *supra*, notes that the term refers to a well defined clinical entity.

[0053] "Bronchoalveolar lavage," or "BAL," is a test which permits removal and examination of cells from the lower respiratory tract and is used in humans as a diagnostic procedure for pulmonary disorders such as IPF. In human patients, it is usually performed during bronchoscopy.

[0054] As used herein, the term "alkyl" refers to a saturated hydrocarbon radical which may be straight-chain or branched-chain (for example, ethyl, isopropyl, t-amyl, or 2,5-dimethylhexyl). This definition applies both when the term is used alone and when it is used as part of a compound term, such as "arylalkyl," "alkylamino" and similar terms. In some embodiments, alkyl groups are those containing 1 to 24 carbon atoms. All numerical ranges

in this specification and claims are intended to be inclusive of their upper and lower limits. Additionally, the alkyl and heteroalkyl groups may be attached to other moieties at any position on the alkyl or heteroalkyl radical which would otherwise be occupied by a hydrogen atom (such as, for example, 2-pentyl, 2-methylpent-1-yl and 2-propyloxy). Divalent alkyl groups may be referred to as "alkylene," and divalent heteroalkyl groups may be referred to as "heteroalkylene," such as those groups used as linkers in the present invention. The alkyl, alkylene, and heteroalkylene moieties may also be optionally substituted with halogen atoms, or other groups such as oxo, cyano, nitro, alkyl, alkylamino, carboxyl, hydroxyl, alkoxy, aryloxy, and the like.

[0055] The terms "cycloalkyl" and "cycloalkylene" refer to a saturated hydrocarbon ring and includes bicyclic and polycyclic rings. Similarly, cycloalkyl and cycloalkylene groups having a heteroatom (e.g. N, O or S) in place of a carbon ring atom may be referred to as "heterocycloalkyl" and "heterocycloalkylene," respectively. Examples of cycloalkyl and heterocycloalkyl groups are, for example, cyclohexyl, norbornyl, adamantyl, morpholinyl, thiomorpholinyl, dioxothiomorpholinyl, and the like. The cycloalkyl and heterocycloalkyl moieties may also be optionally substituted with halogen atoms, or other groups such as nitro, alkyl, alkylamino, carboxyl, alkoxy, aryloxy and the like. In some embodiments, cycloalkyl and cycloalkylene moieties are those having 3 to 12 carbon atoms in the ring (e.g., cyclohexyl, cyclooctyl, norbornyl, adamantyl, and the like). In some embodiments, heterocycloalkyl and heterocycloalkylene moieties are those having 1 to 3 hetero atoms in the ring (e.g., morpholinyl, thiomorpholinyl, dioxothiomorpholinyl, piperidinyl and the like). Additionally, the term "(cycloalkyl)alkyl" refers to a group having a cycloalkyl moiety attached to an alkyl moiety. Examples are cyclohexylmethyl, cyclohexylethyl and cyclopentylpropyl.

[0056] The term "alkenyl" as used herein refers to an alkyl group as described above which contains one or more sites of unsaturation that is a double bond. Similarly, the term "alkynyl" as used herein refers to an alkyl group as described above which contains one or more sites of unsaturation that is a triple bond.

[0057] The term "alkoxy" refers to an alkyl radical as described above which also bears an oxygen substituent which is capable of covalent attachment to another hydrocarbon radical (such as, for example, methoxy, ethoxy and t-butoxy).

[0058] The term "aryl" refers to an aromatic carbocyclic substituent which may be a single ring or multiple rings which are fused together, linked covalently or linked to a common group such as an ethylene or methylene moiety. Similarly, aryl groups having a heteroatom (e.g. N, O or S) in place of a carbon ring atom are referred to as "heteroaryl". Examples of aryl and heteroaryl groups are, for example, phenyl, naphthyl, biphenyl, diphenylmethyl, thienyl, pyridyl and quinoxalyl. The aryl and heteroaryl moieties may also be optionally substituted with halogen atoms, or other groups such as nitro, alkyl, alkylamino, carboxyl, alkoxy, phenoxy and the like. Additionally, the aryl and heteroaryl groups may be attached to other moieties at any position on the aryl or heteroaryl radical which would otherwise be occupied by a hydrogen atom (such as, for example, 2-pyridyl, 3-pyridyl and 4-pyridyl). Divalent aryl groups are "arylene", and divalent heteroaryl groups are referred to as "heteroarylene" such as those groups used as linkers in the present invention.

[0059] The terms "arylalkyl" and "alkylaryl", " refer to an aryl radical attached directly to an alkyl group. Likewise, the terms "arylalkenyl" and "aryloxyalkyl" refer to an alkenyl group, or an oxygen which is attached to an alkyl group, respectively. For brevity, aryl as part of a combined term as above, is meant to include heteroaryl as well. The term "aryloxy" refers to an aryl radical as described above which also bears an oxygen substituent which is capable of covalent attachment to another radical (such as, for example, phenoxy, naphthyloxy, and pyridyloxy).

[0060] The terms "halo" or "halogen," by themselves or as part of another substituent, mean, unless otherwise stated, a fluorine, chlorine, bromine, or iodine atom. Additionally, terms such as "haloalkyl," and "haloalkoxy" are meant to include monohaloalkyl(oxy) and polyhaloalkyl(oxy). For example, the term "C₁-C₆ haloalkyl" is mean to include trifluoromethyl, 2,2,2-trifluoroethyl, 4-chlorobutyl, 3-bromopropyl, and the like.

[0061] The term "hetero" as used in a "heteroatom-containing alkyl group" (a "heteroalkyl" group) or a "heteroatom-containing aryl group" (a "heteroaryl" group) refers to a molecule, linkage or substituent in which one or more carbon atoms are replaced with an atom other than carbon, e.g., nitrogen, oxygen, sulfur, phosphorus or silicon, typically nitrogen, oxygen or sulfur or more than one non-carbon atom (e.g., sulfonamide). Similarly, the term "heteroalkyl" refers to an alkyl substituent that is heteroatom-containing, the terms "heterocyclic" "heterocycle" or "heterocyclyl" refer to a cyclic substituent or group that is heteroatom-containing and is either aromatic or non-aromatic. The terms "heteroaryl" and

"heteroaromatic" respectively refer to "aryl" and "aromatic" substituents that are heteroatom-containing, and the like. The terms "heterocyclic" and "heterocyclyl" include the terms "heteroaryl" and "heteroaromatic". In some embodiments, heterocyclic moieties are those having 1 to 3 hetero atoms in the ring. Examples of heteroalkyl groups include alkoxy, alkoxyaryl, alkylsulfanyl-substituted alkyl, N-alkylated amino alkyl, and the like. Examples of heteroaryl substituents include pyrrolyl, pyrrolidinyl, pyridinyl, quinolinyl, indolyl, pyrimidinyl, imidazolyl, 1,2,4-triazolyl, tetrazolyl, etc., and examples of heteroatom-containing cyclic nonaromatic groups are morpholinyl, piperazinyl, piperidinyl, etc.

[0062] The term "carboxylic acid analog" refers to a variety of groups having an acidic moiety that are capable of mimicking a carboxylic acid residue. Examples of such groups are sulfonic acids, sulfinic acids, phosphoric acids, phosphonic acids, phosphinic acids, sulfonamides, and heterocyclic moieties such as, for example, imidazoles, triazoles and tetrazoles.

[0063] The term "substituted" refers to the replacement of an atom or a group of atoms of a compound with another atom or group of atoms. For example, an atom or a group of atoms may be substituted with one or more of the following substituents or groups: halo, nitro, C₁-C₈alkyl, C₁-C₈alkylamino, hydroxyC₁-C₈alkyl, haloC₁-C₈alkyl, carboxyl, hydroxyl, C₁-C₈alkoxy, C₁-C₈alkoxyC₁-C₈alkoxy, thioC₁-C₈alkyl, aryl, aryloxy, C₃-C₈cycloalkyl, C₃-C₈cycloalkyl C₁-C₈alkyl, heteroaryl, arylC₁-C₈alkyl, heteroarylC₁-C₈alkyl, C₂-C₈alkenyl containing 1 to 2 double bonds, C₂-C₈alkynyl containing 1 to 2 triple bonds, C₄-C₈alk(en)(yn)yl groups, cyano, formyl, C₁-C₈alkylcarbonyl, arylcarbonyl, heteroarylcarbonyl, C₁-C₈alkoxycarbonyl, aryloxycarbonyl, aminocarbonyl, C₁-C₈alkylaminocarbonyl, C₁-C₈dialkylaminocarbonyl, arylaminocarbonyl, diarylaminocarbonyl, arylC₁-C₈alkylaminocarbonyl, haloC₁-C₈alkoxy, C₂-C₈alkenyloxy, C₂-C₈alkynyloxy, arylC₁-C₈alkoxy, aminoC₁-C₈alkyl, C₁-C₈alkylaminoC₁-C₈alkyl, C₁-C₈dialkylaminoC₁-C₈alkyl, arylaminoC₁-C₈alkyl, amino, C₁-C₈dialkylamino, arylamino, arylC₁-C₈alkylamino, C₁-C₈alkylcarbonylamino, arylcarbonylamino, azido, mercapto, C₁-C₈alkylthio, arylthio, haloC₁-C₈alkylthio, thioccyano, isothiocyano, C₁-C₈alkylsulfinyl, C₁-C₈alkylsulfonyl, arylsulfinyl, arylsulfonyl, aminosulfonyl, C₁-C₈alkylaminosulfonyl, C₁-C₈dialkylaminosulfonyl and arylaminosulfonyl. When the term "substituted" appears prior to a list of possible substituted groups, it is intended that the term apply to every member of that group.

[0064] The term "unsubstituted" refers to a native compound that lacks replacement of an atom or a group of atoms.

General:

[0065] The present invention derives from the discovery that 1,3-disubstituted ureas (or the corresponding amides or carbamates, also referred to as the primary pharmacophore) can be further functionalized to provide more potent sEH inhibitors with improved physical properties. As described herein, the introduction of a heterocyclic moiety can increase water solubility and oral availability of sEH inhibitors (see below). The combination of these moieties provides a variety of compounds of increased water solubility.


[0066] The discovery of the heterocyclic pharmacophores has also led to the employment of combinatorial chemistry approaches for establishing a wide spectrum of compounds having sEH inhibitory activity. The polar pharmacophores divide the molecule into domains each of which can be easily manipulated by common chemical approaches in a combinatorial manner, leading to the design and confirmation of novel orally available therapeutic agents for the treatment of diseases such as hypertension and vascular inflammation. The agents of the present invention treat such diseases while simultaneously increasing sodium excretion, reducing vascular and renal inflammation, and reducing male erectile dysfunction. As shown below (see Examples and Figures), alterations in solubility, bioavailability and pharmacological properties leads to compounds that can alter the regulatory lipids of experimental animals increasing the relative amounts of epoxy arachidonate derivatives when compared either to their diol products or to the proinflammatory and hypertensive hydroxyeicosatetraenoic acids (HETEs). Since epoxy arachidonates are anti-hypertensive and anti-inflammatory, altering the lipid ratios can lead to reduced blood pressure and reduced vascular and renal inflammation. This approach has been validated as reported in U.S. Patent Application Nos. 10/817,334 and 11/256,685 which are herein incorporated by reference in their entirety.

[0067] The heterocyclic group improves water solubility of sEH inhibitors as well as the specificity for the sEH, and a wide diversity of functionalities such as an ester, amide, carbamate, or similar functionalities capable of donating or accepting a hydrogen bond similarly can contribute to this polar group. For example, in pharmaceutical chemistry

heterocyclic groups are commonly used to mimic carbonyls as hydrogen bond donors and acceptors. Of course the primary, secondary and tertiary pharmacophore groups can be combined in a single molecule with suitable spacers to improve activity or present the inhibitor as a prodrug.

Methods of Inhibiting Soluble Epoxide Hydrolases:

[0068] In view of the above, the present invention provides, in one aspect, a method for inhibiting a soluble epoxide hydrolase, comprising contacting the soluble epoxide hydrolase with an inhibiting amount of a compound having the formula (I):



(I).

[0069] The symbol R^1 is a member selected from the group consisting of C_1 - C_8 alkyl, aryl C_0 - C_8 alkyl, C_3 - C_{12} cycloalkyl and heterocyclyl, each of which is optionally substituted. In one embodiment each C_1 - C_8 alkyl, aryl C_0 - C_8 alkyl, C_3 - C_{12} cycloalkyl and heterocyclyl is optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C_1 - C_8 alkyl, C_1 - C_8 heteroalkyl, aryl, heteroaryl; wherein said cyclic portions are monocyclic or polycyclic. In one embodiment, the 1 to 2 substituents are each independently selected from the group consisting of C_1 - C_8 alkyl and C_1 - C_8 alkoxy. In one embodiment, the 1 to 2 substituents are each independently selected from the group consisting of C_1 - C_8 haloalkyl and C_1 - C_8 haloalkoxy.

[0070] The symbol Y^1 is selected from the group consisting of a bond, $C(R^5)_2$, NR^5 and O.

[0071] The symbol Y^2 is selected from the group consisting of a bond, NR^5 and O.

[0072] Each symbol R^2 , R^3 and R^5 is independently selected from the group consisting of H, C_1 - C_8 alkyl and COR^6 .

[0073] The symbol A is heterocyclyl, optionally substituted with from 1 to 2 R^7 substituents.

[0074] The symbol L is selected from the group consisting of a direct bond, C_1 - C_{12} alkylene, C_1 - C_{12} heteroalkylene, C_3 - C_6 cycloalkylene, arylene, heteroarylene, -CO-, -SO_m- and -Se-.

[0075] The symbol R^4 is selected from the group consisting of H, C_1 - C_8 alkyl, C_2 - C_6 alkenyl, C_2 - C_6 alkynyl, C_1 - C_8 heteroalkyl, aryl C_0 - C_8 alkyl, C_3 - C_{12} cycloalkyl and heterocyclyl, each of

which is optionally substituted. In one embodiment, each C₁-C₈alkyl, C₂-C₆alkenyl, C₂-C₆alkynyl, C₁-C₈heteroalkyl, arylC₀-C₈alkyl, C₃-C₁₂cycloalkyl and heterocyclyl is optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C₁-C₈alkyl, halo, C₁-C₈heteroalkyl, arylC₀-C₈alkyl, COR⁶, S(O)_mR⁶ and heteroaryl. In one embodiment, R⁴ is selected from the group consisting of C₁-C₈alkyl and C₁-C₈alkoxy. In one embodiment, R⁴ is selected from the group consisting of C₁-C₈haloalkyl and C₁-C₈haloalkoxy.

[0076] Each symbol R⁶ is independently selected from the group consisting of H, C₁-C₈alkyl, OH, C₁-C₈alkoxy and amino.

[0077] Each symbol R⁷ is selected from the group consisting of halo, nitro, C₁-C₈alkyl, C₁-C₈alkylamino, hydroxyC₁-C₈alkyl, haloC₁-C₈alkyl, carboxyl, hydroxyl, C₁-C₈alkoxy, C₁-C₈alkoxyC₁-C₈alkoxy, haloC₁-C₈alkoxy, thioC₁-C₈alkyl, aryl, aryloxy, C₃-C₈cycloalkyl, C₃-C₈cycloalkyl C₁-C₈alkyl, heteroaryl, arylC₁-C₈alkyl, heteroarylC₁-C₈alkyl, C₂-C₈alkenyl containing 1 to 2 double bonds, C₂-C₈alkynyl containing 1 to 2 triple bonds, C₄-C₈alk(en)(yn)yl groups, cyano, formyl, C₁-C₈alkylcarbonyl, arylcarbonyl, heteroarylcarbonyl, C₁-C₈alkoxycarbonyl, aryloxycarbonyl, aminocarbonyl, C₁-C₈alkylaminocarbonyl, C₁-C₈dialkylaminocarbonyl, arylaminocarbonyl, diarylaminocarbonyl, arylC₁-C₈alkylaminocarbonyl, haloC₁-C₈alkoxy, C₂-C₈alkenyloxy, C₂-C₈alkynyloxy, arylC₁-C₈alkoxy, aminoC₁-C₈alkyl, C₁-C₈alkylaminoC₁-C₈alkyl, C₁-C₈dialkylaminoC₁-C₈alkyl, arylaminoC₁-C₈alkyl, amino, C₁-C₈dialkylamino, arylamino, arylC₁-C₈alkylamino, C₁-C₈alkylcarbonylamino, arylcarbonylamino, azido, mercapto, C₁-C₈alkylthio, arylthio, haloC₁-C₈alkylthio, thioccyano, isothioccyano, C₁-C₈alkylsulfinyl, C₁-C₈alkylsulfonyl, arylsulfinyl, arylsulfonyl, aminosulfonyl, C₁-C₈alkylaminosulfonyl, C₁-C₈dialkylaminosulfonyl and arylaminosulfonyl.

[0078] The subscript n is an integer of 0 to 1.

[0079] The subscript m is an integer of from 0 to 2.

[0080] The compounds include all pharmaceutically acceptable derivatives thereof, such as salts, prodrugs, solvates and hydrates.


[0081] In other embodiments Y¹ is NR⁵. In further embodiments Y² is a bond. In still further embodiments Y² is NR⁵. In still other embodiments Y² is O.

[0082] In other embodiments Y^2 is NR^5 . In further embodiments Y^1 is a bond. In still other embodiments Y^1 is $C(R^5)_2$. In further embodiments Y^1 is O. In still further embodiments Y^1 is NR^5 .

[0083] In other embodiments R^2 , R^3 and R^5 are H.

[0084] In further embodiments, A is selected from the group consisting of piperidinyl, 1,3,5-triaza-tricyclo[3.3.1.1^{3,7}]decyl, indolyl, pyridyl, morpholinyl and benzimidazolyl. In still other embodiments A is piperidinyl. In other embodiments A is 1,3,5-triaza-tricyclo[3.3.1.1^{3,7}]decyl. In still further embodiments A is indolyl. In other embodiments A is pyridyl. In other embodiments A is morpholinyl. In other embodiments A is benzimidazolyl.

[0085] In still other embodiments the compound has the formula:



wherein R^1 is a member selected from the group consisting of C_1 - C_8 alkyl, aryl C_0 - C_8 alkyl, C_3 - C_{12} cycloalkyl and heterocyclyl, each of which are optionally substituted. In further embodiments, each of C_1 - C_8 alkyl, aryl C_0 - C_8 alkyl, C_3 - C_{12} cycloalkyl and heterocyclyl are optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C_1 - C_8 alkyl, C_1 - C_8 heteroalkyl, aryl, heteroaryl; wherein said cycloalkyl portions are monocyclic or polycyclic.

[0086] Within these embodiments, L is selected from the group consisting of a direct bond, C_1 - C_{12} heteroalkylene, -CO- and -SO_m-; and


R^4 is selected from the group consisting of H, C_1 - C_8 alkyl, aryl C_0 - C_8 alkyl, C_3 - C_{12} cycloalkyl and heterocyclyl, each of which is optionally substituted. In one embodiment, each C_1 - C_8 alkyl, aryl C_0 - C_8 alkyl, C_3 - C_{12} cycloalkyl and heterocyclyl is optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C_1 - C_8 alkyl, halo, C_1 - C_8 heteroalkyl, aryl C_0 - C_8 alkyl, COR⁶, S(O)_mR⁶ and heteroaryl.

[0087] Within these embodiments, each R⁶ is independently selected from the group consisting of H, C_1 - C_8 alkyl, C_1 - C_8 alkoxy and amino;

the subscript n is an integer of 0 to 1; and

the subscript m is an integer of from 0 to 2.

[0088] In other embodiments the compound has the formula:



wherein R¹ is a member selected from the group consisting of C₁-C₈alkyl, arylC₀-C₈alkyl, C₃-C₁₂cycloalkyl and heterocyclyl, each of which is optionally substituted. In one embodiment each C₁-C₈alkyl, arylC₀-C₈alkyl, C₃-C₁₂cycloalkyl and heterocyclyl is optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C₁-C₈alkyl, C₁-C₈heteroalkyl, aryl, heteroaryl; wherein said cycloalkyl portions are monocyclic or polycyclic.

[0089] Within these embodiments, L is selected from the group consisting of a direct bond, C₁-C₁₂heteroalkylene, -CO- and -SO_m-; and


R⁴ is selected from the group consisting of H, C₁-C₈alkyl, arylC₀-C₈alkyl, C₃-C₁₂cycloalkyl and heterocyclyl, each of which is optionally substituted. In one embodiment, each C₁-C₈alkyl, arylC₀-C₈alkyl, C₃-C₁₂cycloalkyl and heterocyclyl is optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C₁-C₈alkyl, halo, C₁-C₈heteroalkyl, arylC₀-C₈alkyl, COR⁶, S(O)_mR⁶ and heteroaryl.

[0090] Within these embodiments, each R⁶ is independently selected from the group consisting of H, C₁-C₈alkyl, C₁-C₈alkoxy and amino;

the subscript n is an integer of 0 to 1; and

the subscript m is an integer of from 0 to 2.

[0091] In other embodiments the compound has the formula:



wherein R¹ is a member selected from the group consisting of C₁-C₈alkyl, arylC₀-C₈alkyl, C₃-C₁₂cycloalkyl and heterocyclyl, each of which is optionally substituted. In one embodiment each C₁-C₈alkyl, arylC₀-C₈alkyl, C₃-C₁₂cycloalkyl and heterocyclyl is optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C₁-

C₈alkyl, C₁-C₈heteroalkyl, aryl, heteroaryl; wherein said cycloalkyl portions are monocyclic or polycyclic.

[0092] Within these embodiments, L is selected from the group consisting of a direct bond, C₁-C₁₂heteroalkylene, -CO- and -SO_m-; and


R⁴ is selected from the group consisting of H, C₁-C₈alkyl, arylC₀-C₈alkyl, C₃-C₁₂cycloalkyl and heterocyclyl, each of which is optionally substituted. In one embodiment, each C₁-C₈alkyl, arylC₀-C₈alkyl, C₃-C₁₂cycloalkyl and heterocyclyl is optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C₁-C₈alkyl, halo, C₁-C₈heteroalkyl, arylC₀-C₈alkyl, COR⁶, S(O)_mR⁶ and heteroaryl.

[0093] Within these embodiments, each R⁶ is independently selected from the group consisting of H, C₁-C₈alkyl, C₁-C₈alkoxy and amino;

the subscript n is an integer of 0 to 1; and

the subscript m is an integer of from 0 to 2.

[0094] In other embodiments the compound has the formula:



wherein R¹ is a member selected from the group consisting of C₁-C₈alkyl, arylC₀-C₈alkyl, C₃-C₁₂cycloalkyl and heterocyclyl, each of which is optionally substituted. In one embodiment each C₁-C₈alkyl, arylC₀-C₈alkyl, C₃-C₁₂cycloalkyl and heterocyclyl is optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C₁-C₈alkyl, C₁-C₈heteroalkyl, aryl, heteroaryl; wherein said cycloalkyl portions are monocyclic or polycyclic.

[0095] Within these embodiments, L is selected from the group consisting of a direct bond, C₁-C₁₂heteroalkylene, -CO- and -SO_m-; and

R⁴ is selected from the group consisting of H, C₁-C₈alkyl, arylC₀-C₈alkyl, C₃-C₁₂cycloalkyl and heterocyclyl, each of which is optionally substituted. In one embodiment, each C₁-C₈alkyl, arylC₀-C₈alkyl, C₃-C₁₂cycloalkyl and heterocyclyl is optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C₁-C₈alkyl, halo, C₁-C₈heteroalkyl, arylC₀-C₈alkyl, COR⁶, S(O)_mR⁶ and heteroaryl. In one embodiment,


R^4 is selected from the group consisting of C_1 - C_8 alkyl and C_1 - C_8 alkoxy. In one embodiment, R^4 is selected from the group consisting of C_1 - C_8 haloalkyl and C_1 - C_8 haloalkoxy.

[0096] Within these embodiments, each R^6 is independently selected from the group consisting of H, C_1 - C_8 alkyl, C_1 - C_8 alkoxy and amino;

the subscript n is an integer of 0 to 1; and

the subscript m is an integer of from 0 to 2.

[0097] In other embodiments the compound has the formula:



wherein R^1 is a member selected from the group consisting of C_1 - C_8 alkyl, aryl C_0 - C_8 alkyl, C_3 - C_{12} cycloalkyl and heterocyclyl, each of which is optionally substituted. In one embodiment each C_1 - C_8 alkyl, aryl C_0 - C_8 alkyl, C_3 - C_{12} cycloalkyl and heterocyclyl is optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C_1 - C_8 alkyl, C_1 - C_8 heteroalkyl, aryl, heteroaryl; wherein said cycloalkyl portions are monocyclic or polycyclic.

[0098] Within these embodiments, L is selected from the group consisting of a direct bond, C_1 - C_{12} heteroalkylene, -CO- and -SO_m-; and


R^4 is selected from the group consisting of H, C_1 - C_8 alkyl, aryl C_0 - C_8 alkyl, C_3 - C_{12} cycloalkyl and heterocyclyl, each of which is optionally substituted. In one embodiment, each C_1 - C_8 alkyl, aryl C_0 - C_8 alkyl, C_3 - C_{12} cycloalkyl and heterocyclyl is optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C_1 - C_8 alkyl, halo, C_1 - C_8 heteroalkyl, aryl C_0 - C_8 alkyl, COR⁶, S(O)_mR⁶ and heteroaryl.

[0099] Within these embodiments, each R^6 is independently selected from the group consisting of H, C_1 - C_8 alkyl, C_1 - C_8 alkoxy and amino;

the subscript n is an integer of 0 to 1; and

the subscript m is an integer of from 0 to 2.

[0100] In other embodiments the compound has the formula:



wherein R^1 is a member selected from the group consisting of C_1 - C_8 alkyl, aryl C_0 - C_8 alkyl, C_3 - C_{12} cycloalkyl and heterocyclyl, each of which is optionally substituted. In one embodiment each C_1 - C_8 alkyl, aryl C_0 - C_8 alkyl, C_3 - C_{12} cycloalkyl and heterocyclyl is optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C_1 - C_8 alkyl, C_1 - C_8 heteroalkyl, aryl, heteroaryl; wherein said cycloalkyl portions are monocyclic or polycyclic.

[0101] Within these embodiments, L is selected from the group consisting of a direct bond, C_1 - C_{12} heteroalkylene, $-\text{CO}-$ and $-\text{SO}_m-$; and


R^4 is selected from the group consisting of H, C_1 - C_8 alkyl, aryl C_0 - C_8 alkyl, C_3 - C_{12} cycloalkyl and heterocyclyl, each of which is optionally substituted. In one embodiment, each C_1 - C_8 alkyl, aryl C_0 - C_8 alkyl, C_3 - C_{12} cycloalkyl and heterocyclyl is optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C_1 - C_8 alkyl, halo, C_1 - C_8 heteroalkyl, aryl C_0 - C_8 alkyl, COR^6 , $\text{S}(\text{O})_m\text{R}^6$ and heteroaryl.

[0102] Within these embodiments, each R^6 is independently selected from the group consisting of H, C_1 - C_8 alkyl, C_1 - C_8 alkoxy and amino;

the subscript n is an integer of 0 to 1; and

the subscript m is an integer of from 0 to 2.

[0103] In other embodiments the compound has the formula:



wherein R^1 is a member selected from the group consisting of C_1 - C_8 alkyl, aryl C_0 - C_8 alkyl, C_3 - C_{12} cycloalkyl and heterocyclyl, each of which is optionally substituted. In one embodiment each C_1 - C_8 alkyl, aryl C_0 - C_8 alkyl, C_3 - C_{12} cycloalkyl and heterocyclyl is optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C_1 - C_8 alkyl, C_1 - C_8 heteroalkyl, aryl, heteroaryl; wherein said cycloalkyl portions are monocyclic or polycyclic.

[0104] Within these embodiments, L is selected from the group consisting of a direct bond, C₁-C₁₂heteroalkylene, -CO- and -SO_m-; and


R⁴ is selected from the group consisting of H, C₁-C₈alkyl, arylC₀-C₈alkyl, C₃-C₁₂cycloalkyl and heterocyclyl, each of which is optionally substituted. In one embodiment, each C₁-C₈alkyl, arylC₀-C₈alkyl, C₃-C₁₂cycloalkyl and heterocyclyl is optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C₁-C₈alkyl, halo, C₁-C₈heteroalkyl, arylC₀-C₈alkyl, COR⁶, S(O)_mR⁶ and heteroaryl.

[0105] Within these embodiments, each R⁶ is independently selected from the group consisting of H, C₁-C₈alkyl, C₁-C₈alkoxy and amino;

the subscript n is an integer of 0 to 1; and

the subscript m is an integer of from 0 to 2.

[0106] In other embodiments the compound has the formula:



wherein R¹ is a member selected from the group consisting of C₁-C₈alkyl, arylC₀-C₈alkyl, C₃-C₁₂cycloalkyl and heterocyclyl, each of which is optionally substituted. In one embodiment each C₁-C₈alkyl, arylC₀-C₈alkyl, C₃-C₁₂cycloalkyl and heterocyclyl is optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C₁-C₈alkyl, C₁-C₈heteroalkyl, aryl, heteroaryl; wherein said cycloalkyl portions are monocyclic or polycyclic.

[0107] Within these embodiments, L is selected from the group consisting of a direct bond, C₁-C₁₂heteroalkylene, -CO- and -SO_m-; and


R⁴ is selected from the group consisting of H, C₁-C₈alkyl, arylC₀-C₈alkyl, C₃-C₁₂cycloalkyl and heterocyclyl, each of which is optionally substituted. In one embodiment, each C₁-C₈alkyl, arylC₀-C₈alkyl, C₃-C₁₂cycloalkyl and heterocyclyl is optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C₁-C₈alkyl, halo, C₁-C₈heteroalkyl, arylC₀-C₈alkyl, COR⁶, S(O)_mR⁶ and heteroaryl.

[0108] Within these embodiments, each R⁶ is independently selected from the group consisting of H, C₁-C₈alkyl, C₁-C₈alkoxy and amino;

the subscript n is an integer of 0 to 1; and

the subscript m is an integer of from 0 to 2.

[0109] In other embodiments the compound has the formula:



wherein R¹ is a member selected from the group consisting of C₁-C₈alkyl, arylC₀-C₈alkyl, C₃-C₁₂cycloalkyl and heterocyclyl, each of which is optionally substituted. In one embodiment each C₁-C₈alkyl, arylC₀-C₈alkyl, C₃-C₁₂cycloalkyl and heterocyclyl is optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C₁-C₈alkyl, C₁-C₈heteroalkyl, aryl, heteroaryl; wherein said cycloalkyl portions are monocyclic or polycyclic.

[0110] Within these embodiments, L is selected from the group consisting of a direct bond, C₁-C₁₂heteroalkylene, -CO- and -SO_m-; and


R⁴ is selected from the group consisting of H, C₁-C₈alkyl, arylC₀-C₈alkyl, C₃-C₁₂cycloalkyl and heterocyclyl, each of which is optionally substituted. In one embodiment, each C₁-C₈alkyl, arylC₀-C₈alkyl, C₃-C₁₂cycloalkyl and heterocyclyl is optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C₁-C₈alkyl, halo, C₁-C₈heteroalkyl, arylC₀-C₈alkyl, COR⁶, S(O)_mR⁶ and heteroaryl.

[0111] Within these embodiments, each R⁶ is independently selected from the group consisting of H, C₁-C₈alkyl, C₁-C₈alkoxy and amino;

the subscript n is an integer of 0 to 1; and

the subscript m is an integer of from 0 to 2.

[0112] In other embodiments the compound has the formula:



wherein R¹ is a member selected from the group consisting of C₁-C₈alkyl, arylC₀-C₈alkyl, C₃-C₁₂cycloalkyl and heterocyclyl, each of which is optionally substituted. In one embodiment each C₁-C₈alkyl, arylC₀-C₈alkyl, C₃-C₁₂cycloalkyl and heterocyclyl is optionally substituted

with from 1 to 2 substituents each independently selected from the group consisting of C₁-C₈alkyl, C₁-C₈heteroalkyl, aryl, heteroaryl; wherein said cycloalkyl portions are monocyclic or polycyclic.

[0113] Within these embodiments, L is selected from the group consisting of a direct bond, C₁-C₁₂heteroalkylene, -CO- and -SO_m-; and


R⁴ is selected from the group consisting of H, C₁-C₈alkyl, arylC₀-C₈alkyl, C₃-C₁₂cycloalkyl and heterocyclyl, each of which is optionally substituted. In one embodiment, each C₁-C₈alkyl, arylC₀-C₈alkyl, C₃-C₁₂cycloalkyl and heterocyclyl is optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C₁-C₈alkyl, halo, C₁-C₈heteroalkyl, arylC₀-C₈alkyl, COR⁶, S(O)_mR⁶ and heteroaryl;

[0114] Within these embodiments, each R⁶ is independently selected from the group consisting of H, C₁-C₈alkyl, C₁-C₈alkoxy and amino;

the subscript n is an integer of 0 to 1; and

the subscript m is an integer of from 0 to 2.

[0115] In other embodiments the compound has the formula:



wherein R¹ is a member selected from the group consisting of C₁-C₈alkyl, arylC₀-C₈alkyl, C₃-C₁₂cycloalkyl and heterocyclyl, each of which is optionally substituted. In one embodiment each C₁-C₈alkyl, arylC₀-C₈alkyl, C₃-C₁₂cycloalkyl and heterocyclyl is optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C₁-C₈alkyl, C₁-C₈heteroalkyl, aryl, heteroaryl; wherein said cycloalkyl portions are monocyclic or polycyclic.

[0116] Within these embodiments, L is selected from the group consisting of a direct bond, C₁-C₁₂heteroalkylene, -CO- and -SO_m-; and


R⁴ is selected from the group consisting of H, C₁-C₈alkyl, arylC₀-C₈alkyl, C₃-C₁₂cycloalkyl and heterocyclyl, each of which is optionally substituted. In one embodiment, each C₁-C₈alkyl, arylC₀-C₈alkyl, C₃-C₁₂cycloalkyl and heterocyclyl is optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C₁-C₈alkyl, halo, C₁-C₈heteroalkyl, arylC₀-C₈alkyl, COR⁶, S(O)_mR⁶ and heteroaryl.

[0117] Within these embodiments, each R^6 is independently selected from the group consisting of H, C_1 - C_8 alkyl, C_1 - C_8 alkoxy and amino;

the subscript n is an integer of 0 to 1; and

the subscript m is an integer of from 0 to 2.

[0118] In other embodiments the compound has the formula:



wherein R^1 is a member selected from the group consisting of C_1 - C_8 alkyl, aryl C_0 - C_8 alkyl, C_3 - C_{12} cycloalkyl and heterocyclyl, each of which is optionally substituted. In one embodiment each C_1 - C_8 alkyl, aryl C_0 - C_8 alkyl, C_3 - C_{12} cycloalkyl and heterocyclyl is optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C_1 - C_8 alkyl, C_1 - C_8 heteroalkyl, aryl, heteroaryl; wherein said cycloalkyl portions are monocyclic or polycyclic.

[0119] Within these embodiments, L is selected from the group consisting of a direct bond, C_1 - C_{12} heteroalkylene, -CO- and -SO_m-; and

R^4 is selected from the group consisting of H, C_1 - C_8 alkyl, aryl C_0 - C_8 alkyl, C_3 - C_{12} cycloalkyl and heterocyclyl, each of which is optionally substituted. In one embodiment, each C_1 - C_8 alkyl, aryl C_0 - C_8 alkyl, C_3 - C_{12} cycloalkyl and heterocyclyl is optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C_1 - C_8 alkyl, halo, C_1 - C_8 heteroalkyl, aryl C_0 - C_8 alkyl, COR⁶, S(O)_mR⁶ and heteroaryl.

[0120] Within these embodiments, each R^6 is independently selected from the group consisting of H, C_1 - C_8 alkyl, C_1 - C_8 alkoxy and amino;

the subscript n is an integer of 0 to 1; and

the subscript m is an integer of from 0 to 2.

[0121] In any of the above embodiments R^1 is C_1 - C_8 alkyl. In any of the above embodiments R^1 is selected from the group consisting of dodecyl and t-butyl. In any of the above embodiments R^1 is aryl C_0 - C_8 alkyl. In any of the above embodiments R^1 is phenyl. In any of the above embodiments R^1 is C_3 - C_{12} cycloalkyl. In any of the above embodiments R^1 is adamantyl. In any of the above embodiments R^1 is cycloheptyl or cyclohexyl. In any of

the above embodiments R^1 is C_3 - C_{12} cycloalkyl. In any of the above embodiments R^1 is adamantyl. In any of the above embodiments R^1 is cycloheptyl. In any of the above embodiments of R^1 , the group is optionally substituted. In any of the above embodiments, the R^1 group is optionally substituted with from 1 to 2 substituents. In any of the above embodiments the 1 to 2 substituents are each independently selected from the group consisting of C_1 - C_8 alkyl and C_1 - C_8 alkoxy. In any of the above embodiments embodiment, the 1 to 2 substituents are each independently selected from the group consisting of C_1 - C_8 haloalkyl and C_1 - C_8 haloalkoxy.

[0122] In any of the above embodiments L is a direct bond. In any of the above embodiments L is C_1 - C_{12} heteroalkylene. In any of the above embodiments L is -CO-. In any of the above embodiments L is -SO₂-.

[0123] In any of the above embodiments R^4 is selected from the group consisting of H, C_1 - C_8 alkyl, aryl C_0 - C_8 alkyl, C_1 - C_8 alkoxy and heterocyclyl. In any of the above embodiments, R^4 is selected from the group consisting of C_1 - C_8 haloalkyl and C_1 - C_8 haloalkoxy.

[0124] In any of the above embodiments R^6 is H. In any of the above embodiments R^6 is C_1 - C_8 alkyl.

[0125] In any of the above embodiments n is 0. In any of the above embodiments n is 1.

[0126] In other embodiments, the compound is selected from the group consisting of the compounds of Examples 1-70 and Tables 1-4 and 5a and 5b.

[0127] In any of the above embodiments the compounds include all pharmaceutically acceptable derivatives thereof, such as salts, prodrugs, solvates and hydrates.

Assays to Monitor Soluble Epoxide Hydrolase Activity:

[0128] Additionally, the present invention provides a variety of assays and associated methods for monitoring soluble epoxide hydrolase activity, particularly the activity that has been modulated by the administration of one or more of the compounds provided above.

[0129] In one group of embodiments, the invention provides methods for reducing the formation of a biologically active diol produced by the action of a soluble epoxide hydrolase, the method comprising contacting the soluble epoxide hydrolase with an amount of a

compound of formula (I) above, sufficient to inhibit the activity of the soluble epoxide hydrolase and reduce the formation of the biologically active diol.

[0130] In another group of embodiments, the invention provides methods for stabilizing biologically active epoxides in the presence of a soluble epoxide hydrolase, the method comprising contacting the soluble epoxide hydrolase with an amount of a compound of formula (I), sufficient to inhibit the activity of the soluble epoxide hydrolase and stabilize the biologically active epoxide.

[0131] In each of these groups of embodiments, the methods can be carried out as part of an *in vitro* assay or the methods can be carried out *in vivo* by monitoring blood titers of the respective biologically active epoxide or diol.

[0132] Epoxides and diols of some fatty acids are biologically important chemical mediators and are involved in several biological processes. The strongest biological data support the action of oxylipins as chemical mediators between the vascular endothelium and vascular smooth muscle. Epoxy lipids are anti-inflammatory and anti-hypertensive. Additionally, the lipids are thought to be metabolized by beta-oxidation, as well as by epoxide hydration. The soluble epoxide hydrolase is considered to be the major enzyme involved in the hydrolytic metabolism of these oxylipins. The compounds of formula (I) can inhibit the epoxide hydrolase and stabilize the epoxy lipids both *in vitro* and *in vivo*. This activity results in a reduction of hypertension in four separate rodent models. Moreover, the inhibitors show a reduction in renal inflammation associated with and independent of the hypertensive models.

[0133] More particularly, the present invention provides methods for monitoring a variety of lipids in both the arachidonate and linoleate cascade simultaneously in order to address the biology of the system. A GLC-MS system or a LC-MS method can be used to monitor over 740 analytes in a highly quantitative fashion in a single injection. The analytes include the regioisomers of the arachidonate epoxides (EETs), the diols (DHETs), as well as other P450 products including HETEs. Characteristic products of the cyclooxygenase, lipoxygenase, and peroxidase pathways in both the arachidonate and linoleate series can also be monitored. Such methods are particularly useful as being predictive of certain disease states. The oxylipins can be monitored in mammals following the administration of inhibitors of epoxide hydrolase. Generally, EH inhibitors increase epoxy lipid concentrations at the expense of diol concentrations in body fluids and tissues.

[0134] Other compounds for use in this aspect of the invention are those inhibitors of formula (I) in which the primary pharmacophore is separated from a secondary and/or tertiary pharmacophore by a distance that approximates the distance between the terminal carboxylic acid and an epoxide functional group in the natural substrate.

Methods of Treating Diseases Modulated by Soluble Epoxide Hydrolases:

[0135] In another aspect, the present invention provides methods of treating diseases, especially those modulated by soluble epoxide hydrolases (sEH). The methods generally involve administering to a subject in need of such treatment an effective amount of a compound having a formula (I) above. The dose, frequency and timing of such administering will depend in large part on the selected therapeutic agent, the nature of the condition being treated, the condition of the subject including age, weight and presence of other conditions or disorders, the formulation being administered and the discretion of the attending physician. Preferably, the compositions and compounds of the invention and the pharmaceutically acceptable salts thereof are administered *via* oral, parenteral, subcutaneous, intramuscular, intravenous or topical routes. Generally, the compounds are administered in dosages ranging from about 2 mg up to about 2,000 mg per day, although variations will necessarily occur depending, as noted above, on the disease target, the patient, and the route of administration. Dosages are administered orally in the range of about 0.05 mg/kg to about 20 mg/kg, more preferably in the range of about 0.05 mg/kg to about 2 mg/kg, most preferably in the range of about 0.05 mg/kg to about 0.2 mg per kg of body weight per day. The dosage employed for the topical administration will, of course, depend on the size of the area being treated.

[0136] It has previously been shown that inhibitors of soluble epoxide hydrolase ("sEH") can reduce hypertension. *See, e.g.*, U.S. Patent No. 6,351,506. Such inhibitors can be useful in controlling the blood pressure of persons with undesirably high blood pressure, including those who suffer from diabetes.

[0137] In some embodiments, compounds of formula (I) are administered to a subject in need of treatment for hypertension, specifically renal, hepatic, or pulmonary hypertension; inflammation, specifically renal inflammation, vascular inflammation, and lung inflammation; adult respiratory distress syndrome; diabetic complications; end stage renal disease; Raynaud syndrome and arthritis.

Methods for Inhibiting Progression of Kidney Deterioration (Nephropathy) and Reducing Blood Pressure:

[0138] In another aspect of the invention, the compounds of the invention can reduce damage to the kidney, and especially damage to kidneys from diabetes, as measured by albuminuria. The compounds of the invention can reduce kidney deterioration (nephropathy) from diabetes even in individuals who do not have high blood pressure. The conditions of therapeutic administration are as described above.

[0139] *cis*-Epoxyeicosatrienoic acids ("EETs") can be used in conjunction with the compounds of the invention to further reduce kidney damage. EETs, which are epoxides of arachidonic acid, are known to be effectors of blood pressure, regulators of inflammation, and modulators of vascular permeability. Hydrolysis of the epoxides by sEH diminishes this activity. Inhibition of sEH raises the level of EETs since the rate at which the EETs are hydrolyzed into DHETs is reduced. Without wishing to be bound by theory, it is believed that raising the level of EETs interferes with damage to kidney cells by the microvasculature changes and other pathologic effects of diabetic hyperglycemia. Therefore, raising the EET level in the kidney is believed to protect the kidney from progression from microalbuminuria to end stage renal disease.

[0140] EETs are well known in the art. EETs useful in the methods of the present invention include 14,15-EET, 8,9-EET and 11,12-EET, and 5,6 EETs, in that order of preference. Preferably, the EETs are administered as the methyl ester, which is more stable. Persons of skill will recognize that the EETs are regioisomers, such as 8S,9R- and 14R,15S-EET. 8,9-EET, 11,12-EET, and 14R,15S-EET, are commercially available from, for example, Sigma-Aldrich (catalog nos. E5516, E5641, and E5766, respectively, Sigma-Aldrich Corp., St. Louis, MO).

[0141] EETs produced by the endothelium have anti-hypertensive properties and the EETs 11,12-EET and 14,15-EET may be endothelium-derived hyperpolarizing factors (EDHFs). Additionally, EETs such as 11,12-EET have profibrinolytic effects, anti-inflammatory actions and inhibit smooth muscle cell proliferation and migration. In the context of the present invention, these favorable properties are believed to protect the vasculature and organs during renal and cardiovascular disease states.

[0142] It is now believed that sEH activity can be inhibited sufficiently to increase the levels of EETs and thus augment the effects of administering sEH inhibitors by themselves. This permits EETs to be used in conjunction with one or more sEH inhibitors to reduce nephropathy in the methods of the invention. It further permits EETs to be used in conjunction with one or more sEH inhibitors to reduce hypertension, or inflammation, or both. Thus, medicaments of EETs can be made which can be administered in conjunction with one or more sEH inhibitors, or a medicament containing one or more sEH inhibitors can optionally contain one or more EETs.

[0143] The EETs can be administered concurrently with the sEH inhibitor, or following administration of the sEH inhibitor. It is understood that, like all drugs, inhibitors have half lives defined by the rate at which they are metabolized by or excreted from the body, and that the inhibitor will have a period following administration during which it will be present in amounts sufficient to be effective. If EETs are administered after the inhibitor is administered, therefore, it is desirable that the EETs be administered during the period during which the inhibitor will be present in amounts to be effective to delay hydrolysis of the EETs. Typically, the EET or EETs will be administered within 48 hours of administering an sEH inhibitor. Preferably, the EET or EETs are administered within 24 hours of the inhibitor, and even more preferably within 12 hours. In increasing order of desirability, the EET or EETs are administered within 10, 8, 6, 4, 2, hours, 1 hour, or one half hour after administration of the inhibitor. Most preferably, the EET or EETs are administered concurrently with the inhibitor.

[0144] In some embodiments, the EETs, the compound of the invention, or both, are provided in a material that permits them to be released over time to provide a longer duration of action. Slow release coatings are well known in the pharmaceutical art; the choice of the particular slow release coating is not critical to the practice of the present invention.

[0145] EETs are subject to degradation under acidic conditions. Thus, if the EETs are to be administered orally, it is desirable that they are protected from degradation in the stomach. Conveniently, EETs for oral administration may be coated to permit them to pass the acidic environment of the stomach into the basic environment of the intestines. Such coatings are well known in the art. For example, aspirin coated with so-called "enteric coatings" is widely available commercially. Such enteric coatings may be used to protect

EETs during passage through the stomach. An exemplary coating is set forth in the Examples.

[0146] While the anti-hypertensive effects of EETs have been recognized, EETs have not been administered to treat hypertension because it was thought endogenous sEH would hydrolyse the EETs too quickly for them to have any useful effect. Surprisingly, it was found during the course of the studies underlying the present invention that exogenously administered inhibitors of sEH succeeded in inhibiting sEH sufficiently that levels of EETs could be further raised by the administration of exogenous EETs. These findings underlie the co-administration of sEH inhibitors and of EETs described above with respect to inhibiting the development and progression of nephropathy. This is an important improvement in augmenting treatment. While levels of endogenous EETs are expected to rise with the inhibition of sEH activity caused by the action of the sEH inhibitor, and therefore to result in at least some improvement in symptoms or pathology, it may not be sufficient in all cases to inhibit progression of kidney damage fully or to the extent intended. This is particularly true where the diseases or other factors have reduced the endogenous concentrations of EETs below those normally present in healthy individuals. Administration of exogenous EETs in conjunction with a sEH inhibitor is therefore expected to be beneficial and to augment the effects of the sEH inhibitor in reducing the progression of diabetic nephropathy.

[0147] The present invention can be used with regard to any and all forms of diabetes to the extent that they are associated with progressive damage to the kidney or kidney function. The chronic hyperglycemia of diabetes is associated with long-term damage, dysfunction, and failure of various organs, especially the eyes, kidneys, nerves, heart, and blood vessels. The long-term complications of diabetes include retinopathy with potential loss of vision; nephropathy leading to renal failure; peripheral neuropathy with risk of foot ulcers, amputation, and Charcot joints.

[0148] In addition, persons with metabolic syndrome are at high risk of progression to type 2 diabetes, and therefore at higher risk than average for diabetic nephropathy. It is therefore desirable to monitor such individuals for microalbuminuria, and to administer a sEH inhibitor and, optionally, one or more EETs, as an intervention to reduce the development of nephropathy. The practitioner may wait until microalbuminuria is seen before beginning the intervention. As noted above, a person can be diagnosed with metabolic syndrome without having a blood pressure of 130/85 or higher. Both persons with blood pressure of 130/85 or

higher and persons with blood pressure below 130/85 can benefit from the administration of sEH inhibitors and, optionally, of one or more EETs, to slow the progression of damage to their kidneys. In some embodiments, the person has metabolic syndrome and blood pressure below 130/85.

[0149] Dyslipidemia or disorders of lipid metabolism is another risk factor for heart disease. Such disorders include an increased level of LDL cholesterol, a reduced level of HDL cholesterol, and an increased level of triglycerides. An increased level of serum cholesterol, and especially of LDL cholesterol, is associated with an increased risk of heart disease. The kidneys are also damaged by such high levels. It is believed that high levels of triglycerides are associated with kidney damage. In particular, levels of cholesterol over 200 mg/dL, and especially levels over 225 mg/dL, would suggest that sEH inhibitors and, optionally, EETs, should be administered. Similarly, triglyceride levels of more than 215 mg/dL, and especially of 250 mg/dL or higher, would indicate that administration of sEH inhibitors and, optionally, of EETs, would be desirable. The administration of compounds of the present invention with or without the EETs, can reduce the need to administer statin drugs (HMG-CoA reductase inhibitors) to the patients, or reduce the amount of the statins needed. In some embodiments, candidates for the methods, uses and compositions of the invention have triglyceride levels over 215 mg/dL and blood pressure below 130/85. In some embodiments, the candidates have triglyceride levels over 250 mg/dL and blood pressure below 130/85. In some embodiments, candidates for the methods, uses and compositions of the invention have cholesterol levels over 200 mg/dL and blood pressure below 130/85. In some embodiments, the candidates have cholesterol levels over 225 mg/dL and blood pressure below 130/85.

Methods of Inhibiting the Proliferation of Vascular Smooth Muscle Cells:

[0150] In other embodiments, compounds of formula (I) inhibit proliferation of vascular smooth muscle (VSM) cells without significant cell toxicity, (*e.g.*, specific to VSM cells). Because VSM cell proliferation is an integral process in the pathophysiology of atherosclerosis, these compounds are suitable for slowing or inhibiting atherosclerosis. These compounds are useful to subjects at risk for atherosclerosis, such as individuals who have had a heart attack or a test result showing decreased blood circulation to the heart. The conditions of therapeutic administration are as described above.

[0151] The methods of the invention are particularly useful for patients who have had percutaneous intervention, such as angioplasty to reopen a narrowed artery, to reduce or to slow the narrowing of the reopened passage by restenosis. In some embodiments, the artery is a coronary artery. The compounds of the invention can be placed on stents in polymeric coatings to provide a controlled localized release to reduce restenosis. Polymer compositions for implantable medical devices, such as stents, and methods for embedding agents in the polymer for controlled release, are known in the art and taught, for example, in U.S. Patent Nos. 6,335,029; 6,322,847; 6,299,604; 6,290,722; 6,287,285; and 5,637,113. In some embodiments, the coating releases the inhibitor over a period of time, preferably over a period of days, weeks, or months. The particular polymer or other coating chosen is not a critical part of the present invention.

[0152] The methods of the invention are useful for slowing or inhibiting the stenosis or restenosis of natural and synthetic vascular grafts. As noted above in connection with stents, desirably, the synthetic vascular graft comprises a material which releases a compound of the invention over time to slow or inhibit VSM proliferation and the consequent stenosis of the graft. Hemodialysis grafts are a particular embodiment.

[0153] In addition to these uses, the methods of the invention can be used to slow or to inhibit stenosis or restenosis of blood vessels of persons who have had a heart attack, or whose test results indicate that they are at risk of a heart attack.

[0154] In one group of embodiments, compounds of the invention are administered to reduce proliferation of VSM cells in persons who do not have hypertension. In another group of embodiments, compounds of the invention are used to reduce proliferation of VSM cells in persons who are being treated for hypertension, but with an agent that is not an sEH inhibitor.

[0155] The compounds of the invention can be used to interfere with the proliferation of cells which exhibit inappropriate cell cycle regulation. In one important set of embodiments, the cells are cells of a cancer. The proliferation of such cells can be slowed or inhibited by contacting the cells with a compound of the invention. The determination of whether a particular compound of the invention can slow or inhibit the proliferation of cells of any particular type of cancer can be determined using assays routine in the art.

[0156] In addition to the use of the compounds of the invention, the levels of EETs can be raised by adding EETs. VSM cells contacted with both an EET and a compound of the invention exhibited slower proliferation than cells exposed to either the EET alone or to the a

compound of the invention alone. Accordingly, if desired, the slowing or inhibition of VSM cells of a compound of the invention can be enhanced by adding an EET along with a compound of the invention. In the case of stents or vascular grafts, for example, this can conveniently be accomplished by embedding the EET in a coating along with a compound of the invention so that both are released once the stent or graft is in position.

Methods of Inhibiting the Progression of Obstructive Pulmonary Disease, Interstitial Lung Disease, or Asthma:

[0157] Chronic obstructive pulmonary disease, or COPD, encompasses two conditions, emphysema and chronic bronchitis, which relate to damage caused to the lung by air pollution, chronic exposure to chemicals, and tobacco smoke. Emphysema as a disease relates to damage to the alveoli of the lung, which results in loss of the separation between alveoli and a consequent reduction in the overall surface area available for gas exchange. Chronic bronchitis relates to irritation of the bronchioles, resulting in excess production of mucin, and the consequent blocking by mucin of the airways leading to the alveoli. While persons with emphysema do not necessarily have chronic bronchitis or vice versa, it is common for persons with one of the conditions to also have the other, as well as other lung disorders.

[0158] Some of the damage to the lungs due to COPD, emphysema, chronic bronchitis, and other obstructive lung disorders can be inhibited or reversed by administering inhibitors of the enzyme known as soluble epoxide hydrolase, or "sEH". The effects of sEH inhibitors can be increased by also administering EETs. The effect is at least additive over administering the two agents separately, and may indeed be synergistic.

[0159] The studies reported herein show that EETs can be used in conjunction with sEH inhibitors to reduce damage to the lungs by tobacco smoke or, by extension, by occupational or environmental irritants. These findings indicate that the co-administration of sEH inhibitors and of EETs can be used to inhibit or slow the development or progression of COPD, emphysema, chronic bronchitis, or other chronic obstructive lung diseases which cause irritation to the lungs.

[0160] Animal models of COPD and humans with COPD have elevated levels of immunomodulatory lymphocytes and neutrophils. Neutrophils release agents that cause

tissue damage and, if not regulated, will over time have a destructive effect. Without wishing to be bound by theory, it is believed that reducing levels of neutrophils reduces tissue damage contributing to obstructive lung diseases such as COPD, emphysema, and chronic bronchitis. Administration of sEH inhibitors to rats in an animal model of COPD resulted in a reduction in the number of neutrophils found in the lungs. Administration of EETs in addition to the sEH inhibitors also reduced neutrophil levels. The reduction in neutrophil levels in the presence of sEH inhibitor and EETs was greater than in the presence of the sEH inhibitor alone.

[0161] While levels of endogenous EETs are expected to rise with the inhibition of sEH activity caused by the action of the sEH inhibitor, and therefore to result in at least some improvement in symptoms or pathology, it may not be sufficient in all cases to inhibit progression of COPD or other pulmonary diseases. This is particularly true where the diseases or other factors have reduced the endogenous concentrations of EETs below those normally present in healthy individuals. Administration of exogenous EETs in conjunction with an sEH inhibitor is therefore expected to augment the effects of the sEH inhibitor in inhibiting or reducing the progression of COPD or other pulmonary diseases.

[0162] In addition to inhibiting or reducing the progression of chronic obstructive airway conditions, the invention also provides new ways of reducing the severity or progression of chronic restrictive airway diseases. While obstructive airway diseases tend to result from the destruction of the lung parenchyma, and especially of the alveoli, restrictive diseases tend to arise from the deposition of excess collagen in the parenchyma. These restrictive diseases are commonly referred to as "interstitial lung diseases", or "ILDs", and include conditions such as idiopathic pulmonary fibrosis. The methods, compositions and uses of the invention are useful for reducing the severity or progression of ILDs, such as idiopathic pulmonary fibrosis. Macrophages play a significant role in stimulating interstitial cells, particularly fibroblasts, to lay down collagen. Without wishing to be bound by theory, it is believed that neutrophils are involved in activating macrophages, and that the reduction of neutrophil levels found in the studies reported herein demonstrate that the methods and uses of the invention will also be applicable to reducing the severity and progression of ILDs.

[0163] In some embodiments, the ILD is idiopathic pulmonary fibrosis. In other embodiments, the ILD is one associated with an occupational or environmental exposure. Exemplars of such ILDs, are asbestosis, silicosis, coal worker's pneumoconiosis, and

berylliosis. Further, occupational exposure to any of a number of inorganic dusts and organic dusts is believed to be associated with mucus hypersecretion and respiratory disease, including cement dust, coke oven emissions, mica, rock dusts, cotton dust, and grain dust (for a more complete list of occupational dusts associated with these conditions, see Table 254-1 of Speizer, "Environmental Lung Diseases," Harrison's Principles of Internal Medicine, *infra*, at pp. 1429-1436). In other embodiments, the ILD is sarcoidosis of the lungs. ILDs can also result from radiation in medical treatment, particularly for breast cancer, and from connective tissue or collagen diseases such as rheumatoid arthritis and systemic sclerosis. It is believed that the methods, uses and compositions of the invention can be useful in each of these interstitial lung diseases.

[0164] In another set of embodiments, the invention is used to reduce the severity or progression of asthma. Asthma typically results in mucin hypersecretion, resulting in partial airway obstruction. Additionally, irritation of the airway results in the release of mediators which result in airway obstruction. While the lymphocytes and other immunomodulatory cells recruited to the lungs in asthma may differ from those recruited as a result of COPD or an ILD, it is expected that the invention will reduce the influx of immunomodulatory cells, such as neutrophils and eosinophils, and ameliorate the extent of obstruction. Thus, it is expected that the administration of sEH inhibitors, and the administration of sEH inhibitors in combination with EETs, will be useful in reducing airway obstruction due to asthma.

[0165] In each of these diseases and conditions, it is believed that at least some of the damage to the lungs is due to agents released by neutrophils which infiltrate into the lungs. The presence of neutrophils in the airways is thus indicative of continuing damage from the disease or condition, while a reduction in the number of neutrophils is indicative of reduced damage or disease progression. Thus, a reduction in the number of neutrophils in the airways in the presence of an agent is a marker that the agent is reducing damage due to the disease or condition, and is slowing the further development of the disease or condition. The number of neutrophils present in the lungs can be determined by, for example, bronchoalveolar lavage.

Prophylactic and therapeutic methods to reduce stroke damage

[0166] Inhibitors of soluble epoxide hydrolase ("sEH") and EETs administered in conjunction with inhibitors of sEH have been shown to reduce brain damage from strokes. Based on these results, we expect that inhibitors of sEH taken prior to an ischemic stroke will

reduce the area of brain damage and will likely reduce the consequent degree of impairment. The reduced area of damage should also be associated with a faster recovery from the effects of the stroke.

[0167] While the pathophysiologies of different subtypes of stroke differ, they all cause brain damage. Hemorrhagic stroke differs from ischemic stroke in that the damage is largely due to compression of tissue as blood builds up in the confined space within the skull after a blood vessel ruptures, whereas in ischemic stroke, the damage is largely due to loss of oxygen supply to tissues downstream of the blockage of a blood vessel by a clot. Ischemic strokes are divided into thrombotic strokes, in which a clot blocks a blood vessel in the brain, and embolic strokes, in which a clot formed elsewhere in the body is carried through the blood stream and blocks a vessel there. But, in both hemorrhagic stroke and ischemic stroke, the damage is due to the death of brain cells. Based on the results observed in our studies, however, we would expect at least some reduction in brain damage in all types of stroke and in all subtypes.

[0168] A number of factors are associated with an increased risk of stroke. Given the results of the studies underlying the present invention, sEH inhibitors administered to persons with any one or more of the following conditions or risk factors: high blood pressure, tobacco use, diabetes, carotid artery disease, peripheral artery disease, atrial fibrillation, transient ischemic attacks (TIAs), blood disorders such as high red blood cell counts and sickle cell disease, high blood cholesterol, obesity, alcohol use of more than one drink a day for women or two drinks a day for men, use of cocaine, a family history of stroke, a previous stroke or heart attack, or being elderly, will reduce the area of brain damaged of a stroke. With respect to being elderly, the risk of stroke increases for every 10 years. Thus, as an individual reaches 60, 70, or 80, administration of sEH inhibitors has an increasingly larger potential benefit. As noted in the next section, the administration of EETs in combination with one or more sEH inhibitors can be beneficial in further reducing the brain damage. One can expect beneficial effects from sEHI with or without EETs in a variety of diseases which lead to ischemia reperfusion injury such as heart attacks.

[0169] In some uses and methods, the sEH inhibitors and, optionally, EETs, are administered to persons who use tobacco, have carotid artery disease, have peripheral artery disease, have atrial fibrillation, have had one or more transient ischemic attacks (TIAs), have a blood disorder such as a high red blood cell count or sickle cell disease, have high blood

cholesterol, are obese, use alcohol in excess of one drink a day if a woman or two drinks a day if a man, use cocaine, have a family history of stroke, have had a previous stroke or heart attack and do not have high blood pressure or diabetes, or are 60, 70, or 80 years of age or more and do not have hypertension or diabetes.

[0170] Clot dissolving agents, such as tissue plasminogen activator (tPA), have been shown to reduce the extent of damage from ischemic strokes if administered in the hours shortly after a stroke. tPA, for example, is approved by the FDA for use in the first three hours after a stroke. Thus, at least some of the brain damage from a stroke is not instantaneous, but occurs over a period of time or after a period of time has elapsed after the stroke. It is therefore believed that administration of sEH inhibitors, optionally with EETs, can also reduce brain damage if administered within 6 hours after a stroke has occurred, more preferably within 5, 4, 3, or 2 hours after a stroke has occurred, with each successive shorter interval being more preferable. Even more preferably, the inhibitor or inhibitors are administered 2 hours or less or even 1 hour or less after the stroke, to maximize the reduction in brain damage. Persons of skill are well aware of how to make a diagnosis of whether or not a patient has had a stroke. Such determinations are typically made in hospital emergency rooms, following standard differential diagnosis protocols and imaging procedures.

[0171] In some uses and methods, the sEH inhibitors and, optionally, EETs, are administered to persons who have had a stroke within the last 6 hours who: use tobacco, have carotid artery disease, have peripheral artery disease, have atrial fibrillation, have had one or more transient ischemic attacks (TIAs), have a blood disorder such as a high red blood cell count or sickle cell disease, have high blood cholesterol, are obese, use alcohol in excess of one drink a day if a woman or two drinks a day if a man, use cocaine, have a family history of stroke, have had a previous stroke or heart attack and do not have high blood pressure or diabetes, or are 60, 70, or 80 years of age or more and do not have hypertension or diabetes.

[0172] The conditions of therapeutic administration for all of these indications are as described above.

Combination Therapy

[0173] As noted above, the compounds of the present invention will, in some instances, be used in combination with other therapeutic agents to bring about a desired effect. Selection

of additional agents will, in large part, depend on the desired target therapy (*see, e.g.*, Turner, N. *et al. Prog. Drug Res.* (1998) 51: 33-94; Haffner, S. *Diabetes Care* (1998) 21: 160-178; and DeFronzo, R. *et al.* (eds.), *Diabetes Reviews* (1997) Vol. 5 No. 4). A number of studies have investigated the benefits of combination therapies with oral agents (*see, e.g.*, Mahler, R., *J. Clin. Endocrinol. Metab.* (1999) 84: 1165-71; United Kingdom Prospective Diabetes Study Group: UKPDS 28, *Diabetes Care* (1998) 21: 87-92; Bardin, C. W., (ed.), *Current Therapy In Endocrinology And Metabolism*, 6th Edition (Mosby - Year Book, Inc., St. Louis, MO 1997); Chiasson, J. *et al.*, *Ann. Intern. Med.* (1994) 121: 928-935; Coniff, R. *et al.*, *Clin. Ther.* (1997) 19: 16-26; Coniff, R. *et al.*, *Am. J. Med.* (1995) 98: 443-451; and Iwamoto, Y. *et al.*, *Diabet. Med.* (1996) 13 365-370; Kwiterovich, P. *Am. J. Cardiol* (1998) 82(12A): 3U-17U). Combination therapy includes administration of a single pharmaceutical dosage formulation which contains a compound having the general structure of formula 1 and one or more additional active agents, as well as administration of a compound of formula 1 and each active agent in its own separate pharmaceutical dosage formulation. For example, a compound of formula 1 and one or more angiotensin receptor blockers, angiotensin converting enzyme inhibitors, calcium channel blockers, diuretics, alpha blockers, beta blockers, centrally acting agents, vasopeptidase inhibitors, renin inhibitors, endothelin receptor agonists, AGE crosslink breakers, sodium/potassium ATPase inhibitors, endothelin receptor agonists, endothelin receptor antagonists, angiotensin vaccine, and the like; can be administered to the human subject together in a single oral dosage composition, such as a tablet or capsule, or each agent can be administered in separate oral dosage formulations. Where separate dosage formulations are used, a compound of formula 1 and one or more additional active agents can be administered at essentially the same time (i.e., concurrently), or at separately staggered times (i.e., sequentially). Combination therapy is understood to include all these regimens.

Compounds for Inhibiting Soluble Epoxide Hydrolases:

[0174] In addition to the methods provided above, the present invention provides in another aspect, compounds that can inhibit the activity of soluble epoxide hydrolases. In particular, the present invention provides compounds having a formula selected from formula (I) above.

[0175] In one embodiment, compounds are those compounds described above as for the recited uses.

[0176] In one embodiment, sEH inhibitors for treating hypertension or high blood pressure have an IC_{50} in a defined assay of less than 50 μM . In another embodiment, the compounds have an IC_{50} of 1 μM or less. In another embodiment, the compounds have an IC_{50} of 500 nM or less. In another embodiment, the compounds have an IC_{50} of 150 nM or less. In another embodiment, the compounds have an IC_{50} of 100 nM or less. In another embodiment, the compounds have an IC_{50} of 50 nM or less. In another embodiment, the compounds have an IC_{50} of 1 nM or less.


Methods of Preparation

[0177] The compounds of the present invention can be prepared by a variety of methods as outlined generally in the scheme below. It should be noted that the synthetic conditions illustrated in the following scheme are also applicable to those inhibitors based on 4-aminomethylpiperidine (those with a CH_2 spacer).

Scheme 1 - Introduction of a heterocyclic pharmacophore

[0178] Scheme 1 illustrates general methods that can be used for preparation of compounds of the invention having heterocyclic secondary pharmacophore, for example a piperidine. While the scheme is provided for the synthesis of N-(1-benzoylpiperidin-4-yl)-N'-(adamant-1-yl)ureas, one of skill in the art will understand that a number of commercially available or synthetic heterocyclic amines could be used in place of 4-aminopiperidine, and that other substituents other than benzoyl could also be employed.

Scheme 1: Synthesis of N-(1-benzoylpiperidin-4-yl)-N'-(adamant-1-yl)ureas.



[0179] As shown in Scheme 1, 4-aminopiperidine (available from Aldrich Chemical Co., Milwaukee, Wisconsin, USA) is combined with benzaldehyde at room temperature to provide intermediate (i). BOC protection of the piperidine nitrogen provides intermediate carbamate (ii). Reaction of (ii) with a suitable isocyanate provides intermediate (iii). Deprotection of the piperidine (iv) and reaction with a suitable alkylating or acylating agent provides the target compounds. Substitution of adamantyl isocyanate with, for example, a substituted or unsubstituted phenyl isocyanate or cycloalkyl isocyanate (e.g. cyclohexyl isocyanate, also available from Aldrich Chemical Co.) provides other compounds of the invention.

[0180] The following examples are provided to illustrate the invention and are not intended to limit any aspect of the invention as set forth above or in the claims below.

EXAMPLES

[0181] All melting points were determined with a Thomas-Hoover apparatus (A.H. Thomas Co.) and are uncorrected. Compounds with no melting point values exist in the solid state as either foams or glassy solids. Mass spectra were measured by LC-MS (Waters 2790). ¹H-NMR spectra were recorded on QE-300 spectrometer, using tetramethylsilane as an internal standard. Signal multiplicities are represented as singlet (s), doublet (d), double doublet (dd),

triplet (t), quartet (q), quintet (quint), multiplet (m), broad (br), broad singlet (brs), broad doublet (br d), broad triplet (br t), broad multiplet (br m), doublet of doublet of doublets (ddd) and quartet of doublets (qd). Synthetic methods are described for representative compounds.


[0182] The abbreviations used in the examples below have the following meaning: melting point (Mp), mass spectroscopy (MS), thin layer chromatography (TLC), the parent peak in the MS plus H^+ ($[M+H]^+$), minute (min), kilogram (kg), milligram (mg), nanomolar (nM), tetrahydrofuran (THF), tertiary butoxy carbonyl (BOC), potassium sulfate ($KHSO_4$), potassium hydroxide (KOH), magnesium sulfate ($MgSO_4$), hydrogen chloride (HCl), dimethylsulfoxide (DMSO), ethyl (Et), ethyl acetate (EtOAc), methanol (MeOH), dichloromethane (CH_2Cl_2 , DCM), area under the concentration (AUC).

[0183] Lower case bolded Roman numerals in the examples below refer to the corresponding intermediates in Scheme 1 above. Compounds numbers are also used as provided in the Schemes as well as in the Tables below.

Example 1


[0184] 4-Aminopiperidine (2.125 g, 21.2 mmol) was dissolved in toluene (50 mL). To this was added benzaldehyde (2.16 mL, 21.2 mmol). The reaction fitted with a Dean-Stark trap and a condenser and was refluxed for 4 hours under an atmosphere of nitrogen. At this point, when no additional water was seen to form, the reaction was cooled to 0 °C and BOC anhydride (4.63g, 21.2 mmol) was added via syringe over 10 minutes. The reaction was allowed to warm to room temperature over 1 hr and was stirred for an additional 12 hrs. The solvent was removed *in vacuo* and the resulting oil was treated with $KHSO_4(aq)$ (1 M, 21.2 mL). This was stirred for 1.5 hours. Water (25 mL) was added to the reaction and the aqueous suspension was washed with diethylether (3x 100 mL). The water layer was then basified to pH = 10 with KOH (s) and was extracted with dichloromethane (3 x 100 mL). The organic layer was dried over $MgSO_4$ and evaporated to give 4.76 g of a yellow oil. To this oil (1.0 g) was added THF (25 mL). This was stirred for 5 minutes until the oil was completely dissolved. 1-Adamantylisocyanate (0.886 mg, 5.0 mmol, 1eq) was added and the reaction stirred overnight under an atmosphere of nitrogen. The solvent was removed and the residue was chromatographed on silica with 1:1 ethylacetate:hexanes. The major fraction was collected (TLC r_f = 0.8 1:1 hexane:EtOAc) and the solvent removed. The resultant residue was treated with a solution of HCl in methanol (35 mL, 4M). This was stirred for 12 hours.

The solvent was removed to give the product, after drying at 80°C under vacuum, as a white powder (1.123 g, 73% yield overall).



N-(piperidin-4-yl)-*N'*-(adamant-1-yl) urea hydrochloride (**iv**, **1175**)

[0185] ¹H (300MHz, DMSO d₆): 8.96 (br 2H), 6.22 (br, 6H, urea NH + H₂O), 3.61 – 3.52 (m, 1H), 3.24 – 3.10 (m, 2H), 2.95 – 2.80 (m, 2H), 2.10 – 1.70 (br m, 11H), 1.70 – 1.40 (br m, 8H).




N-((piperidin-4-yl)methyl)-*N'*-(adamant-1-yl)urea hydrochloride (**1118**)

[0186] This was run as per above with a yield of 95%. Mp. (free base): 199-201 °C dec. ¹H NMR (300 MHz, DMSO): 8.79 (br, 1H), 8.50 (br, 1H), 6.00 (br, 1H), 5.80 (br, 1H), 3.20 (br d, *J* = 12.3 Hz, 2H), 2.80 – 2.70 (br m, 3H), 2.00 – 1.40 (br m, 19H), 1.30 – 1.15 (br m, 2H).

Example 2


General procedure for the alkylation of piperidiny ureas: *N*-(1-ethylpiperidin-4-yl)-*N'*-(adamant-1-yl) urea (R=Et, **1152**)



[0187] The appropriate piperdiny urea (0.319 mmol) was combined with the appropriate alkyl or benzyl bromide (X=Br) (0.382 mmol) and K₂CO₃ (132 mg, 0.96 mmol) in DMF (3.0 mL). The reaction was heated at 50°C for 12 hours. At this point, the reaction was cooled to

room temperature and the solvent was removed in vacuo. The residue was partitioned between DCM and aqueous NaHCO₃ (satd) and the organic layer removed and dried with Na₂SO₄. The solvent was evaporated and the residue chromatographed on silica gel using ammonia saturated methanol /DCM as the eluent (5:100). Yield = 42%. Mp.: 203-213 °C dec. ¹H NMR (300 MHz, CDCl₃): 4.15 – 4.05 (br, 2H), 3.63 – 3.47 (m, 1H), 2.91-2.81 (br m, 2H), 2.39 (q, *J* = 7.18 Hz, 2H), 2.13 – 1.88 (br m, 13H), 1.66 (br, 6H), 1.40 (qd, *J* = 8.3, 3.3Hz, 2H), 1.07 (t, *J* = 7.19 Hz, 3H).


Example 3



N-(1-*n*-propylpiperidin-4-yl)-*N'*-(adamant-1-yl) urea (**1155**)

[0188] Yield = 60%. Mp.: 195-200 °C dec. ¹H (300 MHz, CDCl₃): 4.10 – 4.00 (br, 2H), 3.60 – 3.45 (m, 1H), 2.90 – 2.78 (m, 2H), 2.32 – 2.22 (m, 2H), 2.10 – 1.70 (m, 13H), 1.70 – 1.57 (br, 6H), 1.56 – 1.30 (m, 4H), 0.88 (t, *J* = 7.4 Hz, 3H).


Example 4



N-(1-*n*-butylpiperidin-4-yl)-*N'*-(adamant-1-yl) urea (**1160**)

[0189] Yield = 53%. Mp.: 195-200 °C dec. ¹H (300 MHz, CDCl₃): 4.05 – 3.95 (br, 2H), 3.51 – 3.45 (m, 1H), 2.90 – 2.80 (m, 2H), 2.35 – 2.25 (m, 2H), 2.10 – 1.60 (br m, 19H), 1.50 – 1.25 (m, 6H), 0.89 (t, *J* = 7.2 Hz, 3H).


Example 5



N-(1-benzylpiperidin-4-yl)-*N'*-(adamant-1-yl) urea (**1158**)

[0190] Yield = 46%. Mp.: 170-173 °C. ¹H (300 MHz, CDCl₃): 7.35 – 7.20 (m, 5H), 4.00 – 3.94 (br, 2H), 3.58 – 3.45 (m, 1H), 3.43 (s, 2H), 2.80 – 2.72 (m, 2H), 2.10 – 1.60 (br m, 19H), 1.35 (qd, *J* = 7.9, 3.3 Hz, 2H).


Example 6



N-((1-ethylpiperidin-4-yl)methyl)-N'-(adamant-1-yl)urea (1154)

[0191] Yield = 50%. Mp.: 143-151 °C dec. ¹H (300 MHz, CDCl₃): 4.28 (t, *J* = 5.4 Hz, 1H), 4.09 (br, 1H), 3.05 (t, *J* = 6.2 Hz, 2H), 2.98 – 2.89 (br m, 2H), 2.38 (q, *J* = 7.4 Hz, 2H), 2.10 – 1.60 (br m, 19H), 1.52 – 1.40 (br m, 1H), 1.27 (qd, *J* = 12.4, 3.7 Hz, 2H), 1.08 (t, *J* = 7.2 Hz, 3H).


Example 7



N-((1-n-propylpiperidin-4-yl)methyl)-N'-(adamant-1-yl)urea (1122)


[0192] Yield = 40%. ¹H (300 MHz, CDCl₃): 4.69 (t, *J* = 5.8 Hz, 1H), 4.38 (br, 1H), 3.08 – 2.94 (m, 4H), 2.42 – 2.32 (m, 2H), 2.10 – 1.55 (br m, 22H), 1.36 (qd, *J* = 11.8, 3.3 Hz, 2H), 0.89 (t, *J* = 7.4 Hz, 3H).

Example 8



N-((1-n-butylpiperidin-4-yl)methyl)-N'-(adamant-1-yl)urea (1161)


[0193] Yield = 43%. ¹H (300 MHz, CDCl₃): 4.30 (br, 1H), 4.12 (br, 1H), 3.05 (t, *J* = 6.2 Hz, 2H), 2.98-2.88 (m, 2H), 2.34 – 2.26 (m, 2H), 2.10 – 1.2 (br m, 26H), 0.09 (t, *J* = 7.2 Hz, 3H).

Example 9*N-((1-benzylpiperidin-4-yl)methyl)-N'-(adamant-1-yl)urea (1119)*

[0194] Yield = 48%. Mp.: 162-167 °C. ¹H (300 MHz, CDCl₃): 7.35 – 7.20 (m, 5H), 4.37 (br t, *J* = 5.8 Hz, 1H), 4.17 (br, 1H), 3.48 (s, 2H), 2.99 (t, *J* = 6.2 Hz, 2H), 2.95 – 2.80 (br m, 2H), 2.10 – 1.40 (br m, 20H), 1.27 (qd, *J* = 11.9, 3.5 Hz, 2H).

Example 10A

General procedure for the acylation of piperidines:

N-(1-acetylpiperidin-4-yl)-N'-(adamant-1-yl) urea (1153)

[0195] The desired piperidinyl urea (6.6 mmol) and an appropriate carboxylic acid (or ester-acid) (7.92 mmol), DMAP (0.805 g, 6.6 mmol) and TEA (5.0 mL, 36 mmol) were all combined in dichloromethane at 0°C. The reaction was allowed to stir for 10 minutes. At this point, EDCI (1.38 g, 7.26 mmol) was added and the reaction was allowed to warm to rt over 2 hours. After reaching room temperature, the reaction was allowed to stir for 18 hrs. The reaction was then washed with K₂CO_{3(aq)} (1M, 3 x 50 mL) followed by HCl_(aq) (1M, 3 x 50 mL). The organic layer was dried and evaporated to give a yellow oil. Recrystallization from acetone or chromatography (SiO₂) with 5% MeOH/DCM afforded the product. Yield = 75%. Mp.: 205-206 °C. ¹H (300 MHz, CDCl₃): 4.67 (br d, *J* = 6.9 Hz, 1H), 4.57 (br s, 1H), 4.44 (br d, *J* = 13.1 Hz, 1H), 3.90 – 3.65 (m, 2H), 3.13 (br t, *J* = 13.1 Hz, 1H), 2.74 (br t, *J* = 13.2 Hz, 1H), 2.20 – 1.50 (br m, 20H), 1.30 – 1.10 (m, 2H).

Example 10B*[0196] Alternative synthesis of N-(1-Acetylpiperidin-4-yl)-N'-(adamant-1-yl) urea (1153)*

Preparation of N-Acetyl piperid-4-yl amide


[0197] A reactor was charged with 1.00 mole-equivalent of 4-piperidinecarboxamide, 15.9 mole-equivalents of THF, and 1.23 mole-equivalents of N, N-(diisopropyl)ethylamine under a nitrogen atmosphere. The resulting mixture was cooled to 20°C internal, and 1.10 mole-equivalents of acetic anhydride was added at such a rate as to maintain an internal temperature of less than 30°C. After addition was complete, the reaction mixture was stirred while maintaining an internal temperature of 20°C. The reaction contents was monitored until the amount of unreacted 4-piperidinecarboxamide was less than 1% relative to N-acetyl piperid-4-yl amide product (typically about 4 – 10 hours). The precipitated product was collected by filtration and washed with THF to remove excess (diisopropyl)ethylamine hydrochloride. The solid product was dried to constant weight in a vacuum oven under a nitrogen bleed while maintaining an internal temperature of ≤50°C to afford the product as a white solid in 94% yield. ; Mp.: 172-174°C. ¹H NMR(CD₃OD) δ: 4.48-4.58 (bd, 1H), 3.92-4.01 (bd, 1H), 3.08-3.22 (m, 1H), 2.62-2.74 (m, 1H), 2.44-2.53 (m, 1H), 2.12 (s, 3H), 1.88-1.93 (m, 2H), 1.45-1.72 (m, 2H); MS: 171 [M+H]⁺.

Preparation of N-(1-Acetylpiperidin-4-yl)-N'-(adamant-1-yl) urea

[0198] A reactor was charged with 1.00 mole-equivalents of N-acetyl piperid-4-yl amide, 0.87 mole-equivalents of 1-adamantyl amine, and 49.7 mole-equivalents of acetonitrile, and the resulting mixture was heated to 75°C internal under a nitrogen atmosphere. (Diacetoxyiodo)benzene (1.00 mole-equivalents) was charged portionwise in such a way that the reaction mixture was maintained between 75 - 80°C internal. After the (diacetoxyiodo)benzene was added, the reaction mixture was heated to 80°C internal. The reaction contents was monitored until the amount of unreacted 1-adamantyl amine was less than 5% relative to product N-(1-acetylpiperidin-4-yl)-N'-(adamant-1-yl) urea (typically about 1 - 6 hours). After completion, the reaction mixture was cooled to 25°C internal, and approximately 24 mole-equivalents of solvent was distilled out under vacuum while maintaining internal temperature below 40°C. The reaction mixture was cooled with agitation to 0 - 5°C internal and stirred for an additional 2 hours. The technical product was collected by filtration and washed with acetonitrile. The crude product was dried to constant weight in a vacuum oven under a nitrogen bleed maintaining an internal temperature of ≤50°C. The dried, crude product was slurried with water maintaining an internal temperature

of $20 \pm 5^\circ\text{C}$ internal for 4 hours and then collected by filtration. The filter cake was washed with heptane under a nitrogen atmosphere then dried to constant weight in a vacuum oven under a nitrogen bleed maintaining an internal temperature of $\leq 70^\circ\text{C}$ to afford product as a white solid in 72% yield based on 1-adamantyl amine. ^1H NMR(DMSO- d_6) δ : 5.65-5.70 (bd, 1H), 5.41 (s, 1H), 4.02-4.10 (m, 1H), 3.61-3.70, (m, 1H), 3.46-3.58 (m, 1H), 3.04-3.23 (m, 1H), 2.70-2.78 (m, 1H), 1.98 (s, 3H), 1.84 (s, 6H), 1.64-1.82 (m, 2H), 1.59 (s, 6H), 1.13-1.25 (m, 1H), 1.00-1.12 (m, 1H); MS: 320 $[\text{M}+\text{H}]^+$; m.p.202-204 $^\circ\text{C}$.


Example 11



N-(1-propionylpiperidin-4-yl)-*N'*-(adamant-1-yl)urea (1163)


[0199] Made by treating 1 eq of the piperidine with 1 eq of propanoyl chloride in pyridine ([starting material] = 0.10 M) at 0°C for 12 hrs. After removal of the solvent, the product was chromatographed on silica gel with 90:1 DCM: MeOH/ NH_3 to give to target in 20% yield. Mp.: 211-224 $^\circ\text{C}$ dec. ^1H (300 MHz, CDCl_3): 4.52 (br d, $J = 12.6$ Hz, 1H), 4.40 – 4.00 (br, 2H), 3.90 – 3.70 (m, 2H), 3.10 (br t, $J = 12.4$ Hz, 1H), 2.75 (br t, $J = 12.5$ Hz, 1H), 2.34 (q, $J = 7.4$ Hz, 2H), 2.10 – 1.60 (br m, 17H), 1.30 – 1.15 (m, 2H), 1.13 (t, $J = 7.3$ Hz, 3H).

Example 12




N-(1-butyrylpiperidin-4-yl)-*N'*-(adamant-1-yl)urea (1157)


[0200] Synthesized as per 1163. Yield: 71%. Mp.: 148-188 $^\circ\text{C}$ dec. ^1H NMR (300 MHz, CDCl_3): 4.52 (br d, $J = 13.3$, 1H), 4.25 – 4.10 (br, 2H), 3.85 – 3.65 (br, 2H), 3.10 (br t, $J = 11.5$ Hz, 1H), 2.75 (br t, $J = 11.3$ Hz, 1H), 2.35 – 2.23 (m, 2H), 2.10 – 1.60 (br m, 19H), 1.30 – 1.15 (m, 2H), 0.96 (t, $J = 7.4$ Hz, 3H).

Example 13*N*-(1-benzoylpiperidin-4-yl)-*N'*-(adamant-1-yl)urea (**1159**)


[0201] Yield = 63% (via acyl chloride). ^1H (300 MHz, CDCl_3): 7.44 – 7.32 (m, 5H), 5.00 – 4.50 (br m, 3H), 3.90–3.78 (br, 1H), 3.76 – 3.60 (br, 1H), 3.20 – 2.90 (br, 2H), 2.10 – 1.60 (br m, 17H), 1.50 – 1.20 (br m, 2H).

Example 14*N*-(1-(pyridine-2-carbonyl)piperidin-4-yl)-*N'*-(adamant-1-yl)urea (**1201**)


[0202] Yield = 70% via EDCI coupling (see **1153**). ^1H (300 MHz, CDCl_3): 8.59 (br d, J = 5.0 Hz, 1H), 7.80 (td, J = 7.7, 1.7 Hz, 1H), 7.56 (br d, J = 7.6 Hz, 1H), 7.35 (ddd, J = 7.6, 4.8, 1.2 Hz, 1H), 4.70 – 4.50 (br m, 3H), 3.90 – 3.70 (m, 2H), 3.15 (br t, J = 12.5 Hz, 1H), 2.95 (br t, J = 12.3 Hz, 1H), 2.10 – 1.60 (br m, 17H), 1.50 – 1.20 (br m, 2H).

*N*-(1-(pyridine-3-carbonyl)piperidin-4-yl)-*N'*-(adamant-1-yl)urea (**1434**)


[0203] Yield = 86% via EDCI coupling. ^1H (300 MHz, CDCl_3): 8.67 (br d, J = 5.0 Hz, 1H), 8.65 (br, 1H), 7.74 (br d, J = 8.0 Hz, 1H), 7.38 (dd, J = 7.9, 5.0 Hz, 1H), 4.67 – 4.23 (br m, 3H), 3.94 – 3.70 (m, 1H), 3.70 – 3.55 (br, 1H), 3.20 – 2.90 (br m, 2H), 2.10 – 1.60 (br m, 17H), 1.50 – 1.20 (br m, 2H).

Example 15*N*-(1-(pyridine-4-carbonyl)piperidin-4-yl)-*N'*-(adamant-1-yl)urea (1433)


[0204] Yield = 81% via EDCI coupling. Mp 197-199 °C. ¹H (300 MHz, CDCl₃): 8.70 (m, 2H), 7.26 (m, 2H), 4.60 (br d, *J* = 14.2 Hz, 1H), 4.40 (d, *J* = 7.6 Hz, 1H), 4.31 (s, 1H), 3.90 – 3.70 (m, 1H), 3.57 (br d, *J* = 14.0 Hz, 1H), 3.13 (br t, *J* = 12.3 Hz, 1H), 2.95 (br t, *J* = 12.0 Hz, 1H), 2.10 – 1.60 (br m, 17H), 1.37 (m, 1H), 1.21 (m, 1H).

Example 16*N*-((1-acetylpiperidin-4-yl)methyl)-*N'*-(adamant-1-yl)urea (1156)


[0205] Yield = 55%. ¹H (300 MHz, CDCl₃) 5.10 – 4.50 (br, 2H), 4.60 (d, *J* = 13.3 Hz, 1H), 3.81 (d, *J* = 13.4 Hz, 1H), 3.15 (br dd, *J* = 13.7, 4.4 Hz, 1H), 3.03 (br t, *J* = 12.6 Hz, 1H), 2.92 (br dd, *J* = 13.0, 4.5 Hz, 1H), 2.53 (br t, *J* = 12.9 Hz, 1H), 2.4 – 1.4 (br m, 21H), 1.20 – 0.99 (m, 2H).

Example 17*N*-((1-propanoylpiperidin-4-yl)methyl)-*N'*-(adamant-1-yl)urea (1162)


[0206] Yield = 20% (via acid chloride). ¹H (300 MHz, CDCl₃): 4.60 (br d, *J* = 12.0 Hz, 1H), 3.85 (br d, *J* = 12.3 Hz, 1H), 3.20 – 2.80 (br, 3H), 2.52 (br t, *J* = 12.8 Hz, 1H), 2.33 (q, *J* = 7.5 Hz, 2H), 2.4 – 1.4 (br m, 18H), 1.13 (t, *J* = 7.5 Hz, 3H), 1.15 – 1.05 (br m, 2H). (note, sample contained water, therefore no urea N-H are seen).

Example 18***N-((1-butylpiperidin-4-yl)methyl)-N'-(adamant-1-yl)urea (1120)***


[0207] Yield = 35%. Mp.: 117-149 °C dec. ¹H (300 MHz, CDCl₃): 4.78 (br t, *J* = 4.7 Hz, 1H), 4.61 (br d, *J* = 13.1 Hz, 1H), 4.47 (s, 1H), 3.86 (br d, *J* = 13.6 Hz, 1H), 3.20 – 3.08 (m, 1H), 2.98 (t, *J* = 13.1 Hz, 1H), 2.95 – 2.84 (m, 1H), 2.52 (t, *J* = 12.6 Hz, 1H), 2.29 (t, *J* = 7.4 Hz, 2H), 2.10 – 1.50 (m, 20H), 1.20 – 1.00 (m, 2H), 0.96 (t, *J* = 7.4 Hz, 3H).

Example 19***N-((1-benzoylpiperidin-4-yl)methyl)-N'-(adamant-1-yl)urea (1121)***

[0208] Yield = 45%. ¹H (300 MHz, CDCl₃): 7.45 – 7.34 (m, 5H), 4.80 – 4.60 (br, 1H), 4.50 – 4.40 (br, 1H), 4.30 – 4.05 (br, 1H), 3.80 – 3.60 (br, 1H), 3.20 – 2.60 (br, 4H), 2.10 – 1.5 (br m, 18H), 1.30 – 1.0 (br, 2H).


Example 20***N-((1-(pyridine-2-carbonyl)piperidin-4-yl)methyl)-N'-(adamant-1-yl)urea (1207)***

[0209] Yield = 73%. ¹H (300 MHz, CDCl₃): 8.59 (br d, *J* = 5.0 Hz, 1H), 7.79 (td, *J* = 7.7, 1.7 Hz, 1H), 7.56 (br d, *J* = 7.7 Hz, 1H), 7.33 (ddd, *J* = 7.6, 4.8, 1.2 Hz, 1H), 4.70 (br d, *J* = 12.7 Hz, 1H), 4.47 (br m, 1H), 4.20 (s, 1H), 3.88 (br d, 13.1 Hz, 1H), 3.20 – 2.90 (m, 3H), 2.77 (br t, *J* = 12.6 Hz, 1H), 2.10 – 1.50 (m, 18H), 1.15 – 1.05 (m, 2H).

Example 21


N-((1-(pyridine-3-carbonyl)piperidin-4-yl)methyl)-N'-(adamant-1-yl)urea (1436)

[0210] Yield = quantitative. ¹H (300 MHz, CDCl₃): 8.65 (dd, *J* = 4.9, 1.6 Hz, 1H), 8.64 (d, *J* = 2.0 Hz, 1H), 7.74 (dt, 7.8, 1.9 Hz, 1H), 7.37 (dd, *J* = 7.9, 4.9 Hz, 1H), 5.00 – 4.90 (br, 1H), 4.78 – 4.60 (br, 1H), 4.60 – 4.44 (br 1H), 3.79 – 3.62 (br, 1H), 3.21 – 2.68 (br m, 4H), 2.10 – 1.50 (m, 18H), 1.15 – 1.05 (m, 2H).

Example 22


N-((1-(pyridine-4-carbonyl)piperidin-4-yl)methyl)-N'-(adamant-1-yl)urea (1435).

[0211] Yield = 77%. 8.70 – 8.66 (m, 2H), 7.28 – 7.25 (m, 2H), 4.77 – 4.58 (br, 2H), 4.44 – 4.36 (br, 1H), 3.60 (br d, *J* = 13.5 Hz, 1H), 3.20 – 2.95 (m, 3H), 2.77 (br t, *J* = 12.5 Hz, 1H), 2.10 – 1.50 (m, 18H), 1.15 – 1.05 (m, 2H).

Example 23


4-[4-(3-Adamantan-1-yl-ureido)-piperidin-1-yl]-4-oxo-butanoic acid methyl ester (1205).

[0212] Yield = 78%. Mp 169-175 °C dec. ¹H (300 MHz, CDCl₃): 4.65 – 4.34 (br m, 3H), 3.90 – 3.67 (br m, 2H), 3.69 (s, 3H), 3.12 (br t, *J* = 13.2 Hz, 1H), 2.76 (br t, *J* = 13.2 Hz, 1H), 2.71 – 2.54 (m, 4H), 2.20 – 1.5 (m, 17H), 1.30 – 1.10 (m, 2H).

Example 24


5-[4-(3-Adamantan-1-yl-ureido)-piperidin-1-yl]-5-oxo-pentanoic acid methyl ester (**1206**)

[0213] Yield = 61%. Mp 152-154 °C. ¹H (300 MHz, CDCl₃): 4.65 – 4.34 (br m, 3H), 3.90 – 3.67 (br m, 2H), 3.66 (s, 3H), 3.09 (br t, *J* = 13.7 Hz, 1H), 2.70 (br t, *J* = 13.7 Hz, 1H), 2.45 – 2.31 (m, 4H), 2.20 – 1.5 (m, 19H), 1.30 – 1.10 (m, 2H).

Example 25


2-[4-(3-Adamantan-1-yl-ureido)-piperidine-1-carbonyl]-benzoic acid methyl ester (**1202**)

[0214] Yield = 63%. ¹H (300 MHz, CDCl₃): 8.03 (d, *J* = 7.9 Hz, 1H), 7.58 (t, *J* = 7.7 Hz, 1H), 7.46 (t, *J* = 7.7 Hz, 1H), 7.25 (d, *J* = 7.7 Hz, 1H), 5.00 – 4.62 (br, 2H), 4.55 (br d, *J* = 13.0 Hz, 1H), 3.87 (s, 3H), 3.85 – 3.72 (br m, 1H), 3.13 (br d, *J* = 13.1 Hz, 1H), 3.11 – 2.94 (m, 2H), 2.10 – 1.10 (m, 19H).


Example 26

3-[4-(3-Adamantan-1-yl-ureido)-piperidine-1-carbonyl]-benzoic acid methyl ester (**1203**)


[0215] Yield = 61%. ¹H (300 MHz, CDCl₃): 8.10 (dd, *J* = 7.6, 1.4 Hz, 1H), 8.04 (d, *J* = 1.4 Hz, 1H), 7.58 (dd, *J* = 7.6, 1.4 Hz, 1H), 7.50 (t, *J* = 7.6 Hz, 1H), 4.7 – 4.4 (br, 3H), 3.93 (s, 3H), 3.90 – 3.81 (br, 1H), 3.70 – 3.55 (br, 1H), 3.20 – 3.90 (br m, 2H), 2.15 – 1.60 (br m, 17H), 1.50 – 1.10 (br m, 2H).

Example 27**4-[4-(3-Adamantan-1-yl-ureido)-piperidine-1-carbonyl]-benzoic acid methyl ester (1204)**

[0216] Yield = 70%. Mp 239-243 °C. ¹H (300 MHz, CDCl₃): 8.08 (d, *J* = 8.5 Hz, 2H), 7.43 (d, *J* = 8.5 Hz, 2H), 4.67 – 4.50 (br m, 2H), 4.45 (br, 1H), 3.94 (s, 3H), 3.90 – 8.74 (m, 1H), 3.65 – 3.55 (br m, 1H),), 3.20 – 3.90 (br m, 2H), 2.15 – 1.60 (br m, 17H), 1.50 – 1.10 (br m, 2H).

Example 28**4-{4-[(3-Adamantan-1-yl-ureido)-methyl]-piperidin-1-yl}-4-oxo-butanoic acid methyl ester (1208)**


[0217] Yield = 72%. ¹H (300 MHz, CDCl₃): 4.70 – 4.10 (br, 2H), 4.58 (d, *J* = 12.4 Hz, 1H), 3.89 (d, *J* = 12.5 Hz, 1H), 3.69 (s, 3H), 3.15 (br dd, *J* = 13.7, 4.4 Hz, 1H), 3.03 (br t, *J* = 12.6 Hz, 1H), 2.92 (br dd, *J* = 13.0, 4.5 Hz, 1H),), 2.64 (s, 4H), 2.53 (br t, *J* = 12.9 Hz, 1H), 2.10 – 1.50 (br m, 18H), 1.15 – 1.00 (m, 2H).

Example 29**5-{4-[(3-Adamantan-1-yl-ureido)-methyl]-piperidin-1-yl}-5-oxo-pentanoic acid methyl ester (1212)**

[0218] Yield = 42%. ¹H (300 MHz, CDCl₃): 4.70 – 4.10 (br m, 2H), 4.58 (d, *J* = 12.4 Hz, 1H), 3.89 (d, *J* = 12.5 Hz, 1H), 3.66 (s, 3H), 3.15 (br dd, *J* = 13.7, 4.4 Hz, 1H), 3.03 (br t, *J* =

12.6 Hz, 1H), 2.92 (br dd, $J = 13.0, 4.5$ Hz, 1H),), 2.53 (br t, $J = 12.9$ Hz, 1H), 2.39 (m, 4H), 2.10 – 1.50 (br m, 20H), 1.20 – 0.95 (m, 2H).


Example 30



2-{4-[(3-Adamantan-1-yl-ureido)-methyl]-piperidine-1-carbonyl}-benzoic acid methyl ester (1210)


[0219] Yield = 76%. ^1H (300 MHz, CDCl_3): 8.02 (d, $J = 7.8$ Hz, 1H), 7.57 (td, $J = 7.5, 1.2$ Hz, 1H), 7.45 (td, $J = 7.6, 1.2$ Hz, 1H), 7.26 (d, $J = 7.6$ Hz, 1H), 5.10 – 4.85 (br m, 1H), 4.74 (br d, $J = 12.5$ Hz, 1H), 4.70 – 4.60 (br, 1H), 3.87 (s, 3H), 3.35 (br d, $J = 12.5$ Hz, 1H), 3.20 – 3.10 (m, 1H), 3.00 – 2.70 (m, 3H),), 2.10 – 1.50 (br m, 18H), 1.20 – 0.95 (m, 2H).

Example 31



3-{4-[(3-Adamantan-1-yl-ureido)-methyl]-piperidine-1-carbonyl}-benzoic acid methyl ester (1209)

[0220] Yield = 67%. ^1H (300 MHz, CDCl_3): 8.08 (d, $J = 7.7$ Hz, 1H), 8.04 (s, 1H), 7.58 (d, $J = 7.7$ Hz, 1H), 7.49 (t, $J = 7.6$ Hz, 1H), 5.10 – 4.40 (br m, 3H), 3.93 (s, 3H) 3.75 – 3.63 (br, 1H), 3.20 – 2.80 (br m, 4H),), 2.10 – 1.50 (br m, 18H), 1.20 – 0.95 (m, 2H).


Example 32

4-{4-[(3-Adamantan-1-yl-ureido)-methyl]-piperidine-1-carbonyl}-benzoic acid methyl ester (1211)

[0221] Yield = 71%. ¹H NMR (300 MHz, CDCl₃): 8.07 (d, *J* = 8.5, 2H), 7.44 (d, *J* = 8.5, 2H), 4.70 (br d, *J* = 12.1 Hz, 1H), 4.55 – 4.45 (br, 1H), 4.22 (br, 1H), 3.94 (s, 3H), 3.64 (br d, *J* = 12.4 Hz, 1H), 3.25 – 2.70 (br m, 4H), 2.10 – 1.50 (br m, 18H), 1.20 – 0.95 (m, 2H).


General procedure for the hydrolysis of methyl esters to the corresponding acids.

[0222] The parent ester was dissolved in methyl alcohol to a concentration of 1 M. To this was added 1.2 eq of KOH (as a 4 M solution). The reaction was heated to 60 °C for 6 hrs. The solvent was removed and the residue chromatographed on silica gel using a 94:5:1 DCM:MeOH:HOAc eluent. Yields were greater than 90%.


Example 33

4-[4-(3-Adamantan-1-yl-ureido)-piperidin-1-yl]-4-oxo-butanoic acid (1503)


[0223] Mp 196 °C dec. ¹H NMR (300 MHz, DMSO): 12.14 (br, 1H), 5.67 (d, *J* = 7.8 Hz, 1H), 5.40 (s, 1H), 4.05 (br d, *J* = 13.2 Hz, 1H), 3.71 (br d, *J* = 13.5 Hz, 1H), 3.50 (br, 1H), 3.07 (br t, *J* = 10.8 Hz, 1H), 2.74 (br t, *J* = 10.8 Hz, 1H), 2.50 – 2.30 (m, 4H), 2.00 – 1.60 (br m, 17H), 1.40 – 0.90 (m, 2H).

Example 34*5-[4-(3-Adamantan-1-yl-ureido)-piperidin-1-yl]-5-oxo-pentanoic acid (1501)*


[0224] ^1H NMR (300 MHz, DMSO): 12.11 (br, 1H), 5.66 (br d, $J = 7.1$ Hz, 1H), 5.40 (br s, 1H), 4.08 (br d, $J = 13.1$ Hz, 1H), 3.67 (br d, $J = 13.6$ Hz, 1H), 3.58 – 3.41 (br, 1H), 3.05 (br t, $J = 11.7$ Hz, 1H), 2.73 (br t, $J = 11.7$ Hz, 1H), 2.28 (t, $J = 7.4$ Hz, 2H), 2.21 (t, $J = 7.4$ Hz, 2H), 2.00 – 1.50 (br m, 19 H), 1.20 – 0.90 (m, 2H).

Example 35*2-[4-(3-Adamantan-1-yl-ureido)-piperidine-1-carbonyl]-benzoic acid (1507)*

[0225] Mp 219 °C dec. ^1H NMR (300 MHz, DMSO): 13.16 (br, 1H), 7.90 (dd, $J = 7.7$, 0.89 Hz, 1H), 7.62 (td, $J = 7.5$, 0.9 Hz, 1H), 7.49 (td, $J = 7.6$, 1.0 Hz, 1H), 7.27 (d, $J = 7.3$ Hz, 1H), 5.71 (d, $J = 7.4$ Hz, 1H), 5.45 (s, 1H), 4.24 – 4.12 (br m, 1H), 3.60 – 3.45 (br, 1H), 3.22 – 3.10 (br m, 1H), 3.05 – 2.85 (br, 2H), 2.02 – 1.38 (br m, 17H), 1.35 – 1.06 (br m, 2H).

Example 36*3-[4-(3-Adamantan-1-yl-ureido)-piperidine-1-carbonyl]-benzoic acid (1505)*


[0226] ^1H NMR (300 MHz, DMSO): 13.23 (br, 1H), 7.97 (br d, $J = 7.4$ Hz, 1H), 7.86 (br s, 1H), 7.59 (br d, $J = 7.3$ Hz, 1H), 7.54 (t, $J = 7.3$ Hz, 1H), 5.70 (br d, 7.8 Hz, 1H), 5.42 (br s, 1H), 4.30 – 4.10 (br, 1H), 3.65 – 2.95 (br m, 4H), 2.00 – 1.50 (br m, 17H), 1.35 – 1.06 (br m, 2H).



4-[4-(3-Adamantan-1-yl-ureido)-piperidine-1-carbonyl]-benzoic acid (1523)

Mp 245-251 °C. ¹H NMR (300 MHz, DMSO): 13.12 (br, 1H), 7.95 (d, *J* = 7.5 Hz, 1H), 7.45 (d, *J* = 7.5 Hz, 1H), 5.69 (d, *J* = 5.7 Hz, 1H), 5.44 (s, 1H), 4.29 – 4.11 (br, 1H), 3.68 – 2.88 (br m, 4H), 2.00 – 1.50 (br m, 17H), 1.35 – 1.06 (br m, 2H).


Example 37



4-{4-[(3-Adamantan-1-yl-ureido)-methyl]-piperidin-1-yl}-4-oxo-butanoic acid (1502)


[0227] ¹H NMR (300 MHz, DMSO): 12.70 – 10.93 (br, 1H), 5.71 (br t, *J* = 5.2 Hz, 1H), 5.44 (s, 1H), 4.30 (br d, *J* = 11.4 Hz, 1H), 3.83 (br d, *J* = 12.0 Hz, 1H), 2.91 (br t, *J* = 12.9 Hz, 1H), 2.84 – 2.78 (m, 2H), 2.50 – 2.30 (br m, 5H), 2.10 – 1.50 (br m, 18H), 1.15 – 0.80 (m, 2H).

Example 38




5-{4-[(3-Adamantan-1-yl-ureido)-methyl]-piperidin-1-yl}-5-oxo-pentanoic acid (1500)


[0228] ¹H NMR (300 MHz, DMSO): 12.80 – 11.10 (br, 1H), 5.70 (br t, *J* = 5.6 Hz, 1H), 5.44 (s, 1H), 4.33 (br d, *J* = 12.4 Hz, 1H), 3.80 (br d, *J* = 13.0 Hz, 1H), 2.89 (br t, *J* = 12.8 Hz, 1H), 2.83 – 2.76 (m, 2H), 2.44 (br t, *J* = 12.6 Hz, 1H), 2.27 (t, *J* = 7.5 Hz, 2H), 2.21 (t, *J* = 7.4 Hz, 2H), 2.10 – 1.50 (br m, 20H), 1.20 – 0.95 (m, 2H).

Example 39*2-{4-[(3-Adamantan-1-yl-ureido)-methyl]-piperidine-1-carbonyl}-benzoic acid (1506)*

[0229] Mp 192 °C dec. ¹H NMR (300 MHz, DMSO): 13.60 – 11.60 (br, 1H), 7.87 (br d, *J* = 7.7 Hz, 1H), 7.53 (br t, *J* = 7.4 Hz, 1H), 7.42 (br t, *J* = 7.4 Hz, 1H), 7.18 (br d, *J* = 7.4 Hz, 1H), 5.75 (br m, 1H), 5.47 (br, 1H), 4.45 (br d, *J* = 12.4 Hz, 1H), 3.17 (br d, *J* = 11.5 Hz, 1H), 2.90 – 2.55 (br m, 4H), 2.10 – 1.50 (br m, 18H), 1.20 – 0.95 (m, 2H).

Example 40*3-{4-[(3-Adamantan-1-yl-ureido)-methyl]-piperidine-1-carbonyl}-benzoic acid (1504)*


[0230] ¹H NMR (300 MHz, DMSO): 13.53 – 12.70 (br, 1H), 7.97 (d, *J* = 7.3 Hz, 1H), 7.85 (s, 1H), 7.61 – 7.51 (m, 2H), 5.75 – 5.68 (br m, 1H), 5.43 (s, 1H), 4.50 – 4.37 (br, 1H), 3.50 – 2.55 (br m, 5H), 2.10 – 1.50 (br m, 18H), 1.20 – 0.92 (m, 2H).

Example 41*4-{4-[(3-Adamantan-1-yl-ureido)-methyl]-piperidine-1-carbonyl}-benzoic acid (1522)*

[0231] Mp 147 °C dec. ¹H NMR (300 MHz, DMSO): 13.80 – 12.40 (br, 1H), 7.96 (d, *J* = 8.1 Hz, 1H), 7.43 (d, *J* = 8.2 Hz, 1H), 5.72 (t, *J* = 5.8 Hz, 1H), 5.45 (s, 1H), 4.44 (br d, *J* =

11.5 Hz, 1H), 3.50 (br m, 1H), 3.50 - 2.55 (br m, 5H), 2.10 - 1.50 (br m, 18H), 1.20 - 0.90 (m, 2H).

Example 42



N-(1-Methanesulfonyl piperidin-4-yl)-N'-(adamant-1-yl) urea

N-Methanesulfonyl piperid-4-yl amide

[0232] A reactor was charged with 1.0 mole-equivalent of 4-piperidinecarboxamide, 16.4 mole-equivalents of THF, and 1.2 mole-equivalents of N, N-(diisopropyl)ethylamine under a nitrogen atmosphere. The resulting mixture was cooled to 0-5°C internal, and 1.2 mole-equivalents of methanesulfonyl chloride was added at such a rate as to maintain an internal temperature of less than 10°C. After addition was complete, the reaction mixture was stirred allowing the temperature to rise to 20°C internal. The reaction contents was monitored until the amount of unreacted 4-piperidinecarboxamide was less than 1% relative to N-methanesulfonyl piperid-4-yl amide product (typically about 2-12 hours). The precipitated product was collected by filtration then washed with dichloromethane to remove excess (diisopropyl)ethylamine hydrochloride. The solid product was dried to constant weight in a vacuum oven under a nitrogen bleed maintaining an internal temperature of ≤50°C to afford product as a light yellow solid in 87% yield. Mp.: 126-128°C. ¹H NMR(DMSO-d₆) δ: 7.30 (s, 1H), 6.91 (s, 1H), 3.46-3.59 (m, 2H), 2.83 (s, 3H), 2.60-2.76 (m, 2H), 2.08-2.24 (m, 1H), 1.70-1.86 (m, 2H), 1.43-1.62 (m, 2H); MS: 207 [M+H]⁺.

N-(1-Methanesulfonyl piperidin-4-yl)-N'-(adamant-1-yl) urea


[0233] A reactor was charged with 1.00 mole-equivalents of N-methanesulfonyl piperid-4-yl amide, 1.06 mole-equivalents of 1-adamantyl amine, and 39.3 mole-equivalents of acetonitrile, and the resulting mixture was heated to 40°C internal under a nitrogen atmosphere. (Diacetoxyiodo)benzene (1.20 mole-equivalents) was charged portionwise in such a way that the reaction mixture was maintained below 75°C internal. After the

(diacetoxyiodo)benzene had been added, the reaction mixture was heated at 65-70°C internal, and the reaction contents monitored until the amount of unreacted 1-adamantyl amine was less than 5% relative to product N-(1-methanesulfonyl piperidin-4-yl)-N'-(adamant-1-yl) urea (typically less than about 6 hours). The resulting mixture was cooled to 20°C internal and filtered to remove a small amount of insoluble material. The filtrate was allowed to stand for 48 hours at which point the precipitated product was collected by filtration. The solid product was dried to constant weight in a vacuum oven under a nitrogen bleed maintaining an internal temperature of $\leq 50^{\circ}\text{C}$ to afford product in 58% yield based on N-methanesulfonyl piperid-4-yl amide. ^1H NMR(CDCl_3) δ : 3.95-4.08 (m, 2H), 3.74-3.82 (m, 2H), 3.63-3.82 (m, 1H), 3.78 (s, 3H), 3.70-3.80 (m, 2H), 2.02-2.12 (m, 5H), 1.90 (s, 6H), 1.67 (s, 6H), 1.40-1.50 (m, 2H); MS: 356 $[\text{M}+\text{H}]^+$; m.p. 228-229°C.

Example 43-63


[0234] Synthesized as described previously in Jones, P. D., *et al. Bioorganic & medicinal chemistry letters* 2006, 16, 5212.

Example 43




1-Piperidin-4-yl-3-(4-trifluoromethoxy-phenyl)-urea (1570)


[0235] ^1H NMR (300 MHz, D_6DMSO) δ ppm 8.61 (s, 1H), 7.63-7.26 (m, 2H), 7.20 (d, $J = 8.29$ Hz, 2H), 6.25 (d, $J = 7.57$ Hz, 1H), 3.60-3.38 (m, 1H), 2.87 (td, $J = 11.85, 3.18, 3.18$ Hz, 2H), 1.79-1.64 (m, 2H), 2.48-2.41 (m, 2H), 1.20 (qd, $J = 11.06, 3.83$ Hz, 2H); m.p. 169-173°C.

Example 44*1-(1-Acetyl-piperidin-4-yl)-3-(4-trifluoromethoxy-phenyl)-urea (1555)*


[0236] ^1H NMR (300 MHz, D6 DMSO) δ ppm 8.07 (s, 1H), 7.48-7.28 (m, 2H), 7.09 (d, J = 8.93 Hz, 2H), 5.87 (d, J = 7.57 Hz, 1H), 4.53-4.26 (m, 1H), 4.05-3.82 (m, 1H), 3.82-3.70 (m, 1H), 3.29-3.06 (m, 1H), 3.01-2.69 (m, 1H), 2.11 (s, 3H), 2.14-1.87 (m, 2H), 1.40-1.25 (m, 2H); m.p. 198-202°C.

Example 45*1-[1-(2,2,2-Trifluoro-acetyl)-piperidin-4-yl]-3-(4-trifluoromethoxy-phenyl)-urea (1591)*


[0237] ^1H NMR (300 MHz, D6 DMSO) δ ppm 7.41-7.03 (m, 5H), 5.21 (s, 1H), 4.50-4.31 (m, 1H), 3.95 (brd, J = 2H), 3.18 (m, 1H), 2.90 (m, 1H), 2.19-1.90 (m, 1H), 1.29 (m, 2H); m.p. 150-154°C.

Example 46*1,3-Di-piperidin-4-yl-urea (1604)*


[0238] ^1H NMR (300 MHz, D6 DMSO) δ ppm 9.19-8.89 (m, 2H), 3.74-3.55 (m, 1H), 3.26-3.12 (m, 2H), 2.95-2.80 (m, 2H), 1.99-1.79 (m, 2H), 1.65-1.45 (m, 2H).

Example 47*1,3-Bis-(1-benzoyl-piperidin-4-yl)-urea (1605)*


[0239] ^1H NMR (300 MHz, CDCl_3) δ ppm 7.67-6.93 (m, 5), 5.39 (d, $J = 7.98$ Hz, 1H), 4.78-4.24 (m, 1H), 4.05-3.43 (m, 2H), 3.34-2.63 (m, 2H), 2.20-1.57 (m, 2H), 1.49-0.71 (m, 2H); ^{13}C NMR (75 MHz, CDCl_3) δ ppm 170.84, 157.25, 135.88, 130.14, 128.84, 126.94, 46.91, 46.66, 41.47, 33.97, 32.67.

Example 48*Adamantane-1-carboxylic acid piperidin-4-ylamide*


[0240] ^1H NMR (300 MHz, CDCl_3) δ ppm 8.97 (d, $J = 7.53$ Hz, 2H), 7.39 (d, $J = 7.53$ Hz, 1H), 3.86-3.73 (m, 1H), 3.28-3.17 (m, 2H), 2.99-2.81 (m, 2H), 2.01-1.53 (m, 19H).

*Adamantane-1-carboxylic acid (1-acetyl-piperidin-4-yl)-amide (1641)*


[0241] ^1H NMR (300 MHz, CDCl_3) δ ppm 5.49 (d, $J = 7.38$ Hz, 1H), 4.60-4.51 (m, 1H), 4.07-3.90 (m, 1H), 3.79 (ddd, $J = 13.76, 5.64, 3.68$ Hz, 1H), 3.17 (ddd, $J = 14.01, 12.08, 2.76$ Hz, 1H), 2.79-2.67 (m, 1H), 2.10 (s, 3H), 2.09-1.65 (m, 17H), 1.37-1.21 (m, 2H).

Example 49*2-Adamantan-1-yl-N-piperidin-4-yl-acetamide*


[0242] ^1H NMR (300 MHz, D₆ DMSO) δ ppm 9.04-8.94 (m, 2H), 7.90 (d, $J = 7.49$ Hz, 1H), 3.99-3.48 (m, 1H), 3.24-3.12 (m, 2H), 3.00-2.79 (m, 2H), 2.10-1.22 (m, 21H).

*N-(1-Acetyl-piperidin-4-yl)-2-adamantan-1-yl-acetamide (1642)*

[0243] ^1H NMR (300 MHz, CDCl₃) δ ppm 5.56 (d, $J = 7.73$ Hz, 1H), 4.55 (d, $J = 14.17$ Hz, 1H), 4.08-3.93 (m, 1H), 3.84-3.73 (m, 1H), 3.22-3.10 (m, 1H), 2.78-2.65 (m, 1H), 2.09 (s, 1H), 2.07-1.92 (m, 3H), 1.91 (s, 2H), 1.76-1.55 (m, 12H), 1.39-1.21 (m, 2H).


Example 50*2-Adamantan-1-yl-N-[1-(2,2,2-trifluoro-acetyl)-piperidin-4-yl]-acetamide (1642)*

[0244] ^1H NMR (300 MHz, CDCl₃) δ ppm 5.30 (d, $J = 7.80$ Hz, 1H), 4.56-4.46 (m, 1H), 4.16-3.94 (m, 2H), 3.29-3.17 (m, 1H), 2.96-2.85 (m, 1H), 2.23-1.51 (m, 19H), 1.47-1.31 (m, 2H).

Example 51


Adamantane-1-carboxylic acid [1-(2,2,2-trifluoro-acetyl)-piperidin-4-yl]-amide (1643)

[0245] ^1H NMR (300 MHz, CDCl_3) δ ppm 5.57-5.27 (m, 1H), 4.60-4.32 (m, 1H), 4.18-3.85 (m, 2H), 3.36-3.09 (m, 1H), 3.00-2.77 (m, 1H), 2.17-1.52 (m, 17H), 1.35 (s, 2H).

Example 52


1-(1-Acetyl-piperidin-4-yl)-3-cycloheptyl-urea (1645)

[0246] ^1H NMR (300 MHz, CDCl_3) δ ppm 4.68-4.60 (m, 2H), 4.49 (d, $J = 11.54$ Hz, 1H), 3.92-3.66 (m, 3H), 3.24-3.10 (m, 1H), 2.83-2.71 (m, 1H), 2.11 (s, 3H), 2.08-1.11 (m, 16H).


Example 53

1-Adamantan-1-yl-3-(1-methanesulfonyl-piperidin-4-yl)-urea (1701)


[0247] ^1H NMR (300 MHz, CDCl_3) δ ppm 4.16-4.00 (m, 2H), 3.82-3.60 (m, 3H), 2.78 (s, 3H), 2.76-2.69 (m, 2H), 2.12-1.61 (m, 17H), 1.53-1.36 (m, 2H).

Example 54*4-(3-Adamantan-1-yl-ureido)-piperidine-1-carboxylic acid methyl ester (1702)*


[0248] ^1H NMR (300 MHz, CDCl_3) δ ppm 5.68 (d, $J = 7.56$ Hz, 1H), 5.42 (s, 1H), 3.82-3.72 (m, 2H), 3.57 (s, 3H), 3.53-3.40 (m, 1H), 3.00-2.85 (m, 2H), 2.03-1.52 (m, 17H), 1.20-1.04 (m, 2H).

Example 55*1-(1-Methanesulfonyl-piperidin-4-yl)-3-(4-trifluoromethoxy-phenyl)-urea (1709)*

[0249] ^1H NMR (300 MHz, CDCl_3) δ ppm 8.04 (s, 1H), 7.44-7.38 (m, 2H), 7.09 (d, $J = 8.36$ Hz, 2H), 5.93 (d, $J = 7.70$ Hz, 1H), 4.00-3.55 (m, 3H), 2.90-2.78 (m, 2H), 2.81 (s, 3H), 2.61-2.55 (m, 2H), 2.15-1.99 (m, 2H), 1.61-1.45 (m, 2H).

Example 56*1-[1-(Toluene-4-sulfonyl)-piperidin-4-yl]-3-(4-trifluoromethoxy-phenyl)-urea (1711)*

[0250] ^1H NMR (300 MHz, CDCl_3) δ ppm 7.91 (s, 1H), 7.63 (d, $J = 8.22$ Hz, 2H), 7.38-7.30 (m, 4H), 7.06 (d, $J = 8.84$ Hz, 1H), 5.78 (s, 1H), 3.77-3.47 (m, 3H), 2.48-2.35 (m, 2H), 2.44 (s, 3H), 2.05-1.93 (m, 2H), 1.57-1.41 (m, 2H).


Example 57

1-[1-(5-Dimethylamino-naphthalene-1-sulfonyl)-piperidin-4-yl]-3-(4-trifluoromethoxy-phenyl)-urea (1710)

[0251] ^1H NMR (300 MHz, CDCl_3) δ ppm 8.59 (d, $J = 8.50$ Hz, 1H), 8.32 (d, $J = 8.71$ Hz, 1H), 8.18 (dd, $J = 7.35, 1.19$ Hz, 1H), 7.54 (ddd, $J = 8.50, 7.51, 3.20$ Hz, 2H), 7.29-7.22 (m, 2H), 7.19 (d, $J = 7.15$ Hz, 1H), 7.02 (d, $J = 8.45$ Hz, 2H), 6.93 (s, 1H), 5.19 (d, $J = 7.73$ Hz, 1H), 3.91-3.64 (m, 3H), 2.89 (s, 6H), 2.86-2.72 (m, 2H), 2.06-1.92 (m, 2H), 1.64-1.46 (m, 2H).


Examples 58-64

[0252] These chemicals were synthesized by the direct reaction of amine with isocyanate following previously described procedures in Morisseau, C., *et al. Biochemical Pharmacology* **2002**, 63, 1599. Jones, P. D., *et al. Bioorganic & medicinal chemistry letters* **2006**, 16, 5212.


Example 58

1-Cyclohexyl-3-(1,3,5-triaza-tricyclo[3.3.1.1^{3,7}]dec-7-yl)-urea (1549)


[0253] ^1H NMR (300 MHz, D_6DMSO) δ ppm 5.62 (s, 1H), 5.37 (s, 1H), 4.25 (d, $J = 11.5$ Hz, 3H), 3.90 (d, $J = 10.8$ Hz, 3H), 3.50-3.21 (m, 6H), 2.50 (s, 1H), 1.82-1.59 (m, 5H) 1.15-0.95 (m, 5H); m.p. 150-154°C.

Example 59*1-Dodecyl-3-piperidin-4-yl-urea (1550)*


[0254] ^1H NMR (300 MHz, D6 DMSO) δ ppm 8.79-8.35 (m, 3H), 3.74-3.55 (m, 1H), 3.26-3.12 (m, 4H), 2.95-2.80 (m, 2H), 1.99-1.79 (m, 2H), 1.65-1.25 (m, 22H), 0.97 (t, $J = 12.8$ Hz, 3H); m.p. 102-105°C.

Example 60*4-(3-Cyclohexyl-ureido)-piperidine-1-carboxylic acid tert-butyl ester (1551)*


[0255] ^1H NMR (300 MHz, CDCl_3) δ ppm 4.26-4.16 (t, $J = 8.6$ Hz, 2H), 4.11-3.86 (m, 2H), 3.80-3.64 (m, 1H), 3.55-3.39 (m, 1H), 2.94-2.78 (t, $J = 12.2$ Hz, 2H), 1.98-1.87 (m, 4H), 1.75-1.65 (m, 3H), 1.45-1.05 (m, 16H); m.p. 167-169°C.

Example 61*1-Dodecyl-3-(1H-indol-5-yl)-urea (1553)*


[0256] ^1H NMR (300 MHz, D6 DMSO) δ ppm 10.9 (s, 1H), 8.10 (s, 1H), 7.50 (s, 1H), 7.30-7.18 (m, 2H), 7.00-6.90 (m, 1H), 6.19 (s, 1H), 6.00-5.95 (m, 1H), 3.41-3.18 (m, 2H), 1.60-1.10 (m, 20H), 0.97 (t, $J = 12.8$ Hz, 3H); m.p. 110-113°C.

Example 62*1-Cyclohexyl-3-(1H-indol-5-yl)-urea (1554)*


[0257] ^1H NMR (300 MHz, D6 DMSO) δ ppm 10.8 (s, 1H), 8.00 (s, 1H), 7.55 (s, 1H), 7.25-7.15 (m, 2H), 6.95-6.87 (m, 1H), 6.15 (s, 1H), 5.95-5.90 (m, 1H), 2.58-2.42 (m, 1H), 1.85-1.05 (m, 10H); m.p. 145-148°C.

Example 63*1-(1H-Benzoimidazol-5-yl)-3-dodecyl-urea (1568)*


[0258] ^1H NMR (300 MHz, D6 DMSO) δ ppm 8.35-8.25 (m, 2H), 7.35-7.20 (m, 2H), 6.65-6.50 (m, 1H), 5.40-4.85 (m, 2H), 3.38-3.21 (m, 2H), 1.40-1.15 (m, 20H), 0.85 (t, $J = 7.6$ Hz, 3H); m.p. 107-109°C.

Example 64*1-(1H-Benzoimidazol-5-yl)-3-cyclohexyl-urea (1569)*


[0259] ^1H NMR (300 MHz, D6 DMSO) δ ppm 8.41-8.29 (s, 1H), 8.15-8.00 (m, 1H), 7.35-7.15 (m, 2H), 6.65-6.47 (m, 1H), 5.40-4.90 (m, 2H), 2.55-2.47 (m, 1H), 1.95-1.05 (m, 10H); m.p. 143-148°C.

Example 65*Pyridin-4-ylmethyl-carbamic acid biphenyl-3-yl ester (1557)*


[0260] White fine crystal. ^1H NMR (CDCl_3): 8.60 (d, $J=5.70$ Hz, 2H), 7.10-7.50 (m, 11H), 5.56 (br, 1H), 4.50 (d, $J=6.30$ Hz, 2H); m.p.: 132 °C.

Example 66*Pyridin-4-ylmethyl-carbamic acid 2-methyl-biphenyl-3-ylmethyl ester (1558)*

[0261] White sponge-like crystal, ^1H NMR (CDCl_3): 8.56 (d, $J=5.70$ Hz, 2H), 7.20-7.45 (m, 10H), 5.25 (s, 3H), 4.42 (d, $J=6.30$ Hz, 2H), 2.25 (s, 3H); m.p. 103 °C.


Example 67*Pyridin-3-ylmethyl-carbamic acid biphenyl-3-yl ester (1559)*

[0262] White crystal, ^1H NMR (CDCl_3): 8.62 (s, 1H), 8.57 (dd, $J_1=1.20$ Hz, $J_2=4.50$ Hz, 1H), 7.70-7.75 (m, 11H), 7.56-7.59 (m, 12H), 7.27-7.46 (m, 7H), 7.11-7.15 (m, 1H), 5.54 (br, 1H), 4.49 (d, $J=6.30$ Hz, 2H); m.p. 113 °C.

Example 68*Pyridin-3-ylmethyl-carbamic acid 2-methyl-biphenyl-3-ylmethyl ester (1560)*

[0263] White crystal, ^1H NMR (CDCl_3): 8.55 (m, 2H), 7.76 (d, $J=7.50$ Hz, 1H), 7.22-7.41 (m, 9H), 5.23 (s, 2H), 5.19 (br, 1H), 4.42 (d, $J=5.70$ Hz, 2H), 2.23 (s, 3H); m.p. 110 °C.


Example 69



Morpholine-4-carboxylic acid biphenyl-3-yl ester (1561)

[0264] White crystal, ^1H NMR (CDCl_3): 7.57-7.60 (m, 2H), 7.27-7.46 (m, 6H), 7.08-7.13 (m, 1H), 3.60-3.79 (m, 8H); m.p. 97 °C.

Example 70



Morpholine-4-carboxylic acid 2-methyl-biphenyl-3-ylmethyl ester (1562)

[0265] Colorless sticky oil. ^1H NMR (CDCl_3): 7.23-7.45 (m, 8H), 5.23 (s, 2H), 3.68 (br, 4H), 3.50-3.53 (m, 4H), 2.23 (s, 3H).

Example 71

[0266] This example provides assays and illustrates the inhibition of human soluble epoxide hydrolases by compounds of the invention.

Enzyme preparation

[0267] Recombinant human sEH was produced in a baculovirus expression system and purified by affinity chromatography. The preparations were at least 97% pure as judged by SDS-PAGE and scanning densitometry. No detectable esterase or glutathione transferase activity, which can interfere with this sEH assay, was observed. Protein concentration was quantified by using the Pierce BCA assay using Fraction V bovine serum albumin as the calibrating standard.

IC₅₀ Assay conditions

[0268] IC₅₀ values were determined in one of three methods. One method uses racemic 4-nitrophenyl-*trans*-2,3-epoxy-3-phenylpropyl carbonate as substrate. Enzyme (0.24 μM human sEH) was incubated with inhibitors for 5 min in sodium phosphate buffer, 0.1 M pH 7.4, at 30°C before substrate introduction ([S] = 40 μM). Activity was assessed by measuring the appearance of the 4-nitrophenolate anion at 405 nm at 30°C during 1 min (Spectramax 200; Molecular Devices). Assays were performed in triplicate. IC₅₀ is a concentration of inhibitor, which reduces enzyme activity by 50%, and was determined by regression of at least five datum points with a minimum of two points in the linear region of the curve on either side of the IC₅₀. The curve was generated from at least three separate runs, each in triplicate.



[0269] Other IC₅₀ values were determined using the procedure described in *Analytical Biochemistry* 343 66-75 (2005) using cyano(6-methoxy-naphthalen-2-yl)methyl *trans*-[(3-phenyloxiran-2-yl)methyl] carbonate as a substrate. Enzymes (0.96 nM for human sEH) were incubated with inhibitors ([I] = 0.5–10,000 nM) for 5 min in BisTris-HCl buffer (25 mM, pH 7.0, containing 0.1 mg/ml of BSA) at 30 °C prior to substrate introduction ([S] = 5 mM). Enzyme activity was measured by monitoring the appearance of 6-methoxy-2-naphthaldehyde. Assays were performed in triplicate. By definition, IC₅₀ values are concentrations of inhibitor that reduce enzyme activity by 50%. IC₅₀ values were determined by regression of at least five datum points, with a minimum of two datum points in the linear region of the curve on either side of the IC₅₀ values. The curve was generated from at least three separate runs, each in triplicate.

[0270] Other inhibition potencies were determined using a fluorescent based high-throughput assay. Inhibitors in solution at 10 mM in DMSO were serially diluted by 10-fold increment in Bis/Tris HCl buffer (25 mM pH 7.0) containing 0.1 mg/mL of BSA (Buffer A). In black 96-well plates, 20 μL of the inhibitor dilution or buffer were delivered in every well, and then 130 μL of Human sEH at ~0.4 μg/mL in solution in Buffer A were added to each well. The plate was then mixed and incubated at room temperature for 5 minutes. Fifty microliters of substrate ((3-Phenyl-oxiranyl)-acetic acid cyano-(6-methoxy-naphthalen-2-yl)-methyl ester; PHOME) at 200 μM in solution in 96:4 Buffer A:DMSO was then added to each well to give [S]_{final} = 50 μM and [E]_{final} = ~4 nM. The plate was then mixed and incubated in the dark at room temperature (~25 °C) for 90 min. Activity was measured by determining the relative quantity of 6-methoxy-2-naphthaldehyde formed with an excitation wavelength of

316 nm and an emission wavelength of 460 nm measured with a SpectraMax M-2 fluorometer (molecular Devices, Sunnyvale CA).

[0271] Assays were conducted with the compounds indicated in Table 1-5, as described above.

Example 72

					
R	Compound #	IC ₅₀ (nM)	R	Compound #	IC ₅₀ (nM)
H	1175	960	H	1118	4258
Et	1152	3758	Et	1154	3949
n-Pr	1155	809	n-Pr	1122	2578
n-Bu	1160	1249	n-Bu	1161	613
benzyl	1158	8.4	benzyl	1119	112

[0272] This example illustrates the inhibition of human soluble epoxide hydrolases by compounds of the invention having an alkyl substituted piperidine moiety.

[0273] Assays were conducted with the compounds indicated in Table 1, according to established protocols (see, above).



Table 1: Inhibition of human sEH by alkyl substituted piperidines:







Example 73

[0274] This example illustrates the inhibition of human soluble epoxide hydrolases by compounds of the invention having an amide substituted piperidine moiety.

[0275] Assays were conducted with the compounds indicated in Table 2, according to established protocols (see, above).

Table 2: Inhibition of human sEH by simple amide substituted piperidines:

					
R	Compound	IC ₅₀ (nM)	R	Compound	IC ₅₀ (nM)













	#			#	
-C(O)Me	1153	14.5	-C(O)Me	1156	5.0
-C(O)Et	1163	3.2	-C(O)Et	1162	8.7
-C(O)- <i>n</i> -Pr	1157	2.6	-C(O)- <i>n</i> -Pr	1120	6.7
-C(O)Ph	1159	1.3	-C(O)Ph	1121	3.2
	1201	1.2		1207	7.6
	1433	1.7		1435	5.4
	1434	2.1		1436	7.3

Example 74

[0276] This example illustrates the inhibition of human soluble epoxide hydrolases by compounds of the invention having an amide-ester substituted piperidine moiety.

[0277] Assays were conducted with the compounds indicated in Table 3, according to established protocols (see, above).

Table 3: Inhibition of human sEH by amide-ester piperidines:













					
R	Compound #	IC ₅₀ (nM)	R	Compound #	IC ₅₀ (nM)
	1205	9.0		1208	6.2
	1206	2.7		1212	3.4
	1202	1.7		1210	1.8
	1203	1.1		1209	4.1
	1204	1.1		1211	1.5

Example 75

[0278] This example illustrates the inhibition of human soluble epoxide hydrolases by compounds of the invention having an amide-acid substituted piperidine moiety.

[0279] Assays were conducted with the compounds indicated in Table 4, according to established protocols (see, above).

Table 4: Inhibition of human sEH by amide-acid piperidines:


					
R	Compound #	IC ₅₀ (nM)	R	Compound #	IC ₅₀ (nM)
	1503	254.5		1502	174.5
	1501	72.8		1500	41.6
	1507	161.2		1506	407.1
	1505	10.1		1504	43.6
	1523	3.3		1522	11.8








Example 76








[0280] This example provides a table of structures of compounds with various other functionalities included in the invention. For example, the urea pharmacophore can be varied with amide or carbamate functionality to improve physical properties of sEH inhibitors as shown in Table 5a.








[0281] Assays were conducted with the compounds indicated in Table 5a and 5b, according to established protocols (see, above).

Table 5a: Inhibition of human sEH by 1-substituted-3-*n*-(substituted)heterocyclic ureas, carbamates and amides:

Compound	Structure	IC ₅₀ (nM)
1549		13586.4

Compound	Structure	IC ₅₀ (nM)
1550		42.5
1551		4.3
1553		639.1
1554		87
1555		11.5
1556		1.8
1557		11468.1

Compound	Structure	IC ₅₀ (nM)
1558		1329.7
1559		22991.5 /
1560		4413.4
1561		65339.4
1562		11994.1
1567		
1568		5021

Compound	Structure	IC ₅₀ (nM)
1569		457
1570		2316
1590		1.1
1591		0.4
1602		561.7
1604	HCl HCl 	100000
1605		4.8











Compound	Structure	IC ₅₀ (nM)
1606		1.7
1641		12649.3
1642		275.1
1643		4208.9
1644		28.3
1645		27.6

Table 5b

Structure	Compound #	IC50 (nM)
	1701	1.4
	1702	0.9
	1710	0.8
	1711	0.4

Example 77**Pharmacokinetic Screening Procedure:**

[0282] This example provides the pharmacokinetic studies, specifically serum profiles carried out using sEH inhibitor compounds of the present invention in dogs. As noted above, the use of 1-substituted urea inhibitors afforded exquisite sensitivity, allowing the determination of the determined pharmacokinetic parameters from serial blood samples collected from individual dogs (see Tables 6-8).

Animals.

[0283] Healthy dogs, 5-6 years-old, were assigned to study groups based on body-weight stratified randomization procedure. The body weight of animals used in all the experiments was about 20 kg. Dogs were maintained on a natural light / dark cycle under standard kennel conditions, with food and water available *ad libitum*.

Drug preparation, administration, blood sample drawing.

[0284] Various amounts of a compound was dissolved in 1 mL of Crisco, heated and sonicated for 15 minutes to dissolve the compounds. The mixture was transferred in solution to a syringe with a cap. The mixture becomes a solid at room temperature and may be kept in a refrigerator until used. sEH inhibitors were administered orally to dogs via syringe. The compounds are administered at room temperature or warmer so that they are in preferably in solution. The dogs are fed immediately thereafter.

[0285] Serial blood samples (100 μ L) were collected from a catheter inserted in the right front leg of the dog. Serial blood samples were collected in EDTA tubes at various time points (0, 15, 30, 60, 120, 180, 240, 300, 360, 480, and 1440 minutes) after administration. The blood samples are centrifuged at 4000 rpm for 10 minutes and the plasma is collected into micro-centrifuge tubes and frozen at -80 °C.

Plasma sample preparation for LC/MS measurement and analysis

[0286] 100 μ L of plasma was collected in another Eppendorf. 200 μ L of water and 500 μ L of ethyl acetate is added and the mixture was vortexed. 10 μ L of surrogate was added and the mixture was vortexed again. The mixture was centrifuged for 6000 rpm for 5 min. and the organic phase was then extracted into another Eppendorf. Another 500 μ L of ethyl acetate is added to the water phase and the mixture is extracted again. The organic phase is dried under nitrogen and the samples reconstituted with 50 μ L of MeOH and at least one internal standard is added to the plasma mixture (e.g. an extraction standard). Aliquots (5 μ L) were injected onto the LC-MS/MS system. For measuring parent compounds and their metabolites by using LC-MS/MS; a Waters 2790 liquid chromatograph equipped with a 30 X 2.1 mm 3 μ m C18 Xterra™ column (Waters) and a Micromass Quattro Ultima triple quadrupole tandem mass spectrometer (Micromass, Manchester, UK) was used.

Analysis.

[0287] Pharmacokinetics analysis was performed using SigmaPlot software system (SPSS science, Chicago, IL). A one-compartment model was used for blood concentration-time

profiles for the oral gavage dosing and fits to the following equation (see, Gibson, G.G. and Skett, P.: INTRODUCTION TO DRUG METABOLISM, SECOND ED., Chapman and Hall, New York 1994, 199-210):

$$C = ae^{-bt}$$

The half-life ($t_{1/2}$) for the elimination phase was calculated by the following equation:

$$t_{1/2} = 0.693/b$$

The area under the concentration (AUC) was calculated by the following equation:

$$AUC = a/b$$

Where:

- C = the total blood concentration at time t
- a = the extrapolated zero intercept
- b = the apparent first-order elimination rate constant

[0288] The results shown in Tables 6, 7 and 8 and examples of the time course of compounds is shown in Figures 1-3.





Table 6: LC/MS analysis












Time	Compound									
	1153	1555	1606	1163	1157	1159	1121	1201	1204	1206
0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
15	288.97	16.07	0.00	5.70	0.58	7.26	4.86	9.19	0.00	0.00
30	276.16	45.76	1.61	16.05	5.18	7.82	3.81	32.65	0.19	0.00
60	241.03	100.35	4.82	31.79	7.77	4.58	1.98	42.48	0.34	0.00
120	107.19	216.91	9.37	24.00	9.50	1.39	0.42	21.09	0.11	0.00
180	56.41	260.79	10.98	14.55	7.05	0.60	0.16	7.15	0.00	0.00
240	26.42	268.90	6.83	10.05	4.60	0.00	0.06	3.16	0.00	0.00
300	20.81	302.64	5.62	7.20	2.45	0.00	0.05	1.72	0.00	0.00

360	10.10		3.21	4.95	2.45	0.00	0.03	0.00	0.00	0.00
480	4.66	320.45	1.47	1.50	0.86	0.00	0.03	0.00	0.00	0.00
1440	0.00	266.29		0.00	0.00	0.00	0.04	0.00	0.00	0.00

[0289] Note the acid moiety makes a big difference in these compounds. The acids reach a maximum concentration faster and gives sustained blood levels. Higher blood levels (bioavailability) generally correspond to higher protein binding and higher efficacy. Accordingly, the presence of an acidic moiety improves the oral availability of these inhibitors.

Table 7: Pharmacokinetic parameters of compounds

Cmpd. (solubility in oil)	Structure	IC ₅₀ (nM)	AUC (μ M* min)	AUCINF _D_pred (min*kg* nM/mg)	AUCINF_ D_pred / IC ₅₀ (AUC/ IC ₅₀)
1153 (Opaque)		14.5	35.8	119214	8221 (2.5)
1156		5	4.9		(1.0)
1555 (Opaque)		11.5	390.1	13002825	1130680 (33.9)
1606 (Suspension)		1.7	2.6	8553	5031(1.5)

1163 (Opaque)		3.19	5.6	18504	5800 (1.75)
1157 (Opaque)		2.64	2.2	7187	2722 (0.8)
1159 (Opaque)		1.3			
1121 (Not dissolved)		3.2			
1201 (Suspension)		1.2	4.8	16100	13416 (4.0)
1204 (Opaque)		1.1			
1206 (Opaque)		2.7			
1642		275.1	5.8		(0.02)
1644		28.3			
1645		27.6	220.7		(8.0)
1701		1.4	4.9		(3.5)





1702		0.9	5.4		(6.0)
1710		0.8			
1711		0.4			

Table 8:

Time	Compound 1153 in solution at 0.1 mg/kg dose	Compound 1153 in solution at 0.3 mg/kg dose
0	0.31	0.00
15	5.33	288.97
30	19.59	276.16
60	56.74	241.03
120	106.43	107.19
180	100.94	56.41
240	75.71	26.42
300	44.51	20.81
360	29.15	10.10
480	13.01	4.66
1440	0.00	0.00

WHAT IS CLAIMED IS:

1. A compound having the formula:



wherein R^1 is a member selected from the group consisting of C_1 - C_8 alkyl, aryl C_0 - C_8 alkyl, C_3 - C_{12} cycloalkyl and heterocyclyl, each optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C_1 - C_8 alkyl, C_1 - C_8 heteroalkyl, aryl, heteroaryl; wherein said cyclic portions are monocyclic or polycyclic;

Y^1 is selected from the group consisting of a bond, $C(R^5)_2$, NR^5 and O;

Y^2 is selected from the group consisting of a bond, NR^5 and O;

each R^2 , R^3 and R^5 is independently selected from the group consisting of H, alkyl and COR^6 ;

A is heterocyclyl, optionally substituted with from 1 to 2 R^7 substituents;

L is selected from the group consisting of a direct bond, C_1 - C_{12} alkylene, C_1 - C_{12} heteroalkylene, C_3 - C_6 cycloalkylene, arylene, heteroarylene, -CO-, - SO_m - and -Se-;

R^4 is selected from the group consisting of H, C_1 - C_8 alkyl, C_2 - C_6 alkenyl, C_2 - C_6 alkynyl, C_1 - C_8 heteroalkyl, aryl C_0 - C_8 alkyl, C_3 - C_{12} cycloalkyl and heterocyclyl, each optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C_1 - C_8 alkyl, halo, C_1 - C_8 heteroalkyl, aryl C_0 - C_8 alkyl, COR^6 , $S(O)_mR^6$ and heteroaryl;

each R^6 is independently selected from the group consisting of H, C_1 - C_8 alkyl, OH, C_1 - C_8 alkoxy and amino;

each R^7 is selected from the group consisting of halo, nitro, C_1 - C_8 alkyl, C_1 - C_8 alkylamino, hydroxy C_1 - C_8 alkyl, halo C_1 - C_8 alkyl, carboxyl, hydroxyl, C_1 - C_8 alkoxy, C_1 - C_8 alkoxy C_1 - C_8 alkoxy, halo C_1 - C_8 alkoxy, thio C_1 - C_8 alkyl, aryl, aryloxy, C_3 - C_8 cycloalkyl, C_3 - C_8 cycloalkyl C_1 - C_8 alkyl, heteroaryl, aryl C_1 - C_8 alkyl, heteroaryl C_1 - C_8 alkyl, C_2 - C_8 alkenyl containing 1 to 2 double bonds, C_2 - C_8 alkynyl containing 1 to 2 triple bonds, C_4 - C_8 alk(en)(yn)yl groups, cyano, formyl, C_1 - C_8 alkylcarbonyl, arylcarbonyl, heteroarylcarbonyl, C_1 - C_8 alkoxycarbonyl, aryloxycarbonyl, aminocarbonyl, C_1 - C_8 alkylaminocarbonyl, C_1 - C_8 dialkylaminocarbonyl, arylaminocarbonyl, diarylaminocarbonyl, aryl C_1 - C_8 alkylaminocarbonyl, halo C_1 - C_8 alkoxy, C_2 - C_8 alkenyloxy, C_2 - C_8 alkynyloxy, aryl C_1 - C_8 alkoxy, amino C_1 - C_8 alkyl, C_1 - C_8 alkylamino C_1 - C_8 alkyl, C_1 - C_8 dialkylamino C_1 - C_8 alkyl,

arylaminoC₁-C₈alkyl, amino, C₁-C₈dialkylamino, arylamino, arylC₁-C₈alkylamino, C₁-C₈alkylcarbonylamino, arylcarbonylamino, azido, mercapto, C₁-C₈alkylthio, arylthio, haloC₁-C₈alkylthio, thiocyano, isothiocyano, C₁-C₈alkylsulfinyl, C₁-C₈alkylsulfonyl, arylsulfinyl, arylsulfonyl, aminosulfonyl, C₁-C₈alkylaminosulfonyl, C₁-C₈dialkylaminosulfonyl and arylaminosulfonyl;

the subscript n is an integer of 0 to 1;

the subscript m is an integer of from 0 to 2; and


pharmaceutically acceptable derivatives thereof.

2. The compound in accordance with claim 1, wherein Y¹ is NR⁵.
3. The compound in accordance with claim 2, wherein Y² is a bond.
4. The compound in accordance with claim 2, wherein Y² is NR⁵.
5. The compound in accordance with claim 2, wherein Y² is O.
6. The compound in accordance with claim 1, wherein Y² is NR⁵.
7. The compound in accordance with claim 6, wherein Y¹ is a bond.
8. The compound in accordance with claim 6, wherein Y¹ is C(R⁵)₂.
9. The compound in accordance with claim 6, wherein Y¹ is O.
10. The compound in accordance with claim 6, wherein Y¹ is NR⁵.
11. The compound in accordance with claim 1, wherein R², R³ and R⁵ are H.
12. The compound in accordance with claim 1, wherein A is selected from the group consisting of piperidinyl, 1,3,5-triaza-tricyclo[3.3.1.1^{3,7}]decyl, indolyl, pyridyl, morpholinyl and benzimidazolyl.
13. The compound in accordance with claim 1, wherein A is piperidinyl.
14. The compound in accordance with claim 1, wherein A is 1,3,5-triaza-tricyclo[3.3.1.1^{3,7}]decyl.

15. The compound in accordance with claim 1, wherein A is indolyl.
16. The compound in accordance with claim 1, wherein A is pyridyl.
17. The compound in accordance with claim 1, wherein A is morpholinyl.
18. The compound in accordance with claim 1, wherein A is

benzimidazolyl.

19. The compound in accordance with claim 1 having the formula:



wherein R^1 is a member selected from the group consisting of C_1 - C_8 alkyl, aryl C_0 - C_8 alkyl, C_3 - C_{12} cycloalkyl and heterocyclyl, optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C_1 - C_8 alkyl, C_1 - C_8 heteroalkyl, aryl, heteroaryl; wherein said cycloalkyl portions are monocyclic or polycyclic;

L is selected from the group consisting of a direct bond, C_1 - C_{12} heteroalkylene, -CO- and -SO_m-;

R^4 is selected from the group consisting of H, C_1 - C_8 alkyl, aryl C_0 - C_8 alkyl, C_3 - C_{12} cycloalkyl and heterocyclyl, each optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C_1 - C_8 alkyl, halo, C_1 - C_8 heteroalkyl, aryl C_0 - C_8 alkyl, COR⁶, S(O)_mR⁶ and heteroaryl;


each R^6 is independently selected from the group consisting of H, C_1 - C_8 alkyl, C_1 - C_8 alkoxy and amino;

the subscript n is an integer of 0 to 1;

the subscript m is an integer of from 0 to 2; and

pharmaceutically acceptable derivatives thereof.

20. The compound in accordance with claim 1 having the formula:



wherein R^1 is a member selected from the group consisting of C_1 - C_8 alkyl, aryl C_0 - C_8 alkyl, C_3 - C_{12} cycloalkyl and heterocyclyl, optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C_1 - C_8 alkyl, C_1 - C_8 heteroalkyl, aryl, heteroaryl; wherein said cycloalkyl portions are monocyclic or polycyclic;

L is selected from the group consisting of a direct bond, C_1 - C_{12} heteroalkylene, -CO- and - SO_m -;

R^4 is selected from the group consisting of H, C_1 - C_8 alkyl, aryl C_0 - C_8 alkyl, C_3 - C_{12} cycloalkyl and heterocyclyl, each optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C_1 - C_8 alkyl, halo, C_1 - C_8 heteroalkyl, aryl C_0 - C_8 alkyl, COR^6 , $S(O)_mR^6$ and heteroaryl;


each R^6 is independently selected from the group consisting of H, C_1 - C_8 alkyl, C_1 - C_8 alkoxy and amino;

the subscript n is an integer of 0 to 1;

the subscript m is an integer of from 0 to 2; and

pharmaceutically acceptable derivatives thereof.

21. The compound in accordance with claim 1 having the formula:



wherein R^1 is a member selected from the group consisting of C_1 - C_8 alkyl, aryl C_0 - C_8 alkyl, C_3 - C_{12} cycloalkyl and heterocyclyl, optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C_1 - C_8 alkyl, C_1 - C_8 heteroalkyl, aryl, heteroaryl; wherein said cycloalkyl portions are monocyclic or polycyclic;

L is selected from the group consisting of a direct bond, C_1 - C_{12} heteroalkylene, -CO- and - SO_m -;

R^4 is selected from the group consisting of H, C_1 - C_8 alkyl, aryl C_0 - C_8 alkyl, C_3 - C_{12} cycloalkyl and heterocyclyl, each optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C_1 - C_8 alkyl, halo, C_1 - C_8 heteroalkyl, aryl C_0 - C_8 alkyl, COR^6 , $S(O)_mR^6$ and heteroaryl;


each R^6 is independently selected from the group consisting of H, C_1 - C_8 alkyl, C_1 - C_8 alkoxy and amino;

the subscript n is an integer of 0 to 1;

the subscript m is an integer of from 0 to 2; and

pharmaceutically acceptable derivatives thereof.

22. The compound in accordance with claim 1 having the formula:



wherein R^1 is a member selected from the group consisting of C_1 - C_8 alkyl, aryl C_0 - C_8 alkyl, C_3 - C_{12} cycloalkyl and heterocyclyl, optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C_1 - C_8 alkyl, C_1 - C_8 heteroalkyl, aryl, heteroaryl; wherein said cycloalkyl portions are monocyclic or polycyclic;

L is selected from the group consisting of a direct bond, C_1 - C_{12} heteroalkylene, $-CO-$ and $-SO_m-$;

R^4 is selected from the group consisting of H, C_1 - C_8 alkyl, aryl C_0 - C_8 alkyl, C_3 - C_{12} cycloalkyl and heterocyclyl, each optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C_1 - C_8 alkyl, halo, C_1 - C_8 heteroalkyl, aryl C_0 - C_8 alkyl, COR^6 , $S(O)_mR^6$ and heteroaryl;


each R^6 is independently selected from the group consisting of H, C_1 - C_8 alkyl, C_1 - C_8 alkoxy and amino;

the subscript n is an integer of 0 to 1;

the subscript m is an integer of from 0 to 2; and

pharmaceutically acceptable derivatives thereof.

23. The compound in accordance with claim 1 having the formula:



wherein R^1 is a member selected from the group consisting of C_1 - C_8 alkyl, aryl C_0 - C_8 alkyl, C_3 - C_{12} cycloalkyl and heterocyclyl, optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C_1 - C_8 alkyl, C_1 - C_8 heteroalkyl, aryl, heteroaryl; wherein said cycloalkyl portions are monocyclic or polycyclic;

L is selected from the group consisting of a direct bond, C_1 - C_{12} heteroalkylene, -CO- and -SO_m-;

R^4 is selected from the group consisting of H, C_1 - C_8 alkyl, aryl C_0 - C_8 alkyl, C_3 - C_{12} cycloalkyl and heterocyclyl, each optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C_1 - C_8 alkyl, halo, C_1 - C_8 heteroalkyl, aryl C_0 - C_8 alkyl, COR⁶, S(O)_mR⁶ and heteroaryl;


each R^6 is independently selected from the group consisting of H, C_1 - C_8 alkyl, C_1 - C_8 alkoxy and amino;

the subscript n is an integer of 0 to 1;

the subscript m is an integer of from 0 to 2; and

pharmaceutically acceptable salts, solvates, hydrates, and prodrugs thereof.

24. The compound in accordance with claim 1 having the formula:



wherein R^1 is a member selected from the group consisting of C_1 - C_8 alkyl, aryl C_0 - C_8 alkyl, C_3 - C_{12} cycloalkyl and heterocyclyl, optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C_1 - C_8 alkyl, C_1 -

C₈heteroalkyl, aryl, heteroaryl; wherein said cycloalkyl portions are monocyclic or polycyclic;

L is selected from the group consisting of a direct bond, C₁-C₁₂heteroalkylene, -CO- and -SO_m-;

R⁴ is selected from the group consisting of H, C₁-C₈alkyl, arylC₀-C₈alkyl, C₃-C₁₂cycloalkyl and heterocyclyl, each optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C₁-C₈alkyl, halo, C₁-C₈heteroalkyl, arylC₀-C₈alkyl, COR⁶, S(O)_mR⁶ and heteroaryl;


each R⁶ is independently selected from the group consisting of H, C₁-C₈alkyl, C₁-C₈alkoxy and amino;

the subscript n is an integer of 0 to 1;

the subscript m is an integer of from 0 to 2; and

pharmaceutically acceptable salts, solvates, hydrates, and prodrugs thereof.

25. The compound in accordance with claim 1 having the formula:



wherein R¹ is a member selected from the group consisting of C₁-C₈alkyl, arylC₀-C₈alkyl, C₃-C₁₂cycloalkyl and heterocyclyl, optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C₁-C₈alkyl, C₁-C₈heteroalkyl, aryl, heteroaryl; wherein said cycloalkyl portions are monocyclic or polycyclic;

L is selected from the group consisting of a direct bond, C₁-C₁₂heteroalkylene, -CO- and -SO_m-;

R⁴ is selected from the group consisting of H, C₁-C₈alkyl, arylC₀-C₈alkyl, C₃-C₁₂cycloalkyl and heterocyclyl, each optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C₁-C₈alkyl, halo, C₁-C₈heteroalkyl, arylC₀-C₈alkyl, COR⁶, S(O)_mR⁶ and heteroaryl;


each R^6 is independently selected from the group consisting of H, C_1 - C_8 alkyl, C_1 - C_8 alkoxy and amino;

the subscript n is an integer of 0 to 1;

the subscript m is an integer of from 0 to 2; and

pharmaceutically acceptable derivatives thereof.

26. The compound in accordance with claim 1 having the formula:



wherein R^1 is a member selected from the group consisting of C_1 - C_8 alkyl, aryl C_0 - C_8 alkyl, C_3 - C_{12} cycloalkyl and heterocyclyl, optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C_1 - C_8 alkyl, C_1 - C_8 heteroalkyl, aryl, heteroaryl; wherein said cycloalkyl portions are monocyclic or polycyclic;

L is selected from the group consisting of a direct bond, C_1 - C_{12} heteroalkylene, -CO- and - SO_m -;

R^4 is selected from the group consisting of H, C_1 - C_8 alkyl, aryl C_0 - C_8 alkyl, C_3 - C_{12} cycloalkyl and heterocyclyl, each optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C_1 - C_8 alkyl, halo, C_1 - C_8 heteroalkyl, aryl C_0 - C_8 alkyl, COR^6 , $S(O)_mR^6$ and heteroaryl;


each R^6 is independently selected from the group consisting of H, C_1 - C_8 alkyl, C_1 - C_8 alkoxy and amino;

the subscript n is an integer of 0 to 1;

the subscript m is an integer of from 0 to 2; and

pharmaceutically acceptable salts, solvates, hydrates, and prodrugs thereof.

27. The compound in accordance with claim 1 having the formula:



wherein R^1 is a member selected from the group consisting of C_1 - C_8 alkyl, aryl C_0 - C_8 alkyl, C_3 - C_{12} cycloalkyl and heterocyclyl, optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C_1 - C_8 alkyl, C_1 - C_8 heteroalkyl, aryl, heteroaryl; wherein said cycloalkyl portions are monocyclic or polycyclic;

L is selected from the group consisting of a direct bond, C_1 - C_{12} heteroalkylene, -CO- and -SO_m-;

R^4 is selected from the group consisting of H, C_1 - C_8 alkyl, aryl C_0 - C_8 alkyl, C_3 - C_{12} cycloalkyl and heterocyclyl, each optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C_1 - C_8 alkyl, halo, C_1 - C_8 heteroalkyl, aryl C_0 - C_8 alkyl, COR⁶, S(O)_mR⁶ and heteroaryl;


each R⁶ is independently selected from the group consisting of H, C_1 - C_8 alkyl C_1 - C_8 alkoxy and amino;

the subscript n is an integer of 0 to 1;

the subscript m is an integer of from 0 to 2; and

pharmaceutically acceptable derivatives thereof.

28. The compound in accordance with claim 1 having the formula:



wherein R^1 is a member selected from the group consisting of C_1 - C_8 alkyl, aryl C_0 - C_8 alkyl, C_3 - C_{12} cycloalkyl and heterocyclyl, optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C_1 - C_8 alkyl, C_1 - C_8 heteroalkyl, aryl, heteroaryl; wherein said cycloalkyl portions are monocyclic or polycyclic;

L is selected from the group consisting of a direct bond, C_1 - C_{12} heteroalkylene, -CO- and -SO_m-;

R^4 is selected from the group consisting of H, C_1 - C_8 alkyl, aryl C_0 - C_8 alkyl, C_3 - C_{12} cycloalkyl and heterocyclyl, each optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C_1 - C_8 alkyl, halo, C_1 - C_8 heteroalkyl, aryl C_0 - C_8 alkyl, COR^6 , $S(\dot{O})_mR^6$ and heteroaryl;


each R^6 is independently selected from the group consisting of H, C_1 - C_8 alkyl, C_1 - C_8 alkoxy and amino;

the subscript n is an integer of 0 to 1;

the subscript m is an integer of from 0 to 2; and

pharmaceutically acceptable salts, solvates, hydrates, and prodrugs thereof.

29. The compound in accordance with claim 1 having the formula:



wherein R^1 is a member selected from the group consisting of C_1 - C_8 alkyl, aryl C_0 - C_8 alkyl, C_3 - C_{12} cycloalkyl and heterocyclyl, optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C_1 - C_8 alkyl, C_1 - C_8 heteroalkyl, aryl, heteroaryl; wherein said cycloalkyl portions are monocyclic or polycyclic;

L is selected from the group consisting of a direct bond, C_1 - C_{12} heteroalkylene, -CO- and - SO_m -;

R^4 is selected from the group consisting of H, C_1 - C_8 alkyl, aryl C_0 - C_8 alkyl, C_3 - C_{12} cycloalkyl and heterocyclyl, each optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C_1 - C_8 alkyl, halo, C_1 - C_8 heteroalkyl, aryl C_0 - C_8 alkyl, COR^6 , $S(O)_mR^6$ and heteroaryl;


each R^6 is independently selected from the group consisting of H, C_1 - C_8 alkyl, C_1 - C_8 alkoxy and amino;

the subscript n is an integer of 0 to 1;

the subscript m is an integer of from 0 to 2; and

pharmaceutically acceptable derivatives thereof.

30. The compound in accordance with claim 1 having the formula:



wherein R¹ is a member selected from the group consisting of C₁-C₈alkyl, arylC₀-C₈alkyl, C₃-C₁₂cycloalkyl and heterocyclyl, optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C₁-C₈alkyl, C₁-C₈heteroalkyl, aryl, heteroaryl; wherein said cycloalkyl portions are monocyclic or polycyclic;

L is selected from the group consisting of a direct bond, C₁-C₁₂heteroalkylene, -CO- and -SO_m-;

R⁴ is selected from the group consisting of H, C₁-C₈alkyl, arylC₀-C₈alkyl, C₃-C₁₂cycloalkyl and heterocyclyl, each optionally substituted with from 1 to 2 substituents each independently selected from the group consisting of C₁-C₈alkyl, halo, C₁-C₈heteroalkyl, arylC₀-C₈alkyl, COR⁶, S(O)_mR⁶ and heteroaryl;

each R⁶ is independently selected from the group consisting of H, C₁-C₈alkyl, C₁-C₈alkoxy and amino;

the subscript n is an integer of 0 to 1;

the subscript m is an integer of from 0 to 2; and

pharmaceutically acceptable derivatives thereof.

31. The compound in accordance with any of the preceding claims, wherein R¹ is C₁-C₈alkyl.

32. The compound in accordance with any of the preceding claims, wherein R¹ is selected from the group consisting of dodecyl and t-butyl.

33. The compound in accordance with any of the preceding claims, wherein R¹ is arylC₀-C₈alkyl.

34. The compound in accordance with any of the preceding claims, wherein R¹ is phenyl.

35. The compound in accordance with any of the preceding claims, wherein R¹ is C₃-C₁₂cycloalkyl.

36. The compound in accordance with any of the preceding claims, wherein R¹ is adamantyl.

37. The compound in accordance with any of the preceding claims, wherein R¹ is cycloheptyl or cyclohexyl.

38. The compound in accordance with any of the preceding claims, wherein R¹ is C₃-C₁₂cycloalkyl.

39. The compound in accordance with any of the preceding claims, wherein R¹ is adamantyl.

40. The compound in accordance with any of the preceding claims, wherein R¹ is cycloheptyl.

41. The compound in accordance with any of the preceding claims, wherein L is a direct bond.

42. The compound in accordance with any of the preceding claims, wherein L is C₁-C₁₂heteroalkylene.

43. The compound in accordance with any of the preceding claims, wherein L is -CO-.

44. The compound in accordance with any of the preceding claims, wherein L is -SO₂-.

45. The compound in accordance with any of the preceding claims, wherein R⁴ is selected from the group consisting of H, C₁-C₈alkyl, arylC₀-C₈alkyl and heterocyclyl.

46. The compound in accordance with any of the preceding claims, wherein R^6 is H.
47. The compound in accordance with any of the preceding claims, wherein R^6 is C_1 - C_8 alkyl.
48. The compound in accordance with any of the preceding claims, wherein n is 0.
49. The compound in accordance with any of the preceding claims, wherein n is 1.
50. The compound in accordance with any of the preceding claims, which has an IC_{50} against sEH of 150nM or less.
51. A compound selected from the group consisting of the compounds of Examples 1-70 and Tables 1-4 and 5a and 5b.
52. A pharmaceutical composition comprising a pharmaceutically acceptable excipient and a compound of any of claims 1 to 51.
53. A method for inhibiting a soluble epoxide hydrolase, comprising contacting said soluble epoxide hydrolase with an inhibiting amount of a compound of any of claims 1 to 51.
54. A method of treating diseases modulated by soluble epoxide hydrolases, said method comprising administering to a subject in need of such treatment an effective amount of a compound of any of claims 1 to 51.
55. The method in accordance with claim 54, wherein said disease is selected from the group consisting of hypertension, inflammation, adult respiratory distress syndrome; diabetic complications; end stage renal disease; Raynaud syndrome and arthritis.
56. The method in accordance with claim 54, wherein said treatment increases sodium excretion, reduces vascular and renal inflammation, and reduces male erectile dysfunction.

57. The method in accordance with claim **54**, wherein said hypertension is selected from the group consisting of renal hypertension, pulmonary hypertension and hepatic hypertension.

58. The method in accordance with claim **54**, wherein said inflammation is selected from the group consisting of renal inflammation, vascular inflammation, and lung inflammation.

59. A method for reducing renal deterioration in a subject, said method comprising administering to said subject an effective amount of a compound of any of claims **1** to **51**.

60. The method in accordance with claim **59**, wherein said renal deterioration is present in said subject afflicted with diabetes, hypertension or an inflammatory disorder.

61. A method for inhibiting progression of nephropathy in a subject, said method comprising administering to said subject an effective amount of a compound of any of claims **1** to **51**.

62. The method in accordance with claim **61** wherein the subject is (a) a person with diabetes mellitus whose blood pressure is 130/85 or less, (b) a person with metabolic syndrome whose blood pressure is 130/85 or less, (c) a person with a triglyceride level over 215 mg/dL, or (d) a person with a cholesterol level over 200 mg/dL.

63. A method for reducing blood pressure in a subject, said method comprising administering to said subject an effective amount of a compound of any of claims **1** to **51**.

64. The method in accordance with claim **63**, said method further comprising administering to said subject an effective amount of a cis-epoxyeicosatrienoic acid.

65. The method in accordance with claim **64**, wherein said cis-epoxyeicosatrienoic acid is administered with said compound having formula (I).

66. A method of inhibiting the progression of obstructive pulmonary disease, an interstitial lung disease, or asthma in a subject, said method comprising administering to said subject an effective amount of a compound of any of claims **1** to **51**.

67. The method in accordance with claim **66**, wherein said obstructive pulmonary disease is selected from the group consisting of chronic obstructive pulmonary disease, emphysema, and chronic bronchitis.

68. The method in accordance with claim **66**, wherein said interstitial lung disease is idiopathic pulmonary fibrosis or is one associated with exposure to dust.

69. The method in accordance with claim **66**, said method further comprising administering to said subject an effective amount of a cis-epoxyeicosantrienoic acid.

70. The method in accordance with claim **66**, wherein said cis-epoxyeicosantrienoic acid is administered with said compound having formula (I).

71. A method of reducing vascular inflammation in a subject, said method comprising administering to said subject an effective amount of a compound of any of claims **1** to **51**.

72. A method of reducing renal inflammation in a subject, said method comprising administering to a subject an effective amount of a compound of any of claims **1** to **51**.

73. A method of regulating endothelial cell function in a subject, said method comprising administering to said subject an effective amount of a compound of any of claims **1** to **51**.

74. A method of decreasing endothelial cell inflammation in a subject, said method comprising administering to said subject an effective amount of a compound of any of claims **1** to **51**.

75. The method for reducing the formation of a biologically active diol produced by the action of a soluble epoxide hydrolase, said method comprising contacting said soluble epoxide hydrolase with an amount of a compound of any of claims **1** to **51**,

sufficient to inhibit the activity of said soluble epoxide hydrolase and reduce the formation of said biologically active diol.

76. The method in accordance with claim 75, wherein said contacting is conducted in an *in vitro* assay.

77. The method in accordance with claim 75, wherein said contacting is conducted *in vivo*.

78. A method for monitoring the activity of a soluble epoxide hydrolase, said method comprising contacting said soluble epoxide hydrolase with an amount of a compound of any of claims 1 to 51 sufficient to produce a detectable change in fluorescence of said soluble epoxide hydrolase by interacting with one or more tryptophan residues present in the catalytic site of said sEH.

Figure 1

Pharmacokinetic profile of compounds with different piperidine substitutions given as a single oral dose of 0.3 mg/kg.




Figure 2

Pharmacokinetic profile of compounds 1153, 1555 and 1645.




Figure 3

Pharmacokinetic profile of compound 1153 following single oral administration 0.1 and 0.3 mg/kg orally.




Figure 4

Pharmacokinetic profile of compound **1153** and other compounds following single oral administration 0.3 mg/kg of canine model




Figure 5

Exposure of selected compounds as a function of inverse potency.

