



US 20090088206A1

(19) **United States**

(12) **Patent Application Publication**
Silverbrook et al.

(10) **Pub. No.: US 2009/0088206 A1**

(43) **Pub. Date: Apr. 2, 2009**

(54) **MOBILE TELECOMMUNICATIONS DEVICE WITH PRINTING AND SENSING MODULES**

Related U.S. Application Data

(75) Inventors: **Kia Silverbrook**, Balmain (AU);
Paul Lapstun, Balmain (AU);
Simon Robert Walmsley, Balmain (AU)

(63) Continuation of application No. 11/228,480, filed on Sep. 19, 2005, now Pat. No. 7,469,829.

Publication Classification

Correspondence Address:
SILVERBROOK RESEARCH PTY LTD
393 DARLING STREET
BALMAIN 2041 (AU)

(51) **Int. Cl.**
H04M 1/00 (2006.01)

(52) **U.S. Cl.** **455/556.1**


(57) **ABSTRACT**

(73) Assignee: **Silverbrook Research Pty Ltd**

A mobile telecommunications includes a mobile phone module. A printer module is operatively connected to the mobile phone module and includes a print engine controller. A tag sensor module is operatively connected to the mobile phone module and includes an image sensor and processor.

(21) Appl. No.: **12/276,357**

(22) Filed: **Nov. 23, 2008**






FIG. 1




FIG. 2




FIG. 3




FIG. 4




FIG. 5




FIG. 6



FIG. 7




FIG. 8




FIG. 9




FIG. 10




FIG. 11




FIG. 12




FIG. 13




FIG. 14




FIG. 15




FIG. 16




FIG. 17




FIG. 18




FIG. 19




FIG. 20




FIG. 21




FIG. 22




FIG. 23




FIG. 24




FIG. 25




FIG. 26




FIG. 27




FIG. 28




FIG. 29




FIG. 30




FIG. 31




FIG. 32




FIG. 33




FIG. 34




FIG. 35




FIG. 36




FIG. 37




FIG. 38




FIG. 39




FIG. 40




FIG. 41




FIG. 42




FIG. 43




FIG. 44




FIG. 45

| Contacts for John Smith | |
|------------------------------|-------------------------------|
| Miller, Maria: 186 655 2550 | Rodriguez, John: 144 454 5335 |
| Wilson, Susan: 151 425 0617 | Lewis, Robert: 252 340 840 |
| Moore, Margaret: 310 007 167 | Lee, Michael: 470 877 477 |
| Taylor, Dorothy: 697 367 671 | Walker, William: 170 482 2298 |

650

FIG. 46




FIG. 47




FIG. 48




FIG. 49




FIG. 50




FIG. 51




FIG. 52




FIG. 53




FIG. 54




FIG. 55





FIG. 56






FIG. 58




FIG. 59




FIG. 60




FIG. 61




FIG. 62




FIG. 63




FIG. 65




FIG. 66




FIG. 67




FIG. 68




FIG. 69




FIG. 70




FIG. 71




FIG. 72




FIG. 73




FIG. 74




FIG. 75




FIG. 76




FIG. 77




FIG. 78




FIG. 79




FIG. 80





FIG. 81



857
scan event

856

| | | |
|------------|----------------------------------|---------------------------------|
| target | | |
| operation | | |
| parameters | image/jpeg category = "photo" | <binary contents of jpeg image> |
| | | |
| | | |

858

FIG. 82




FIG. 83




FIG. 84




FIG. 85




FIG. 86




FIG. 87




FIG. 88




FIG. 89




FIG. 90




FIG. 91




FIG. 92




FIG. 95




FIG. 96




FIG. 97




FIG. 98




FIG. 99




FIG. 100




FIG. 101




FIG. 102




FIG. 103




FIG. 104




FIG. 105




FIG. 106




FIG. 107




FIG. 108



Silent Cry
 Breaking free
 Of other peoples shackles
 Isn't always easy

My life is my own
 I am what I want to be

Breaking free
 Of other peoples rules
 Isn't why I act this way

My life is my own
 I am what I want to be

MP3

email

920

FIG. 109



DigiRadio **Week 41**

Top 10

| This Week | Last Week | Title - Artist | Listen | Order |
|-----------|-----------|----------------------------------|--------|--------------------------|
| 1 | 1 | My Land -- Velvet 5 | | <input type="checkbox"/> |
| 2 | 3 | Secret Garden -- Silver Angels | | <input type="checkbox"/> |
| 3 | 2 | Lollipop -- Didi | | <input type="checkbox"/> |
| 4 | 6 | The Happy Ending -- Cowboy Girls | | <input type="checkbox"/> |
| 5 | 4 | High Energy -- Black Day | | <input type="checkbox"/> |
| 6 | 5 | Free Bird -- Satsia Keys | | <input type="checkbox"/> |
| 7 | - | Whitewash -- Berkley Boys | | <input type="checkbox"/> |
| 8 | 7 | She is Loved -- Old School | | <input type="checkbox"/> |
| 9 | - | Rain -- Planet Earth | | <input type="checkbox"/> |
| 10 | 8 | Last Dance -- John Mecury | | <input type="checkbox"/> |

Submit

930

FIG. 110




FIG. 111



FIG. 112

**WHO WANTS TO BE A
MILLIONAIRE**

**HOME VIEWER
QUESTION**

MY FINAL ANSWER IS:

A

B

C

D

MY ANSWER

960

FIG. 113

MOBILE TELECOMMUNICATIONS DEVICE WITH PRINTING AND SENSING MODULES

CROSS REFERENCE TO RELATED APPLICATION

[0001] This application is a continuation of U.S. application Ser. No. 11/228,480 filed on Sep. 19, 2005, all of which are herein incorporated by reference.

FIELD OF THE INVENTION

[0002] The present invention generally relates to a mobile device incorporating a printer. The invention more specifically relates to a mobile device such as a mobile telecommunications device, for example a mobile or cellular telephone that incorporates a printer which is able to print a wide variety of content on a print medium. However, it will be appreciated by those skilled in the art that the present invention can be used by other types of portable or mobile devices, or even non-portable devices.

COPENING APPLICATIONS

[0003] The following applications have been filed by the applicant simultaneously with the application Ser. No. 11/228,480:

Table with 5 columns of patent numbers: 11/228,540, 11/228,531, 11/228,482, 11/228,484, 11/228,488, 11/228,538, 11/228,527, 11/228,522, 11/228,509, 11/228,512, 11/228,481, 11/228,517, 11/228,478

[0004] The disclosures of these copending applications are incorporated herein by reference.

CROSS REFERENCES

[0005] The present patent application is a Continuation application of U.S. patent application Ser. No. 11/228,480, filed on Sep. 19, 2005. The following patents or patent applications filed by the applicant or assignee of the present invention are hereby incorporated by cross-reference:

Table with 5 columns of patent numbers: 6,405,055, 7,130,075, 10/919,381, 7,108,437, 6,750,901, 6,331,946, 6,374,354, 6,745,331, 10/636,263, 10/940,653, 7,099,051, 6,914,686, 11/003,418, 11/003,700

-continued

Large table with 5 columns of patent numbers: 11/003,698, 11/003,463, 11/003,684, 10/815,630, 7,097,094, 10/815,647, 10/815,641, 10/815,615, 10/815,614, 11/041,652, 11/041,627, 11/041,723, 10/815,626, 10/815,629, 10/550,895, 10/815,624, 10/913,372, 10/913,376, 11/172,814, 11/124,158, 11/124,197, 11/124,160, 11/124,152, 11/124,194, 11/124,150, 11/124,184, 11/124,161, 11/124,188, 11/124,180, 11/124,148, 11/187,976, 10/760,273, 7,090,336, 10/760,243, 10/760,209, 10/760,235, 10/760,231, 7,108,353, 6,991,322, 10/728,783, 10/728,779, 6,830,318, 7,118,202, 10/773,197, 7,118,201, 11/060,805, 11/097,299, 11/212,637, 11/084,742, 6,825,945, 6,824,044, 09/575,186, 6,976,220, 6,813,558, 6,720,985, 7,131,058, 6,973,450, 09/722,174, 10/291,471, 10/291,825, 7,009,738, 6,714,678, 10/291,510, 6,867,880, 10/291,525, 6,850,931, 10/685,455, 6,889,896, 10/943,874, 10/949,293, 10/981,626, 10/992,713, 11/020,321, 11/059,674, 11/082,827, 11/123,136

-continued

| | | | | |
|------------|------------|------------|------------|------------|
| 11/202,252 | 11/202,253 | 11/203,200 | 11/202,218 | 11/206,778 |
| 11/203,424 | 11/222,977 | 7,068,382 | 7,007,851 | 6,957,921 |
| 6,457,883 | 10/743,671 | 7,044,381 | 7,094,910 | 7,091,344 |
| 7,122,685 | 7,038,066 | 7,099,019 | 7,062,651 | 6,789,194 |
| 6,789,191 | 10/900,129 | 10/900,127 | 10/913,328 | 10/913,350 |
| 10/982,975 | 10/983,029 | 6,644,642 | 6,502,614 | 6,622,999 |
| 6,669,385 | 6,827,116 | 7,011,128 | 10/949,307 | 6,549,935 |
| 6,987,573 | 6,727,996 | 6,591,884 | 6,439,706 | 6,760,119 |
| 09/575,198 | 7,064,851 | 6,826,547 | 6,290,349 | 6,428,155 |
| 6,785,016 | 6,831,682 | 6,741,871 | 6,927,871 | 6,980,306 |
| 6,965,439 | 6,840,606 | 7,036,918 | 6,977,746 | 6,970,264 |
| 7,068,389 | 7,093,991 | 10/659,026 | 10/884,885 | 10/884,883 |
| 10/901,154 | 10/932,044 | 10/962,412 | 10/962,510 | 10/962,552 |
| 10/965,733 | 10/965,933 | 10/974,742 | 10/982,974 | 10/983,018 |
| 10/986,375 | 11/107,817 | 11/148,238 | 11/149,160 | 6,982,798 |
| 6,870,966 | 6,822,639 | 6,474,888 | 6,627,870 | 6,724,374 |
| 6,788,982 | 09/722,141 | 6,788,293 | 6,946,672 | 6,737,591 |
| 7,091,960 | 09/693,514 | 6,792,165 | 7,105,753 | 6,795,593 |
| 6,980,704 | 6,768,821 | 7,132,612 | 7,041,916 | 6,797,895 |
| 7,015,901 | 10/782,894 | 10/782,895 | 10/778,056 | 10/778,058 |
| 10/778,060 | 10/778,059 | 10/778,063 | 10/778,062 | 10/778,061 |
| 10/778,057 | 7,096,199 | 10/917,468 | 10/917,467 | 10/917,466 |
| 10/917,465 | 10/917,356 | 10/948,169 | 10/948,253 | 10/948,157 |
| 10/917,436 | 10/943,856 | 10/919,379 | 7,019,319 | 10/943,878 |
| 10/943,849 | 7,043,096 | 11/071,267 | 11/144,840 | 11/155,556 |
| 11/155,557 | 11/193,481 | 11/193,435 | 11/193,482 | 11/193,479 |
| 7,055,739 | 09/575,129 | 6,830,196 | 6,832,717 | 09/721,862 |
| 7,120,853 | 7,082,562 | 6,843,420 | 10/291,718 | 6,789,731 |
| 7,057,608 | 6,766,944 | 6,766,945 | 10/291,715 | 10/291,559 |
| 10/291,660 | 10/531,734 | 10/409,864 | 7,108,192 | 10/537,159 |
| 7,111,791 | 7,077,333 | 6,983,878 | 10/786,631 | 10/853,782 |
| 10/893,372 | 6,929,186 | 6,994,264 | 7,017,826 | 7,014,123 |
| 10/971,051 | 10/971,145 | 10/971,146 | 7,017,823 | 7,025,276 |
| 10/990,459 | 7,080,780 | 11/074,802 | 10/492,169 | 10/492,152 |
| 10/492,168 | 10/492,161 | 10/492,154 | 10/502,575 | 10/531,229 |
| 10/683,151 | 10/531,733 | 10/683,040 | 10/510,391 | 10/510,392 |
| 10/919,261 | 10/778,090 | 6,957,768 | 09/575,162 | 09/575,172 |
| 09/575,170 | 7,106,888 | 7,123,239 | 6,982,701 | 6,982,703 |
| 10/291,538 | 6,786,397 | 6,947,027 | 6,975,299 | 7,139,431 |
| 7,048,178 | 7,118,025 | 6,839,053 | 7,015,900 | 7,010,147 |
| 7,133,557 | 6,914,593 | 10/291,546 | 6,938,826 | 10/913,340 |
| 7,123,245 | 6,992,662 | 11/039,897 | 11/074,800 | 11/074,782 |
| 11/074,777 | 11/075,917 | 11/102,698 | 11/102,843 | 11/202,112 |
| 10/727,181 | 10/727,162 | 10/727,163 | 10/727,245 | 7,121,639 |
| 10/727,233 | 10/727,280 | 10/727,157 | 10/727,178 | 7,096,137 |
| 10/727,257 | 10/727,238 | 10/727,251 | 10/727,159 | 10/727,180 |
| 10/727,179 | 10/727,192 | 10/727,274 | 10/727,164 | 10/727,161 |
| 10/727,198 | 10/727,158 | 10/754,536 | 10/754,938 | 10/727,227 |
| 10/727,160 | 10/934,720 | 11/212,702 | 10/296,522 | 6,795,215 |
| 7,070,098 | 09/575,109 | 6,805,419 | 6,859,289 | 6,977,751 |
| 6,398,332 | 6,394,573 | 6,622,923 | 6,747,760 | 6,921,144 |
| 10/884,881 | 7,092,112 | 10/949,294 | 11/039,866 | 11/123,011 |
| 6,986,560 | 7,008,033 | 11/148,237 | 10/922,846 | 10/922,845 |
| 10/854,521 | 10/854,522 | 10/854,488 | 10/854,487 | 10/854,503 |
| 10/854,504 | 10/854,509 | 10/854,510 | 7,093,989 | 10/854,497 |
| 10/854,495 | 10/854,498 | 10/854,511 | 10/854,512 | 10/854,525 |
| 10/854,526 | 10/854,516 | 10/854,508 | 10/854,507 | 10/854,515 |
| 10/854,506 | 10/854,505 | 10/854,493 | 10/854,494 | 10/854,489 |
| 10/854,490 | 10/854,492 | 10/854,491 | 10/854,528 | 10/854,523 |
| 10/854,527 | 10/854,524 | 10/854,520 | 10/854,514 | 10/854,519 |
| 10/854,513 | 10/854,499 | 10/854,501 | 10/854,500 | 10/854,502 |
| 10/854,518 | 10/854,517 | 10/934,628 | 11/212,823 | 10/760,254 |
| 10/760,210 | 10/760,202 | 10/760,197 | 10/760,198 | 10/760,249 |
| 10/760,263 | 10/760,196 | 10/760,247 | 10/760,223 | 10/760,264 |
| 10/760,244 | 7,097,291 | 10/760,222 | 10/760,248 | 7,083,273 |
| 10/760,192 | 10/760,203 | 10/760,204 | 10/760,205 | 10/760,206 |
| 10/760,267 | 10/760,270 | 10/760,259 | 10/760,271 | 10/760,275 |
| 10/760,274 | 7,121,655 | 10/760,184 | 10/760,195 | 10/760,186 |
| 10/760,261 | 7,083,272 | 11/014,764 | 11/014,763 | 11/014,748 |
| 11/014,747 | 11/014,761 | 11/014,760 | 11/014,757 | 11/014,714 |
| 11/014,713 | 11/014,762 | 11/014,724 | 11/014,723 | 11/014,756 |
| 11/014,736 | 11/014,759 | 11/014,758 | 11/014,725 | 11/014,739 |
| 11/014,738 | 11/014,737 | 11/014,726 | 11/014,745 | 11/014,712 |
| 11/014,715 | 11/014,751 | 11/014,735 | 11/014,734 | 11/014,719 |
| 11/014,750 | 11/014,749 | 11/014,746 | 11/014,769 | 11/014,729 |
| 11/014,743 | 11/014,733 | 11/014,754 | 11/014,755 | 11/014,765 |

-continued

| | | | | |
|------------|------------|------------|------------|------------|
| 11/014,766 | 11/014,740 | 11/014,720 | 11/014,753 | 11/014,752 |
| 11/014,744 | 11/014,741 | 11/014,768 | 11/014,767 | 11/014,718 |
| 11/014,717 | 11/014,716 | 11/014,732 | 11/014,742 | 11/097,268 |
| 11/097,185 | 11/097,184 | 6,454,482 | 6,808,330 | 6,527,365 |
| 6,474,773 | 6,550,997 | 7,093,923 | 6,957,923 | 7,131,724 |
| 10/949,288 | 10/962,400 | 7,125,098 | 11/185,722 | 11/181,754 |
| 11/203,180 | 7,079,292 | | | |

BACKGROUND OF THE INVENTION

[0006] The assignee has developed mobile or cellular telephones, Personal Data Assistants (PDAs) and other mobile telecommunication devices, with the ability to print hard copies of content, such as images or information stored or accessed by the device, (see for example, U.S. Pat. No. 6,405,055, filed on Nov. 9, 1999). Likewise, the assignee has also designed digital cameras with the ability to print captured images with an in-built printer (see for example, U.S. Pat. No. 6,750,901, filed on Jul. 10, 1998). As the prevalence of mobile telecommunications devices increases, the functionality of these devices is further enhanced by the ability to print hard copies.

[0007] As these devices are portable, they should be compact for user convenience. Accordingly, any printer incorporated into the device needs to maintain a small form factor. Also, the additional load on the battery should be relatively small. Furthermore, the consumables (such as ink, paper, etc.) should be relatively inexpensive and simple to replenish. It is these factors that strongly influence the commercial success or otherwise of products of this type.

[0008] The assignee of the present invention has also developed the Netpage system for enabling interaction with computer software using a printed interface and a proprietary stylus-shaped sensing device. As described in detail in U.S. Pat. No. 6,792,165, filed on Nov. 25, 2000 and U.S. patent application Ser. No. 10/778,056, filed on Feb. 17, 2004, a Netpage pen captures, identifies and decodes tags of coded data printed onto a surface such as a page. In a preferred Netpage implementation, each tag encodes a position and an identity of the document. By decoding at least one of the tags and transmitting the position (or a refined version of the position, representing a higher resolution position of the pen) and identity referred to by the decoded tag, a remote computer can determine an action to perform. Such actions can include, for example, causing information to be saved remotely for subsequent retrieval, downloading of a webpage for printing or display via a computer, bill payment or even the performance of handwriting recognition based on a series of locations of the Netpage pen relative to the surface.

[0009] When printing a Netpage, a printer in a mobile telecommunications device can print the Netpage tags simultaneously with visible user information. The association between the tags and information can already exist on a remote Netpage server, such as where the printer is printing a fully rendered page (including tags) provided by the Netpage server or another computer. Alternatively, the mobile telecommunications device can generate the tags (or source them remotely) and define an association between the tags and user information. The association is then recorded in the remote Netpage server.

[0010] A problem with these options is that they require the mobile telecommunications device to include Netpage tag

printing capabilities. This requires an additional row of print nozzles in the printhead, and reduces the amounts of ink that can be stored for non-tag use. Whilst this is less of an issue with large, mains-powered printers, it can be an issue in small form-factor articles such as mobile telecommunications devices. Alternatively, the mobile telecommunications device can be configured to print on print media that is pre-printed with Netpage tags. That way the printer need only print the user information and record an association between the visible information and the pre-printed tags.

[0011] It is desirable to provide functional applications making use of the mobile telecommunications device. Such applications can include, for example, mobile printing applications, linking, capturing and/or printing generic or specific objects to a print medium, and many other applications providing functionality to the mobile telecommunications device and various uses of types of print media.

SUMMARY OF THE INVENTION

[0012] In one particular, but non-limiting, aspect, an M-Print device is a mobile device such as a telephone or PDA which incorporates a printer. Paper is either manually presented or auto-fed from a cartridge, depending on device form factor. The printer may or may not print tags, for example infrared tags, and the printer or a sensor detects tags printed, for example pre-printed, onto blank media. The paper path either includes a tag reader, or it includes a simpler sensor for reading a linear data track on the card. The data track can encode the same identifier as the tags. Reading the identifier allows the M-Print device to associate the card's graphic and/or interactive content with the identifier. This allows subsequent interactions with the card to be properly interpreted. The graphic and/or interactive content is stored on a network-based server, indexed by the identifier.

[0013] It should be noted that the media identifier (i.e. print media identifier) may correspond to a range of 2D coordinates without an explicit single media identifier. Hence, reference to the media identifier is to be read as a reference to an explicit or defined one or more media identifiers, or, as a reference to a range of 2D coordinates.

[0014] The device also optionally incorporates a pointer. The pointer may be used to click on a hyperlink, but generally doesn't operate at a sufficiently high rate to capture motion. Alternatively, the telephone may incorporate a fully-functional Netpage-type pen. Even when the M-Print device doesn't incorporate a pointer, the user can interact with printed cards by feeding them through the paper path. The data track reader or tag reader in the paper path extracts the identifier, which allows the device to identify the graphic and/or interactive content of the card, and object(s) linked to the card. Not all M-Print cards have to be produced by an M-Print device. For example, pre-printed M-Print cards of a collectible or promotional nature may be included in cereal packets or magazines. And even blank media may bear advertising on the reverse side. Not all M-Print cards have to be interacted with via a pointer in an M-Print device. They can be interacted with via any device, or another scanning device altogether which can read the data track or an application-specific printed barcode.

[0015] An M-Print card acts as a token for the graphic and/or interactive content of the card, including any objects linked to the card. A user can easily obtain the original digital content of the card by clicking on the card or 'virtually scanning' the card through the paper path. For example, a photo

acts as a token for the original digital image, and a business card acts as a token for the contact details linked to the card. By acting as a token for its own content, a card allows a user to obtain a perfect re-print. In addition to the identifier, the data track and the tags encode a digital signature which allows the card to be authenticated. This has two purposes. Firstly, it allows a blank card to be authenticated during printing to prevent the use of non-sanctioned blanks. Secondly, it allows a card to be authenticated when used as a token, to prevent fraudulent access to the content of the card or objects linked to the card.

[0016] Various applications are possible using aspects, components or features of the mobile telecommunications device and associated coded print medium. Such applications can include mobile printing applications, linking, capturing and/or printing generic or specific objects to a print medium, and many other applications providing practical uses for the coded print medium and/or the mobile telecommunications device. Various particular applications are herein described.

[0017] In a first aspect the present invention system for printing video information on a print medium, the system comprising:

[0018] a mobile telecommunications device which comprises:

[0019] a printer module to print the video information on the print medium; and,

[0020] a sensor module to sense a print media identifier of the print medium.

[0021] Optionally information associated with the video information is optionally stored in an archives.

[0022] Optionally the sensor module is used to link the video information to the print media identifier.

[0023] Optionally the print medium is provided with coded data in a format, the coded data encoding information, at least some of the information being indicative of the print media identifier.

[0024] Optionally the format is a linear pattern.

[0025] Optionally the information is further indicative of a two-dimensional coordinate grid, and the format is a two-dimensional pattern.

[0026] Optionally the printer module prints at least some of the coded data on the print medium.

[0027] Optionally the system further including use of a database to store an association of the video information with the print media identifier.

[0028] Optionally the print medium is provided with first coded data in a first format and second coded data in a second format, the first coded data encoding first information and the second coded data encoding second information, at least some of the first information being indicative of the print media identifier, the first format being a linear pattern, at least some of the second information being indicative of the print media identifier and of a two-dimensional coordinate grid, the second format being a two-dimensional pattern.

[0029] Optionally the database is at least one of stored locally at the mobile telecommunications device and stored remotely at a server.

[0030] Optionally the mobile telecommunications device including:

[0031] a media feed path, such that when the print medium is presented in the media feed path at least some of the coded data is read using the sensor module, and the print media identifier is determined using the at least some read coded data.

[0032] Optionally information associated with the video information can be subsequently retrieved from the archive using the print media identifier.

[0033] Optionally the print medium includes at least one interactive element associated with a linked object, and the linked object is associated with a region of the print medium using the second coded data, and the linked object is stored in an object repository.

[0034] Optionally printing requires paying for the video information using the mobile telecommunications device.

[0035] Optionally the information is further indicative of at least part of a digital signature associated with the print media identifier, the sensor module determining, by reading at least some of the coded data, at least part of the digital signature, and the printer module printing, if the digital signature is authentic, the video information.

[0036] Optionally the printed video information is a permission token readable using the sensor module to at least one of: retrieve information associated with the video information from the archive; receive video via the mobile telecommunications device; receive a video file; receive streaming video; initiate payment for the video information; initiate payment for video associated with the video information; select a video channel; select a video source; select a television channel; obtain a copy of the video information; and gain access to a resource.

[0037] Optionally printing the video information causes information associated with the video information to be archived.

[0038] Optionally the information associated with the video information includes one or more of: the video information; a visual description of the video information; a video clip; an image of the video information; an interactive description of the video information; contents of the video information; a video stream; a video track; a video channel; recorded video; synthesized video; an animation; a video effect; a video source; a television channel; a television station; and video information details.

[0039] Optionally the video information includes at least one of: television program information; movie information; lyrics; words of a song; musical notes; a musical score; a song title; a movie title; a program title; information about a video; a name of a musician; a name of a producer; a name of a director; a name of an actor; and information about a person.

[0040] Optionally the video information is associated with video played on the mobile telecommunications device.

BRIEF DESCRIPTION OF THE DRAWINGS

[0041] An example embodiment of the present invention should become apparent from the following description, which is given by way of example only, of a preferred but non-limiting embodiment, described in connection with the accompanying figures.

[0042] FIG. 1 illustrates an example High Level Architecture;

[0043] FIG. 2 illustrates example M-Doc Retriever Components;

[0044] FIG. 3 illustrates an example Nugget Generation Service;

[0045] FIG. 4 illustrates an example Player;

[0046] FIG. 5 illustrates an example PlayRequest;

[0047] FIG. 6 illustrates example Values, Types and Categories;

[0048] FIG. 7 illustrates an example interactive business card;

[0049] FIG. 8 illustrates an example Player Sequence;

[0050] FIG. 9 illustrates an example RequestRouter and related classes;

[0051] FIG. 10 illustrates an example UserRequestRouter;

[0052] FIG. 11 illustrates a typical arrangement of routers and player agents in a Netpage system;

[0053] FIG. 12 illustrates example Capability and Request Propagation;

[0054] FIG. 13 illustrates an example Capability Aggregation;

[0055] FIG. 14 illustrates an example Capability Transformation;

[0056] FIG. 15 illustrates example PlayerProfiles;

[0057] FIG. 16 illustrates an example Printed Interface for selecting the current player profile;

[0058] FIG. 17 illustrates example PlayRequests embedded in an interactive document;

[0059] FIG. 18 illustrates an example Request Routing;

[0060] FIG. 19 illustrates an example Synchronous Messaging Sequence Diagram;

[0061] FIG. 20 illustrates an example Asynchronous Messaging Communication Sequence;

[0062] FIG. 21 illustrates an example Streaming Messaging Sequence;

[0063] FIG. 22 illustrates an example Interactive Messaging Sequence;

[0064] FIG. 23 illustrates an example Hybrid Messaging Sequence;

[0065] FIG. 24 illustrates an example Player Session Sequence Diagram;

[0066] FIG. 25 illustrates an example Player Session Detailed Sequence Diagram;

[0067] FIG. 26 illustrates an example Desktop Player Deployment;

[0068] FIG. 27 illustrates an example Short-Range Thin Mobile Player Deployment;

[0069] FIG. 28 illustrates an example Long-Range Thin Mobile Player Deployment;

[0070] FIG. 29 illustrates an example Smart Mobile Player;

[0071] FIG. 30 illustrates an Object association being displayed in a physical Player Device;

[0072] FIG. 31 illustrates an Object association being displayed in the Explorer application;

[0073] FIG. 32 illustrates a Creation of an impression object association;

[0074] FIG. 33 illustrates an example Tagged Sticker;

[0075] FIG. 34 illustrates an example Reusable Sticker;

[0076] FIG. 35 illustrates an example Sticker with "Confirm Action";

[0077] FIG. 36 illustrates an example Sticker with limited interactive areas to prevent accidental invocation of destructive operations;

[0078] FIG. 37 illustrates example Category Specific Stickers;

[0079] FIG. 38 illustrates an example Swipe based printed toolbar for creating impression associations;

[0080] FIG. 39 illustrates an example Swipe Based Sticker with Transparent Region;

[0081] FIG. 40 illustrates an example Swipe Based Sticker with Graphics over the Transparent Region;

[0082] FIG. 41 illustrates an example Impression Associations Object Model;

- [0083] FIG. 42 illustrates example Field Associations in the Netpage Server;
- [0084] FIG. 43 illustrates an example Object Association Sample Application;
- [0085] FIG. 44 illustrates an example Underlying Form;
- [0086] FIG. 45 illustrates an example Overlaid Form;
- [0087] FIG. 46 illustrates an example Printed Contacts with Phone Numbers;
- [0088] FIG. 47 illustrates an example State machine for basic clipboard interaction;
- [0089] FIG. 48 illustrates an example interactive Netpage card with common operations;
- [0090] FIG. 49 illustrates an example State machine for operation based clipboard;
- [0091] FIG. 50 illustrates simultaneously supporting both object first and command first models;
- [0092] FIG. 51 illustrates example Single use clipboard entries;
- [0093] FIG. 52 illustrates an example Single-use clipboard with timeouts;
- [0094] FIG. 53 illustrates an example Multi-use clipboard with timeouts;
- [0095] FIG. 54 illustrates an example Interactive card for selecting a printer;
- [0096] FIG. 55 illustrates example Field details of printer selection card;
- [0097] FIG. 56 illustrates an example Netpage form containing various commands;
- [0098] FIG. 57 illustrates an example Command form showing details of office printer field;
- [0099] FIG. 58 illustrates an example SMS Based Downloadable Content Purchase;
- [0100] FIG. 59 illustrates an example Netpage Play Sequence for Previewing a Ringtone;
- [0101] FIG. 60 illustrates an example Using play requests to deliver the product;
- [0102] FIG. 61 illustrates an example Using play requests to purchase the product, and traditional delivery;
- [0103] FIG. 62 illustrates an example Hybrid approach using traditional delivery on the last hop to the handset;
- [0104] FIG. 63 illustrates an example Load card;
- [0105] FIG. 64 illustrates an example Validating an ID;
- [0106] FIG. 65 illustrates an example High level printing sequence;
- [0107] FIG. 66 illustrates an example High level sequence diagram for uploading from a mobile device;
- [0108] FIG. 67 illustrates an example High level sequence diagram for downloading to a mobile device, using a SMS alert to trigger the download;
- [0109] FIG. 68 illustrates an example Sequence fragment showing the processing of scanned ID;
- [0110] FIG. 69 illustrates an example Local Photo Printing Sequence;
- [0111] FIG. 70 illustrates an example Printing Uploads to a Photo Archive;
- [0112] FIG. 71 illustrates an example Capturing a Netpage document via printing;
- [0113] FIG. 72 illustrates an example Business Card;
- [0114] FIG. 73 illustrates example Business Card Phone Number Fields;
- [0115] FIG. 74 illustrates an example Business Card Fax Field;
- [0116] FIG. 75 illustrates an example Business Card Web URL Field;
- [0117] FIG. 76 illustrates example Business Card SMS and MMS Fields;
- [0118] FIG. 77 illustrates an example Business Card Email Field;
- [0119] FIG. 78 illustrates an example Street Address Field;
- [0120] FIG. 79 illustrates an example Business Card Photo and Name Field;
- [0121] FIG. 80 illustrates an example Business Card Identifier Field;
- [0122] FIG. 81 illustrates an example Printed photo card;
- [0123] FIG. 82 illustrates example Interactive fields for photo card;
- [0124] FIG. 83 illustrates an example Scanning of an M-Print printout;
- [0125] FIG. 84 illustrates an example Sequence diagram for generating Netpage clicks from a mobile device GUI;
- [0126] FIG. 85 illustrates a schematic representation of the modular interaction in a printer/mobile phone;
- [0127] FIG. 86 illustrates a schematic representation of the modular interaction in a tag sensor/mobile phone;
- [0128] FIG. 87 illustrates a schematic representation of the modular interaction in a printer/tag sensor/mobile phone;
- [0129] FIG. 88 is a more detailed schematic representation of the architecture within the mobile phone of FIG. 87;
- [0130] FIG. 89 is a more detailed schematic representation of the architecture within the mobile phone module of FIG. 88;
- [0131] FIG. 90 is a more detailed schematic representation of the architecture within the printer module of FIG. 88;
- [0132] FIG. 91 is a more detailed schematic representation of the architecture within the tag sensor module of FIG. 88;
- [0133] FIG. 92 is a schematic representation of the architecture within a tag decoder module for use instead of the tag sensor module of FIG. 88;
- [0134] FIG. 93 illustrates an exploded perspective view of a "candy bar" type mobile phone embodiment;
- [0135] FIG. 94 illustrates a partially cut away front and bottom view of the embodiment shown in FIG. 93;
- [0136] FIG. 95 illustrates a partially cut away rear and bottom view of the embodiment shown in FIG. 93;
- [0137] FIG. 96 illustrates a front elevation of the embodiment shown in FIG. 93 with a card being fed into the entry slot;
- [0138] FIG. 97 illustrates a cross section view taken along line A-A of FIG. 96;
- [0139] FIG. 98 illustrates a cross section view taken along line A-A of FIG. 96 with the card emerging from the media exit slot of the mobile phone;
- [0140] FIG. 99 illustrates a lateral cross section through a print cartridge;
- [0141] FIG. 100 illustrates the media coding on the card with separate clock and data tracks;
- [0142] FIG. 101 illustrates a block diagram of an M-print system that uses media with separate clock and data tracks;
- [0143] FIG. 102 illustrates a simplified circuit diagram for an optical encoder;
- [0144] FIG. 103 illustrates a block diagram of the MoPEC with the clock and data inputs;
- [0145] FIG. 104 illustrates a block diagram of the optional edge detector and page sync generator for the M-print system of FIG. 101;
- [0146] FIG. 105 illustrates a block diagram of a MoPEC that uses media with a pilot sequence in the data track to generate a page sync signal;

[0147] FIG. 106 illustrates a schematic representation of the position of the encoders along the media feed path.

[0148] FIG. 107 illustrates an example word game/puzzle printed on a print medium;

[0149] FIG. 108 illustrates an example crossword printed on a print medium;

[0150] FIG. 109 illustrates an example song lyrics printed on a print medium;

[0151] FIG. 110 illustrates an example top music list printed on a print medium;

[0152] FIG. 111 illustrates an example movie channel highlights printed on a print medium;

[0153] FIG. 112 illustrates an example sport highlight printed on a print medium;

[0154] FIG. 113 illustrates an example TV show interaction card printed on a print medium.

DETAILED DESCRIPTION OF THE PREFERRED EMBODIMENTS

[0155] The following modes, given by way of example only, are described in order to provide a more precise understanding of the subject matter of a preferred embodiment or embodiments. In the figures, incorporated to illustrate features of an example embodiment, like reference numerals are used to identify like parts throughout the figures.

1.0 Printing Internet Based Content Product Architecture

[0156] An example of a M-Print print media is the size of a business card. In general, documents or web based materials that have been designed for display on a desktop monitor or to be printed on A4 or Letter paper and may not print well on such sized media. If the content is reduced for the business card media then the content may be too small for easy reading. If multiple pages of media are used to print a page then the user is required to assemble the pages in the correct order before the printout is meaningful. To have presentable, effective content on a business card sized media the content should be specifically authored for that sized media. Described herein is a general mechanism to allow the authors and providers of web applications and web sites to make explicit use of the new media size, such as a business card.

[0157] The term “Mobile Document” or M-Doc is herein used to refer to documents specifically authored to be printed via M-Print. The format of a “Mobile Document” (i.e. print medium) may vary, it can be pre-rendered and in a format ready to be sent directly to the printer, or it can be in a higher level format that requires rendering before printing. On some mobile devices it is not possible to render the “Mobile Document” on the device, thus the “Mobile Document” is rendered before being sent to the mobile device. In regard of other mobile devices, the “Mobile Document” can be sent in the high level format and rendered on the mobile device. In general, to be able to render on the device the “Mobile Document” format is provided in an encapsulated format that contains the data necessary to render the M-Doc. Thus, by providing the M-Doc in an encapsulated format, the M-Doc does not necessarily have to rely on a particular font or bitmap being available on the mobile device (i.e. mobile telecommunications device).

[0158] A common usage of a “Mobile Document” is for the author of a web page to summarise contents of the web-page in a “Mobile Document”, which will herein be referred to as a “Nugget”, and to provide a link on the page for users to print

the nugget. When the web page is static HTML the content of the nugget can also be static. If the web page is dynamic HTML then it is likely the content of the nugget may also have to be dynamically created.

[0159] Current 2.5 G mobile data networks have low bandwidth, high latency, and are expensive to transfer data over. The emerging 3 G networks improve the bandwidth and latency but are still expensive to transfer data over. Mobile carriers tend to subsidise some of the data transfer mechanisms to encourage use, so it is possible to have a situation where it is significantly cheaper to send data via an MMS than it is to transfer it via a HTTP request over the same network. For this reason the proposed architecture supports multiple ways of delivering an M-Doc to a mobile device. The architecture is also designed to minimise the number of requests that need to be made from the device to retrieve a M-Doc and to also to minimise the amount of data that needs to be transferred to the device to transmit an M-Doc.

[0160] There are three messaging services in common use in the mobile networks at the moment: SMS (Short Message Service), EMS (Enhanced Message Service and MMS) (Multimedia Message Service). SMS is generally designed for sending text only messages up to 160 characters long. EMS is an enhanced version of SMS consisting of several SMS messages clustered together. This mechanism is used to deliver ring tones, etc to handsets. Both SMS and EMS are implemented using existing mechanisms in the GSM or CDMA networks and do not require IP based bearers such as GPRS. MMS provides the ability to send a mixture of multimedia formats such as images, sound and movies along with a definition of how to use these multimedia formats using the Synchronized Multimedia Integration Language, SMIL. MMS does not have any theoretical size limits. MMS is implemented on top of IP bearers and requires GPRS or one the 3 G equivalents to be deployed. Since MMS uses IP bearers it is not able to self-transfer or “push” itself out to a handset, instead it uses SMS to alert the user to the fact that an MMS message is waiting in the network for the user to retrieve, so it requires a “push” and “pull” to retrieve the message, whereas SMS requires a single “push” and EMS is delivered by multiple “pushes”.

1.1 High Level Architecture

[0161] Referring to FIG. 1, a M-Doc 500 residing in the network 501 generally requires delivery to the mobile device 100 before it can be printed. There are two ways in which a request to retrieve and print an M-Doc 500 can originate:

[0162] 1—direct user action, typically clicking on a link on a web page; or

[0163] 2—the arrival of an SMS or MMS containing a M-Doc reference 507 or an M-Doc 500 itself.

[0164] A M-Doc Retriever 502 is a component responsible for fetching an M-Doc 500. The M-Doc 500 is then passed to the M-Doc Printing Service 503 and printed. The following sections explain each of these major components and their inputs and outputs in more detail.

1.1.1 Web/WAP Browser

[0165] The Web Browser 504 is a third party application available on the mobile device 100. It is used by the user to browse web pages. A web site that supports printing M-Docs 500 includes web pages that contain M-Doc Reference links. When the user clicks on a M-Doc Reference link, a M-Doc

500 reference is returned to the browser **504**. The M-Doc reference **507** can be handled by the browser **504** in a number of ways dependent upon the operating system running on the mobile device **100**.

[0166] It is also possible for the M-Doc Retriever **502** to be activated directly by passing the M-Doc Retriever **502** a web page reference. This triggers a Nugget Creation service **506** to generate a Nugget for the website which the web page reference is associated with. The ability to generate a meaningful Nugget for a website depends on the content of the website.

1.1.2 M-Doc Retriever

[0167] The M-Doc retriever **502** is activated by the arrival of M-Doc reference **507** to the device.

[0168] Referring to FIG. 2, the M-Doc Retriever **502** is responsible for taking a M-Doc Reference **507** and resolving it to an M-Doc **500** to be passed onto the M-Doc Printing Service **503**. There are a number of ways that a M-Doc Reference **507** can be supplied to the M-Doc Retriever **502**:

[0169] 1. MIME type recogniser **508**—This can be activated either by clicking on a link in a web page that causes an “HTTP Get” of an object whose MIME type is an M-Doc reference **507**. Or it can be activated by the arrival on the mobile device of an Obex transfer **511**.

[0170] 2. Message Monitor **509**—This is a component that monitors the Inbox of the Messaging Service on the mobile device. When it receives a message from any source that contains an M-Doc reference **507**, the Message Monitor **504** passes the M-Doc reference **507** onto the M-Doc Retriever **502**.

[0171] 3. Web browser plugin **510**—This is triggered by explicit scripting code in a web page being browsed on a web browser **504**. When the Web browser plugin is activated, it is passed a M-Doc reference **507** which is passed onto the M-Doc Retriever **502**.

[0172] The M-Doc Retriever **502** receives the M-Doc Reference **507** which is in the format of a URI (Uniform Resource Identifier). The M-Doc Retriever **502** appends device specific information to URI and is dispatched via an HTTP request to the M-Doc Retrieval Service **512** running on the device. Device specific information that is appended to the URI is dependent upon how the system has been deployed and the capabilities of the device.

[0173] If a Mobile Device Capability Service **513** is deployed in the network **501** then the device specific information appended only requires identification the handset, via IMEI. If the Mobile Device Capability Service **513** is not deployed in the network **501** then the device **100** is required to append information relating to the printer **4**, the formats of M-Doc's **500** the device **100** is capable of printing and the preferred delivery method. The printer information required is deployment specific. If the renderer is able to look up the printer characteristics based on the handset or a printer version number then only those need to be provided, but if not, then information relating the printers resolution and colour space parameters are required.

[0174] The M-Doc URI that is supplied by the application is used to retrieve the M-Doc **500**. This URI contains information needed to retrieve or generate the M-Doc **500** from the application **514**. If the format of the returned M-Doc **500** matches the format(s) the device **100** is capable of printing, then the document **500** is delivered to the device **100**. If there is an unsuccessful match, the M-Doc **500** is rendered. This is performed by passing the document **500** to the rendering

service **515** along with the printer information. The rendering service returns the document in a pre-rendered format which can be printed by a mobile device **100** containing a printer **4**.

[0175] The way in which the M-Doc **500** is delivered back to the M-Doc retriever **502** can also vary. It may be returned in the reply to the original HTTP request or it may be sent via an MMS or e-mail. These later two cases are most likely to be used in an environment where the pricing policy of a carrier encourages MMS or email use over general web browsing. The preferred delivery method may be included in the retrieval request or it may be looked up via the Mobile Device Capability Service **513**.

[0176] The Rendering Service **515** may also be used directly by application writers who want to provide pre-rendered M-Doc's within their application. In this case the Rendering Service **515** is accessed via SOAP (Simple Object Access Protocol) as a web service, providing the M-Doc **500** in its authored format and obtaining the pre-rendered print format document and a thumbnail image for use in a GUI **516** of the application **514** running on the device **100**.

[0177] When an MMS **517** is sent to the mobile device **100**, the MMS **517** is stored in the mobile network at a MMS Message Centre **518** and an SMS is sent to the device to alert the user an MMS **517** is waiting to be fetched. With a modification this notification mechanism can be used to deliver an M-Doc **500** to a phone **100**. The SMS notification can contain both an M-Doc reference **507** and an MMS notification. The request to fetch the MMS from the Message Centre **518** can be enhanced with the M-Doc reference **509**, allowing the Message Centre **518** to contact the M-Doc Retrieval Service **512** to retrieve the M-Doc **500** in the body of the MMS **517**. This service is called an M-Doc MMS service.

[0178] Any email, MMS, Obex or web page may contain a direct M-Doc **500** rather than an M-Doc Reference **507**. In this case the M-Doc **500** is passed directly onto the M-Doc Printing Service **503**. Unless the sender of the message knows the capability of the handset receiving the M-Doc **500**, the M-Doc **500** may not be able to be rendered appropriately, hence the M-Doc Reference **507** approach is preferred, but in some cases, such as a subscription, the sender may know the capabilities of the handset and hence be able to by-pass the M-Doc Retrieval process and deliver the M-Doc **500** directly.

1.1.3 M-Doc Printing Service

[0179] The M-Doc Printing Service **503** prints the document **500** to the printer **4** in the mobile device **100**. M-Doc's **500** may have different document formats, but the M-Doc Retriever stage ensures that it retrieves an M-Doc **500** in a format that can be printed by the mobile device **100** without any further network interactions.

1.1.4 Nugget Production

[0180] A Nugget is the distillation of the content of a web page onto an M-Print sized printout. In general this not only involves reducing the web layout so that the content fits onto the M-Print printout. The process also involves selecting the key pieces of information on the web page and explicitly composing an M-Doc **500** that presents the information appropriately. Nugget support can be provided in two ways:

[0181] 1. As part of the design of the application **514**

[0182] 2. By a nugget generating service **519**.

[0183] Providing nugget support as part of the design of web application **514** requires the author of the web interface

to provide a link to a nugget on the web page. Depending on the nature of the web content the nugget could either be statically authored along with the page or it could be dynamically authored based on the dynamic content on the web page.

[0184] For web sites that do not support Nuggets as part of the interface, nuggets can be generated by a nugget generation service 519.

[0185] Referring to FIG. 3, the Nugget Generation Service 519 is activated when a special form of a M-Doc Reference 507 is passed to the M-Doc Retriever 502 on the mobile device 100, which references a web page rather than an M-Doc. The Nugget Retrieval Service detects this and passes the request onto the Nugget Creation Service 519.

[0186] The Nugget Creation Service 519 generates a nugget for the supplied web page in one of two ways:

[0187] 1. If the supplied web page comes from an explicitly supported web application, it passes the web page onto the nugget generator for that web application. Common web applications such as: Google, e-bay, Yahoo, Wikipedia and Amazon could be supported.

[0188] 2. If the web page is not from a supported application, then the contents is scaled to fit into an M-Doc 500.

[0189] The nugget generator for supported applications include knowledge of the structure of the web page and the main purpose of the web application, and thus be able to extract information from the key fields and present that in a nugget. For example:

[0190] A Google web page could be distilled to a nugget by showing the: search criteria; the top ten hits; how many other hits where returned.

[0191] An Amazon web page could be distilled to showing the contents of the shopping cart.

[0192] A Wikipedia web page could be distilled to the term and the definition.

1.2 Applications

[0193] This section discusses some applications of Internet Based M-Document printing architecture. Any M-Doc 500 can be Netpage enabled.

1.2.1 Daily Subscription Services

[0194] Many people buy the daily newspapers to access a few small sections of the paper, eg. puzzles, crosswords or cartoons. Using M-Doc printing it is possible for a user to browse online to the content and then request a printout of the content of their choice. To avoid having to browse each day, a subscription service that “pushes” the user’s desired sections out to them each day can be set up. The service could use: SMS, MMS or e-mail to “push” the M-Doc References out to the mobile device. The user can then print then content of the subscription when required.

[0195] Some of the sections of a newspaper that would suit this form of distribution are:

[0196] Crossword puzzles: Crossword grid on one sheet; clues on another.

[0197] Number puzzles, eg. Sudoku

[0198] Jokes

[0199] Cartoons

[0200] Local Weather

1.2.2 Navigation and Location Based Services

[0201] Web services such as “WhereIs” (www.whereis.com) provide both the ability to get a list of directions to go from one location to another and/or a map. Using a mobile device’s browser 504 the user can enter the destination and their current location and then have the map and directions delivered as an M-Doc 500 to be printed.

[0202] This gives a more convenient presentation of the map and directions to refer to while driving. Also in many regions in the world it is illegal to look at a mobile phone while driving, but it is not illegal to consult a map or written directions.

[0203] Mobile devices 100 that support location services are able to supply their location automatically. In this case it is only necessary to specify the destination to receive a map and/or a set of directions to print.

[0204] As well as assisting navigation, location based services can be used to present of list of possible destinations. For example:

[0205] A service that prints out the list of restaurants within walking distance;

[0206] Directions to the closest Service Station (or any type of shop);

[0207] Directions to the closest public transport stop.

1.2.3 Company Business Cards

[0208] Corporate websites often promote a company’s public image, this can be extended by providing the ability to print a “Company Business Card” that gives the general information about the company and its general contact details. As well as a general “Company Business Card”, individual departments could easily have their own business cards, eg. the Service Department contact details.

[0209] Web sites for companies normally have a page dedicated to how to find them, that is, directions on how to get to their buildings from major transport hubs. These sites could easily include M-Documents 500 showing maps of:

[0210] How to get to the company’s premises

[0211] Where the closest parking is

[0212] Where the closest Hotel is

[0213] Directions on how to navigate from one building to another.

1.2.4 Discount Coupon/Voucher

[0214] Discount coupons can be delivered by M-Documents 500. These can be delivered via the web as part of an advertisement, either directly with the advertisement containing a link to a M-Document 500 or a coupon could be delivered to the mobile device as a reward for clicking through an advertisement to the companies web site.

[0215] A company could “push” out via SMS, MMS or e-mail vouchers to members of their loyalty scheme or just to the general public as a promotion. Another variation on this scheme is the ability to deliver a voucher or coupon to a user who enters a competition or votes on-line. For example, using an SMS to vote on a reality TV show could result in an MMS

being returned with a coupon for a prize, or voting from a web site could return an M-Doc 500 with an advertisement and the possibility of a prize.

1.2.5 On-Line Receipts

[0216] When performing on-line transactions from a mobile device 100 a receipt for the transaction can be returned via an M-Doc 500. This gives a printout that can be filed with a user's other receipts. The receipts can contain bar codes and/or be Netpage enabled to allow the transaction to be recalled on-line on demand. Some example on-line transactions this could be used for are:

- [0217] Betting, the nugget can record: the selected options, the odds, the money wagered and the possible payouts;
- [0218] Banking, the nugget can be similar to an EFTPOS receipt;
- [0219] Purchasing, the nugget can be similar to a shop receipt;
- [0220] Paying bills;
- [0221] Taxi payment

1.2.6 Ticketing

[0222] For tickets that do not require magnetic stripes it is possible to deliver them over-the-air at the time of purchase. This could included: Public transport tickets; Theme park ride tickets; Theatre tickets; Cinema tickets.

1.2.7 Web CAM Print

[0223] While viewing a web cam on your mobile device, a user can select print and have an M-Document 500 of the image at that time sent to the users phone.

1.2.8 On-Line Gaming

[0224] On-line games can use Nuggets to provide additional information about the game. They can be used to provide: Cheat sheets; Maps; Character summaries; Brag cards, to demonstrate what level you have reached; Vouchers or Coupons as rewards for achievement.

2. Player Architecture

[0225] A Netpage Player 520 is a physical or virtual device capable of "playing" requests of various types. A play request 521 consists of three parts:

- [0226] 1. The target 522, which specifies which player 520 the request 521 should be played.
- [0227] 2. The operation 523, which specifies the action to be performed.
- [0228] 3. A set of values 524, which are supplied as parameters to the operation 523'.

[0229] Typically play requests 521 arise in response to user actions. For example, the user clicks on a tagged surface with a Netpage pointer, or interacts with an application that is in contact with the Netpage system. Play requests 521 can be used to provide a simple feedback mechanism (such as a request to display a text string to the user), or may be used to cause more sophisticated interactions with physical devices (such as setting the thermostat temperature on a home air conditioning system).

[0230] Individual players 520 can be associated with a user 525 as shown in FIG. 4. A user 525 may be associated with

multiple players 520 each of which supports the playing of possibly overlapping sets of PlayRequests 521.

[0231] It is likely that in many cases a single physical NetpagePlayer device 520 is shared between multiple users 525. For example, a hi-fi audio system in a family room may be configured as an audio player for multiple members of the family. For the sake of brevity, this section focuses on cases where physical players are exclusively used by a single user, however, it will be appreciated that this section may be applied to multiple users.

[0232] Central to the NetpagePlayer 520 concept is the notion of a PlayRequest 521 which are objects that represent a request to perform an operation on some device. This sections describes various details related to PlayRequests 521.

2.1 Structure of a PlayRequest

[0233] A PlayRequest (see FIG. 5) consists of three parts, each of which is optional:

- [0234] 1. An optional target 522 which specifies which Netpage player 520 the request 521 should be played,
- [0235] 2. An optional operation 523 which specifies the type of action to be performed on the target player 522, and
- [0236] 3. An optional list of values 524 which are supplied as parameters to the operation 523.

[0237] A play request 521 may either be fully or partially specified. A fully specified play request completely specifies all of the information (target, operation, and parameters) required to unambiguously deliver the request to the target 522 and to perform the desired operation 532. A partially specified play request provides some indication of the request 521 to be played, but does not provide enough information in order for the play request 521 to be successfully delivered and played without further processing.

[0238] A target 522 may either fully or partially specify the target 522 of a play request 521. A fully specified target completely identifies the physical player 520 on which the request 521 should be played. A partially specified target provides some indication of the desired target 522, but does not provide enough information in order for the play request 521 to be delivered without further processing. An operation 523 can also be fully or partially specified. A Value 524 consists of a physical type 525 and associated data 526. For example, the physical type 525 might be "image/jpeg" and the data 526 would be the binary image data.

2.2 Values and Types

[0239] A Value 524 represents an instance of some physical type 525. Each Value 524 has an associated physical type 525 and zero or more associated type categories. The physical type identifies the structure of the data element of the Value 524. A possible mechanism would be to use MIME types. For example, if the physical type 525 is image/jpeg then the data element would contain the binary data of an image in jpeg format.

[0240] Referring to FIG. 6, a Value is also optionally associated with one or more Categories 527. A Category 527 is used to provide additional information about the value 524 which may allow it to be handled more sensibly by the system (i.e. to allow a PlayRequest to be better matched against the capabilities of candidate targets during request routing). As an example, an image value produced by a digital camera may have the physical type 525 image/jpeg, but may also be associated with a category 527 of "photo", whereas an image

value produced by a fax package might also have the physical type 525 image/jpeg, but could be associated with a category 527 of “facsimile” or with no category at all.

[0241] RequestRouters can take into account both the physical type 525 of a value 524 and the categories 527 to which it belongs when determining the most appropriate way to handle a request 521.

2.3 Sample PlayRequests

[0242] To better demonstrate the PlayRequest concept, this section provides a number of sample PlayRequests 521. A PlayRequest 521 can be viewed in tabular form as shown below by example in Table 1.

TABLE 1

| | |
|------------|--|
| target | <identification of the target of the request> |
| operation | <the name of the operation to be performed> |
| parameters | <physical type and categories of parameter 1> <value of parameter 1> |
| ... | ... |
| ... | <physical type and categories of parameter n> <value of parameter n> |

[0243] Firstly, the Request 1 shows a fully specified PlayRequest 521 for dialing a number on a specific mobile phone.

| Request 1 | |
|------------|--------------------------|
| target | mobile-phone-xyz56474238 |
| operation | dial |
| parameters | phone-number “555 6754” |

[0244] The target field 522 is fully specified and indicates that the request 521 is to be performed on the device 520 identified by the name/address “mobile-phone-xyz56474238”. Note that for simplicity, simple text strings to indicate the address of each physical target 522. The play request 521 contains an operation of “dial” which is understood by the mobile phone’s NetpagePlayer 520. The request 521 also includes a phone number which is a required parameter 528 to the “dial” operation 523.

[0245] As shown below, Request 2 is only partially specified due to only containing a partially specified target 522. The target 522 specifies that the request 521 should be played on a mobile phone, but does not specify which mobile phone.

| Request 2 | |
|------------|-------------------------|
| target | mobile phone |
| operation | dial |
| parameters | phone-number “555 6754” |

[0246] Request 3 shown below is also only partially specified. In this case, the target 522 has been completely left out. Although only being partially specified, the request 521 has a definite meaning: “dial the phone number 555 6754”. The device to be used to dial the number is still to be determined.

| Request 3 | |
|------------|-------------------------|
| target | |
| operation | dial |
| parameters | phone-number “555 6754” |

[0247] Request 4 is even less fully specified than Request 3. Request 4 simply contains the phone number “555 6754”. The operation to be performed with the number and the device to handle the request (the target) is still to be determined and the device to handle the request (the target) is still to be determined.

| Request 4 | |
|------------|-------------------------|
| target | |
| operation | |
| parameters | phone-number “555 6754” |

[0248] Request 5 contains a fully specified target 522, but does not specify an operation 523. Thus, the target of the request 521 is known, but what the target 522 is to do with the request (the operation) is still to be determined.

| Request 5 | |
|------------|--------------------------|
| target | mobile-phone-xyz56474238 |
| operation | |
| parameters | phone-number “555 6754” |

[0249] Request 6 can be used to send a simple text message to the user. The target 522 is not specified, so the request means display the following message on whichever player is the most appropriate at the current time.

| Request 6 | |
|------------|--|
| target | |
| operation | display |
| parameters | text “Temperature in Sydney is 28° C.” |

2.4 Invocation of PlayRequests

[0250] Play requests 521 can arise in one of two ways:

[0251] 1. The user interacts with a printed Netpage form that has been authored to include invocations of play requests 521.

[0252] 2. An arbitrary application sends a play request 521 to a Netpage Server 529.

[0253] These are discussed in the following sections.

2.4.1 Authored PlayRequests

[0254] PlayRequests 521 can be authored directly into a printed Netpage document. FIG. 7 provides an example of an interactive business card 530. The business card 530 contains interactive elements 531 that can be triggered by clicking on them with a Netpage pointer. Each interactive element causes a PlayRequest 521 to be invoked. The Netpage Server 529 then arranges for the request 521 to be played by routing it to the appropriate player device 520.

[0255] For example, referring to FIG. 7, consider a user with a Netpage-enabled mobile phone device 100 with a built-in Netpage pointer. The user clicks on the mobile phone icon 532 on the business card 530 which causes the PlayRequest 521 to be triggered. The server 529 routes the play request 521 to the user's mobile phone 100 and upon receiving the request 521, the mobile phone 100 commences dialing the required number.

2.4.2 Application Invoked PlayRequests

[0256] FIG. 8 shows a typical example of an application invoked PlayRequest 521. The steps are as follows:

- [0257] 1. A Netpage pen 533 transmits a digital ink stroke 534 to the Netpage Server 529.
- [0258] 2. The stroke 534 is determined to be a request 521 to submit a Netpage form for processing.
- [0259] 3. The form is submitted to the corresponding Application 535.
- [0260] 4. As part of the form submission processing, the application 535 requests that a play request 521 be played by a Netpage Player 520 associated with the user 525 who made the submission.
- [0261] 5. The Server 529 determines the target device 522 and relays the play request 521 to that device 522.

2.5 Player Devices

[0262] Netpage Player instances can be deployed on various Player devices (platforms). Individual players support some subset of the full range of PlayRequests 521 supported by Netpage. Table 2 shows some examples of Netpage Player Devices.

digital camera of a mobile phone is capable of capturing images), access to such captured data is not accessible via the Netpage Player concept, but can be accessed via a Netpage Clipboard, which will be discussed in more detail.

2.6 Request Processing

[0264] This sections describes how PlayRequest objects 521 are processed throughout the Netpage system. The processing of requests includes two operations:

- [0265] 1. The routing of requests 521 from one Netpage-Player 520 to another.
- [0266] 2. The transformation of PlayRequests 521 (for example to change a partially specified request more specified) as they are being routed.

2.6.1 Request Routing

[0267] A play request 521 is routed from source to the eventual destination via one or more intermediary RequestRouters 536 as shown in FIG. 9. RequestRouters 536 implement the NetpagePlayer interface, and are responsible for routing each PlayRequest 521 they receive to an appropriate target NetpagePlayer 520. Each RequestRouter 536 maintains a set of potential targets 538. Eventually a PlayRequest 521 arrives at a PlayerAgent 537 which is responsible for actually performing the play request 521.

[0268] All PlayRequests 521 from (or on behalf of) a user 525 are initially handled by a RequestRouter 536 inside the Netpage Server 529. This router is called the UserRequestRouter 539 (see FIG. 10). Typically the UserRequestRouter 539 forwards requests to a RequestRouter 536 residing on a physical device, although such forwarding may pass through

TABLE 2

Example Netpage Player Devices

| Player Device | Comments |
|-------------------------|--|
| Desktop Player 585 | This device is a powerful computing unit usually with fixed network connectivity. A desktop player is capable of playing a wide range of PlayRequests (e.g. audio, video, image, html, etc). The player can interact with various external software/hardware components running on the device. |
| Thin Mobile Player 587 | This device is a mobile unit with limited computing power such as web-enabled or low-end mobile phones. The thin player running on such mobile device is capable of playing various PlayRequests by utilizing the capabilities of the device. Examples include sending SMS objects, dialling phone number objects, etc. Due to the processing limitations of the device, a remote server (Netpage and Application Server) processes the input strokes/clicks and provides the objects to the player. |
| Smart Mobile Player 588 | This device is a mobile unit with more computing and storage capabilities, such as a high-end smart mobile phone or a PDA. Such device is capable of enabling most of the Netpage functionality by running a Micro edition of the Netpage Server locally. In such an environment, the player can receive PlayRequests from the local server (running on the device) and no on-line connectivity to a remote server peer would be necessarily required at the time of playing. |
| Embedded Player | An embedded player is a custom device that is built for a specific application. Examples of such players are Digital Camera, capable of playing (i.e. showing) images and possibly video; or Audio Player, capable of playing audio. The Netpage player is either built into the device or as a detachable unit. |

[0263] Note that while some of the devices mentioned in Table 2 are also capable of recording/capturing objects (e.g. a

arbitrary number of intermediary RequestRouters 536 along the way. Device based RequestRouters 536 are respon-

sible for routing requests **521** to the various player agents **537** running on the device. The typical scenario is shown in FIG. **11**. The UserRequestRouter **539** has a set of potential targets **538** which are all RequestRouters **536** residing on physical devices. Each device's RequestRouter **536** then has a set of potential PlayerAgent targets. The PlayerAgents are the NetpagePlayers **520** that actually play requests **521**.

2.6.2 Request Transformation

[**0269**] Each RequestRouter **536** can optionally transform the PlayRequest **521** it receives before passing it on to a subsequent NetpagePlayer **520**. The transformation typically produces a more fully specified version of the supplied PlayRequest **521**, but may also produce a completely new PlayRequest **521** with no fields in common with the source PlayRequest **521**.

2.6.3 Player Capabilities

[**0270**] Different players have different capabilities. That is, each player is capable of playing a different set of PlayRequests **521**. The capabilities of a NetpagePlayer **520** are specified in a CapabilitySpecification **540**. The capabilities **541** of each child player are taken into account by RequestRouters **536** when handling PlayRequests **521**. The capabilities **541** of different players may overlap, potentially resulting in ambiguous PlayRequests **521**. Such ambiguities are resolved by RequestRouters using methods described in further detail below. The CapabilitySpecification **540** is not limited to simply specifying which operations **523** can be performed on which value types **524**. It may also specify finer grained details. For a specific PlayRequest **521** the CapabilitySpecification **540** might specify that it can only handle a subset of possible values. For example, a player **520** that supports the playing of audio objects could place a limitation on the size of audio objects supported.

2.6.3.1 Capability and Request Propagation

[**0271**] As shown in FIG. **12**, a PlayerAgent **537** advertises its capabilities **541** to its parent RequestRouter **542** which in turn propagates the aggregation of its children's capabilities **544** to its parent RequestRouter **543**. Eventually the propagation reaches the UserRequestRouter **539** which then has an overall view of the capabilities **545** of all of the players at its disposal. PlayRequest propagation moves in the opposite direction. Requests **521** start at the UserRequestRouter which determines the most appropriate child to which the request should be sent. The (possibly transformed) request is sent to the selected child which in turn propagates the request to one of its children. Eventually the request reaches a PlayerAgent **537** which is responsible for actually playing the request.

2.6.3.2 Capability Aggregation and Transformation

[**0272**] As a RequestRouter propagates player capabilities (**541**, **544**, **545**) to its parent RequestRouter **536**, it may perform capability aggregation and transformation. Capability Aggregation is where the router **536** combines the capabilities of its children into a single capability specification **548**. Capability Transformation is where the router **536** modifies the advertised capabilities of its children due to capabilities (or perhaps limitations) of the router itself.

[**0273**] FIG. **13** provides an example of a simple capability aggregation. The router has two children **550**, **551**, the first child **550** of which advertises the capability to display jpeg

images, the second child advertises the capability **553** to display plain text. The router **536** then aggregates the child capabilities **552**, **553** into a single capability specification **540** which is capable of displaying both jpeg images and plain text.

[**0274**] FIG. **14** provides an example of a capability transformation. The PlayerAgent **537** advertises its capability **555** to display image/jpegs. The RequestRouter **536** has access to an image converter **559** that can convert images in png format to jpeg format. As such, the capability specification **555** is transformed before propagation into a capability specification **556** that includes the ability to display files in png format as well as in jpeg format.

2.6.4 Dynamic Capabilities

[**0275**] The capabilities advertised by a particular NetpagePlayer **520** can change over time. For example:

[**0276**] 1. Additional hardware or software can be installed/removed to/from a device, enabling the player to support more/less PlayRequests **521**.

[**0277**] 2. The maximum object size supported by a player may change depending on the spare capacity in the player's memory.

[**0278**] 3. A mobile player might be capable of receiving streaming media when it is connected to the network through a high-bandwidth network.

[**0279**] 4. Common user interactions with the player (e.g. starting an application, changing a setting) can cause the player to advertise more or less capabilities.

[**0280**] Such changes in capabilities are to be communicated to the player's parent RequestRouter **536**, and potentially, but not always, to the parent's parent, and so on all the way to the UserRequestRouter **539**.

[**0281**] At the same time, as dynamic capability changes are being propagated, requests **521** are being routed in the opposite direction (as shown in FIG. **12**). This creates a race condition between capability propagation and request routing, such that by the time a request arrives at a RequestRouter **536**, either the request can no longer be handled by the player **520**, or the player **520** is no longer the most appropriate recipient for that request **521**. Either case may require that a request **521** be rejected by the player **520** (be it a router or an agent) and re-routed to the appropriate player **520**.

[**0282**] Additionally, dynamic propagation of capability changes could potentially cause an undesirable level of network traffic, harming overall system performance.

2.6.5 Request Handling by the UserRequestRouter

[**0283**] As already discussed, all PlayRequests **521** presented to the NetpageServer **529** are handled by the UserRequestRouter **539**. The purpose of the UserRequestRouter **539** is twofold: (i) To determine the most appropriate child NetpagePlayer (the target **522**) to which the request **521** should be routed; and (ii) To determine any required transformations to the request **521** that are necessary in order for the selected target **521** to be able to handle the request **521**.

[**0284**] In order to determine both of the above, the UserRequestRouter **539** takes into account the content of the PlayRequest **521** and the context within which it is handled. The context includes a large range of factors, including, but not limited to the following:

- [0285] 1. The capabilities of each of the available children NetpagePlayers. Availability being partially determined by the user identity.
- [0286] 2. The current contents of the Netpage clipboard.
- [0287] 3. The originating source of the request (e.g. the Netpage pointer device which triggered the play request) and/or the route via which the request arrived.
- [0288] 4. The current player profile.
- [0289] 5. The current date and time.

2.6.6 Player Profiles

[0290] It is possible that multiple players registered with a user support the same PlayRequests 521. As a concrete example, consider the following scenario where a user has registered the following players. The user 525 has three registered players 520 all of which are capable of playing images:

- [0291] A camera phone for playing phone numbers, plain text, and images.
- [0292] A digital camera for playing images.
- [0293] A desktop application for playing plain text, html, images, video and audio.

[0294] Now consider the case where the UserRequestRouter 539 receives the following partially specified PlayRequest 521:

| | | |
|------------|---------|-------------------|
| target | display | |
| operation | image | contents of image |
| parameters | | |

[0295] The request 521 could potentially be played on any of the devices 520 mentioned. As such, the request 521 is ambiguous.

[0296] PlayerProfiles 557 are one mechanism which can be used in order to allow the UserRequestRouter 539 to resolve such ambiguities. A PlayerProfile 557 provides a (typically restricted) view of the set of players 520 available for a particular user 525 and the set of PlayRequests 521 that can be played on those players 520. A user 525 may have multiple player profiles 525 indicating the various scenarios within which they use the Netpage system. At any point in time, one of these profiles 525 is set as the Current Profile 558 as shown in FIG. 15.

[0297] For example, a user might have the following profiles:

- [0298] An “office” profile that directs most player requests to their desktop PC.
- [0299] A “home” profile that directs requests to various devices throughout the user’s house.
- [0300] A “mobile” profile that directs player requests to various portable devices (e.g. a smart phone).
- [0301] A “car” profile that directs player requests to devices within the user’s automobile.

[0302] A user can quickly change their current profile by a simple user action. For example, if in the office, the user could select the profile via a desktop GUI. Alternatively the user could use their Netpage pen/pointer to select a profile from a printed interface 559 such as that shown in FIG. 16. The

system could also allow a user to specify regular scheduled times at which their current profile should switch.

2.6.7 An Example Request Routing

[0303] Consider the interactive business card 530 shown in FIG. 7. The business card contains a number of interactive elements including the two fields 560, 561 highlighted in FIG. 17. Each of the fields 560, 561 is represented by a partially specified PlayRequest 562, 563. Clicking on either field 560, 561 with a Netpage pointer causes the corresponding play request 562, 563 to be submitted to the Netpage Server 529 for processing.

[0304] FIG. 18 provides an example of how such a field might be routed. At step 564 we have the original play request as submitted to the server. At step 565 the UserRequestRouter interrogates the PlayRequest and the current context, and determines that the request should be routed to the user’s mobile phone. As such it transforms the original PlayRequest to produce the request shown in step 566 and routes the play request to the RequestRouter on the mobile phone. At step 567 the mobile phone’s RequestRouter checks whether the phone is in a quiescent state (i.e. no applications running). If so, it transforms the PlayRequest by setting the operation to “dial”, and is routed to the voice communications sub-system agent 568. If, however, the SMS creation application is running, then the PlayRequest is transformed by setting the operation to “set-destination-number”, and it is routed to the running SMS creation application 569. Lastly, if instead the Contacts application is running, then the PlayRequest is transformed by setting the operation to “add-contact”, and it is routed to the Contacts application 570.

[0305] The end result is that the act of clicking on a telephone number on the business card can have very different results depending on the context within which it is applied. In this example, both the current context within the Netpage Server 529 and the current context on the mobile phone were taken into account when processing the PlayRequest 521.

2.7 Communicating with Players

[0306] Various communication methods are used between a Netpage Server 529, intermediate gateways 570 and the Netpage client to enable the playing of PlayRequests 521 on the Player device 520. Environmental factors such as the following affect the selected communication mechanism:

- [0307] Available network connectivity.
- [0308] Type of player device being targeted.
- [0309] Size and type of objects being transferred and the nature of the operation being played.

[0310] This section describes categories of messaging mechanisms. Note that in a single play scenario a combination of messaging methods can be used.

2.7.1 RPC (Synchronous) Messaging

[0311] Referring to FIG. 19, in an environment where a persistent connection can be maintained between the Netpage Server 529 and the Player 520, the server 529 can send the play request 521 to the player, block till play a request is handled and a response 571 is returned. A Desktop Player in an active session can communicate to the server 529 using this method.

2.7.2 Notification (Asynchronous) Messaging

[0312] Referring to FIG. 20, notification messaging is used when the environment allows playing of an Object through an asynchronous play() request 521 initiated from the Netpage Server 529 to the Netpage Player 520, delivering the object to be played. The server 529 may continue its activities and optionally receive a future response from the Player. The example of a notification based request delivery is when Netpage server pushes an image to a Netpage Player.

[0313] Depending on the underlying network infrastructure, a suitable protocol is used to push notifications to the Netpage Player, i.e. WAP push, SMS, etc.

2.7.3 Streaming

[0314] Referring to FIG. 21, for certain media types, it is preferable to be able to stream data to a player rather than transmitting the entire object before playing commences. The reasons are that:

[0315] Large objects may take significant time to transmit in their entirety to the player. Streaming allows for playing to take place before the entire object has arrived at the player thereby reducing latency.

[0316] Target player devices may not have the capacity to hold the entire object. In that case, streaming is one option for playing the object on the device due to this limitation.

[0317] Unbounded objects such as live video can be transmitted by streaming.

[0318] Video and audio provide the most significant examples of types that are typically better suited to streaming. To enable the streaming Netpage Server would be involved in the player selection process and would then leave actual streaming up to the two parties. Otherwise the server is likely to be a bottleneck and a source of additional latency.

[0319] Player can perform read-ahead operations to buffer the data ahead of playing and avoid network delays and jitters which can affect the user's experience.

2.7.4 Interactive Messaging

[0320] Referring to FIG. 22, in some scenarios multiple user/pointer interactions with the Netpage Server 529 invoking multiple play requests is required to complete a user play experience. For instance consider a scenario where a user has a Netpage printout photo that he/she would like to send as a MMS message to a friend. One way of achieving this is by the user clicking on the friend's business card's MMS hyperlink. This action sends a play request to the player activating the MMS editor with the phone number to which the message is being sent. At this point user can choose to click on the photo to attach it to the MMS message. This results in the photo being sent as a second play request to the Player, wherein the photo is attached to the MMS content. The state of the player 520 allows chaining multiple play requests 521 to complete a transaction.

2.7.5 Hybrid Messaging

[0321] Referring to FIG. 23, in some scenarios a multi-transaction messaging without user interaction is performed to play an object. Some examples of hybrid messaging are:

[0322] Consider a scenario where a low-end mobile phone player without support for the suitable push-based notification, wishes to play an unbounded object. A hybrid solution can be adopted to push a small notification to the device, notifying the player application (i.e. through SMS) to initiate a stream-based communication to the Netpage Server request (i.e. WSP) for delivery of the object.

[0323] Displaying a URL object also uses a multi-transaction hybrid messaging, where the original object (the URI) is pushed to the device using a Notification message. At this point the player (without user interaction) retrieves the URI content by sending a synchronous request/response message through HTTP.

2.7.6 Player Session Establishment

[0324] When players 520 are instantiated on devices (for instance during user login on a desktop player or on-demand by the mobile user), the player 520 registers the mobile device 100 is available for play requests by initiating a player session 580 with the Netpage Server 529.

[0325] FIG. 24 shows the basic lifecycle of a Netpage-Player session 580. First, a process, which is typically running on a remote machine/device, calls the startPlayerSession() method 581 to commence a NetpagePlayer session 581 with the Netpage Server 529. A userId 582 is provided which indicates the user 525 to which the supplied player 520 should be associated. Upon reception of a startPlayerSession() request 581, the server 529 creates a PlayerSession object which is returned to the remote process 583. This object can be used at some later time to terminate the session by calling the terminate() method.

[0326] FIG. 25 shows more details of the handling a player session 580 within the server 529. As shown previously, a player session is created 589 by calling the startPlayerSession() method on the Netpage Server's CommandProcessor. This causes the creation of a PlayerSession which in turn creates a NetpagePlayerProxy which is run within the server and acts as a proxy for the real player by implementing the NetpagePlayer interface and passing all requests on to the real player. NetpagePlayerManager::addSession() is called to register the session with the NetpagePlayerManager. The NetpagePlayerManager is a singleton object responsible for managing all NetpagePlayer sessions and also for coordinating all NetpagePlayer traffic within the server.

2.8 Player Deployment

2.8.1 Player Connectivity

[0327] Netpage Player 520 can be deployed on various devices with different network connectivity capabilities. Table 3 lists some examples of player network connectivity and transmission mechanisms. Note that a deployment environment may utilize a combination of connectivity types. Each connectivity type explains how one hop communicates to the next hop. For instance a player communicates with a wireless gateway on the path to the Netpage Server.

TABLE 3

| Netpage Player Connectivity Types | | |
|-----------------------------------|---|---|
| Player Connectivity | Comments | Example Standards |
| Local | On a desktop device or a smart mobile, the player communicates with the next hop locally through the on-board IPC mechanisms. The next hop could be the server running on the same desktop, or the micro server running on the smart mobile, or the gateway to the remote server running locally. | Shared memory, TCP/IP on the loop-back interface, etc. |
| Fixed Network | The connectivity to the next hop is over a fixed (wired) network. For instance the desktop player communicates to the remote server through IP-based protocols over Internet. | TCP over the Internet through a dial-up serial link, etc. |
| Short-range wireless | The player connects to the next hop through a Wireless Personal Area network (WPAN). For instance a player running on a PDA uses Bluetooth to communicate to a Relay module running on a local desktop. | IrDA, Bluetooth, 802.15, etc. |
| Long-range wireless | The player communicates with the next hop through a long-range wireless network with national (WLAN) or global (WWAN and Satellite) coverage. For instance the player is a WAP-enabled cell phone connecting to the remote server over GPRS wireless network. | 802.11a, b, g, GPRS, WCDMA, etc. |

2.8.2 Player Deployment Configuration

[0328] Different combinations of player devices and connectivity types can be configured to provide a suitable Netpage Player and Server integration environment. FIGS. 26 to 29 demonstrate some of the more widely applicable types of deployment environments. Example pen connectivity is demonstrated for clarity.

3. Object Association Design

3.1 Object Associations Overview

[0329] A Netpage object association allows content (objects 601) to be associated with locations 513 on Netpage documents 603 and printouts. Arbitrary content types can be supported, but common examples include pictures/photos, audio, and video.

[0330] An object 601 can either be associated 616 with a document during the authoring of the document (static association) or can be associated with a particular document printout at some arbitrary time after that printout has been created (dynamic association).

[0331] Additionally, an association 616 may either be an impression association or a field association. An impression association is a dynamic association that is associated with a particular {x,y} location 613 on an impression. A field association is associated with a particular field of a form (static association) or form instance (dynamic association).

3.2 Communicating Status to the User

[0332] At times the mechanisms described require communication of status information (often errors) to the user. The simplest way to achieve this is to make use of the Netpage Player infrastructure. Special operations (e.g. show-status-ok-message and show-status-error-message) can be designated for transmitting status information to the user. The player architecture would determine, for each message, the most appropriate device (or devices) on which to display the message and the way in which to display it. For example, it

may be that in certain situations the pointer is the only available player, in which case an error status might be “played” by illuminating a red LED on the pointer or playing a short sound.

3.3 Impression Associations

[0333] An object 601 can be associated dynamically with a specific {x,y} location 613 on an impression. The associations 616 are stored inside the Netpage Server 529 and can then be viewed in a number of ways:

- [0334] 1. By interacting with the physical impression using a device that communicates with the Netpage Server 529 to retrieve the associated objects 601.
- [0335] 2. By interacting with a virtual view of the impression from within a graphical software application 602.

3.4 Interacting with Dynamic Associations

[0336] Referring to FIG. 30, an associated object 601 can be viewed by interacting with the physical impression using a Netpage Tag aware device. This shows an example where a tag reading device with built in screen is passed over a physical impression. The device communicates impression locations to the Netpage server 529 which responds with information regarding any associated object 601 that is currently sensed by the device. Depending on configuration, the device might begin immediately playing each associated object or present the user 525 with the option of playing the object 601. If multiple objects 601 are within the device’s field of view, then the device could present the user with a list of the objects 601 for selection.

[0337] Associated objects 601 can also be viewed by interacting with a virtual view of the impression from within a graphical software application 602. There are a number of possible mechanisms for displaying associated objects 601 in such an application 602. Each mechanism is responsible for:

- [0338] Indicating the presence of an associated object (or objects 601), and
- [0339] Displaying the actual content of an associated object 601.

[0340] An example mechanism is shown in FIG. 31 where a graphical “Netpage Explorer” application 602 is being used to view an impression which contains associated objects 601. The example shows an approach in which some visible token 603 (in this case a black star) is displayed that indicates the locations that contain object associations 616. The display of the tokens 603 can be toggled by clicking on a toolbar button 609. To view an associated object 601 the user clicks (or alternatively double-clicks) on the relevant token 603 which causes the Netpage Explorer application 602 to retrieve the associated object 601 from the Netpage Server 529 and to then play the object 601. Depending on the capabilities of the Netpage Explorer application 602, the object 601 can either be played within the Netpage Explorer application 602 itself, or by an external application.

3.5 Methods for Creating Impression Associations

[0341] This section describes various alternative techniques that may be provided to allow users to dynamically associate content with a location on an impression. They include:

- [0342] Modal association mechanisms
- [0343] Sticker based mechanisms
- [0344] Swipe Based mechanisms
- [0345] Swipe Based Stickers

3.5.1 Modal Association

[0346] A Modal Association involves first placing the user/pen session in a mode in which the next pointer click is interpreted as the specification of an impression location to which a current clipboard object 601 should be associated.

[0347] FIG. 32 shows an example of how an impression object association 617 might be created modally. In this case, the user attaches a photo to an impression. The steps are as follows:

- [0348] 1. The user takes a photograph using their digital camera 610.
- [0349] 2. The user pushes the photograph to the Netpage clipboard on the Netpage Server 529 (possibly implicitly).
- [0350] 3. The user clicks with their Netpage pointer 533 on a printed toolbar 611. In this case, the user clicks on the “Attach Object” button 612. This places the pointer session into a mode in which the next click with the pointer 533 is interpreted as the specification of an impression location to which the current clipboard object 601 should be associated.
- [0351] 4. The user clicks on the desired location 613 on a printed page 614. This causes the Netpage Server 527 to retrieve the current object 601 from the user’s clipboard 615 and to associate the object with the impression location selected in step 3.

[0352] An alternative approach requires steps 3 and 4 to be performed in the opposite order. That is, the “Attach Object” command is interpreted to mean associate the object with the impression location most recently touched by the user.

[0353] Modal association mechanisms can be implemented on top of the Netpage Clipboard 615 mechanism.

3.5.2 Tagged Stickers

[0354] A tagged sticker 620 is a physical adhesive sticker which is Netpage tag encoded 617. That is, it is a Netpage impression printed onto a physical sticker. Clicking on a

tagged sticker causes an object to be associated with that sticker (impression). Tagged stickers 620 can be physically attached to any surface whether it be tagged or otherwise (eg. books, desks, walls, etc) and thus provide a very flexible mechanism for dynamically associating objects with locations.

[0355] FIG. 33 shows an example of a simple tagged sticker 620. In order to associate an object 601 with the sticker 620, the user would perform the following steps.

- [0356] 1. Push object 601 into Netpage Clipboard 615
- [0357] 2. Physically paste sticker 620 onto any surface
- [0358] 3. Use Netpage pointer 533 to click on the sticker 620 to associate the object 620.

[0359] Once an object 601 has been associated with a sticker 620, there are various ways in which the user can retrieve/play the object 601. Firstly, the object 601 can be interacted with using a physical Netpage Player device 520. Secondly, simply clicking on the sticker 620 with a Netpage pointer 533 would cause the object 601 to be played. This latter behaviour suggests that sticker associations would actually be implemented as field associations 618.

3.5.3 Reusable Stickers

[0360] As so far described, once an object 601 is associated with a sticker 620, that association 616 cannot be altered. A reusable sticker 621 allows for the object associated with a sticker to be changed, or erased. Such a sticker 621 is shown in FIG. 34. The “Attach” button 622 is used to associate an object 601 with the sticker 621 and allows for a new object 601 to be associated with the sticker 621, overwriting any previous association 616. The “Clear” button 623 allows for any association 616 to be removed.

[0361] Both “Attach” 622 and “Clear” 623 are destructive operations in that they remove any association 616 that may have been in place before the operation took place. As such, it may be desirable to be able to protect against accidental invocation of such operations, especially in the sticker scenario in which the entire sticker is a clickable area.

[0362] One mechanism for doing that is shown in FIG. 35 in which a sticker 621 has a “Confirm Action” button 624. In order for a destructive operation to be confirmed, the user must first select the operation and subsequently select the “Confirm Action” button 624. A suitable timeout (say 10 seconds) can be used such that confirmations must take place within the timeout period in order to be valid.

[0363] An alternative for preventing accidental invocation of destructive operations is to limit the interactivity of the sticker to small areas within the sticker as shown in FIG. 36. The associated object 601 is only played when the user selects the “Play” operation 625. The overall sticker 621 is not interactive. As such, accidental invocation of destructive operations should be much less likely.

3.5.4 Category Specific Stickers

[0364] So far we have described stickers which retrieve the object 601 most recently assigned to the Netpage Clipboard 615. The Netpage Clipboard 615 can store multiple objects 601 per user 625 with each object 601 falling into an object category or set of categories. As such, it is possible to have Category Specific Stickers 627 that retrieve current objects from the Netpage Clipboard 615 by category.

[0365] FIG. 37 provides examples. Clicking “Attach” on the left sticker causes the current clipboard object 601 with a

category of “video” to be associated with the sticker **620**. The sticker on the right achieves a similar effect for objects in the “photo” category.

3.5.5 Swipe Based mechanisms

[0366] The printed toolbar in FIG. **38** allows an impression association **617** to be created by swiping a command from a printed toolbar **626** to the location on an impression to which the object **601** is to be associated. The user temporarily places the toolbar **626** on top of the destination impression and swipes from the toolbar **626** to the impression. The swiping action provides the system with digital ink samples from both the toolbar and the destination impression. These samples enable the determination of both which object **601** is to be associated (for the card shown the possibilities being the current video clip, current photo, current audio clip, or in the case of the “Any” icon, the current object regardless of type) and to which impression and location on that impression the object **601** is to be associated.

3.5.6 Swipe Based Stickers

[0367] A limitation of the stickers described earlier is that they do not actually create an association **616** between the object **601** and the underlying impression on which the sticker is applied. For example, consider the situation where a sticker has been applied to a tagged impression, and subsequently an object **601** is associated with the sticker. If the underlying impression is viewed within the Netpage Explorer application, then the sticker and associated object **601** is not be displayed since the Netpage Server **529** is not aware that the sticker has been applied to that impression.

[0368] The above problem can be solved by applying the swipe based approach to stickers. The user steps involved are:

[0369] 1. Push object **601** into Netpage Clipboard **615**

[0370] 2. Physically paste sticker **620** onto a tagged impression **600**

[0371] 3. Use Netpage pointer **533** to swipe from sticker **620** to impression **600**.

[0372] The action of swiping across both the sticker **620** and the impression **600** creates a triple association between the impression **600**, the sticker **620**, and the object **601**. Specifically, the Netpage server **529** is now aware of:

[0373] The sticker **620** to which the object **601** has been associated, and

[0374] The impression **600** on which the sticker **620** has been placed, and the location **613** on the impression **600** at which the sticker **620** has been placed, and thereby the location **613** on the impression **600** to which the object **601** is associated.

[0375] The above associations **616** allow the object **601** and sticker **620** to be displayed inside tools such as Netpage Explorer **602**.

[0376] A variant of the swipe based sticker is shown in FIG. **39**. It includes a transparent region **628** which allows the tags of the underlying impression **600** to be seen through the sticker **620**. This makes it possible to create a triple association **616** with a swipe that remains within the confines of the sticker **620**.

[0377] In addition, the transparent region **628** may be transparent in the infrared spectrum in order for the Netpage pointer **533** to be able to see the Netpage tags on the underlying impression **600**. This allows for the transparent region **628** to be non-transparent in the visible spectrum. As such, graphics can be printed over the transparent region **628**. For example, a swipe based category specific sticker can be con-

structed which includes indicative graphics printed over the transparent region **628** as shown in FIG. **40**. It is also possible that the instead of using a transparent region **628**, the sticker **620** may alternatively include a hole.

3.5.7 Impression Associations Object Model

[0378] FIG. **41** shows the basic object model representation of impression associations **617**. An ImpressionAssociation **617** includes a location and the object’s content. An ImpressionLocation includes an {impression,x,y} tuple **629**. The content of an associated object is represented as a PlayRequest **521**. In the common case, the PlayRequest **521** includes a single value, but it also possible to associate targets and operations. For example, any PlayRequest **521** can be associated with an impression.

[0379] A swipe based sticker is associated with an ImpressionAssociation on the underlying impression.

3.6 Field Associations

[0380] An object **601** can be dynamically associated with a particular field of a form instance **630**. Such an associated object **601** is then delivered to the relevant application as part of a submission of the form instance **630**. This can be used, for example, to dynamically attach images (e.g. photos) to a Netpage form **632** and to then have those images sent to the application when the user clicks on the “submit” form command.

[0381] The relationship between field associations **618** and impression associations **617** is shown in FIG. **42**. A FieldAssociation **618** consists of a specification of the field with which the object **601** is associated and a reference to the underlying impression association **617** which provides details of the actual object **601**. The ImpressionAssociation **617** structure has been described. The field is specified by a FieldInstanceAddress **631** which specifies a form **632** instance **630** and a field number **633** within that form instance **630**. A FormInstance **630** is a specific instance of a Form **632** which is printed on to a Printout **633**.

3.6.1 A Sample Application

[0382] FIG. **43** shows a simple application that demonstrates the use of field associations **618**. Use of the application proceeds as follows:

[0383] 1. The user clicks on the “Click here to attach photo” button **640** with a Netpage pen **533** or pointing device. This causes the application to request the current photo from the Netpage clipboard **615** associated with the user **525**. That photo is then associated with the large rectangular field **641**.

[0384] 2. The user can click on the large field **641** in order to retrieve the associated photo and display it on a suitable Netpage Player device associated with that user **525**.

[0385] 3. The overall form can be submitted by clicking on the “Submit” button **642**. This causes a form submission to be sent to the relevant application. The form submission includes the photo currently associated with the large field **641**.

[0386] The following sections use the sample application to describe the remaining details of the field association mechanism.

3.6.2 Form Design for the Sample Application

[0387] In order to design a form **632** that supports a simple application, two forms are specified. The first form **643** is a

standard application form. The second form **644** is a special form that include fields that share the same impression coordinates as elements from the first form, but are overlaid on top of the first form's fields.

[0388] The underlying (first) form **643** is shown in FIG. 44. This includes a submit button **642** for the application and also a field of type ObjectReceiver **644**. It is to this second field **644** that an object is to be assigned. The actual assignment occurs as a result of user interaction with the overlaid form as described below.

[0389] The overlaid form **644** is shown in FIG. 45. The application name for the overlaid form **644** is the system supplied "sys:object-associator" application. This is a standard internal application that expects to receive a form submission with a "submit" button having one of the names as shown in Table 4. The table describes the meanings of each of the possible submit buttons. Note that an object-associator form does not need to provide all four submit buttons, although it must minimally provide both a "set" and a "target" button.

TABLE 4

| Submit buttons supported by the sys: object-associator application | |
|--|--|
| Name | Description |
| set | The set command indicates that an object of the specified type is to be fetched from the Netpage clipboard and associated with an ObjectReceiver field on the underlying form. The location of the relevant ObjectReceiver field is indicated by the "target" field that must also be part of this form. The type of object to be associated is indicated by the field's value. If it is left blank, then the current clipboard object (regardless of type) is retrieved and associated. |
| clear | The clear command indicates that the object association currently assigned to the "target" field should be removed. |
| show | The show command causes the object associated with the target field (if any) to be displayed on a suitable Netpage Player. |
| target | The target field has two roles. Firstly it indicates the location/field on which the set, clear and show commands should act. Secondly, if the target field is clicked then it behaves as if it is a show command. |

[0390] The below pseudo code outlines the handling of the set command. The main principle to note is that the center of the target field provides the {x,y} location to which the retrieved object should be associated. This {x,y} location is also used to locate a form field with which the object is to be associated. This is achieved by determining the uppermost field on the page that intersects with {x,y} and that is also receptive to object associations. In the case of the example, the uppermost field on the page that intersects {x,y} is the target field itself, but it being a submit field, is not receptive to object associations. The next uppermost field that intersects {x,y} is the ObjectReceiver field on the underlying form. The end result is that the object is associated with a field on the underlying application form rather than the overlaid sys: object-associator form.

```
ObjectAssociatorApp::handleSetCommand(a_submission,
a_formDescription)
{
    let l_setField = a_submission.getSubmitButton( )
    // fetch the target field for the current form
    let l_targetField = a_formDescription.fetchField("target")
    // Calculate the impression location to which the object
```

-continued

```
is to be
    // associated. The center of the "target" field is used as
the
    // location to place the object.
let l_targetCenter = l_targetField.center( )
let l_location =
    ImpressionLocation(a_submission.getImpressionId( ),
targetCenter);
    // Look for a receptive field to which we can associate
the object.
    // A receptive field is a field with a type that indicates
it is
    // receptive to object associations. "submit" fields are
not
    // receptive, but most other field types are. N.B. The
receptive
    // field is typically on another form.
let l_targetField =
    (the uppermost receptive field on the page that
includes l_location)
    // Retrieve an object of the appropriate type from the
NetpageClipboard.
    // The type to retrieve is indicated by the "value"
element of the
    // "set" field
let l_objectRequestType = l_setField.value( )
let l_clipboard = getClipboard(l_submission.userId( ))
let l_object = l_clipboard.fetchObject(l_objectRequestType)
    // create the associations
let l_impressionAssoc =
createImpressionAssociation(l_location, l_object)
createFieldAssociation(l_targetField, l_impressionAssoc)
}
```

3.6.3 Field Associations and Form Submissions

[0391] Netpage forms **632** generally have one or more form submission buttons **642**. Clicking on such a button **642** with a pointer **533** causes the Netpage server **529** to perform handwriting recognition of the digital ink (if any) assigned to the form **632**, and to bundle the result into a form submission which is then posted to the application associated with the form **632**. The handwriting recognition largely involves converting handwriting fields (such as textual combs, and check boxes) into their digital equivalents (for example digital ink in textual combs is converted to text).

[0392] Associated objects **601** can optionally be submitted as part of such form submissions. The requirement to transfer an associated object **601** (or otherwise) as part of the form submission is specified in the form definition for that form.

3.7 Static Associations (Embedded Objects)

[0393] Objects **601** can be associated with a document at document creation time. As with dynamic associations, such associations can either be impression associations **617** or field associations **618**. Static associations are specified in the Interface Description for the document. Static associations are represented as PlayRequests **521**.

4. Netpage Clipboard

[0394] The Netpage Clipboard **615** is a system supplied, per user object repository to which the user can push an object **601**. The object **601** thus pushed is considered to be the user's "current object" which may then be accessed by applications, in particular by the UserRequestRouter, but in general by any application that is acting on behalf of the user.

4.1 Representation of Clipboard Objects

[0395] Clipboard objects are stored as Netpage Player PlayRequest objects 521. A PlayRequest 521 corresponds to a request to perform an action. It consists of three parts:

[0396] 1. A target, which specifies on which player (device) the request should be executed.

[0397] 2. The operation, which specifies the action to be taken.

[0398] 3. A set of values, which are supplied as parameters to the operation.

[0399] A Value represents an instance of some physical type and consists of a type specification and data. The type

The form has been authored such that clicking on any of the phone numbers causes that phone number to be sent to the Netpage clipboard 615 for that user 525. For example, clicking on the phone number for "Susan Wilson" 615 causes the following value to be pushed to the clipboard 615:

[0404] value {phone-number, "151 425 0617"}

4.2.2 Push Via Physical Device

[0405] Values 524 can be pushed to the clipboard 615 by Netpage aware devices that are capable of capturing and/or storing typed objects. Table 5 provides some example devices and scenarios in which they might push values to the Netpage clipboard 615.

TABLE 5

| Examples of Netpage aware devices capable of pushing objects to the clipboard | |
|---|--|
| Device | Example scenario |
| Digital Camera | User takes a photo with the digital camera and then selects "Send to Netpage" from a menu. This results in the photo being added to the Netpage clipboard (say with type: image/jpeg). |
| mp3 audio players | User chooses a favourite song (or song collection) on the audio player and selects "Send to Netpage" from a menu. |
| Video camera | Similar to the digital camera scenario, but for video instead of still photo. |
| Dictation device | User records a message and then pushes the audio file to the Netpage clipboard. |

specification has a physical type and zero or more associated type categories. The physical type identifies the structure of the data element of the Value. This document does not specify a particular representation for physical types. A possible mechanism would be to use MIME types. For example, if the physical type is image/jpeg then the data element would contain the binary data of an image in jpeg format.

[0400] A shorthand form of specifying PlayRequests will now be used in this section. As an example, instead of using the tabular form this section will use the following syntax for PlayRequests that only have a single item:

[0401] value {phone-number, "555 3473"}

| | |
|-----------|-------------------------|
| target | |
| operation | |
| values | phone-number "555 3473" |

4.2 Mechanisms for Pushing Values to the Clipboard

[0402] In general, a user performs an explicit user action in order to push a value to the clipboard. Such actions may take various forms as described in the following sections. Once a value is in the clipboard any application can access the value. For example the value can be dynamically associated with a form field on a printed impression.

4.2.1 Push Via Printed Netpage Form

[0403] Values can be pushed to the clipboard by interacting with a printed Netpage form such as that shown in FIG. 46.

4.2.3 Implicit Push

[0406] To improve usability, it may be possible for certain devices to support implicit (or auto) push which is where certain user interactions with a device cause a value to be automatically pushed to the Netpage clipboard 615. As an example, the user may configure their digital camera so that taking a photo causes the photo to be pushed to the Netpage clipboard 615.

4.3 Netpage Clipboard Interface

[0407] In order for a device or application to push a value to the Netpage clipboard 615 or retrieve the current object 601, the device or application first retrieves a reference to a NetpageClipboard object for that user from the Netpage server 629. The following listing shows the NetpageClipboard interface in its most basic form. The interface allows the current clipboard value to be set, fetched and cleared.

```

interface NetpageClipboard
{
    void
    setObject(in PlayRequest a_object);
    PlayRequest
    fetchObject( );
    void
    clear( );
};

```

[0408] The sections that follow discuss alternatives for various aspects of the Netpage clipboard interface.

4.3.1 Multiple Values Per User

[0409] The Netpage clipboard 615 is able to support multiple current values each of which belong to a different cat-

egory. For example, the clipboard 615 can hold a current audio and current video at the same time. PlayRequest values can specify one or more categories to which that value belongs. Note that an object category is generally independent of the specific physical type of the value being added to the clipboard. For example, setObject() might be called with a value that has a category of "photo", and a physical type of image/j peg.

[0410] This listing shows a NetpageClipboard interface that supports multiple current values.

```

interface NetpageClipboard
{
    void
    setObject(in PlayRequest);
    PlayRequest
    fetchObject();
    PlayRequest
    fetchObject(in ObjectCategory);
    void
    clear(in ObjectCategory);
    void
    clearAll();
};

```

[0411] Such a clipboard would still support the current object concept which would return the most recently added object. To that end, the clipboard interface in the listing has two fetchObject() methods. The first takes no parameters and returns the most recently added object. The second takes an ObjectCategory as a parameter and returns the most recently added object which belongs to the specified object category.

[0412] More generally the clipboard could reuse the general capability matching mechanism required by RequestRouters in the Netpage Player architecture. This would provide the clipboard with a very powerful interface for retrieving PlayRequests.

4.3.2 Multiple Representations of Values

[0413] As with clipboards in standard desktop environments, it may be desirable to allow the Netpage clipboard to support multiple representations of values, each of which would have a different MIME type. For example, a text object could be stored as both a text/plain and a text/rtf document.

4.3.3 Using Values from the Netpage Clipboard

[0414] Once a user places a value in the clipboard, the value can be accessed by applications in response to actions by the user. The basic clipboard interaction model is shown in FIG. 47. Referring to FIGS. 47 and 48, the clipboard starts empty 652. A value can then be pushed 653 into the clipboard 615. At that point an operation can be selected 654 by the user at which point the selected operation is executed against the current value in the clipboard. If an operation is selected while the clipboard is empty, then an error 655 is returned to the user.

[0415] The model presented in FIG. 47 is called the value first model as it requires the user to first select the parameter to an operation, and to then select the operation itself.

[0416] One way in which an operation can be invoked by a user is for the user to interact with a printed Netpage form 660 which contains a set of PlayRequests which specify operations. FIG. 48 shows such a printed command sheet and Table 6 describes the meaning of each operation. When a field is selected by the user (by clicking on it with a Netpage pointer), the corresponding operation is performed on the value currently stored in the clipboard

TABLE 6

| Description of commands | |
|-------------------------|--|
| Command | Descriptions |
| Play | Executes the default action for the current clipboard value. For example, for a phone number object, the default action might be to dial the number, while for an image it might be to display the image on a device capable of image display. |
| Display | Display the current clipboard value. This is different to play, since for a phone number, for example, the phone number is displayed rather than dialled. |
| Attach to Page | Associate the current clipboard value with a location on a printed page. |
| Print | Print the current value. |

4.4 Placing Operations and Targets in the Clipboard

[0417] As clipboard entries are actually stored as PlayRequests 521 it is also possible to push operations and targets to the clipboard 615.

4.4.1 Adding Operations to the Clipboard

[0418] FIG. 49 shows a clipboard model which allows operations 523 to be stored in the clipboard 615 rather than values. In this model, the user pushes an operation 523 to the clipboard 615 at step 661, and then selects the value 524 to which the command 523 should be applied at step 662. So, for example, a "play" operation could be pushed to the clipboard 615, and then a phone number could be subsequently selected from a contacts list as already shown in FIG. 46. This model is called the operation first model as it requires the user to first select an operation 523, and to then select the parameter 524 for the operation 523.

4.4.2 Allowing both Value First and Operation First Models

[0419] It is possible to simultaneously support both the value first and operation first models as shown in FIG. 50. In this model an empty clipboard 615 allows an operation 523 or a value 524 to be pushed at steps 663 or 664. This gives the user the freedom to perform operations 523 in whichever order seems natural. Also, if a user is using operation first, then once the user has placed an operation 523 in the clipboard 615, they can perform that operation 523 on as many values 623 as required simply by pushing values to the clipboard 615 at step 665 (and vice-versa for value first at step 666). In order for a user to switch between models, however, the clipboard 615 must be explicitly cleared at steps 667 and 668.

[0420] The following examples show the two models in action. In each case, the user's steps are shown numbered and the contents of the clipboard 615 are shown after each step. In the first case, the user uses the value first model by first pushing a phone number to the clipboard 615, and then selecting the operation 523 to be applied to that object:

```

Push value
value { phone-number, "555 1287" }
Push operation
value { phone-number, "555 1287" }
operation { play }

```

[0421] At this point, an observer of the clipboard 615 (likely the UserRequestHandler) determines that the PlayRe-

quest 521 as shown below can be produced by combining the operation 523 and value 524 PlayRequests 521. The resultant PlayRequest 521 can then be routed by the UserRequest-Handler. Typically the UserRequestHandler “plays” a phone-number by sending the request to a device capable of dialing the phone number.

[0422] PlayRequest created by merging contents of clipboard:

| | | |
|-----------|--------------|------------|
| target | play | |
| operation | phone-number | “555 1287” |
| values | | |

[0423] The second case uses the operation first model:

| | |
|------------------------------------|--|
| Push operation | |
| operation { play } | |
| Push value | |
| operation { play } | |
| value { phone-number, “555 1287” } | |

[0424] At this point, the clipboard 615 determines that the PlayRequest 521 can be produced by combining the operation 523 and value 524 PlayRequests 521.

4.4.3 Ambiguous Usage

[0425] One problem associated with this mechanism of pushing values 524 or operations 523 to the clipboard 615 is a value 529 or operation 523 can remain in the clipboard 615 indefinitely. As such, it is easy for a user 525 to forget that an object 601 is in the clipboard 615 and for unexpected results to emerge. This is particularly the case if we simultaneously allow both the value first and operation first models. As an example, suppose the user performs the following actions:

[0426] 1. Push “play” operation to the clipboard

[0427] 2. Push a phone number (the number is dialed)

[0428] 3. An hour later, click on another phone number.

[0429] Using the state machine indicated by FIG. 50, step (3) would cause the number to be dialed. This may not be what the user expected as they have likely forgotten the fact that the “play” operation is currently residing in the clipboard.

[0430] There are a number of approaches to addressing these usability concerns:

[0431] Single Use Clipboard Entries

[0432] Clipboard Timeouts

4.4.4. Single Use Clipboard Entries

[0433] FIG. 51 provides an alternate model to that previously described. In this model, using an item in the clipboard 615 at either of steps 525 or 626 results in that item being removed from the clipboard 615 at state 670. That is, operations 523 and values 524 only remain in the clipboard 615 for a single use after which the clipboard 615 is returned to the Clipboard Empty state 627. This model largely avoids the usability concerns described above, although not completely, as will be described in further detail.

4.4.5 Clipboard Timeouts

[0434] While a single-use clipboard model improves the usability of the Netpage clipboard 615, there are still prob-

lematic scenarios which result from allowing both value first and operation first models to coexist. Consider the following steps:

[0435] Push “play” operation to the clipboard 615

[0436] An hour later, push a phone number

[0437] In the above, it is not clear whether the user 525 has indicated that they would like to apply the “play” command to the phone number, or whether they had forgotten that they had pushed the “play” operation an hour ago and were actually attempting to simply push a phone number to the clipboard 615.

[0438] In order to address the ambiguity, the concept of clipboard timeouts can be introduced, as shown in FIG. 52. In this model, objects only remain in the clipboard for a limited duration, 60 seconds in the example for steps 675 and 676, but the exact value could be user configurable.

[0439] FIG. 52 shows clipboard timeouts in the context of a single-use clipboard. It is also possible to introduce clipboard timeouts within a multi-use clipboard, as shown in FIG. 53. Each application of an operation to a value at steps 680 and 681 resets the timeout period which allows for multiple values to be applied to an operation without having to push the operation each time. Similarly, it allows multiple operations to be applied to a value without having to push the value each time.

4.4.6 Multi Value Operations

[0440] The clipboard 615 concept can be extended to support operations that require more than one parameter 524. The basic approach is to allow multiple values 524 to be pushed to the clipboard 615. The clipboard 615 can then combine the values 524 with a pushed operation 523 to create a PlayRequest 521 with multiple parameters.

4.4.7 Adding Targets to the Clipboard

[0441] Consider the command sheet already shown in FIG. 48. Clicking on each operation with a Netpage pointer 533 causes the corresponding operation 523 to be pushed to the clipboard 615. The operation 523 does not necessarily take effect immediately. The operation takes effect when there is sufficient information available in order to determine the full details of the PlayRequest 621 being requested by the user 525. There are cases in which it proves valuable to allow the user 525 to be able to specify the target 522 of an operation 623. For example, suppose a user wishes to print a photo from their digital camera, but does not wish to print it to their default printer.

[0442] Selection of the printer can be achieved by selecting the printer from a list of printers printed on a Netpage card 700 as shown in FIG. 54. Clicking on a printer 707 on the card simply causes the details of that printer to be pushed to the Netpage clipboard 615.

[0443] FIG. 55 shows the details of each of the fields on the card. Each field corresponds to a PlayRequest (521a, 521b, 521c, 521d, 521e, 521f, 521g) that specifies a target 522 and nothing else.

[0444] The following steps provide an example in which the user pushes a target to the clipboard.

| |
|---|
| 1. Push photo of family dog to clipboard |
| value { image/png category =“photo”, <contents of photo of dog> } |

-continued

```

2. Select printer by clicking on card
value { image/png category ="photo", <contents of photo of dog> }
target { home-color-printer }
3. Push "print" command to clipboard (e.g. using printed command
sheet shown in FIG. 3
value { image/png category ="photo", <contents of photo of dog> }
target { home-color-printer }
operation { print }

```

[0445] At this point, a PlayRequest 521 can be constructed that combines all the elements from the clipboard 515 as shown in FIG. 52.

| PlayRequest created by merging contents of clipboard | |
|--|--|
| target | home-color-printer |
| operation | print |
| values | image/png category ="photo" <contents of photo of dog> |

[0446] Once the full PlayRequest 521 is determined, it is performed and, depending on the clipboard model being used, the clipboard 615 would either be cleared of all contents (the single-use model), or left as is in readiness for future related requests 521 (the multi-use model). In the latter case, the subsequent act of pushing another photo (say of the family cat) to the clipboard 615 would leave the clipboard 615 in the following state:

```

target { home-color-printer }
operation { print }
value { image/png category ="photo", <contents of photo of cat> }

```

[0447] At this point, the clipboard contents indicate that the user wishes to print the newly selected photo on the color inkjet printer at home. This approach allows the user to request the printout of a number of photos on a particular printer, without having to specify the target 522 or the operation 523 each time, by simply clicking on each required photo.

[0448] Even in the multi-use case, if the user is inactive for some configurable period of time, then a clipboard timeout causes the clipboard 615 to be cleared.

4.4.8 Pushing More Fully Specified PlayRequests

[0449] As the clipboard 615 supports the pushing of PlayRequests 521, the application author is not limited to pushing values 524, operations 523, and targets 522. It is also possible to push PlayRequests 521 that are more fully specified. For example, consider the printed command sheet 710 shown in FIG. 56. It contains various commands 711 that can be invoked by clicking on the sheet with a Netpage pointer 533.

[0450] FIG. 57 shows the configuration of one of the commands. Namely, the "print using . . . office printer" command 712. As can be seen, it corresponds to a PlayRequest 521 that specifies both a target 522 and a command 712.

```

1. Push photo of family dog to clipboard
value { image/png category ="photo", <contents of photo of dog> }
2. Click on "print using ... office printer" field
value { image/png category ="photo", <contents of photo of dog> }
target { office-personal-printer }
operation { print }

```

[0451] At this point, a PlayRequest 521 can be constructed that combines all the elements from the clipboard 615 as shown in FIG. 52. As such, the "print using . . . office printer" command 711 has reduced the number of clicks required by the user to perform the action from three clicks to two.

| PlayRequest created by merging contents of clipboard | |
|--|--|
| target | office-personal-printer |
| operation | print |
| values | image/png category ="photo" <contents of photo of dog> |

4.4.9 Communicating Status to the User

[0452] At times the mechanisms described may require communication of status information (often errors) to the user. One method is to make use of the Netpage Player infrastructure. Special operations (eg. show-status-ok-message and show-status-error-message) can be designated for transmitting status information to the user. The player architecture would determine, for each message, the appropriate device (or devices) on which to display the message and the way in which to display it. For example, it may be that in certain situations the pointer 533 is the only available player in which case an error status might be "played" by illuminating a red LED on the pointer 533 or playing a short sound.

5. Downloadable Content Billing

5.1 Overview

[0453] There is already an existing market place for purchasing and downloading products to mobile devices. Products such as: ringtones (monophone, polyphonic and real tone); wallpapers; games and other applications; music; music videos; films and TV. The printing capabilities of M-Print can add further to this list of products.

[0454] The traditional methods for purchasing and downloading such products are based around web browsing and SMS to initiate the download and EMS or MMS to deliver the product to the phone 100, see FIG. 58. The user enters and sends a product code via SMS at steps 720 and 721 to a vendor 723 who then delivers the product to the originating handset 100, or to the mobile number supplied with the product code at step 724.

[0455] Netpage and M-Print technologies have the ability to simplify the user experience in accessing and purchasing these products, while also being able to utilise the existing infrastructure for the billing and delivery of the products.

[0456] FIG. 59 shows the typical sequence of events for a Netpage play sequence, cast in terms of downloading a preview of a ringtone. In the general Netpage play sequence a Netpage click at step 730 triggers a form submission which in turn results in a general "play" event being routed at steps 732 and 734 to a Netpage player via the Netpage Player Architec-

ture. For downloadable content the form submission is shown as a simple hyperlink 731 and the “play” event is shown as a download of content, in this case a ringtone.

[0457] Using a Netpage pen or pointer 533 the user 525 can click on a printed advertisement 715 in a magazine, newspaper, direct mail, on a product’s packaging or possibly on a product itself. This can automatically deliver some content to the user’s preferred Netpage Player 520 for that content. Most likely the Netpage Player 520 is the user’s mobile phone 100, as is shown in FIG. 59. Alternatively it can commence a dialogue with the user via the device’s UI to determine what the user wants to do with the product they selected via their click. For content like ringtones or phone themes, this provides a more convenient interface than the existing SMS interfaces in use today.

[0458] M-Print devices can provide a Netpage scan operation, and this can also be used to initiate a product download or purchase as above. The card that is scanned could have been printed on a M-Print printer 4 or it could be provided along with another product, e.g. a card in a breakfast cereal box.

[0459] Combining the abilities of M-Print and Netpage can lead to a powerful suite of new product promotion and sales tools. For example, a user can use a Netpage pointer 533 in a mobile phone 100 to click on the latest ringtone advertisement in their favourite magazine. This results in purchasing the ringtone, charging it to their mobile phone account, download and install it on their phone 100. It can also print on their phone a promotional card that allows a one time download of the same ringtone for them to give a friend. When their friend scans the card they receive the same ringtone downloaded and installed on their phone. Depending on the promotion running at the time the friend may receive the ringtone for free or at a discounted rate.

5.2 Downloading Content

[0460] FIG. 59 shows the typical Netpage player sequence of events that are involved in downloading a product, in this case a ringtone, from a Netpage based application. In the diagram the ringtone download event being routed to the phone in steps 732 and 734 consist of a ringtone, with the play operation of preview 716. It may have the target handset specified or it may rely on the Netpage player request routing mechanisms to determine the appropriate target 522 for the play request 521.

[0461] It has already been noted that the mobile computing environment already has some well established mechanisms for satisfying on-line product purchases. Below are three possible ways Netpage player requests can be integrated into the existing mechanisms to provide the user with a simpler user experience. In each of the cases the request to purchase or preview the product is instigated via a Netpage stroke, click or scan. The differences arise in how the Netpage application 733 procures the product and delivers it to the user.

5.3 Netpage as Middle Man

[0462] FIG. 60 shows a scenario where the Netpage ringtone application is used as an alternative interface and delivery mechanism to an existing ringtone vendor 723. The Netpage application 733 does not own the rights to the products it is providing. Instead it is acting as a middleman, forwarding the requests at step 736 onto the product vendor

723 on behalf of the Netpage user and routing the requested product at step 739 back to the Netpage user via the Netpage player mechanism.

[0463] This approach allows the user to benefit from the Netpage Player Architecture, which allows the user to customize the way they want the product to be routed after they have received it from the vendor. It also allows for the Netpage Player to provide extended handling of products on the mobile device. For example, the player may prompt the user if they wish to back up their existing ringtone before installing a new ringtone or it may guide the user through installing the ringtone as a custom ringtone for a particular phone number or set of phone numbers.

5.4 Netpage as a Sales Agent

[0464] FIG. 61 shows the Netpage application 733 acting as a sales agent for the product vendor 723. The play request 521 contains the user information and the product ID, and is routed to a special player 743 at step 741 that passes the request onto the vendor 725 at step 742. The vendor 723 then delivers the product in its normal way, in this case via EMS/MMS at step 744.

5.6 Hybrid Approach

[0465] FIG. 62 shows a hybrid scenario where the both the Netpage Player Architecture and the existing mobile technologies are used to deliver the purchased product. The request 521 to purchase the product may be satisfied by the ringtone application 733 either internally as a pure Netpage application or acting as a middle man. The play request is dispatched containing both the purchased product and a voucher to be printed.

[0466] The play request 521 is routed as a Netpage player request and when it reaches a player 745 deployed within the mobile network, acting a mobile device proxy, it is split into a product delivery and a print job. The product is sent out via an EMS/MMS message at step 746 and delivered to the mobile device 100 in the same way as a traditionally purchased product at step 747. The print job in the form of an M-Doc reference 507 is delivered to the phone 100 via one of the mechanisms initiating a print job on the mobile device 100.

5.7 Billing for Downloaded Content

[0467] The ability to bill or charge for services and products is at the heart of all businesses. To be able to bill you need to be able to:

- [0468] 1. identify a party to bill;
- [0469] 2. have a mechanism to deliver and ensure payment of a bill; and,
- [0470] 3. be able to justify the bill based on records of services or products provided.

[0471] When accessing a service or purchasing a product over a mobile network the user is typically charged for both the data or call traffic involved in making the transaction and also for the product or service purchased. For example, if a ringtone was purchased via Netpage, there is a charge for the ringtone and also a charge the data traffic used to download the content to the mobile device. It is possible for a 3rd party vendor to enter into a commercial relationship with the carrier whereby the carrier waives or reduces the data transfer costs, in return for a payment from the vendor. Mobile carriers play a central role in billing. They own the private networks used

by mobile devices to connect to both the public telephone and data networks and it is at their discretion that a mobile device has access to any services. They already have a billing relationship with each of their customers and hence are able to identify them and bill them. Over time the billing options offered by carriers have evolved from the simple post-pay phone bill to include pre-paid, post-paid and plan-based billing, where customers are committed to paying a certain amount per period for which they can access a range of services. Carriers also have the ability to adjust or waive billing based on a user's activity over a billing period, for example, if you send more than certain number of SMSs in a day then all SMSs is to be charged at a different rate.

[0472] For pre-paid accounts the account balance is checked before the transaction is commenced to ensure it has sufficient credit to pay for the service. Not all services can predict the total cost before they are delivered and in those cases it is up to the individual carriers to decide whether those services are to be made available to pre-paid customers or not.

[0473] Mobile carriers recognise the value of their ability to identify and bill customers and make it available to third parties on a commercial basis. They do not make it freely available. The ability to integrate into a carrier's billing system is typically offered in a number of different ways, of which some are:

- [0474]** 1. SMS/MMS-based services
- [0475]** 2. Hosting of 3rd party applications and billing the traffic for those applications differently
- [0476]** 3. Billing of data traffic to nominated servers at different rates
- [0477]** 4. The ability to bill on behalf of a third party, based on billing records provided by the third party.

[0478] To bill for products or services attained via Netpage interactions it is necessary to identify where in the sequence of events it makes sense to generate billing records and which party in the transaction is responsible for maintaining and acting on those billing records. To make these services available to users with pre-paid mobile accounts it may be necessary to be able to predict ahead of time the total cost of the transaction.

[0479] If we consider the SMS-based content download scenario, FIG. 58, there are three billing opportunities:

- [0480]** 1. The SMS to initiate the transaction may be a billable SMS
- [0481]** 2. The purchase of the content from the vendor
- [0482]** 3. The delivery of the content via a SMS or MMS.

[0483] The first SMS is a standard SMS that the user may be billed for, it may be billed differently given that it is destined for a vendor who has a business relationship with the carrier. The second SMS/MMS is not billed to the sender, as would normally happen, but it is billed to the receiver, via an agreement between the vendor and mobile carrier. In both of these cases the mobile carrier generates and manages the billing records. The purchase cost for the content is also billed to the receiver and the vendor is responsible for generating the billing record. In most cases this billing record is forwarded onto the mobile carrier, typically once a day via a batch transfer. The carrier accumulates these records and includes them on the user's phone bill as a service for the vendor. The carrier then makes a periodic payment of funds collected on the vendor's behalf to the vendor. This alleviates the need for the vendor to establish a billing relationship with each of its

customers and also allows the mobile carrier to derive more revenue from its existing billing relationship with the customer.

[0484] For the vendor to be able to generate billing records that a mobile carrier can incorporate into a customer's bill the mobile carrier needs to provide the vendor with a "customer id" or "billing id" per transaction that the carrier can use to link a billing record with a customer. The provision of customer id and the ability to generate billing records needs to be done in a secure way to reduce the possibility of fraud. To ensure the required security is maintained each vendor enters into a contractual relationship with each mobile carrier before the "customer id" data is shared with them.

[0485] In situations where a vendor cannot or does not want to work with a mobile carrier they need to implement their own means of identifying and billing their customers. Identifying a user of a mobile device without the assistance of the mobile carrier in a uniform way across all mobile devices is non-trivial.

[0486] Introducing Netpage and M-Print technologies provide a number of new billing opportunities for all parties involved. If we consider the case where Netpage acts a middle man, there are two billing opportunities:

- [0487]** 1. When Netpage application retrieves the content from the content vendor;
- [0488]** 2. For the network traffic used to deliver the click and the ringtone.

[0489] The Netpage application fetching the content from the vendor generates a billing record for the customer. As for the SMS case above, it is possible to arrange with a mobile vendor to accept these billing records and to bill on the application's behalf. To do this the data traffic associated with the hyperlink activation is to be tagged with a "customer id" to be associated with the billing record.

[0490] The mobile carrier tracks the data traffic used to send the click event and deliver the play request. By default that traffic would be billed in the same way as all other data traffic to and from the device. In a situation where the Netpage application is billing via the carrier it may be possible to strike a deal with the mobile carrier where they waive the data traffic costs in return for a payment per transaction.

[0491] In the case of Netpage acting as a Sales Agent, the Netpage system is not involved in delivering the product but only in making the sale. In this case there are four billing opportunities:

- [0492]** 1. The data traffic for the Netpage click;
- [0493]** 2. The forwarding of the purchase request to the vendor;
- [0494]** 3. The purchase of the content;
- [0495]** 4. The delivery of the content

[0496] The mobile carrier tracks and generate billing records for the data traffic and the delivery of the content. As in the SMS case the delivery message is charged to the receiver rather than the sender, via an agreement with the carrier.

[0497] In this case the billing record for the content purchase generated by the ringtone vendor and would be handled in same way as for the SMS case above. It would be possible to have an agreement with the carrier whereby the cost of the data traffic and the delivery message are waived in return for a payment from the vendor.

[0498] In most cases the Netpage application would be managed by the vendor as an alternative interface to their existing business and as such it does not need to bill for its

forwarding services. If it is run by a different business then it generates a billing record for the forwarding service. This may be delivered either to the user or to the vendor who has agreed to pay for forwarded requests.

[0499] The billing options for the hybrid approach are essentially the same as for when Netpage is a middle man but the number of deliveries, and hence billable events, to the mobile device is increased. In this case the bill for delivering the M-Doc may be changed to the vendor rather than the customer since it is an unsolicited promotion. Each of these billable events could be filtered by the mobile carrier based on later billing records that enter the system. For example, the cost of delivering the M-Doc may be waived or credited back, if the offer on the printout is taken up by another user.

5.8 Digital Rights Management

[0500] Closely related to billing is ensuring that the product or service is only used for the purpose(s) it was purchased for, e.g. a ringtone purchased for one phone, can not be installed on more than one phone, or a music file that is downloaded as a sample can only be played X times before being purchased.

[0501] Digital Rights Management (DRM) schemes are being adopted by mobile device manufactures and mobile carriers. Where content is being delivered via the existing mobile mechanisms DRM is automatically triggered. The Netpage Player on a mobile device is implemented to hook into the DRM mechanisms on the mobile device. It prevents a user by-passing DRM restrictions on downloaded content.

5.9 Identifying the User

[0502] Mobile carriers identify the user of a mobile device when the device negotiates access to the network, either at boot time or when it comes within range of a base station. For GSM and CDMA networks a user's identity is determined by matching the International Mobile Subscriber Identity (IMSI) with a user's records held by the carrier. The IMSI is not sent during negotiation but rather an identity derived from it called a Temporary Mobile Subscriber Identifier (TMSI) is sent. Access to the IMSI can be protected by a PIN and most phones can be set up to prompt the user for a PIN when it is turned on. This is used to gain access to protected data, such as the IMSI. During the connection time negotiations the International Mobile Equipment Identity (IMEI) is also transmitted. This is not used to determine who the user is, but it is used to filter out mobile devices that are blocked from the network, e.g. stolen mobiles can be blocked based on their IMEI.

[0503] When a mobile network allows a user on a GSM network, they assign the user a SIM card and then activate the SIM card. For a non-pre-paid SIM card the user needs to present sufficient identification information that the carrier is satisfied they know who the person is, that they are able to pay their bill, and where to send the bill. For a pre-paid account the carrier does not need such information, but some countries do require carriers to collect user identity information even for pre-paid accounts. Once the user has an activated SIM card it can be used from any handset and the correct account is billed for usage. Users are encouraged to protect their SIM cards with a PIN, so that it cannot be used until a PIN is supplied. However this is not enforced by the carriers, as it is a user choice.

[0504] The Netpage system, includes the concept of a Netpage user, each of whom has a Netpage account. Some

Netpage applications require knowledge of the user. To be able to access those applications via a Netpage pointer or scanner built into a mobile device, a link between the mobile device and a Netpage user is established. To do this there is a configuration and activation step, similar to a SIM card activation where the Netpage sub-systems on the mobile device are configured and a mapping is setup between the user identity for the mobile device and a Netpage user. If the Netpage account is being established for the first time then, as with a mobile carrier, the user identifies themselves so that the Netpage network operator is able to bill the user for any Netpage related costs incurred.

[0505] There are times where a mobile user's identity cannot be determined via a mobile carrier: possibly a company does not want to or cannot get the information from a carrier; the mobile device may be connecting to the network without a carrier being involved; or the carrier may not have the information required, e.g. anonymous pre-paid accounts. In these situations the functionality available to the user can be reduced to functionality that does not require knowledge of the user's identity or additional Netpage specific information can be used to establish the user's identity to the satisfaction of the Netpage system.

[0506] Netpage-specific user identity information is stored on the device during the Netpage registration/activation process. To give the same level of user identity portability as a SIM card the information can be stored on the SIM card, if it is present. If that is not possible, due to a mobile carrier denying access to it or it not being present, it can be stored in a secure store within the device and if that is not possible, on the normal file system of the device. If the identity information is stored on the SIM card, it can automatically move with the user's carrier identity when they swap SIM cards.

6. Use Cases

6.1 M-Print Blanks

[0507] The M-Print printer 4 is able to print on special M-Print blanks that are specially designed to provide optimal print quality in a M-Print printer 4. The blanks are purchased by a user in packs and loaded one-by-one into the printer when a print is being made.

[0508] To ensure valid blanks are loaded into the printer 4, a mechanism for validating the supplied blanks and rejecting imitations can be supplied. This can be done by reading an ID from the blank during printing and validating that ID either locally or via a network service.

[0509] The blanks are pre-tagged. For Netpage to be able to correctly register a printout an ImpressionID is determined from the pre-tagged blank when the printout is printed. This implies the M-Print printer is able to read the ImpressionID from the blank.

[0510] Both cases can use the ID encoded on the blank. The proposed scheme for validating the ID involves reading a second number from the blank called the signature. The signature and ID can then be validated as a pair.

[0511] The proposed mechanism for this is to consult a network based service that securely stores the ID and signature pairs that have been manufactured.

[0512] Both the ID and the signature are readable by the printer 4 and in the Netpage case by a Netpage pointer 533. The M-Print printer 4 does not contain a Netpage pointer 533, but it includes a bar code reader. This means the ID and the signature are provided on the back of the blank as a linear bar

code, most likely in IR ink, for the printer 4 and on the front of the blank encoded in the Netpage tag encoding for the Netpage pointer 533.

[0513] In some circumstances, validation of the ID may not be possible in real time before the printout completes. Thus, users are informed if non-genuine blanks are being loaded into the printer and warn the user that loaded non-genuine blanks may decrease the lifetime of the printer's printhead.

[0514] While complete validation of the ID may not be possible before printing, coding on the blank can be detected that indicates the orientation of the blank and also the start of the timing codes that allow the printer 4 to detect the speed at which the blank is moving through the printer 4. If these can not be detected the blank may be rejected before printing commences.

6.1.1 Loading a Card

[0515] Referring to FIG. 63, a print job has been submitted to the printer 4, before it can commence it must be supplied with a valid blank the right way up.

[0516] 1. The user is prompted to insert a blank (step 750)

[0517] 2. The user inserts a blank (step 751)

[0518] If the user inserts the paper upside down at option 752, the user is prompted to re-insert the blank the other way. If the loaded paper is uncoded or incorrectly coded, the user is prompted to insert a genuine M-Print blank.

6.1.2 Validate an ID

[0519] Referring to FIG. 64, during or immediately after printing the printer 4 sends back the ID and possibly the signature of the blank at step 750. In the background the M-Print services on the mobile device validates the ID at step 757, either locally at step 759 or via a network service at step 758, and if the validation fails it informs the user at step 763. There is a timing issue here in that the user may no longer be looking at the mobile device 100 when the result of validation is known, to alert the user that the blank they have printed on is not valid and that using that media shortens the life of the printhead the M-Print service on the device can deliver the message as a local SMS causing the device to alert the user of a new message.

[0520] Once the ID and signature have been validated it is passed at step 762 onto a Netpage microserver 761 for processing as the ImpressionID of the printout. The user is alerted that the last print was done on an invalid blank and continuing to use such blanks shortens the life of the printer 4.

6.2 Printing

[0521] Common to all the use cases present below is printing. From a users perspective, printing normally has two stages, a third may be added if an error occurs or the blank is invalid:

[0522] 1. Loading the blank

[0523] 2. Printing

[0524] 3. Error reporting

[0525] The user view of loading the blank and reporting an invalid blank are covered above. The user's view of printing is both: a progress dialog that allows the user to view the progress of the print and cancel the print; and being able to see the blank move through the printer and emerge from the device.

[0526] Cancelling the print stops the printer using any more ink, but the ID and signature from the blank may still be read for validation.

6.2.1 Print

[0527] 1. The user is prompted to load a card.

[0528] 2. A print progress dialogue is displayed, with a cancel button

[0529] 3. The blank is drawn fully through the printer and the print progress dialogue is removed

[0530] If the user wants to cancel the print job the user presses cancel on the print progress bar which results in the print job stopping and the blank being ejected. If an error occurs such as a paper jam, an error message may be provided to alert the user. The user may then dismiss the dialog of the error message and progress dialogs are removed. If a blank fails validation, the user is alerted of the failure.

[0531] FIG. 65 shows a Printer DC 770 as the object that exposes the graphics model used by applications 514 to build up the printed image. It shows the printing following after the application 514 has completed drawing the page. On some systems these operations may overlap or the application 514 may be requested to draw the page multiple times with different clipping regions, eg. rendering in bands, either way the logical flow should still be the same. If capturing all printed documents as Netpage documents is supported then fully composed page is lodged with the Microserver 761, the Microserver 761 treats this a document lodgement, and records a printout for that document, when the ID and signature are successfully validated and passed onto the microserver 761.

[0532] FIG. 65 shows the ID and signature being passed out from the printer 4 soon after printing has commenced, the timing of the transmission of the ID and signature is not significant for the user since they only know about it if the validation fails which occurs after the print has completed. For Netpage enabled printouts, this timing is more critical, since a situation can occur where a printout is immediately handed to another user who clicks on it with a Netpage pointer or pen 733 and expects a result. Where the printing device does not have network connectivity this may not work at all. If the printing device does have network connectivity it still might not work, or at least have a perceivable latency, while the network validation and the ID and registration of the printout is completed.

6.3 Uploading and Downloading Data

[0533] Moving data on and off mobile devices via the wireless network reliably presents a number of challenges:

[0534] 1. Wireless networks are inherently unreliable and the link can be lost at any point. This can occur due to signal loss or the mobile device having to disable the radio link to conserve power or to allow another power hungry activity to start up, eg. printing.

[0535] 2. The bandwidth available on the existing 2.5 G networks is limited and it could take up to several minutes to transmit a high resolution photo on or off the device

[0536] 3. The cost of transferring data over a mobile network can vary and it may be significantly cheaper to delay the transfer to a non-peak time, e.g. late at night.

[0537] 4. Mobile carriers might prefer non-urgent data transfers to happen during lulls in the network traffic.

[0538] 5. It may be cost effective to support different means of transferring data. A HTTP Put over GPRS is the most obvious way, but it may be possible to take advantage of carrier price subsidies and send the same data via an MMS or SMS message.

[0539] Referring to FIGS. 66 and 67, to provide flexibility in how data uploading and downloading is achieved and to insulate the rest of the architecture from it, each mobile device 100 has a service responsible for delivering and receiving data from the network. It queues data transfer requests 780 and guarantees delivery of the data in the an efficient manner. It supports partial transfers and resumption of transfers after a break in the data link to minimise the data sent over a wireless network. An equivalent service can be located in the network to both receive data from the mobile device and forward it on to its destinations and also to queue data being sent to the mobile device.

[0540] The network based component of this service provides a carrier integration point. A carrier may choose to host this service and bill the traffic for it differently to encourage usage of the M-Print and Netpage services. It also provides a single point of modification to take advantage of new features in the carrier networks, eg. a new data push model not based on SMS.

[0541] The device based component of this service provides a simple interface to the device based M-Print and Netpage services, while providing the ability to exploit all the features of a mobile device 100 to access network based services. This may include taking advantage of WLAN connectivity where possible.

[0542] The download sequence shown in FIG. 67 illustrates how “data push” to a mobile device can be achieved which cannot be directly reached from the general internet. It shows a SMS message being sent to the device to inform the download service that there are downloads waiting to be fetched. The message may include some information about the urgency of the downloads, to allow the device side download service to decide when it should fetch the download(s).

6.4 Netpage Pointer/Scanner

[0543] In the printing scenario a blank’s ID is read during printing. This ID is used to both facilitate validation of the blank as a valid M-Print blank and also as an Impression ID for Netpage. The Impression ID is used by the Netpage server 529 to associate the M-Print printout with the document that was printed onto the blank.

[0544] An M-Print blank has the ID encoded on the back of the blank in a way that is readable by the paper feed mechanism. If the blank has been pre-tagged with Netpage tags then the ID is also embedded in the Netpage tags. To initiate a Netpage interaction the first step is for the user to perform an action that retrieves the ID and supplies it to a Netpage server. The ID can be retrieved by:

- [0545] 1. A stroke or click with a Netpage Pen;
- [0546] 2. A click with a Netpage Pointer;
- [0547] 3. Scanning the ID on the back of the card.

[0548] The first two of these actions use Netpage specific devices to read the Netpage tags. The pen 533 provides a stream of digital ink along with the ID and the pointer provides a position on the printout along with the ID. The last uses a scanning mechanism to read the ID from the back of the printout. It can be the same scanner as is used in the M-Print printer paper feed mechanism or it can be a dedicated scanner that the printout is feed into or passed over, similar to a bar

code reader. This mechanism only provides the ID, it does not provide any positional information, but Netpage applications can be authored to support a “scan” of the printout as well as a click or a stroke on the printout.

6.4.1 Activate a Netpage Application Via a Scan

[0549] The user passes an existing M-Print printout back through their M-Print printer to activate the associated Netpage application.

[0550] The printout is drawn through the printer and a Netpage application is launched. If there is no Netpage application for the printout, the user is told the printout has no associated application. If the printout fails validation, the user is alerted of the failure.

[0551] The effect the user sees as a result of a Netpage application being launched varies depending on the application, some examples are:

- [0552] For a photo the use may see the photo displayed on the screen with the option to reprint it or send to someone.
- [0553] For a business card the user may receive a vCard on their mobile device which can be processed in the normal way.
- [0554] For a coupon a completed SMS/MMS/email may be displayed asking the user if they wish to send it off to enter the competition.
- [0555] Any printout may be displayed on the mobile device showing the print image and allowing the user to navigate the hyperlinks and fields in the printout and activate them. If the device has a touch screen, the user can use a pointer to select fields and generate digital ink.

[0556] FIG. 68 is a sequence fragment that shows the processing of a scanned ID from the paper feed mechanism in the printer. If a scanned ID and signature is returned to the Print Service while it is printing, see FIG. 65, it is validated and then passed onto the Netpage Microserver 761 triggering the submission of the Netpage document. The validation is performed by the Print Service 754 in this case to ensure the user can be warned about using invalid media as early as possible. If the Printer Service receives a scanned ID and signature while it is not printing at step 790 then it passes it directly to the Netpage Microserver 761 as a pseudo-click or scan. The Microserver 761 processes it in a similar way to the way it processes a Netpage pointer click.

7. Applications

[0557] 7.1 Photo Printing Photo printing is a major application for M-Print. In its simplest form, photo printing can be done completely locally, without any dependence on network services or interactions. Printing a photo can interact with a photo archive. If a photo is printed then it is likely the user may wish to access or print the photo again. When a photo is printed it can be pushed out to the photo archive making it available for on-line retrieval or access. Netpage functionality offers a convenient and natural way of interacting with a printed photo. A Netpage enabled photo can act as a permission token, giving the holder of the printout permission to retrieve and reprint the photo from the archives Photo archiving from mobile devices is an independent application

from photo printing. Users typically take more photos than they wish to keep in an archive than they wish to print.

7.1.1 Local Photo Printing

[0558] Referring to FIG. 69, a camera phone user takes a photo at step 795 and elects to print it.

[0559] 1. The user uses the default photo application 796 on their device and takes a photo at step 795

[0560] 2. The user selects print from the applications menu

[0561] 3. The user is prompted to load a blank

[0562] 4. The print is produced

[0563] Other options include:

[0564] The user prints with a border at step 797 by selecting print options from the menu before printing and selects to print with a border, and the user can then select print from the applications menu.

[0565] The user requests the date is printed with the photo at step 798 by selecting print options from the menu and selecting the print date and time option, and the user can then select print from the applications menu.

[0566] The user adds a caption at step 799 where the user selects photo options from the menu and selects add caption,

[0567] wherein the user is prompted to enter a caption and the user selects print from the applications menu.

7.1.2 Printing a Photo Archives the Photo

[0568] Referring to FIG. 70, printing a photo generally implies that the photo has more worth to the user than the photos the user has taken and not printed, it is more likely to be shared and hence more likely to be referred to in an archive. This scenario describes pushing a photo that is printed to the photo archive on the mobile device 100 to give it priority in being transferred off the device 100 and into the archive 800.

[0569] When the photo is pushed to the archive the user is given the opportunity to specify what access permission's should be applied to the photo at step 801 in the archive 800. In this scenario it is kept to public or private 802 for simplicity, but it could easily be a more complex selection from various ACLs (Access Control Lists) maintained by the user.

[0570] 1. The user uses the default photo application 796 on their device 100 and takes a photo.

[0571] 2. The user may set some print options 801

[0572] 3. The user selects print from the applications menu 803

[0573] 4. The user is prompted whether the photo should be public or private in the archive 802

[0574] 5. The user is prompted to load a blank

[0575] 6. The print is produced.

[0576] Optionally, default settings may be applied for archiving the images where the user may not be prompted if the default settings indicate whether all photos should be public or private.

[0577] This sequence diagram shows the most likely case, where uploading the photo to the archive occurs after printing has finished. This is the most likely case, since power demands of printing require the network connectivity section of the phone to be powered down, or at least avoided. Some devices may be able to support both, in which case the upload could occur during the print. The photo archive is accessible from both a browser on a mobile device 100 or a desktop

browser. The user is able to print a photo from the archive to either a desktop printer or the printer in their mobile device.

7.1.3 Printing Archives a Netpage Enabled Photo

[0578] In this use case the user interactions are the same as for "Printing a Photo Archives the Photo", but in the background, the document, the printout, and the impression ID are registered with the Netpage infrastructure. The printout can be interacted with via a Netpage pointer 533 immediately on the device it was printed on, but it is not be active for other pointers or pens until it has been successfully uploaded to the network based Netpage services.

[0579] Referring to FIG. 71, for Netpage enabled photos that already are being archived in a general purpose photo archive it is not desirable for the Netpage server 529 to also store the photo, so the Netpage server 529 stores a reference to the photo in the archive 800, allowing it to be retrieved when necessary. The Netpage server 529 still tracks user interactions with the photo: reprints, digital ink, etc but it generally does not store the actual image itself. When the photo is pushed to the archive the pusher receives a reference to the photo that can be used to retrieve the photo when it is required.

[0580] The need to move the photo and the Netpage document associations out into the network to enable general Netpage interactive on the printed photo, gives the pushing of the photo to the photo archive more importance. In this case the push to the archive includes a flag indicating the photo should be moved to the off device archive as soon as possible. The registering of a printout with the Netpage services can not complete until the blank has been validated since the ID is used as the Netpage impression ID.

[0581] In this case the photo reference rather than the photo is lodged with the Netpage microserver. The printout can be interacted with via a Netpage pointer on the same device after the ID and signature have been validated, but other pointers and pens can only interact with the document after it has been successfully uploaded to the Netpage network server.

8. Player Use Cases

8.1 Business Card Application

[0582] This section covers the Netpage Player PlayRequests 521 used in the interactive Netpage Business Card and describes the behaviour of the Player Agents 537 handling such objects and commands. FIG. 72 shows the sample business card 810. The fields (text 811 and images 812) are generally associated with PlayRequests 521 that (partially) specify what action is required when a user clicks on one of the fields with a Netpage pointer 533.

8.1.1 Phone Number

[0583] Referring to FIG. 73, the phone number fields 817, 818 on the business card 810 are associated with PlayRequests 816, 819 that simply specify a phone number, without specifying the operation to be performed or the target of the operation. The author of the business card 810 is thus providing maximum freedom to the receiver of the business card 810 to make use of the phone number fields as they see fit. For example, one user may have their system configured to react to such PlayRequests 816, 819 by having their mobile phone dial the specified number, while another user may prefer to

have such PlayRequests **816**, **819** simply pushed to the Netpage Clipboard **615** for later use.

[**0584**] The mobile phone icon **813** is configured with a more fully specified PlayRequest **809** than the phone number fields **817**, **818**. The PlayRequest **809** specifies an operation (“dial”) that should be performed when that field is selected. The operation overrides the default handling of phone-number values that might otherwise be performed in the absence of an explicit operation. Note that the target of the request is still left unspecified. This gives the routing system the freedom to determine the most appropriate device with which to make the call. This is especially appropriate for a business card **810** which might be handed out to hundreds of users who each typically have their own phone. Placing a specific target in the PlayRequest would have been possible, although inappropriate in this case. The landline telephone icon **813** is configured similarly to the mobile phone icon, but with a different value for the phone number.

8.1.2 Fax Number

[**0585**] Referring to FIG. **74**, the Fax phone number field **820** is configured exactly as for the phone number fields except that the phone number value is now also marked as belonging to the “fax” category **823**. This additional information can potentially be used during request routing in order to select targets which specifically cater for “fax” phone numbers rather than targets which simply specify that they cater for phone numbers in general. The “fax” button field **821** specifies an operation (“fax”) in the PlayRequest **822**. The exact semantics of that operation are target dependant. For example, on a mobile phone, the Fax Agent might launch the Fax editor with the destination fax number pre-configured.

8.1.3 Web Address

[**0586**] Referring to FIG. **75**, the web URL field **824** and “WWW” icon **825** are configured similarly to the phone number field and phone icons. The icon **825** is specifically configured to cause a web browser to be invoked **826** on the specified URL, whereas the PlayRequest **827** for the URL field is less fully specified and is therefore more flexible in terms of its possible interpretations.

8.1.4 SMS and MMS Fields

[**0587**] Referring to FIG. **76**, the “SMS” field **829** is configured to invoke an “SMS” operation **831**. This request could be routed to an SMS Agent running on the user’s mobile phone which would launch the SMS editor with the destination phone number filled in. The “MMS” field **828** is configured similarly to the “SMS” field.

8.1.5 Email Address

[**0588**] Referring to FIG. **77**, the web email address field **833** and “Email” icon **832** are configured similarly to the phone number field and phone icons. The icon **832** is specifically configured to perform a “create-email” operation **834**, which can typically be handled routing the request to an agent which is capable of launching email tool with the destination email address pre-configured. The email address field **833** is less fully specified and is therefore more flexible in terms of its possible interpretations.

8.1.6 Street Address

[**0589**] Referring to FIG. **78**, the Street Address field **836** is configured to map to a PlayRequest **837** that contains a loca-

tion value **841** specified using a type of location. The specific details of this type are not specified in this document. The important thing to note is that it stores information that specifies the location in various ways. As such, the value can be handled differently by a large number of agents. Examples might be:

[**0590**] A Web MAP Search Agent which presents the location in a web browser by accessing a web-based map search facility

[**0591**] A Print Agent on an m-print phone which prints the location details (and possibly directions) on an m-print card.

[**0592**] A GPS Navigator Agent which displays the location in a handheld GPS device.

8.1.7 Photo

[**0593**] Referring to FIG. **79**, the Name field **838** and “Photo” icon **839** are configured to map to a PlayRequest **840** that specifies a jpeg photograph. Typically, this request can be routed to an agent capable of displaying the image.

8.2 Scanning Support

[**0594**] Referring to FIG. **80**, interactive Netpage documents can be authored to specify an action upon reception of a scan event. A scan event simply contains the ID of the printed document without any {x,y} coordinate information. In the m-print context, a scan is achieved by feeding a printed card back through the paper feed mechanism. This enables the m-print device to determine the ID of the card and to transmit a scan-hit to the Netpage Server **529**. Upon reception of a scan-hit, the server **529** invokes any scan action that has been registered for the identified printout.

[**0595**] The printed business card **820** can be authored to invoke a PlayRequest **851** in response to a scan event. Typically, such a PlayRequest **851** provides information pertaining to the entire content of the printout. In the case of the business card, the document can be authored to invoke a PlayRequest **851** that contains a text/directory object **852** that specifies most of the details from the card. Such a PlayRequest **851** would typically be routed to a Contacts Application (such as vCard Agent) which would then modify its database to include the details from the business card.

8.2.1 M-Print Photo Cards Including Scan Support

[**0596**] FIG. **81** shows a printed photo card **855**. The card **855** can be made to be interactive as shown in FIG. **82**. The card **855** contains two fields. The first field is a standard Netpage field **856**, while the second is the scan event field **857**. Both fields **856**, **857** are configured to map to a PlayRequest **858** that contains the contents of the photo in electronic form (in this case as a jpeg image). Typically, this request **858** is routed to an agent capable of displaying the image, although the fact that the request is only partially specified (the target and operation field are empty) gives the request router (and therefore the user) more freedom to interpret the request as appropriate. For example, previous actions by the user may mean that clicking on the photo is interpreted as a request to associate the photo with a particular location on printed Netpage document.

8.3 Printout Interactivity on the Mobile Device GUI

[**0597**] When a scan of an M-Print printout is performed on a mobile device **100** the action taken can vary. One possible

action is to display the printout on the mobile device's GUI with the hyperlinks and form fields active so that a user can navigate between them and fill them in or activate them, in the same way a Netpage user can on a printout using a Netpage pen or pointer.

[0598] If the mobile device has a touch screen and a stylus then it is possible to support all the interactions that a user with a Netpage pen could have with the printout. If the mobile device doesn't support a touch screen and stylus then it is possible to tab through the hyperlinks and submit fields on the form and activate them in the same way that a user with Netpage pointer and a printout could.

[0599] FIG. 83 shows a mobile phone 100 where an M-Print printout of a business card 820 has been scanned and the printout is now displayed on the phone's screen 860 with the first hyperlink 861 highlighted ready to be selected. The user can move through the active areas using standard navigation keys 862 on the mobile device 100, in the same way they can navigate the hyperlinks on a web page. Selecting a hyperlink in this way via the GUI is the same as clicking a Netpage Pointer 533 on the printout of the business card 820.

[0600] Below is a use case illustrating the sequence of events for a user to activate a hyperlink by scanning the printout.

8.3.1 Scan a Business Card and Send an MMS to the Person

- [0601] 1. The user inserts a printout into the paper feed slot on the mobile device (870)
- [0602] 2. The printout is drawn through the mobile device
- [0603] 3. The image on the printout is displayed on the mobile device (880), the first hyperlink has a focus region drawn around it
- [0604] 4. The user moves focus to the MMS hyperlink and selects it
- [0605] 5. The MMS editor on the device is displayed with the address filled out from the details on the business card (890).

[0606] The upper portion of the sequence diagram in FIG. 84 is a repeat of the sequence for the case where a scan is occurring. When the Netpage Microserver receives the "scan click" it retrieves the document and displays it on the screen using the Document Displayer. The Document Displayer allows the user to step through the hyperlinks and fields and select them. When one is selected the Netpage Microserver is sent a click event, just as if it had come from a Netpage pointer. The Netpage processing results in a play request being sent to the Netpage Player on the device, which responds by opening up the MMS editor with the message already addressed to the recipient identified by the business card that was scanned in.

9.0 Mobile Telecommunications Device Overview

[0607] Whilst the main embodiment includes both Netpage and printing functionality, only one or the other of these features is provided in other embodiments.

[0608] One such embodiment is shown in FIG. 85, in which a mobile telecommunications device in the form of a mobile phone 1 (also known as a "cellphone") includes a mobile phone module 2 and a printer module 4. The mobile 30 phone module is configured to send and receive voice and data via a telecommunications network (not shown) in a conventional manner known to those skilled in the art. The printer module

4 is configured to print a page 6. Depending upon the particular implementation, the printer module 4 can be configured to print the page 6 in color or monochrome.

[0609] The mobile telecommunications device can use any of a variety of known operating systems, such as Symbian (with UIQ and Series 60 GUIs), Windows Mobile, PalmOS, and Linux.

[0610] In the preferred embodiment (described in more detail below), the print media is pre-printed with tags, and the printer module 4 prints visible information onto the page 6 in registration with the tags. In other embodiments, Netpage tags are printed by the printer module onto the page 6 along with the other information. The tags can be printed using either the same visible ink as used to print visible information, or using an infrared or other substantially invisible ink.

[0611] The information printed by the printer module 4 can include user data stored in the mobile phone 1 (including 10 phonebook and appointment data) or text and images received via the telecommunications network or from another device via a communication mechanism such as Bluetooth™ or infrared transmission. If the mobile phone 1 includes a camera, the printer module 4 can be configured to print the captured images. In the preferred form, the mobile phone module 2 provides at least basic editing capabilities to enable cropping, filtering or addition of text or other image data to the captured image before printing. The configuration and operation of the printer module 4 is described in more detail below in the context of various types of mobile telecommunication device that incorporate a printhead.

[0612] FIG. 86 shows another embodiment of a mobile telecommunications device, in which the printer module 4 is omitted, and a Netpage tag sensor module 8 is included. The Netpage module 8 enables interaction between the mobile phone 1 and a page 10 including Netpage tags. The configuration and operation of the Netpage pointer in a mobile phone 1 is described in more detail below. Although not shown, the mobile phone 1 with Netpage module 8 can include a camera.

[0613] FIG. 87 shows a mobile phone 1 that includes both a printer module 4, and a Netpage tag sensor module 8. As with the embodiment of FIG. 86, the printer module 4 can be configured to print tagged or untagged pages. As shown in FIG. 87, where tagged pages 10 are produced (and irrespective of whether the tags were pre-printed or printed by the printer module 4), the Netpage tag sensor module 8 can be used to interact with the resultant printed media.

[0614] A more detailed architectural view of the mobile phone 1 of FIG. 87 is shown in FIG. 88, in which features corresponding to those shown in FIG. 87 are indicated with the same reference numerals. It will be appreciated that FIG. 88 deals only with communication between various electronic components in the mobile telecommunications device and omits mechanical features. These are described in more detail below.

[0615] The Netpage tag sensor module 8 includes a monolithically integrated Netpage image sensor and processor 12 that captures image data and receives a signal from a contact switch 14. The contact switch 14 is connected to a nib (not shown) to determine when the nib is pressed into contact with a surface. The sensor and processor 12 also outputs a signal to control illumination of an infrared LED 16 in response to the stylus being pressed against the surface. The image sensor and processor 12 outputs processed tag information to a Netpage pointer driver 18 that interfaces with the phone oper-

ating system 20 running on the mobile telecommunications device's processor (not shown).

[0616] Output to be printed is sent by the phone operating system 20 to a printer driver 22, which passes it on to a MoPEC chip 24. The MoPEC chip processes the output to generate dot data for supply to the printhead 26, as described in more detail below. The MoPEC chip 24 also receives a signal from a media sensor 28 indicating when the media is in position to be printed, and outputs a control signal to a media transport 30.

[0617] The printhead 26 is disposed within a replaceable cartridge 32, which also includes ink 34 for supply to the printhead.

9.1 Mobile Telecommunications Device Module

[0618] FIG. 89 shows the mobile phone module 2 in more detail. The majority of the components other than those directly related to printing and Netpage tag sensing are standard and well known to those in the art. Depending upon the specific implementation of the mobile phone 1, any number of the illustrated components can be included as part of one or more integrated circuits.

[0619] Operation of, and communication between, the mobile phone module 2 components is controlled by a mobile phone controller 36. The components include:

- [0620] 'mobile radio transceiver 38 for wireless communication with a mobile telecommunications network;
- [0621] program memory 40 for storing program code for execution on the mobile phone controller 36;
- [0622] working memory 42 for storing data used and generated by the program code during execution. Although shown as separate from the mobile phone controller 36, either or both memories 40 and 42 may be incorporated in the package or silicon of the controller;
- [0623] keypad 44 and buttons 46 for accepting numerical and other user input;
- [0624] touch sensor 48 which overlays display 50 for accepting user input via a stylus or fingertip pressure;
- [0625] removable memory card 52 containing non-volatile memory 54 for storing arbitrary user data, such as digital photographs or files;
- [0626] local area radio transceiver 56, such as a Bluetooth™ transceiver;
- [0627] GPS receiver 58 for enabling determination of the location of the mobile telecommunications device (alternatively the phone may rely on mobile network mechanisms for determining its location);
- [0628] microphone 60 for capturing a user's speech;
- [0629] speaker 62 for outputting sounds, including voice during a phone call;
- [0630] camera image sensor 64 including a CCD for capturing images;
- [0631] camera flash 66;
- [0632] power manager 68 for monitoring and controlling power consumption of the mobile telecommunications device and its components; and
- [0633] SIM (subscriber Identity Module) card 70 including SIM 72 for identifying the subscriber to mobile networks.

[0634] The mobile phone controller 36 implements the baseband functions of mobile voice and data communications protocols such as GSM, GSM modem for data, GPRS and CDMA, as well as higher-level messaging protocols such as SMS and MMS. The one or more local-area radio transceivers

56 enable wireless communication with peripherals such as headsets and Netpage pens, and hosts such as personal computers. The mobile phone controller 36 also implements the baseband functions of local-area voice and data communications protocols such as IEEE 802.11, IEEE 802.15, and Bluetooth™.

[0635] The mobile phone module 2 may also include sensors and/or motors (not shown) for electronically adjusting zoom, focus, aperture and exposure in relation to the digital camera. Similarly, as shown in FIG. 90, components of the printer module 4 include:

- [0636] print engine controller (PEC) 74 in the form of a MoPEC device;
- [0637] program memory 76 for storing program code for execution by the print engine controller 74;
- [0638] working memory 78 for storing data used and generated by the program code during execution by the print engine controller 74; and
- [0639] a master QA chip 80 for authenticating printhead cartridge 32 via its QA chip 82.

[0640] Whilst the printhead cartridge in the preferred form includes the ink supply 34, the ink reservoirs can be housed in a separate cartridge in alternative embodiments.

[0641] FIG. 91 shows the components of the tag sensor module 8, which includes a CMOS tag image processor 74 that communicates with image memory 76. A CMOS tag image sensor 78 sends captured image data to the processor 74 for processing. The contact sensor 14 indicates when a nib (not shown) is brought into contact with a surface with sufficient force to close a switch within the contact sensor 14. Once the switch is closed, the infrared LED 16 illuminates the surface, and the image sensor 78 captures at least one image and sends it to the image processor 74 for processing. Once processed (as described below in more detail), image data is sent to the mobile phone controller 36 for decoding.

[0642] In an alternative embodiment, shown in FIG. 92, the tag sensor module 8 is replaced by a tag decoder module 81. The tag decoder module 81 includes all the elements of the tag sensor module 8, but adds a hardware-based tag decoder 82, as well as program memory 84 and working memory 86 for the tag decoder. This arrangement reduces the computational load placed on the mobile phone controller, with a corresponding increase in chip area compared to using the tag sensor module 8.

[0643] The Netpage sensor module can be incorporated in the form of a Netpage pointer, which is a simplified Netpage pen suitable mostly for activating hyperlinks. It preferably incorporates a non-marking stylus in place of the pen's marking nib (described in detail later in the specification); it uses a surface contact sensor in place of the pen's continuous force sensor; and it preferably operates at a lower position sampling rate, making it unsuitable for capturing drawings and handwriting. A Netpage pointer is less expensive to implement than a Netpage pen, and tag image processing and tag decoding can potentially be performed by software without hardware support, depending on sampling rate.

[0644] The various aspects of the invention can be embodied in any of a number of mobile telecommunications device types. Several different devices are described here, but in the interests of brevity, the detailed description will concentrate on the mobile telecommunications device embodiment.

9.2 Mobile Device

[0645] One preferred embodiment is the non-Netpage enabled 'candy bar' mobile telecommunications device in the

form of a mobile phone shown in FIGS. 92 to 98. While a candy bar style phone is described here, it could equally take the form of a “flip” style phone, which includes a pair of body sections that are hinged to each other. Typically, the display is disposed on one of the body sections, and the keypad is disposed on the other, such that the display and keypad are positioned adjacent to each other when the device is in the closed position.

[0646] In further embodiments, the device can have two body sections that rotate or slide relative to each other. Typically, the aim of these mechanical relationships between first and second body sections is to protect the display from scratches and/or the keypad from accidental activation. Photo printing is considered one of the most compelling uses of the mobile Memjet printer. A preferred embodiment of the invention therefore includes a camera, with its attendant processing power and memory capacity.

[0647] The elements of the mobile telecommunications device are best shown in FIG. 93, which (for clarity) omits minor details such as wires and hardware that operatively connect the various elements of the mobile telecommunications device together. The wires and other hardware will be well known to those skilled in the art. The mobile phone 100 comprises a chassis moulding 102, a front moulding 104 and a rear cover moulding 106. A rechargeable battery 108, such as a lithium ion or nickel metal hydride battery, is mounted to the chassis moulding 102 and covered by the rear cover moulding 106. The battery 108 powers the various components of the mobile phone 100 via battery connector 276 and the camera and speaker connector 278.

[0648] The front moulding 104 mounts to the emphasis to enclose the various components, and includes numerical interface buttons 136 positioned in vertical rows on each side of the display 138. A multi-directional control pad 142 and other control buttons 284 enable menu navigation and other control inputs. A daughterboard 280 is mounted to the chassis moulding 102 and includes a directional switch 286 for the multi directional control pad 142. The mobile telecommunications device includes a cartridge access cover 132 that protects the interior of the mobile telecommunications device from dust and other foreign objects when a print cartridge 148 is not inserted in the cradle 124.

[0649] An optional camera module 110 is also mounted to the chassis moulding 102, to enable image capture through a hole 112 in the rear cover moulding 106. The camera module 110 includes a lens assembly and a CCD image sensor for capturing images. A lens cover 268 in the hole 112 protects the lens of the camera module 110. The rear cover moulding 106 also includes an inlet slot 228 and an outlet slot 150 through which print media passes.

[0650] The chassis moulding 102 supports a data/recharge connector 114, which enables a proprietary data cable to be plugged into the mobile telecommunications device for uploading and downloading data such as address book information, photographs, messages, and any type of information that might be sent or received by the mobile telecommunications device. The data/recharge connector 114 is configured to engage a corresponding interface in a desktop stand (not shown), which holds the mobile telecommunications device in a generally upright position whilst data is being sent or received by the mobile telecommunications device. The data/recharge connector also includes contacts that enable recharging of the battery 108 via the desktop stand. A separate recharge socket 116 in the data/recharge connector 114 is

configured to receive a complimentary recharge plug for enabling recharging of the battery when the desktop stand is not in use.

[0651] A microphone 170 is mounted to the chassis moulding 102 for converting sound, such as a user's voice, into an electronic signal to be sampled by the mobile telecommunications device's analog to digital conversion circuitry. This conversion is well known to those skilled in the art and so is not described in more detail here. A SIM (Subscriber Identity Module) holder 118 is formed in the chassis moulding 102, to receive a SIM card 120. The chassis moulding is also configured to support a print cartridge cradle 124 and a drive mechanism 126, which receive a replaceable print cartridge 148. These features are described in more detail below. Another moulding in the chassis moulding 102 supports an aerial (not shown) for sending and receiving RF signals to and from a mobile telecommunications network.

[0652] A main printed circuit board (PCB) 130 is supported by the chassis moulding 102, and includes a number of momentary pushbuttons 132. The various integrated and discrete components that support the communications and processing (including printing processing) functions are mounted to the main PCB, but for clarity are not shown in the diagram.

[0653] A conductive elastomeric overlay 134 is positioned on the main PCB 130 beneath the keys 136 on the front 40 moulding 104. The elastomer incorporates a carbon impregnated pill on a flexible profile. When one of the keys 136 is pressed, it pushes the carbon pill to a 2-wire open circuit pattern 132 on the PCB surface. This provides a low impedance closed circuit. Alternatively, a small dome is formed on the overlay corresponding to each key 132.

[0654] Polyester film is screen printed with carbon paint and used in a similar manner to the carbon pills. Thin adhesive film with beryllium copper domes can also be used. A loudspeaker 144 is installed adjacent apertures 272 in the front moulding 104 to enable a user to hear sound such as voice communication and other audible signals.

[0655] A color display 138 is also mounted to the main PCB 130, to enable visual feedback to a user of the mobile telecommunications device. A transparent lens moulding 146 protects the display 138. In one form, the transparent lens is touch-sensitive (or is omitted and the display 138 is touch sensitive), enabling a user to interact with icons and input text displayed on the display 138, with a finger or stylus.

[0656] A vibration assembly 274 is also mounted to the chassis moulding 102, and includes a motor that drives an eccentrically mounted weight to cause vibration. The vibration is transmitted to the chassis 102 and provides tactile feedback to a user, which is useful in noisy environments where ringtones are not audible.

10. Print Media Printing

[0657] A Netpage printer normally prints the tags which make up the surface coding on demand, i.e. at the same time as it prints graphic page content. As an alternative, in a Netpage printer not capable of printing tags such as the preferred embodiment, pre-tagged but otherwise blank Netpages can be used. The printer, instead of being capable of tag printing, typically incorporates a Netpage tag sensor. The printer senses the tags and hence the region ID of a blank either prior to, during, or after the printing of the graphic page content onto the blank. It communicates the region ID to the

Netpage server, and the server associates the page content and the region ID in the usual way.

[0658] A particular Netpage surface coding scheme allocates a minimum number of bits to the representation of spatial coordinates within a surface region. If a particular media size is significantly smaller than the maximum size representable in the minimum number of bits, then the Netpage code space may be inefficiently utilised. It can therefore be of interest to allocate different sub-areas of a region to a collection of blanks. Although this makes the associations maintained by the Netpage server more complex, and makes subsequent routing of interactions more complex, it leads to more efficient code space utilisation. In the limit case the surface coding may utilise a single region with a single coordinate space, i.e. without explicit region IDs.

[0659] If regions are sub-divided in this way, then the Netpage printer uses the tag sensor to determine not only the region ID but also the surface coding location of a known physical position on the print medium, i.e. relative to two edges of the medium. From the surface coding location and its corresponding physical position on the medium, and the known (or determined) size of the medium, it then determines the spatial extent of the medium in the region's coordinate space, and communicates both the region ID and the spatial extent to the server. The server associates the page content with the specified sub-area of the region.

[0660] A number of mechanisms can be used to read tag data from a blank. A conventional Netpage tag sensor incorporating a two-dimensional image sensor can be used to capture an image of the tagged surface of the blank at any convenient point in the printer's paper path. As an alternative, a linear image sensor can be used to capture successive line images of the tagged surface of the blank during transport. The line images can be used to create a two-dimensional image which is processed in the usual way. As a further alternative, region ID data and other salient data can be encoded linearly on the blank, and a simple photodetector and ADC can be used to acquire samples of the linear encoding during transport.

[0661] One important advantage of using a two-dimensional image sensor is that tag sensing can occur before motorised transport of the print medium commences. For example, if the print medium is manually inserted by the user, then tag sensing can occur during insertion. This has the further advantage that if the tag data is validated by the device, then the print medium can be rejected and possibly ejected before printing commences. For example, the print medium may have been pre-printed with advertising or other graphic content on the reverse side from the intended printing side. The device can use the tag data to detect incorrect media insertion, i.e. upside-down or back-to-front. The device can also prevent accidental overprinting of an already-printed medium. And it can detect the attempted use of an invalid print medium and refuse printing, eg. to protect print quality. The device can also derive print medium characteristics from the tag data, to allow it to perform optimal print preparation.

[0662] If a linear image sensor is used, or if a photodetector is used, then image sensing must occur during motorised transport of the print medium to ensure accurate imaging. Unless there are at least two points of contact between the transport mechanism and the print medium in the printing path, separated by a minimum distance equal to the tag data acquisition distance, tag data cannot be extracted before printing commences, and the validation advantages discussed

above do not obtain. In the case of a linear image sensor, the tag data acquisition distance equals the diameter of the normal tag imaging field of view. In the case of a photodetector, the tag data acquisition distance is as long as the required linear encoding.

[0663] If the tag sensor is operable during the entire printing phase at a sufficiently high sampling rate, then it can also be used to perform accurate motion sensing, with the motion data being used to provide a line synchronisation signal to the print engine. This can be used to eliminate the effects of jitter in the transport mechanism.

[0664] FIGS. 100 to 106 show one embodiment of the encoded medium and the media sensing and printing system within the mobile telecommunications device. While the encoding of the cards is briefly discussed here, it is described in detail in the Coded Media sub-section of this specification.

[0665] Referring to FIG. 100, the 'back-side' of one of the cards 226 is shown. The back-side of the card has two coded data tracks: a 'clock track' 434 and a 'data track' 436 running along the longitudinal sides of the cards. The coded data may be in the form of a two-dimensional grid or pattern. The cards are encoded with data indicating, inter alia:

- [0666]** the orientation of the card;
- [0667]** the media type and authenticity;
- [0668]** the longitudinal size;
- [0669]** the pre-printed side;
- [0670]** detection of prior printing on the card; and,
- [0671]** the position of the card relative to the printhead IC.

[0672] In one form, the encoded data is printed in IR ink so that it is invisible and does not encroach on the space available for printing visible images.

[0673] In a basic form, the M-Print cards 226 are only encoded with a data track and clocking (as a separate clock track or a self-clocking data track). However, in the more sophisticated embodiment shown in the figures, the cards 226 have a pre-printed Netpage tag pattern 438 covering the majority of the back-side. The front side may also have a pre-printed tag pattern. It is preferred in these embodiments that the data track encodes first information that is at least indicative of second information encoded in the tags. Most preferably, the first information is simply the document identity that is encoded in each of the tags.

[0674] The clock track 434 allows the MoPEC 326 (see FIG. 101) to determine, by its presence, that the front of the card 226 is facing the printhead 202, and allows the printer to sense the motion of the card 226 during printing. The clock track 434 also provides a clock for the densely coded data track 436.

[0675] The data track 436 provides the Netpage identifier and optionally associated digital signatures which allows MoPEC 326 to reject fraudulent or un-authorised media 226, and to report the Netpage identifier of the front-side Netpage tag pattern to a Netpage server. It should be noted that a fragment of a digital signature can also be considered a digital signature in its own right.

[0676] FIG. 101 shows a block diagram of an M-Print system that uses media encoded with separate clock and data tracks. The clock and data tracks are read by separate optical encoders. The system may optionally have an explicit edge detector 474 which is discussed in more detail below in relation to FIG. 104.

[0677] FIG. 102 shows a simplified circuit for an optical encoder which may be used as the clock track or data track

optical encoder. It incorporates a Schmitt trigger **466** to provide the MoPEC **326** with an essentially binary signal representative of the marks and spaces encountered by the encoder in the clock or data track. An IR LED **472** is configured to illuminate a mark-sized area of the card **226** and a phototransistor **468** is configured to capture the light **470** reflected by the card. The LED **472** has a peak wavelength matched to the peak absorption wavelength of the infrared ink used to print the media coding.

[**0678**] As an alternative, the optical encoders can sense the direction of media movement by configuring them to be 'quadrature encoders'. A quadrature encoder contains a pair of optical encoders spatially positioned to read the clock track **90** degrees out of phase. Its in-phase and quadrature outputs allow the MoPEC **326** to identify not just the motion of the clock track **434** but also the direction of the motion. A quadrature encoder is generally not required, since the media transport direction is known a priori because the printer controller also controls the transport motor. However, the use of a quadrature encoder can help decouple a bi-directional motion sensing mechanism from the motion control mechanism.

[**0679**] FIG. **103** shows a block diagram of the MoPEC **326**. It incorporates a digital phase lock loop (DPLL) **444** to track the clock inherent in the clock track **434** (see FIG. **100**), a line sync generator **448** to generate the line sync signal **476** from the clock **446**, and a data decoder **450** to decode the data in the data track **436**. De-framing, error detection and error correction may be performed by software running on MoPEC's general-purpose processor **452**, or it may be performed by dedicated hardware in MoPEC.

[**0680**] The data decoder **450** uses the clock **446** recovered by the DPLL **444** to sample the signal from the data track optical encoder **442**. It may either sample the continuous signal from the data track optical encoder **442**, or it may actually trigger the LED of the data track optical encoder **442** for the duration of the sample period, thereby reducing the total power consumption of the LED. The DPLL **444** may be a PLL, or it may simply measure and filter the period between successive clock pulses.

[**0681**] The line sync generator **456** consists of a numerically-controlled oscillator which generates line sync pulses **476** at a rate which is a multiple of the rate of the clock **446** recovered from the clock track **434**.

[**0682**] As shown in FIG. **101**, the print engine may optionally incorporate an explicit edge detector **474** to provide longitudinal registration of the card **226** with the operation of the printhead **202**. In this case, as shown in FIG. **104**, it generates a page sync signal **478** to signal the start of printing after counting a fixed number of line syncs **476** after edge detection. Longitudinal registration may also be achieved by other card-in detection mechanisms ranging from opto-sensors, de-capping mechanical switches, drive shaft/tension spring contact switch and motor load detection.

[**0683**] Optionally, the printer can rely on the media coding itself to obtain longitudinal registration. For example, it may rely on acquisition of a pilot sequence on the data track **436** to obtain registration. In this case, as shown in FIG. **105**, it generates a page sync signal **478** to signal the start of printing after counting a fixed number of line syncs **476** after pilot detection. The pilot detector **460** consists of a shift register and combinatorial logic to recognise the pilot sequence **480** provided by the data decoder **450**, and generate the pilot sync signal **482**. Relying on the media coding itself can provide

superior information for registering printed content with the Netpage tag pattern **438** (FIG. **100**).

[**0684**] As shown in FIG. **106**, the data track optical encoder **442** is positioned adjacent to the first clock data encoder **440**, so that the data track **436** (see FIG. **100**) can be decoded as early as possible and using the recovered clock signal **446**. The clock must be acquired before printing can commence, so a first optical encoder **440** is positioned before the printhead **202** in the media feed path. However, as the clock needs to be tracked throughout the print, a second clock optical encoder **464** is positioned coincident with or downstream of the printhead **202**. This is described in more detail below.

[**0685**] FIG. **99** shows the printed card **226** being withdrawn from the print cartridge, **148**. It will be appreciated that the printed card **226** needs to be manually withdrawn by the user. Once the trailing edge of the card **226** has passed between the drive shaft **178** and the spring fingers **238**, it is no longer driven along the media feed path. However, as the printhead **202** is less than 2 mm from the drive shaft **178**, the momentum of the card **226** projects the trailing edge of past the printhead **202**.

[**0686**] While the momentum of the card is sufficient to carry the trailing edge past the printhead, it is not enough to fling it out of the exit slot **150** (FIG. **98**). Instead, the card **226** is lightly gripped by the opposed lock actuator arms **232** as it protrudes from the exit slot **150** in the side of the mobile phone **100**. This retains the card **226** so it does not simply fall from exit slot **150**, but rather allows users to manually remove the printed card **226** from the mobile phone **100** at their convenience. This is important to the practicality of the mobile telecommunications device because the card **226** is fed into one side of the mobile telecommunications device and retrieved from the other, so users will typically want to swap the hand that holds the mobile telecommunications device when collecting the printed card. By lightly retaining the printed card, users do not need to swap hands and be ready to collect the card before completion of the print job (approximately 1-2 secs). Alternatively, the velocity of the card as it leaves the roller can be made high enough that the card exits the outlet slot **123** under its own inertia.

10.1 M-Print Flip Printing

[**0687**] One can allow a previously printed m-print Netpage card to be re-inserted into the printing mechanism "flipped-over", so that the side not previously printed on (i.e. the back of the card) is now facing towards the print head. The printer would detect such an insertion and would automatically print additional information on to the back of the card. The additional information would typically, but not necessarily, be application and context specific. That is:

[**0688**] the application which created the original print-out would determine what is printed onto the back side of the card, and

[**0689**] would be able to take into account context specific information such as the impression ID of the card.

[**0690**] This allows applications to print information onto the back side of the card which is specific to the original printout on the front side of the card. There are many potential uses for such a mechanism. For the sake of discussion, one such case is described below.

10.11 Camera Use-Case

[**0691**] 1. User takes a photo using an m-print enabled camera phone

- [0692] 2. User prints photo onto Netpage tagged card
- [0693] 3. User feeds card back through printer flipped-over
- [0694] 4. Various details about the photo would then be printed onto the back of the card. Examples of details might be:
- [0695] The date and time the photo was taken;
- [0696] Location where photo was taken, either automatically determined by a geographical positioning system within the phone (eg. GPS or cell-based location detection), or manually entered after the fact by the user; and/or
- [0697] Arbitrary textual information entered by the user (perhaps entered on the phone itself or via a web-based photo archiving application sometime after the photo was taken).
- [0698] The time duration between the user taking the original photo and inserting the flipped-over card could be arbitrarily long. As such, the mechanism can act as a “what is this photo that I just found?” facility. Another advantage is that it removes the need to have text obscuring parts of the photo in order to provide date/time information.

11. General Netpage Overview

[0699] Netpage interactivity can be used to provide printed user interfaces to various phone functions and applications, such as enabling particular operational modes of the mobile telecommunications device or interacting with a calculator application, as well as providing general “keypad”, “keyboard” and “tablet” input to the mobile telecommunications device. Such interfaces can be pre-printed and bundled with a phone, purchased separately (as a way of customizing phone operation, similar to ringtones and themes) or printed on demand where the phone incorporates a printer.

[0700] A printed Netpage business card provides a good example of how a variety of functions can be usefully combined in a single interface, including:

- [0701] loading contact details into an address book
- [0702] displaying a Web page
- [0703] displaying an image
- [0704] dialing a contact number
- [0705] bringing up an e-mail, SMS or MMS form
- [0706] loading location info into a navigation system
- [0707] activating a promotion or special offer

[0708] Any of these functions can be made single-use only. A business card may be printed by the mobile telecommunications device user for presentation to someone else, or may be printed from a Web page relating to a business for the mobile telecommunications device user’s own use. It may also be pre-printed.

[0709] As described below, the primary benefit of incorporating a Netpage pointer or pen in another device is synergy. A Netpage pointer or pen incorporated in a mobile phone, smartphone or telecommunications-enabled PDA, for example, allows the device to act as both a Netpage pointer and as a relay between the pointer and the mobile phone network and hence a Netpage server. When the pointer is used to interact with a page, the target application of the interaction can display information on the phone display and initiate further interaction with the user via the phone touchscreen. The pointer is most usefully configured so that its “nib” is in a corner of the phone body, allowing the user to easily manipulate the phone to designate a tagged surface. The

phone can incorporate a marking nib and optionally a continuous force sensor to provide full Netpage pen functionality.

[0710] An exemplary Netpage interaction will now be described to show how a sensing device in the form of a Netpage enabled mobile device interacts with the coded data on a print medium in the form of a card. Whilst in the preferred form the print medium is a card generated by the mobile device or another mobile device, it can also be a commercially pre-printed card that is purchased or otherwise provided as part of a commercial transaction. The print medium can also be a page of a book, magazine, newspaper or brochure, for example. The print medium can be provided with coded data in a variety of formats, the coded data encoding a range of information, preferably, at least some of the information being indicative of the print media identifier. The information can be indicative of a two-dimensional coordinate grid, and the format can be a two-dimensional pattern.

[0711] For example, the print medium can be provided with first coded data in a first format and second coded data in a second format, the first coded data encoding first information and the second coded data encoding second information, with at least some of the first information being indicative of the print media identifier, the first format being a linear pattern, and with at least some of the second information being indicative of the print media identifier and of a two-dimensional coordinate grid, the second format being a two-dimensional pattern. In a particular example form, the information is further indicative of at least part of a digital signature associated with the print media identifier, the sensor module determining, by reading at least some of the coded data, at least part of the digital signature, and the printer module can then print, if the digital signature is authentic, content on the print media.

[0712] The mobile device senses a tag using an area image sensor and detects tag data. The mobile device uses the sensed data tag to generate interaction data, which is sent via a mobile telecommunications network to a document server. The document server uses the ID to access the document description, and interpret the interaction. In appropriate circumstances, the document server sends a corresponding message to an application server, which can then perform a corresponding action.

[0713] Typically Netpage pen and Netpage-enabled mobile device users register with a registration server, which associates the user with an identifier stored in the respective Netpage pen or Netpage enabled mobile device. By providing the sensing device identifier as part of the interaction data, this allows users to be identified, allowing transactions or the like to be performed. Netpage documents are generated by having an ID server generate an ID which is transferred to the document server. The document server determines a document description and then records an association between the document description and the ID, to allow subsequent retrieval of the document description using the ID. The ID is then used to generate the tag data, as will be described in more detail below, before the document is printed by a suitable printer, using the page description and the tag map.

[0714] Each tag is represented by a pattern which contains two kinds of elements. The first kind of element is a target. Targets allow a tag to be located in an image of a coded surface, and allow the perspective distortion of the tag to be inferred. The second kind of element is a macrodot. Each macrodot encodes the value of a bit by its presence or absence. The pattern is represented on the coded surface in

such a way as to allow it to be acquired by an optical imaging system, and in particular by an optical system with a narrow-band response in the near-infrared. The pattern is typically printed onto the surface using a narrowband near-infrared ink.

[0715] In the preferred embodiment, the region typically corresponds to the entire surface of an M-Print card, and the region ID corresponds to the unique M-Print card ID. For clarity in the following discussion we refer to items and IDs, with the understanding that the ID corresponds to the region ID. The surface coding is designed so that an acquisition field of view large enough to guarantee acquisition of an entire tag is large enough to guarantee acquisition of the ID of the region containing the tag. Acquisition of the tag itself guarantees acquisition of the tag's two-dimensional position within the region, as well as other tag-specific data. The surface coding therefore allows a sensing device to acquire a region ID and a tag position during a purely local interaction with a coded surface, e.g. during a "click" or tap on a coded surface with a pen.

[0716] Optional embodiments of the present invention may also be said to broadly consist in the parts, elements and features referred to or indicated herein, individually or collectively, in any or all combinations of two or more of the parts, elements or features, and wherein specific integers are mentioned herein which have known equivalents in the art to which the invention relates, such known equivalents are deemed to be incorporated herein as if individually set forth. Although a preferred embodiment has been described in detail, it should be understood that various changes, substitutions, and alterations can be made by one of ordinary skill in the art without departing from the scope of the present invention.

12. Further Example Applications—Entertainment Services

12.1 Games and Puzzles

[0717] Mobile phone printing of games and puzzles that are traditionally printed on paper provides consumers with several significant advantages. Despite the success of hand-held video games, mobile phone games and DVD consoles in cars, traditional paper-based games have not lost their appeal. These games include connect-the-dots, tic-tac-toe (also known as 'noughts and crosses'), crossword puzzles and a vast array of word and knowledge-based games. Most print newspapers, magazines and comic books usually include a section with paper-based games. Specialist publications are also sold at newsagents and other vendors.

[0718] The overall mass market appeal of paper based game publications has been steadily declining as:

[0719] Games are readily available on the internet and most websites offer them for free.

[0720] Most mass market publications are printed using low quality paper.

[0721] Many consumers do not feel the need to purchase an entire volume of games when their interest in a game is spontaneous or intermittent.

[0722] The internet has benefited consumers as:

[0723] Many websites offer free games and puzzles to print and play.

[0724] Consumers can select from a wider range of games and puzzles as many people are designing their own unique games.

[0725] Consumers are able to select as many or as few games to print, without restrictions on print volumes.

[0726] The web provides consumers with an easy and convenient way to source paper-based games.

[0727] Games that combine traditional puzzles with a degree of interactivity or progression are also possible.

12.2 Mobile Games and Puzzles

[0728] Dell Crosswords, the most popular name in the US for crossword puzzles and word search games, now sells puzzles and games to mobile phone users, as well as online. The consumer purchases the crossword or word search game software from the Dell Crosswords website. This is then downloaded to a computer and installed on a mobile phone via USB, wireless or infrared connection, or installed directly over the air. Once installed, users can download a new puzzle or game each day, to play using a keypad, stylus or pen. To request a puzzle or game:

[0729] 1. Click 'Dell Crosswords' icon from the phone menu.

[0730] 2. Select the 'request game' option.

[0731] 3. Click 'send'.

[0732] 4. A game is sent to the user's phone using SMS, MMS or email.

12.2.1 Print Opportunities

[0733] Daily, printable games, puzzles and quizzes can be incorporated into news and other paid subscriptions. Paid subscribers can receive games or puzzles periodically to print as required. It is possible to work with some paper size limitations, such as by printing a crossword grid on one page with the clues on a second.

12.2.2 Interactivity Opportunities

[0734] Gamers can enter into draws and competitions, interacting with service providers in real-time.

[0735] Referring to FIG. 107, the printed Find the Art Words! 900 example demonstrates the following possibilities:

[0736] Click each of the letters of the found words.

[0737] Select the completed checkbox and then click the SUBMIT button when the word puzzle is completed.

[0738] Referring to FIG. 108, the printed Quick Crossword 910 example provides the user with the opportunity to use the pen or pointer device to:

[0739] Fill in each of the words in the crossword.

[0740] Click the clue to receive another hint or the answer.

[0741] Click the 'results' link to retrieve the full crossword solution.

[0742] The printed gaming information may be a permission token readable using the sensor module to at least one of: retrieve information associated with the gaming information from the archive; retrieve a game state; identify a game state and set a state of a game from the game state; retrieve a map; identify a position on a map; identify a position on a map and set a state of a game from the map position; retrieve a game score; initiate payment for the gaming information; transmit the gaming information to a game server; obtain a copy of the gaming information; and gain access to a resource. Printing the gaming information may cause information associated with the gaming information to be archived. Information associated with the gaming information may include one or more of: the gaming information; a visual description of the gaming information; an image of the gaming information; an

interactive description of the gaming information; contents of the gaming information; and gaming information details. The gaming information may include at least one of: a game state; a game score; a high score list; a game level; a map; a brag card; a game highlight; a game screenshot; a password; an access key; a cheat code; and game instructions. The gaming information may be associated with a game played on the mobile telecommunications device.

[0743] Furthermore, the printed puzzle may be a permission token readable using the sensor module to at least one of: retrieve information associated with the puzzle from the archive; retrieve a puzzle state; retrieve a new puzzle; have a puzzle answer checked; retrieve a score; initiate payment for the puzzle; transmit the puzzle to a server; obtain a copy of the puzzle; and gain access to a resource. Printing the puzzle may cause information associated with the puzzle to be archived.

[0744] Information associated with the puzzle may include one or more of: the puzzle; a visual description of the puzzle; an image of the puzzle; an interactive description of the puzzle; contents of the puzzle; and puzzle details. The puzzle may include at least one of: a crossword; a numerical puzzle; a word puzzle; a sudoku; a quiz; a puzzle state; a puzzle score; a list of puzzles; a password; and puzzle instructions. The puzzle may be printed periodically.

12.3 Music

[0745] Global sales of recorded music in 2003, in both video and audio formats, were valued at US\$32 billion. In July 2004, Jupiter Research reported that US digital music sales for 2004 will more than double 2003 sales to an excess of more US\$270 million. It will grow rapidly to US\$1.7 billion in 2009, totalling 12% of US consumer spending on music. The consultancy BearingPoint has reported that, in Europe and other regions, ringtones are a billion dollar business and that ringtones, digital radio and games may provide the new revenue streams that the US music industry is seeking. Until 2004, growth in the digital music market was held back by concerns about digital rights management—the protection of intellectual property. A variety of different proprietary standards currently exist. Rapid market growth has taken place in 2004 despite these concerns. In a September 2004 report titled Music Enabled Handsets—Next 3G Device Focus, Strategy Analytics reports that digital music is the next 3G opportunity beyond still and video imaging, while total music-enabled device sales will scale to 54 percent of global handset sales in 2009. Nokia is developing relationships with Loudeye OD2 and Universal Music, and marketing specialist 3300 and 5510 handsets. Motorola is aggressively pursuing music-focused alliances with MTV and Apple. Both cases illustrate the importance that music content will play in the emerging music-enabled device market. Strategy Analytics also reports that: MP3, a file format without digital rights protection, will remain the dominant audio format in the mobile market because of its strengths in the wired broadband domain; and Mobile converged devices will account for 50% of music enabled device sales through 2006.

[0746] Wireless operators and major record companies including Sony Music, T-Mobile, Universal Music and Vodafone are all working on plans to make sure that the mobile phone will soon be as important a channel as the internet in the short term, and as traditional record stores in the long term.

[0747] Mobile music can be divided into three different content streams: Downloaded music; Streaming music; Interactive music content.

12.3.1 Downloaded Music

[0748] In Western Europe the legal music download market has taken off in 2004. The market is expected to be worth US\$4.41 billion (EUR3.5 billion) a year by 2009. 2004 has marked the launch of new music download sites in Europe such as Apple's iTunes Music Store, Sony's Connect, and Napster. Currently, half of the online music consumers are between 16 and 24 years. However, Forrester Research reports that as online music services expand their offerings and become easier to use that they will also gain momentum with older consumers. Forrester Research forecasts that Britain, France and Germany will dominate the market, with over 60% of legal music downloads in Europe sold in these three countries in 2009. Spain and Italy will grow strongly to account for around 20% of the European market by 2009.

[0749] Apple reports that it sold five million tracks in Europe in the first 10 weeks after the launch of British French and German iTunes stores. The market leader, it has since expanded its coverage of Europe to 12 countries. Worldwide, it has sold over 150 million protected AAC-format tracks, mainly through its US website which opened in April 2003. Loudeye's OD2 division, 'On Demand Distribution', is Europe's leading music download distributor to retail partners. OD2 tracks are sold in Microsoft's WMA format with digital rights protection. OD2 has launched interactive music services with retail partners including MSN (in 6 European countries); Ninemsn (Australia); Tonlist (Iceland); NEC's Packard Bell 'Music Station' (France, Germany and the UK); the charity Oxfam in the UK; and Eircom in Ireland. The company is now working with Nokia to deliver services to Nokia handsets.

12.3.2 Streaming Music

[0750] Online radio stations, record companies and musicians websites all offer legal streaming music services to enhance the user experience and to promote their products. UK digital media company, 7 Digital Media has designed and built a proprietary download engine to enable digital media distribution on behalf of record labels, broadcast, retail and brand partners. Their client base includes Universal, EMI, Warner Music, Sony BMG, V2, Echo, Independiente, O2 and many others and they have distributed content via over 175 partner sites including AOL, MSN, Lycos, Freeserve, Yahoo!, NME and XFM. BMG Records and Atlantic Records use 7 Digital Media to manage single promotions and billing via SMS and credit/debit card for both the chart toppers. They provide:

[0751] Secure, global distribution of digital media.

[0752] Acceptance of payments via SMS, Credit Card, Debit Card and BT (UK PSTN) phone bill.

[0753] Compatibility with most digital media formats.

[0754] Consumers of streaming audio usually use a generic media player such as RealPlayer, QuickTime or Windows Media Player to listen to their favourite online radio stations or to hear songs and tunes from other websites. Real Networks provides the RealPlayer for mobile devices using the Symbian, PALM and Pocket PC operating systems, including select Nokia handsets. Its key features include:

[0755] Playback of RealAudio, RealVideo and 3GPP compliant content via streaming or download.

[0756] Seamless integration with RealPlayer for PC to drag and drop MP3 and RealAudio files to devices.

[0757] Access to news, sports and entertainment updates.

[0758] Access to downloadable content including music videos, travel guidance, auto review and much more.

[0759] Microsoft is planning to make its media software available to chip and handset makers to enable more consumers to play music in the Windows Media format on their mobile phones. Motorola and NEC have Microsoft's media decoders integrated into their handsets for 3G mobile networks. In contrast, server-side Apple QuickTime technology is in use by operators such as Verizon Wireless, Sprint, NTT DoCoMo and KDDI. QuickTime manages media for photograph e-mailing and other data services.

12.3.3 Mobile Music Content Services

[0760] Nokia has developed a mobile file sharing network, adapting peer-to-peer (P2P) file sharing schemes used by internet users, that has been tested on their 6600 model handsets. The network can currently support image and text sharing. Developing the ability to share digital music is considered a priority. Pop stars such as Anastacia, John Mayer and Madonna are all promoting mobile phones by providing special promotional offers that include, ringtones, MP3 and voicemail downloads, and SMS competitions. In the United States, Preferred Voice (PVI), a personalisation services provider, is offering 'Rockin' Ringback', where users choose an audio file for callers to their phone to listen to while the phone is ringing. Selections can be personalised for different callers, days and times. PVI hope that this will provide wireless carriers with a new way to increase average revenue per user and decrease chum. The service has been successfully deployed for 19 US carriers. The market opportunity for ringbacks is regarded as substantial. Korea's main mobile operator, SK Telecom has achieved more than 30% penetration in just 2 years.

12.3.4 Print Opportunities

[0761] Consumers will be able to print Karaoke lyrics, playlists, cover art, related trading cards, gossip and news messages, and also competition information and entries.

12.3.5 Interactivity Opportunities

[0762] The ability to interact with playlists, cover art, related trading cards, gossip, news and competition entries will encourage consumer use of value added services.

[0763] Referring to FIG. 109, the printed Silver Angels Lyrics 920 example demonstrates the following:

[0764] Click on the 'Silver Angels' logo to visit the artists' website.

[0765] Click on the 'MP3' link to download the song.

[0766] Click on the 'email' link to send a fan email to the group.

[0767] Ringtone and ringback options are also possible.

[0768] Referring to FIG. 110, the printed DigiRadio Top 10 card 930 example shows how a user can listen to, and order, music using a printed menu of interactive links:

[0769] Click on the 'DigiRadio' logo to visit the web site.

[0770] Click on the 'Week 41' link to view the full chart.

[0771] Click on each of the 'listen' icons to listen to the music online.

[0772] Select the 'order' checkboxes of the singles that they want to purchase (this assumes that

[0773] the format of the music has been pre-selected by the user).

[0774] If the user has selected to purchase singles from the Top 10 list they can then select the completed checkbox and click on the SUBMIT button to send the order.

[0775] The printed audio information may be a permission token readable using the sensor module to at least one of: retrieve information associated with the audio information from the archive; receive audio via the mobile telecommunications device; receive an audio file; receive streaming audio; initiate payment for the audio information; initiate payment for audio associated with the audio information; select an audio channel; select an audio source; select a radio station; obtain a copy of the audio information; and gain access to a resource. Printing the audio information may cause information associated with the audio information to be archived. Information associated with the audio information includes one or more of: the audio information; a visual description of the audio information; a music chart; an image of the audio information; an interactive description of the audio information; contents of the audio information; an audio clip; an audio stream; an audio track; recorded music; synthesized music; recorded voice; synthesized voice; a sound effect; an audio channel; an audio source; a radio station; and audio information details. The audio information may include at least one of: lyrics; words of a song; musical notes; a musical score; a song title; an album title; information about a song; a name of a musician; and information about a musician. The audio information may be associated with audio played on the mobile telecommunications device. 12.4 TV and Video

[0776] Mobile TV and video consists of three different content streams:

[0777] Camera phone based video recording and publishing.

[0778] Streaming TV broadcast services.

[0779] TV-like interactive content.

12.4.1 Mobile Video

[0780] The worldwide value of consumer video subscription services delivered via the internet is forecast to exceed US\$4.6 billion in 2008. The market is expanding to include more types of content, as well as extending to mobile phones. An LG A survey of 228 telecommunications experts at the ITU Telecom Asia 2004 event in Korea, indicated that the convergence of mobile handsets with other digital devices could have a major impact on the markets for both digital still cameras and video cameras. Convergence will eventually combine phone, camera, video camera, music and other features. 95% of respondents said that it was either very likely or somewhat likely (73% and 22% respectively) that consumers will eventually choose a single converged 3G device over multiple devices. Of these, 72% expect to see the transition within the next two years and 24% within 3-5 years. Of the functions available in new 3G handsets, respondents stated that video telephony (41%), TV/Video on demand (23%) and video or photo mailing (20%) were the most important. EarthCam Mobile, a wireless Java application with an online companion site enables people to view webcams from around the world, including traffic and weather cams, on a mobile phone.

[0781] SK Telecom in Korea already offers on-demand video programming, and plans to offer 39 digital video channels delivered via satellite. NTT DoCoMo is in trials for streaming television broadcasts on its 3G FOMA networks. In the US, Sprint PCS launched a streaming video service earlier this month offering television content from stations such as CNN, NBC Universal, FOX Sports and The Weather Channel. A new MMS content service, FanTESStic, the UK's first MMS interactive soap opera broadcast, was launched in September 2004 by Endemol UK, the largest independent TV producer in Britain, together with Opera Telecom, a mobile services provider. FanTESStic consists of 80 comic strip-style episodes delivered over a 16-week period. Mobile users are charged US 90c per episode or US\$2.72 for five episodes, with charges appearing on the user's monthly mobile phone bill. Openwave Systems is developing and providing customisable, personalised video messaging for 3G phones, such as personal, celebrity or game video greetings for different people. Users are expected to share popular video clips as MMS messages. Popular applications of streaming video content are expected to be clips of sports highlights and music videos available on demand. Journalists and bloggers (web log users) are expected to use mobile phone video technology to cover news stories live from the scene.

12.4.2 Mobile TV Broadcast Services

[0782] Mobile TV provides a new channel for existing media players while, for mobile operators, it provides a value-enhanced service and increased revenue per user. The British Broadcasting Corporation believes that IP-based broadcasting, delivered via numerous access devices, will become increasingly important, and that convergence will increasingly separate content from delivery. Leading mobile phone manufacturers Motorola, NEC, Nokia, Siemens and Sony Ericsson are co-operating to develop mobile broadcast services. In 2003, NEC developed the world's first working prototype of a mobile phone capable of receiving terrestrial digital TV broadcasting. Mobile phone TV services are being introduced on the Japanese market while the European market for commercial mobile broadcast services is envisaged to start opening up towards the end of 2005. In the United States, MobiTV is a live TV streaming service for mobile phones developed by Idetic. MobiTV's service is currently available on some Sprint PCS Vision handset models.

12.4.3 Mobile Interactive TV

[0783] Interactive TV allows viewers to interact directly with TV broadcasts, to play games, or send messages. Currently, there are over 32 million digital television receivers in use in Europe, of which at least 25 million have interactive capability. The leading mobile interactive TV software and applications server company is Macromedia, which has licensed Macromedia Flash to most interactive television platform providers. Digeo, OpenTV and Motorola are embedding Macromedia Flash Player into their set top boxes. Macromedia also produce Flash Lite, a product for mass-market mobile phones, taking account of processing power, memory and network connectivity issues. Existing online Flash content can be repurposed for access by enabled mobile phones. Macromedia technology is embedded into all new NTT DoCoMo i-mode handsets. The first handsets became available in Japan in May 2003.

12.4.4 Print Opportunities

[0784] Printing of digital TV frames such as important sports events. Printing of TV schedules. Printing of interac-

tive TV messages including ads, special offers, competition details and entries. Printing of MMS pay-per-view messages, news and gossip.

12.4.5 Interactivity Opportunities

[0785] Interactivity can help to promote the use of value-added services by promoting the use of interactive printed cards as collectables, subscription services and shortcuts to playbacks and MMS messaging.

[0786] Referring to FIG. 111, the printed Dtv Movie Channel Highlights 940 demonstrates the following possibilities:

[0787] Click on the 'Dtv' logo to visit the service provider's website.

[0788] Click on each of the 'information' icons to visit each programs information web page.

[0789] Click on the 'envelope' icon to send an email.

[0790] Referring to FIG. 112, the printed Dtv Weekly Soccer Review 950 example shows the following:

[0791] Click on the 'Dtv' logo to visit the service provider's website.

[0792] Click on the 'play' icon to play the video.

[0793] Click on the 'email' icon to send the video link to another person.

[0794] Click on the 'archives' icon to visit the video archives web page.

[0795] Referring to FIG. 113, the printed Who Wants To Be A Millionaire TV show 960 example provides the user with the opportunity to participate in a Home Viewer Question competition by printing the entry form and then using the pen or pointer device to complete and submit their entry.

[0796] The printed video information may be a permission token readable using the sensor module to at least one of: retrieve information associated with the video information from the archive; receive video via the mobile telecommunications device; receive a video file; receive streaming video; initiate payment for the video information; initiate payment for video associated with the video information; select a video channel; select a video source; select a television channel; obtain a copy of the video information; and gain access to a resource. Printing the video information may cause information associated with the video information to be archived. Information associated with the video information may include one or more of: the video information; a visual description of the video information; a video clip; an image of the video information; an interactive description of the video information; contents of the video information; a video stream; a video track; a video channel; recorded video; synthesized video; an animation; a video effect; a video source; a television channel; a television station; and video information details. The video information may include at least one of: television program information; movie information; lyrics; words of a song; musical notes; a musical score; a song title; a movie title; a program title; information about a video; a name of a musician; a name of a producer; a name of a director; a name of an actor; and information about a person. The video information may be associated with video played on the mobile telecommunications device.

1. A mobile telecommunications device comprising:
 - a mobile phone module;
 - a printer module operatively connected to the mobile phone module and including a print engine controller; and

a tag sensor module operatively connected to the mobile phone module and including an image sensor and processor.

2. A mobile telecommunications device as claimed in claim 1, in which the printer module includes a program memory connected to the print engine controller for storing program code for execution by the print engine controller and a working memory for storing data used and generated by the program code.

3. A mobile telecommunications device as claimed in claim 1, in which the printer module includes a quality assurance integrated circuit for authenticating a printhead cartridge to be used by the telecommunications device.

4. A mobile telecommunications device as claimed in claim 1, in which the print engine controller is configured to

connect operatively with a printhead of the printhead cartridge to control operation of the printhead.

5. A mobile telecommunications device as claimed in claim 1, in which the printer module includes media sensors that are operatively connected to the print engine controller to sense the presence of media in the device.

6. A mobile telecommunications device as claimed in claim 1, in which the tag sensor module includes a contact sensor connected to the image processor and an illumination LED such that the image sensor and illumination LED can be activated by the contact sensor.

7. A mobile telecommunications device as claimed in claim 1, in which the tag sensor module includes an image memory in which an image captured by the image sensor is stored.

* * * * *