



US 20060079856A1

(19) **United States**(12) **Patent Application Publication**  
**Smith et al.**(10) **Pub. No.: US 2006/0079856 A1**(43) **Pub. Date: Apr. 13, 2006**(54) **CLOSURE ASSEMBLY**

(60) Provisional application No. 60/284,277, filed on Apr. 17, 2001.

(75) Inventors: **Sidney T. Smith**, Lake Forest, IL (US);  
**Larry Rosenbaum**, Gurnee, IL (US);  
**Sue Rosenbaum**, legal representative,  
Tucson, AZ (US); **William S. Hurst**,  
Burlington, WI (US); **Melissa J.**  
**Skelnik**, Wonder Lake, IL (US);  
**Bradley Buchanan**, Glenview, IL (US)**Publication Classification**(51) **Int. Cl.**  
**A61B 19/00** (2006.01)  
**A61M 5/32** (2006.01)  
(52) **U.S. Cl.** ..... **604/415**

Correspondence Address:

**BAXTER HEALTHCARE CORPORATION**  
**ONE BAXTER PARKWAY**  
**DF2-2E**  
**DEERFIELD, IL 60015 (US)**(57) **ABSTRACT**(73) Assignees: **Baxter International Inc.**, Deerfield, IL  
(US); **Baxter Healthcare S.A.**, Zurich  
(CH)(21) Appl. No.: **11/282,284**(22) Filed: **Nov. 18, 2005****Related U.S. Application Data**

(62) Division of application No. 10/124,599, filed on Apr. 16, 2002, now Pat. No. 6,974,447.

The present invention provides a receptacle (30) for a therapeutic fluid susceptible to deterioration on exposure to a gas such as oxygen or carbon dioxide. The receptacle (30) has walls of sheet material each including at least one layer forming a barrier essentially impermeable to such gas, and a seal sealing the walls together in a region thereof. A transfer tube (40) is sealed in the seal having a proximal end in the receptacle (30), a distal end accessible from outside the receptacle (30), a flow passage (56) extending between said proximal and distal ends, and a closure (54) blocking flow through the flow passage (56) adapted to be pierced by a tubular needle for transfer of therapeutic through the needle. The transfer tube (40) and closure (54) are essentially impermeable to said gas.




FIG. 1a




FIG. 1b




FIG. 1c




FIG. 2a




FIG. 2b




FIG. 3a




FIG. 3b




FIG. 3c




FIG. 9




FIG. 5




FIG. 7




FIG. 4




FIG. 6





FIG. 8



## CLOSURE ASSEMBLY

### CROSS-REFERENCE TO RELATED APPLICATIONS

[0001] This application claims the benefit of provisional application Ser. No. 60/284,277, filed Apr. 17, 2001, which is incorporated by reference and made a part hereof.

### TECHNICAL FIELD

[0002] The present invention relates to a high gas barrier primary receptacle system, and more particularly to a receptacle system for medical solutions.

### BACKGROUND OF THE INVENTION

[0003] There is an ever increasing number of therapeutic fluids being developed for delivery by a flexible receptacle. Many of these therapeutic fluids are sensitive as they degrade or react with gases such as oxygen and carbon dioxide. These therapeutic fluids must be protected from contact by such gases to maintain the efficacy of the therapeutic fluid.

[0004] For example, hemoglobin solutions are known to lose their ability to function as blood substitutes during storage. A hemoglobin solution loses its ability to function as a blood substitute because of spontaneous transformation of oxyhemoglobin in the solution to methemoglobin, a physiologically inactive form of hemoglobin which does not function as a blood substitute by releasing oxygen into a patient's bloodstream. To improve shelf life, the blood substitutes industry delays loss of function by refrigerating or freezing the solutions, or controlling the oxygenation state of the hemoglobin within the solution.

[0005] Therapeutic hemoglobin solutions are typically oxygenated, stored frozen in conventional oxygen-permeable, 200 ml plastic solution bags, and thawed to room temperature hours before use.

[0006] WO 99/15289 describes a multiple layer structure for fabricating medical products. The layer structure has a core layer of an ethylene vinyl alcohol copolymer, a solution contact layer of a polyolefin positioned on a first side of the core layer, an outer layer positioned on a second side of the core layer opposite the solution contact layer, the outer layer being selected from the group consisting of polyamides, polyesters and polyolefins, and a tie layer on each side of the core layer. The tie layer is 0.2-1.2 mils in thickness, and is the only layer of the structure which may be composed of ethylene vinyl acetate.

[0007] U.S. Pat. No. 6,271,351 describes a method of storing deoxyhemoglobin in a container which is said to exhibit low oxygen permeability. The container is composed of a layered structure including ethylene vinyl alcohol, but does not include ethylene vinyl acetate.

[0008] There is a need for containers having minimal oxygen permeability which would enable deoxygenated hemoglobin solutions to be stored for weeks or months at room temperature and then used as a blood substitute.

[0009] Receptacles used for the shipping, storing, and delivery of liquids, such as medical or therapeutic fluids, are often fabricated from single-ply or multiple-ply polymeric materials. Two sheets of these materials are placed in

overlapping relationship and the overlapping sheets are bonded at their outer peripheries to define a chamber or pouch for containing liquids. It is also possible to extrude these materials as a tube and to seal longitudinally spaced portions of the tube to define chambers between two adjacent seals. Typically, the materials are joined along their inner surfaces using bonding techniques such as heat sealing, radio-frequency sealing, thermal transfer welding, adhesive sealing, solvent bonding, sonic sealing, and laser welding.

[0010] It is also common to provide such receptacles with access ports to provide access to the interior of the receptacle. Access ports typically take the form of one or more end ports (transfer tubes) inserted between the sidewalls of the receptacle or panel ports attached to a sidewall of the receptacle. The end ports typically have a fluid passageway with a closure wall positioned inside the passageway to form a fluid tight seal of the receptacle. The closure, typically in the form of a membrane, must be punctured by an access needle or "spike" to allow for delivery of the contents of the receptacle.

[0011] Conventional flexible solution receptacles employing end port designs typically use flexible PVC or soft polyolefins such as LDPE to construct the port tubes. Such materials have sufficient elasticity to grip the outside of an access spike to retain the spike during fluid delivery. The inner diameter of the end ports are dimensioned to be smaller than the outer diameter of the access device. Due to the ductility of PVC or LDPE, the port tube can expand about the outside of the access spike to form an interference fit therewith. However, such receptacle and port closure systems are readily permeated by oxygen and other gases such as carbon dioxide. If such receptacles are to be utilized to house a gas sensitive liquid, such packages must utilize a gas barrier overwrap material.

[0012] To provide a stand-alone gas barrier primary receptacle, all components of the receptacle system should be fabricated using barrier material. For medical applications where such receptacles are typically disposed of by incineration, it is desirable to construct the receptacle system components from non-halogen containing polymers. Halogen containing compounds have the potential for creating inorganic acids upon incineration. Further, for medical applications, it is also desirable to construct the receptacle system components from polymers having a low quantity of low molecular weight additives, such as plasticizers, as such low molecular weight components can potentially leach out into the fluids contained or transported therein.

[0013] It is well known that certain materials provide a high resistance to the ingress of oxygen or other gases. For example, ethylene vinyl alcohol (EVOH) provides a high barrier to the ingress of oxygen. However, EVOH provides a significant design challenge for use in flexible receptacle systems as EVOH is also known to be a very rigid material. A port tube containing a significant quantity of EVOH will have insufficient elasticity to expand around an access device. Thus, such an EVOH containing port tube cannot be dimensioned to be smaller in diameter than an access device.

[0014] Due to the variation in the outer diameter dimensions of access devices commercially, it is also difficult to design a single port tube to have an appropriate diameter to form an interference fit with all access devices commercially

available. The spike holder or needle holder has sufficient elastomeric properties to form around an access device and form a grasping hold of the access device. The present invention is provided to solve these and other problems.

#### SUMMARY OF THE INVENTION

[0015] The present invention provides a receptacle for a therapeutic fluid susceptible to deterioration on exposure to a gas such as oxygen or carbon dioxide. The receptacle has walls of sheet material each including at least one layer forming a barrier essentially impermeable to said gas, and a seal sealing the walls together in a region thereof. A transfer tube is sealed in the seal having a proximal end in the receptacle, a distal end accessible from outside the receptacle, a flow passage extending between said proximal and distal ends, and a closure blocking flow through said flow passage adapted to be pierced by a tubular needle for transfer of therapeutic through the needle. The transfer tube and closure are essentially impermeable to said gas.

[0016] The present invention further provides a transfer tube for attachment to a receptacle adapted to hold a fluent therapeutic susceptible to deterioration on exposure to gas such as oxygen or carbon dioxide. The transfer tube has a tubular body having a proximal end, a distal end opposite the proximal end, a flow passage extending between said proximal and distal ends adapted to communicate with said receptacle, and a closure blocking flow through the flow passage and adapted to be pierced by a tubular needle for transfer of therapeutic through the needle. The tubular body and closure are essentially impermeable to said gas.

[0017] The present invention is also directed to a needle holder for application to the distal end of a transfer tube of a receptacle particularly adapted to hold a fluent therapeutic susceptible to deterioration on exposure to gas such as oxygen or carbon dioxide. The needle holder is adapted to hold in place the carrier of a transfer needle with the needle piercing the transfer tube. The holder has a body having a first annular wall defining a first cavity at a first end of the body, a second annular wall defining a second cavity at a second end of the body, and a flow passage extending between the two cavities, the first annular wall being sized for an interference fit with said transfer tube to releasably attach the needle holder to the transfer tube, and the second annular wall being sized for an interference fit with said needle carrier to releasably attach the needle carrier to the needle holder in a position in which needle is disposed in said flow passage.

[0018] Additional features, advantages, and other aspects and attributes of the present invention will be discussed with reference to the following drawings and accompanying specification.

#### BRIEF DESCRIPTION OF THE DRAWINGS

[0019] **FIG. 1a** is a plan view of a flowable materials receptacle and closure system;

[0020] **FIG. 1b** is a cross-sectional view taken along line b-b of **FIG. 1a**;

[0021] **FIG. 1c** is a plan view of a flowable materials receptacle having a fill port and an administration port;

[0022] **FIG. 2a** is a cross-sectional view of a three-layer tubing;

[0023] **FIG. 2b** is a cross-sectional view of a two-layer tubing;

[0024] **FIG. 3a** is a cross-sectional view of a two-layer membrane film;

[0025] **FIG. 3b** is a cross-sectional view of a three-layer membrane film;

[0026] **FIG. 3c** is a cross-sectional view of a five-layer membrane film;

[0027] **FIG. 4** is a cross-sectional view of a membrane film and tube assembly;

[0028] **FIG. 5** is a side view of a needle or "spike" holder;

[0029] **FIG. 6** is cross-sectional view of the spike holder of **FIG. 6**;

[0030] **FIG. 7** is an cross-sectional view taken along line A-A of **FIG. 6**;

[0031] **FIG. 8** is an assembly of the membrane film and tube assembly with the spike holder or needle holder of **FIG. 5** with a spike being introduced therein; and

[0032] **FIG. 9** is a cross-sectional view of a four-layer membrane film.

#### DETAILED DESCRIPTION OF THE INVENTION

[0033] While this invention is susceptible of embodiments in many different forms, there is shown in the drawings and will herein be described in detail preferred embodiments of the invention with the understanding that the present disclosure is to be considered as an exemplification of the principles of the invention and is not intended to limit the broad aspect of the invention to the embodiments illustrated.

[0034] **FIG. 1a** shows a flowable materials receptacle and closure system generally referred to as **10**. The system includes a flowable materials receptacle **30**, a port (transfer) tube and closure assembly **40**, and a needle or "spike" holder **50**. The relative size of the receptacle **30**, assembly **40**, and spike holder **50** are exaggerated for illustrative purposes. In a preferred form of the invention, the system **10** is useful for containing and delivering a fluent therapeutic susceptible to deterioration on exposure to a gas such as oxygen or carbon dioxide. The system is also particularly well suited for storage and delivery of a buffered solution.

[0035] What is meant by "flowable material" is a material that will flow by the force of gravity. Flowable materials therefore include both liquid items and powdered or granular items and the like. Flowable materials receptacles find particular use for storage and delivery of medical or therapeutic fluids and include, but are not limited to, I.V. receptacles, peritoneal dialysis drain and fill receptacles, blood receptacles, blood product receptacles, blood substitute receptacles, nutritional receptacles, food receptacles and the like.

[0036] **FIGS. 1a** and **8** illustrate the assembly **40** as including a port (transfer) tube **52** and a closure in the form of a wall or membrane **54**. The port tube **52** defines a fluid flow passage **56** and has an end surface **58**. The membrane **54** is shown attached to the port tube end surface **58**. It is contemplated by the present invention the membrane **54**



could also be positioned inside the port tube flow passage **56** without departing from the scope of the present invention.

[0037] While it is contemplated the port tube **52** can have any number of layers, in a preferred form of the invention the port tube **52** will include either a discrete layer of a barrier material or a blend layer including a barrier material. The barrier material will present a barrier to the passage of gasses or water vapor transmission, and, in a preferred form of the invention, will reduce the passage rate of oxygen therethrough. It is also desirable that all materials in the solution contact layer, and more preferably all materials used in the tubing, be free of halogens, plasticizers or other low-molecular weight or water soluble components that can leach out into the solutions transferred through the tubing. Suitable barrier materials include ethylene vinyl alcohol copolymers having an ethylene content of from about 25% to about 45% by mole percent, more preferably from about 28% to about 36% by mole percent and most preferably from about 30% to about 34% by mole percent.

[0038] In an even more preferred form of the invention, the port tube **52** will have multiple layers. FIG. 2a and FIG. 2b show respectively a three-layer port tube **52** and a two-layer port tube. The three-layer port tube **52** has an outside or an outermost layer **60**, a core layer **62** and an inside solution contact layer **64**. Similarly, the two-layer port tube **52** has an outside layer **60** and an inside, solution contact layer **64**.

[0039] In a preferred form of the invention, the multiple layer transfer tube or port tube **52** will have a discrete layer of a barrier material with the remaining layers being selected from polyolefins. The layers of the tube can be positioned in any order, however, in a preferred form of the invention, the barrier layer is not positioned as the outside layer **60**. Thus, the layers of a three layer tube can be positioned in one of six orders selected from the group: first/second/third, first/third/second, second/first/third, second/third/first, third/first/second, and third/second/first. Further, in tube embodiments having more than two layers, the tube **52** can be symmetrical or asymmetrical from a material aspect and from a thickness of layers aspect.

[0040] Suitable polyolefins include homopolymers, copolymers and terpolymers obtained using, at least in part, monomers selected from  $\alpha$ -olefins having from 2 to 12 carbons. One particularly suitable polyolefin is an ethylene and  $\alpha$ -olefin interpolmer (which sometimes shall be referred to as a copolymer). Suitable ethylene and  $\alpha$ -olefin interpolymers preferably have a density, as measured by ASTM D-792 of less than about 0.915 g/cc and are commonly referred to as very low density polyethylene (VLDPE), ultra low density ethylene (ULDPE) and the like. The  $\alpha$ -olefin should have from 3-17 carbons, more preferably from 4-12 and most preferably 4-8 carbons. In a preferred form of the invention, the ethylene and  $\alpha$ -olefin copolymers are obtained using single site catalysts. Suitable single site catalyst systems, among others, are those disclosed in U.S. Pat. Nos. 5,783,638 and 5,272,236. Suitable ethylene and  $\alpha$ -olefin copolymers include those sold by Dow Chemical Company under the AFFINITY trademark, Dupont-Dow under the ENGAGE trademark and Exxon under the EXACT and PLASTOMER trademarks.

[0041] The polyolefins also include modified polyolefins and modified olefins blended with unmodified olefins. Suit-

able modified polyolefins are typically polyethylene or polyethylene copolymers. The polyethylenes can be ULDPE, low density (LDPE), linear low density (LLDPE), medium density polyethylene (MDPE), and high density polyethylenes (HDPE). The modified polyethylenes may have a density from 0.850-0.95 g/cc. The polyethylene may be modified by grafting or otherwise chemically, electronically or physically associating a group of carboxylic acids, and carboxylic acid anhydrides. Suitable modifying groups include, for example, maleic acid, fumaric acid, itaconic acid, citraconic acid, allylsuccinic acid, cyclohex-4-ene-1,2-dicarboxylic acid, 4-methylcyclohex-4-ene-1,2-dicarboxylic acid, bicyclo[2.2.1]hept-5-ene-2,3-dicarboxylic acid, x-methylbicyclo[2.2.1]hept-5-ene-2,3-dicarboxylic acid, maleic anhydride, itaconic anhydride, citraconic anhydride, allylsuccinic anhydride, citraconic anhydride, allylsuccinic anhydride, cyclohex-4-ene-1,2-dicarboxylic anhydride, 4-methylcyclohex-4-ene-1,2-dicarboxylic anhydride, bicyclo[2.2.1]hept-5-ene-2,3-dicarboxylic anhydride, and x-methylbicyclo[2.2.1]hept-5-ene-2,2-dicarboxylic anhydride.

[0042] Examples of other modifying groups include  $C_1$ - $C_8$  alkyl esters or glycidyl ester derivatives of unsaturated carboxylic acids such as methyl acrylate, methyl methacrylate, ethyl acrylate, ethyl methacrylate, butyl acrylate, butyl methacrylate, glycidyl acrylate, glycidyl methacrylate, monoethyl maleate, diethyl maleate, monomethyl maleate, diethyl maleate, monomethyl fumarate, dimethyl fumarate, monomethyl itaconate, and diethylitaconate; amide derivatives of unsaturated carboxylic acids such as acrylamide, methacrylamide, maleimonoamide, maleic diamide, maleic N-monoethylamide, maleic N,N-diethylamide, maleic N-monobutylamide, maleic N,N dibutylamide, fumaric monoamide, fumaric diamide, fumaric N-monoethylamide, fumaric N,N-diethylamide, fumaric N-monobutylamide and fumaric N,N-dibutylamide; imide derivatives of unsaturated carboxylic acids such as maleimide, N-butymaleimide and N-phenylmaleimide; and metal salts of unsaturated carboxylic acids such as sodium acrylate, sodium methacrylate, potassium acrylate and potassium methacrylate. More preferably, the polyolefin is modified by a fused ring carboxylic anhydride and most preferably a maleic anhydride.

[0043] The polyolefins also include ethylene vinyl acetate copolymers, modified ethylene vinyl acetate copolymers and blends thereof. The modified EVA has an associated modifying group selected from the above listed modifying groups.

[0044] In one preferred form of the invention, the tube **52** has a solution contact layer **64** of a modified EVA copolymer sold by DuPont Packaging under the trademark BYNEL® CXA, a core layer **62** of an EVOH and an outside layer **60** of a modified EVA, again preferably CXA. Such a structure is symmetrical from a materials standpoint. According to a preferred form of the invention, such tubing will have layers of the following thickness ranges: outside layer **60** from about 0.002 inches to about 0.042 inches, preferably about 0.010 inches, the core layer **62** from about 0.016 inches to about 0.056 inches, preferably about 0.039 inches, and the solution contact layer **64** of from about 0.002 inches to about 0.042 inches, preferably about 0.010 inches.

[0045] In another preferred form of the invention, the tube **52** has a solution contact layer **64** of an EVOH, a core layer

**62** of a modified EVA and preferably BYNEL® CXA and an outside or outermost layer **60** of an ethylene and  $\alpha$ -olefin copolymer. Such a structure is symmetrical from a materials standpoint. The tube layers can have various relative thicknesses. According to a preferred form of the invention, tube **52** will have layers of the following thickness ranges: outside layer **60** from about 0.002 inches to about 0.042 inches; the core layer **62** from about 0.002 inches to about 0.042 inches; and the solution contact layer **64** from about 0.016 inches to about 0.056 inches. The outermost layer **60** of EVA is well suited for bonding to the transfer tube, especially upon heat sealing.

[0046] In a further preferred form, the tube **52** has a solution contact layer **64** of BYNEL® CXA, a core layer **62** of EVOH, and an outside layer **60** of a blend of 50% ULDPE and 50% CXA. Such tubing will have layers of the following thickness ranges: outside layer **60** from about 0.002 inches to about 0.042 inches, preferably about 0.010 inches; the core layer **62** from about 0.016 inches to about 0.056 inches, preferably about 0.039 inches; and the solution contact layer **64** of from about 0.002 inches to about 0.042 inches, preferably about 0.010 inches.

[0047] In a preferred form of the invention, the port tube **52** shall have the following dimensions: inside diameter from about 0.100 inches to about 0.500 inches and the wall thickness shall be from about 0.020 inches to about 0.064 inches. The port tube **52** can be prepared by injection molding, extrusion, coextrusion or other polymer processing techniques well known in the art.

[0048] Turning our attention now to the closure **54**, the membrane film forming the closure **54** can have any number of layers, but in a preferred form of the invention has multiple layers. The membrane film **54**, in a preferred form of the invention, shall have a barrier layer as defined above. **FIG. 3a** shows a two-layer structure **54** having an outside layer **72** and an inside layer **70**. **FIG. 3b** shows a three-layer structure **54** having an outside layer **72**, an inside layer **70** and a core layer **74**. **FIG. 3c** shows a five-layer structure **54** having an outside layer **72**, an inside layer **70**, a core layer **74**, and two tie layers **76**. In a preferred form of the invention, one layer shall be of a barrier material defined above and the remaining layer or layers shall be selected from the polyolefins defined above, polyamides and polyesters. One of the inside layer **70** or outside layer **72** shall define a tubing contact layer or seal layer.

[0049] Suitable polyamides include those obtained from a ring-opening reaction of lactams having from 4-12 carbons. This group of polyamides therefore includes, but is not limited to, nylon 6, nylon 10 and nylon 12.

[0050] Acceptable polyamides also include aliphatic polyamides resulting from the condensation reaction of di-amines having a carbon number within a range of 2-13, aliphatic polyamides resulting from a condensation reaction of di-acids having a carbon number within a range of 2-13, polyamides resulting from the condensation reaction of dimer fatty acids, and amide containing copolymers. Thus, suitable aliphatic polyamides include, for example, nylon 66, nylon 6,10 and dimer fatty acid polyamides.

[0051] Suitable polyesters include polycondensation products of di- or polycarboxylic acids and di or poly hydroxy alcohols or alkylene oxides. Preferably, the polyesters are a

condensation product of ethylene glycol and a saturated carboxylic acid such as ortho or isophthalic acids and adipic acid. More preferably the polyesters include polyethyleneterephthalates produced by condensation of ethylene glycol and terephthalic acid; polybutyleneterephthalates produced by a condensations of 1,4-butanediol and terephthalic acid; and polyethyleneterephthalate copolymers and polybutyleneterephthalate copolymers which have a third component of an acid component such as phthalic acid, isophthalic acid, sebacic acid, adipic acid, azelaic acid, glutaric acid, succinic acid, oxalic acid, etc.; and a diol component such as 1,4-cyclohexanedimethanol, diethyleneglycol, propyleneglycol, etc. and blended mixtures thereof.

[0052] In a preferred form of the invention, the membrane structure shall have five layers as shown in **FIG. 3c** and is described in detail in commonly assigned U.S. Pat. No. 6,083,587 which is incorporated herein by reference and made a part hereof. The outside layer **72** is a polyamide and preferably nylon 12, the two tie layers **76** are a modified EVA copolymer, the core layer **74** is an EVOH and the inner layer **70** is a modified EVA. In a preferred form of the invention the inside layer **70** defines the tubing contact layer.

[0053] Further, the structure shown in **FIG. 3c** has the following layer thickness ranges: outside layer **72** from about 0.0005 inches to about 0.003 inches; the tie layers **76** from about 0.0005 inches to about 0.02 inches; the core layer **74** of from about 0.0005 inches to about 0.0015 inches; and an inside layer **70** of from about 0.008 inches to about 0.012 inches.

[0054] In another preferred form, the membrane structure has four layers as shown in **FIG. 9**. **FIG. 9** shows a membrane **126** having an outer layer **128** of a polyamide, preferably nylon and more preferably a nylon 12, a third layer **130** of a modified ethylene vinyl acetate, preferably CXA, a second layer **132** of a barrier material, preferably EVOH, and an inner solution contact layer **134** of a modified ethylene vinyl acetate, preferably CXA.

[0055] The outer layer **128** has a thickness of a range of about 0.0003 to 0.0007 inches, and preferably about 0.0005 inches. The third layer **130** has a thickness range of between 0.0003 to 0.0007 inches, and preferably about 0.0005 inches. The second layer **132** has a thickness range of between 0.0007 to 0.0013 inches, and preferably about 0.001 inches. The inner layer **134** has a thickness of between 0.006 and 0.01 inches, and preferably about 0.008 inches. The membrane film can be formed by extrusion, coextrusion, lamination, extrusion coating, or other polymer processing technique well known in the art.

[0056] Turning our attention now to the receptacle **30** (**FIGS. 1a, 1b and 1c**). In a preferred form of the invention the receptacle **30** is of a polymeric material or structure and more preferably includes a barrier material as an additive to a layer or as a discrete barrier layer as defined above. In a preferred form of the invention, the receptacle has sidewalls **80** which are positioned in registration and sealed along a peripheral seam **82**. The sealing can be carried out by conductive heat sealing or inductive heat sealing such as through radio frequency sealing or can be sealed by other methods well known in the art. The peripheral seam **82**, preferably, has an outer seal **84**, an inner seal **86** and a material depot **88** positioned therebetween. One or more access or administration ports **89** can be provided as is well

known in the art. In a preferred form of the invention the receptacle can have a fill port **89'** on one end of the container and a administration port **89** on an opposite end of the container. The administration port can be the closure assembly **40** described above. The fill port **89'** can have the same structure as the administration port or, in a more preferred form of the invention, will be of a polyolefin material, a polyolefin blend or one of the other materials set forth above but will not include the gas barrier material of the administration port. The fill port **89'** can be removed after filling the container by a hot knife or during a step of sealing the container after filling. The material depot **88** defines an unsealed portion where material from the seals **84** and **86** can flow. The sidewalls **80** define a fluid containing chamber **90**. The fluid chamber is capable of storing flowable materials and more preferably is capable of forming a fluid tight seal. The receptacle and closure assembly will preferably have an oxygen permeability of less than 0.10 cc/day, more preferably less than 0.075 cc/day and most preferably less than 0.04 cc/day, or any range or combination of ranges therein.

[0057] In a preferred form of the invention, the sidewalls **80** are of a multiple layer structure and can include the material structures as shown in **FIGS. 3a to 3c** and the description set forth above for these structures. In a preferred form of the invention, the sidewall **80** has five layers. The structure is the same as that disclosed in **FIG. 3c** but includes an additional layer outward from inside layer **70**. The inner layer is preferably a polyolefin and more preferably an ethylene and  $\alpha$ -olefin copolymer. The relative thicknesses of the layers is fully set forth in U.S. Pat. No. 6,083,587 at column 5, line 64 through column 6, line 8.

[0058] The receptacle **30** shall have the following physical properties: modulus of elasticity of the sidewall of the receptacle is less than 60,000 psi and more preferably less than 40,000 psi; is suitable of storing an oxygen sensitive composition for at least about 6 months, more preferably at least about 1 year, more preferably at least about 2 years and even more preferably at least about 3 years; is capable of achieving these storage periods at temperatures of about room temperature and more preferably from 5° C. to about 45° C.

[0059] Turning our attention now to **FIG. 4** showing a port tube/closure assembly **40**. The assembly **40** preferably is constructed without the use of solvents or adhesives. The assembly **40** has one of the closure **54** described above formed into a disk shape and attached to the port tube end surface **58**. The closure can also be attached inside the port tube flow passage **56**. The closure **54** can be placed in contact with the end surface **58** of the port tube and attached thereto using conductive heat sealing, inductive heat sealing (such as using radio frequency energies), ultrasonic welding, vibration welding, or other techniques well known in the art.

[0060] It should be understood that a port tube **52** having any of the constructions described above can be combined with a closure **54** having any of the constructions described above. Thus, an assembly of a port tube **52** having any number of layers and a closure **54** having two layers, three layers or more is contemplated by the present invention. It is also contemplated that a port tube **52** having two layers, three layers or more could be combined with a membrane film **54** having any number of layers.

[0061] The spike holder **50** (which also may be referred to as a needle holder) is shown in **FIGS. 1a**, and **5-8**. The spike holder **50** has a body **100** having a first annular wall defining a first cavity or chamber **110** at a first end of the body, a second annular wall defining a second cavity or a second chamber **112** at a second end of the body, and a flow passage **114** connecting the first and second chambers. The first chamber **110** is dimensioned to telescopically receive an end portion **116** of the port tube **52**. In a preferred form of the invention the spike holder is fixedly attached to the port tube but could be releasably attached without departing from the scope of the present invention. It is contemplated by the present invention the annular wall could extend into the port tube flow passage **56** and attach thereto without departing from the present invention. The second chamber **112** is dimensioned to have an interference fit with an access spike or transfer needle **117** described below. As noted herein, the term interference fit means that the second chamber **112** has an identical or smaller dimension than the spike holders inserted therein but is capable of deforming (e.g., elastically) around the insert to hold the inserted device by friction. It is contemplated the second chamber **112** will fixedly attach to the insert or releasably attach to the insert. In a preferred form of the invention, the first chamber **110** and the second chamber **112** have a generally circular cross-sectional shape, the first chamber **110** having a first diameter and the second chamber **112** having a second diameter, the first diameter being larger than the second diameter.

[0062] In a preferred form of the invention, the spike holder **50** has an outwardly extending flange **118** at an intermediate portion thereof. The flange **118** is positioned generally at the intersection of the first chamber **110** and the second chamber **112**. The flange **118** has a first surface **120** which is textured to facilitate handling and manipulation of the holder. In one embodiment, this texture is provided by a plurality of buttresses **122** around the first annular wall of the body **100**. In a preferred form of the invention, the flange **118** is generally circular in cross-sectional shape and the buttresses **122** are circumferentially spaced about the first surface **120**. The buttresses are shown having a generally tear-drop shape, however, they could be of numerous different shapes without departing from the present invention. The buttresses are provided to form a gripping surface for those handling the spike holder **50**. It may also be desirable to add an internal shoulder or other feature to the spike holder **50** to limit the extent the transfer tube can be inserted into the flow passage.

[0063] The spike holder **50** is formed from a polyolefin as defined above and more particularly is an ethylene and  $\alpha$ -olefin copolymer. The spike holder **50** can also have a textured or matte finish on a portion or the entire outer surface **124** of the holder **50** for ease of handling. The spike holder **50** can be formed by any suitable polymer forming technique known to those skilled in the art and preferably the spike holder **50** is formed by injection molding. The spike holder **50** can also include a membrane film **54'** positioned in the passageway **114** in lieu of or in addition to the membrane **54**.

[0064] In a preferred form of the invention, the spike holder **50** is formed directly over the end portion **116** of the port tube/membrane film assemblies **40** described above. Such a process is conventional and referred to as an overmolding process. The overmolding process includes the

steps of: (1) providing a tubing as set forth above; providing a mold for forming a spike holder; inserting a portion **116** of the tubing **52** into the mold; and supplying polymeric material to the mold to form a spike holder on the tubing.

[**0065**] In an embodiment of the invention, the tubing, closure, and/or container sidewalls are comprised of a multilayer polymeric structure which includes a first layer of an ethylene vinyl alcohol copolymer having first and second sides, and a second layer of a modified ethylene vinyl acetate copolymer attached to the first side of the first layer. The second layer has a thickness of greater than 1.2 mils, preferably at least 1.3, 1.4, 1.5, 1.6, 1.7, 1.8, 1.9, 2.0, 2.1, 2.2, 2.3, 2.4, 2.5, 2.6, 2.7, 2.8, 2.9, or 3.0 mils. The polymeric structure optionally includes a third layer attached to the second side of the first layer. Preferably, the third layer comprises a polyamide or polyester as described herein. In one embodiment, the sidewalls of a container include a core layer, outside layer, or solution contact layer comprising a modified ethylene vinyl acetate copolymer as described herein. In another embodiment, the polymeric structure comprises an outside layer of a polyamide or polyester, a core layer of an ethylene vinyl alcohol copolymer, and a sealing layer of a modified ethylene vinyl acetate copolymer, wherein the core layer is between the outside and sealing layers. This polymeric structure optionally includes one or more tie layers attached to the core layer.

[**0066**] The receptacles of the present invention are used to store deoxyhemoglobin solutions or other therapeutic fluids which react with oxygen. The receptacles are filled with the solution in a low oxygen or oxygen free environment, sealed, and then stored at about 5 to 45° C. for weeks or months prior to use. Conventional methods of filling and sealing containers in a low oxygen or oxygen free environment are suitable for the invention. After storage, the deoxyhemoglobin solution contains less than 15% methemoglobin and is physiologically acceptable for administration to a patient. In a preferred embodiment, the deoxyhemoglobin solutions are stored at room temperature and ambient conditions.

[**0067**] The following is an example of the present invention and is not intended to limit the claims of the present invention.

#### EXAMPLE

[**0068**] Several 250 ml volume receptacles were fabricated as shown in **FIG. 1c** with a fill port and an administration port. Each receptacles had a total nominal surface area of approximately 450 cm<sup>2</sup>. The administration port had a core layer of an EVOH and an outside layer of a modified EVA (CXA) and a solution contact layer of a modified EVA (CXA). A membrane film was sealed to a distal end of the administration port. The membrane had an outer layer **134** of nylon 12, a third layer **130** of a modified ethylene vinyl acetate (CXA), a second layer **132** of EVOH, and an inner solution contact layer **128** of a modified ethylene vinyl acetate (CXA) (see **FIG. 9**). The fill port was injection molded of ethylene vinyl acetate (EVA). The receptacle sidewalls were fabricated from a five-layer structure as shown in **FIG. 3c**. An outside layer **72** was nylon 12, two tie layers **76** were a modified EVA copolymer (CXA), a core layer **74** was an EVOH and the inner layer **70** was a metallocene catalyzed ultra low density polyethylene. The

empty containers were sterilized by exposure to gamma radiation. The sterile containers were aseptically filled with an oxygen sensitive indicator solution through the fill port and the fill port was sealed and removed by a heated bar. The oxygen permeability of the containers were measured at 70% relative humidity at temperatures of 4° C., 23° C. and 40° C. and found to be 0.0008, 0.0041, and 0.0396 cc/day/package, respectively.

[**0069**] It is understood that, given the above description of the embodiments of the invention, various modifications may be made by one skilled in the art. Such modifications are intended to be encompassed by the claims below.

What is claimed is:

1. A closure assembly comprising:

a transfer tubing defining a fluid passageway, the tubing having an end surface; and

a membrane material disposed across the fluid passageway to provide a fluid tight seal, the membrane material being a multiple layered polymeric structure.

2. The closure of claim 1 wherein the membrane material is attached to the end surface of the tubing.

3. The closure of claim 1 wherein the membrane comprises:

a first layer of an ethylene vinyl alcohol copolymer having first side and a second side; and

a second layer of a modified ethylene vinyl acetate copolymer attached to the first side of the first layer.

4. The closure of claim 3 wherein the second layer is positioned between the first layer of ethylene vinyl alcohol copolymer and the end of the tubing.

5. The closure of claim 3 wherein the ethylene vinyl alcohol copolymer has an ethylene content of from about 25% to about 45% by mole percent.

6. The closure of claim 3 wherein the ethylene vinyl alcohol copolymer has an ethylene content of from about 28% to about 36% by mole percent.

7. The closure of claim 3 wherein the ethylene vinyl alcohol copolymer has an ethylene content of from about 30% to about 34% by mole percent.

8. The closure of claim 3 wherein the modified ethylene vinyl acetate copolymer has a modifying group selected from the group consisting of: carboxylic acid and carboxylic acid anhydrides.

9. The closure of claim 8 wherein the modifying group is maleic acid, fumaric acid, itaconic acid, citraconic acid, allylsuccinic acid, cyclohex-4-ene-1,2-dicarboxylic acid, 4-methylcyclohex-4-ene-1,2-dicarboxylic acid, bicyclo[2.2.1]hept-5-ene-2,3-dicarboxylic acid, x-methylbicyclo[2.2.1]hept-5-ene-2,3-dicarboxylic acid, maleic anhydride, itaconic anhydride, citraconic anhydride, allylsuccinic anhydride, cyclohex-4-ene-1,2-dicarboxylic anhydride, 4-methylcyclohex-4-ene-1,2-dicarboxylic anhydride, bicyclo[2.2.1]hept-5-ene-2,3-dicarboxylic anhydride, x-methylbicyclo[2.2.1]hept-5-ene-2,2-dicarboxylic anhydride, methyl acrylate, methyl methacrylate, ethyl acrylate, ethyl methacrylate, butyl acrylate, butyl methacrylate, glycidyl acrylate, glycidyl methacrylate, monoethyl maleate, diethyl maleate, monomethyl maleate, diethyl maleate, monomethyl fumarate, dimethyl fumarate, monomethyl itaconate, diethylitaconate, amide derivatives of unsaturated carboxylic acids including acrylamide, methacrylamide, maleicmonoa-

mide, maleic diamide, maleic N-monoethylamide, maleic N,N-diethylamide, maleic N-monobutylamide, maleic N,N-dibutylamide, fumaric monoamide, fumaric diamide, fumaric N-monoethylamide, fumaric N,N-diethylamide, fumaric N-monobutylamide and fumaric N,N-dibutylamide, imide derivatives of unsaturated carboxylic acids including maleimide, N-butylmaleimide and N-phenylmaleimide; and metal salts of unsaturated carboxylic acids including sodium acrylate, sodium methacrylate, potassium acrylate or potassium methacrylate.

10. The closure of claim 9 wherein the modifying group is a fused ring carboxylic acid anhydride.

11. The closure of claim 1 further comprising a third layer attached to the second side of the first layer.

12. The closure of claim 11 wherein the third layer is selected from the group consisting of polyamides and polyesters.

13. The closure of claim 12 wherein the polyamides are aliphatic polyamides obtained from the condensation reaction of di-amines having a carbon number within a range of 2-13, aliphatic polyamides resulting from a condensation reaction of di-acids having a carbon number within a range of 2-13, polyamides resulting from the condensation reaction of dimer fatty acids, and amide containing copolymers.

14. The closure of claim 12 wherein the polyamide is obtained from a ring-opening reaction of a lactam having from 4-12 carbons.

15. The closure of claim 12 wherein the modified ethylene vinyl acetate copolymer has a modifying group selected from the group consisting of: carboxylic acid and carboxylic acid anhydrides.

16. The closure of claim 15 wherein the modifying group is maleic acid, fumaric acid, itaconic acid, citraconic acid, allylsuccinic acid, cyclohex-4-ene-1,2-dicarboxylic acid, 4-methylcyclohex-4-ene-1,2-dicarboxylic acid, bicyclo [2.2.1]hept-5-ene-2,3-dicarboxylic acid, x-methylbicyclo [2.2.1]hept-5-ene-2,3-dicarboxylic acid, maleic anhydride, itaconic anhydride, citraconic anhydride, allylsuccinic anhydride, cyclohex-4-ene-1,2-dicarboxylic anhydride, 4-methylcyclohex-4-ene-1,2-dicarboxylic anhydride, bicyclo [2.2.1]hept-5-ene-2,3-dicarboxylic anhydride, x-methylbicyclo [2.2.1]hept-5-ene-2,2-dicarboxylic anhydride, methyl acrylate, methyl methacrylate, ethyl acrylate, ethyl methacrylate, butyl acrylate, butyl methacrylate, glycidyl acrylate, glycidyl methacrylate, monoethyl maleate, diethyl maleate, monomethyl maleate, diethyl maleate, monomethyl fumarate, dimethyl fumarate, monomethyl itaconate, diethylitaconate, amide derivatives of unsaturated carboxylic acids including acrylamide, methacrylamide, maleicmonoamide, maleic diamide, maleic N-monoethylamide, maleic N,N-diethylamide, maleic N-monobutylamide, maleic N,N-dibutylamide, fumaric monoamide, fumaric diamide, fumaric N-monoethylamide, fumaric N,N-diethylamide, fumaric N-monobutylamide and fumaric N,N-dibutylamide, imide derivatives of unsaturated carboxylic acids including maleimide, N-butylmaleimide and N-phenylmaleimide; and metal salts of unsaturated carboxylic acids including sodium acrylate, sodium methacrylate, potassium acrylate or potassium methacrylate.

17. The closure of claim 16 wherein the modifying group is a fused ring carboxylic acid anhydride.

18. The closure of claim 11 wherein the ethylene vinyl alcohol copolymer has an ethylene content of from about 25% to about 45% by mole percent.

19. The closure of claim 11 wherein the ethylene vinyl alcohol copolymer has an ethylene content of from about 28% to about 36% by mole percent.

20. The closure of claim 18 wherein the ethylene vinyl alcohol copolymer has an ethylene content of from about 30% to about 34% by mole percent.

21. A closure assembly comprising:

a transfer tubing having a multiple layered structure defining a fluid passageway, the tubing having an end surface; and

a membrane material disposed across the fluid passageway to provide a fluid tight seal.

22. The closure of claim 21 wherein the membrane material is attached to the end surface of the tubing.

23. The closure of claim 21 wherein the tubing is a multiple layered tubing.

24. The closure of claim 23 wherein the tubing has a layer of a barrier material.

25. The closure of claim 24 wherein the barrier material is a barrier to the transmission of oxygen.

26. The closure of claim 23 wherein the tubing has a first layer and a second layer, the first layer comprising an ethylene vinyl alcohol copolymer; and a second layer connected to the first layer and comprising a polyolefin, the first layer and the second layer being coaxially disposed with respect to one another.

27. The closure of claim 26 wherein the first layer is disposed coaxially within the second layer.

28. The closure of claim 26 wherein the first layer is disposed coaxially about the second layer.

29. The closure of claim 26 wherein the polyolefin is selected from the group consisting of: (1) ethylene and  $\alpha$ -olefin interpolymers having a density of less than about 0.915 g/cc, (2) ethylene vinyl acetate copolymers, and (3) modified ethylene vinyl acetate copolymers.

30. The closure of claim 29 wherein the polyolefin is an ethylene and  $\alpha$ -olefin copolymer.

31. The closure of claim 29 wherein the polyolefin is an ethylene vinyl acetate copolymer.

32. The closure of claim 29 wherein the polyolefin is a modified ethylene vinyl acetate copolymer.

33. The closure of claim 32 wherein the modified ethylene vinyl acetate copolymer has a modifying group selected from the group consisting of: carboxylic acid and carboxylic acid anhydrides.

34. The closure of claim 33 wherein the modifying group is maleic acid, fumaric acid, itaconic acid, citraconic acid, allylsuccinic acid, cyclohex-4-ene-1,2-dicarboxylic acid, 4-methylcyclohex-4-ene-1,2-dicarboxylic acid, bicyclo [2.2.1]hept-5-ene-2,3-dicarboxylic acid, x-methylbicyclo [2.2.1]hept-5-ene-2,3-dicarboxylic acid, maleic anhydride, itaconic anhydride, citraconic anhydride, allylsuccinic anhydride, cyclohex-4-ene-1,2-dicarboxylic anhydride, 4-methylcyclohex-4-ene-1,2-dicarboxylic anhydride, bicyclo [2.2.1]hept-5-ene-2,3-dicarboxylic anhydride, x-methylbicyclo [2.2.1]hept-5-ene-2,2-dicarboxylic anhydride, methyl acrylate, methyl methacrylate, ethyl acrylate, ethyl methacrylate, butyl acrylate, butyl methacrylate, glycidyl acrylate, glycidyl methacrylate, monoethyl maleate, diethyl maleate, monomethyl maleate, diethyl maleate, monomethyl fumarate, dimethyl fumarate, monomethyl itaconate, diethylitaconate, amide derivatives of unsaturated carboxylic acids including acrylamide, methacrylamide, maleicmonoamide

mide, maleic diamide, maleic N-monoethylamide, maleic N,N-diethylamide, maleic N-monobutylamide, maleic N,N-dibutylamide, fumaric monoamide, fumaric diamide, fumaric N-monoethylamide, fumaric N,N-diethylamide, fumaric N-monobutylamide and fumaric N,N-dibutylamide, imide derivatives of unsaturated carboxylic acids including maleimide, N-butylmaleimide and N-phenylmaleimide; and metal salts of unsaturated carboxylic acids including sodium acrylate, sodium methacrylate, potassium acrylate or potassium methacrylate.

**35.** The closure of claim 34 wherein the modifying group is a fused ring carboxylic acid anhydride.

**36.** The closure of claim 26 further comprising a third layer of a polyolefin.

**37.** The closure of claim 36 wherein the third layer is of the same material as the second layer.

**38.** The closure of claim 36 wherein the third layer is of a different material from the second layer.

**39.** The closure of claim 36 wherein the polyolefin is an ethylene and  $\alpha$ -olefin copolymer.

**40.** The closure of claim 36 wherein the polyolefin is an ethylene vinyl acetate copolymer.

**41.** The closure of claim 36 wherein the polyolefin is a modified ethylene vinyl acetate copolymer.

**42.** The closure of claim 41 wherein the modified ethylene vinyl acetate copolymer has a modifying group selected from the group consisting of: carboxylic acid and carboxylic acid anhydrides.

**43.** The closure of claim 42 wherein the modifying group is maleic acid, fumaric acid, itaconic acid, citraconic acid, allylsuccinic acid, cyclohex-4-ene-1,2-dicarboxylic acid, 4-methylcyclohex-4-ene-1,2-dicarboxylic acid, bicyclo[2.2.1]hept-5-ene-2,3-dicarboxylic acid, x-methylbicyclo[2.2.1]hept-5-ene-2,3-dicarboxylic acid, maleic anhydride, itaconic anhydride, citraconic anhydride, allylsuccinic anhydride, cyclohex-4-ene-1,2-dicarboxylic anhydride, 4-methylcyclohex-4-ene-1,2-dicarboxylic anhydride, bicyclo[2.2.1]hept-5-ene-2,3-dicarboxylic anhydride, x-methylbicyclo[2.2.1]hept-5-ene-2,2-dicarboxylic anhydride, methyl acrylate, methyl methacrylate, ethyl acrylate, ethyl methacrylate, butyl acrylate, butyl methacrylate, glycidyl acrylate, glycidyl methacrylate, monoethyl maleate, diethyl maleate, monomethyl maleate, diethyl maleate, monomethyl fumarate, dimethyl fumarate, monomethyl itaconate, diethylitaconate, amide derivatives of unsaturated carboxylic

acids including acrylamide, methacrylamide, maleicmonoamide, maleic diamide, maleic N-monoethylamide, maleic N,N-diethylamide, maleic N-monobutylamide, maleic N,N-dibutylamide, fumaric monoamide, fumaric diamide, fumaric N-monoethylamide, fumaric N,N-diethylamide, fumaric N-monobutylamide and fumaric N,N-dibutylamide, imide derivatives of unsaturated carboxylic acids including maleimide, N-butylmaleimide and N-phenylmaleimide; and metal salts of unsaturated carboxylic acids including sodium acrylate, sodium methacrylate, potassium acrylate or potassium methacrylate.

**44.** The closure of claim 43 wherein the modifying group is a fused ring carboxylic acid anhydride.

**45.** A closure assembly comprising:

a transfer tubing having a multiple layered structure having a first layer of an ethylene vinyl alcohol copolymer and a second layer of a polyolefin, the tubing defining a fluid passageway, the tubing having an end surface; and

a membrane material having a first layer of an ethylene vinyl alcohol copolymer and a second layer of a modified ethylene vinyl acetate copolymer, the membrane material disposed across the fluid passageway to provide a fluid tight seal.

**46.** The closure of claim 45 wherein the membrane material is attached to the end surface of the tubing.

**47.** A closure assembly comprising:

a transfer tubing having a first layer of an ethylene vinyl alcohol copolymer, a second layer of a polyolefin and a third layer selected from the group consisting of polyamides and polyesters, the tubing defining a fluid passageway, the tubing having an end surface; and

a membrane material having a first layer of an ethylene vinyl alcohol copolymer, a second layer of a modified ethylene vinyl acetate copolymer and a third layer selected from the group of polyamides and polyesters, the membrane material being disposed across the fluid passageway to provide a fluid tight seal.

**48.** The closure of claim 47 wherein the membrane material is attached to the end surface of the tubing.

\* \* \* \* \*