

(19) **DANMARK**



Patent- og
Varemærkestyrelsen

(12)

Oversættelse af europæisk patentskrift

(10) **DK/EP 4103236 T3**

-
- (51) Int.Cl.: **A 61 K 47/55 (2017.01)** **A 61 K 47/69 (2017.01)** **A 61 K 49/00 (2006.01)**
A 61 K 51/12 (2006.01) **A 61 K 103/00 (2006.01)** **A 61 P 35/00 (2006.01)**
- (45) Oversættelsen bekendtgjort den: **2023-11-13**
- (80) Dato for Den Europæiske Patentmyndigheds bekendtgørelse om meddelelse af patentet: **2023-08-16**
- (86) Europæisk ansøgning nr.: **21810835.5**
- (86) Europæisk indleveringsdag: **2021-10-26**
- (87) Den europæiske ansøgnings publiceringsdag: **2022-12-21**
- (86) International ansøgning nr.: **US2021056610**
- (87) Internationalt publikationsnr.: **WO2022093793**
- (30) Prioritet: **2020-10-27 US 202063105995 P** **2020-11-20 US 202063116393 P**
2020-11-23 US 202063117110 P **2021-03-01 US 202163155043 P**
2021-07-15 US 202163222181 P **2021-09-09 US 202163242201 P**
2021-10-12 US 202163254837 P
- (84) Designerede stater: **AL AT BE BG CH CY CZ DE DK EE ES FI FR GB GR HR HU IE IS IT LI LT LU LV MC MK MT NL NO PL PT RO RS SE SI SK SM TR**
- (73) Patenthaver: **Elucida Oncology, Inc., 1 Deer Park Drive, Suite E, Monmouth Junction, NJ 08852, USA**
- (72) Opfinder: **MA, Kai, , Monmouth Junction, NJ 08852, USA**
VENKATESAN, Aranapakam, M., , Monmouth Junction, NJ 08852, USA
CHEN, Feng, , Monmouth Junction, NJ 08852, USA
WU, Fei, , Monmouth Junction, NJ 08852, USA
TÜRKER, Melik, Ziya, , Monmouth Junction, NJ 08852, USA
GARDINIER, Thomas, Courtney, II, , Monmouth Junction, NJ 08852, USA
GERMANO, Geno, J., Jr., , Monmouth Junction, NJ 08852, USA
ADAMS, Gregory, Paul, , Monmouth Junction, NJ 08852, USA
LEE, Francis, Y., F., , Monmouth Junction, NJ 08852, USA
- (74) Fuldmægtig i Danmark: **Inspicos P/S, Agern Allé 24, 2970 Hørsholm, Danmark**
- (54) Benævnelse: **FOLATE RECEPTOR TARGETED NANOPARTICLE DRUG CONJUGATES AND USES THEREOF**
- (56) Fremdragne publikationer:
WO-A1-2011/003109
WO-A1-2017/189961
US-B2- 9 999 694
Adams G.P.: "Abstract 305: ELU001, a targeted C'Dot drug conjugate (CDC) for the treatment of folate receptor alpha (FR[alpha]) overexpressing cancers", , 1 July 2021 (2021-07-01), XP055887830, Retrieved from the Internet: URL:https://cancerres.aacrjournals.org/content/81/13_Supplement/305.abstract [retrieved on 2022-02-06]

Fortsættes ...

Adams Gregory P ET AL: "Title: ELU001, a targeted C'Dot drug conjugate (CDC) for the treatment of folate receptor alpha (FR[alpha]) overexpressing cancers", , 10 April 2021 (2021-04-10), XP055887831, Retrieved from the Internet: URL:<https://d1io3yog0oux5.cloudfront.net/elucidaoncology/files/docs/publications/20210422/Elucida+AACR+2021+Poster.pdf> [retrieved on 2022-02-06] -& Anonymous: "Elucida Oncology to Present Preclinical Data on ELU001 at the American Association for Cancer Research Annual Meeting ELU001 is Elucida's Lead C'Dot Drug Conjugate Designed to Target FR[alpha]-Overexpressing Cancers", , 29 March 2021 (2021-03-29), XP055887832, Retrieved from the Internet: URL:<https://www.biospace.com/article/releases/elucida-oncology-to-present-preclinical-data-on-elu001-at-the-american-association-for-cancer-research-annual-meeting-elu001-is-elucida-s-lead-c-dot-drug-conjugate-design> Anonymous: "A Study to Evaluate ELU001 in Patients With Solid Tumors That Overexpress Folate Receptor Alpha (FR[alpha])", , 4 August 2021 (2021-08-04), XP055887833, Retrieved from the Internet: URL:<https://clinicaltrials.gov/ct2/show/record/NCT05001282?term=elucida+oncology&draw=2&rank=1> [retrieved on 2022-02-06]

Description

RELATED APPLICATIONS

[0001] This application claims the benefit of U.S. Provisional Application No. 63/105,995, filed on October 27, 2020, U.S. Provisional Application No. 63/116,393, filed on November 20, 2020, U.S. Provisional Application No. 63/117,110, filed on November 23, 2020, U.S. Provisional Application No. 63/155,043, filed on March 1, 2021, U.S. Provisional Application No. 63/222,181, filed on July 15, 2021, U.S. Provisional Application No. 63/242,201, filed on September 9, 2021, and U.S. Provisional Application No. 63/254,837, filed on October 12, 2021.

BACKGROUND

[0002] Targeted delivery of therapeutics (e.g., cytotoxic drugs) to cancer cells is an emerging approach for cancer treatment. The toxicity of the delivered therapeutics to healthy tissue or organs in a subject can be greatly reduced by the selective delivery of drugs to a targeted disease area, leading to improved therapeutic outcomes. Antibody drug conjugates (ADCs) are a popular platform for targeted drug delivery, which typically feature a highly toxic drug substance covalently attached to a monoclonal antibody that can target cancer, wherein the toxic drug substance is released upon targeting of the cancer. However, many challenges remain with conventional targeted drug delivery platforms, such as ADCs, including difficulties in production, limitations in drug loading capacity, poor tumor penetration, and lack of ability to overcome tumor heterogeneity.

[0003] Cornell University and Memorial Sloan Kettering Cancer Center developed ultrasmall sub-10 nm silica-organic hybrid nanoparticles, referred to as Cornell prime dots (C'Dots), which have significant potential in diagnostics and therapeutic applications. For example, C'Dots can be conjugated with epidermal growth factor receptor inhibitors, e.g., gefitinib, which is a cancer-targeted agent that inhibits cancer growth (WO 2015/183882 A1). However, the mechanism of action (MOA) of EGFR inhibitors requires active binding to the epidermal growth factor receptor, so a continuous high concentration of the payload in the targeted cancer cell is required to effectively inhibit cancer cell proliferation. This type of MOA is generally not compatible with the fast blood circulation half-life of C'Dots.

[0004] Folate receptor alpha (FR α), also known as FOLR1, has received significant attention from the scientific community as a potential target for cancer therapy, and other isoforms of FR have also been identified as potential biological targets. See, e.g., Targeting Folate Receptor Alpha For Cancer Treatment, Cheung, A., et al. *Oncotarget* (2016) 7 (32):52553; Targeting the folate receptor: diagnostic and therapeutic approaches to personalize cancer treatments, Ledermann, J. A. et al., *Annals of Oncology* (2015), 26:2034-2043. Folate receptor (FR) is an ideal target for

cancer therapy, as FR can be overexpressed in tumors, such as those of the ovary, endometrium, breast, colon, and lung, but its distribution in normal tissues is low and restricted. Emerging insights have suggested that FR may also exhibit cell-growth regulation and signaling functions, in addition to serving as a folate receptor and transporter. These features together render FR an attractive therapeutic target.

[0005] Folic acid is transported into the cells by various mechanisms, and the most prevalent mechanism is mediation through folate receptors, of which there are four glycopeptide members (FR alpha [FOLR1], FR beta [FOLR2], FR gamma [FOLR3], and FR delta [FOLR4]). Among these four members, the alpha isoform (FR alpha or FR α) is a glycosylphosphatidylinositol (GPI)-anchored membrane protein with high affinity for binding and transporting the active form of folate, 5-methyltetrahydrofolate (5MTF). The alpha isoform has been reported to be over-expressed in certain solid tumors, for example, in ovarian cancer, fallopian tube cancer, primary peritoneum cancer, uterus cancer, kidney cancer, lung cancer, brain cancer, gastrointestinal cancer, and breast carcinomas. The alpha isoform is also over-expressed in certain hematological malignancies, which can be exploited for treatment of these malignancies, e.g., for treatment of acute myeloid lymphoma (AML), including pediatric AML. This low and restricted distribution in normal tissues or cells, alongside emerging insights into tumor-promoting functions and association of expression with patient prognosis, together render FR α an attractive therapeutic target. Additionally, the beta isoform (FR β) is overexpressed in certain cancers, e.g., hematological malignancies such as acute myeloid leukemia (AML) and chronic myelogenous leukemia (CML), providing the opportunity to develop targeted therapies for these cancers.

[0006] Although many FR-targeted drug delivery platforms have been developed and tested for cancer treatment in the past, e.g., using both ADCs and small-molecule drug conjugates, none of them are successfully approved for clinical use due to their limited therapeutic outcome (EP 0624377 A2, US 9192682 B2, Leamon, et al., "Comparative preclinical activity of the folate-targeted Vinca alkaloid conjugates EC140 and EC145, Int. J. Cancer (2007) 121:1585-1592; Leamon et al., "Folate-Vinca Alkaloid Conjugates for Cancer Therapy: A Structure-Activity Relationships, Bioconjugate Chemistry (2014) 25:560-568; Scaranti, M., et al. Exploiting the folate receptor α in oncology. Nat Rev Clin Oncol. (2020) 17: 349-359).

[0007] Therefore, successful development of a FR-targeted drug delivery platform remains highly desired.

SUMMARY

[0008] The present invention provides nanoparticle-drug conjugates (NDCs), pharmaceutical compositions comprising NDCs, and uses thereof, as set out in the appended claims. In one aspect, the present invention provides a nanoparticle-drug conjugate (NDC) comprising: (a) a silica nanoparticle; (b) polyethylene glycol (PEG)

that is covalently bonded to the surface of the nanoparticle; (c) a targeting ligand comprising folic acid, wherein the targeting ligand is attached to the nanoparticle directly or indirectly through a spacer group; and (d) a linker-payload conjugate, wherein: (i) the payload is exatecan; (ii) the linker-payload conjugate is attached to the nanoparticle directly or indirectly through a spacer group; (iii) the linker is a protease-cleavable linker; and (iv) the exatecan is released upon cleavage of the linker. In another aspect, the present invention provides a pharmaceutical composition comprising an NDC according to the invention, and a pharmaceutically acceptable excipient, optionally wherein the pharmaceutical composition is suitable for intravenous administration, and/or wherein the pharmaceutical composition is in a unit dosage form. In a further aspect, the present invention provides an NDC or a pharmaceutical compositions according to the invention for use in medicine, including for use in treating cancer.

[0009] The present disclosure provides a nanoparticle-drug conjugate (NDC) comprising: (a) a silica nanoparticle, and polyethylene glycol (PEG) covalently bonded to the surface of the nanoparticle; (b) a targeting ligand comprising folic acid, or a derivative or salt thereof, wherein the targeting ligand is attached to the nanoparticle directly or indirectly through a spacer group; and (c) a linker-payload conjugate, wherein: (i) the payload is exatecan; (ii) the linker-payload conjugate is attached to the nanoparticle directly or indirectly through a spacer group; (iii) the linker is a protease-cleavable linker; and (iv) the exatecan is released upon cleavage of the linker.

[0010] This disclosure also relates to nanoparticle-drug-conjugates (NDCs) comprising: (a) a nanoparticle that comprises a silica-based core and a silica shell surrounding at least a portion of the core; polyethylene glycol (PEG) covalently bonded to the surface of the nanoparticle, and a fluorescent compound covalently encapsulated within the core of the nanoparticle; (b) a targeting ligand that binds to folate receptor (FR), wherein the targeting ligand comprises folic acid, or a folate receptor binding derivative thereof, and wherein the targeting ligand is attached to the nanoparticle directly or indirectly through a spacer group; (c) a linker-payload conjugate, wherein the payload is a cytotoxic agent; wherein the linker-payload conjugate is attached to the nanoparticle directly or indirectly thorough a spacer group; wherein the cytotoxic agent is released upon cleavage of the linker; wherein the linker in the linker-payload conjugate is a protease-cleavable linker; and wherein the NDC has an average diameter between about 1 nm and about 10 nm, e.g., between about 3 nm and about 8 nm, or between about 3 nm and about 6 nm. The cytotoxic agent may be exatecan.


[0011] In the NDCs of the present disclosure, the average nanoparticle to payload ratio may range from 1 to 80, such as from 1 to 21 (e.g., 1 to 13, or 1 to 12) and the

average nanoparticle to targeting ligand ratio may range from 1 to 50, such as from 1 to 25 (e.g., 1 to 11).

[0012] The NDCs of the present disclosure may have an average diameter of between about 1 nm and about 10 nm, e.g., between about 5 nm and about 8 nm, between about 3 nm and about 8 nm, or between about 3 nm and about 6 nm.


[0013] The NDCs of the present disclosure may comprise any suitable dye or detectable compound, such as a fluorescent compound. For example, in an NDC of the present disclosure, the fluorescent compound may be Cy5. The fluorescent compound may be encapsulated within the nanoparticle (e.g., covalently linked to the silica core). The NDCs of the present disclosure can comprise a targeting ligand that binds to a folate receptor (FR). The targeting ligand may comprise folic acid or a derivative thereof. It should be understood that "folic acid" may encompass an amide or an ester of folic acid, e.g., folic acid may be conjugated to the nanoparticle (or spacer group) at its carboxyl terminus via an amide or ester bond. For example, "folic acid" may refer to the folic acid amide present in the exemplary NDC illustrated in FIG. 1.

[0014] The NDCs of the present disclosure may comprise structure (S-1):




wherein Payload comprises exatecan; Linker comprises a protease-cleavable linker; and the silicon atom is a part of the nanoparticle.

[0015] For example, the NDCs of the present disclosure may comprise structure (S-1a):




wherein the silicon atom is a part of the nanoparticle.

[0016] The NDCs of the present disclosure may comprise Structure (S-2):



wherein Targeting Ligand is folic acid, or a folate receptor binding derivative thereof, and the silicon atom is a part of the nanoparticle.

[0017] For example, the NDCs of the present disclosure may comprise structure (S-2a):




wherein the silicon atom is a part of the nanoparticle.

[0018] The NDCs of the present disclosure may comprise a combination of Structures **(S-1)** and **(S-2)**. For example, the NDCs may comprise both Structure **(S-1a)** and Structure **(S-2a)**, e.g., as depicted in FIG. 1. Structures S-1, S-1a, S-2, or S-2a may be present in the NDC at any desired ratio, e.g., at a ratio disclosed herein.

[0019] The disclosure also relates to NDCs comprising a nanoparticle that comprises a silica-based core and a silica shell surrounding at least a portion of the core; polyethylene glycol (PEG) covalently bonded to the surface of the nanoparticle; a fluorescent compound covalently encapsulated within the core of the nanoparticle; a targeting ligand, wherein the targeting ligand is folic acid; a linker-payload conjugate, wherein the linker-payload conjugate is a protease cleavable linker that is capable of undergoing hydrolysis at a C-terminal end upon protease binding thereby releasing the payload from the nanoparticle, wherein the protease comprises a serine protease or a cysteine protease, wherein the payload in the linker-payload conjugate is exatecan, or an analog of exatecan; and wherein the fluorescent compound is Cy5.


[0020] The disclosure also relates to NDCs comprising a nanoparticle that comprises a silica-based core and a silica shell surrounding at least a portion of the core; polyethylene glycol (PEG) covalently bonded to the surface of the nanoparticle; a Cy5 dye covalently encapsulated within the core of the nanoparticle; a targeting ligand

that binds to folate receptor, wherein the targeting ligand is folic acid, and wherein the targeting ligand is attached to the nanoparticle indirectly through a spacer group; a linker-payload conjugate, wherein the linker-payload conjugate is attached to the nanoparticle indirectly through a spacer group, wherein the linker-payload conjugate comprises a compound comprising the structure




and wherein the NDC has an average diameter between about 1 nm and about 10 nm (e.g., between about 1 and about 6 nm).

[0021] This disclosure also relates to nanoparticle drug conjugates (NDC) comprising: (a) a silica nanoparticle that comprises a silica-based core and a silica shell surrounding at least a portion of the core; and polyethylene glycol (PEG) covalently bonded to the surface of the nanoparticle; (b) an exatecan-linker moiety comprising the structure of Formula (NP-3):



(NP-3),

wherein x is 4 and y is 9; and (c) a targeting ligand moiety comprising the structure of Formula (NP-2)



(NP-2),

wherein x is 4 and y is 3, and wherein the exatecan-linker moiety and the targeting ligand moiety are each conjugated to a surface of the nanoparticle. The NDC may comprise a fluorescent dye (e.g., Cy5) covalently encapsulated within the core of the nanoparticle.

[0022] This disclosure also provides a method of treating a folate receptor (FR)-expressing cancer (e.g., a folate receptor (FR)-expressing tumor), comprising administering to a subject in need thereof an effective amount of an NDC described herein. The method may include administration of NDCs to the subject in need thereof intravenously. In the methods of the present disclosure, the subject may have a

cancer selected from the group consisting of ovarian cancer, endometrial cancer, fallopian tube cancer, cervical cancer, breast cancer (including, e.g., HER2+ breast cancer, HR+ breast cancer, HR- breast cancer, and triple-negative breast cancer), lung cancer (e.g., non-small cell lung cancer (NSCLC), mesothelioma, uterine cancer, gastrointestinal cancer (e.g., esophageal cancer, colon cancer, rectal cancer, and stomach cancer), pancreatic cancer, bladder cancer, kidney cancer, liver cancer, head and neck cancer, brain cancer, thyroid cancer, skin cancer, prostate cancer, testicular cancer, acute myeloid leukemia (AML, e.g., pediatric AML), and chronic myelogenous leukemia (CML). The NDCs of the present disclosure may also be used for targeting tumor associated macrophages, which may be used as a means to modify the immune status of a tumor in a subject. The NDCs of the present disclosure may be used in a method of treating an advanced, recurrent, or refractory solid tumor.

[0023] This disclosure provides use of an NDC for treating a folate receptor (FR)-expressing cancer (e.g., a folate receptor (FR)-expressing tumor). The use may include administration of NDCs intravenously to the subject in need thereof. In the use of the NDC, the subject may have a cancer selected from the group consisting of ovarian cancer, endometrial cancer, fallopian tube cancer, cervical cancer, breast cancer (including, e.g., HER2+ breast cancer, HR+ breast cancer, HR- breast cancer, and triple-negative breast cancer), lung cancer (e.g., non-small cell lung cancer (NSCLC), mesothelioma, uterine cancer, gastrointestinal cancer (e.g., esophageal cancer, colon cancer, rectal cancer, and stomach cancer), pancreatic cancer, bladder cancer, kidney cancer, liver cancer, head and neck cancer, brain cancer, thyroid cancer, skin cancer, prostate cancer, testicular cancer, acute myeloid leukemia (AML, e.g., pediatric AML), and chronic myelogenous leukemia (CML). In the use of the NDC, the cancer may be an advanced, recurrent, or refractory solid tumor.

[0024] This disclosure provides NDCs for use in the manufacture of a medicament for treating a folate receptor (FR)-expressing cancer (e.g., a folate receptor (FR)-expressing tumor). The use in the manufacture of a medicament may include administration of NDCs intravenously to the subject in need thereof. The use in the manufacture of a medicament may include administration of NDCs to a subject, wherein the subject has a cancer selected from the group consisting of ovarian cancer, endometrial cancer, fallopian tube cancer, cervical cancer, breast cancer (including, e.g., HER2+ breast cancer, HR+ breast cancer, HR-breast cancer, and triple-negative breast cancer), lung cancer (e.g., non-small cell lung cancer (NSCLC), mesothelioma, uterine cancer, gastrointestinal cancer (e.g., esophageal cancer, colon cancer, rectal cancer, and stomach cancer), pancreatic cancer, bladder cancer, kidney cancer, liver cancer, head and neck cancer, brain cancer, thyroid cancer, skin cancer, prostate cancer, testicular cancer, acute myeloid leukemia (AML, e.g., pediatric AML), and chronic myelogenous leukemia (CML). The NDCs of the present disclosure may be used in the manufacture of a medicament for treating an advanced, recurrent, or refractory solid tumors.

[0025] This disclosure also relates to a pharmaceutical composition comprising an NDC and a pharmaceutically acceptable excipient. The pharmaceutical compositions disclosed herein may be used for treating a folate receptor (FR)-expressing cancer (e.g., a folate receptor (FR)-expressing tumor).

BRIEF DESCRIPTION OF THE DRAWINGS

[0026]

FIG. 1 illustrates a representative chemical structure of nanoparticle-drug conjugate (NDC).

FIG. 2 depicts a flow chart for the synthesis of an exemplary functionalized nanoparticle (dibenzocyclooctyne (DBCO)-functionalized C'Dot).

FIG. 3 depicts a flow chart for the synthesis of an exemplary NDC (FA-CDC) comprising a C'Dot functionalized with folic acid (FA) and exatecan.

FIG. 4 illustrates a representative UV-Vis absorbance spectrum of an exemplary functionalized nanoparticle (DBCO-functionalized C'Dot). The absorption peak at 648 nm correspond to the Cy5 dye that is covalently encapsulated within the core of the C'Dot. The absorption peaks around 270 to 320 nm correspond to DBCO groups.

FIG. 5 illustrates a representative UV-Vis absorbance spectrum of an exemplary NDC (folic acid (FA)-functionalized C'Dot comprising exatecan (FA-CDC)). The absorption peak at 648 nm correspond to the Cy5 dye that is covalently encapsulated within the core of C'Dot. The absorption peaks around 330 to 400 nm correspond to exatecan.

FIG. 6 depicts a fluorescence correlation spectroscopy (FCS) correlation curve of an exemplary NDC (folic acid (FA)-functionalized exatecan-linker conjugated C'Dot (FA-CDC)) that is fitted by a single-modal FCS correlation function. Average hydrodynamic diameter was obtained *via* fitting the FCS correlation curve.

FIG. 7 depicts a chromatogram showing the elution of an exemplary NDC (folic acid (FA)-functionalized exatecan-linker conjugated C'Dot (FA-CDC)) by a gel permeation chromatography (GPC). The elution of FA-CDC (striped line under the curve) is compared to the elution time of protein standards with varying molecular weight (dashed line).

FIG. 8 depicts a reversed phase HPLC chromatogram of a purified exemplary NDC (folic acid (FA)-functionalized exatecan-linker conjugated C'Dot (FA-CDC)) at 330 nm.

This wavelength can be used to monitor both the FA-CDC and impurities that may be present after the synthesis or due to any degradation of the NDC.

FIG. 9 illustrates the UV-Vis absorbance spectra of an exemplary exatecan-payload conjugate. Exatecan has an absorption maximum around 360 nm.

FIGS. 10A-10B illustrate a representative HPLC chromatographs providing analysis of an exemplary NDC prepared according to Example 3, that is conjugated with folic acid as targeting ligand and with exatecan as a payload (NDC prepared using the exatecan-linker conjugate precursor 202, from Example 1). **FIG. 10A** depicts a representative HPLC chromatograph at 360 nm of the non-cleaved NDC showing a single peak at elution time around 6.3 min which corresponds to the non-released payload retained on the NDC. **FIG. 10B** depicts a representative HPLC chromatograph at 360 nm of a cleaved NDC, showing an additional peak at elution time around 3 to 4 min which corresponds to the released exatecan payload. The area under curve (AUC) of the released payload and the retained payload were used to calculate the percentage of released payload.

FIGS. 11A-11C are plots illustrating a drug releasing analysis of exemplary NDCs loaded with folic acid as targeting ligand and protease (cathepsin-B) cleavable exatecan-linker conjugates, at different time points after incubation with cathepsin-B. **FIG. 11A** depicts the reverse-phase HPLC chromatograph of NDC B at different time points after incubation with Cathepsin-B. **FIG. 11B** depicts the reverse-phase HPLC chromatograph of NDC C at different time points after incubation with cathepsin-B. **FIG. 11C** depicts the reverse-phase HPLC chromatograph of NDC D (prepared using the exatecan-linker conjugate precursor 202, from Example 1) at different time points after incubation with cathepsin-B.

FIGS. 12A-12C are plots illustrating a drug releasing kinetics of exemplary NDCs loaded with protease (cathepsin-B) cleavable exatecan-linker conjugates, at different time points after incubation with cathepsin-B enzyme, and depicts the time for half of the payloads to be released, *i.e.*, $T_{1/2}$. **FIG. 12A** depicts the $T_{1/2}$ as 2.9 hours for NDC B. **FIG. 12B** depicts the $T_{1/2}$ as 2.6 hours for NDC C. **FIG. 12C** depicts the $T_{1/2}$ as 1.4 hours for NDC D.

FIG. 13 depicts the competitive binding of an exemplary NDC (folic acid (FA)-functionalized drug-linker conjugated C'Dot (FA-CDC)) in a FR alpha positive (KB) cell line, when compared with free folic acid.

FIG. 14 depicts the flow cytometry of representative NDCs (two folic acid (FA)-functionalized drug-linker conjugated C'Dot (FA-CDCs)) in KB cell line with varied folic acid ligand density (either an average of 0, 12, or 25 folic acid molecules per nanoparticle). The exatecan-linker conjugate precursor used to prepare each NDC

used in the study is described in Example 1 (Compound 202). Blocking in the blocking group was achieved using 1 mM of free folic acid. A CDC with no folic acid, but same amount of exatecan-linker conjugate, was used as the negative control group.

FIG. 15 depicts the flow cytometry of representative NDCs (three folic acid (FA)-functionalized drug-linker conjugated C'Dots (FA-CDCs) in KB cell line with varied drug per particle ratio (DPR). The exatecan-linker conjugate precursor used to prepare the NDCs used in the study is described in Example 1 (Compound 202). Blocking in the blocking group was achieved using 1 mM of free folic acid. All FA-CDCs comprise between 12 and 22 folic acid moieties. FA-CDCs with high drug-particle ratio (DPR) comprise between 35 and 50 exatecan-linker conjugate groups. FA-CDCs with medium DPR comprise between 17 and 25 exatecan-linker conjugate groups. FA-CDCs with low DPR have between 5 and 10 exatecan-linker conjugate groups. CDCs with no folic acid, and 17 to 25 drug linkers, was used as the negative control group.

FIG. 16 depicts the flow cytometry of a representative NDC (folic acid (FA)-functionalized drug-linker conjugated C'Dot (FA-CDC)) at 1 nM that was pre-incubated with varied amounts of human plasma for 24 hours. Blocking in the blocking group was achieved with 1 mM of free folic acid. The exatecan-linker conjugate precursor used to prepare the NDC used in the study is described in Example 1 (Compound 202), to provide an average of 25 exatecan molecules per nanoparticle. The average number of folic acid ligands per nanoparticle was 15. CDC with no folic acid, but same amount of drug linkers was used as the negative control group.

FIG. 17 shows the confocal microscopy images of an exemplary NDC (folic acid (FA)-functionalized drug-linker conjugated C'Dot (FA-CDC), shown in Examples as NDC B) in KB (+++++) and TOV-112D (-) cell lines at 1 hour and 24 hours. Blocking in the blocking group was achieved using 0.1 mM of free folic acid. The average number of folic acid ligands on the FA-CDC (NDC B) is 12, and the number of exatecan-linker conjugates is 40). The lysosome was stained by using LysoTracker® Green, which is a green-fluorescent dye for labeling and tracking acidic organelles in live cells. With color images (not shown), the CDC appears red, the lysosome appears green, and the nucleus appears blue, due to fluorescence.

FIG. 18 is an image comparing the Z-stack confocal microscopic imaging of KB tumor spheroids treated with an exemplary folate-receptor (FR)-targeting NDC (NDC D, prepared according to Example 3 using the exatecan-linker conjugate precursor 202), a payload-free FR-targeting nanoparticle (FA-C'Dot), a FR-targeting ADC, or the corresponding payload-free FR-targeting antibody, at 37 °C for 4 hours, followed by washing. Scale bar: 200 µm.

FIG. 19A depicts a representative maximum intensity projection (MIP) PET/CT imaging of healthy nude mice injected with ^{89}Zr -DFO-FA-CDC at 1, 24, 48 and 72 hours post-injection.

FIG. 19B illustrates the biodistribution pattern of ^{89}Zr -DFO-FA-CDC in healthy nude mice at 2 and 24 hour post-injection (n=3). The exatecan-linker conjugate precursor used to prepare the NDC used in the study is described in Example 1 (Compound 202); the average number of folic acid ligands on each NDC (FA-CDC) is 12; and the average number of exatecan-linker conjugates on each NDC is 25.

FIGS. 20A-20F depicts the *in vivo* tumor growth inhibition studies of six exemplary folate receptor targeting NDCs (NDCs A-F) in KB tumor-bearing mice (n=7). NDC-A comprises about 19 drug-linker conjugate groups and about 18 folic acid ligands per nanoparticle. NDC B comprises about 25 drug-linker groups and about 15 folic acid ligands per nanoparticle. NDC C comprises about 19 drug-linker conjugate groups and about 13 folic acid ligands per nanoparticle. NDC D comprises about 25 drug-linker conjugate groups and about 12 folic acid ligands per nanoparticle. NDC E comprises about 17 drug-linker conjugate groups and about 17 folic acid ligands per nanoparticle. NDC F comprises about 23 drug-linker conjugate groups and about 20 folic acid ligands per nanoparticle.

FIGS. 21A-21B depict the IC_{50} curves of an exemplary NDC in irinotecan-resistant and naive KB cells, compared to non-conjugated irinotecan. **FIG. 21A** shows the IC_{50} curves of irinotecan in regular KB cells (naive cells), and in KB cells treated four times with irinotecan (irinotecan-resistant cells). **FIG. 21B** shows the IC_{50} curves of the exemplary NDC in the naive cells, and in the irinotecan-resistant cells. The exatecan-linker conjugate precursor used to prepare the exemplary NDC of this study is described in Example 1 (Compound 202).

FIGS. 22A-22B depict the IC_{50} curves of an exemplary NDC in exatecan-resistant and naive KB cells, compared to non-conjugated exatecan. **FIG. 21A** shows the IC_{50} curves of exatecan in regular KB cells (naive cells), and in KB cells treated four times or seven times with exatecan (exatecan-resistant cells). **FIG. 22A** shows the IC_{50} curves of the exemplary NDC in the naive cells and in the exatecan-resistant cells (4-cycle and 7-cycle pretreatment). The exatecan-linker conjugate precursor used to prepare the exemplary NDC of this study is described in Example 1 (Compound 202).

FIG. 23 provides a table demonstrating the cytotoxicity of exemplary folate receptor targeting NDCs ("FA-CDC") with varying drug-to-particle ratios (DPRs), in different FR- α overexpressing cancer cell lines, compared to non-conjugated exatecan. The exatecan-linker conjugate precursor used to prepare the exemplary NDCs of this study is described in Example 1 (Compound 202).

FIG. 24 provides a table showing the cytotoxicity of an exemplary NDC in various 3D patient-derived platinum-resistant tumor spheroids. The exatecan-linker conjugate precursor used to prepare the exemplary NDC of this study is described in Example 1 (Compound 202).

FIGS. 25A-25D provide flow cytometry histograms demonstrating the specific folate receptor (FR) alpha targeting capability of an exemplary FR-targeting NDC (prepared according to Example 3, using the exatecan-linker conjugate precursor 202 of Example 1) to both the IGROV-1 (FR alpha positive human ovarian cancer) and the engineered AML MV4;11 cell line that overexpresses FR alpha. **FIG. 25A** is the flow cytometry histogram of the FR targeting NDC (10 nM) and non-targeting NDC (negative control; 10 nM) in IGROV-1 cell line. **FIG. 25B** is the flow cytometry histogram of anti-FR alpha antibody-PE and isotype antibody-PE (negative control) in IGROV-1 cell line. **FIG. 25C** is the flow cytometry histogram of the FR targeting NDC (10 nM) and non-targeting NDC (negative control; 10 nM) in engineered AML MV4;11 cell line that overexpresses FR alpha. **FIG. 25D** is the flow cytometry histogram of anti-FR alpha antibody-PE and isotype antibody-PE (negative control) in engineered AML MV4; 11 cell line that overexpresses FR alpha.

FIGS. 26A-26B are graphs illustrating the *in vitro* cytotoxic activity of an exemplary NDC (prepared according to Example 3 using the exatecan-linker conjugate precursor of Example 1, Compound 202) in IGROV-1 (FR alpha positive human ovarian cancer) cell line (**FIG. 26A**) and MV4; 11 engineered AML MV4;11 cell line that overexpresses FR alpha (**FIG. 26B**) using non-targeted NDC as negative control.

FIG. 27 is a graph providing the bodyweight change of FR alpha overexpressing AML mice over time after treatment with normal saline or an exemplary NDC (prepared according to Example 3, using the exatecan-linker conjugate precursor of Example 1, Compound 202) at three different dose regimens (0.33 mg/kg, Q3Dx6 (denoted with squares); 0.50 mg/kg, Q3Dx3 (denoted with diamonds); or 0.65 mg/kg, Q3Dx3 (denoted with triangles)).

FIG. 28 provides images from *in vivo* bioluminescence imaging (BLI) of FR alpha overexpressing AML mice treated with normal saline or an exemplary NDC (prepared according to Example 3, using the exatecan-linker conjugate precursor of Example 1, Compound 202) at three different dose regimens (0.33 mg/kg, Q3Dx6); 0.50 mg/kg, Q3Dx3; or 0.65 mg/kg, Q3Dx3).

FIG. 29 is a graph providing the quantitative *in vivo* bioluminescence imaging analysis of FR alpha overexpressing AML mice treated with normal saline or an exemplary NDC (prepared according to Example 1, using the exatecan-linker conjugate precursor of Example 1, Compound 202) at three different dose regimens (0.33 mg/kg, Q3Dx6); 0.50 mg/kg, Q3Dx3; or 0.65 mg/kg, Q3Dx3).

FIG. 30 is a graph indicating the leukemia detected in bone marrow aspiration at Day 42 post-leukemia cell injection, obtained from mice treated with normal saline or an exemplary NDC (prepared according to Example 3, using the exatecan-linker conjugate precursor of Example 1, Compound 202) at three different dose regimens (0.33 mg/kg, Q3D×6); 0.50 mg/kg, Q3D×3; or 0.65 mg/kg, Q3D×3).

FIG. 31 is an illustration of the timeline used for preparing FR alpha overexpressing AML mice and dosing the mice with an exemplary NDC (prepared according to Example 3, using the exatecan-linker conjugate precursor of Example 1, Compound 202) at three different dose regimens (0.33 mg/kg, Q3D×6); 0.50 mg/kg, Q3D×3; or 0.65 mg/kg, Q3D×3), and imaging the mice with bioluminescent imaging (BLI). Each day of dosing is denoted by a triangle (i.e., on days 46, 49, and 52 for all dose groups, and also on days 55, 58, and 62 for the 0.33 mg/kg Q3D×6 dose group).

FIG. 32 shows the confocal microscopy images of an exemplary NDC (folic acid (FA)-functionalized drug-linker conjugated C'Dot (FA-CDC), shown in Examples as NDC D, prepared using exatecan-linker conjugate precursor 202) in KB (++++) and TOV-112D (-) cell lines after 1 hour and 24 hours. Blocking in the blocking group was achieved using 0.1 mM of free folic acid. The lysosome was stained by using LysoTracker® Green, which is a green-fluorescent dye for labeling and tracking acidic organelles in live cells. With color images (not shown), the CDC appears red, the lysosome appears green, and the nucleus appears blue, due to fluorescence.

FIGS. 33A-33B are graphs demonstrating the stability of exemplary NDCs prepared using methods disclosed herein. **FIG. 33A** compares the stability of an NDC produced using a diene-based functionalized nanoparticle (i.e., based on the protocol outlined in Example 3), and a comparative NDC produced using an amine-based functionalized nanoparticle, in human serum at 37 °C, over 7 days. **FIG. 33B** compares the stability of the NDC produced using a diene-based bifunctional precursor, and the comparative NDC produced using an amine-based bifunctional precursor, in mouse serum at 37 °C, over 7 days.

DETAILED DESCRIPTION

[0027] Described herein are nanoparticle drug conjugates (NDC), which comprise a nanoparticle (e.g., a silica nanoparticle, such as a multi-modal silica-based nanoparticle) that allows conjugation to targeting ligands and to cytotoxic payloads, for detection, prevention, monitoring, and/or treatment of a disease, such as cancer.

[0028] This disclosure provides compositions and methods of using a nanoparticle drug conjugate (NDC) comprising: a nanoparticle; a targeting ligand that binds to a

folate receptor (e.g., folic acid, or a derivative or salt thereof), and a linker-payload conjugate, that may comprise exatecan and a protease-cleavable linker.

[0029] The conjugation of both targeting ligands and linker-drug conjugates to the nanoparticle can be achieved *via* a highly efficient "click chemistry" reaction, which is fast, simple to perform, versatile, and results in high product yields. The payload may be a cytotoxic agent comprising exatecan, or a salt or analog thereof, that is attached to the nanoparticle *via* a cleavable linker group. The cleavable linker group can be cleaved when the NDC is internalized in a cancer cell (e.g., in a tumor cell), such as in the endosome or lysosomal compartment of the cell, causing release of the active cytotoxic agent from the NDCs. The cleavage may be catalyzed by a protease (e.g., cathepsin B).

[0030] The NDCs disclosed herein provide an optimal platform for drug delivery, due in part to their physical properties. For example, the NDCs comprise nanoparticles that are ultrasmall in diameter (e.g., with average diameter between about 1 nm and about 10 nm, such as between about 5 nm and about 8 nm) and benefit from enhanced permeability and retention (EPR) effects in tumor microenvironments, while retaining desired clearance and pharmacokinetic properties.

[0031] The NDCs described herein have certain advantages over other drug delivery platforms (e.g., ADCs such as FR-targeted ADCs, and FR-targeted small molecule drugs (e.g., chemotherapeutics)). For example, a single NDC of the present disclosure may include up to about 80 drug molecules on each nanoparticle (e.g., 80 exatecan molecules). In contrast, in conventional ADCs, only about 4 to 8 therapeutic/drug molecules can be attached to the antibody, and conventional FR-targeted small molecule drugs are limited to only a single therapeutic/drug molecule. Thus, the NDCs described herein can carry at least 10 times more drug molecules NDC, relative to conventional drug delivery platforms, and deliver a relatively higher drug load to cells.

[0032] While conventional folate receptor (FR)-targeting drug-delivery platforms, such as ADCs and FR-targeted small molecular chemotherapeutics, usually exhibit high potency in cancer cells with high receptor expression level, their efficacy in cancer cells with medium or low FR expression level is limited. In contrast, the NDCs of the present disclosure can effectively target cancer cells with both high and low FR expression levels and provide potent therapy for cancers that have low FR expression (see, e.g., FIG. 23 and associated assay described in the Examples).

[0033] Without wishing to be bound by any particular theory of mechanism, it is believed that, because the NDCs disclosed herein can include multiple FR-targeting ligands on a single nanoparticle, there is a multivalent or avidity effect on binding to several FRs on the cell surface. In contrast, a single ADC generally can only bind to up to two FRs on the cell surface, and a single FR-targeted chemotherapy drug can only

bind to one FR on the cell surface. Thus, the multivalent effect of the FR-targeted NDCs of the present disclosure can significantly enhance the binding of NDC to cells that express FR, leading to improved targeting efficiency and therapeutic outcomes. This multivalent effect can also render the NDCs of the present disclosure suitable for treating cancers that have low FR-expression, that cannot be effectively treated using conventional FR-targeted drug delivery platforms, such as ADCs or FR-targeted chemotherapy drugs.

[0034] The efficacy of ADCs in solid tumor treatment is usually greatly limited by their poor tumor penetration. In contrast, the FR-targeted NDCs disclosed herein exhibit highly effective tumor penetration, permitting the delivery of therapeutics throughout a tumor following administration, which improves therapeutic outcomes in treating solid tumors, relative to the use of ADCs.

[0035] The NDCs of the present disclosure have a smaller size than conventional drug delivery platforms, such as ADCs. Notably, the NDCs of the present disclosure are smaller than the particle size cut off for renal clearance, permitting the NDC to be renally clearable. As a result, NDCs that are administered to a subject but do not enter a cancer cell (i.e., non-targeted NDCs) can be rapidly cleared from the body via renal elimination. This target- and/or-clear approach reduces the toxicity of NDCs as compared to conventional drug delivery platforms, such as ADCs, and prevents undesirable accumulation of the NDCs (or their payloads) in healthy tissues or organs. The NDCs of the present disclosure exhibit improved biodistribution than conventional drug delivery platforms, such as ADCs, resulting in reduced side effect and toxicity.

Nanoparticles

[0036] This disclosure relates to NDCs comprising a nanoparticle, such as a silica nanoparticle. The nanoparticle may comprise a silica-based core and a silica shell surrounding at least a portion of the core. Alternatively, the nanoparticle may have only the core and no shell. The core of the nanoparticle may contain the reaction product of a reactive fluorescent compound and a co-reactive organo-silane compound. For example, the core of the nanoparticle may contain the reaction product of a reactive fluorescent compound and a co-reactive organo-silane compound, and silica. In preferred aspects of the present disclosure, the nanoparticle is a core-shell particle.

[0037] The diameter of the core may be from about 0.5 nm to about 100 nm, from about 0.1 nm to about 50 nm, from about 0.5 nm to about 25 nm, from about 0.8 nm to about 15 nm, or from about 1 nm to about 8 nm. For example, the diameter of the core may be from about 3 nm to about 8 nm, or 3 nm to about 6 nm, e.g., the diameter of the core may be from about 3 nm to about 4 nm, about 4 nm to about 5

nm, about 5 nm to about 6 nm, about 6 nm to about 7 nm, or about 7 nm to about 8 nm.

[0038] The shell of the nanoparticle can be the reaction product of a silica forming compound, such as a tetraalkyl orthosilicate, for example tetraethyl orthosilicate (TEOS). The shell of the nanoparticle may have a range of layers. For example, the silica shell may be from about 1 to about 20 layers, from about 1 to about 15 layers, from about 1 to about 10 layers, or from about 1 to about 5 layers. For example, the silica shell may comprise from about 1 to about 3 layers. The thickness of the shell may range from about 0.5 nm to about 90 nm, from about 0.5 nm to about 40 nm, from about 0.5 nm to about 20 nm, from about 0.5 nm to about 10 nm, or from about 0.5 nm to about 5 nm, e.g., about 1 nm, about 2 nm, about 3 nm, about 4 nm, or about 5 nm. For example, the thickness of the silica shell may be from about 0.5 nm to about 2 nm. The silica shell of the nanoparticle may cover only a portion of nanoparticle or the entire particle. For example, the silica shell may cover about 1 to about 100 percent, from about 10 to about 80 percent, from about 20 to about 60 percent, or from about 30 to about 50 percent of the nanoparticle. For example, the silica shell may cover about 50 to about 100 percent. The silica shell can be either solid, i.e., substantially non-porous, meso-porous, semi-porous, or the silica shell may be porous. The silica nanoparticle can be either solid, i.e., substantially non-porous, meso-porous, semi-porous, or the silica nanoparticle may be porous. In some embodiments, the nanoparticle is a non-mesoporous nanoparticle, e.g., a non-mesoporous silica nanoparticle, such as a non-mesoporous silica core-shell nanoparticle.

[0039] The surface of the nanoparticle may be modified to incorporate at least one functional group. An organic polymer may be attached to the nanoparticle and can be modified to incorporate at least one functional group by any known techniques in the art. The functional groups can include, but are not limited to, dibenzocyclooctyne (DBCO), maleimide, N-hydroxysuccinimide (NHS) ester, a diene (e.g., cyclopentadiene), an amine, or a thiol. For example, a bifunctional group comprising a silane at one terminus, and a DBCO, maleimide, NHS ester, diene (e.g., cyclopentadiene), amine, or thiol at the other terminus, may be condensed onto the surface of the silica nanoparticle via the silane group. The incorporation of the functional group can also be accomplished through known techniques in the art, such as using "click chemistry," amide coupling reactions, 1,2-additions such as a Michael addition, or Diels-Alder (2+4) cycloaddition reactions. This incorporation allows attachment of various targeting ligands, contrast agents and/or therapeutic agents to the nanoparticle.

[0040] The organic polymers that may be attached to the nanoparticle include, but are not limited to, poly(ethylene glycol) (PEG), polylactate, polylactic acids, sugars, lipids, polyglutamic acid (PGA), polyglycolic acid, poly(lactic-co-glycolic acid) (PLGA),

polyvinyl acetate (PVA), and combinations thereof. In preferred aspects of the present disclosure, the organic polymer is polyethylene glycol (PEG).

[0041] In preferred aspects of the present disclosure, the surface of the nanoparticle is functionalized. For example, the surface of the nanoparticle can have functional groups other than those resulting from the synthesis of the nanoparticles (e.g., -OH groups (resulting from terminal Si-OH groups on a nanoparticle surface) and PEG groups (resulting from Si-PEG groups on the nanoparticle surface). Such functionalization and functionalization methods are known in the art.

[0042] The nanoparticle may comprise a non-pore surface and a pore surface. In an embodiment, at least a portion of the individual nanoparticle non-pore surface and at least a portion of the individual nanoparticle pore surface are functionalized. In an embodiment, at least a portion of the nanoparticle non-pore surface and the at least a portion of the pore surface have different functionalization. The pore surface is also referred to herein as the interior surface. The nanoparticles may also have a non-pore surface (or non-porous surface). The non-pore surface is also referred to herein as the exterior nanoparticle surface.

[0043] The pore surface (e.g., at least a portion of the pore surface) and/or the non-pore surface (e.g., at least a portion of the non-pore surface) of the nanoparticle can be functionalized. For example, the nanoparticles can be reacted with compounds such that a functional group of the compound is presented on (e.g., covalently bonded to) the surface of the nanoparticle. The surface can be functionalized with hydrophilic groups (e.g., polar groups such as ketone groups, carboxylic acid, carboxylate groups, and ester groups), which provide a surface having hydrophilic character, or hydrophobic groups (e.g., nonpolar groups such as alkyl, aryl, and alkylaryl groups), which provide a surface having hydrophobic character. Such functionalization is known in the art. For example, diethoxydimethylsilane (DEDMS) can be condensed on at least a portion of the pore surface such that the pore surface has hydrophobic character, allowing increased loading performance of a hydrophobic cytotoxic payload relative to nanoparticles that are not functionalized so.

[0044] In preferred aspects of the present disclosure, the surface of the nanoparticle is at least partially functionalized with polyethylene glycol (PEG) groups. The attachment of PEG to the nanoparticle may be accomplished by a covalent bond or a non-covalent bond, such as by ionic bond, hydrogen bond, hydrophobic bond, coordination, adhesive, and physical absorption.


[0045] In certain aspects, the PEG groups are attached (e.g., covalently attached) to the surface of the nanoparticle. In a core-shell nanoparticle, the PEG groups are covalently bonded to the silica at the surface of the shell *via* a Si-O-C bond and or to

the silica in the core. In a core nanoparticle, the PEG groups are covalently bonded to the silica in the core.

[0046] In preferred aspects, the nanoparticle is a core-shell nanoparticle, wherein the PEG groups are covalently bonded to the silica at the surface of the shell *via* a Si-O-C bond. The PEG groups on the nanoparticle surface can prevent adsorption of serum proteins to the nanoparticle in a physiological environment (e.g., in a subject), and may facilitate efficient urinary excretion and decrease aggregation of the nanoparticle (see, e.g., Burns et al. "Fluorescent silica nanoparticles with efficient urinary excretion for nanomedicine", Nano Letters (2009) 9(1):442-448).


[0047] The PEG groups may be derived from PEG polymer having a molecular weight (Mw) of 400 g/mol to 2000 g/mol, including all integer g/mol values and ranges therebetween. In an embodiment, the PEG groups are derived from PEG polymer having a Mw of 460 g/mol to 590 g/mol, which contain 6 to 9 ethylene glycol units. In various embodiments, the nanoparticles are at least 50%, at least 75%, at least 90%, or at least 95% functionalized with PEG groups. In an embodiment, the nanoparticles are functionalized with PEG groups with the maximum number of PEG groups such that, the pores remain accessible (e.g., the pores can be functionalized). In an embodiment, the pore surface is a silica surface having terminal silanol (Si-OH) groups.

[0048] A polyethylene glycol unit disclosed herein may be functionalized with a functional group, for example, a "click chemistry" group, such as dibenzocyclooctyne (DBCO) or azide, a diene (e.g., cyclopentadiene), a maleimide, an NHS ester, an amine, a thiol, or an activated acetylene moiety such as



While DBCO can be used, the functional group may also be another alkyne, such as another strained alkyne (e.g., DIBO or a derivative thereof, or a derivative of DBCO). Also, the functional group may be a nitrone or a nitrile oxide.

[0049] Alternatively, or in addition to the foregoing, a functional group can be introduced to an NDC without necessarily requiring a PEG group. For example, an NDC may be functionalized with a functional group such as a "click chemistry" group, e.g., dibenzocyclooctyne (DBCO) or azide; a diene (e.g., cyclopentadiene); a maleimide; an NHS ester; an amine; a thiol; or an activated acetylene moiety such as



that may comprise any suitable linker, or may have no linker. While DBCO can be used to functionalize the nanoparticle, the functional group may also be another alkyne, such as another strained alkyne (e.g., DIBO or a derivative thereof, or a derivative of DBCO). Also, the functional group may be a nitrone or a nitrile oxide.


[0050] For example, a DBCO-functionalized linker may be introduced to a nanoparticle (e.g., a PEGylated C'Dot) by reacting the silane group on a DBCO-linker-silane compound with a silanol group on the surface of the nanoparticle (e.g., under the PEG layer on the C'Dot surface). Similarly, a diene-functionalized precursor (e.g., cyclopentadiene-functionalized precursor) may be introduced to a nanoparticle (e.g., a PEGylated C'Dot) by reacting the silane group on a diene-linker-silane or diene-silane precursor compound with a silanol group on the surface of the nanoparticle (e.g., under the PEG layer on the C'Dot surface), followed by functionalizing the diene on the nanoparticle with a second precursor that comprises a reactive group (e.g., DBCO) via a dienophile. The linker group in the DBCO-linker-silane or diene-linker-silane can comprise any structure (or sub-structure), including but not limited to PEG, a carbon chain (e.g., alkylene), a heteroalkylene group, or the like. The diene-functionalized linker covalently attached to the nanoparticle may be further modified, e.g., by reaction with a DBCO-functionalized group. For example, the diene-functionalized linker covalently attached to the nanoparticle may be contacted with a DBCO-linker-maleimide compound (or other suitable DBCO-linker-dienophile), to form a cycloadduct between the diene and maleimide, resulting in an NDC comprising DBCO groups attached to its surface, e.g., using cycloaddition chemistry, such as a Diels-Alder cycloaddition.

[0051] Functionalization (e.g., with one of the aforementioned functional groups, such as DBCO or cyclopentadiene) facilitates the conjugation of suitably functionalized FR-targeting ligands and/or functionalized drug payloads (such as azide-functionalized FR-targeting ligands and/or azide-functionalized drug payloads) to the nanoparticle by a coupling reaction, e.g., *via* click chemistry, (3+2) cycloaddition reactions, amide coupling, or Diels-Alder reaction. This functionalization approach also improves the versatility of the formulation chemistry and the stability of the FR-targeted NDC constructs.

[0052] An advantage of the NDCs disclosed herein is that they can be prepared using relatively stable linker or spacer groups, or precursors thereof. The linker or spacer groups, or their precursors, can avoid premature or undesired cleavage, which can occur using other linkers or precursors. For example, certain methods of functionalizing nanoparticles employ amine-silane precursors (to provide amine-functionalized nanoparticles) that are modified at the amine groups to conjugate other moieties to the nanoparticle. However, the amine-silane precursors can be unstable and can self-condense during reaction, causing undesired aggregation. The aggregates can be very difficult to separate from the functionalized nanoparticles. Additionally, the amine groups on the surface of the nanoparticle can promote undesired reactivity, that may lead to premature release of the payload, or undesired release of the targeting ligand.

[0053] The NDCs disclosed herein can be produced using relatively stable precursors, and the NDCs are stable and highly pure. For example, the nanoparticles of the present NDCs can be prepared with a silane-diene precursor (such as a silane-cyclopentadiene precursor), to afford a nanoparticle functionalized with one or more diene groups. The diene groups may then be reacted with a second precursor, such as a dienophile-containing precursor (e.g., a PEG-maleimide derivative, e.g., a DBCO-PEG-maleimide), causing a stable cycloadduct to form. The resulting functionalized nanoparticle, comprising the cycloadduct, may optionally be reacted with one or more subsequent precursors (such as targeting ligand precursors and/or payload-linker conjugate precursors described herein), to further functionalize the nanoparticle. The diene-silane precursors, and the cycloadducts that are produced, do not exhibit the undesired qualities of other functionalized nanoparticles, e.g., they have relatively high serum stability, can be produced in high yield and purity (e.g., free of aggregated precursor). See, e.g., FIGS. 33A-33B. Additionally, as this nanoparticle functionalization approach is highly modular, any desired ratio of payload, targeting ligand, or otherwise, can be introduced to the nanoparticle. Examples of preparing nanoparticles using these methods, and their benefits, are provided in the Examples.

[0054] The NDCs of the present disclosure may comprise a structure of Formula (NP):



wherein x is an integer of 0 to 20, e.g., 4; wherein the silicon atom is a part of the nanoparticle; and wherein the

adjacent to the triazole moiety denotes a point of attachment to a targeting ligand or payload-linker conjugate, either directly or indirectly, e.g., via a linker or spacer group, e.g., a PEG moiety. For example, the attachment may be to a linker or spacer group, e.g., the linker of a linker-payload conjugate, or a linker or spacer group of a folate receptor targeting ligand, e.g., a PEG moiety. The NDCs of the present disclosure may be prepared from diene (e.g., cyclopentadiene) functionalized nanoparticles, e.g., by conjugating a linker moiety (e.g., a linker comprising a dienophile, such as maleimide) to the diene with a cycloaddition reaction.

[0055] The silica shell surface of the nanoparticles can be modified by using known cross-linking agents to introduce surface functional groups. Crosslinking agents include, but are not limited to, divinyl benzene, ethylene glycol dimethacrylate, trimethylol propane trimethacrylate, N,N'-methylene-bis-acrylamide, alkyl ethers, sugars, peptides, DNA fragments, or other known functionally equivalent agents.

[0056] In order to permit the nanoparticle to be detectable by not only optical imaging (such as fluorescence imaging), but also other imaging techniques, such as positron emission tomography (PET), single photon emission computed tomography (SPECT), computerized tomography (CT), and magnetic resonance imaging (MRI), the nanoparticle may also be conjugated to a contrast agent, such as a radionuclide.

[0057] The nanoparticles may incorporate any suitable fluorescent compound, such as a fluorescent organic compound, a dye, a pigment, or a combination thereof. Such fluorescent compounds can be incorporated into the silica matrix of the core of the nanoparticle. A wide variety of suitable chemically reactive fluorescent dyes/fluorophores are known, see for example, MOLECULAR PROBES HANDBOOK OF FLUORESCENT PROBES AND RESEARCH CHEMICALS, 6th ed., R. P. Haugland, ed. (1996). In preferred aspects of the present disclosure, the fluorescent compound is covalently encapsulated within the core of the nanoparticle.

[0058] In some aspects, fluorescent compound can be, but is not limited to, a near infrared fluorescent (NIRF) dye that is positioned within the silica core of the nanoparticle, that can provide greater brightness and fluorescent quantum yield relative to the free fluorescent dye. It is well-known that the near infrared-emitting probes exhibit decreased tissue attenuation and autofluorescence (Burns et al. "Fluorescent silica nanoparticles with efficient urinary excretion for nanomedicine", Nano Letters (2009) 9(1):442-448).

[0059] Fluorescent compounds that may be used (e.g., encapsulated by an NDC) in the present disclosure, include, but are not limited to, Cy5, Cy5.5 (also known as Cy5++), Cy2, fluorescein isothiocyanate (FITC), tetramethylrhodamine isothiocyanate (TRITC), phycoerythrin, Cy7, fluorescein (FAM), Cy3, Cy3.5 (also known as Cy3++), Texas Red (sulforhodamine 101 acid chloride), LIGHTCYCLER®-Red 640, LIGHTCYCLER®-Red 705, tetramethylrhodamine (TMR), rhodamine, rhodamine derivative (ROX), hexachlorofluorescein (HEX), rhodamine 6G (R6G), the rhodamine derivative JA133, Alexa Fluorescent Dyes (such as ALEXA FLUOR® 488, ALEXA FLUOR® 546, ALEXA FLUOR® 633, ALEXA FLUOR® 555, and ALEXA FLUOR® 647), 4',6-diamidino-2-phenylindole (DAPI), propidium iodide, aminomethylcoumarin (AMCA), Spectrum Green, Spectrum Orange, Spectrum Aqua, LISSAMINE™, and fluorescent transition metal complexes, such as europium.

[0060] Fluorescent compounds that can be used also include fluorescent proteins, such as GFP (green fluorescent protein), enhanced GFP (EGFP), blue fluorescent protein and derivatives (BFP, EBFP, EBFP2, azurite, mKalamal), cyan fluorescent protein and derivatives (CFP, ECFP, Cerulean, CyPet) and yellow fluorescent protein and derivatives (YFP, Citrine, Venus, YPet) (WO 2008/142571, WO 2009/056282, WO 1999/22026).

[0061] In preferred aspects of the present disclosure, the fluorescent compound is selected from the group consisting of Cy5 and Cy5.5. In preferred aspects, the fluorescent compound is Cy5.

[0062] A fluorescent nanoparticle may be synthesized by the steps of: (1) covalently conjugating a fluorescent compound, such as a reactive fluorescent dye (e.g., Cy5), with a reactive moiety including, but not limited to, maleimide, iodoacetamide, thiosulfate, amine, N-hydroxysuccinimide ester, 4-sulfo-2,3,5,6-tetrafluorophenyl (STP) ester, sulfosuccinimidyl ester, sulfodichlorophenol esters, sulfonyl chloride, hydroxyl, isothiocyanate, carboxyl, to an organo-silane compound, such as a co-reactive organo-silane compound, to form a fluorescent silica precursor, and reacting the fluorescent silica precursor to form a fluorescent core; or (2) reacting the fluorescent silica precursor with a silica forming compound, such as tetraalkoxysilane, to form a fluorescent core. The fluorescent core may then be reacted with a silica forming compound, such as a tetraalkoxysilane, to form a silica shell on the core, to provide the fluorescent nanoparticle.

[0063] Fluorescent silica-based nanoparticles are known in the art and are described by US 8298677B2, US 9625456 B2, US 10548997 B2, US 9999694 B2, US 10039847 B2 and US 10548998 B2.

[0064] In preferred aspects of the present disclosure, the NDCs comprise a nanoparticle that comprises a silica-based core and a silica shell surrounding at least a portion of the core and polyethylene glycol (PEG) is covalently bonded to the surface of the nanoparticle, and a fluorescent compound is covalently encapsulated within the core of the nanoparticle.

Targeting Ligand

[0065] The NDCs of the present disclosure may comprise a targeting ligand that is attached to the nanoparticle directly or indirectly through a spacer group. NDCs with targeting ligands can enhance internalization of the payload/drugs in tumor cells and/or deliver drugs into tumor cells due to increased permeability, as well as the targeting ability of the NDC. The targeting ligand can allow the nanoparticle to target a specific cell type through the specific binding between the ligand and the cellular component. The targeting ligand may also facilitate entry of the nanoparticle into the cell or barrier transport, for example, for assaying the intracellular environment.

[0066] The targeting ligands of the present disclosure are capable of binding to receptors on tumor cells. Specifically, the targeting ligands can bind to the folate receptor (FR), including all four human isoforms of FR, including FR alpha (FR α , also known as FOLR1), FR beta (FR β , also known as FOLR2), FR gamma (FR γ , also known

as FOLR3), and FR delta ($FR\delta$, also known as FOLR4). Conjugation of FR targeting ligand to the surface of the nanoparticle of the present disclosure allows for targeted therapy of FR-overexpressing cancerous cells, tissues, and tumors. For example, NDCs of the present disclosure comprising targeting ligands that can bind to folate receptor alpha ($FR\alpha$), such as folic acid, may be used for targeting ovarian cancer, endometrial cancer, fallopian tube cancer, peritoneal cancer, cervical cancer, breast cancer, lung cancer, mesothelioma, uterine cancer, gastrointestinal cancer (e.g., esophageal cancer, colon cancer, rectal cancer, and stomach cancer), pancreatic cancer, bladder cancer, kidney cancer, liver cancer, head and neck cancer, brain cancer, thyroid cancer, skin cancer, prostate cancer, and testicular cancer, acute myeloid leukemia (AML, e.g., pediatric AML). NDCs of the present disclosure comprising targeting ligands that can bind to folate receptor beta ($FR\beta$) may be used for targeting acute myeloid leukemia (AML, e.g., pediatric AML), chronic myelogenous leukemia (CML), and tumor associated macrophages. Tumor associated macrophages can be targeted as a means to modify the immune status of the tumor. Without wishing to be bound by theory, the binding affinity of FR-targeted NDCs to folate receptors can be enhanced due to multivalence effect.

[0067] Folate receptor can be highly expressed in solid tumor cells, including ovarian, kidney, lung, brain, endometrial, colorectal, pancreatic, gastric, prostate, breast and non-small-cell lung cancers. FR is over-expressed in other cancers including fallopian tube cancer, cervical cancer, mesothelioma, uterine cancer, esophageal cancer, stomach cancer, bladder cancer, liver cancer, head and neck cancer, thyroid cancer, skin cancer, and testicular cancer. FR is also over-expressed in hematological malignancies, such as acute myeloid leukemia (AML) and chronic myelogenous leukemia (CML).

[0068] In preferred aspects of the present disclosure, the targeting ligands bind to folate receptor alpha ($FR\alpha$), folate receptor beta ($FR\beta$), or both.

[0069] The present disclosure provides FR-targeting ligands that are capable of binding to specific cell types having elevated levels of $FR\alpha$, such as, but not limited to, cancer (e.g., adenocarcinomas) of uterus, ovary, breast, cervix, kidney, colon, testicles (e.g., testicular choriocarcinoma), brain (e.g., ependymal brain tumors), malignant pleural mesothelioma, and nonfunctioning pituitary adenocarcinoma. The present disclosure also provides FR-targeting ligands that are capable of targeting acute myeloid leukemia (AML, e.g., pediatric AML), chronic myelogenous leukemia (CML), and tumor associated macrophages. The targeting ligand can be any suitable molecule that can bind a FR, such as $FR\alpha$, such as a small organic molecule (e.g., folate or a folate analog), an antigen-binding portion of an antibody (e.g. a Fab fragment, a Fab' fragment, a $F(ab')_2$ fragment, a scFv fragment, a Fv fragment, a dsFv diabody, a dAb fragment, a Fd' fragment, a Fd fragment, or an isolated complementarity determining region (CDR) region), an antibody mimetic (e.g.,

aptamer, an affibody, affilin, affimer, anticalin, avimer, Darpin, and the like), a nucleic acid, lipid, and the like.

[0070] In aspects of the present disclosure, the targeting ligand is folic acid, or a folate receptor binding derivative thereof. It will be understood that "folic acid" can encompass any amide or ester derivative of folic acid. For example, free folic acid may be modified to be conjugated to the nanoparticle via a spacer group, such as PEG or a PEG derivative (e.g., by forming an amide bond between the terminal carboxylic acid of folic acid, and a nitrogen atom of the spacer group).

[0071] The FR-targeted NDCs may not only accumulate in a cancer cell or tumor, but may also penetrate the tumor tissue and deliver payloads to the entire tumor tissue for optimal treatment efficacy. Without wishing to be bound by any particular theory or mechanism, it is believed that the targeting ligands bind to the specific receptor groups on the surface of the cancer cell, resulting in receptor-mediated cell uptake of NDCs. This receptor-mediated cell uptake of NDCs happens *via* the endocytosis process, and eventually traffics NDCs to endosomes and lysosomes in cancer cells.

[0072] In aspects of the present disclosure, the NDCs comprise a targeting ligand that is attached to the nanoparticle directly or indirectly through a spacer group. For example, the targeting ligand can be attached to the nanoparticle directly *via* the silica of the nanoparticle (i.e., covalently bonded). In preferred aspects, the targeting ligand is attached to the nanoparticle indirectly through a suitable spacer group.

[0073] The spacer group can be any group that can act as a spacer, e.g., as a spacer between a targeting ligand and the nanoparticle, and attach the targeting ligand to the nanoparticle. The spacer group may be a divalent linker, such as a divalent linker that comprises a chain length of between about 5 and about 200 atoms (e.g., carbon atoms, heteroatoms, or a combination thereof), such as between about 5 and about 100 atoms, between about 5 and about 80 atoms, between about 10 and about 80 atoms, between about 10 and about 70 atoms, between about 10 and about 30 atoms, between about 20 and about 30 atoms, between about 30 and about 80 atoms, or between about 30 and about 60 atoms. Suitable spacer groups may comprise an alkylene, alkenylene, alkynylene, heteroalkylene (e.g., PEG), carbocyclyl, heterocyclyl, aryl, heteroaryl, or a combination thereof. For example, the spacer group may comprise a PEG group, an alkylene group, or a combination thereof. The spacer group may be substituted or unsubstituted, e.g., the spacer group may comprise a substituted alkylene, substituted heteroalkylene, or a combination thereof. For example, the spacer group may comprise a PEG group (or PEG spacer), an alkylene group (or alkylene spacer), one or more heteroatoms, and/or one or more cyclic groups (e.g., heterocyclylene groups, such as a piperazine).

[0074] The targeting ligand, such as folic acid, may be attached to the nanoparticle

indirectly through a PEG spacer group. The folic acid may be present in the NDC as an amide, e.g., to facilitate conjugation to a PEG spacer group or other divalent linker, e.g., as shown in FIG. 1. The number of PEG monomers in a PEG spacer may range from 2 to 20, from 2 to 10, from 2 to 8, or from 2 to 5. In preferred aspects, the number of PEG groups as spacers in a functionalized FR-targeting ligand is 3.

[0075] The average nanoparticle to targeting ligand (e.g., folic acid) ratio may range from about 1 to about 50, from about 1 to about 40, from about 1 to about 30, or from about 1 to about 20. For example, the average nanoparticle to targeting ligand (e.g., folic acid) ratio may be about 1:1, 1:2, 1:3, 1:4, 1:5, 1:6, 1:7, 1:8, 1:9, 1:10, 1:11, 1:12, 1:13, 1:14, 1:15, 1:16, 1:17, 1:18, 1:19, 1:20, 1:21, 1:22, 1:23, 1:24, 1:25, 1:26, 1:27, 1:28, 1:29, 1:30, 1:40, or 1:50. For example, the average nanoparticle to targeting ligand ratio may range from about 1 to about 20, e.g., the average number of folic acid molecules on each nanoparticle may be between about 5 and about 10, between about 10 and about 15, or between about 15 and about 20, e.g., about 1, about 2, about 3, about 4, about 5, about 6, about 7, about 8, about 9, about 10, about 11, about 12, about 13, about 14, or about 15 folic acid molecules per nanoparticle. An NDC disclosed herein may comprise about 10 folic acid molecules. An NDC disclosed herein may comprise about 11 folic acid molecules. An NDC disclosed herein may comprise about 12 folic acid molecules. An NDC disclosed herein may comprise about 13 folic acid molecules. An NDC disclosed herein may comprise about 14 folic acid molecules. An NDC disclosed herein may comprise about 15 folic acid molecules.

[0076] A smaller number of targeting ligands attached to the nanoparticle may help maintain the hydrodynamic diameter of the nanoparticle, e.g., to meet the renal clearance cutoff size range (Hilderbrand et al., Near-infrared fluorescence: Application to in vivo molecular imaging, Curr. Opin. Chem. Biol., (2010) 14:71-79). The number of targeting ligands measured may be an average number of targeting ligands attached to more than one nanoparticle. Alternatively, one nanoparticle may be measured to determine the number of targeting ligands attached.

[0077] The number of targeting ligands attached to the nanoparticle can be measured by any suitable methods, such as, but not limited to, optical imaging, fluorescence correlation spectroscopy (FCS), UV-Vis, chromatography, mass spectroscopy, or indirect enzymatic analysis.


[0078] The targeting ligand can be attached to the nanoparticle *via* covalent bonding to the silica of the nanoparticle (e.g., indirectly through a spacer group). The ligand may be conjugated to a nanoparticle (e.g., via a functional group on the nanoparticle surface) described herein, for example, using coupling reactions, Click Chemistry (e.g., a 3+2 Click Chemistry reaction), cycloaddition (e.g., a 3+2 or 2+4 cycloaddition reaction, using the appropriate functional groups), or conjugation via a carboxylate,

ester, alcohol, carbamide, aldehyde, amine, sulfur oxide, nitrile oxide, nitron, nitrogen oxide, halide, or any other suitable compound known in the art.

[0079] In preferred aspects of the present disclosure, the conjugation of FR-targeting ligands can be accomplished by "click chemistry" reaction using a diarylcyclooctyne (DBCO) group. Any suitable reaction mechanism may be adapted in the present disclosure for "click chemistry", so long as facile and controlled attachment of the targeting ligand to the nanoparticle can be achieved.

[0080] In some aspects, a triple bond (e.g., alkyne, e.g., terminal alkyne) is introduced onto the surface of a nanoparticle (e.g., via a PEG covalently conjugated with the shell of the nanoparticle, or through another suitable linker or spacer group). Separately, an azide bond, or other group that is reactive with a triple bond, may be introduced onto the desired targeting ligand. For example, folic acid may be modified by conjugating the terminal carboxylic acid of folic acid with a spacer group (e.g., a PEG moiety), that comprises an azide at one terminus). The nanoparticle (e.g., PEGylated nanoparticle) comprising the free triple bond, and the targeting ligand (comprising a group reactive with the triple bond), can be mixed (with or without a copper or other metal catalyst) to effect cycloaddition of the group reactive with the triple bond (e.g., azide) to the triple bond, resulting in the conjugation of the targeting ligand with the nanoparticle (e.g., "Click Chemistry"). Many variations of this approach can also be used, as will be readily apparent to a person of ordinary skill in the art.

[0081] An azide functionalized FR-ligand (where the FR-ligand may comprise a spacer group, and the spacer group may possess the azide group) can be attached to the nanoparticle either directly or indirectly *via* an alkyne (e.g., DBCO group). Spacer groups, such as, but not limited to PEG groups, can be present in a FR-targeting ligand precursor, and may possess a terminal group (e.g., azide) to facilitate conjugation to the nanoparticle, and after conjugation, the spacer group may be disposed between the targeting ligand and the nanoparticle. For example, the FR-targeting ligand precursor may comprise a structure of Formula (D-1):



wherein y is an integer of 0 to 20 (e.g., 3). For example, y may be 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, or 20, e.g., 2, 3, or 4.


[0082] In some aspects, the FR-targeting ligand may be functionalized with a suitable terminal group, such as, but not limited to an azide group. The azide functionalized FR-ligand can be attached to the nanoparticle either directly or

indirectly *via* the DBCO groups. Spacer groups, such as, but not limited to PEG groups can be present between the azide functionalized FR-ligand and the nanoparticle. In preferred aspects, the FR-targeting ligand is functionalized to include spacer groups, such as, but not limited to PEG groups that terminate with an azide group that reacts with the DBCO groups on the surface of the nanoparticle.

[0083] The functionalization of FR-targeting ligand may include hydrophilic PEG groups as spacers, that may enhance solubility in water, and may reduce or eliminate aggregation and precipitation of the nanoparticle.

[0084] In aspects of the present disclosure, the number of PEG groups as spacers that can be present in a functionalized FR-targeting ligand may be in the range of from 2 to 20, from 2 to 10, from 2 to 8, or from 2 to 5. In preferred aspects, the number of PEG groups as spacers in a functionalized FR-targeting ligand is 3.

[0085] The NDCs of the present disclosure comprising a targeting ligand may comprise a structure of Formula (NP-2):



wherein x is an integer of 0 to 10 (e.g., 0, 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, e.g., 4), and y is an integer of 0 to 20 (e.g., 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, or 20, e.g., 3), and the silicon atom is a part of the nanoparticle (e.g., bonded with the silica shell of a core-shell silica nanoparticle). For example, x may be 4, and y may be 3. Each nanoparticle of the NDCs disclosed herein may comprise more than one molecule of Formula (NP-2), for example, the nanoparticle may comprise between about 1 and about 20 molecules of Formula (NP-2), e.g., between about 5 and about 20 molecules of Formula (NP-2), between about 8 and about 15 molecules of Formula (NP-2), between about 10 and about 15 molecules of Formula (NP-2), e.g., about 1, about 2, about 3, about 4, about 5, about 6, about 7, about 8, about 9, about 10, about 11, about 12, about 13, about 14, about 15, about 16, about 17, about 18, about 19, or about 20 molecules of Formula (NP-2). An NDC disclosed herein may comprise about 12 molecules of Formula (NP-2). An NDC disclosed herein may comprise about 13 molecules of Formula (NP-2).

Linker-Payload Conjugate

[0086] The NDCs of the present disclosure can also comprise a linker-payload

conjugate that is attached to the nanoparticle directly or indirectly through a spacer group. In preferred aspects, the linker-payload conjugate is attached to the nanoparticle through a spacer group. The payload may be exatecan, or a salt or analog thereof.

[0087] The spacer group can be any group that can act as a spacer, e.g., as a spacer between a payload/linker conjugate and the nanoparticle, and attach the linker-payload conjugate to the nanoparticle. The spacer group may be a divalent linker, such as a divalent linker that comprises a chain length of between about 5 and about 200 atoms (e.g., carbon atoms, heteroatoms, or a combination thereof), such as between about 5 and about 100 atoms, between about 5 and about 80 atoms, between about 10 and about 80 atoms, between about 10 and about 70 atoms, between about 10 and about 30 atoms, between about 20 and about 30 atoms, between about 30 and about 80 atoms, or between about 30 and about 60 atoms. Suitable spacer groups may comprise an alkylene, alkenylene, alkynylene, heteroalkylene (e.g., PEG), carbocyclyl, heterocyclyl, aryl, heteroaryl, or a combination thereof. For example, the spacer group may comprise a PEG group, an alkylene group, or a combination thereof. The spacer group may be substituted or unsubstituted, e.g., the spacer group may comprise a substituted alkylene, substituted heteroalkylene, or a combination thereof. For example, the spacer group may comprise a PEG group (or PEG spacer), an alkylene group (or alkylene spacer), one or more heteroatoms, and/or one or more or cyclic groups.

[0088] It will be understood that chemical modifications may be made to the payload in order to make reactions of the payload with linker more convenient for purposes of preparing conjugates of the present disclosure. For example, a functional group, e.g., amine, hydroxyl, or sulfhydryl, may be appended to the payload (e.g., exatecan) at a position which has minimal or an acceptable effect on the activity or other properties of the payload (e.g., exatecan). Alternatively, an existing functional group on the payload (e.g., pendant amine group) may be the point of attachment to the linker. For example, exatecan contains an amine functional group suitable for coupling to the linker moiety

[0089] The payload (e.g., exatecan payload, or a salt or analog thereof) can be cleaved from the nanoparticle inside a cell, or a cell organelle, e.g., by an enzyme, thereby releasing exatecan, e.g., inside the cell or cell organelle). Exatecan is a topoisomerase 1 (Topo-1) inhibitor that can stabilize the complexes of DNA and Topo-1 enzyme, preventing DNA relegation and inducing lethal DNA strand breaks. The generation of these DNA lesions is effective for killing cancer cells, allowing NDCs of the present disclosure to achieve the desired therapeutic effect.

[0090] In preferred aspects of the present disclosure, the payload is exatecan, or a

salt thereof. In other preferred aspects of the present disclosure, the payload is an analog of exatecan, or a salt thereof.

[0091] In aspects of the present disclosure, the average nanoparticle to payload ratio ranges from 1 to 80, from 1 to 70, from 1 to 60, from 1 to 50, from 1 to 40, from 1 to 30, from 1 to 20, from 1 to 15, from 1 to 12 and preferably from 1 to 10. For example, the average nanoparticle to payload (e.g., exatecan, or a salt or analog thereof) ratio may be about 1:1, 1:2, 1:3, 1:4, 1:5, 1:6, 1:7, 1:8, 1:9, 1:10, 1:11, 1:12, 1:13, 1:14, 1:15, 1:16, 1:17, 1:18, 1:19, 1:20, 1:21, 1:22, 1:23, 1:24, 1:25, 1:26, 1:27, 1:28, 1:29, 1:30, 1:32, 1:34, 1:36, 1:38, 1:40, 1:45, 1:50, 1:55, 1:60, 1:65, 1:70, 1:75, or 1:80. For example, the average number of exatecan molecules on each nanoparticle may be between about 5 and about 10, between about 10 and about 15, between about 15 and about 20, between about 20 and about 25, or between about 25 and about 30, e.g., about 1, about 2, about 3, about 4, about 5, about 6, about 7, about 8, about 9, about 10, about 11, about 12, about 13, about 14, about 15, about 16, about 17, about 18, about 19, about 20, about 21, about 22, about 23, about 24, about 25, about 26, about 27, about 28, about 29, or about 30 exatecan molecules per nanoparticle. An NDC disclosed herein may comprise about 18 exatecan molecules. An NDC disclosed herein may comprise about 19 exatecan molecules. An NDC disclosed herein may comprise about 20 exatecan molecules. An NDC disclosed herein may comprise about 21 exatecan molecules. An NDC disclosed herein may comprise about 22 exatecan molecules. An NDC disclosed herein may comprise about 23 exatecan molecules. An NDC disclosed herein may comprise about 24 exatecan molecules. An NDC disclosed herein may comprise about 25 exatecan molecules. An NDC disclosed herein may comprise about 26 exatecan molecules. An NDC disclosed herein may comprise about 27 exatecan molecules.


[0092] Vintafolide, developed by Endocyte and Merck & Co. is a small molecule drug conjugate consisting of a small molecule targeting the Folate Receptor, which is over expressed on certain cancers, such as ovarian cancer, and a chemotherapy drug, Vinblastine (US 7601332 B2 and US 1002942 B2). However, vintafolide is capable of carrying single molecule of payload only, attached to the targeting moiety by a pH-cleavable linker. In contrast to that, in the present disclosure several cytotoxic payloads (e.g., exatecan molecules) can be incorporated onto the surface of single nanoparticle.

[0093] The linkers in the linker-payload conjugates can be self-immolative linkers that are capable of releasing the active payload *in vitro* as well as *in vivo* under conditions sufficient for enzymatic release of the active payload (e.g., a condition presenting an enzyme capable of catalyzing the release).

[0094] The linkers described herein can be used, for example, to attach a cytotoxic drug payload (e.g., exatecan) to a carrier and/or a targeting moiety (e.g.,

nanoparticle) that binds to a cancer cell (e.g., binds to a receptor on the surface of a cancer cell) and gets internalized into the cell (e.g., through the endosome and lysosomal compartment). Once internalized, the linkers can be cleaved or degraded to release active cytotoxic drug. Specifically, the protease-cleavable linkers can release their payload under the action of proteases such as cathepsin, trypsin or other proteases in the lysosomal compartment of the cell.

[0095] The cleavable linkers described herein may comprise a structure of Formula (F):



wherein each instance of $[AA]$ is a natural or non-natural amino acid residue; z is an integer of 1 to 5; w is an integer of 1 to 4 (e.g., 2 or 3); and each



denotes a point of attachment, e.g., to a spacer group (e.g., PEG) or another portion of the linker, or to an exatecan molecule. For example, $-[AA]_w-$ may comprise Val-Lys, Val-Cit, Phe-Lys, Trp-Lys, Asp-Lys, Val-Arg, or Val-Ala, and z may be 2, wherein one




denotes an attachment to the oxygen atom of a PEG group, and the other



denotes an attachment to the nitrogen atom of exatecan. For example, $-[AA]_w-$ may comprise Val-Lys.

[0096] The cleavable linkers described herein may comprise a structure of Formula (F-1):



wherein one



denotes a point of attachment to the oxygen atom of a PEG group, and the other



denotes a point of attachment to the nitrogen atom of exatecan.

[0097] The linkers of this disclosure can be prepared from linker precursors that contain reactive groups at one or both ends of the molecule. The reactive groups can be selected to allow conjugation to exatecan or an analog thereof at one end, and also

facilitate conjugation to the nanoparticle at the other end. It is desirable for the payload to contain an amine, a hydroxyl, hydrazone, hydrazide or a sulfhydryl group in order to facilitate conjugation to the linker. For example, exatecan comprises a primary amine group that can facilitate its conjugation to the linker.

[0098] The linker-payload conjugate precursors can be attached to the nanoparticle using any suitable techniques and methods, and many such techniques are well-known in the art. See, e.g., WO 2017/189961, WO 2015/183882, WO 2013/192609, WO 2016/179260 and WO 2018/213851, which describe silica-based core-shell or silica-based core nanoparticles that can be used to prepare targeted nanoparticle-based drug delivery systems. Additionally, linker-payload conjugate precursors, or ligand-linker precursors, can be attached to a nanoparticle using a reaction or method described in Kolb et al. *Angew. Chem. Int. Ed.* (2001) 40:2004-2021.

[0099] The linker-payload conjugate may be attached to the nanoparticle directly or indirectly through a spacer group, such as a spacer group described herein. Suitable spacer groups include, but are not limited to, a divalent linker (e.g., a divalent linker described herein), such as PEG spacer, or an alkylene spacer (e.g., a methylene spacer), which may further comprise a heteroatom or cyclic group (e.g., heterocyclylene group). The linker-payload conjugate can be absorbed into the interstices or pores of the silica shell, or coated onto the silica shell of the nanoparticle, such as a fluorescent nanoparticle (e.g., covalently attached to the surface of the nanoparticle). In other aspects, where the silica shell is not covering all of the surface of the nanoparticle, the linker-payload conjugate can be associated with the fluorescent core, such as by physical absorption or by bonding interaction.

[0100] In some aspects, the linker-payload conjugate may also be associated with the PEG groups that are covalently bonded to the surface of the nanoparticle. For example, the linker-payload conjugate may be attached to the nanoparticle through the PEG. The PEGs can have multiple functional groups for attachment to the nanoparticle and to the linker-payload conjugate.


[0101] In specific aspects of the present disclosure, the linker-payload conjugates (or linker-payload conjugate precursor) may be functionalized with a hydrophilic PEG spacer. The linker-payload conjugate precursor may be functionalized with a hydrophilic PEG spacer and/or suitable terminal group such as, but not limited to, an azide group, to facilitate covalently attaching the linker-payload conjugate (e.g., via the spacer group) to the surface of the nanoparticle, e.g., *via* reaction with a DBCO group on the nanoparticle surface). Other terminal groups can include a nitrile oxide or nitron, e.g., for conjugation via a 3+2 cycloaddition reaction, to a suitable group on the nanoparticle (e.g., a diene moiety).

[0102] The number of PEG groups as spacers that can be present in a functionalized linker-payload conjugate (or precursor thereof) may range from 0 to 20, e.g., from 2 to 20, from 2 to 10, or from 5 to 8, e.g., 5, 6, 7, 8, 9, 10, 11, or 12. In preferred aspects, the number of PEG groups as spacers in a functionalized linker-payload conjugate is 9.

[0103] For example, exatecan can be conjugated to a protease-cleavable linker to form the linker-payload conjugate. This linker-conjugate can be prepared from a precursor functionalized with a PEG spacer that has a terminal reactive group, such as an azide, for further conjugation to the surface of the nanoparticle, e.g., *via* a DBCO group.

[0104] The protease-cleavable linker can be designed to be labile to cathepsin B (Cat-B), an enzyme that is over-expressed in malignant tumors, thereby effecting release of the cytotoxic agent, such as exatecan by a self-immolative process.

[0105] The linker payload conjugate precursor can comprise a structure of Formula (E-1):




wherein y is an integer of 0 to 20, e.g., 5 to 15, e.g., 9.

[0106] The linker and linker-payload conjugates described in the present disclosure have several advantages, ranging from superior serum stability to faster release kinetics mechanism, relative to conventional drug delivery platforms, linkers, or linker-payload conjugates. Also, the ability to pair these linkers with a variety of chemical groups provides the opportunity for the selective release of free payload/drugs, with minimal derivatization, that is a significant advantage.

[0107] In preferred aspects of the present disclosure, the linker in the linker-payload conjugate is a protease-cleavable linker.


[0108] The NDCs of the present disclosure comprising a payload-linker moiety may comprise a structure of Formula (NP-3):



(NP-3), wherein x is an integer of 0 to 10 (e.g., 0, 1, 2, 3, 4, 5, 6, 7, 8, 9, or 10, e.g., 4), and y is an integer of 0 to 20 (e.g., 0, 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, or 20, e.g., 9), and the silicon atom is a part of the nanoparticle (e.g., bonded with the silica shell of a core-shell silica nanoparticle. For example x may be 4, and y may be 9. An NDC disclosed herein may comprise more than one molecule of Formula (NP-3), for example, the nanoparticle may comprise between about 1 and about 80 molecules of Formula (NP-3), e.g., between about 1 and about 60 molecules of Formula (NP-3), between about 1 and about 40 molecules of Formula (NP-3), between about 1 and about 30 molecules of Formula (NP-3), between about 10 and about 30 molecules of Formula (NP-3), between about 15 and about 25 molecules of Formula (NP-3), e.g., about 1, about 2, about 3, about 4, about 5, about 6, about 7, about 8, about 9, about 10, about 11, about 12, about 13, about 14, about 15, about 16, about 17, about 18, about 19, about 20, about 21, about 22, about 23, about 24, about 25, about 26, about 27, about 28, about 29, or about 30 molecules of Formula (NP-3).

[0109] Upon contact with a protease (e.g., within a cancer cell, such as within the lysosome of a cancer cell), an NDC of the present disclosure may undergo cleavage to release free exatecan. The cleavage of an NDC disclosed herein may concomitantly release exatecan, carbon dioxide, and 4-aminobenzyl alcohol from the NDC. For example, the cleavage of an exemplary NDC disclosed herein is provided in Scheme 1

below.



Scheme 1. Exemplary cleavage mechanism of an NDC disclosed herein.

[0110] The NDCs disclosed herein may comprise both a molecule of Formula (NP-2), and a molecule of Formula (NP-3), e.g., each NDC may comprise about 1 and about 20 molecules of Formula (NP-2), and about 1 and about 30 molecules of Formula (NP-3). For example, each NDC may comprise about 10 and about 15 molecules of Formula (NP-2), and about 15 and about 25 molecules of Formula (NP-3). An NDC disclosed herein may comprise an average of 13 molecules of Formula (NP-2), and an average of 21 molecules of Formula (NP-3); an average of 12 molecules of Formula (NP-2), and an average of 25 molecules of Formula (NP-3); an average of 12 molecules of Formula (NP-2), and an average of 20 molecules of Formula (NP-3).

[0111] This disclosure provides compositions and methods directed to a nanoparticle-drug conjugate (NDC) comprising: a nanoparticle; a targeting ligand that binds to folate receptor; and a linker-payload conjugate, wherein the NDC has an average diameter between about 1 nm and about 10 nm. For example, a nanoparticle comprising folic acid as a targeting ligand, and a linker-payload conjugate comprising exatecan conjugated via a protease-cleavable linker, wherein the NDC has an average diameter between about 1 nm and about 10 nm.

[0112] FIG. 1 illustrates a representative nanoparticle-drug conjugate (NDC) that has an average diameter of about 6 nm, comprising a nanoparticle that comprises a silica-based core and a silica shell surrounding at least a portion of the core, polyethylene glycol (PEG) covalently bonded to the surface of the nanoparticle, and a fluorescent compound (Cy5) covalently encapsulated within the core of the nanoparticle, folic acid (FA) as the targeting ligand that can bind to a folate receptor, and a linker-payload conjugate that comprises a protease-cleavable linker-exatecan conjugate. It will be understood that "folic acid" is intended to encompass any amide or ester derivative of

folic acid, e.g., as shown in FIG. 1 where folic acid is covalently attached to the spacer group (PEG) via an amide group.

[0113] The NDC may have an average diameter between about 5 nm to about 8 nm, or between about 6 nm to about 7 nm. The average diameter of NDCs can be measured by any suitable methods, such as, but not limited to, fluorescence correlation spectroscopy (FCS) (see, e.g., FIG. 6) and gel permeation chromatography (GPC) (FIG. 7).


[0114] The NDCs of the present disclosure can comprise nanoparticles that can be functionalized with contrast agents for positron emission tomography (PET), single photon emission computed tomography (SPECT), computerized tomography (CT), magnetic resonance imaging (MRI), and optical imaging (such as fluorescence imaging including near-infrared fluorescence (NIRF) imaging, bio luminescence imaging, or combinations thereof).

[0115] A contrast agent, such as a radionuclide (radiolabel) including, but not limited to ^{89}Zr , ^{64}Cu , ^{68}Ga , ^{86}Y , ^{124}I and ^{177}Lu , may be attached to the nanoparticle. Alternatively, the nanoparticle can be attached to a chelator moiety, for example, DFO, DOTA, TETA and DTPA, that is adapted to bind a radionuclide. Such nanoparticle may be detected by PET, SPECT, CT, MRI, or optical imaging (such as fluorescence imaging including near-infrared fluorescence (NIRF) imaging, bio luminescence imaging, or combinations thereof).

[0116] The radionuclide can additionally serve as a therapeutic agent for creating a multitherapeutic platform. This coupling allows the therapeutic agent to be delivered to the specific cell type through the specific binding between the targeting ligand and the cellular component.

Protease-Cleavable Linker-Payload Conjugates

[0117] A linker-payload conjugate may comprise a compound of Formula **(I)**




or a salt thereof, wherein,

[0118]


⋮

line represents an attachment to the nanoparticle through a spacer group; A is a dipeptide selected from the group consisting of Val-Cit, Phe-Lys, Trp-Lys, Asp-Lys,



Val-Lys, Val-Arg, and Val-Ala, or A is a tetrapeptide selected from the group consisting of Val-Phe-Gly-Sar, Val-Cit-Gly-Sar, Val-Lys-Gly-Sar, Val-Ala-Gly-Sar, Val-Phe-Gly-Pro, Val-Cit-Gly-Pro, Val-Lys-Gly-Pro, Val-Ala-Gly-Pro, Val-Cit-Gly-any natural or unnatural N-alkyl substituted alpha amino acid, Val-Lys-Gly-any natural or unnatural N-alkyl substituted alpha amino acid, Val-Phe-Gly-any natural or unnatural N-alkyl substituted alpha amino acid, Val-Ala-Gly-any natural or unnatural N-alkyl substituted alpha amino acid, Phe-Lys-Gly-any natural or unnatural N-alkyl substituted alpha amino acid, and Trp-Lys-Gly-any natural or unnatural N-alkyl substituted alpha amino acid; Payload is exatecan, and the primary amine group of exatecan is represented by Z; R^1 and R^2 in each occurrence is independently hydrogen, substituted or unsubstituted C_{1-6} alkyl or substituted or unsubstituted C_{1-6} alkoxy, or hydroxyl; R^3 and R^4 in each occurrence is independently hydrogen, halo, substituted or unsubstituted C_{1-6} alkyl, or substituted or unsubstituted C_{1-6} alkoxy; R^5 is selected from the group consisting of hydrogen, substituted or unsubstituted C_{1-6} alkyl; substituted or unsubstituted C_{3-7} cycloalkyl, substituted or unsubstituted aryl, substituted or unsubstituted heteroaryl, and substituted or unsubstituted C_{5-6} heterocycloalkyl; with the proviso that, when A is a dipeptide, R^5 is H; R^a , R^b , and R^c in each occurrence is independently hydrogen or substituted or unsubstituted C_{1-6} alkyl; X is absent, -O-, -CO- or -NR^a-; Y is absent,



or




wherein the carbonyl in




or


is bonded to Z; with the proviso that, when Y is



X is absent and n is 1; when Y is




is absent and n is 0; when Y is




X is absent and n is 0; and/or when X is -CO-, Y is absent and n is 0; X₁ and X₂ are independently -CH- or -N-; X₃ is -CH-; X₄ is -CH-; Z is -NR^c- or -O-; n is 0 or 1; q is 1 to 3.

[0119] In preferred aspects of Formula (I), A is Val-Lys; R¹-R⁵ are each independently hydrogen; X is absent; Y is



wherein the carbonyl in



is bonded to Z; n is 1; X₁, X₂, X₃, and X₄ are each independently -CH-; Z is -NR^c- wherein R^c is hydrogen, and wherein the N is the nitrogen atom present in the exatecan payload.

[0120] In the linker-payload conjugate of Formula (I), the payload may be exatecan, which has a functional group that is bonded to the linker, wherein the functional group is an amine (when exatecan is bonded to the linker, it is a secondary amine, and once released (or prior to conjugation), i.e., as a separate molecular entity, the amine of exatecan is a primary amine).


[0121] *Exemplary Linker-payload Conjugates:* Representative linker-payload conjugates of the present disclosure include, but are not limited to the following substructures, wherein



line represents a direct bond to the nanoparticle or an indirect bond to the nanoparticle through a spacer group. Suitable spacer groups include, but are not limited to a PEG spacer, or an alkylene spacer (e.g., methylene spacer), which may further comprise heteroatoms, or cyclic groups (e.g., heterocyclylene groups). In preferred aspects, the spacer group is a PEG spacer.

[0122] An exemplary linker-payload conjugate of Formula (I) of the present

disclosure includes the following sub-structure:




[0123] *Linkers and Precursors Thereof:* The linkers of this disclosure, and/or their precursors, can contain reactive groups at both ends of the molecule. The reactive groups can be selected to allow conjugation to exatecan or a salt or analog thereof at one end, and also facilitate conjugation to a nanoparticle (e.g., via a spacer group) at the other end. For example, the linker can connect to exatecan *via* a chemically reactive functional group that is a part of the exatecan, such as the primary amine of exatecan (that becomes a secondary amine upon conjugation to the linker).

[0124] The linker can be conjugated to a functionalized polyethylene glycol or a C₅-C₆ alkyl chain *via* a chemically reactive functional group that is a part of the linker such as a primary or secondary amine or carboxyl group.



[0125] *Protease-cleavable Linkers:* Proteases are involved in all stages of cancer disease from tumor cells growth and survival, to angiogenesis and invasions. Therefore, they can be utilized to treat cancer as selective triggers towards activation of linker/payload system. This disclosure relates to linkers that are cleavable by the action of proteases thereby releasing the free payload (e.g., exatecan). Lysosomal proteases such as cathepsin B and serine proteases such as cathepsin A or tripeptidyl-peptidase I have been extensively studied in the context of prodrug development. Proteolytic enzymes such as caspases are also well-known to be utilized as biological triggers for the selective activation of payload or for specific cargo delivery to a target cell such as a cancer cell.

[0126] A linker (or precursor thereof) can comprise a compound of Formula **(I-A)**





wherein: A is a dipeptide selected from the group consisting of Val-Cit, Phe-Lys, Trp-Lys, Asp-Lys, Val-Lys, Val-Arg, and Val-Ala, or A is a tetrapeptide selected from the group consisting of Val-Phe-Gly-Sar, Val-Cit-Gly-Sar, Val-Lys-Gly-Sar, Val-Ala-Gly-Sar, Val-Phe-Gly-Pro, Val-Cit-Gly-Pro, Val-Lys-Gly-Pro, Val-Ala-Gly-Pro, Val-Cit-Gly-any natural or unnatural N-alkyl substituted alpha amino acid, Val-Lys-Gly-any natural or unnatural N-alkyl substituted alpha amino acid, Val-Phe-Gly-any natural or


unnatural N-alkyl substituted alpha amino acid, Val-Ala-Gly-any natural or unnatural N-alkyl substituted alpha amino acid, Phe-Lys-Gly-any natural or unnatural N-alkyl substituted alpha amino acid, and Trp-Lys-Gly-any natural or unnatural N-alkyl substituted alpha amino acid; R^1 and R^2 in each occurrence is independently hydrogen, substituted or unsubstituted C_{1-6} alkyl or substituted or unsubstituted C_{1-6} alkoxy, or hydroxy; R^3 and R^4 in each occurrence is independently hydrogen, halo, substituted or unsubstituted C_{1-6} alkyl or substituted or unsubstituted C_{1-6} alkoxy; R^5 is selected from the group consisting of hydrogen, substituted or unsubstituted C_{1-6} alkyl; substituted or unsubstituted C_{3-7} cycloalkyl, substituted or unsubstituted aryl, substituted or unsubstituted heteroaryl, and substituted or unsubstituted C_{5-6} heterocycloalkyl, with the proviso that, when A is a dipeptide, R^5 is H; $R^{1'}$, $R^{2'}$, $R^{3'}$, $R^{4'}$ and $R^{5'}$ in each occurrence is independently hydrogen, substituted or unsubstituted C_{1-6} alkyl or substituted or unsubstituted C_{1-6} cycloalkyl; X is absent, -O-, -CO- or -NR^a-; Y is absent,




wherein the carbonyl in




is bonded to Zi, with the proviso that, when Y is




X is absent and n is 1; with the proviso that, when Y is




X is absent and n is 0, with the proviso that, when Y is




X is absent and n is 0 or 1; with the proviso that, when X is -CO-, Y is absent and n is 0; X₃ is -CH-; X₄ is -CH-; Z₁ is a functional group selected from the group consisting of halo, hydroxy, -OSO₂-CH₃, -OSO₂CF₃, 4-nitrophenoxy, -COCl, and -COOH; Z₂ is a functional group selected from the group consisting of -NH₂, -NHR^c, and -COOH; or Z₂ is -C(O)-T₁; T₁ is a functionalized polyethylene glycol or a C₅-C₆ alkyl chain that has a terminal group selected from the group consisting of azide,




and



R^a, R^b and R^c in each occurrence is independently hydrogen or substituted or unsubstituted C₁₋₆ alkyl; n is 0 or 1; and q is 1 to 3. In certain aspects of Formula (**I-A**), A is Val-Lys; R¹-R⁵ are each independently hydrogen; X is absent; Y is



wherein the carbonyl in



is bonded to Z; n is 1; X₁, X₂, X₃ and X₄ are each independently -CH-; Z₁ is a functional group selected from the group consisting of halo, hydroxy, -OSO₂-CH₃, -OSO₂CF₃, 4-nitrophenoxy, -COCl, and -COOH; Z₂ is a functional group selected from the group consisting of -NH₂, -NHR^c, and -COOH or Z₂ is -C(O)-T₁, wherein Ti is as defined in Formula (**I-A**).

Pharmaceutical Compositions

[0127] The present disclosure further provides a pharmaceutical composition for treating a disease (e.g., cancer, such as a cancer associated with folate receptor expressing tumor), wherein the composition comprises an effective amount of an NDC described herein.

[0128] In specific aspects of the present disclosure, the pharmaceutical composition comprising the NDCs can be used to treat cancer selected from the group consisting of ovarian cancer, endometrial cancer, fallopian tube cancer, cervical cancer, breast cancer, lung cancer, mesothelioma, uterine cancer, gastrointestinal cancer (e.g., esophageal cancer, colon cancer, rectal cancer, and stomach cancer), pancreatic

cancer, bladder cancer, kidney cancer, liver cancer, head and neck cancer, brain cancer, thyroid cancer, skin cancer, prostate cancer, testicular cancer, acute myeloid leukemia (AML, e.g., pediatric AML), and chronic myelogenous leukemia (CML). The pharmaceutical composition comprising the NDCs may also be used for targeting tumor associated macrophages, e.g., to modify the immune status of a tumor in a subject.

[0129] The pharmaceutical compositions of the present disclosure may comprise a pharmaceutically acceptable excipient, such as a non-toxic carrier, adjuvant, diluent, or vehicle that does not negatively impact the pharmacological activity of the NDCs with which it is formulated. Pharmaceutically acceptable excipients useful in the manufacture of the pharmaceutical compositions of the present disclosure are any of those that are well known in the art of pharmaceutical formulation, and can include inert diluents, dispersing and/or granulating agents, surface active agents and/or emulsifiers, disintegrating agents, binding agents, preservatives, buffering agents, lubricating agents, and/or oils. Pharmaceutically acceptable excipients useful in the manufacture of the pharmaceutical compositions of the present disclosure include, but are not limited to, ion exchangers, alumina, aluminum stearate, lecithin, serum proteins (e.g., human serum albumin), buffer substances (e.g., phosphates), glycine, sorbic acid, potassium sorbate, glyceride mixtures (e.g., mixtures of saturated vegetable fatty acids), water, salts or electrolytes (e.g., protamine sulfate, disodium hydrogen phosphate, potassium hydrogen phosphate, sodium chloride, zinc salts), colloidal silica, magnesium trisilicate, polyvinyl pyrrolidone, cellulose-based substances, polyethylene glycol, sodium carboxymethylcellulose, polyacrylates, waxes, polyethylene-polyoxypropylene-block polymers, polyethylene glycol, and wool fat.

[0130] The pharmaceutical compositions of the present disclosure may be administered orally in the form of a suitable pharmaceutical unit dosage form. The pharmaceutical compositions of the present disclosure may be prepared in many forms that include tablets, hard or soft gelatin capsules, aqueous solutions, suspensions, liposomes, and other slow-release formulations, such as shaped polymeric gels.

[0131] Suitable modes of administration for the NDCs or composition include, but are not limited to, oral, intravenous, rectal, sublingual, mucosal, nasal, ophthalmic, subcutaneous, intramuscular, transdermal, spinal, intrathecal, intra-articular, intra-arterial, sub-arachnoid, bronchial, lymphatic administration, intra-tumoral, and other routes suitable for systemic delivery of active ingredients.

[0132] The present pharmaceutical composition may be administered by any method known in the art, including, without limitation, transdermal (passive via patch, gel, cream, ointment or iontophoretic); intravenous (bolus, infusion); subcutaneous

(infusion, depot); transmucosal (buccal and sublingual, e.g., orodispersible tablets, wafers, film, and effervescent formulations); conjunctival (eyedrops); rectal (suppository, enema)); or intradermal (bolus, infusion, depot). The composition may be delivered topically.

[0133] Oral liquid pharmaceutical compositions may be in the form of, for example, aqueous or oily suspensions, solutions, emulsions, syrups or elixirs, or may be presented as a dry product for constitution with water or other suitable vehicle before use. Such liquid pharmaceutical compositions may contain conventional additives such as suspending agents, emulsifying agents, non-aqueous vehicles (which may include edible oils), or preservatives.

[0134] The pharmaceutical compositions of the present disclosure may also be formulated for parenteral administration (e.g., by injection, for example, bolus injection or continuous infusion) and may be presented in unit dosage form in ampules, pre-filled syringes, infusion containers (e.g., small volume infusion containers), or multi-dose containers, that may contain an added preservative.

[0135] The pharmaceutical compositions may take such forms as suspensions, solutions, or emulsions in oily or aqueous vehicles, and may contain formulating agents such as suspending, stabilizing and/or dispersing agents. Alternatively, the pharmaceutical compositions of the present disclosure may be in powder form, obtained by aseptic isolation of sterile solid or by lyophilization from solution, for constitution with a suitable vehicle, e.g., sterile, pyrogen-free water, before use.

[0136] For topical administration (e.g., to the epidermis), the pharmaceutical compositions may be formulated as an ointment, cream, or lotion, or as the active ingredient of a transdermal patch. Suitable transdermal delivery systems are disclosed, for example, in A. Fisher et al. (U.S. Pat. No. 4,788,603), and R. Bawa et al. (U.S. Pat. Nos. 4,931,279; 4,668,506; and 4,713,224). Ointments and creams may, for example, be formulated with an aqueous or oily base with the addition of suitable thickening and/or gelling agents. Lotions may be formulated with an aqueous or oily base and will in general also contain one or more emulsifying agents, stabilizing agents, dispersing agents, suspending agents, thickening agents, or coloring agents. The pharmaceutical compositions can also be delivered via iontophoresis, e.g., as disclosed in U.S. Pat. Nos. 4,140,122; 4,383,529; or 4,051,842.

[0137] Pharmaceutical compositions suitable for topical administration in the mouth include unit dosage forms such as lozenges comprising a pharmaceutical composition of the present disclosure in a flavored base, such as sucrose and acacia or tragacanth; pastilles comprising the pharmaceutical composition in an inert base such as gelatin and glycerin or sucrose and acacia; mucoadherent gels, and mouthwashes comprising the pharmaceutical composition in a suitable liquid carrier.

[0138] For topical administration to the eye, the pharmaceutical compositions can be administered as drops, gels (S. Chrai et al, U.S. Pat. No. 4,255,415), gums (S. L. Lin et al, U.S. Pat. No. 4, 136, 177) or via a prolonged-release ocular insert (A. S. Michaels, U.S. Pat. No. 3,867,519 and H. M. Haddad et al., U.S. Pat. No. 3,870,791).

[0139] When desired, the above-described pharmaceutical compositions can be adapted to give sustained release of a therapeutic compound employed, e.g., by combination with certain hydrophilic polymer matrices, e.g., comprising natural gels, synthetic polymer gels or mixtures thereof.

[0140] Pharmaceutical compositions suitable for rectal administration wherein the carrier is a solid are most preferably presented as unit dose suppositories. Suitable carriers include cocoa butter and other materials commonly used in the art, and the suppositories may be conveniently formed by admixture of the pharmaceutical composition with the softened or melted carrier(s) followed by chilling and shaping in molds.

[0141] Pharmaceutical compositions suitable for vaginal administration may be presented as pessaries, tampons, creams, gels, pastes, foams, or sprays containing, in addition to the nanoparticles and the therapeutic agent, a carrier. Such carriers are well known in the art.

[0142] For administration by inhalation, the pharmaceutical compositions according to the present disclosure are conveniently delivered from an insufflator, nebulizer or a pressurized pack or other convenient means of delivering an aerosol spray. Pressurized packs may comprise a suitable propellant such as dichlorodifluoromethane, trichlorofluoromethane, dichlorotetrafluoroethane, carbon dioxide or other suitable gas. In the case of a pressurized aerosol, the dosage unit may be determined by providing a valve to deliver a metered amount.

[0143] Alternatively, for administration by inhalation or insufflation, the pharmaceutical compositions of the present disclosure may take the form of a dry powder composition, for example, a powder mix of the pharmaceutical composition and a suitable powder base such as lactose or starch. The powder composition may be presented in unit dosage form in, for example, capsules or cartridges or, e.g., gelatin or blister packs from which the powder may be administered with the aid of an inhalator or insufflator.

[0144] For intra-nasal administration, the pharmaceutical compositions of the present disclosure may be administered via a liquid spray, such as via a plastic bottle atomizer. Typical of these are the MISTOMETER[®] (isoproterenol inhaler- Wintrop) and the MEDIHALER[®] (isoproterenol inhaler-Riker).

[0145] Pharmaceutical compositions of the present disclosure may also contain other adjuvants such as flavorings, colorings, anti-microbial agents, or preservatives.

[0146] It will be further appreciated that the amount of the pharmaceutical compositions suitable for use in treatment will vary not only with the therapeutic agent selected but also with the route of administration, the nature of the condition being treated and the age and condition of the patient and will be ultimately at the discretion of the attendant physician or clinician. For evaluations of these factors, see J. F. Brien et al., *Europ. J. Clin. Pharmacol.*, 14, 133 (1978); and Physicians'Desk Reference, Charles E. Baker, Jr., Pub., Medical Economics Co., Oradell, N.J. (41st ed., 1987).

Administration and Methods of Treatment

[0147] NDCs of the present disclosure can be administered to a subject. The subject can be a mammal, preferably a human. Mammals include, but are not limited to, murines, rats, rabbits, simians, bovines, ovine, swine, canines, feline, farm animals, sport animals, pets, equine, and primates.

[0148] NDCs may be administered to a subject by, but not restricted to, the following routes: oral, intravenous, nasal, subcutaneous, local, intramuscular or transdermal. For example, the NDCs of the present disclosure may be administered to a subject intravenously.

[0149] The methods and compositions of the present disclosure can be used to help a physician or surgeon to identify and characterize areas of disease, such as cancers, including, but not restricted to, cancers that overexpress FR, to distinguish diseased and normal tissue, such as detecting tumor margins that are difficult to detect using an ordinary operating microscope, e.g., in brain surgery, to help dictate a therapeutic or surgical intervention, e.g., by determining whether a lesion is cancerous and should be removed or non-cancerous and left alone, or in surgically staging a disease.

[0150] The methods and compositions of the present disclosure may be used, but are not limited to, metastatic disease detection, treatment response monitoring, and targeted delivery of payload, including by passing the blood-brain barrier.

[0151] The methods and compositions of the present disclosure can also be used in the detection, characterization and/or determination of the localization of a disease, including early disease, the severity of a disease or a disease-associated condition, the staging of a disease, and/or monitoring a disease. The presence, absence, or level of an emitted signal can be indicative of a disease state.

[0152] The methods and compositions of the present disclosure can also be used to monitor and/or guide various therapeutic interventions, such as surgical and catheter-based procedures, and monitoring drug therapy, including cell based therapies. The methods of the present disclosure can also be used in prognosis of a disease or disease condition. Cellular subpopulations residing within or marginating the disease site, such as stem-like cells ("cancer stem cells") and/or inflammatory/phagocytic cells may be identified and characterized using the methods and compositions of the present disclosure.

[0153] With respect to each of the foregoing, examples of such disease or disease conditions that can be detected or monitored (before, during or after therapy) include cancer (for example, melanoma, thyroid, colorectal, ovarian, lung, breast, prostate, cervical, skin, brain, gastrointestinal, mouth, kidney, esophageal, bone cancer), that can be used to identify subjects that have an increased susceptibility for developing cancer and/or malignancies, i.e., they are predisposed to develop cancer and/or malignancies, inflammation (for example, inflammatory conditions induced by the presence of cancerous lesions), cardiovascular disease (for example, atherosclerosis and inflammatory conditions of blood vessels, ischemia, stroke, thrombosis), dermatologic disease (for example, Kaposi's Sarcoma, psoriasis), ophthalmic disease (for example, macular degeneration, diabetic retinopathy), infectious disease (for example, bacterial, viral, fungal and parasitic infections, including Acquired Immunodeficiency Syndrome (AIDS)), immunologic disease (for example, an autoimmune disorder, lymphoma, multiple sclerosis, rheumatoid arthritis, diabetes mellitus), central nervous system disease (for example, a neurodegenerative disease, such as Parkinson's disease or Alzheimer's disease), inherited diseases, metabolic diseases, environmental diseases (for example, lead, mercury and radioactive poisoning, skin cancer), bone-related disease (for example, osteoporosis, primary and metastatic bone tumors, osteoarthritis) and a neurodegenerative disease.

[0154] The methods and compositions of the present disclosure, therefore, can be used, for example, to determine the presence and/or localization of tumor and/or co-resident stem-like cells ("cancer stem cells"), the presence and/or localization of inflammatory cells, including the presence of activated macrophages, for instance in peritumoral regions, the presence and in localization of vascular disease including areas at risk for acute occlusion (i.e., vulnerable plaques) in coronary and peripheral arteries, regions of expanding aneurysms, unstable plaque in carotid arteries, and ischemic areas. The methods and compositions of the present disclosure can also be used in identification and evaluation of cell death, injury, apoptosis, necrosis, hypoxia and angiogenesis (PCT/US2006/049222).

[0155] The methods of the present disclosure comprise administering to a subject in need thereof an effective amount of an NDC described herein. For example, the NDC

can be administered to the subject in need thereof intravenously. An "effective amount" is an amount of the NDC that elicits a desired biological or medicinal response under the conditions of administration, such as an amount that reduces the signs and/or symptoms of a disease or disorder being treated, e.g., reduces tumor size or tumor burden. The actual amount administered can be determined by an ordinarily skilled clinician based upon, for example, the subject's age, weight, sex, general health and tolerance to drugs, severity of disease, dosage form selected, route of administration, and other factors.

[0156] In specific aspects of the method, the subject has a cancer selected from the group consisting of ovarian cancer, endometrial cancer, fallopian tube cancer, cervical cancer, breast cancer, lung cancer, mesothelioma, uterine cancer, gastrointestinal cancer (e.g., esophageal cancer, colon cancer, rectal cancer, and stomach cancer), pancreatic cancer, bladder cancer, kidney cancer, liver cancer, head and neck cancer, brain cancer, thyroid cancer, skin cancer, prostate cancer, testicular cancer, acute myeloid leukemia (AML, e.g., pediatric AML), and chronic myelogenous leukemia (CML).

[0157] The present disclosure also includes use of NDCs for treating a folate receptor expressing tumor. For example, the use of NDC may comprise administration to the subject in need thereof intravenously.

[0158] The present disclosure also relates to the use of NDCs in a subject with cancer selected from the group consisting of ovarian cancer, endometrial cancer, fallopian tube cancer, cervical cancer, breast cancer, lung cancer, mesothelioma, uterine cancer, gastrointestinal cancer (e.g., esophageal cancer, colon cancer, rectal cancer, and stomach cancer), pancreatic cancer, bladder cancer, kidney cancer, liver cancer, head and neck cancer, brain cancer, thyroid cancer, skin cancer, prostate cancer, testicular cancer, acute myeloid leukemia (AML, e.g., pediatric AML), and chronic myelogenous leukemia (CML).

[0159] The NDCs of the present disclosure may also be used in the manufacture of a medicament for treating a folate receptor expressing tumor, wherein the NDC is administered to the subject in need thereof intravenously and wherein the subject has a cancer selected from the group consisting of ovarian cancer, endometrial cancer, fallopian tube cancer, cervical cancer, breast cancer, lung cancer, mesothelioma, uterine cancer, gastrointestinal cancer (e.g., esophageal cancer, colon cancer, rectal cancer, and stomach cancer), pancreatic cancer, bladder cancer, kidney cancer, liver cancer, head and neck cancer, brain cancer, thyroid cancer, skin cancer, prostate cancer, testicular cancer, acute myeloid leukemia (AML, e.g., pediatric AML), and chronic myelogenous leukemia (CML).

[0160] The compositions and methods disclosed herein can include compositions and

methods that include administering a NDC as disclosed herein in combination with one or more additional anti-cancer agents. In such circumstances the NDC can be administered before, substantially concurrently with, or after the additional agent or agents. Suitable additional agents, include, for example chemotherapeutic agents such as mechlorethamine, cyclophosphamide, melphalan, chlorambucil, ifosfamide, busulfan, N-nitroso-N-methylurea, carmustine, lomustine, semustine, fotemustine, streptozotocin, dacarbazine, mitozolomide, temozolomide, thiotepa, mitomycin, diaziquone, cisplatin, carboplatin, oxaliplatin, procarbazine, hexamethylmelamine, methotrexate, pemetrexed, fluorouracil (e.g. 5-fluorouracil), capecitabine, cytarabine, gemcitabine, decitabine, azacitidine, fludarabine, nelarabine, cladribine, clofarabine, pentostatin, thioguanine, mercaptopurine, vincristine, vinblastine, vinorelbine, vindesine, vinflunine, paclitaxel, docetaxel, irinotecan, topotecan, camptothecin, etoposide, mitoxantrone, teniposide, novobiocin, merbarone, doxorubicin, daunorubicin, epirubicin, idarubicin, pirarubicin, aclarubicin, mitomycin C, actinomycin, bleomycin, bisantrene, gemcitabine, cytarabine, and the like. Other anti-cancer agents that can be used with a NDC in the compositions and methods disclosed herein include, immune check point inhibitors (e.g., anti-PD1, anti-PDL1, anti-CTLA4 antibodies), hormone receptor antagonists, other chemotherapeutic conjugates (e.g., in the form of antibody-drug conjugates, nanoparticle drug conjugates, and the like), and the like.

[0161] The terminology used in the description of the invention herein is for the purpose of describing particular embodiments only and is not intended to be limiting of the invention. As used in the description of the embodiments of the invention and the appended claims, the singular forms of "a", "an" and "the" are intended to include the plural forms as well, unless the context clearly indicates otherwise. Also, as used herein, "and/or" refers to and encompasses any and all possible combinations of one or more of the associated listed items.

[0162] The term "about," when referring to a value means $\pm 20\%$, or ± 10 . Further, the term "about" when used in connection with one or more numbers or numerical ranges, should be understood to refer to all such numbers, including all numbers in a range and modifies that range by extending the boundaries above and below the numerical values set forth. The recitation of numerical ranges by endpoints includes all numbers, e.g., whole integers, including fractions thereof, subsumed within that range (for example, the recitation of 1 to 5 includes 1, 2, 3, 4, and 5, as well as fractions thereof, e.g., 1.5, 2.25, 3.75, 4.1, and the like) and any range within that range.

[0163] Throughout this specification and the claims, the terms "comprise," "comprises," and "comprising" are used in a non-exclusive sense, except where the context requires otherwise. Likewise, the term "include" and its grammatical variants

are intended to be non-limiting, such that recitation of items in a list is not to the exclusion of other like items that can be substituted or added to the listed items.

[0164] Although specific terms are employed herein, they are used in a generic and descriptive sense only and not for purposes of limitation. Unless otherwise defined, all technical and scientific terms used herein have the same meaning as commonly understood by one of ordinary skill in the art to which this presently described subject matter belongs.

[0165] It will be understood that in the detailed description and appended claims, the abbreviations and nomenclature employed are those which are standard in amino acid and peptide chemistry.

ABBREVIATIONS

[0166] The abbreviations used in this disclosure, unless otherwise indicated are as follows:

Fmoc:

Fluorenylmethoxycarbonyl

MeOH:

Methanol

Cit-OH:

L-Citrulline

DCM:

Dichloromethane

EEDQ:

2-Ethoxy-1-(ethoxycarbonyl)-1,2-dihydroquinoline

THF:

Tetrahydrofuran

NMR:

Nuclear Magnetic Resonance

DMSO:

Dimethyl sulfoxide

LCMS:

Liquid Chromatography-Mass Spectrometry

TEA:

Triethylamine

HATU:

(1-[Bis(dimethylamino)methylene]-1H-1,2,3-triazolo[4,5-b]pyridinium 3-oxide hexafluorophosphate

DMF:

Dimethylformamide

DIPEA:

N,N-Diisopropylethylamine

TMSCN:

Trimethylsilyl cyanide

RP HPLC:

Reverse Phase High-Pressure Liquid Chromatography

SFC:

Supercritical fluid chromatography

CAN:

Acetonitrile

NMP:

N-Methyl pyrrolidone

r.t:

Room Temperature

TEA:

Triethylamine

TFA:

Trifluoroacetic acid

MTBE:

Methyl tert-butyl ether

EtOAC:

Ethyl acetate

PyBOP:

(Benzotriazole-1-yl-oxytripyrrolidinenophosphoniumhexafluorophosphate)

DEFINITIONS

[0167] As used herein, the term "alkyl" refers to monovalent aliphatic hydrocarbon group that may comprise 1 to 18 carbon atoms, such as 1 to about 12 carbon atoms, or 1 to about 6 carbon atoms ("C₁₋₁₈ alkyl"). An alkyl group can be straight chain, branched chain, monocyclic moiety or polycyclic moiety or combinations thereof. Examples of alkyl groups include methyl, ethyl, propyl, isopropyl, butyl, *iso*-butyl, *sec*-butyl, *tert*-butyl, pentyl, hexyl, cyclopropyl, cyclobutyl, cyclopentyl, cyclohexyl, norbornyl, and the like. Each instance of an alkyl group may be independently optionally substituted, i.e., unsubstituted (an "unsubstituted alkyl") or substituted (a "substituted alkyl") with one or more substituents e.g., for instance from 1 to 5 substituents, 1 to 3 substituents, or 1 substituent.

[0168] As used herein, the term "alkenyl" refers to a monovalent straight-chain or branched hydrocarbon group having from 2 to 18 carbon atoms, one or more carbon-carbon double bonds, and no triple bonds ("C₂₋₁₈ alkenyl"). An alkenyl group may have 2 to 8 carbon atoms, 2 to 6 carbon atoms, 2 to 5 carbon atoms, 2 to 4 carbon atoms, or 2 to 3 carbon atoms. The one or more carbon-carbon double bonds can be internal

(such as in 2-butenyl) or terminal (such as in 1-butenyl). Examples of alkenyl groups include ethenyl, 1-propenyl, 2-propenyl, 1-butenyl, 2-butenyl, butadienyl, pentenyl, pentadienyl, hexenyl, heptenyl, octenyl, octatrienyl, and the like. Each instance of an alkenyl group may be independently optionally substituted, i.e., unsubstituted (an "unsubstituted alkenyl") or substituted (a "substituted alkenyl") with one or more substituents e.g., for instance from 1 to 5 substituents, 1 to 3 substituents, or 1 substituent.

[0169] As used herein, the term "alkynyl" refers to a monovalent straight-chain or branched hydrocarbon group having from 2 to 18 carbon atoms, one or more carbon-carbon triple bonds ("C₂₋₁₈ alkynyl"). The alkynyl group may have 2 to 8 carbon atoms, 2 to 6 carbon atoms, 2 to 5 carbon atoms, 2 to 4 carbon atoms, or 2 to 3 carbon atoms. The one or more carbon-carbon triple bonds can be internal (such as in 2-butyne) or terminal (such as in 1-butyne). Examples of alkynyl groups include ethynyl, 1-propynyl, 2-propynyl, 1-butyne, 2-butyne, and the like. Each instance of an alkynyl group may be independently optionally substituted, i.e., unsubstituted (an "unsubstituted alkynyl") or substituted (a "substituted alkynyl") with one or more substituents, e.g., for instance from 1 to 5 substituents, 1 to 3 substituents, or 1 substituent.

[0170] As used herein, the term "heteroalkyl" refers to a non-cyclic stable straight or branched chain, or combinations thereof, including at least one carbon atom and at least one heteroatom selected from the group consisting of O, N, P, Si, and S, and wherein the nitrogen and sulfur atoms may optionally be oxidized, and the nitrogen heteroatom may optionally be quaternized. The heteroatom(s) O, N, P, S, and Si may be placed at any position of the heteroalkyl group.

[0171] The terms "alkylene," "alkenylene," "alkynylene," or "heteroalkylene," alone or as part of another substituent, mean, unless otherwise stated, a divalent radical derived from an alkyl, alkenyl, alkynyl, or heteroalkyl, respectively. The term "alkenylene," by itself or as part of another substituent, means, unless otherwise stated, a divalent radical derived from an alkene. An alkylene, alkenylene, alkynylene, or heteroalkylene group may be described as, e.g., a C₁₋₆-membered alkylene, C₁₋₆-membered alkenylene, C₁₋₆-membered alkynylene, or C₁₋₆-membered heteroalkylene, wherein the term "membered" refers to the non-hydrogen atoms within the moiety. In the case of heteroalkylene groups, heteroatoms can also occupy either or both of the chain termini (e.g., alkyleneoxy, alkyleneedioxy, alkyleneamino, alkylene-diamino, and the like). Still further, for alkylene and heteroalkylene linking groups, no orientation of the linking group is implied by the direction in which the formula of the linking group is written. For example, the formula -C(O)₂R'- may represent both -C(O)₂R'- and -R'C(O)₂-. Each instance of an alkylene, alkenylene, alkynylene, or heteroalkylene group may be independently optionally substituted, i.e., unsubstituted (an

"unsubstituted alkylene") or substituted (a "substituted heteroalkylene") with one or more substituents.

[0172] As used herein, the terms "substituted alkyl," "substituted alkenyl," "substituted alkynyl," "substituted heteroalkyl," "substituted heteroalkenyl," "substituted heteroalkynyl," "substituted cycloalkyl," "substituted heterocyclyl," "substituted aryl," and "substituted heteroaryl" refer to alkyl, alkenyl, alkynyl, heteroalkyl, heteroalkenyl, heteroalkynyl, cycloalkyl, heterocyclyl, aryl, and heteroaryl moieties, respectively, having substituents replacing one or more hydrogen atoms on one or more carbons or heteroatoms of the moiety. Such substituents can include, for example, alkyl, alkenyl, alkynyl, halogen, hydroxyl, alkylcarbonyloxy, arylcarbonyloxy, alkoxycarbonyloxy, aryloxy carbonyloxy, carboxylate, alkylcarbonyl, arylcarbonyl, alkoxycarbonyl, aminocarbonyl, alkylaminocarbonyl, dialkylaminocarbonyl, alkylthiocarbonyl, alkoxyl, phosphate, phosphonate, phosphinato, amino (including alkylamino, dialkylamino, arylamino, diarylamino and alkylarylamino), acylamino (including alkylcarbonylamino, arylcarbonylamino, carbamoyl and ureido), amidino, imino, sulfhydryl, alkylthio, arylthio, thiocarboxylate, sulfates, alkylsulfinyl, sulfonate, sulfamoyl, sulfonamido, nitro, trifluoromethyl, cyano, azido, heterocyclyl, alkylaryl, or an aromatic or heteroaromatic moiety. Cycloalkyls can be further substituted, e.g., with the substituents described above.

[0173] As used herein, the term "alkoxy" refers to a group of formula -O-alkyl. The term "alkoxy" or "alkoxyl" includes substituted and unsubstituted alkyl, alkenyl and alkynyl groups covalently linked to an oxygen atom. Examples of alkoxy groups or alkoxyl radicals include, but are not limited to, methoxy, ethoxy, isopropoxy, propoxy, butoxy and pentoxy groups. Examples of substituted alkoxy groups include halogenated alkoxy groups. The alkoxy groups can be substituted with groups such as alkenyl, alkynyl, halogen, hydroxyl, alkylcarbonyloxy, arylcarbonyloxy, alkoxycarbonyloxy, aryloxy carbonyloxy, carboxylate, alkylcarbonyl, arylcarbonyl, alkoxycarbonyl, aminocarbonyl, alkylaminocarbonyl, dialkylaminocarbonyl, alkylthiocarbonyl, alkoxyl, phosphate, phosphonate, phosphinato, amino (including alkylamino, dialkylamino, arylamino, diarylamino, and alkylarylamino), acylamino (including alkylcarbonylamino, arylcarbonylamino, carbamoyl and ureido), amidino, imino, sulfhydryl, alkylthio, arylthio, thiocarboxylate, sulfates, alkylsulfinyl, sulfonate, sulfamoyl, sulfonamido, nitro, trifluoromethyl, cyano, azido, heterocyclyl, alkylaryl, or an aromatic or heteroaromatic moieties. Examples of halogen substituted alkoxy groups include, but are not limited to, fluoromethoxy, difluoromethoxy, trifluoromethoxy, chloromethoxy, dichloromethoxy and trichloromethoxy.

[0174] As used herein, the term "aryl," refers to stable aromatic ring system, that may be monocyclic or polycyclic, of which all the ring atoms are carbon, and which may be substituted or unsubstituted. The aromatic ring system may have, for example, 3-7 ring atoms. Examples include phenyl, benzyl, naphthyl, anthracyl, and

the like. Each instance of an aryl group may be independently optionally substituted, i.e., unsubstituted (an "unsubstituted aryl") or substituted (a "substituted aryl") with one or more substituents.

[0175] As used herein, the term "heteroaryl" refers to an aryl group that includes one or more ring heteroatoms. For example, a heteroaryl can include a stable 5-, 6-, or 7-membered monocyclic or 7-, 8-, or 9-membered bicyclic aromatic heterocyclic ring which consists of carbon atoms and one or more heteroatoms, independently selected from the group consisting of nitrogen, oxygen and sulfur. The nitrogen atom may be substituted or unsubstituted (e.g., N or NR₄ wherein R₄ is H or other substituents, as defined). Examples of heteroaryl groups include pyrrole, furan, indole, thiophene, thiazole, isothiazole, imidazole, triazole, tetrazole, pyrazole, oxazole, isoxazole, pyridine, pyrazine, pyridazine, pyrimidine, and the like.

[0176] As used herein, the terms "cycloalkylene," "heterocyclylene," "arylene," and "heteroarylene," alone or as part of another substituent, mean a divalent radical derived from a cycloalkyl, heterocyclyl, aryl, and heteroaryl, respectively. Each instance of a cycloalkylene, heterocyclylene, arylene, or heteroarylene may be independently optionally substituted, i.e., unsubstituted (an "unsubstituted arylene") or substituted (a "substituted heteroarylene") with one or more substituents.


[0177] As used herein, the term "cycloalkyl", is intended to include non-aromatic cyclic hydrocarbon rings, such as hydrocarbon rings having from three to eight carbon atoms in their ring structure. Cycloalkyl can include cyclobutyl, cyclopropyl, cyclopentyl, cyclohexyl and the like. The cycloalkyl group can be either monocyclic ("monocyclic cycloalkyl") or contain a fused, bridged or spiro ring system such as a bicyclic system ("bicyclic cycloalkyl") and can be saturated or can be partially unsaturated. "Cycloalkyl" also includes ring systems wherein the cycloalkyl ring, as defined above, is fused with one or more aryl groups wherein the point of attachment is on the cycloalkyl ring, and in such instances, the number of carbons continue to designate the number of carbons in the cycloalkyl ring system. Each instance of a cycloalkyl group may be independently optionally substituted, i.e., unsubstituted (an "unsubstituted cycloalkyl") or substituted (a "substituted cycloalkyl") with one or more substituents.

[0178] As used herein, the term "heterocyclyl" refers to a monovalent cyclic molecular structure comprising atoms of at least two different elements in the ring or rings (i.e., a radical of a heterocyclic ring). Additional reference is made to: Oxford Dictionary of Biochemistry and Molecular Biology, Oxford University Press, Oxford, 1997 as evidence that heterocyclic ring is a term well-established in field of organic chemistry.


[0179] As used herein, the term "dipeptide" refers to a peptide that is composed of

two amino-acid residues, that may be denoted herein as $-A_1-A_2-$. For example, dipeptides employed in the synthesis of protease-cleavable linker-payload conjugates of the present disclosure may be selected from the group consisting of Val-Cit, Phe-Lys, Trp-Lys, Asp-Lys, Val-Lys, and Val-Ala.

[0180] As used herein, the term "functionalized polyethylene glycol" refers to the polyethylene glycol comprising a functional group. For example, a functionalized polyethylene glycol may be polyethylene glycol functionalized with a terminal group selected from the group consisting of azide,




and




wherein R^{1'}, R^{2'}, R^{3'}, R^{4'} and R^{5'} in each occurrence is independently hydrogen, substituted or unsubstituted C₁₋₆ alkyl or substituted or unsubstituted C₁₋₆ cycloalkyl. In preferred aspects, R^{1'}, R^{2'}, R^{3'}, R^{4'} and R^{5'} in each occurrence is hydrogen. In preferred aspects, R^{1'}, R^{2'}, R^{3'}, R^{4'} and R^{5'} in each occurrence is methyl.


[0181] In some aspects of the present disclosure, the term "functionalized polyethylene glycol" refers to, but is not limited to the following structures.



and




[0182] As used herein, Ti may refer to a functionalized polyethylene glycol or a C₅-C₆ alkyl chain that has a terminal group selected from the group consisting of azide,




wherein R^{1'}, R^{2'}, R^{3'}, R^{4'} and R^{5'} in each occurrence is independently hydrogen, substituted or unsubstituted C₁₋₆ alkyl or substituted or unsubstituted C₁₋₆ cycloalkyl. In preferred aspects of T¹, R^{1'}, R^{2'}, R^{3'}, R^{4'} and R^{5'} in each occurrence is hydrogen. In

preferred aspects of T^1 , $R^{1'}$, $R^{2'}$, $R^{3'}$, $R^{4'}$ and $R^{5'}$ in each occurrence is methyl. In preferred aspects, T_i is a functionalized polyethylene glycol that has an azide terminal group. In preferred aspects, T_1 is a C_5 - C_6 alkyl chain that has an azide terminal group. The repeat unit ($-O-CH_2-CH_2-$) of polyethylene glycol (PEG) can range from 5-20 units, preferably 5-15 units and more preferably 6-12.

[0183] As used herein, T_1 may refer to a C_5 - C_6 alkyl chain that has a terminal group selected from the group consisting of azide,



and



wherein $R^{1'}$, $R^{2'}$, $R^{3'}$, $R^{4'}$ and $R^{5'}$ in each occurrence is independently hydrogen, substituted or unsubstituted C_{1-6} alkyl or substituted or unsubstituted C_{1-6} cycloalkyl. In preferred aspects, $R^{1'}$, $R^{2'}$, $R^{3'}$, $R^{4'}$ and $R^{5'}$ in each occurrence is hydrogen. In preferred aspects, $R^{1'}$, $R^{2'}$, $R^{3'}$, $R^{4'}$ and $R^{5'}$ in each occurrence is methyl.

[0184] Monofunctionalized azide-terminated PEG and monofunctionalized azide-terminated C_5 - C_6 alkyl chain can be made from PEG using known procedures and suitable reagents, such as those disclosed in the Schemes provided herein.

[0185] As used herein, the term "halo" or "halogen" refers to F, Cl, Br, or I.

[0186] An aryl or heteroaryl group described herein can be substituted at one or more ring positions with such substituents as described above, for example, alkyl, alkenyl, alkynyl, halogen, hydroxyl, alkoxy, alkylcarbonyloxy, arylcarbonyloxy, alkoxycarbonyloxy, aryloxy, carboxylate, alkylcarbonyl, alkylaminocarbonyl, aralkylaminocarbonyl, alkenylaminocarbonyl, alkylcarbonyl, arylcarbonyl, aralkylcarbonyl, alkenylcarbonyl, alkoxycarbonyl, aminocarbonyl, alkylthiocarbonyl, phosphate, phosphonate, phosphinato, amino (including alkylamino, dialkylamino, arylamino, diarylamino and alkylaryl amino), acylamino (including alkylcarbonylamino, arylcarbonylamino, carbamoyl and ureido), amidino, imino, sulfhydryl, alkylthio, arylthio, thiocarboxylate, sulfates, alkylsulfinyl, sulfonate, sulfamoyl, sulfonamido, nitro, trifluoromethyl, cyano, azido, heterocyclyl, alkylaryl, or an aromatic or heteroaromatic moiety.

[0187] As used herein, the term "hydroxy" refers to a group of formula $-OH$.

[0188] As used herein, the term "hydroxyl" refers to a hydroxyl radical ($\cdot OH$).

[0189] As used herein, the phrase "optionally substituted" means unsubstituted or substituted. In general, the term "substituted" means that at least one hydrogen present on a group (e.g., a carbon or nitrogen atom) is replaced with a permissible substituent, e.g., a substituent which upon substitution results in a stable compound. The term "substituted" can include substitution with all permissible substituents of organic compounds, such as any of the substituents described herein that result in the formation of a stable compound. For purposes of the present disclosure, heteroatoms such as nitrogen may have hydrogen substituents and/or any suitable substituent as described herein which satisfy the valencies of the heteroatoms and results in the formation of a stable moiety.

[0190] As used herein, the term "tetrapeptide" refers to a peptide that is composed of four amino-acid residues, that may be denoted herein as $-A_1-A_2-A_3-A_4-$. Tetrapeptides employed in the synthesis of protease-cleavable linker-payload conjugates of the present disclosure is selected from the group consisting of Val-Phe-Gly-Sar, Val-Cit-Gly-Sar, Val-Lys-Gly-Sar, Val-Ala-Gly-Sar, Val-Phe-Gly-Pro, Val-Cit-Gly-Pro, Val-Lys-Gly-Pro, Val-Ala-Gly-Pro, Val-Cit-Gly-any natural or unnatural N-alkyl substituted alpha amino acid, Val-Lys-Gly-any natural or unnatural N-alkyl substituted alpha amino acid, Val-Phe-Gly-any natural or unnatural N-alkyl substituted alpha amino acid, Val-Ala-Gly-any natural or unnatural N-alkyl substituted alpha amino acid, Phe-Lys-Gly-any natural or unnatural N-alkyl substituted alpha amino acid, and Trp-Lys-Gly-any natural or unnatural N-alkyl substituted alpha amino acid.

[0191] Furthermore, it will be appreciated by one of ordinary skill in the art that the synthetic methods, as described herein, utilize a variety of protecting groups. As used herein, the term "protecting group" refers to a particular functional moiety, e.g., O, S, or N, that is temporarily blocked so that a reaction can be carried out selectively at another reactive site in a multifunctional compound. Protecting groups may be introduced and removed at appropriate stages during the synthesis of a compound using methods that are known to one of ordinary skill in the art. The protecting groups are applied according to standard methods of organic synthesis as described in the literature (Theodora W. Greene and Peter G. M. Wuts (2007) *Protecting Groups in Organic Synthesis*, 4th edition, John Wiley and Sons).

[0192] Exemplary protecting groups include, but are not limited to, oxygen, sulfur, nitrogen and carbon protecting groups. For example, oxygen protecting groups include, but are not limited to, methyl ethers, substituted methyl ethers (e.g., MOM (methoxymethyl ether), MTM (methylthiomethyl ether), BOM (benzyloxymethyl ether), PMBM (pimethoxybenzyloxymethyl ether), optionally substituted ethyl ethers, optionally substituted benzyl ethers, silyl ethers (e.g., TMS (trimethylsilyl ether), TES (triethylsilyl ether), TIPS (triisopropylsilyl ether), TBDMS (t-butyldimethylsilyl ether), tribenzyl silyl ether, TBDPS (t-butyldiphenyl silyl ether), esters (e.g., formate,

acetate, benzoate (Bz), trifluoroacetate, dichloroacetate) carbonates, cyclic acetals and ketals. In addition, nitrogen protecting groups include, but are not limited to, carbamates (including methyl, ethyl and substituted ethyl carbamates (e.g., Troc), amides, cyclic imide derivatives, N-Alkyl and N-Aryl amines, imine derivatives, and enamine derivatives, etc. Amino protecting groups include, but are not limited to fluorenylmethyloxycarbonyl (Fmoc), tert-butyloxycarbonyl (Boc), carboxybenzyl (Cbz), acetamide, trifluoroacetamide, etc. Certain other exemplary protecting groups are detailed herein, however, it will be appreciated that the present disclosure is not intended to be limited to these protecting groups; rather, a variety of additional equivalent protecting groups may be utilized according to methods known to one skilled in the art.

[0193] Throughout this disclosure, a nanoparticle-drug-conjugate (NDC) may sometimes be referred to as a CDC (C'Dot-drug-conjugate), e.g., a FA-CDC.

[0194] The following examples are provided to further illustrate the embodiments of the present invention but are not intended to limit the scope of the invention. While they are typical of those that might be used, other procedures, methodologies, or techniques known to those skilled in the art may alternatively be used.

EXAMPLES

[0195] In order that the invention described herein may be more fully understood, the following examples are set forth. These examples are offered to illustrate the nanoparticle drug conjugates, methods of use, and methods of making, and are not to be construed in any way as limiting their scope.

[0196] The compounds provided herein can be prepared from readily available starting materials using modifications to the specific synthesis protocols set forth below that would be well known to those of skill in the art. It will be appreciated that where typical or preferred process conditions (i.e., reaction temperatures, times, mole ratios of reactants, solvents, pressures, etc.) are given, other process conditions can also be used unless otherwise stated. Optimum reaction conditions may vary with the particular reactants or solvents used, but such conditions can be determined by those skilled in the art by routine optimization procedures.

[0197] Additionally, as will be apparent to those skilled in the art, conventional protecting groups may be necessary to prevent certain functional groups from undergoing undesired reactions. The choice of suitable protecting group for a particular functional group as well as suitable conditions for protection and deprotection are well known in the art. For example, numerous protecting groups, and their introduction and removal, are described in Greene et al. Protecting Groups in

Organic Synthesis, Second Edition, Wiley, New York, 1991, and references cited therein.

General Methods

[0198] Methods useful for making the compounds discussed herein are set forth in the following Examples and are generalized here. One of skill in the art will recognize that these Examples can be adapted to prepare the linker-payload conjugates, linkers and payloads and their pharmaceutically accepted salts thereof according to the present disclosure. In the reactions described, reactive functional groups, such as hydroxy, amino, imino, thio or carboxy groups, may be protected wherever desired, e.g., to avoid unwanted reactions. Conventional protecting groups may also be used in accordance with standard practice and techniques of synthesis. The materials needed to synthesize the novel linkers bearing payloads such as exatecan were obtained commercially, and their corresponding analogs are prepared as disclosed in the following examples.

[0199] Reagents were purchased from commercial suppliers (Combi-Blocks/SIGMA-ALDRICH) and used without further purification. All non-aqueous reactions were run in flame-dried glassware under a positive pressure of argon. Anhydrous solvents were purchased from commercial suppliers (RANKEM). All the amino acids such as Cit, Val, Phe, Lys, Trp, Asp are naturally occurring amino acids with S-configuration. In several examples, tetrapeptide and unnatural amino acids can also be used. Flash chromatography was performed on 230-400 mesh silica gel with the indicated solvent systems. Proton Nuclear magnetic resonance spectra were recorded on Bruker Spectrometer at 400MHZ using DMSO as solvent. Peak positions are given in parts per million downfield from tetramethylsilane as the internal standard. J values are expressed in hertz. Mass analyses were performed on (Agilent/Shimadzu) spectrometer using electrospray (ES) technique. HPLC analyses were performed on (Agilent/Waters), PDA-UV detector equipped with a Gemini C-18 (1000x 4.6 mm; 5u) and all compounds tested were determined to be >95% pure using this method. As can be seen in many protease-cleavable linker-payload conjugates, two peaks were isolated at the end of the reaction. The Peak-A (or Peak-1) is the desired compound with the stereochemistry as shown.

[0200] Compounds prepared according to the procedures described herein may be isolated by preparative HPLC methods. Representative HPLC conditions and methods are provided below:

Agilent UPLC-MS; Column: Column-YMC Triart C18 (2.1x33mm, 3u)
Gradient Conditions: Flow rate: 1.0 ml/min; column temperature: 50 °C;
Solvent A: 0.01% HCOOH in water and Solvent B: 0.01% HCOOH in CH₃CN;
Mobile phase: 95% [0.01% HCOOH in water] and 5% [0.01% HCOOH in CH₃CN] held for 0.50 min, then to 1% [0.01% HCOOH in water] and 99%

[0.01% HCOOH in CH₃CN] in 3.00 min, held this conditions up to 4.00 min and finally back to initial condition in 4.10 min and held for 4.50 min (Table 1).

Table 1: HPLC Gradient Conditions.


TIME	MODULE	%A	% B
0.00	Pumps	95	5
0.50	Pumps	95	5
3.00	Pumps	1	99
4.00	Pumps	1	99
4.10	Pumps	95	5
4.50	Pumps	95	5

Example 1: Synthesis of Exatecan-Linker Conjugate Precursors

[0201] Exatecan-linker conjugate precursors suitable for preparing an NDC of the present disclosure can be synthesized according to the following protocols. As the exatecan-linker conjugate precursors comprise a terminal azide group, they are suitable for attaching to a nanoparticle functionalized with alkyne moieties (e.g., DBCO), using click chemistry.

Synthesis of (S)-2-amino-N-(4-(((tert-butyl)diphenylsilyl)oxy)methyl)phenyl)-6-((diphenyl(p tolyl)methyl)amino)hexanamide (161)

[0202]



Scheme 2: Synthesis of compound (161).

[0203] *Synthesis of 4-(((tert-butyl)diphenylsilyl)oxy)methyl)aniline (159):* Imidazole (5.54 g, 81.22 mmol) was added to a solution of (4-aminophenyl)methanol (**75**) (5.0 g, 40.61 mmol) in DMF (25 mL) at 0°C, followed by *tert*-butyl(chloro)diphenylsilane (13.39 g, 48.73 mmol), and the reaction mixture was stirred at room temperature for 16 h. The progress of the reaction was monitored by TLC. After completion of starting


material, the reaction mixture was quenched with water (20 mL) and extracted with EtOAc (2x200 mL). The combined organic layers were dried over anhydrous Na₂SO₄, concentrated under reduced pressure, and purified by column chromatography using silica gel (230-400 mesh) eluting with 10% EtOAc in petroleum ether to afford 4-(((*tert*-butyldiphenylsilyl)oxy)methyl)aniline (**159**; 6.6 g) as a gum.

LCMS: *m/z* 362.31 [(M+H)⁺]; *R_t*: 2.58 min; 93.68% purity.

[0204] *Synthesis of (9H-fluoren-9-yl)methyl(S)-(1-((4-(((*tert*-butyldiphenylsilyl)oxy)methyl)phenyl)amino)-6-((diphenyl(*p*-tolyl)methyl)amino)-1-oxohexan-2-yl)carbamate (160)*: Diisopropylethylamine (4.18 mL, 24 mmol), HATU (6.08 g, 16 mmol) and 4-(((*tert*-butyldiphenylsilyl)oxy)methyl)aniline (**159**) (2.89 g, 8 mmol) were added to a solution of N²-(((9H-fluoren-9-yl)methoxy)carbonyl)-N⁶-(diphenyl(*p*-tolyl)methyl)-L-lysine (**149**) (5.0 g, 8 mmol) in DMF (50 mL) at 0 °C, and the reaction mixture was stirred at room temperature for 16 h. The progress of the reaction was monitored by TLC. After completion of starting material, the reaction mixture was quenched with ice water. The precipitated solid was filtered and dried under vacuum to afford (9H-fluoren-9-yl)methyl (S)-(1-((4-(((*tert*-butyldiphenylsilyl)oxy)methyl)phenyl)amino)-6-((diphenyl(*p*-tolyl)methyl)amino)-1-oxohexan-2-yl)carbamate (**160**; 5.5 g) as a solid. LCMS: *m/z* 990.37 [(M+H)⁺]; *R_t*: 2.84 min; 96.79% purity.

[0205] *Synthesis of (S)-2-amino-N-(4-(((*tert*-butyldiphenylsilyl)oxy)methyl)phenyl)-6-((diphenyl(*p*-tolyl)methyl)amino)hexanamide (161)*: Piperidine (16.5 mL) was added to a solution of (9H-fluoren-9-yl)methyl (S)-(1-((4-(((*tert*-butyldiphenylsilyl)oxy)methyl)phenyl)amino)-6-((diphenyl(*p*-tolyl)methyl)amino)-1-oxohexan-2-yl)carbamate (**160**) (5.5 g, 5.68 mmol) in DMF (38.5 mL) at room temperature, and the reaction mixture was stirred at room temperature for 3 h. The progress of the reaction was monitored by TLC. After completion of starting material, the reaction mixture was concentrated under reduced pressure, and purified by column chromatography using silica gel (230-400 mesh) eluting with 100% EtOAc to afford (S)-2-amino-N-(4-(((*tert*-butyldiphenylsilyl)oxy)methyl)phenyl)-6-((diphenyl(*p*-tolyl)methyl)amino)hexanamide (**160**; 3.5 g) as a gum. LCMS: *m/z* 744.24 [(M-H)⁻]; *R_t*: 2.20 min; 90.16% purity.

Synthesis of 4-((32S,35S)-1-azido-35-(4-((diphenyl(*p*-tolyl)methyl)amino)butyl)-32-isopropyl-30,33-dioxo-3,6,9,12,15,18,21,24,27-nonaoxa-31,34-diazahexatriacontan-36-amido)benzyl (4-nitrophenyl) carbonate (191).

[0206]**Scheme 3:** Synthesis of compound (**191**).**[0207]** *Synthesis of (9H-Fluoren-9-yl)methyl((S)-1-(((S)-1-((4-(((tert-butyl)diphenylsilyl)oxy)methyl)phenyl)amino)-6-((diphenyl(p-tolyl)methyl)amino)-1-oxohexan-2-yl)amino)-3-methyl-1-oxobutan-2-yl)carbamate (**187**):*

Diisopropylethylamine (1.54 mL, 8.83 mmol), HATU (2.24 g, 5.89 mmol) and (S)-2-amino-N-(4-(((tert-butyl)diphenylsilyl)oxy)methyl)phenyl)-6-((diphenyl(p-tolyl)methyl)amino)hexanamide (**161**) (2.19 g, 2.94 mmol) were added to a solution of (((N-(9-Fluorenylmethoxycarbonyl)-L-valine (1 g, 2.94 mmol), in DMF (20 mL) at 0 °C, and the reaction mixture was stirred at room temperature for 3 h. The progress of the reaction was monitored by TLC. After completion of starting material, the reaction mixture was quenched with ice water. The precipitated solid was filtered and dried under vacuum to afford (((9H-fluoren-9-yl)methyl ((S)-1-(((S)-1-((4-(((tert-butyl)diphenylsilyl)oxy)methyl)phenyl)amino)-6-((diphenyl(p-tolyl)methyl)amino)-1-oxohexan-2-yl)amino)-3-methyl-1-oxobutan-2-yl)carbamate (**187**; 2.5 g) as a solid. LCMS: MH^+ 1067, retention time 2.42 min.

[0208] *Synthesis of (S)-2-((S)-2-Amino-3-methylbutanamido)-N-(4-(((tert-butyl)diphenylsilyl)oxy)methyl)phenyl)-6-((diphenyl(p-tolyl)methyl)amino)hexanamide (**188**):* A 30% solution of piperidine in DMF (4.5 mL) was added to a solution of (((9H-fluoren-9-yl)methyl ((S)-1-(((S)-1-((4-(((tert-butyl)diphenylsilyl)oxy)methyl)phenyl)amino)-6-((diphenyl(p-tolyl)methyl)amino)-1-oxohexan-2-yl)amino)-3-methyl-1-oxobutan-2-yl)carbamate (**187**) (1.5 g, 1.40 mmol) in DMF (6 mL) at room temperature, and the reaction mixture was stirred at room temperature for 2 h. The progress of the reaction was monitored by TLC. After completion of starting material, the reaction mixture was concentrated under reduced

and purified by flash chromatography eluting with 100% EtOAc, to afford (S)-2-((S)-2-amino-3-methylbutanamido)-N-(4-(((tert-butyldiphenylsilyl)oxy)methyl)phenyl)-6-(((diphenyl(p-tolyl)methyl)amino)hexanamide (**188**; 1.1 g) as a solid. ¹H NMR (400 MHz, DMSO-*d*₆): δ 10.07 (s, 1H), 7.64-7.63 (d, 4H), 7.56-7.54 (d, 2H), 7.46-7.35 (m, 9H), 7.27-7.24 (m, 8H), 7.185-7.11 (m, 2H), 7.05-7.03 (d, 2H), 4.71 (s, 2H), 4.44 (d, 1H), 3.25-3.16 (d, 1H), 3.01-3.00 (m, 1H), 2.21 (s, 3H), 1.98-1.93 (m, 2H), 1.68-1.38 (m, 4H), 1.15 (s, 10H), LCMS: MH⁺ 845, retention time 3.63 min.


[0209] *Synthesis of 1-azido-N-((S)-1-(((S)-1-((4-(((tert-butyldiphenylsilyl)oxy)methyl)phenyl)amino)-6-(((diphenyl(p-tolyl)methyl)amino)-1-oxohexan-2-yl)amino)-3-methyl-1-oxobutan-2-yl)-3,6,9,12,15,18,21,24,27-nonaoxatriacontan-30-amide (189)*: Diisopropylethylamine (0.49 mL, 2.83 mmol), HATU (719.47 mg, 1.89 mmol) and (S)-2-((S)-2-amino-3-methylbutanamido)-N-(4-(((tert-butyldiphenylsilyl)oxy)methyl)phenyl)-6-(((diphenyl(p-tolyl)methyl)amino)hexanamide (**188**) (800 mg, 0.94 mmol) were added to a solution of 1-azido-3,6,9,12,15,18,21,24,27-nonaoxatriacontan-30-oic acid (**86**) (484 mg, 0.94 mmol) in DMF (8 mL) at 0 °C, and the reaction mixture was stirred at room temperature for 6 h. The progress of the reaction was monitored by TLC. After completion of starting material, the reaction mixture was quenched with water (15 mL) and extracted with EtOAc (2x30 mL). The combined organic layers were dried over anhydrous Na₂SO₄, concentrated under reduced, and purified by flash chromatography eluting with 3% MeOH in DCM to provide 1-azido-N-((S)-1-(((S)-1-((4-(((tert-butyldiphenylsilyl)oxy)methyl)phenyl)amino)-6-(((diphenyl(p-tolyl)methyl)amino)-1-oxohexan-2-yl)amino)-3-methyl-1-oxobutan-2-yl)-3,6,9,12,15,18,21,24,27-nonaoxatriacontan-30-amide (**189**; 0.60 g) as a gum. ¹H NMR (400 MHz, DMSO-*d*₆): δ 9.91 (s, 1H), 8.02-8.00 (d, 2H), 7.95 (s, 2H), 7.87-7.85 (d, 1H), 7.64-7.63 (d, 4H), 7.57-7.55 (d, 2H), 7.46-7.32 (m, 11H), 7.26-7.24 (m, 8H), 7.15-7.11 (t, 2H), 7.05-7.03 (d, 2H), 4.71 (s, 2H), 4.35-4.33 (m, 1H), 4.19 (s, 1H), 3.59-3.36 (m, 38H), 2.68-2.38 (m, 6H), 2.22 (s, 3H), 1.98-1.92 (m, 2H), 1.47-1.17 (m, 4H), 1.02 (s, 9H), 0.85-0.80 (m, 6H). LCMS: MH⁺ 1338, retention time 2.92 min.

[0210] *Synthesis of 1-azido-N-((S)-1-(((S)-6-(((diphenyl(p-tolyl)methyl)amino)-1-((4-(hydroxymethyl)phenyl)amino)-1-oxohexan-2-yl)amino)-3-methyl-1-oxobutan-2-yl)-3,6,9,12, 15,18,21,24,27-nonaoxatriacontan-30-amide (190)*: NH₄F (166 mg, 4.48 mmol) was added to a solution of 1-azido-N-((S)-1-(((S)-1-((4-(((tert-butyldiphenylsilyl)oxy)methyl)phenyl)amino)-6-(((diphenyl(p-tolyl)methyl)amino)-1-oxohexan-2-yl)amino)-3-methyl-1-oxobutan-2-yl)-3,6,9,12,15,18,21,24,27-nonaoxatriacontan-30-amide (**189**) (600 mg, 0.44 mmol) in methanol (10 mL) at room temperature, and the reaction mixture was stirred at room temperature for 6 h. The progress of the reaction was monitored by TLC. After completion of starting material, the reaction mixture was concentrated under reduced pressure, and the residue obtained was diluted with water (15 mL) and extracted with EtOAc (2x20 mL).

The combined organic layers were dried over anhydrous Na₂SO₄, concentrated under reduced pressure, and purified by flash chromatography eluting with 5 % MeOH in DCM to afford 1-azido-N-((S)-1-(((S)-6-((diphenyl(p-tolyl)methyl)amino)-1-((4-(hydroxymethyl)phenyl)amino)-1-oxohexan-2-yl)amino)-3-methyl-1-oxobutan-2-yl)-3,6,9,12,15,18,21,24,27-nonaoxatriacontan-30-amide (**190**; 0.40 g) as a gum. ¹H NMR (400 MHz, DMSO-*d*₆): δ 9.81 (s, 1H), 7.96-7.94 (d, 1H), 7.84-7.81 (d, 1H), 7.53-7.51 (d, 2H), 7.37-7.35 (d, 4H), 7.26-7.12 (m, 9H), 7.096-7.04 (d, 2H), 5.06-5.04 (t, 1H), 4.43-4.41 (d, 2H), 4.35 (m, 1H), 4.18-4.16 (t, 1H), 3.60-3.46 (m, 33H), 3.39-3.36 (t, 2H), 2.50-2.23 (m, 2H), 2.23 (s, 3H), 2.23-1.93 (m, 2H), 1.48-1.23 (m, 6H), 0.85-0.80 (m, 6H). LCMS: MH⁺ 1100, retention time 3.72 min.

[0211] *Synthesis of 4-((32S,35S)-1-azido-35-(4-((diphenyl(p-tolyl)methyl)amino)butyl)-32-isopropyl-30,33-dioxo-3,6,9,12,15,18,21,24,27-nonaoxa-31,34-diazahexatriacontan-36-amido)benzyl (4-nitrophenyl) carbonate (191)*: Pyridine (0.14 mL, 1.80 mmol) and 4-nitrophenyl chloroformate (**14**) (145 mg, 0.72 mmol) were added to a solution of 1-azido-N-((S)-1-(((S)-6-((diphenyl(p-tolyl)methyl)amino)-1-((4-(hydroxymethyl)phenyl)amino)-1-oxohexan-2-yl)amino)-3-methyl-1-oxobutan-2-yl)-3,6,9,12,15,18,21,24,27-nonaoxatriacontan-30-amide (**190**) (400 mg, 0.36 mmol) in DCM (10 mL) at 0 °C, and the reaction mixture was stirred at room temperature for 6 h. The progress of the reaction was monitored by TLC. After completion of starting material, the reaction mixture was concentrated under reduced pressure, and purified by flash chromatography eluting with 3% MeOH in DCM to afford 4-((32S,35S)-1-azido-35-(4-((diphenyl(p-tolyl)methyl)amino)butyl)-32-isopropyl-30,33-dioxo-3,6,9,12,15,18,21,24,27-nonaoxa-31,34-diazahexatriacontan-36-amido)benzyl (4-nitrophenyl) carbonate (**191**; 0.34 g) as a gum. LCMS: MH⁺ 1265, retention time 1.33 min.

Synthesis of 4-((32S,35S)-35-(4-aminobutyl)-1-azido-32-isopropyl-30,33-dioxo-3,6,9,12,15,18,21,24,27-nonaoxa-31,34-diazahexatriacontan-36-amido)benzyl ((1S,9S)-9-ethyl-5-fluoro-9-hydroxy-4-methyl-10,13-dioxo-2,3,9,10,13,15-hexahydro-1H,12H-benzo[de]pyrano[3'.4':6,7]indolizino[1.2-b]quinolin-1-yl)carbamate (202).

[0212]**Scheme 4:** Synthesis of protease-cleavable linker-payload conjugate precursor (**202**).

[0213] Synthesis of 4-((32*S*,35*S*)-1-azido-35-(4-((diphenyl(*p*-tolyl)methyl)amino)butyl)-32-isopropyl-30,33-dioxo-3,6,9,12,15,18,21,24,27-nonaoxa-31,34-diazahexatriacontan-36-amido)benzyl ((1*S*,9*S*)-9-ethyl-5-fluoro-9-hydroxy-4-methyl-10,13-dioxo-2,3,9,10,13,15-hexahydro-1*H*,12*H*-benzo[*de*]pyrano[3',4':6,7]indolizino[1,2-*b*]quinolin-1-yl)carbamate (**201**): Triethylamine (0.09 mL, 0.62 mmol) and (1*R*,9*R*)-1-amino-9-ethyl-5-fluoro-9-hydroxy-4-methyl-1,2,3,9,12,15-hexahydro-10*H*,13*H*-benzo[*de*]pyrano[3',4':6,7]indolizino[1,2-*b*]quinoline-10,13-dione methanesulfonate (exatecan mesylate; **16**; 131 mg, 0.25 mmol) were added to a solution 4-((32*S*,35*S*)-1-azido-35-(4-((diphenyl(*p*-tolyl)methyl)amino)butyl)-32-isopropyl-30,33-dioxo-3,6,9,12,15,18,21,24,27-nonaoxa-31,34-diazahexatriacontan-36-amido)benzyl (4-nitrophenyl) carbonate (**191**; 311 mg, 0.25 mmol) in NMP (2.5 mL) at 0 °C, and the mixture was stirred at room temperature for 8 h. The progress of the reaction was monitored by LCMS. After completion of starting material, the reaction mixture was quenched with water (15 mL) and extracted with 10% methanol in chloroform (2x20 mL). The combined organic layers were dried over anhydrous sodium sulfate (Na₂SO₄) and concentrated under reduced pressure. Diethyl ether was added to the crude material, and the resulting precipitate was filtered and purified using column chromatography (Combi-Flash) eluting with 5% MeOH in DCM to provide 4-((32*S*,35*S*)-1-azido-35-(4-((diphenyl(*p*-tolyl)methyl)amino)butyl)-32-isopropyl-30,33-dioxo-3,6,9,12,15,18,21,24,27-nonaoxa-31,34-diazahexatriacontan-36-amido)benzyl ((1*S*,9*S*)-9-ethyl-5-fluoro-9-hydroxy-4-methyl-10,13-dioxo-2,3,9,10,13,15-hexahydro-1*H*,12*H*-benzo[*de*]pyrano[3',4':6,7]indolizino[1,2-*b*]quinolin-1-yl)carbamate (**201**) as a solid (0.3 g). LCMS: MH⁺ 1561, retention time 2.18 min.

[0214] Synthesis of 4-((32*S*,35*S*)-35-(4-aminobutyl)-1-azido-32-isopropyl-30,33-dioxo-3,6,9,12,15,18,21,24,27-nonaoxa-31,34-diazahexatriacontan-36-amido)benzyl


((1*S*,9*S*)-9-ethyl-5-fluoro-9-hydroxy-4-methyl-10,13-dioxo-2,3,9,10,13,15-hexahydro-1*H*,12*H*-benzo[de]pyrano[3',4':6,7]indolizino[1,2-*b*]quinolin-1-yl)carbamate (**202**): A 1% solution of trifluoroacetic acid (TFA) in DCM was added to a solution of 4-((32*S*,35*S*)-1-azido-35-(4-((diphenyl(*p*-tolyl)methyl)amino)butyl)-32-isopropyl-30,33-dioxo-3,6,9,12,15,18,21,24,27-nonaoxa-31,34-diazahexatriacontan-36-amido)benzyl ((1*S*,9*S*)-9-ethyl-5-fluoro-9-hydroxy-4-methyl-10,13-dioxo-2,3,9,10,13,15-hexahydro-1*H*,12*H*-benzo[de]pyrano[3',4':6,7]indolizino[1,2-*b*]quinolin-1-yl)carbamate (**201**; 300 mg, 0.19 mmol) in DCM (5 mL) at 0 °C, and the reaction mixture was stirred at room temperature for 1 h. The progress of the reaction was monitored by LCMS. After completion of starting material, the reaction mixture was concentrated under reduced pressure, and the residue was triturated with diethyl ether and purified by RP-prep-HPLC to provide 4-((32*S*,35*S*)-35-(4-aminobutyl)-1-azido-32-isopropyl-30,33-dioxo-3,6,9,12,15,18,21,24,27-nonaoxa-31,34-diazahexatriacontan-36-amido)benzyl ((1*S*,9*S*)-9-ethyl-5-fluoro-9-hydroxy-4-methyl-10,13-dioxo-2,3,9,10,13,15-hexahydro-1*H*,12*H*-benzo[de]pyrano[3',4':6,7]indolizino[1,2-*b*]quinolin-1-yl)carbamate (**202**) (70mg) as a solid. ¹H NMR (400 MHz, DMSO-*d*₆): δ 9.96 (s, 1H), 8.12-8.10 (q, 2H), 7.89-7.87 (d, 1H), 7.76-7.61 (d, 1H), 7.59-7.31 (m, 7H), 6.51 (s, 1H), 5.44 (s, 2H), 5.29 (s, 3H), 5.09 (s, 2H), 4.37-4.20 (m, 1H), 4.18-4.16 (t, 1H), 3.49-3.44 (m, 4H), 3.12-2.55 (m, 39H), 2.40-1.34 (m, 15H), 0.89-0.82 (m, 9H), LCMS: MH⁺ 1305, retention time 5.33 and 5.47 min.

Example 2: Synthesis of Folic Acid Conjugate Precursors

[0215] Folic acid conjugate precursors suitable for preparing a folate receptor targeting NDC disclosed herein can be prepared according to one of the following synthetic protocols. As the folic acid conjugate precursors comprise a terminal azide group, they are suitable for attaching to a nanoparticle functionalized with alkyne moieties (e.g., DBCO), using click chemistry.

Synthesis of (S)-16-(4-(((2-amino-4-oxo-3,4-dihydropteridin-6-yl)methyl)amino)benzamido)-1-azido-13-oxo-3,6,9-trioxa-12-azaheptadecan-17-oic acid (606)

[0216]



[0217] Preparation of compound 600: Compound 599 (160 g, 512 mmol) was dissolved in TFAA (800 mL) at 25 °C and stirred under a nitrogen atmosphere in the dark for 5 hrs. The solvent was then removed at 50 °C in vacuo to give the crude product. The crude product was triturated with MTBE (750 mL) for 60 min and then filtered to afford compound 600 (203 g, crude) as a solid, which was used in next step without further purification. LC-MS: ¹H NMR: (400 MHz, CDCl₃) δ 12.74 (br s, 1H), 8.88 (s, 1H), 7.97-8.05 (m, 2H), 7.66-7.74 (m, 2H), 5.26 (s, 1H).

[0218] Preparation of Compound 602: TBTU (238 g, 740 mmol) and DIPEA (95.7 g, 740 mmol) were added to a solution of compound 601 (225 g, 529 mmol) in DMF (2.25 L). After 30 min stirring at 20 °C, 2-(2-(2-(2-azidoethoxy)ethoxy)ethoxy)ethan-1-amine (Reagent A; 121 g, 555 mmol) was added and the mixture was stirred at 50 °C for 12 hrs. Two reaction mixtures were combined and worked up, and the residue was diluted with H₂O (3 L) and extracted with ethyl acetate (1500 mL x 3). The combined organic layers were washed with brine (800 mL x 3), dried over Na₂SO₄, filtered and concentrated under reduced pressure, and purified by column chromatography (SiO₂, Petroleum ether/Ethyl acetate = 100/1 to 1/1) to afford compound 602 (590 g) as an oil. ¹H NMR: (400 MHz, CDCl₃) δ 7.76-7.78 (m, 2H), 7.63-7.60 (m, 2H), 7.41-7.27 (m, 4H), 6.43 (s, 1H), 5.70 (s, 1H), 4.42-4.38 (m, 2H), 4.24-4.23 (m, 2H), 3.63-3.36 (m, 16H), 2.28-2.18 (m, 3H), 1.98-1.96 (m, 1H), 1.48 (s, 9H).

[0219] Preparation of Compound 603: N-ethylethanamine (1.27 kg, 17.4 mol) was added to a solution of compound 602 (435 g, 695 mmol) in DCM (4.35 L) and the mixture was stirred at 25 °C 3 hrs. The solvent was then removed at room temperature in vacuo, and the residue was purified by flash column chromatography (DCM/MeOH = 100/1 to 1/1) to afford compound 603 (245 g) as an oil. ¹H NMR: (400


MHz, CDCl₃) δ 6.55 (s, 1H), 3.67-3.30 (m, 17H), 2.34-2.30 (m, 2H), 2.10-2.06 (m, 1H), 1.87 (s, 2H), 1.77-1.73 (m, 1H), 1.44 (s, 9H).

[0220] Preparation of compound 604: TBTU (119 g, 372 mmol) and DIEA (160 g, 1.24 mol) were added to a solution of compound 600 (101 g, 248 mmol) in DMF (900 mL) and the mixture was stirred for 30 minutes. Then compound 603 (100 g, 248 mmol) in DMF (100 mL) was added. The mixture was stirred at 25 °C for 12 hrs. Two reaction mixtures were combined and concentrated and the residue was diluted with H₂O (2.5 L) and extracted with ethyl acetate (1 L $\times$ 5). The combined organic layers were washed with brine (600 mL $\times$ 3), dried over Na₂SO₄, filtered and concentrated under reduced pressure to afford compound 4 (420 g, crude) as a solid, which was used in next step without further purification.

[0221] Preparation of compound 605: K₂CO₃ (585 g, 4.23 mol) was added to a solution of compound 604 (420 g, 529 mmol) in THF (4.2 mL) and H₂O (500 mL) and the mixture was stirred at 60°C for 0.5 hr.. The reaction mixture was concentrated under reduced pressure to remove THF and the residue was diluted with H₂O (500 mL) and adjusted the pH to 3 with HCl (M=1), filtered and concentrated under reduced pressure to afford compound 605 (260 g, crude) as a solid, which was used directly without purification.

[0222] Preparation of compound 606: Trifluoroacetic acid (2.12 kg, 18.6 mol) was added in one portion to a mixture of compound 605 (260 g, 373 mmol) in CH₂Cl₂ (2.6 L) at 20 °C under nitrogen, and the mixture was stirred at 20 °C for 5 hrs. The reaction mixture was concentrated under reduced pressure and purified by HPLC (column: Agela DuraShell C18 250*80mm*10um; mobile phase: [water (10mM NH₄HCO₃)-MeOH]; B%: 5%-40%, 20 min) to give afford compound 606 (52.5 g, 81.82 mmol, 21.96% yield) as a solid. (M+H) 642.80; IR: 2107 (N₃ Bond).

Synthesis of (S)-38-(4-(((2-amino-4-oxo-3,4-dihydropteridin-6-yl)methyl)amino)benzamido)-1-azido-30,35-dioxo-3,6,9,12,15,18,21,24,27-nona-31,34-diazanonatriacontan-39-oic acid (472)

[0223]

Scheme 5: Synthesis of folic acid conjugate precursor (**472**).

[0224] *Synthesis of tert-butyl (1-azido-30-oxo-3,6,9,12,15,18,21,24,27-nonaoxa-31-azatritriacontan-33-yl)carbamate (465)*: Triethylamine (0.36 mL, 2.64 mmol), EDC (218 mg, 1.14 mmol), HOBT (154 mg, 1.14 mmol) and tert-butyl (2-aminoethyl)carbamate (**464**) (124 mg, 0.881 mmol) were added to a solution of 1-azido-3,6,9,12,15,18,21,24,27-nonaoxatriacontan-30-oic acid (**86**; 450mg, 0.881 mmol), in DCM (20 mL) at 0 °C, and the reaction mixture was stirred at room temperature for 16 h. The progress of the reaction was monitored by TLC. After consumption of starting material, the reaction mixture was extracted with DCM and water, and the organic layer was dried over Na₂SO₄, and evaporated under vacuum. The residue was purified by flash chromatography and dried under vacuum to provide tert-butyl (1-azido-30-oxo-3,6,9, 12, 15, 18,21,24,27 -nonaoxa-31-azatritriacontan-33-yl)carbamate (**465**; 0.45 g) as a liquid. ¹H NMR (400 MHz, DMSO-*d*₆): 7.83 (t, 1H), 6.75 (t, 1H), 3.61-3.31(m, 38H), 3.02-2.97 (t, 4H), 2.28 (t, 2H), 1.37(s, 9H).

[0225] *Synthesis of N-(2-Aminoethyl)-1-azido-3,6,9,12,15,18,21,24,27-nonaoxatriacontan-30-amide (466)*: A solution of tert-butyl (1-azido-30-oxo-3,6,9,12,15,18,21,24,27-nonaoxa-31-azatritriacontan-33-yl)carbamate (**465**) (350 mg, 0.462 mmol) in DCM was cooled to 0 °C and TFA was added to it by dropwise, and the reaction mixture was then stirred at RT for 16h. The progress of the reaction

was monitored by TLC. After consumption of starting material, the reaction mixture was concentrated under reduced pressure and azeotroped with DCM (3 times) to provide crude (**466**), which was purified by flash chromatography eluting with 5% MeOH in DCM to provide N-(2-aminoethyl)-1-azido-3,6,9,12,15,18,21,24,27-nonaoxatriacontan-30-amide (**466**; 0.25 g) as a liquid. ¹H NMR (400 MHz, DMSO-*d*₆): 8.02 (t, 1H), 7.73 (t, 2H), 3.71-3.26 (m, 40H), 2.86(t, 2H), 2.35(t, 2H).

[0226] *Synthesis of tert-butyl (S)-38-((((9H-fluoren-9-yl)methoxy)carbonyl)amino)-1-azido-30,35-dioxo-3,6,9,12,15,18,21,24,27-nonaoxa-31,34-diazanonatriacontan-39-oate (467)*: Diisopropylethylamine (0.174 mL, 1.0 mmol), PyBOP (416 mg, 0.8 mmol) and N-(2-aminoethyl)-1-azido-3,6,9,12,15,18,21,24,27-nonaoxatriacontan-30-amide (**466**) (331mg, 0.6 mmol) were added to a solution of (S)-4-((((9H-fluoren-9-yl)methoxy)carbonyl)amino)-5-(tert-butoxy)-5-oxopentanoic acid (170mg, 0.4 mmol), in DMF (5 mL) at 0 °C, and the reaction mixture was stirred at rt for 16 h. The progress of the reaction was monitored by TLC. After consumption of starting material, the reaction mixture was evaporated under vacuum at low temperature, and purified by flash chromatography eluting with 5% MeOH in DCM to afford tert-butyl (S)-38-((((9H-fluoren-9-yl)methoxy)carbonyl)amino)-1-azido-30,35-dioxo-3,6,9,12,15,18,21,24,27-nonaoxa-31,34-diazanonatriacontan-39-oate (**467**; 0.35 g) as a liquid. MH⁺ 962, retention time 1.81 min.

[0227] *Synthesis of tert-butyl (S)-38-amino-1-azido-30,35-dioxo-3,6,9,12,15,18,21,24,27-nonaoxa-31,34-diazanonatriacontan-39-oate (468)*: A 30% solution of piperidine in DMF (1ml) was added to a solution of tert-butyl (S)-38-((((9H-fluoren-9-yl)methoxy)carbonyl)amino)-1-azido-30,35-dioxo-3,6,9,12,15,18,21,24,27-nonaoxa-31,34-diazanonatriacontan-39-oate (**467**; 350mg, 3.65 mmol) in DMF (5 mL) at room temperature, and the reaction mixture was stirred at room temperature for 3 h. The progress of the reaction was monitored by TLC. After completion of starting material, the reaction mixture was concentrated under reduced pressure to afford tert-butyl (S)-38-amino-1-azido-30,35-dioxo-3,6,9,12,15,18,21,24,27-nonaoxa-31,34-diazanonatriacontan-39-oate (**468**; 250 mg), which was used in the next step without further purification. MH⁺ 739, retention time 1.50 min.

[0228] *Synthesis of tert-butyl (S)-38-(4-(N-((2-amino-4-oxo-3,4-dihydropteridin-6-yl)methyl)-2,2,2-trifluoroacetamido)benzamido)-1-azido-30,35-dioxo-3,6,9,12,15,18,21,24,27-nonaoxa-31,34-diazanonatriacontan-39-oate (470)*: Diisopropylethylamine (0.107 mL, 0.613 mmol), PyBOP (254 mg, 0.49 mmol) and tert-butyl (S)-38-amino-1-azido-30,35-dioxo-3,6,9,12,15,18,21,24,27-nonaoxa-31,34-diazanonatriacontan-39-oate (**468**) (271 mg, 0.368 mmol) were added to a solution of 4-(N-((2-amino-4-oxo-3,4-dihydropteridin-6-yl)methyl)-2,2,2-trifluoroacetamido)benzoic acid (**469**; 100mg, 0.245 mmol) in DMF (5 mL) at 0°C, and the reaction mixture was stirred at room temperature for 16 h. The progress of the

reaction was monitored by TLC. After completion of starting material, the reaction mixture was concentrated under vacuum at low temperature, then purified by flash chromatography eluting with 10% MeOH in DCM to afford tert-butyl (S)-38-(4-(N-((2-amino-4-oxo-3,4-dihydropteridin-6-yl)methyl)-2,2,2-trifluoroacetamido)benzamido)-1-azido-30,35-dioxo-3,6,9,12,15,18,21,24,27-nonaoxa-31,34-diazanonatriacontan-39-oate (**470**; 180 mg) as a solid. MH^+ 1129, retention time 2.61 min.

[0229] *Synthesis of (S)-38-(4-(N-((2-Amino-4-oxo-3,4-dihydropteridin-6-yl)methyl)-2,2,2-trifluoroacetamido)benzamido)-1-azido-30,35-dioxo-3,6,9,12,15,18,21,24,27-nonaoxa-31,34-diazanonatriacontan-39-oic acid (471)*: Trifluoroacetic acid (0.123 mL, 1.59 mmol) was added to a solution of tert-butyl (S)-38-(4-(N-((2-amino-4-oxo-3,4-dihydropteridin-6-yl)methyl)-2,2,2-trifluoroacetamido)benzamido)-1-azido-30,35-dioxo-3,6,9,12,15,18,21,24,27-nonaoxa-31,34-diazanonatriacontan-39-oate (**470**) (180 mg, 0.16 mmol) in DCM was added at room temperature, and the reaction mixture was stirred at room temperature for 16h. The progress of the reaction was monitored by TLC. After completion of starting material, the reaction mixture was concentrated under reduced pressure and azeotroped with DCM (3 times) to afford crude product (**471**; 100 mg), that was used in the next step without further purification. MH^+ 1073, retention time 2.34 min.

[0230] *Synthesis of (S)-38-(4-(((2-Amino-4-oxo-3,4-dihydropteridin-6-yl)methyl)amino)benzamido)-1-azido-30,35-dioxo-3,6,9,12,15,18,21,24,27-nonaoxa-31,34-diazanonatriacontan-39-oic acid (472)*: Aqueous NH_3 (dissolved in DMF) (0.01 mL, 0.71 mmol) was added to a solution of (S)-38-(4-(N-((2-amino-4-oxo-3,4-dihydropteridin-6-yl)methyl)-2,2,2-trifluoroacetamido)benzamido)-1-azido-30,35-dioxo-3,6,9,12,15,18,21,24,27-nonaoxa-31,34-diazanonatriacontan-39-oic acid (**471**; 80 mg, 0.071 mmol) in DMF (3mL) at 0 °C, and the reaction mixture was stirred at room temperature for 6 h. After completion of starting material, the reaction mixture was concentrated under reduced pressure, and the residue was purified by RP-prep-HPLC to afford (S)-38-(4-(((2-Amino-4-oxo-3,4-dihydropteridin-6-yl)methyl)amino)benzamido)-1-azido-30,35-dioxo-3,6,9,12,15,18,21,24,27-nonaoxa-31,34-diazanonatriacontan-39-oic acid (**472**; 15 mg) as a solid. ^1H NMR (400 MHz, $DMSO-d_6$): 8.62 (s, 1H), 8.01 (d, 1H), 7.98 (t, 1H), 7.64 (d, 2H), 6.64 (d, 2H), 4.47 (d, 2H), 4.21 (t, 1H), 3.68-3.35 (m, 38H), 3.07 (t, 4H), 2.32-2.11 (t, 6H), 1.86 (t, 1H). LCMS: MH^+ 977, retention time 1.96 min.

[0231] *LCMS Method*: Column- YMC TRIART C18 (33 × 2.1 mm, 3u); (mobile phase: 95% [0.1% HCOOH in water] and 5% [0.1% HCOOH in CH_3CN] held for 0.50 min then to 1% [0.1% HCOOH in water] and 99% [0.1% HCOOH in CH_3CN] in 3.0 min, held this composition up to 4.00 min and finally back to initial condition in 4.10 min, held for 4.50 min). Flow rate- 1.0 ml/min.

Example 3: Synthesis of Nanoparticle Drug Conjugates (NDCs)

Preparation of Nanoparticles

[0232] Aqueous synthesis methodology can be used for the preparation and functionalization of ultrasmall nanoparticles of the present disclosure. For example, methodology based on the procedures outlined in WO 2016/179260 A1 and WO 2018/213851 A1 may be used.

[0233] For example, a fluorescent compound such as, but not limited to Cy5, can be functionalized with a maleimide group, to provide a maleimide-functionalized fluorescent compound that has a net positive charge. This can be conjugated with a thiol-silane, such as (3-mercaptopropyl)trimethoxysilane (MPTMS) to produce a silane-functionalized fluorescent compound such as Cy5-silane. The conjugation may be performed in dimethyl sulfoxide (DMSO) in a glovebox under inert atmosphere overnight (16-24 hours) and at room temperature (18-25 °C).


[0234] On the following day, the next step of the synthesis can be performed in a suitable chamber, such as a glass flask, container, or reactor, and can involve stirring deionized water with a pH of around 8.5-10.5 which can be achieved using an aqueous solution of ammonium hydroxide of pH 7.5-8.5. A silica precursor, such as a tetraalkyl orthosilicate, e.g., tetramethyl orthosilicate (TMOS), can then be added into the reaction chamber under vigorous stirring at room temperature, followed by immediately adding the silane-functionalized fluorescent compound, e.g., Cy5-silane. The reaction can be left stirring at room temperature overnight (1-48 hours), to provide silica cores encapsulating the fluorescent compound, e.g., Cy5 dye.

[0235] The following day, a PEG-silane can be added into the reaction under stirring at room temperature to coat the silica core with PEG molecules, and the reaction can be left stirring for 1-48 hours. This step may be followed by heating between 75-85 °C for 1-48 hours. The reaction can then be cooled down to room temperature and purified (e.g., including sterile filtration to remove aggregates formed as side-product of the reaction, and bacteria if any present). Further functionalization of the nanoparticle may then be performed.

Functionalization of Nanoparticles

[0236] A nanoparticle prepared using a method disclosed herein may be further functionalized, e.g., using a method outlined in FIGS. 2 or 3, or in Scheme 6 below. For example, (3-cyclopentadienylpropyl)triethoxysilane ("diene-silane") can be used to functionalize a nanoparticle (e.g., C'Dot) with cyclopentadiene groups, then DBCO-PEG-maleimide can be reacted with the diene-functionalized nanoparticle to provide a

DBCO-functionalized nanoparticle.



Scheme 6. An exemplary method of functionalizing a nanoparticle with DBCO.

[0237] For example, Cy5-C'Dot (which may be prepared using a method described herein) was diluted with deionized water to a desired concentration, typically between 15 to 30 μM , in a round-bottom flask with a stir bar. (3-Cyclopentadienylpropyl)triethoxysilane (cyclopentadiene) was first diluted 100x in DMSO and then added into the reaction with stirring, to reach a desired particle to cyclopentadiene molar ratio. After overnight reaction, 10x PBS was added into the reaction to achieve a final concentration of 1x PBS. Next, a DBCO-maleimide precursor (e.g., DBCO-PEG4-maleimide) was dissolved in DMSO and added into the reaction to reach a desired particle to DBCO molar ratio. After mixing for about 30 min to 1 hour, the reaction mixture was heated to 80 $^{\circ}\text{C}$ while stirring overnight. The reaction solution was then concentrated and purified using gel permeation chromatography (GPC) to obtain diene-based DBCO-C'Dot.


[0238] The purification may be performed based on the principle of size separation. Aggregates and free small molecules having molecular weight different than that of the pegylated nanoparticles are separated using gel permeation chromatography columns (GPC) or Tangential Flow Filtration (TFF) system. Two different membranes, 300 kDa, and 50 kDa cut-off sizes were employed for the removal of large aggregates and free small molecules respectively. Both GPC and TFF systems can be used to transfer the aqueous medium to water, saline etc. Purified DBCO-C'Dot in deionized water can be sterile filtered again and the quality control (QC) steps can be performed, followed by storage in refrigerator at 2-8 $^{\circ}\text{C}$.

[0239] Without wishing to be bound by theory, it is believed that the neutral charge of the cyclopentadiene groups averts hydrolysis of the amide bonds in the linkage, that can be accelerated by other types of precursors (e.g., when using amine-silanes instead of diene-silanes, the primary amine groups can cause hydrolysis). Thus, the NDCs produced using this method are highly stable (see, e.g., comparison in FIGS. 33A-33B). Additionally, using diene-functionalized nanoparticles (e.g., cyclopentadiene-functionalized nanoparticles) in the preparation of NDCS greatly diminishes the self-condensation of silane during the reaction, and improves the

stability, size homogeneity, reaction yield, and purity of the functionalized nanoparticles, relative to other methods (e.g., using amine-silanes).

Preparation of Targeted NDCs

[0240] NDCs of the present disclosure comprising the nanoparticle (also referred as C'Dot), targeting ligand (folic acid) and linker-drug conjugates can be prepared as outlined in the flow chart presented in FIG. 3, and in Scheme 7 below. By adjusting the amount of targeting ligand precursor used in the functionalization step, a desired number of targeting ligands per nanoparticle can be achieved. For example, nanoparticles of the present disclosure may be functionalized to contain about 10 to about 20 folic acid moieties, e.g., about 10, about 11, about 12, about 13, about 14, or about 15 folic acid moieties. Similarly, by adjusting the amount of payload-linker conjugate precursor used in the functionalization step, a desired number of payload moieties per nanoparticle can be achieved. For example, nanoparticles of the present disclosure may be functionalized to contain about 10 to about 40 exatecan-linker moieties, e.g., about 20, about 21, about 22, about 23, about 24, or about 25 exatecan moieties.



Scheme 7. An exemplary method of functionalizing a nanoparticle with folic acid moieties and exatecan-linker moieties.

[0241] *Synthesis of folic-acid conjugated nanoparticle:* DBCO-C'Dot (referred as C'Dot in FIG. 3) was diluted using deionized water to a concentration of 15-45 μM . After the temperature of DBCO-C'Dot solution was around 18-25 $^{\circ}\text{C}$, folate receptor (FR)-targeting ligand precursor such as, folic acid (FA) functionalized with an azide (compound 606 prepared in Example 2) was dissolved in DMSO (0.021 M) and was then added into the reaction with stirring at room temperature, providing a C'Dot functionalized with FA *via* the DBCO group on the surface. The reaction ratio between DBCO-C'Dot and FA was kept from 1:5 to 1:30, and the solution was stirred for 16-24 hours at temperature of 18-25 $^{\circ}\text{C}$. FR-targeting ligand addition is followed by sterile filtration, purification and QC testing to yield FA-C'Dot (referred as C'Dot intermediate in FIG. 3), and can be stored in a refrigerator at 2-8 $^{\circ}\text{C}$. FA-C'Dot comprises a portion of DBCO groups that are available for further click-reactions, e.g., with molecules with azide functionality. It will be understood that the folate-targeting ligand (e.g., folic acid) can be conjugated to the nanoparticle after conjugation with, e.g., a payload-linker conjugate.

[0242] The volume of the FR-targeting ligand conjugation reaction can range from 5 mL to 30 L, and the concentration of DBCO-C'Dot can range from 15 to 45 μM . The following parameters are given for a typical reaction volume of 600 mL and a DBCO-C'Dot concentration of 25 μM . The ratio of DBCO-C'Dot to FR-targeting ligands was precisely controlled to obtain the desired number of FR-targeting ligands per particle, and typically can range from 1:5 to 1:30. For a typical ratio of 1:12, folate-PEG-azide was dissolved in DMSO to a concentration of 0.021 M, and 8.571 mL of the folate-PEG-azide/DMSO solution was added into the reaction. After stirring overnight at room temperature, the reaction mixture was either purified to obtain FA-C'Dot or continue directly to next conjugation step if the purity of FA-C'Dot is no less than 95%. The conversion rate of FR-targeting ligand is typically higher than 95%.

[0243] The number of folic acid groups attached onto each FA-C'Dot was characterized by UV-Vis, and a representative UV-Vis absorbance spectrum is shown in FIG. 4. The number of DBCO groups on each C'Dot can be calculated using the extinction coefficient of C'Dot and DBCO groups

[0244] *Synthesis of FA-targeted NDC (or FA-CDC) comprising exatecan:* FA-C'Dots were diluted using deionized water to a concentration of 15-45 μM . After the FA-C'Dot solution temperature reached around 18-25 $^{\circ}\text{C}$, exatecan-linker conjugate precursor (e.g., compound 202 described in Example 1) cathepsin dissolved in DMSO (0.04 M) was added into the reaction under stirring at room temperature. This step functionalized the FA-C'Dot with the linker-drug conjugate *via* the available DBCO groups on the surface. The reaction ratio between FA-C'Dot and linker-drug conjugate was kept around 1:10-1:50 and the solution was stirred for 16-24 hours. The addition of linker-drug conjugate was followed by sterile filtration, and purification. FA-CDC

(also referred as NDC) in deionized water is QC tested, and stored in refrigerator at 2-8°C.

[0245] The volume of the cleavable exatecan conjugation reaction can range from 5 mL to 30 L, and the concentration of FA-C'Dot can range from 15 to 45 μ M. The following parameters are given for a typical reaction volume of 600 mL and a FA-C'Dot concentration of 25 μ M. The ratio of FA-C'Dot to cleavable exatecan was precisely controlled to obtain the desired number of cleavable exatecan per particle, and typically can range from 1:10 to 1:60. For a typical ratio of 1:40, cleavable exatecan was dissolved in DMSO to a concentration of 0.04 M, and 15 mL of the cleavable exatecan/DMSO solution was added into the reaction. After stirring overnight at room temperature, the reaction mixture was purified to obtain FA-CDC.

[0246] The number of exatecan payloads attached onto each NDC, e.g., folic acid (FA)-functionalized drug-linker conjugated C'Dot (FA-CDC), may be characterized by UV-Vis. A representative UV-Vis absorbance spectrum is shown in FIG. 5. The number of exatecan payloads on each C'Dot can be calculated using the extinction coefficient of C'Dot and Exatecan at 360 nm after the subtraction of the absorption of Folic Acid at the same wavelength.

[0247] As stated above, a nanoparticle may be functionalized with a folate receptor targeting ligand and a payload-linker conjugate in any order (e.g., the protocol outlined above for functionalizing the nanoparticle with exatecan may be carried out prior to the protocol for conjugating folic acid).

[0248] *Particle Size Determination:* The average diameter of NDCs can be measured by any suitable methods, such as, but not limited to fluorescence correlation spectroscopy (FCS) (FIG. 6) and gel permeation chromatography (GPC) (FIG. 7).

[0249] FCS detects the fluorescence fluctuation resulted from particle diffusion through the focal spot on the objective. Particle diffusion information is then extracted from the autocorrelation of signal intensity fluctuations, from which the average hydrodynamic particle size can be obtained by fitting the autocorrelation curve using a single-modal FCS correlation function. The average hydrodynamic diameter of NDC was about 6 nm to about 7 nm (FIG. 6).

[0250] GPC is a type of molecular sieving chromatography, where the separation mechanism is based on the size of the analyte (here NDC's). The elution time of NDC is compared to a series of proteins with varying molecular weight. The results suggest that the elution time of NDC's is comparable to that of protein standards with molecular weight between 158 kDa and 44 kDa, consistent with the particle size average hydrodynamic size of about 6.4 nm (FIG. 7).


[0251] *Purity Analysis:* The purity of NDCs was analyzed using reverse phase HPLC (RP-HPLC). RP-HPLC is coupled to a photodiode array detector, using a commercially available Waters Xbridge Peptide BEH C18 column. RP-HPLC separates molecules with different polarities and is suitable as an analytical method for NDCs because of its ultrasmall sub-10 nm particle size. Using RP-HPLC, the nanoparticles are well separated from aggregates and other chemical moieties such as targeting ligands that are non-covalently associated with the nanoparticles and degraded products. Different chemical moieties are identified based on their elution time and unique UV/Vis spectra. The photodiode array detector collects UV-Vis spectra from 210 to 800 nm, and impurities of interest are measured at 330 nm. A representative chromatogram shown for the NDCs in FIG. 8, suggests that the purity of NDCs of the present disclosure is higher than 99.0 %.



Example 4: Drug-Release Assays

[0252] NDCs of the present disclosure comprise a linker-payload conjugate, e.g., a protease-cleavable linker, such as cathepsin-B (Cat-B) cleavable linker. Upon contact with a protease, the NDCs may release the payload (i.e., exatecan). The drug-releasing profile and the stability of linker-drug conjugates on the nanoparticle were tested according to the following protocols.

[0253] The NDCs were prepared using methods described in Example 3, and then incubated under the desired releasing conditions for release kinetics tests. The NDCs tested in the assay are provided in Table 2 below.

Table 2: Exemplary NDCs used in drug-release assays.

NDC	Exatecan-Linker Conjugate Structure
B	

NDC	Exatecan-Linker Conjugate Structure
C	
D	 (prepared from 202, Example 1)

[0254] Number of FA ligands per particle is between 12 and 22; Number of linker-drug conjugates per particle is between 17 and 25. Each payload-linker is conjugated to the NDC via a DBCO moiety (prepared according to the protocol outlined in Example 3).

[0255] Exatecan exhibits an absorption maximum at a wavelength of around 360 nm (FIG. 9), and this signal can be used to trace the payloads in high-performance liquid chromatography (HPLC) for releasing and stability studies. The amount of released drugs vs non-released drugs was measured using reverse phase HPLC by analyzing the area under curve (AUC) (FIG. 10A and FIG. 10B).

[0256] General Method: A Waters Xbridge Peptide BEH C18 column with 4.6 mm × 50 mm dimensions, a particle size of 5 μm, and a pore size of 300 Å was used (part number 186003622). Acetonitrile (VWR HiPerSolv Chromanorm, UHPLC Grade) was used as received without further preparation, 0.01% trifluoroacetic acid in deionized water was prepared by adding 1 mL of trifluoroacetic acid (HPLC grade, Millipore-Sigma) into 999 mL 18.2 MΩ•cm deionized water that was generated using an IQ7000 Millipore deionized water system and passed through a 0.2 μm filter before use. The seal wash used for the system was composed of 90% 18.2 MΩ•cm deionized water and 10% methanol (HPLC grade, VWR). The injection needle was washed using a mixture of 25 vol% 18.2 MΩ•cm deionized water, 25 vol% acetonitrile, 25 vol% methanol, and 25 vol% 2-propanol. Samples were prepared in a concentration range of 0.25 to 2 μM and the injection volume ranges from 60 μL to 10 μL, respectively. Higher sample concentration can be used if detector signal is low. Vials used for all injections are fresh Waters Total Recovery vials with screw caps that have pre-slit PTFE septa (part number 186000385C).

[0257] Before any sample injections were started, the PDA lamp was turned on and allowed to warm up for at least 30 minutes. The system and column were equilibrated with 95% 0.01% TFA in deionized water, 5% acetonitrile for at least 10 minutes at a flow rate of 1.0 mL/min after the PDA lamp had warmed up. Two blank injections, with injection volumes of 10 μ L containing only 18.2 M Ω •cm deionized water, were performed before the injection of any samples for analysis. The gradient used began at 95% 0.01% TFA in deionized water and 5% acetonitrile and linearly changed to 15% 0.01% TFA in deionized water, 85% acetonitrile over 8 minutes. Acetonitrile composition was increased to 95% over an additional minute and held at 95% for an additional 2 minutes to ensure that any strongly retained compounds are eluted. The composition of the solvent was then changed back to the starting composition of the gradient over an additional minute and allowed to equilibrate for 3 minutes before another injection began. Between sample injections a blank injection was run to ensure that no carryover occurred.

[0258] For a typical cathepsin B (Cat-B) protease cleaving study, 2 μ L, 0.33 μ g/ μ L of Cat-B (sigma Aldrich) was first added with 300 μ L of activation buffer (25 mM MES, 5 mM DTT, pH 5.0), forming 2.2 μ g/mL of Cat-B. The mixture was kept at room temperature for 15 min before use. After activation, 100 μ L of 2 μ M drug-nanoparticle-conjugate was mixed with 100 μ L of activated Cat-B. The mixture was then transferred to 37 $^{\circ}$ C. To monitor the cleaving kinetics, at selected post-incubation time points (e.g., 2, 4, 24 h), 10 μ L of mixture was sampled and injected in HPLC (TFA/acetonitrile). For the analysis of cleaving data, Empower 3 ApexTrack integration was used to determine peak areas for all relevant components.

[0259] The RP-HPLC chromatograph of three representative NDCs (NDC B, NDC C, and NDC D) at different time points after incubation with cathepsin-B is depicted in FIGS. 11A-11C, respectively. The time for half of the payloads to be released from each NDC, *i.e.*, $T_{1/2}$, under the specific experimental condition was analyzed by fitting and is depicted in FIGS. 12A-12C respectively. FIG. 12A depicts the $T_{1/2}$ as 2.9 hours for NDC B. FIG. 12B depicts the $T_{1/2}$ as 2.6 hours for NDC C. FIG. 12C depicts the $T_{1/2}$ as 1.4 hours for NDC D.

[0260] *Stability Test:* To assess the drug releasing profile and stability of the linker-drug conjugates under non-cleavage conditions, an exemplary NDC was incubated in phosphate-buffered saline (PBS) buffer or animal serum at 37 $^{\circ}$ C. The NDC was prepared according to Example 3, using the exatecan-linker conjugate precursor 202 from Example 1)

[0261] For a typical stability test in PBS buffer, 600 μ L of PBS mixture (drug-nanoparticle-conjugate concentration was kept at 2 μ M, while the volume percentage of PBS was kept as 50%) was prepared and kept at 37 $^{\circ}$ C. To monitor the stability of

the linker-drug conjugates attached to nanoparticles, at selected post-incubation time points (e.g., 4, 24, 48 and 72 h), 10 μ L of mixture was sampled and injected in HPLC (TFA/acetonitrile). For the analysis of cleaving data, Empower 3 ApexTrack integration is used to determine peak areas for all relevant components.

[0262] For a typical stability test in plasma from varied species (e.g., mouse, rat, dog, monkey and human), 600 μ L plasma mixture (drug-nanoparticle-conjugate concentration was kept at 2 μ M, while the volume percentage of plasma was kept as 62.5%) was prepared and kept at 37 °C. To monitor the stability of linker-drug conjugates, at selected post-incubation time points (e.g., 4, 24, 48 and 72 h), 80 μ L of mixture was first mixed with 80 μ L of cold acetonitrile, and then went through 30 min of centrifugation at 10,000 rpm. After removal of the proteins, 60 μ L of supernatant was carefully sampled and injected in HPLC. For cathepsin-B-cleavable NDC, TFA/acetonitrile was used. For the analysis of stability data, Empower 3 ApexTrack integration was used to determine peak areas for all relevant components.

[0263] The linker-payload conjugate of the NDC (as prepared in Example 3, using the exatecan-linker conjugate precursor 202 from Example 1) is stable, as 5% of less of the exatecan was released from the linker drug conjugate after 24 hours under non-cleavage conditions, *i.e.*, when maintained in PBS, human serum, or mouse serum.

Example 5: *In Vitro* Flow Cytometry Cell Binding Study

[0264] Cell-binding activity of the NDCs disclosed herein was tested according to the following protocols. NDCs used were prepared according to Example 3, using the exatecan-linker conjugate precursor 202 of Example 1. The amount of folic acid per nanoparticle, and the amount of exatecan per nanoparticle, could be adjusted according to the protocol outlined in Example 3.

[0265] *Cells and Cell Culture:* Human KB cell line, SKOV-3 cells and TOV-1 12 cell line were purchased from ATCC. I-GROV1, human ovarian carcinoma cell line was purchased from EMD Millipore. Cells were maintained in Folic Acid free RPMI 1640 media/10% FBS, and 1% of penicillin/streptomycin, unless otherwise specified. Cancer cells were cultured in folic acid-free medium (RPMI1640, ThermoFisher, GIBCO) for at least one week before the study. Cell binding studies were performed by incubating 5x10⁵ cells (total of 500 μ L, 1 Million/mL) in cold PBS (with 1% of BSA) with FA-CDC prepared in Example 3 (concentration: 1 nM) for 60 min at 4°C (n=3). After that, the cell suspension was stained with viability kit (LIVE/DEAD™ Fixable Violet Dead Cell Stain Kit, Thermo Fisher) for 10-15 min. Then, cells were centrifuged (2000 rpm, 5 min), washed (2-3 times) using cold PBS (with 1% of BSA) before resuspending in PBS (with 1% of BSA). Triplicate samples were analyzed on a LSRFortessa flow cytometer (BD Biosciences) (Cy5 channel, 633 nm/647 nm,

Live/dead cell stain, 405 nm). Results were processed using FlowJo and Prism 7 software (GraphPad).

[0266] The competitive binding study (FIG. 13) was performed using the NDC of Example 3. The active targeting of NDC can be fully blocked by incubating with the presence of 1 mM free Folic Acid.

[0267] The competitive binding study shows >40-fold enhancement in binding capability of the NDC when compared with free folic acid, demonstrating the presence of a multivalent effect when conjugating multiple folic acid ligands on each ultrasmall C'Dot (FIG. 13).

[0268] These results demonstrate the advantages of conjugating multiple small tumor-directing ligands on the surface of nanoparticle (C'Dots) for enhancing the targeting capability using the multivalent effect. The folate receptor targeting can be blocked by competitive binding of free folic acid, such as by incubating with the presence of 1 mM free Folic Acid.

[0269] The flow cytometry shows comparable folate receptor targeting efficacy of two NDC formulations with varied folic acid ligand density, in KB cell line. The linker-exatecan conjugate precursor used to prepare the NDCs in this study is described in Example 1 (Compound 202). The blocking group has 1 mM of free Folic Acid. (**FIG. 14**).

[0270] The results demonstrated dramatic increase (>300-fold of MFI) in folate receptor- α active targeting when the folic acid ligand density was increased from zero to 12 (i.e., 12 folic acid molecules per nanoparticle), while little difference was observed upon further increasing that density to 25 folic acid molecules per nanoparticle.

[0271] The flow cytometry shows comparable folate receptor targeting efficacy of three NDCs in KB cell line with varied drug per particle (DPR) (i.e., number of exatecan molecules per nanoparticle). The blocking group involved blocking receptors with 1 mM of free folic acid. The NDCs with different ratios of exatecan per nanoparticle were prepared using Compound 202 described in Example 1, and the results of the study are provided in **FIG. 15**. All FA-CDCs comprise between 12 and 22 folic acid moieties. FA-CDCs with high drug-particle ratio (DPR) comprise between 35 and 50 exatecan-linker conjugate groups. FA-CDCs with medium DPR comprise between 17 and 25 exatecan-linker conjugate groups. FA-CDCs with low DPR have between 5 and 10 exatecan-linker conjugate groups.

[0272] These results together with the nearly unchanged FCS sizing changes of the three NDCs demonstrate the robust surface chemistry and maintained folate receptor

targeting capability of NDCs disclosed herein, which is surprisingly not perturbed by altering the loading capacity of payload and demonstrates a significant advantage of the NDCs disclosed herein over other drug delivery platforms.





[0273] Pre-incubating NDCs in human plasma did not negatively affect folate receptor targeting ability. This study was designed to test the possible negative impact of human plasma on the NDCs, such as the formation of protein corona. The formation of protein corona and its negative impact on the designed active targeting capability of drug delivery system has been well documented in the literature. The results of this flow cytometry study are depicted in FIG. 16, which show nearly unchanged folate receptor targeting efficacy of NDCs at 1 nM, after pre-incubation with varied amounts of human plasma for 24 hours. The NDCs were prepared according to the method of Example 3, using the exatecan-payload conjugate precursor of Example 1 (Compound 202). The blocking group involved blocking with 1 mM of free folic acid. This study clearly demonstrated that the formation of a protein corona (if any) on the NDC had nearly no negative impact on the *in vitro* targeting capability of the NDCs.






Example 6: *In vitro* Cell Viability Assay:



[0274] The *in vitro* cytotoxicity of the NDCs disclosed herein were tested in cancer cells. The cancer cells were cultured in folic acid-free medium (RPMI1640, ThermoFisher, GIBCO) for at least one week before the study. Cells were plated in opaque 96-well plates at a density of 3×10^3 cells per well (total of 90 mL) and allowed to attach overnight. The following day, cells were treated with NDC (prepared according to Example 3) at a concentration range of 0-50 nM (0, 0.001, 0.005, 0.01, 0.05, 0.1, 0.5, 1, 5, 10, 50 nM) by adding 10 mL of 10× stock FA-CDC solution.

[0275] Cells were treated for a pre-defined exposure time (depending on the study design, e.g., 4-6 hours, or 7 days). In the case of short-exposure-time viability study, cancer cells in each wells were washed with 100 mL PBS and refreshed with 100 mL of cell medium. After washing, the plates were returned back to 37 °C incubator for 7 days before the viability assay. In the case of 7-day-exposure-time viability study, no additional washing step was performed. After 7 days, the cell viability was assessed using the CellTiter-Glo2.0 assay (Promega) according to manufacturer's instructions. Data for both viability and proliferation were plotted using Prism7 software (GraphPad). Representative cell viability results of six FA-CDCs with similar surface density of Folic Acid targeting ligands and drug linkers is presented in provided in Table 3.

Table 3. Representative cell viability results of NDCs with similar surface density of folic acid targeting ligands and linker-drug conjugates.

Payload-Linker Conjugate	IC ₅₀ in KB cell line (nM)	IC ₅₀ in SKOV-3 cell line (nM)
	0.2 - 5.2	10.7
	0.5 - 1.0	17.9
	0.7 - 7.2	n.t.
	17.5	n.t.

Payload-Linker Conjugate	IC ₅₀ in KB cell line (nM)	IC ₅₀ in SKOV-3 cell line (nM)
	0.2 - 2.2	0.4
	5.2	n.t.
	72.2	n.t.
	42.7	n.t.
	0.6	0.9

Payload-Linker Conjugate	IC ₅₀ in KB cell line (nM)	IC ₅₀ in SKOV-3 cell line (nM)
	49.4	n.t.
 (prepared from 202, Example 1)	0.3	0.13

[0276] Number of FA ligands per particle is between 12 and 22; Number of linker-drug conjugates per particle is between 17 and 25. Each payload-linker is conjugated to the NDC via a DBCO moiety (prepared according to the protocol outlined in Example 3).

Example 7: Two-dimensional (2D) Confocal Imaging of NDC in Cancer Cells



[0277] A 2D confocal imaging study was carried out to determine the targeting of cells with varying levels of folate-receptor availability, using two exemplary NDCs. The cells with high folate-receptor expression (denoted +++) were KB cells. The cells with no FR expression (denoted (-)) were TOV-112D cell line. FR-blocked cells were also used.

[0278] KB cells were maintained in folic acid free RPMI 1640 media with 10% FBS, 1% penicillin/streptomycin. TOV-112D cells were maintained in 1:1 mixture of MCDB 105 medium containing a final concentration of 1.5 g/L sodium bicarbonate and Medium 199 containing a final concentration of 2.2 g/L sodium bicarbonate, supplemented with 15% FBS and 1% penicillin/streptomycin. Cells were trypsinized and seeded in 8-well Lab-Tek chambered coverglass, at 1.0×10^5 cells per well, and cultured overnight to allow for attachment.

[0279] The NDCs were prepared according to Example 3 and are displayed below in

Table 4. NDC D was prepared using the linker-payload conjugate (**202**) described in Example 1.

Table 4. Exemplary NDCs used in 2D Confocal Imaging Assay.

NDC	Exatecan-Linker Conjugate
B	
D	 (prepared from 202, Example 1)

[0280] Before incubation with NDC, cells were washed once with folic acid free RPMI 1640 media. The NDC was added into folic acid free RPMI 1640 media to final concentration of 50 nM. For blocking conditions, folic acid (20 mM stock dissolved in 0.1 M NaOH) was added to final concentration of 0.1 mM and co-incubated with NDC. Cells were incubated with NDC at 37 °C for either 1 hours or 24 hours. After incubation, cells were washed three times. To stain lysosomes, LysoTracker Green DND-26 (Thermo Fisher Cat. L7526, ex/em504/511 nm) was added to final concentration of 100 nM in folic acid free RPMI 1640 media with 10% FBS, 1% P/S, and incubated at 37 °C for 45 min. Cells were washed once to remove remaining lysotracker dyes. To stain nuclei, Hoechst 33342 solution (Thermo Fisher Cat.62249, 20 mM) was diluted 1:4000 in Folic Acid free RPMI 1640 media with 10% FBS, 1% P/S, and incubated at 37 °C for 10 min. Cells were washed once, and media was exchanged to phenol red free RPMI 1640 media for confocal imaging using Nikon spinning disk confocal microscope, 60x objective, 405 nm, 488 nm, 640 nm laser lines, exposure time 100 ms for 405 channel, 500 ms for 488 channel, and 600 ms for 640 channel.

[0281] Results from confocal microscope imaging of NDC in KB (++++) and TOV-1 12D(-) cell lines at 1 hour time point showed that NDC were mainly present at the cell membrane of KB cells, which express high level of folate receptors, but not in blocking

conditions or folate negative cell line TOV-112D, suggesting specific binding of NDC to folate receptors. After 24 hours, membrane bound NDC were internalized and the amount of internalized NDC significantly increased as compared with 1 hour time point. The internalized NDC were localized in acidic organelles stained by LysoTracker, indicating that the trafficking of NDC occurred through the endo-lysosomal pathway. The effect of serum on the binding capability of NDC was also investigated by pre-incubating NDCs in media supplemented with 10% FBS overnight, prior to incubating them with cells, and no significant difference was observed (data not shown), suggesting that the presence of serum had no impact on the binding capability of NDCs.

[0282] These results of confocal microscopy of NDC B are provided in FIG. 17, and results for NDC D are provided in FIG. 32. These images demonstrated the highly specific active targeting and lysosome trafficking of the NDCs of the present disclosure, indicating that once the FA-targeting NDCs bind to cells they become internalized in folate receptor positive cell lines, where the exatecan payload may be cleaved (e.g., by cathepsin-B) to release free exatecan in the cancerous cell.

Example 8: Confocal imaging of FA-CDC in 3D tumor spheroid model in KB Cells

[0283] A 3D tumor spheroid model assay was conducted to determine the tumor penetration of the NDCs disclosed herein. The assay compared an exemplary NDC (prepared according to Example 3, using exatecan-linker conjugate precursor 202 of Example 1), with a payload-free FA-targeting nanoparticle (also prepared according to Example 3, with only the FA precursor and without exatecan-payload conjugate precursor); a folate receptor (FR)-targeting ADC; and the corresponding payload-free FR-targeting antibody. The FR-targeting antibody was prepared based upon the published sequence of mirvetuximab (provided in U.S. Patent No. 9,637,547 as huMov19). The ADC was prepared with the same antibody and was conjugated to the maytansinoid drug DM4 (created by Syngene International Ltd.) via a 4-(pyridin-2-yl)disulfanyl-2-sulfo-butyric acid (sSPDB) linker (based on the linker used in U.S. Patent No. 9,637,547). The ADC and antibody were each conjugated with Cy5 organic dye, by reaction with Cy5-NHS ester, and were purified by a PD-10 column.

[0284] Corning ultra-low attachment surface 96-well spheroid microplates were utilized in seeding KB cells for having KB spheroids with cell density 10,000 / well. Single-cell suspensions were generated from trypsinized monolayers and diluted to 100,000 cells/mL using RPMI medium (folic acid free). 100 μ L of cell suspension were dispensed into each well of a microplate. The plate was kept in an incubator for 24 hours for cells forming spheroids. KB cell spheroids can be easily observed by microscope with 10X objective.

[0285] 3D KB spheroids formed after overnight culturing in an ultra-low 96-well microplates. NDC (prepared according to Example 3, using exatecan-linker conjugate precursor 202 of Example 1), folate-targeted nanoparticles ("FA-C'Dot"), FR-targeted ADC, or payload-free FR-targeted-antibody were added into wells (n=3) with 50 nM final concentration and incubated for 4 hours at 37 °C. Each treated KB spheroid and control spheroid were washed with PBS for three times and then carefully transferred to a glass bottom 96-well plate (Cellvis) for observation by Nikon A1R-STED confocal microscope, using laser line 640 nm, 20 X objective. Z-stacks were acquired by taking 2-dimensional images each separated by 1 µm in the Z-direction.

[0286] Results from the Z-stack confocal microscope imaging of KB tumor spheroid treated with the NDC, FA-C'Dot, FR-targeted ADC, and payload-free FR-targeted antibody is depicted in FIG. 18. The results show that the penetration and well diffusion of NDC and FA-C'Dots throughout the whole >800 nm of tumor spheroids. In contrast, labeled antibody and ADC merely accumulated around, but not inside of, the tumor spheroids. The ability of the NDCs disclosed herein to achieve efficient tumor penetration is highly advantageous, and shows significant improvement compared to conventional drug delivery platforms.

Example 9: ⁸⁹Zr Radiolabeling of DFO-FA-CDC and *In vivo* Static PET/CT and Biodistribution Studies

[0287] A radiolabeling assay was conducted to determine the *in vivo* biodistribution of the folate receptor-targeting NDCs of the present disclosure. The NDCs used for the assay were conjugated with the chelator desferrioxamine (DFO) and then bound with a radionuclide (⁸⁹Zr).

[0288] For a typical ⁸⁹Zr labeling, about 1 nmol of DFO-conjugated NDC were mixed with 1 mCi of ⁸⁹Zr-oxalate (produced and provided by University of Wisconsin-Madison Cyclotron group) in HEPES buffer (pH 8) at 37 °C for 60 min; final labeling pH was kept at 7-7.5. The labeling yield could be monitored by using radio instant thin-layer chromatography (iTLC). An ethylenediaminetetraacetic acid (EDTA) challenge procedure was then introduced to remove any nonspecifically bound ⁸⁹Zr from the particle surface. As-synthesized labeled NDC (⁸⁹Zr-DFO-FA-CDC) were then purified by using a PD-10 column. The final radiochemical purity was quantified by using iTLC.

[0289] For PET/CT imaging, healthy nude mice (n = 3) were i.v.-injected with 200-300 µCi (7.4-11.1 MBq) ⁸⁹Zr-DFO-FA-CDC. Approximately 5 min prior to the acquisition of PET/CT images, mice were anesthetized by inhalation of 2% isoflurane/oxygen gas mixture and placed on the scanner bed; anesthesia was maintained using 1% isoflurane/gas mixture. PET/CT imaging was performed in a small-animal PET/CT scanner (Inveon microPET/microCT) at 1-2, 24, 48, and 72 h

post-injection. An energy window of 350-700 keV and a coincidence timing window of 6 ns were used. Data were sorted into 2D histograms by Fourier rebinning, and transverse images were reconstructed by filtered backprojection into a $128 \times 128 \times 63$ ($0.72 \times 0.72 \times 1.3$ mm³) matrix. The PET/CT imaging data were normalized to correct for nonuniformity of response, dead-time count losses, positron branching ratio, and physical decay to the time of injection; no attenuation, scatter, or partial-volume averaging corrections were applied. The counting rates in the reconstructed images were converted to activity concentrations (percentage injected dose per gram of tissue, % ID/g) by use of a system calibration factor derived from the imaging of a mouse-sized water-equivalent phantom containing ⁸⁹Zr. Region-of-interest (ROI) analyses of the PET data were performed using IRW software. At 72 h post-injection, organs from each individual mouse were collected, wet-weighted and gamma counted (Automatic Wizard2 γ -Counter, PerkinElmer). The uptake of ⁸⁹Zr-DFO-FA-CDC was presented as % ID/g (mean $\pm$ SD).






[0290] The NDCs of the present disclosure enable precise tumor targeting, deep tumor penetration and high tumor killing efficacy. The NDCs can be cleared rapidly and efficiently from the body, which reduces the potential for off-target toxicities and results in an improved safety profile. The NDCs disclosed herein (comprising targeting ligands (folic acid) and payload (exatecan)) can be administered to a subject and circulate through the blood stream, target the cancer (e.g., tumor), diffuse, penetrate, internalize, and cleave the exatecan payload, killing the cancer cells.


[0291] In this study, the renal clearance and biodistribution pattern of FA-CDC were tested. As shown in FIG. 19A, after the intravenous injection, the ⁸⁹Zr-DFO-FA-CDC circulated in the blood stream of healthy nude mouse, as indicated by the high radioactive signal from the heart and artery. Dominant radioactive signal can also be seen from the mouse bladder, demonstrate the renal clearance of the NDC. After 24 h, the majority of the injected ⁸⁹Zr-DFO-FA-CDC was cleared out of the mouse body. The changes in biodistribution pattern at 2 hours and 24 hours post-injection is also shown in FIG. 19B. As expected, the NDC can circulate in the blood stream with a dominant renal clearance pathway, whilst avoiding clearance by the mononuclear phagocytic system (MPS) (i.e., liver and spleen).

Example 10: Human KB Tumor Model and *in vivo* Efficacy Study

[0292] The *in vivo* efficacy of the NDC was carried out using a human KB tumor mouse model. The assay compared the NDC prepared according to Example 3 using the exatecan-payload conjugate precursor 202 (Example 1; here labeled D, and shown in FIG. 20D, with the NDCs indicated in Table 5 below (NDCs A-C and E-F). Each NDC was compared to a control and free exatecan, and NDCs E and F were compared to free exatecan and irinotecan (CPT-11).

Table 5. Exemplary NDCs used in the *in vivo* efficacy study.

NDC	Payload-Linker Conjugate
A	
B	
C	
D	 (prepared from 202, Example 1)
E	

NDC	Payload-Linker Conjugate
F	

[0293] Number of FA ligands per particle is between 12 and 22; Number of linker-drug conjugates per particle is between 17 and 25. Each payload-linker is conjugated to the NDC via a DBCO moiety (prepared according to the protocol outlined in Example 3).

[0294] Human KB cell line was purchased from ATCC and maintained in folic acid free RPMI 1640 media/10% FBS, and 1% of penicillin/streptomycin, unless otherwise specified. Once the KB cells were cultured to reach an adequate cell count, the cell viability was confirmed by a hemocytometer and trypan blue staining assay. For subcutaneous implantation, each mouse was injected with KB cells at a density of 2×10^6 cells/mice at 0.1 mL Matrigel/cell dilution volume per injection on the left lower flank of the thigh. Once a subcutaneous tumor volume has reached a palpable size of 75 to 150 mm³ in a required number of mice for this study, the mice was randomized and assigned to each treatment cohort resulting with comparable tumor volume statistics. Following randomization and study cohort assignment, each dose cohort was treated according to the routes of administration, dosage and schedule.

[0295] Two dose levels of each of NDCs B-D were used in the efficacy study (only one dose level for NDCs A, E and F). Tumor volume measurements were performed using a calibrated caliper every second day during the dose treatment period, followed by twice weekly measurements during the recovery period of the in-life phase, and tumor volumes were determined using the formula length (mm) $\times$ width (mm) $\times$ width (mm) $\times$ 0.50. Body weight measurements were performed every second day during the dose treatment period, followed by twice weekly measurements during the recovery period of the in-life phase. Mice were euthanized when the end points of the study reached 1000 mm³. Tumors were harvested and tumor size was measured. Tumor were surgically excised and snap-frozen for storage at -80 °C until future analysis.

[0296] FIGS. 20A-20F depicts the *in vivo* tumor growth inhibition studies of the six folate receptor-targeting NDCs in KB tumor-bearing mice (n=7). The tumor growth charts depicted for the *in vivo* efficacy study shows a clear response of tumor growth

inhibition in mice treated with the NDC prepared according to Example 3 using the exatecan-payload conjugate precursor 202 (from Example 1), which is shown in FIG. 20D. Similarly, growth inhibition was observed in NDC A (FIG. 20A), NDC B (FIG. 20B), and NDC C (FIG. 20C). In contrast, mice treated with NDC E (FIG. 20E), and NDC F (FIG. 20F) showed no significant inhibition in tumor growth. Doses for the NDCs are provided in FIGS. 20A - 20F. Clear response of tumor growth inhibition was observed in mice treated with NDCs A-D. Control group mice received normal saline follow the same Q3DX3 dose regimen.

Example 11: Activity of NDCs in Drug-Resistant Cell Lines

[0297] An assay was carried out using the NDCs disclosed herein to determine their activity in drug-resistant cancer cells (specifically, irinotecan-resistant KB cells and exatecan-resistant KB cells). The NDCs used in this assay were prepared according to Example 3, using the exatecan-linker conjugate precursor 202 (from Example 1).

Development of TOP1 inhibitor-resistant folate receptor alpha positive cancer cells.

[0298] Naive human KB cell line were purchased from ATCC and maintained in folic acid free RPMI 1640 media/10% FBS, and 1% of penicillin/streptomycin. To develop the TOP1 inhibitor resistant KB cells, the cells in flask (50-60% confluence) were repeatedly treated with increasing concentration of exatecan, topotecan, SN-38 or irinotecan for over 4 months. The starting TOP1 inhibitor treatment concentration was close to the KB cell's IC₉₀ values. After each treatment, the cells were carefully washed with fresh RPMI 1640 media and left to proliferate for an additional 2-3 days until reaching 50-60% confluence. The next round of TOP1 inhibitor treatment was started with 2-10X higher TOP1 inhibitor concentration.

Resistant factor and IC₅₀ assay.

[0299] Both naive and TOP1 inhibitor resistant KB cell were cultured in folic acid-free medium (RPMI1640, ThermoFisher, GIBCO). Cells were plated in opaque 96-well plates at a density of 3×10^3 cells per well (total of 90 μ L) and allowed to attach overnight. The following day, cells were treated with selected TOP1 inhibitors (e.g., free exatecan) or NDC at suitable concentration ranges. After exposing the TOP1 inhibitors with both types of cells for the same period of time, the cell viability was assessed using the CellTiter-Glo2.0 assay (Promega) according to manufacturer's instructions. Data for both viability and proliferation were plotted using Prism7 software (GraphPad). The resistant factor can be calculated by using the following

equation:

$$\text{Resistant factor} = \frac{IC_{50} \text{ of resistant KB cell}}{IC_{50} \text{ of naive KB cell}}$$

Irinotecan-resistant KB cell line and potency test of NDC

[0300] FIG. 21A shows the IC₅₀ curves of irinotecan in both naive and resistant KB cells, which demonstrates the successful development of 5X irinotecan-resistant KB cells, where IC₅₀ free irinotecan in irinotecan-resistant KB cells was 3,618 nM, compared to 668 nM in naive cells. FIG. 21B provides the IC₅₀ curves of the NDC (FA-CDC) (prepared according to Example 3, using the exatecan-linker conjugate precursor 202 of Example 1) in the naive KB cells (IC₅₀ = 0.27 nM) and resistant KB cells (IC₅₀ = 0.26 nM), indicating the NDC has a high potency that is uniform across both naive KB cells and TOP1 inhibitor-resistant KB cells.

Exatecan-resistant KB cell line and potency test of NDC

[0301] FIG. 22A shows the IC₅₀ curves of exatecan in both naive and resistant KB cells, which demonstrates the successful development of >8X exatecan-resistant KB cells, where IC₅₀ of exatecan in regular KB cells was 2 nM, compared with 4 nM in KB cells pretreated 4x with exatecan, and 16.9 nM in KB cells pretreated 7x with exatecan. FIG. 22B shows the IC₅₀ curves of the NDC (FA-CDC) (prepared according to Example 3, using the exatecan-linker conjugate precursor 202 of Example 1) in both naive and resistant KB cells (4x or 7x pretreatment), where the IC₅₀ of the FA-CDC was 0.27 nM, 0.28 nM, and 0.30 nM, respectively. The results indicated the NDC possesses high potency uniformly in both the naive and resistant KB cells.

Example 12: Activity of NDCs in cancer cells with varied folate receptor expression levels

[0302] An assay was conducted to determine the cytotoxicity of exemplary NDCs (FA-CDCs), with varying levels of drug-to-particle ratio, in different FR-alpha overexpressing cancer cell lines, compared to non-conjugated exatecan. The NDCs were prepared according to Example 3, using the payload-linker conjugate precursor 202, of Example 1. The NDCs (FA-CDCs) tested had a drug-to-particle ratio (DPR) of 43, 20, 8, and 1 (i.e., 43, 20, 8, and 1 exatecan-linker groups per nanoparticle).

[0303] Cancer cells with varied FR alpha expression levels (KB (++++), IGROV-1(++), SK-OV-3(++), HCC827(++), A549(-), and BT549(-)) were cultured in folic acid-free medium (RPMI1640, ThermoFisher, GIBCO) for at least one week before the study. Assays for 7-day exposure and 6-hour exposure were both conducted.

[0304] Cells were plated in opaque 96-well plates at a density of 3×10^3 cells per well (total of 90 μ L) and allowed to attach overnight. The following day, cells were treated with NDC with varied drug-to-particle ratio (DPR) at a concentration ranging from 0-50 nM (0, 0.001, 0.005, 0.01, 0.05, 0.1, 0.5, 1, 5, 10, 50 nM) by adding 10 μ L of 10x stock compounds.

[0305] For the 6-hour exposure viability study cells were treated for 6 hours and washed (3x) with 100 μ L PBS. 100 μ L of fresh cell medium was then added to each well and the plate was incubated for an additional 7 days at 37°C before performing the CellTiter-Glo[®] cytotoxic assay (Promega) according to manufacturer's instructions. The results of the 7-day exposure assay are presented in **FIG. 23**, which demonstrate that the NDC was highly potent across all cell lines, despite differing levels of FR expression in the cells.

[0306] For the 7-day exposure viability study, the cells were incubated with compounds for the entire 7-day period, followed by the CellTiter-Glo[®] cytotoxic assay. Data for half maximal inhibitory concentration (IC₅₀) was plotted using Prism7 software (GraphPad). The results of the 6-hour exposure assay are presented in **FIG. 23**, which demonstrate that the NDC was highly potent across all cell lines, despite differing levels of FR expression in the cells.

Example 13: Cytotoxicity of NDCs in Patient-Derived Pt-Resistant Tumor Cell Lines

[0307] An assay was conducted to establish the cytotoxicity of an exemplary NDC (prepared according to Example 1, using the exatecan-linker conjugate precursor Compound 202 from Example 1) in various patient derived tumor cell lines that are Pt-resistant, with comparison to non-conjugated exatecan. Cell lines were obtained from ovarian cancer, non-small cell lung cancer (NSCLC), breast cancer (both HR+, HER2+; and HR-, HER2+; and triple negative breast cancer (TNBC)), endometrial cancer, and head and neck (H&N) cancers. The results of the assay are provided in **FIG. 24**.

[0308] The cytotoxic efficacy was determined by Kiyatec using the KIYA-PREDICT[™] assay. The FR α immunohistochemistry (IHC) scoring of tumor tissue from platinum-resistant ovarian, endometrium, non-small cell lung, breast, triple-negative breast, head & neck cancer patients were conducted by XenoSTART by using the Biocare Medical FR α IHC Assay Kit (cat # BRI4006KAA), following the manufacturer's protocol. A total of 28 PDX models from different indications were selected based on the IHC scores and provided to Kiyatec for the KIYA-PREDICT[™] assay. Briefly, cryopreserved PDX tumors were thawed and enzymatically dissociated to single cells, and plated into 384-well spheroid microplates (Coming). Flow cytometry was also

performed to assess the FR levels among different PDX models. Following the 24 hours of spheroid formation, NDC or controls were added at the designed concentration range and incubated for 7 days. After that, the cell viability was measured by CellTiter-Glo® 3D (Promega). The data was analyzed in Microsoft Excel and GraphPad Prism.

Example 14: *In vitro* and *in vivo* efficacy of an exemplary NDC in pediatric acute myeloid leukemia models

[0309] Assays were carried out to establish the *in vitro* and *in vivo* efficacy of an exemplary NDC (prepared according to the protocol in Example 3, using the exatecan-linker conjugate precursor 202 from Example 1) in folate-receptor alpha-positive pediatric acute myeloid leukemia models.

***In vitro* flow cytometry cell binding study**

[0310] Cancer cells (IGROV-1 and AML MV4;11 cell lines) were cultured in folic acid-free medium (RPMI1640, ThermoFisher, GIBCO) for at least one week before the study. Cell binding studies were performed by incubating 5×10^5 cells (total of 500 μ L, 1 million/mL) in cold phosphate-buffered saline (PBS) (with 1% of bovine serum albumin (BSA)) with the exemplary NDC or with anti-FR alpha phycoerythrin (PE)-conjugated antibodies (anti-FR alpha antibody-PE) (concentration: 10 nM) for 60 min at 4°C (n=3). A non-targeted CDC and isotype antibody-PE were used as negative controls for the exemplary NDC and anti-FR alpha antibody-PE, respectively. The cell suspension was then stained with viability kit (LIVE/DEAD™ Fixable Violet Dead Cell Stain Kit, Thermo Fisher) for 10-15 min. The cells were next centrifuged (2000 revolutions per minute, 5 min), washed (2-3 times) using cold PBS (with 1% of BSA) before resuspending in PBS (with 1% of BSA). Triplicate samples were analyzed on a LSRFortessa flow cytometer (BD Biosciences) (Cy5 channel, 633 nm/647 nm, Live/dead cell stain, 405 nm). Results were processed using FlowJo and Prism 7 software (GraphPad).

[0311] The flow cytometry histograms of the exemplary NDC and anti-FR alpha antibody-PE compared with the respective negative controls (non-targeted NDC or isotype antibody-PE) are shown in **FIGS. 25A-25D**. The flow study demonstrates the specific FR alpha targeting capability of the exemplary NDC to both the IGROV-1 (FR alpha positive human ovarian cancer) and the AML MV4;11 cell lines.

***In vitro* CellTiter-Glo® cytotoxic assay**

[0312] Cancer cells (IGROV-1 and AML MV4;11 cell lines) were cultured in folic acid-

free medium (RPMI1640, ThermoFisher, GIBCO) for at least one week before the study. Cells were plated in opaque 96-well plates at a density of 3×10^3 cells per well (total of 90 μ L) and allowed to attach overnight. The following day, cells were treated with the exemplary NDC at a concentration ranging from 0-100 nM, by adding 10 μ L of 10 $\times$ stock NDC solution. For the shorter exposure viability study, cells were treated for 4 hours and washed (3x) with 100 μ L PBS. 100 μ L of fresh cell medium without the NDC was then added to each well and the plate was incubated for an additional 5 days at 37°C before performing the CellTiter-Glo[®] cytotoxic assay (Promega) according to manufacturer's instructions. Data for half maximal inhibitory concentration (IC₅₀) was plotted using Prism7 software (GraphPad).

[0313] The *in vitro* specific cytotoxic activity of the exemplary NDC in FR alpha positive human ovarian cancer and MV4; 11 AML cell lines is displayed in **FIGS. 26A-26B**. Cells were treated with the exemplary NDC at the indicated concentrations, incubated at 37 °C for 4 hours, washed, and returned to the incubator for an additional 5 days, before performing the CellTiter-Glo[®] cytotoxic assay.

CBFA2T3-GLIS2 fusion-positive AML cell line-derived xenograft models

[0314] *In vivo* anti-tumor killing activity of the exemplary NDC was assessed in cell line-derived xenograft (CDX) models. NOD scid gamma (NSG) mice were fed with folate free chow for 1 week prior to injection with AML cell lines. Then 1-5 million fusion-positive cell lines (M07e, WSU-AML) and engineered cells (MV4;11 FOLR+) transduced with Luciferase reporter were transplanted into the NSG mice via tail-vein injections. Leukemia burden and response to treatments was monitored using non-invasive bioluminescent imaging (from both the front and the back of the mouse), and flow cytometry analysis of mouse peripheral blood drawn by submandibular bleeds was carried out bi-weekly, starting from the first week of CDC treatment. Mice were monitored for disease symptoms (including tachypnea, hunchback, persistent weight loss, fatigue, and hind-limb paralysis). Mice from the saline control group (Cohort 1) were euthanized due to the high AML burden on Day 44 post-leukemia injection (tissues including blood, bone marrow, thymus, liver, lungs and spleen were harvested at necropsy and analyzed for the presence of leukemia cells). Mice from the treatment groups (Cohorts 2-4) continued to receive weekly bioluminescent imaging and bodyweight monitoring. An illustration of the timeline for mice preparation, treatment, and imaging is provided in **FIG. 31**.

[0315] All the mice were randomized prior to dosing and weighed to provide the correct designed dose based on Table 6 below. Leukemia burden and response to treatments was monitored weekly using non-invasive bioluminescent imaging. Bodyweight was measured every other day. The mice were terminated if their weight loss was over 20%.

Table 6. Dose design (n=5 per group)

Cohort	Material Administered	Study Phase	Dose (mg/kg of Exatecan)	Regimen	IV Dose volume (mL/kg)	Clinical Observations and Study End Points
1	Normal saline	Vehicle control	n/ap	Q3D × 3	10	• Every other day body weight (BW)
2	NDC	escalation	0.33	Q3D × 6	10	
3	NDC	escalation	0.50	Q3D × 3	10	• End point: BW loss >20%
4	NDC	escalation	0.65	Q3D × 3	10	

[0316] FIG. 27 provides the body weight change of AML mice treated with normal saline and the exemplary NDC at the three dose levels indicated in Table 6. The normal saline group (Cohort 1) showed a bodyweight loss within 20%, mainly due to the leukemia burden. In the 0.33 mg/kg (Q3Dx6) dose group (Cohort 2), 4 of 5 mice tolerated the NDC well (<20% loss), and bodyweight was gained after 6 doses; while the remaining mouse showed >20% bodyweight loss after the 5th dose, and more bodyweight loss after the 6th dose. In the 0.50 mg/kg (Q3Dx3) dose group (Cohort 3), all 5 mice tolerated the NDC well (<20% loss), and bodyweight was gained after 3 doses. In the 0.65 mg/kg (Q3Dx3) group (Cohort 4), 2 of 5 mice tolerated the NDC well (<20% loss), and bodyweight was gained after 3 doses, while 3 of 5 mice showed >20% bodyweight loss after the 3rd dose.

[0317] FIG. 28 provides the *in vivo* bioluminescence images (BLI) obtained from the AML mice treated with normal saline or the exemplary NDC at each dose regimen (*i.e.*, Cohorts 1-4 from Table 6). Quantitative *in vivo* bioluminescence imaging analysis of Cohorts 1-4 (*i.e.*, AML mice treated with normal saline or the exemplary NDC at each dose regimen outlined in Table 6) is provided in **FIG. 29**. In the normal saline group (Cohort 1), the leukemia burden continued to progress, with the average whole-body BLI signal increasing >90 fold in 34 days, while a quick and dose-dependent suppression of the leukemia burden was achieved in all 3 treatment groups (Cohorts 2-4). The 0.5 mg/kg (Q3Dx3) dose group (Cohort 3) showed 11-fold less leukemia burden on Day 34 when compared with burden on Day 1 post-leukemia injection. When comparing the 0.33 mg/kg (Q3Dx6) dose group (Cohort 2) with the 0.65 mg/kg (Q3Dx3) dose group (Cohort 4), 0.33 mg/kg was tolerated better with a slightly better response. Taken together, these data indicate the exemplary NDC successfully suppressed the leukemia burden in the FR alpha positive AML mice, and showed quick and dose-dependent response.

[0318] FIG. 30 provides a graph illustrating the results of bone marrow aspiration of Cohorts 1-4 (i.e., the mice treated with normal saline or the exemplary NDC at each dose group indicated in Table 6) on Day 42 post-leukemia injection. Leukemia was detected in the group of mice treated with normal saline (Cohort 1), while no detectable leukemia burden could be observed in any of the mice from the treatment groups (Cohorts 2-4).

Example 15. Stability of Linker Derived from Diene

[0319] In order to determine the stability of NDCs disclosed herein prepared using a diene-based functionalization approach, the stability of NDC prepared using a diene based functionalization approach were compared to NDC prepared using an amine-based functionalization approach.

[0320] The NDCs were incubated in 0.9% saline, PBS, human plasma (10%), and mouse plasma (10%) at 37 °C in a shaking dry bath for different time periods. Prior to analysis, plasma proteins in the samples were removed by precipitation, through addition of an equivalent volume of cold acetonitrile, followed by centrifugation at 10000 rpm in an Eppendorf 5425 microcentrifuge. Following centrifugation, the clear supernatant was transferred from the centrifuge tube into a clear total recovery HPLC vial. The supernatant free of any visible aggregation was diluted with an equivalent volume of deionized water to adjust the sample matrix to match the starting conditions of the HPLC separation and avoid loss of sensitivity. The purity and impurity of each sample is then quantified by RP-HPLC.

[0321] The targeted-NDCs produced using the methods described in Example 3, using the diene-silane precursor exhibited high stability in mouse and human plasma, and showed significant stability improvement, relative to corresponding NDCs produced using an amine-silane precursor (see FIGS. 33A and 33B)). In the NDCs prepared using the diene-silane precursor, more than 95% of exatecan drugs remain on the NDCs for up to 7 days in mouse and human plasma, obtained by the UV-Vis spectra of the NDC peaks in RP-HPLC chromatograms. Meanwhile, an independent RP-HPLC assay monitoring free exatecan suggested that the released exatecan was below detection limit of RP-HPLC, i.e., 0.02%, and the absence of non-desired free drug further demonstrates their high plasma stability. The targeted-NDCs also exhibited high storage stability at 4 °C in 0.9% saline. Their purity, size distribution, and hydrodynamic diameter were characterized by RP-HPLC, SEC and FCS respectively, and remained unchanged over 6 months under storage condition. Such high storage stability is another key parameter important for both clinical translation and commercial manufacture.

Example 16. Pharmacokinetics and Toxicology Study

[0322] The pharmacokinetics and toxicology of an exemplary NDC were assessed in a rat model and in a dog model. The NDC used in this study was prepared according to Example 3, using the exatecan-linker conjugate precursor compound 202 of Example 1. As demonstrated in the above examples, this exemplary NDC is highly stable in plasma and elicits antitumor efficacy in a variety of cell line and PDX-derived tumor models both in vitro and in vivo.

[0323] In 15-day repeat dose toxicology and toxicokinetic (TK) studies performed in Wistar Han rats and Beagle dogs, the NDC was tolerated at up to 0.87 mg/kg/day in rats and 0.174 mg/kg/day in dogs based upon conjugated exatecan concentration when administered on a QWx3 schedule via a 1-hour infusion. Observed dose-related toxicities for both species were limited to the bone marrow and gastrointestinal tract. These are the same organs as those observed when free payload (exatecan) was administered, suggesting that the delivery of exatecan conjugated to the NDC did not broaden the tissue toxicity profile. Observed toxicities were recovered or substantially reduced by the end of a two-week recovery period. No drug-related hepatic, renal, pulmonary or ocular toxicities were observed, and there were no drug-related deaths in the repeat dose toxicity study.

[0324] TK parameters, estimated in the 15-day GLP study, revealed similar plasma exposure values in males and females for the NDC, total exatecan (conjugated and released) and released exatecan. The NDC exhibited an average circulatory half-life ranging from approximately 15 to 20 hours in rats, and 24 to 29 hours in dogs, with no accumulation of the NDC, total exatecan, or free exatecan observed from day 1 to day 15. Based upon AUC_{0-last} (hr*ng/mL) released payload levels in the circulation were less than approximately 0.3% and 0.1% of the total payload levels in the rat and the dog respectively. No NDC anti-drug antibodies were induced in either species. In summary, the NDC has a favorable nonclinical safety/TK profile.

Cited references

REFERENCES CITED IN THE DESCRIPTION

This list of references cited by the applicant is for the reader's convenience only. It does not form part of the European patent document. Even though great care has been taken in compiling the references, errors or omissions cannot be excluded and the EPO disclaims all liability in this regard.

Patent documents cited in the description

- [US63105995 \[0001\]](#)
- [US63116393 \[0001\]](#)
- [US63117110 \[0001\]](#)
- [US63155043 \[0001\]](#)
- [US63222181 \[0001\]](#)
- [US63242201 \[0001\]](#)
- [US63254837 \[0001\]](#)
- [WO2015183882A1 \[0003\]](#)
- [EP0624377A2 \[0006\]](#)
- [US9192682B2 \[0006\]](#)
- [WO2008142571A \[0060\]](#)
- [WO2009056282A \[0060\]](#)
- [WO199922026A \[0060\]](#)
- [US8298677B2 \[0063\]](#)
- [US9625456B2 \[0063\]](#)
- [US10548997B2 \[0063\]](#)
- [US9999694B2 \[0063\]](#)
- [US10039847B2 \[0063\]](#)
- [US10548998B2 \[0063\]](#)
- [US7601332B2 \[0092\]](#)
- [US1002942B2 \[0092\]](#)
- [WO2017189961A \[0098\]](#)
- [WO2015183882A \[0098\]](#)
- [WO2013192609A \[0098\]](#)
- [WO2016179260A \[0098\]](#)
- [WO2018213851A \[0098\]](#)
- [US4788603A \[0136\]](#)
- [US4931279A \[0136\]](#)
- [US4668506A \[0136\]](#)
- [US4713224A \[0136\]](#)
- [US4140122A \[0136\]](#)
- [US4383529A \[0136\]](#)
- [US4051842A \[0136\]](#)
- [US4255415A \[0138\]](#)
- [US4136177A \[0138\]](#)
- [US3867519A \[0138\]](#)
- [US3870791A \[0138\]](#)
- [US2006049222W \[0154\]](#)
- [WO2016179260A1 \[0232\]](#)
- [WO2018213851A1 \[0232\]](#)
- [US9637547B \[0283\] \[0283\]](#)

Non-patent literature cited in the description

- **CHEUNG, A. et al.** Targeting Folate Receptor Alpha For Cancer Treatment *Oncotarget*, 2016, vol. 7, 3252-553- [0004]
- **LEDERMANN, J. A. et al.** *Annals of Oncology*, 2015, vol. 26, 2034-2043 [0004]
- **LEAMON et al.** Comparative preclinical activity of the folate-targeted Vinca alkaloid conjugates EC140 and EC145 *Int. J. Cancer*, 2007, vol. 121, 1585-1592 [0006]
- **LEAMON et al.** Folate-Vinca Alkaloid Conjugates for Cancer Therapy: A Structure-Activity Relationships *Bioconjugate Chemistry*, 2014, vol. 25, 560-568 [0006]
- **SCARANTI, M. et al.** Exploiting the folate receptor α in oncology *Nat Rev Clin Oncol.*, 2020, vol. 17, 349-359 [0006]
- **BURNS et al.** Fluorescent silica nanoparticles with efficient urinary excretion for nanomedicine *Nano Letters*, 2009, vol. 9, 1442-448 [0046] [0058]
- **MOLECULAR PROBES HANDBOOK OF FLUORESCENT PROBES AND RESEARCH CHEMICALS** 19960000 [0057]
- **HILDERBRAND et al.** Near-infrared fluorescence: Application to in vivo molecular imaging *Curr. Opin. Chem. Biol.*, 2010, vol. 14, 71-79 [0076]
- **KOLB et al.** *Angew. Chem. Int. Ed.*, 2001, vol. 40, 2004-2021 [0098]
- **J. F. BRIEN et al.** *Europ. J. Clin. Pharmacol.*, 1978, vol. 14, 133- [0146]
- **CHARLES E. BAKER, JR.** *Physicians' Desk Reference* Medical Economics Co. 19870000 [0146]
- *Oxford Dictionary of Biochemistry and Molecular Biology* Oxford University Press 19970000 [0178]
- **THEODORA W. GREENE PETER G. M. WUTS** *Protecting Groups in Organic Synthesis* John Wiley and Sons 20070000 [0191]
- **GREENE et al.** *Protecting Groups in Organic Synthesis* Wiley 19910000 [0197]

PATENTKRAV

1. Et nanopartikel-lægemiddel-konjugat (nanoparticle drug conjugate (NDC)) omfattende:


- (a) en siliciumdioxid-nanopartikel;
- (b) polyethylenglycol (PEG), der er covalent bundet til overfladen af nanopartiklen;
- (c) en målligand omfattende folsyre, hvori målliganden er knyttet til nanopartiklen direkte eller indirekte gennem en spacer-gruppe; og
- (d) et linker-payload-konjugat, hvori:
 - (i) payload er exatecan;
 - (ii) linker-payload-konjugatet er knyttet til nanopartiklen gennem en spacer-gruppe;
 - (iii) linkerens er en protease-spaltbar linker; og
 - (iv) exatecanen frigives ved spaltning af linkerens.

2. NDC ifølge krav 1, hvori NDC har en gennemsnitlig diameter mellem omkring 1 nm og omkring 10 nm, eller mellem omkring 5 nm og omkring 8 nm.

3. NDC ifølge et hvilket som helst af de foregående krav, hvori det gennemsnitlige antal exatecanmolekyler på hver nanopartikel er fra omkring 1 til omkring 30, og/eller hvori det gennemsnitlige antal folsyremolekyler på hver nanopartikel er fra omkring 1 til omkring 30.

4. NDC ifølge et hvilket som helst af de foregående krav, som yderligere omfatter en fluorescerende forbindelse, der er covalent indkapslet i nanopartiklen.

5. NDC ifølge et hvilket som helst af de foregående krav, omfattende en struktur med Formel (NP):



hvori

- x er et helt tal fra 0 til 20;
- siliciumatomet er en del af nanopartiklen; og


§

i tilknytning til triazoldelen angiver et tilknytningspunkt til en målligand eller payload-linker-konjugat, enten direkte eller indirekte via en linker eller spacer-gruppe.

6. NDC ifølge krav 5, hvori spacer-gruppen er en PEG-del.

7. NDC ifølge et hvilket som helst af de foregående krav, omfattende:

(a) en struktur med Formel (S-1):




hvor

Payload er exatecan;

Linker er en protease-spaltbar linker eller cathepsin-B-spaltbar linker, og siliciumatomet er en del af nanopartiklen; og/eller


(b) en struktur med Formel (S-2):



hvor

målliganden (Targeting Ligand) er folsyre; og siliciumatomet er en del af nanopartiklen.

8. NDC ifølge et hvilket som helst af de foregående krav, hvor linker-payload-konjugatet omfatter en struktur med Formel (I):



eller et salt deraf,

hvor

~


repræsenterer en tilknytning af nanopartiklen gennem en spacer-gruppe;

A er Val-Lys;


Payload er en rest af exatecan, hvor Z repræsenterer en amin af exatecan (-NR^c-); R¹, R², R³, R⁴ og R⁵ i hver forekomst uafhængigt er hydrogen;

X er fraværende;

Y er



hvor carbonyl i



er bundet til Z;

X₁, X₂, X₃ og X₄ hver uafhængigt er -CH-;


R^c er hydrogen; og

n er 1.

9. NDC ifølge et hvilket som helst af de foregående krav, hvori proteasen omfatter en serinprotease eller en cysteinprotease.


10. NDC ifølge et hvilket som helst af de foregående krav, omfattende:

a) en struktur med Formel (NP-3):



hvori x er 4 og y er 9, og hvori siliciumatomet er en del af nanopartiklen; og

(b) en struktur med Formel (NP-2):



hvori x er 4 og y er 3, og siliciumatomet er en del af nanopartiklen.

11. NDC ifølge krav 10, hvori NDC omfatter mellem 1 og 30 molekyler med Formel (NP-3), og/eller hvori NDC omfatter mellem 1 og 20 molekyler med Formel (NP-2).

12. NDC ifølge krav 10 eller krav 11, yderligere omfattende et fluorescerende farvestof covalent indkapslet i kernen af nanopartiklen.

13. NDC ifølge krav 4 eller krav 12, hvori den fluorescerende forbindelse eller det fluorescerende farvestof er et Cy5-farvestof.

14. Farmaceutisk sammensætning omfattende et NDC ifølge et hvilket som helst af de foregående krav, og en farmaceutisk acceptabel excipients.

15. Farmaceutisk sammensætning ifølge krav 14, hvori den farmaceutiske sammensætning er egnet til intravenøs administration, og/eller hvori den farmaceutiske sammensætning er i en enhedsdosisform.

16. NDC ifølge et hvilket som helst af kravene 1-13 eller en farmaceutisk sammensætning ifølge krav 14 eller krav 15 til anvendelse til behandling af cancer.

17. NDC eller sammensætning til anvendelse ifølge krav 16, hvori canceren er valgt fra gruppen bestående af ovariecancer, endometriecancer, æggeledercancer, cervixcancer, brystcancer, lungecancer, mesotheliom, uteruscancer, gastrointestinal cancer, pancreascancer, blærecancer, nyrecancer, levercancer, hoved- og halscancer, hjerne-cancer, skjoldbruskcancer, hudcancer, prostatacancer, testikelcancer, akut myeloid leukæmi (AML) og kronisk myeloid leukæmi (CML).

18. NDC eller sammensætning til anvendelse ifølge krav 17, hvori den gastrointestinale cancer er spiserørscancer, coloncancer, endetarmscancer eller mavecancer, eller hvori AML er pædiatrisk AML.

19. NDC ifølge et hvilket som helst af kravene 1-13 eller en farmaceutisk sammensætning ifølge krav 14 eller 15 til anvendelse som lægemiddel.

DRAWINGS




FIG. 1




FIG. 1
CONTINUED




FIG. 2




FIG. 3




FIG. 3
CONTINUED




FIG. 4




FIG. 5




FIG. 6




FIG. 7




FIG. 8




FIG. 9




FIG. 10A




FIG. 10B




FIG. 11C




FIG. 11B




FIG. 11A




FIG. 12C




FIG. 12B




FIG. 12A




FIG. 13




FIG. 14




FIG. 14
CONTINUED




FIG. 15




FIG. 15
CONTINUED




FIG. 16




FIG. 16
CONTINUED




FIG. 17




FIG. 18




FIG. 19A




FIG. 19B




FIG. 20A

FIG. 20B

FIG. 20C




FIG. 20D

FIG. 20E

FIG. 20F


FIG. 21A
#Irinotecan in Irinotecan-resistant KB

FIG. 21A


FIG. 21B
Potency of FA-CDC in regular and Irinotecan-resistant KB

FIG. 21B

Potency of Exatecan in regular and resistant KB




FIG. 22A

Potency of FA-CDC in regular and Exa-resistant KB




FIG. 22B

		7-day exposure (CellTiter-Glo® cytotoxic assay)					
Compound names	DPR*	KB(++++)	IGROV-1(++)	SK-OV-3(++)	HCC827(++)	A549(-)	BT549(-)
FA-CDC	43	0.02 nM	0.10 nM	0.20 nM	0.2 nM	0.6 nM	0.1 nM
FA-CJC	20	0.23 nM	0.44 nM	0.70 nM	0.3 nM	1.9 nM	0.33 nM
FA-CDC	8	0.70 nM	0.63 nM	2.3 nM	0.6 nM	2.4 nM	0.62 nM
Free Exatecan	1	1.6 nM	0.84 nM	0.5 nM	0.6 nM	3.2 nM	0.4 nM

		6-hour exposure (CellTiter-Glo® cytotoxic assay)					
Compound names	DPR*	KB(++++)	IGROV-1(++)	SK-OV-3(++)	HCC827(++)	A549(-)	BT549(-)
FA-CDC	43	2.0 nM	1.8 nM	2.7 nM	1.1 nM	6.1 nM	1.2 nM
FA-CDC	20	3.6 nM	6.2 nM	44.5 nM	2.7 nM	38.8 nM	4.4 nM
FA-CDC	8	6.0 nM	8.2 nM	50.7 nM	6.9 nM	49.5 nM	24.5 nM
Free Exatecan	1	74.4 nM	25.6 nM	55.8 nM	2.7 nM	39.7 nM	8.8 nM

*DPR : Drug-to-Particle Ratio

FIG. 23

Histology	Model	FR alpha positivity (IHC score)	Cytotoxicity IC50 (nM)		Fold increase in potency (Targeted vs. Free)	
			NDC	Exatecan	NDC vs. Exatecan	Mean
Ovarian	ST004	3+	2.8	74.7	26.6	
Ovarian	ST3308	3+	1.8	7.7	4.4	
Ovarian	ST024	3+	0.4	3.9	9.6	13.5
Ovarian	ST182B	2+	0.2	0.7	4.4	
Ovarian	ST206	2+	17.4	202.8	11.7	
Ovarian	ST2442	2+	0.8	1.7	2.2	6.1
Ovarian	ST182	1+	0.3	2.8	8.5	
Ovarian	ST419	1+	0.16	0.34	2.1	
Ovarian	ST4321	1+	0.3	0.7	2.4	4.3
Ovarian	ST2199	1+	-	-	-	-

Histology	Model	FR alpha positivity (IHC score)	Cytotoxicity IC50 (nM)		Fold increase in potency (Targeted vs. Free)	
			NDC	Exatecan	NDC vs. Exatecan	Mean
NSCL	ST1931	3+	0.25	2.13	8.5	
NSCL	ST1989	3+	2.4	17.4	7.3	7.9
NSCL	ST1243	2+	0.46	4.74	10.3	
NSCL	ST3647	2+	0.31	2.87	9.3	
Breast (HR-, HER2+)	ST353	2+	1.69	5.79	3.4	
Breast (HR+, HER2+)	ST430	2+	0.42	1.58	3.8	
Breast (HR+, HER2+)	STF040	2+	3.18	33.64	10.6	7.5
TNBC	ST1248	1+	1.93	161.9	83.9	
TNBC	ST1599	1+	3.20	157.5	49.2	66.6

Histology	Model	FR alpha positivity (IHC score)	Cytotoxicity IC50 (nM)		Fold increase in potency (Targeted vs. Free)	
			NDC	Exatecan	NDC vs. Exatecan	Mean
Endometrium	ST1392	3+	0.39	3.44	8.8	
Endometrium	ST2043	3+	36.6	409.5	11.2	
Endometrium	ST4413	3+	2.47	25.82	10.5	10.2
Endometrium	ST2073	2+	3.15	7.9	2.5	
Endometrium	ST2136	2+	6.13	21.4	3.5	
Endometrium	ST2846	2+	0.80	16.67	20.8	
Head&Neck	ST1203	2+	0.22	2.29	10.4	
Head&Neck	ST2216	2+	1.21	9.74	8.0	
Head&Neck	ST2430	2+	0.37	2.0	5.3	
NSCL	ST3898	2+	4.04	61.6	15.2	9.4

FIG. 24




FIG. 25A




FIG. 25B




FIG. 25C




FIG. 25D




FIG. 26A




FIG. 26B




FIG. 27




FIG. 28




FIG. 29




FIG. 30




FIG. 31




FIG. 32




FIG. 33A




FIG. 33B