



(22) Date de dépôt/Filing Date: 2012/06/26

(41) Mise à la disp. pub./Open to Public Insp.: 2013/03/12

(45) Date de délivrance/Issue Date: 2017/10/17

(30) Priorité/Priority: 2011/09/12 (US13/230,534)

(51) Cl.Int./Int.Cl. *G06Q 50/04* (2012.01),
G06F 17/50 (2006.01)


(72) Inventeurs/Inventors:
COWART, GEORGE STEPHEN, US;
KUMPF, STEVEN JAMES, US;
HAGBERG, KYLE K., US

(73) Propriétaire/Owner:
THE BOEING COMPANY, US

(74) Agent: SMART & BIGGAR

(54) Titre : UN SYSTEME DE GESTION D'OBJET

(54) Title: AN OBJECT MANAGEMENT SYSTEM



(57) Abrégé/Abstract:

A method and apparatus for managing a configuration of a vehicle structure. Data sets are compared each representing the configuration of the vehicle structure at different phases in a lifecycle of the vehicle structure. Each of the data sets includes identifications of components for the vehicle structure. Differences are identified between the identifications of the components in the data sets.

ABSTRACT

A method and apparatus for managing a configuration of a vehicle structure.

5 Data sets are compared each representing the configuration of the vehicle structure at different phases in a lifecycle of the vehicle structure. Each of the data sets includes identifications of components for the vehicle structure. Differences are identified between the identifications of the components in the data sets.

10

AN OBJECT MANAGEMENT SYSTEM

BACKGROUND INFORMATION

5 The present disclosure relates generally to managing objects and, in particular, to managing configurations for objects. Still more particularly, the present disclosure relates to a method and apparatus for managing a configuration of an object during different phases in the lifecycle of the object.

10 Oftentimes, objects, such as aircraft, trains, ships, and other platforms, have complex configurations. These complex configurations may have thousands or hundreds of thousands of components. Ensuring that an object has been manufactured with the correct configuration as specified in a design for the object is desirable as part of managing the object during a lifecycle of the
15 object. The lifecycle of an object may include phases, such as, for example, without limitation, the design of the object, the creation of a plan for manufacturing the object, the manufacturing of the object, inspection of the object, maintenance for the object, and/or other suitable types of phases.

20 Typically, different bills of materials are created for an object during the different phases in the lifecycle of the object. A bill of materials (BOM) is a list of the raw materials, sub-assemblies, intermediate assemblies, sub-components, parts, and/or other components needed for object. A bill of materials also may include the quantities of the components and other
25 suitable information used for the object.

A bill of materials may be used to define an object at any phase of the lifecycle of the object. For example, an engineering bill of materials (EBOM) defines an object at the design phase. The engineering bill of materials identifies the
30 components needed for manufacturing the object as specified in a design for the object. The design may take the form of, for example, a computer-aided design (CAD) model.

As another example, a manufacturing bill of materials (MBOM) defines an object during a manufacturing phase and/or after manufacturing of the object has been completed. In particular, the manufacturing bill of materials identifies the components of the object as the object is being and/or has been built.

Typically, an object is considered to have a correct configuration when the manufacturing bill of materials can be reconciled with the engineering bill of materials. Reconciling these two different bills of materials includes making sure that both bills of materials are consistent with each other and define substantially the same configuration for the object.

With currently available systems for managing objects, ensuring that the different bills of materials for a particular object are reconciled may be more time-consuming and difficult than desired. For example, the different bills of materials for a particular object may be created at different times and/or using different systems. These bills of materials may be compatible with different software, have different formats, contain different data types and/or data content, identify different versions of components, and/or have other differences. As a result, detecting discrepancies between the different bills of materials may take more time, effort, and/or resources than desired.

For example, an engineering bill of materials for an aircraft may be created using a computer-aided design model of the aircraft. The manufacturing bill of materials may be created by operators at some later point in time using the engineering bill of materials and/or the model of the aircraft. The engineering and manufacturing bills of materials may not have the same format and/or may identify the components that form the configuration for the object in the same manner. Detecting discrepancies between engineering and manufacturing bills of materials may take more time, effort, and/or resources than desired.

Therefore, it would be advantageous to have a method and apparatus that takes into account at least some of the issues discussed above, as well as other possible issues.

SUMMARY

5 In one embodiment, there is provided a method for managing a configuration of a vehicle structure. The method involves assigning a unique key to components in a plurality of components of a vehicle structure in each of a plurality of data sets. The unique key for a particular component in the plurality of components distinguishes the particular component
10 from other components in the plurality of components for the vehicle structure. The unique key includes a component identifier and an instance identifier. The instance identifier distinguishes components having the same component identifier by describing a location in the vehicle structure of each component having the same component identifier. The method further involves comparing a first data set with a second data set. The first
15 data set corresponds to the plurality of components of the vehicle structure at a first phase in a lifecycle of the vehicle structure, and the second data set corresponds to the plurality of components of the vehicle structure at a second phase in the lifecycle of the vehicle structure. The first data set comprises design data or manufacturing planning data and the second data set comprises as-built data. Each data set includes identifications of
20 components for the vehicle structure. Comparing also involves comparing first unique keys for the identifications of the components in the first data set with second unique keys for the identifications of the components in the second data set. The method further involves identifying differences between the identifications of the components in the data sets, wherein two or more of the data sets have different formats and include different pieces of
25 information for different attributes for the components, and wherein the unique key is common to all of the data sets and each of the data sets uses the unique key to distinguish between different components in the data sets.

The method may further involve establishing whether the differences between the
30 identifications of the components in the data sets are errors, wherein differences are determined by a policy and a comparison of the first data set and the second data set, recording error descriptions of established errors and difference descriptions of correct but

different identifications of the components between the data sets; and correcting the error in the respective data set of the data sets and annotating correct differences in one or more of the data sets to establish a corrected correlation between identifications of the components in the data sets.

5

The method may further involve visually presenting on a graphical user interface a display to represent the differences identified between the identifications of the components in the data sets.

10 The method may further involve recording dispositions for the differences identified between the identifications of the components in the data sets.

The method may further involve repeating the steps of comparing the data sets, identifying the differences between the identifications of the components in the data sets, and
15 recording the dispositions for the differences identified between the identifications of the components in the data sets until the differences are no longer present between the identifications of the components in the data sets.

The method may further involve determining whether an identification of a particular
20 component in the first data set matches any of the identifications of the components in the second data set, wherein the particular component is an assembly of a plurality of components for the vehicle structure, and assuming that all of the plurality of components for the assembly are present in the second data set if the identification for the particular component in the first data set matches one of the identifications of the components in the
25 second data set. The differences between the identifications of the components in the data sets may indicate at least one of overages and underages in the components for the vehicle structure with respect to the configuration of the vehicle structure at a particular phase in the lifecycle of the vehicle structure, and the method may further include visually presenting on a display graphical indicators indicating the overages and the underages in
30 the components for the vehicle structure and rectifying components from the vehicle identified as overages or underages.

The first data set may correspond to the plurality of components of the vehicle structure at a design phase of the lifecycle of the vehicle structure, the second data set may correspond to the plurality of components of the vehicle structure at a manufacturing planning phase of the life cycle of the vehicle, and the method may further involve
5 comparing the second data set with a third data set, the third data set corresponding to the plurality of components of the vehicle structure at a manufacturing design phase of the lifecycle of the vehicle structure.

The unique key for the particular component may be common to all of the data sets, and
10 the unique keys for the identifications of the components in all of the data sets may have the same format, and the unique key may further include information for a component including an installation tool for use with the component.

The steps of comparing the data sets and identifying the differences between the
15 identifications of the components in the data sets may be performed during one or more of the different phases of the lifecycle of the vehicle structure.

The method may further involve updating at least one of the data sets based on the differences between the identifications of the components in the data sets.

20 The vehicle structure may be an aircraft, an aircraft structure, a spacecraft, an automobile, a train, a surface ship, a submarine, a jet engine, a wing box, or an assembly for a vehicle.

The method may involve displaying a comparison of the first data set and the second data
25 set on a graphical user interface; wherein the graphical user interface comprises a first table and a second table; wherein the first table provides a component number, a location index, a vendor part number, at least one designation of material for the component, a weight of the component, a drawing number associated with the component, an installation side, and a maximum storage temperature for the component; and wherein the
30 second table provides the component number, the location index, an installation tool associated with the component, an indication of a requirement for certification, a storage

location, an assembly jig number associated with the component, the installation side, and an assembly cell.

5 In another embodiment, there is provided an apparatus having a storage system including a unique key for each component in a plurality of components of a vehicle structure. The unique key is stored in a plurality of data sets. The unique key for a particular component in the plurality of components distinguishes the particular component from other components in the plurality of components for the vehicle structure. The unique key includes a component identifier and an instance identifier. The instance identifier
10 distinguishes components having the same component identifier by describing a location in the vehicle structure of each component having the same component identifier. The apparatus further has a computer system configured to compare a first data set with a second data set. The first data set corresponds to the plurality of components of the vehicle structure at a first phase in a lifecycle of the vehicle structure, and the second data set corresponds to the plurality of components of the vehicle structure at a second phase
15 in the lifecycle of the vehicle structure. The first data set comprises design data or manufacturing planning data and the second data set comprises as-built data. Each data set includes identifications of components for the vehicle structure, and comparing involves comparing first unique keys for the identification of the components in the first data set with second unique keys for the identification of the components in the second
20 data set. The computer system is further configured to identify differences between the identifications of the components in the data sets, wherein two or more of the data sets have different formats and include different pieces of information for different attributes for the components, and wherein the unique key is common to all of the data sets and each of the data sets uses the unique key to distinguish between different components in the data sets.

The computer system may be further configured to establish whether the differences between the identifications of the components in the data sets are errors based on a
30 policy, the policy including a criteria for a component, and record error descriptions of established errors and difference descriptions of correct but different identifications of the components between the data sets.

In being configured to identify the differences between the identifications of the components in the data sets, the computer system may be configured to determine whether at least one of an overage and an underage in the components are present with respect to a particular data set in the data sets.

The apparatus may further include a graphical user interface, wherein the computer system may be further configured to visually present the differences identified on the graphical user interface and wherein the graphical user interface may be configured to receive user input providing dispositions for the differences in a storage system.

The computer system may further be configured to record dispositions for the differences identified between the identifications of the components in the data sets.

In another embodiment, there is provided a vehicle manufacturing system. The system includes a storage system configured to store data sets. Each data set represents a configuration of a vehicle structure at different phases in a lifecycle of the vehicle structure. Each of the data sets includes identifications of components for the configuration of the vehicle structure. The storage system further includes a unique key for each of the components of the vehicle structure in each of the data sets. The unique key for a particular component distinguishes the particular component from other components for the vehicle structure. The unique key for a particular component includes a component identifier and an instance identifier. The instance identifier distinguishes components having the same component identifier by describing a location in the vehicle structure of each component having the same component identifier. The system further includes an object manager. The object manager is configured to compare a first data set representing the configuration of the vehicle structure at a first phase in the lifecycle of the vehicle structure with a second data set representing the configuration of the vehicle structure at a second phase in the lifecycle of the vehicle structure. The first data set includes design data or manufacturing planning data and the second data set includes as-built data. The comparison includes comparing first unique keys for the identifications of the components in the first data set

with second unique keys for the identifications of the components in the second data set. The object manager is further configured to identify differences between the identifications of the components for the vehicle structure in the first data set and the identifications of the components for the vehicle structure in the second data set, and record dispositions provided for the differences in the storage system, wherein the first data set and the second data set each have different formats and include different pieces of information for different attribute for the components, and wherein the unique key is common to all of the data sets and each of the data sets uses the unique key to distinguish between different components in the data sets.

The system may further include a manufacturing facility configured to manufacture the vehicle structure.

The system may further include a graphical user interface, wherein the object manager is configured to visually present the differences identified on the graphical user interface and the graphical user interface may be configured to receive user input providing the dispositions for the differences in the storage system.

In another embodiment, there is provided a method for managing a configuration of a vehicle structure. The method involves selecting, using an object manager associated with a computer system, a first design data set identifying components in a design for a vehicle structure, and a second manufacturing data set identifying components used in manufacturing the vehicle structure. The method further involves assigning a unique key to components in a plurality of components of a vehicle structure in each of a plurality of data sets, the unique key for a particular component in the plurality of components distinguishing the particular component from other components in the plurality of components for the vehicle structure, the unique key including a component identifier and an instance identifier, the instance identifier distinguishing a location for each of the components having the same component identifier. The method further involves comparing, using the object manager, the first design data set with the second manufacturing data set, the first design data set corresponding to a plurality of components in the design of the vehicle structure at a first phase in a lifecycle of the

vehicle structure, and the second manufacturing data set corresponding to a plurality of components used in manufacturing of the vehicle structure at a second phase in the lifecycle of the vehicle structure, wherein each data set includes identifications of components and the unique key for the components in the plurality of components for the vehicle structure. Comparing including comparing first unique keys for the identifications of the components in the first design data set with second unique keys for the identifications of the components in the second manufacturing data set. The method further involves identifying differences between the identifications of the components in the data sets, wherein differences are identified where the unique keys in the first data set do not match the unique keys in the second data set, and where there is a discrepancy between the information associated with the unique key in the design data set and the information associated with the same unique key in the manufacturing data set. The method further involves generating and sending an output signal identifying the differences between the data sets to an operator at a manufacturing facility, recording the differences in a database.

In another embodiment, there is provided a computer-managed build process for a complex product. The process involves causing at least one processor, during a design phase of the product, to generate an as-specified data set containing engineering design requirements of the product, each engineering design requirement identified by a unique identifier. The process further involves causing the at least one processor, during a manufacturing planning phase of the product, to generate an as-planned data set containing manufacturing planning requirements for building the product according to the engineering design requirements, the manufacturing planning requirements identifying the engineering design requirements by their unique identifiers. The process further involves causing the at least one processor to access at least one policy that identifies criteria for determining whether differences are acceptable; to compare the identifiers in the data sets to identify differences between the identifiers in the data sets; and upon determining that the identified differences resulting from the comparison are consistent with the criteria of the accessed policy, to output a first indication that the as-specified data set and the as-planned data set are reconciled; and upon determining that the identified

differences resulting from the comparison are not consistent with the criteria of the accessed policy, to output a second indication that the as-specified data set and the as-planned data set are not reconciled.

- 5 The manufacturing planning phase may overlap the design phase, wherein the as-specified data set may be modified repeatedly during the design phase, and the as-planned data set may be modified to reflect modifications to the as-specified data set, and wherein the differences between the identifiers in the data sets are identified repeatedly throughout the manufacturing planning phase.

10

The product may be a vehicle or an aircraft.

The engineering design requirements may specify parts of the product, and identifying the differences may include identifying parts that are included in only one of the data sets.

15

Identifying the differences may include identifying a 1:1 correspondence of identifiers in the as-specified data set and the as-planned data set.

20

Each part specified in the as-specified data set may be identified by a unique key including part identification and part location information.

25

The as-specified data set may expressly identify an assembly and each assembly parts in the assembly, wherein the as-planned data set does not expressly identify the assembly but does describe how the assembly is built from the assembly part, and wherein comparing the identifiers in the data sets includes determining that the manufacturing planning requirements represent the assembly if all of the assembly parts are included in the as-planned data set.

30

The as-specified data set may include data taken from engineering bills of material, and the as-planned data set may include data taken from manufacturing bills of material.

The process may further involve, during a build phase of the product, generating documents that describe build steps that have been completed, the documents identifying any engineering design requirements by their unique identifiers, and during the build phase, identifying differences between the unique identifiers in the as-planned and as-built data sets to certify completion of the product.

The as-built data set may grow during the build process and may be repeatedly compared to the as-planned data set until the build process has been completed, and the differences between the identifiers in the as-planned and as-built data sets may be identified repeatedly throughout the build phase.

Identifying the differences between the identifiers in the as-planned and as-built data sets may include identifying overages and underages in the as-built data set.

The policy may include criteria for changes to the design of the product between the design phase and the manufacturing planning phase.

The second indication may be an error indication.

The engineering design requirements of the product may include handling requirements for components of the product, wherein the manufacturing planning requirements include handling conditions for components of the product, wherein the policy includes criteria that the reconcile handling conditions with the handling requirements.

The as-specified data set may include identifiers for different parts included in the product, wherein the as-planned data set may include a definition for a sub-assembly that lists at least two of the different parts that are included in the sub-assembly and wherein the as-planned data set does not include identifiers for the at least two of the different parts included in the definition, and wherein comparing the identifiers in the

data sets to identify differences between the identifiers in the data sets may comprise: assuming that the parts in the definition for the sub-assembly included in the as-planned data set are included in the sub-assembly; and determining that no difference is present between the data sets with respect to the parts in the definition for the sub-assembly.

The manufacturing planning phase may overlap the design phase, the as-specified data set may be modified repeatedly during the design phase, and the criteria in the policy may reflect the modifications to the as-specified data set.

In another embodiment, there is provided an object management system for building a complex product. The object management system comprises a computer processor; a computer memory containing a program that, when executed on the computer processor, performs an operation for processing data, comprising: during a design phase of the product, generate an as-specified data set containing engineering design requirements of the product, each engineering design requirement identified by a unique identifier; during a manufacturing planning phase of the product, generate an as-planned data set containing manufacturing planning requirements for building the product according to the engineering design requirements, the manufacturing planning requirements identifying the engineering design requirements by their unique identifiers; access at least one policy that identifies criteria for determining whether differences are acceptable; compare the identifiers in the data sets to identify differences between the identifiers in the data sets; and upon determining that the identified differences resulting from the comparison are consistent with the criteria of the accessed policy, output a first indication that the as-specified data set and the as-planned data set are reconciled; and upon determining that the identified differences resulting from the comparison are not consistent with the criteria of the accessed policy, output a second indication that the as-specified data set and the as-planned data set are not reconciled.

The as-specified data set may include identifiers for different parts included in the product, wherein the as-planned data set includes a definition for a sub-assembly that lists at least two of the different parts that are included in the sub-assembly and wherein the as-planned data set does not include identifiers for the at least
5 two of the different parts included in the definition, and wherein comparing the identifiers in the data sets to identify differences between the identifiers in the data sets comprises: assuming that the parts in the definition for a sub-assembly are included in the sub-assembly; and determining that no difference is present between the data sets with respect to the parts in the definition for the sub-assembly.

10

The policy may include criteria for changes to the design of the product between the design phase and the manufacturing planning phase.

The second indication may be an error indication.

15

The engineering design requirements of the product may include handling requirements for components of the product, wherein the manufacturing planning requirements includes handling conditions for components of the product, wherein the policy includes criteria that the reconcile handling conditions with the handling
20 requirements.

20

These and other features and functions may be achieved independently in various embodiments of the present disclosure or may be combined to form yet other embodiments as can be understood by reference to the following description and
25 drawings.

25

BRIEF DESCRIPTION OF THE DRAWINGS

The novel features believed characteristic of the advantageous embodiments are set forth in the appended claims. The advantageous embodiments, however, as well as a preferred mode
30 of use, further objectives, and advantages thereof, will best be understood by reference to the

30

following detailed description of an embodiment of the present disclosure when read in conjunction with the accompanying drawings, wherein:

5 **Figure 1** is an illustration of a development environment in the form of a block diagram in accordance with an embodiment;

Figure 2 is an illustration of data sets in accordance with an embodiment;

10 **Figure 3** is an illustration of a difference between data sets in accordance with an embodiment;

Figure 4 is an illustration of a data set in accordance with an embodiment;

15 **Figure 5** is an illustration of a data set in accordance with an embodiment;

Figure 6 is an illustration of a comparison between two data sets in accordance with an advantageous embodiment;

5 **Figure 7** is an illustration of a comparison between two data sets in accordance with an advantageous embodiment;

Figure 8 is an illustration of a comparison between two data sets in accordance with an advantageous embodiment;

10 **Figure 9** is an illustration of a graphical user interface displaying results of a comparison between two data sets in accordance with an advantageous embodiment;

15 **Figure 10** is an illustration of a graphical user interface displaying results of another comparison between two data sets in accordance with an advantageous embodiment;

20 **Figure 11** is an illustration of a graphical user interface displaying results of a comparison between two data sets in accordance with an advantageous embodiment;

25 **Figure 12** is an illustration of a graphical user interface displaying results of a comparison between two data sets in accordance with an advantageous embodiment;

Figure 13 is an illustration of a flowchart of a process for identifying parts in a vehicle in accordance with an advantageous embodiment;

30 **Figure 14** is an illustration of a flowchart of a process for managing components used in developing a vehicle structure in accordance with an advantageous embodiment;

Figure 15 is an illustration of a flowchart of a process for manufacturing a vehicle in accordance with an advantageous embodiment;

5 **Figure 16** is an illustration of a data processing system in accordance with an advantageous embodiment;

Figure 17 is an illustration of an aircraft manufacturing and service method in accordance with an advantageous embodiment; and

10 **Figure 18** is an illustration of an aircraft in which an advantageous embodiment may be implemented.

DETAILED DESCRIPTION

15 The different advantageous embodiments recognize and take into account one or more different considerations. For example, the different advantageous embodiments recognize and take into account that the parts for an object may be different during different phases in a lifecycle of the object. For example, parts specified in a design for an object, such as an aircraft, may not match the parts specified in a manufacturing plan for manufacturing the
20 aircraft. For example, an availability of parts may result in a different type of part than the part specified in the design for the aircraft being added to the manufacturing plan for the aircraft.

25 Further, the different advantageous embodiments recognize and take into account that when the manufacturing plan is used to manufacture the aircraft, the parts designated in the manufacturing plan may sometimes differ from the parts actually used to assemble the aircraft. The different advantageous embodiments recognize and take into account that these differences may occur based on an availability of parts, a client request to make a change to
30 the aircraft after the manufacturing plan has been generated, a combination of the two, or for other reasons.

Further, the different advantageous embodiments recognize and take into account that it may be desirable to track the differences between the configuration specified in the design of the aircraft, the configuration planned for the aircraft, and the configuration for the aircraft actually built. Additionally, the different advantageous embodiments recognize and take into account that in some cases, updates to the design of the aircraft based on changes made when generating the manufacturing plan for the aircraft and/or actually assembling the aircraft may be desirable. Further, if changes are made for other reasons, such as regulatory or certification reasons, updating the data in the design of the aircraft also may be desirable. Further, updates for manufacturing plan also may be desirable based on these changes.

Thus, the different advantageous embodiments provide a method and apparatus for managing an object, such as a vehicle structure. In one advantageous embodiment, a method for managing a configuration of a vehicle structure is provided. Data sets, each representing the configuration of the vehicle structure at different phases in the lifecycle of the vehicle structure, are compared. Each data set includes identifications of components for the vehicle structure. Differences between the identifications of the components in the data sets are identified.

With reference now to **Figure 1**, an illustration of an object management environment in the form of a block diagram is depicted in accordance with an advantageous embodiment. In **Figure 1**, an object management environment **100** is an example of an environment in the form of a block diagram in which the different advantageous embodiments may be implemented to manage an object **104** during phases **101** in a lifecycle **103** of the object **104**.

The different phases **101** in the lifecycle **103** of an object **104** may include, for example, without limitation, at least one of a conception phase, a design phase, a manufacturing planning phase, a manufacturing phase, a testing phase, a certification phase, a selling phase, a delivery phase, an in-use phase, an operation phase, an in-service phase, a support phase, a

5 maintenance phase, a retirement phase, a recycling phase, a disposal phase, a reconfiguration phase, a re-engineering phase, and other suitable types of phases in the lifecycle **103** of the object **104**. In some cases, one of the phases **101** in the lifecycle **103** of the object **104** may be a combination of two or more of the phases listed above.

10 As used herein, the phrase “at least one of”, when used with a list of items, means different combinations of one or more of the listed items may be used and only one of each item in the list may be needed. For example, “at least one of item A, item B, and item C” may include, for example, without limitation, item A, or item A and item B. This example also may include item A, item B, and item C, or item B and item C. In other examples, “at least one of” may be, for example, without limitation, two of item A, one of item B, and ten of item C; four of item B and seven of item C; and other suitable combinations.

15 In these illustrative examples, the object **104** may be a vehicle structure **105**. The vehicle structure **105** may be selected from one of an aircraft, a spacecraft, an automobile, a train, a surface ship, a submarine, an aircraft structure, a jet engine, a wing box, an assembly for a vehicle, and/or some other suitable type of structure for a vehicle.

20 As depicted, object **104** may be managed using a computer system **108** in the object management environment **100**. In particular, the computer system **108** is configured to manage data **102** used in the different phases **101** in the lifecycle **103** of the object **104**. For example, an object manager **110** in the computer system **108** is configured to manage the data **102** used in the different phases **101** in the lifecycle **103** of the object **104**.

25 The computer system **108** may take the form of a number of computers **112** in these illustrative examples. As used herein, a number of items means one or more items. For example, a number of computers means one or more computers. When the computers **112** include more than one computer, these computers are in communication with each other. The object manager **110**

may be implemented as hardware, software, or a combination of the two in one or more of the computers **112** in the computer system **108**.

In these illustrative examples, the data **102** for the object **104** is in the form of data sets **114**. The data sets **114** may be stored in a storage system **113** in the computer system **108**. The storage system **113** may comprise any number of databases, tables, reports, logs, spreadsheets, and/or other types of data structures.

The data sets **114**, in these depicted examples, identify components **115** for the object **104**. The components **115** may include, for example, individual parts used in manufacturing the object **104**, assemblies of parts, sub-assemblies of parts, and/or the object **104** itself. Further, the components **115** for the object **104** may include a number of designs, models, specifications, and/or other items used in the object **104**. In one illustrative example, each of the data sets **114** may take the form of a bill of materials (BOM) used for the object **104**.

As depicted, each of the data sets **114** identifying the components **115** for managing the object **104** may be for a different phase in the phases **101** in the lifecycle **103** of the object **104**. In particular, each of the data sets **114** may include identifications of the components **115** that form a configuration **117** for the object **104** at a particular phase in the lifecycle **103** of the object **104**.

In other words, the identifications of the components **115** for the object **104** in a particular data set of the data sets **114** represent the configuration **117** for the object **104** at the phase corresponding to the particular data set. The configuration **117** for an object **104** includes the particular parts, sub-assemblies, assemblies, and/or other components for the object **104** as well as the manner in which these different components are assembled to form the object **104**.

As one illustrative example, the data sets **114** may include data for a design phase **118**, a manufacturing planning phase **120**, and a manufacturing phase

122 in the lifecycle **103** of the object. In particular, the data sets **114** may include design data **124** for the design phase **118**, manufacturing planning data **126** for the manufacturing planning phase **120**, and as-built data **128** for the manufacturing phase **122**.

5

The design data **124** identifies the components **115** specified in a design **130** for the object **104**, relationships between the components **115** for the object **104**, and other suitable information for the object **104**. The design data **124** may also be referred to as “as-specified” data. In some cases, the design data **124** may include the design **130** itself. The design **130** of the object **104** may be, for example, a computer aided design (CAD) model of the object **104**.

10

In one illustrative example, the design data **124** takes the form of an engineering bill of materials (EBOM) for the object **104**. The engineering bill of materials may be represented in, for example, a hierarchical diagram identifying the design **130** of the object **104**, assemblies specified in the design **130**, subassemblies that form the assemblies, parts that form the subassemblies and/or assemblies of the object, and/or other suitable information as specified in the design **130**.

15

20

In these illustrative examples, a hierarchical diagram is any diagram that shows relationships between the components **115** at different levels. One example of a hierarchical diagram may be a tree diagram. A tree diagram comprises linked nodes in which each node may have zero or more children nodes and, at most, one parent node.

25

Further, the manufacturing planning data **126** includes data that is used in planning the manufacturing of the object **104**. The manufacturing planning data **126** may also be referred to as “as-planned” data. The manufacturing planning data **126** for the object **104** may include, for example, without limitation, an identification of the components **115** to be used in manufacturing the object **104**, an identification of the assemblies and subassemblies to be formed using the components **115** for the object **104**, instructions for

30

manufacturing the object **104**, and other suitable information for manufacturing the object **104**.

As one illustrative example, the manufacturing planning data **126** may include a manufacturing plan for manufacturing the object **104**, a number of shop orders for the different parts, sub-assemblies, assemblies, and/or other components needed to manufacture the object **104**, and/or other suitable information. A shop order is a list of the components **115**, such as parts, sub-assemblies, and/or assemblies, which need to be obtained to assemble the object **104**. A component may be obtained by purchasing the component, assembling various parts to form the component, and/or obtaining the component in some other suitable manner. Further, a shop order may be, for example, a work order for a particular part.

In these illustrative examples, the manufacturing planning data **126** may be generated using the design data **124**. For example, the manufacturing planning data **126** may be generated in the form of a sales bill of materials (SBOM) when the design data **124** takes the form of an engineering bill of materials. The sales bill of materials identifies the particular components that need to be ordered to manufacture the object **104**. Similar to the engineering bill of materials, the sales bill of materials also may be represented in the form of a hierarchical diagram.

The as-built data **128** includes data generated for the object **104** after manufacturing of the object **104** has been completed and/or after manufacturing of subassemblies and/or assemblies that form the object **104** has been completed. In this manner, the as-built data **128** may be generated as the object **104** is physically being manufactured. The as-built data **128** is generated based on the actual components **115** and/or relationships between the components **115** in the object **104** that are used in manufacturing the object **104**. In these illustrative examples, the as-built data **128** may be generated in the form of a manufacturing bill of materials (MBOM). The

manufacturing bill of materials also may be represented in the form of a hierarchical diagram.

5 In these illustrative examples, each of the different data sets **114** may identify the components **115** for the object **104** using a unique key **135** for each of the components **115**. The unique key **135** identifies a particular component in the components **115** such that the particular component may be distinguished from other components of the same type, part number, and/or model.

10 The unique key **135** may comprise a component identifier **137** and an instance identifier **139** for each component. These two pieces of information may be included for every component identified in each of the different data sets **114**. The component identifier **137** may be, for example, a part number or a model number. Different components may have the same part identifier. For
15 example, bolts of the same type and/or model may have the same part number.

The instance identifier **139** in the unique key **135** allows components having the same part identifier to be distinguished from each other. The instance
20 identifier **139** for a component represents a precise installation instance for the bolt in the assembly. As one illustrative example, an assembly may include a group of bolts having the same part numbers. The instance identifier **139** used for a particular bolt may distinguish that bolt from the other bolts in the group of bolts using, for example, a location index for the particular bolt that
25 describes a location of that bolt in the assembly.

In these illustrative examples, the unique key **135** is used for each component identified in each of the data sets **114**. For example, the different data sets
30 **114** may have different formats, include different pieces of information for different attributes for the components **115** identified, and/or have other differences. However, each of the data sets **114** uses the unique key **135** to distinguish between the different components **115**. In this manner, the unique key **135** may be common to all of the data sets **114**.

Additionally, in these depicted examples, the data **102** may include other information in addition to, and/or in place of, the design data **124**, the manufacturing planning data **126**, and the as-built data **128**. For example, the data **102** may include work order details, notes, maintenance information, and/or other suitable information.

Depending on which phase in the phases **101** of the lifecycle **103** of the object **104** that the object **104** is in, one or more of the data sets **114** for the object **104** may be an empty set or a null set. For example, if the manufacturing planning phase **120** has not yet begun for the object **104**, the manufacturing planning data **126** and the as-built data **128** for the object **104** may be empty data sets.

Further, the design data **124**, the manufacturing planning data **126**, and/or the as-built data **128** may be changed during any of the phases **101** in the lifecycle **103** of the object **104**. For example, changes may be made to the design data **124** during the manufacturing planning phase **120**. In some cases, changes may be made to the design data **124** during the manufacturing phase **122**. Additionally, in managing the data **102** for the object **104**, the object manager **110** updates the data **102** with new data as the new data for the object **104** is entered for the object **104**.

Further, the object manager **110** may perform inspections of the data **102** at any time during the lifecycle **103** of the object **104**. For example, these inspections may be performed while the object **104** is being manufactured, after an assembly for the object **104** has been completed, after manufacturing of the object **104** has been completed, when maintenance of the object **104** is being performed, and/or at other times during the lifecycle **103** of the object.

In one illustrative example, the object manager **110** selects at least two of the data sets **114** for inspection. This selection may be made based on, for

example, user input received at the object manager **110**. In some cases, all of the data sets **114** may be selected.

5 The object manager **110** compares the data sets **114** that are selected to form a comparison **132**. Further, the object manager **110** uses the unique key **135** for each component in the components **115** identified in each of the data sets **114** selected for the comparison to form the comparison **132**.

As one illustrative example, the design data **124** and the manufacturing planning data **126** may be selected for comparison. In this example, the
10 object manager **110** compares the two data sets by determining whether the unique keys for the components **115** identified in the manufacturing planning data **126** match unique keys for the components **115** identified in the design data **124**.

15 Further, the object manager **110** uses the comparison **132** and a policy **133** to determine whether any differences **131** are present between the data sets **114** that are selected. The policy **133** may include a number of rules, criteria, and/or other information for determining whether differences **131** are present between the data sets **114** based on the comparison **132** formed.

20 Differences **131** may be identified when the data **102** in the different data sets **114** does not match as desired. For example, differences **131** may be present when the components **115** and/or the relationships between the components **115** identified in the different data sets **114** do not match as desired. In
25 particular, one or more differences **131** may be identified when the unique keys identified in one data set do not match the unique keys identified in another data set.

As depicted, a difference **134** may comprise an overage **136** of the
30 components **115** for the object **104**, an underage **138** of the components **115** for the object, or a combination of the two. An overage **136** of the components **115** may be present when parts not identified in the data **102** for one phase in the phases **101** of the lifecycle **103** of the object **104** are

identified in the data **102** for another phase. For example, the overage **136** may be present when unique keys for parts not identified in the design data **124** for the object **104** are identified in the manufacturing planning data **126** and/or the as-built data **128**. In this example, the overage **136** is with respect to the design data **124**.

An underage **138** of the components **115** may be present when parts that are identified in the data **102** for one phase in the phases **101** of the lifecycle **103** of the object **104** are not identified in the data **102** for another phase. For example, the underage **138** may be present when the data **102** for the design data **124** identifies unique keys for parts that are not identified in the manufacturing planning data **126** and/or the as-built data **128**. In this example, the underage **138** is with respect to the design data **124**.

A difference **134** between the identifications of the components **115** in the data sets **114** may be present in response to a number of different factors. For example, a difference **134** may be present when a phase in the phases **101** of the lifecycle **103** of the object **104** has not yet been completed. As one illustrative example, the difference **134** may be present between the design data **124** and the as-built data **128** when the manufacturing phase **122** has not yet been completed for the object **104**.

Further, the difference **134** may be present in response to an issue with the availability of parts, certain parts being discontinued, a client request for changes to one or more of the parts for the object **104**, errors in the entry of the data **102** by a human operator, and/or other suitable factors.

In some illustrative examples, a difference **134** between the data sets **114** may be identified even when the unique keys for the components **115** identified in the data sets **114** match. For example, the unique keys identified in the design data **124** may match the unique keys identified in the manufacturing planning data **126**. However, when performing the comparison **132**, the object manager **110** may also compare the information associated

with each unique key **135** for the components **115** in these two data sets to form the comparison **132**.

The object manager **110** uses policy **133** and the comparison **132** of the information to determine whether one or more differences **131** are present. In this example, a difference **134** may be a discrepancy between the information associated with a unique key **135** in the design data **124** and the information associated with the same unique key **135** in the manufacturing planning data **126**.

In these illustrative examples, the object manager **110** is configured to indicate when any differences **131** between the data sets **114** are identified. For example, the object manager **110** may visually present any differences **131** identified on a display on a display system **140**. In particular, the indication may be displayed on a graphical user interface on the display system **140**.

The display system **140** may be in communication with the computer system **108**. In some illustrative examples, the display system **140** may be part of the computer system **108**. The display system **140** may comprise a number of display devices that may be in any number of locations.

As one illustrative example, the object manager **110** displays an indication of any differences **131** on the display system **140** at a manufacturing facility **142** at which the object **104** is being manufactured. In this manner, an operator at the manufacturing facility **142** may be able to respond to the indication of any differences **131** between the data sets **114**.

For example, when an indication of a difference **134** is displayed on the display system **140**, the operator may determine whether the difference **134** between the components **115** identified in the data sets **114** requires a disposition. A disposition, in these illustrative examples, is a resolution for the difference **134**. For example, a disposition may be a correction for the difference **134** when the difference **134** is an error, an explanation for the

difference **134** when the difference **134** is a correct difference or some other suitable type of resolution for the difference **134**.

Further, the disposition may include a description of the difference **134**. For example, when the difference **134** is an error, the disposition may include an error description. When the difference **134** is a correct difference, the disposition may include a difference description. This difference description may be an explanation for the difference **134** and may indicate that the difference **134** is not an error.

The object manager **110** is configured to record dispositions **144** provided for differences **131**. In recording these dispositions **144**, the object manager **110** stores the dispositions **144** in the storage system **113**.

When a difference **134** is identified, at least one of the object manager **110** and an operator establish whether the difference **134** is an error. For example, the operator may determine whether a difference **134** indicated on the display system **140** is the result of an error in the manufacturing of the object **104**. If the difference **134** is the result of an error in the manufacturing of the object **104**, the operator may respond by correcting the error. For example, the operator may correct the as-built data **128**. This correction may be one form of providing a disposition for the difference **134**.

As one illustrative example, the operator may enter new data for one or more of the data sets **114** to correct the error. The object manager **110** is configured to use the new data to update the data sets **114** such that the difference between the data sets **114** is no longer present after the data sets **114** are updated. As another example, if the error is that an incorrect part was used in the assembly of the object **104**, the operator may replace the part in the object **104** with the new part and enter new data into one or more of the data sets **114** to correct the error.

In some cases, the difference **134** may not be the result of an error. For example, the difference **134** may have an explanation that makes the difference **134** correct or acceptable. When the difference **134** is not the result of an error, the operator may respond by entering data that provides an explanation for the difference **134** between the components **115** identified in the data sets **114**.

For example, when the design data **124** identifies a part that is not identified in the as-built data **128**, the operator may provide an explanation for the difference **134**. The explanation may indicate that the part identified in the design data **124** was no longer available when building the object **104** and that a new part was used during manufacturing. This explanation is an example of another type of disposition for the difference **134**.

In one illustrative example, the manufacturing planning data **126** may include instructions for a manufacturing plan for manufacturing the object **104**. During manufacturing, a client using the manufacturing plan to manufacture the object **104** may make a change to one or more of the instructions. For example, the client may add a parameter, such as a torque value, to the instructions. This torque value may not be present in the design data **124**.

Object manager **110** may identify the added torque value in the instructions as a difference **134** between the design data **124** and the manufacturing planning data **126**. As a result, the torque value may be added to the design data **124**. In this manner, future manufacturing plans and/or other information in the manufacturing planning data **126** generated using the design data **124** may include the torque value.

In other illustrative examples, however, an operator may provide an explanation for the difference **134** between the design data **124** and the manufacturing planning data **126**. In particular, the operator may indicate that the torque value was added to the manufacturing plan due to special circumstances during the manufacturing of the object **104**. The explanation

may also indicate that the torque value is not to be added to the design data **124**.

5 Once a disposition has been provided for a particular difference **134**, the particular difference **134** may no longer be identified by the object manager **110** when future comparisons are formed. In other words, the particular difference **134** is no longer flagged as an error between the different data sets **114**.

10 In some illustrative examples, the object manager **110** may indicate the difference **134** by generating and sending out a report identifying the difference **134** between the data sets **114**. The report may be sent to a number of operators at the manufacturing facility **142** and/or at other locations.

15 In another illustrative example, the object manager **110** may indicate the difference **134** between the data sets **114** by performing at least one of sending out an email to an operator identifying the difference **134**, recording the difference **134** in a database or table, generating a visible and/or audible alert, and some other suitable action to indicate that the data **102** in the data
20 sets **114** does not match as desired.

In these illustrative examples, when an inspection of the data sets **114** indicates that differences **131** that represent errors are no longer present between the data sets **114**, these data sets **114** are considered to be
25 reconciled. In this manner, reconciling of the data sets **114** may be performed by ensuring that the different data sets **114** are consistent with each other, according to policy **133**, and that dispositions **144** have been provided for any previously identified differences **131** between the data sets **114**. Further, reconciling the data sets **114** ensures that the configuration **117** for the object
30 **104** identified by each of the different data sets **114** is correct.

When the object **104** is an aircraft, the manufacturing facility **142** for the aircraft and the computer system **108** may be referred to as an aircraft

manufacturing system. In these illustrative examples, some, all, or none of the computer system **108** may be located in the manufacturing facility **142**.

5 In this manner, the object manager **110** provides a system for managing the data **102** for the object **104** to reduce a number of errors that may be present in the data **102** over time during the lifecycle **103** of the object **104**. Further, this type of management of the data **102** may reduce the number of errors made when actually manufacturing the object **104**.

10 Additionally, data for the comparison **132** formed may be saved in the storage system **113** for future use. Further, the identification of the difference **134** may also be stored for future use. For example, data from multiple comparisons performed by the object manager **110** during the developing of the object **104** may be saved. The object manager **110** may be configured to analyze this
15 data and determine the evolution of the degree of matching between the different data sets **114**.

For example, the data sets **114** may be compared on a daily basis and the results of this comparison saved and analyzed. In this manner, the progress
20 in matching the different components **115** may be evaluated over the duration of the development process. Further, the progress of a particular component in the different components **115** may be evaluated. In some illustrative examples, the results of the comparison of the data sets **114** for one component in the components **115** may be compared with the results of the
25 comparison of the data sets **114** for another component in the components **115**.

An operator may also view the data stored from multiple comparisons performed over time to resolve repetitive issues with the matching of the
30 components **115** in the different data sets **114** and/or spot trends in the matching of the components **115**.

When the object **104** takes the form of a vehicle structure **105**, the vehicle structure **105** may comprise hundreds, thousands, or hundreds of thousands of components **115**. Inspecting the data **102** identifying the components **115** in the configuration **117** for the vehicle structure **105** at the different phases **101** in the lifecycle **103** of the vehicle structure **105** may be more time-consuming and require more effort than desired if performed manually by an operator.

For example, time constraints may be present for when identifications of differences **131** have to be made based on contracts, deadlines, regulations, and/or other suitable factors. Further, time constraints may be present in an effort to complete the vehicle structure **105** for delivery as fast as possible, when expected by a customer, or some combination thereof.

The object manager **110** in computer system **108** allows inspections of the data **102** to be performed more rapidly and more efficiently such that these different time constraints may be satisfied. Further, the object manager **110** may allow inspections of different pairs of data sets in the data sets **114** to be compared at substantially the same time. For example, the object manager **110** may compare the design data **124** with the manufacturing planning data **126**, while also comparing the design data **124** with the as-built data **128**.

The illustration of the development environment **100** in **Figure 1** is not meant to imply physical or architectural limitations to the manner in which an advantageous embodiment may be implemented. Other components in addition to and/or in place of the ones illustrated may be used. Some components may be unnecessary. Also, the blocks are presented to illustrate some functional components. One or more of these blocks may be combined and/or divided into different blocks when implemented in an advantageous embodiment.

For example, in some illustrative examples, assemblies for the object **104** may be manufactured at a different manufacturing facility than manufacturing

facility **142**. In other illustrative examples, the object **104** may take some form other than a vehicle structure **105**. For example, the object **104** may be a complex assembly, a complex structure, a building, a bridge, a computer system, a piece of furniture having a complex configuration, or some other suitable type of object.

Further, depending on the implementation, the disposition provided for any difference **134** identified may be performed by software running on computer system **108**. In some cases, the disposition may be generated by an artificial intelligence (AI) implemented in computer system **108**.

Additionally, in other illustrative examples, the data sets **114** stored in the storage system **113** may include data sets for other phases **101** in the lifecycle **103** of the object **104** other than the design phase **118**, the manufacturing planning phase **120**, and the manufacturing phase **122**.

In one illustrative example, the data sets **114** may include reconfiguration data **146** for a reconfiguration phase **148**. In the reconfiguration phase **148**, a client may design a new configuration for the object **104** that is different from the configuration **117** for the object **104** as manufactured by a supplier. For example, the client may wish to change the type of valves used in a hydraulic system in the object **104**. The client may enter new data to form the reconfiguration data **146** identifying the components **115** for the new configuration of the object **104**.

The object manager **110** may be used to determine whether the new configuration for the object **104** meets requirements and can be re-certified. The object manager **110** forms a comparison **132** between the reconfiguration data **146** and the design data **124** for the object **104** using the policy **133**. The policy **133** may include a number of criteria and/or requirements for changes to the design **130** of the object **104**. The object manager **110** identifies any differences **131** between the reconfiguration data **146** and the design data **124** using the comparison **132**.

Further, at least one of the object manager **110** and an operator may determine which of the differences **131** between the reconfiguration data **146** and the design data **124** meet the criteria and/or requirements of the policy **133** and which of the differences **131** are errors. Dispositions **144** may be provided for each of the differences **131** identified.

Depending on the details provided in the dispositions **144** for the differences **131** identified, changes may be made to at least one of the reconfiguration data **146** and the design data **124**. In this illustrative example, the object manager **110** may also update other data sets in the data sets **114** when changes are made to the reconfiguration data **146** and/or the design data **124**.

In this manner, the object manager **110** may be configured to manage the data **102** for the object **104** even after the fully assembled object **104** has been delivered to a client. Further, data sets **114** in the data **102** generated at any point in time during the lifecycle **103** of the object **104** may be compared to ensure that the data **102** is up-to-date and accurate. In some cases, two data sets may be generated during the same phase in the lifecycle **103** of the object **104**. These two data sets may be compared to identify the differences **131** between the two data sets. In this manner, changes that occur during that phase in the lifecycle **103** may be evaluated.

With reference now to **Figure 2**, an illustration of data sets is depicted in accordance with an advantageous embodiment. In this illustrative example, examples of data sets **114** from **Figure 1** are depicted. In particular, an example of one implementation for the design data **124**, the manufacturing planning data **126**, and the as-built data **128** from **Figure 1** is depicted.

In this illustrative example, the design data **124**, the manufacturing planning data **126**, and the as-built data **128** are represented in the form of tree diagrams. These tree diagrams may be displayed on the display system **140** from **Figure 1**.

In this illustrative example, the design data **124** may include a tree diagram **202**. The tree diagram **202** identifies components **204**. These components **204** may include, but not be limited to, a model **206**, a first part **208**, a second part **210**, a third part **212**, a fourth part **214**, a fifth part **216**, and a sixth part **218**. These components **204** may be identified from a design plan for the vehicle structure **105** in **Figure 1**. Further, these components **204** form a design configuration **205** for the vehicle structure **105**.

As depicted, the second part **210** and the third part **212** form an assembly. Further, the fourth part **214**, the fifth part **216**, and the sixth part **218** form an assembly. The first part **208**, the assembly formed by the second part **210** and the third part **212**, and the assembly formed by the fourth part **214**, the fifth part **216**, and the sixth part **218** may be assembled to form the vehicle structure **105** in **Figure 1** according to the model **206**.

In this illustrative example, the manufacturing planning data **126** also may include a tree diagram **220** identifying components **222**. These components **222** may be identified from a manufacturing plan for manufacturing the vehicle structure **105** based on the design data **124**. Further, these components **222** form a manufacturing plan configuration **223** for the vehicle structure **105**.

Additionally, the as-built data **128** also may include a tree diagram **224** identifying components **226**. These components **226** may be identified as the components actually assembled to form the vehicle structure **105**. Further, these components **226** form an as-built configuration **227** for the vehicle structure **105**.

When manufacturing of the vehicle structure **105** has been completed, the components **204** identified in the design data **124** should be the same as the components **222** identified in the manufacturing planning data **126** and the components **226** identified in the as-built data **128**. The object manager **110** in **Figure 1** may select at least two of the design data **124**, the manufacturing

planning data **126**, and the as-built data **128** for comparison in this illustrative example. This comparison may be used to determine whether any differences are present between these different data sets.

5 For example, the components **204** identified in the tree diagram **202** in the design data **124** may be compared to the components **222** identified in the tree diagram **220** for the manufacturing planning data **126**. As depicted, a comparison between the design data **124** and the manufacturing planning data **126** determines that no differences are present between the components
10 **204** identified in the design data **124** and the components **222** identified in the manufacturing planning data **126**.

In particular, the model **206**, the first part **208**, the second part **210**, and the fourth part **214** are identified in the manufacturing planning data **126**. In other
15 words, the model **206**, the first part **208**, the second part **210**, and the fourth part **214** are identified in the manufacturing plan for manufacturing for the vehicle structure **105**.

When comparing the design data **124** and the manufacturing planning data
20 **126**, the object manager **110** may determine that the second part **210** is identified in the manufacturing plan as assembled. For example, the second part **210** may have been received from a supplier of the second part **210** in an assembled form and ready for use.

25 The object manager **110** assumes that any parts used in the assembly of the second part **210** are present when the second part **210** is received in the assembled form. In other words, when comparing the design data **124** and the manufacturing planning data **126**, the object manager **110** assumes that the third part **212** is present in the manufacturing planning data **126**. In this
30 manner, the third part **212** does not need to be specifically identified in the manufacturing planning data **126**.

Further, the object manager **110** also determines that the fourth part **214** is identified in the manufacturing planning data **126** in an assembled form. As a result, the object manager **110** assumes that the fifth part **216** and the sixth part **218** are present in the manufacturing planning data **126**. The fifth part **216** and the sixth part **218** do not need to be specifically identified in the manufacturing planning data **126**.

In this manner, the object manager **110** uses the comparison between the design data **124** and the manufacturing planning data **126** to determine that no differences are present between these two data sets. When no differences are present between two data sets, these data sets are fully matched or fully reconciled.

The object manager **110** then displays match indicators **230**, **232**, **234**, **236**, **238**, **240**, and **242** to indicate that the components **204** in the design data **124** have been matched with the components **222** in the manufacturing planning data **126**. The match indicators **236**, **240**, and **242** next to the third part **212**, the fifth part **216**, and the sixth part **218**, respectively, are up arrows. These up arrows indicate that these parts were identified in the manufacturing planning data **126** based on their respective parent parts being identified in the manufacturing planning data **126**.

In particular, the match indicator **236** next to the third part **212** indicates that the third part **212** has been identified in the manufacturing planning data **126** based on the second part **210** being identified in the manufacturing planning data **126**. Further, the match indicator **240** next to the fifth part **216** and the match indicator **242** next to the sixth part **218** indicate that these parts have been identified in the manufacturing planning data **126** based on the fourth part **214** being identified in the manufacturing planning data **126**.

Further, indicator **244** indicates that all of the components **222** identified in the manufacturing planning data **126** are identified in the design data **124** and that all of the components **204** identified in the design data **124** are identified in the

manufacturing planning data **126**. In a similar manner, the object manager **110** may compare the design data **124** and the as-built data **128**. The object manager **110** also determines that no differences are present between the design data **124** and the as-built data **128**, as indicated by indicator **246**.

5

In this manner, the object manager **110** reconciles the design data **124**, the manufacturing planning data **126**, and the as-built data **128**. In this illustrative example, this reconciliation ensures that the design configuration **205**, the manufacturing plan configuration **223**, and the as-built configuration **227** substantially match as desired.

10

With reference now to **Figure 3**, an illustration of a difference between data sets is depicted in accordance with an advantageous embodiment. In this illustrative example, the object manager **110** in **Figure 1** compares the design data **124** and the manufacturing planning data **126** and determines that a difference is present between these two data sets.

15

For example, this comparison may be performed at a time prior to the comparison performed between the design data **124** and the manufacturing planning data **126** in **Figure 2**, when no differences are present between these data sets. In particular, the comparison between the design data **124** and the manufacturing planning data **126** in **Figure 3** is performed when the fourth part **214** has not yet been received from the supplier and added to the manufacturing plan for manufacturing the vehicle structure **105** in **Figure 1**.

20

25

As a result, the object manager **110** changes the match indicators **238**, **240**, and **242** displayed for the fourth part **214**, the fifth part **216**, and the sixth part **218**, respectively, in **Figure 2** to difference indicators **300**, **302**, and **304**, respectively.

30

As depicted, these difference indicators **300**, **302**, and **304** indicate that the fourth part **214**, the fifth part **216**, and the sixth part **218**, respectively, have not yet been identified in the manufacturing planning data **126**. Further, another

indicator **306** is displayed for the manufacturing planning data **126** instead of the indicator **244** in **Figure 2**. This indicator **306** indicates that the manufacturing planning data **126** has not yet been reconciled or matched with the design data **124**.

5

In other words, not all of the components **204** identified in the design data **124** are identified in the manufacturing planning data **126**. As a result, the object manager **110** may determine that the design configuration **205** does not match the manufacturing plan configuration **223** for the vehicle structure **105**.

10

With reference now to **Figure 4**, an illustration of a data set is depicted in accordance with an advantageous embodiment. In this illustrative example, an example of one of data sets **114** from **Figure 1** is depicted. In particular, an example of one implementation for the design data **124** from **Figure 1** is depicted. As depicted, the design data **124** is represented in a first table **400**.

15

In this illustrative example, the design data **124** is an empty data set. In other words, the first table **400** representing the design data **124** has not yet been populated with information for any components **402**. The components **402** that will be identified in the design data **124** are the components for forming the object **104** from **Figure 1**. In particular, the first table **400** has not yet been populated with information for attributes **404** for any components **402**. This information may be added to the first table **400** during a design phase **118** for the object **104** to be formed by the components **402**.

20

25

The attributes **404** include a part number **408**, a location index **410**, a vendor part number **412**, a material **414**, a weight **416**, a drawing number **418**, an installation side **420**, and a maximum storage temperature **422**. In this illustrative example, the part number **408** for a part is an identifier given to the part by the manufacturer who uses the part to form the object **104**. The location index **410** for a part identifies a location for the part with respect to the configuration **117** for the object **104**. For example, the location index **410** may identify an installation location for the part with respect to the object **104**.

30

The vendor part number **412** is an identifier given to a part by the supplier of that part. The material **414** for a part may be the primary material from which the part is formed. The weight **416** of the part may be described in units such as, for example, without limitation, kilograms (kg). The drawing number **418** for a part is an identifier for the part used in a design for the object **104**. The installation side **420** for a part is the side of the configuration **117** for the object **104** at which the part is to be installed. The maximum storage temperature **420** for a part is a maximum temperature for an environment in which the part is stored. The maximum storage temperature **420** may be described in units, such as, for example, without limitation, degrees Fahrenheit.

In this illustrative example, the part number **408** and the location index **410** for a component form a unique key **424** for that component. For example, the part number **408** is an example of a component identifier **137** from **Figure 1**. The location index **410** is an example of instance identifier **139** from **Figure 1**.

In the illustrative examples, the unique key **424** is different for each of the components **402** to be identified in the design table **400**. For example, a first part and a second part may have the same part number **408**, but the location index **410** may be different for these two components. In this manner, the location index **410** in the unique key **424** allows the different components **402** to be identified in the design data **124** to be distinguished from each other.

With reference now to **Figure 5**, an illustration of a data set is depicted in accordance with an advantageous embodiment. In this illustrative example, an example of one of data sets **114** from **Figure 1** is depicted. In particular, an example of one implementation for the as-built data **128** from **Figure 1** is depicted. As depicted, the as-built data **128** is represented in a second table **500**.

In this illustrative example, the as-built data **128** is an empty data set. In other words, the second table **500** representing the as-built data **128** has not yet

been populated with information for any components **502**. In particular, the second table **500** has not yet been populated with an identification of components **502** and/or information for attributes **504** for these components **502**. The components **502** to be identified in the as-built data **128** are the components that are being assembled to form the object **104**. The second table **520** is populated with information during a manufacturing phase **123** for the object **104**.

The attributes **504** for these components **502** include a part number **508**, a location index **510**, an installation tool **512**, a certification required indication **514**, a storage location **516**, an assembly jig number **518**, an installation side **520**, and an assembly cell **522**. The part number **508** and the location index **510** for a part form a unique key **524** for the part, similar to the unique key **424** identified in the design data **124** in **Figure 4**. In other words, the unique key **524** is of the same type as the unique key **424** in **Figure 4**.

The installation tool **512** for a part is the tool used for installing the part to form the object **104**. The certification required indication **514** for a part indicates whether the part requires a certification. The storage location **516** for a part is the location in which the part is stored. The assembly jig number **518** for a part is an identifier for an assembly jig for the part. The assembly cell **522** for a part may be a location in a manufacturing facility in which the part is installed in an assembly for the object.

With reference now to **Figure 6**, an illustration of a comparison between two data sets is depicted in accordance with an advantageous embodiment. In this illustrative example, the first table **400** from **Figure 4** and the second table **500** from **Figure 5** have been populated with information. In particular, the design data **124** in the first table **400** identifies a first part **600** and a second part **602** as the components **402** for the object **104** as specified by a design of the object **104**. The as-built data **128** in the second table **500** identifies a third part **604** for the object **104**.

In this illustrative example, the first part **600** and the second part **602** have the same part number **408**. However, the location index **410** for the first part **600** is different from the location index **410** for the second part **602**. In this manner, the unique key **424** for the first part **600** and the unique key **424** for the second part **602** allows these parts to be distinguished from each other even when they have the same part number **408**. Further, this unique key **424** is common to the as-built data **128**. In other words, the unique key **424** used for the components **402** identified in the design data **124** is the same type of unique key **524** used for the components **502** identified in the as-built data **128**.

The object manager **110** from **Figure 1** may be used to form a comparison **132** between the as-built data **128** represented in second table **500** and the design data **124** represented in first table **400** in **Figure 4** to ensure that the configuration **117** for the object **104** being manufactured is a correct configuration as specified by the design data **124**. The comparison **132** is formed by matching the unique key **424** for each of the components **402** identified in the design data **124** with the unique key **524** for each of the components **502** identified in the as-built data **128**.

For example, when the comparison **132** is formed, a match **606** is identified between the unique key **424** for the first part **600** identified in the design data **124** and the unique key **524** for the third part **604** identified in the as-built data **128**. However, no match is found between the unique key **424** for the second part **602** identified in the design data **124** and the unique key **524** for any of the components **502** identified in the as-built data **128**.

This mismatch indicates an underage for the configuration **117** of the object **104** with respect to the design data **124**. In other words, fewer parts than needed as specified by the design data **124** have been assembled for the object **104**. In response to this difference, an operator may determine whether the difference is the result of an error in the design data **124** and/or the as-

built data **128** or the difference has an acceptable explanation. The operator may provide a disposition for this difference by providing the explanation.

With reference now to **Figure 7**, an illustration of a comparison between two data sets is depicted in accordance with an advantageous embodiment. In this illustrative example, the first table **400** from **Figure 4** and the second table **500** from **Figure 5** have been populated with information. In particular, the design data **124** in the first table **400** identifies a first part **700** as a component in components **402** for the object **104** as specified by a design of the object **104**. The as-built data **128** in the second table **500** identifies a second part **702** and a third part **704** for the object **104**.

The object manager **110** from **Figure 1** may be used to form a comparison **132** between the as-built data **128** represented in second table **500** and the design data **124** represented in first table **400** in **Figure 4** to ensure that the configuration **117** for the object **104** being manufactured is a correct configuration as specified by the design data **124**.

For example, when the comparison **132** is formed, a match **706** is identified between the unique key **424** for the first part **700** identified in the design data **124** and the unique key **524** for the second part **702** identified in the as-built data **128**. However, no match is found between the unique key **524** for the third part **704** identified in the as-built data **128** and the unique key **424** for any of the components **402** identified in the design data **124**.

This mismatch indicates an overage for the configuration **117** of the object **104** with respect to the design data **124**. In other words, more parts than needed as specified by the design data **124** have been assembled to form the object **104**. Further, in response to this difference, an operator may determine whether the difference is the result of an error in the design data **124** and/or the as-built data **128** or the difference has an acceptable explanation. The operator may provide a disposition for this difference by providing the explanation.

With reference now to **Figure 8**, an illustration of a comparison between two data sets is depicted in accordance with an advantageous embodiment. In this illustrative example, the first table **400** from **Figure 4** and the second table **500** from **Figure 5** have been populated with information. In particular, the design data **124** in the first table **400** identifies a first part **800** and a second part **802** as the components **402** for the object **104**. The as-built data **128** in the second table **500** identifies a third part **804** and a fourth part **806** for the object **104**.

The object manager **110** from **Figure 1** may form a comparison **132** between these two data sets. This comparison **132** may indicate that the components **402** identified in the design data **124** match the components **502** identified in the as-built data **128**. In particular, a match **808** is found between the unique key **424** for the first part **800** identified in the design data **124** and the unique key **524** for the third part **804** identified in the as-built data **128**. Further, a match **810** is found between the unique key **424** for the second part **802** identified in the design data **124** and the unique key **524** for the fourth part **806** identified in the as-built data **128**.

However, when forming the comparison **132** between the two data sets, the object manager **110** may use a policy **133** to determine whether any difference is present between the two data sets. For example, the policy **133** may indicate that a component identified for the object **104** in the manufacturing phase **122** may need to be stored in a storage location **516** in which a temperature of the storage location **516** does not exceed a maximum storage temperature **422** for the particular component. The policy **133** may also include, for example, a list of storage locations and the maximum temperatures reaches at those storage locations.

In one illustrative example, the policy **133** may indicate that the storage location, W-98, reaches a maximum temperature greater than about **100** degrees Fahrenheit. As a result, the object manager **110** identifies difference

812 between the information provided for the first part **800** in the design data **124** and the information provided for the third part **804** in the as-built data **128** using the policy **133**. Further the object manager **110** identifies difference **814** between the information provided for the second part **802** in the design data **124** and the information provided for the fourth part **806** in the as-built data **128** using the policy **133**. These differences may be referred to as discrepancies or inconsistencies in the information for the attributes provided by the two data sets.

With reference now to **Figure 9**, an illustration of a graphical user interface displaying results of a comparison between two data sets is depicted in accordance with an advantageous embodiment. In this illustrative example, a graphical user interface **900** may be displayed on the display system **140** from **Figure 1**. The graphical user interface **900** displays the results for a comparison between design data, such as design data **124** in **Figure 1**, and manufacturing planning data, such as manufacturing planning data **126** in **Figure 1**.

In particular, the graphical user interface **900** displays a tree diagram **902** identifying components **903**. The portion of the tree diagram **902** displayed in the graphical user interface **900** may identify the components **903** identified from the design data **124**. In this illustrative example, a portion **904** of the tree diagram **902** is shown in an exploded view of the tree diagram **902** for an assembly **906**. The assembly **906** comprises a plurality of parts **908**.

Further, an information section **905** is also displayed in the graphical user interface **900**. This information section **905** displays the results of the comparison between the two data sets, as well as other suitable information.

A particular part in the components **903** identified in the tree diagram **902** may be matched to the manufacturing planning data **126** when, for example, a shop order instance (SOI) is present for the particular part. The presence of a shop order instance indicates that the particular part has been identified in the

manufacturing plan and that an order for the particular part has been placed with the supplier.

5 In this illustrative example, the assembly **906** has been selected in the tree diagram **902** for the design data **124**. In response to this selection, information about the assembly **906** is displayed in the information section **905**. Further, a shop order instance tab **910** is also displayed in the information section **905**. The presence of the shop order instance tab **910** indicates that the assembly **906** is also identified in the manufacturing
10 planning data **126**. In particular, a shop order number **912** for the assembly **906** is displayed under the shop order instance tab **910**.

Further, as indicated, match indicators **914** displayed next to the assembly **906** and the parts **908** that form the assembly **906** indicate that no differences
15 are found between the design data **124** and the manufacturing planning data **126** with respect to the assembly and the plurality of parts **908**. In other words, the match indicators **914** indicate that the assembly **906** and all of the parts **908** that form the assembly **906** have been identified in the manufacturing planning data **126**.

20

With reference now to **Figure 10**, an illustration of a graphical user interface displaying results of another comparison between two data sets is depicted in accordance with an advantageous embodiment. In this illustrative example, a different portion **1000** of the tree diagram **902** is displayed on the graphical
25 user interface **1000**. This portion **1000** is for an assembly **1002** that includes a plurality of parts **1004**.

In this illustrative example, a part **1006** in the parts **1004** for the assembly **1002** has been selected. In response to this selection, information for the part
30 **1006** is displayed in the information section **905** on the graphical user interface **900**. When a difference is present between the design data **124** and the manufacturing planning data **126**, an indication of this difference is displayed under a comparison tab **1007** in the information section **905**.

In this illustrative example, an underage indication **1008** is displayed under the comparison tab **1007**. This underage indication **1008** indicates that the part **1006** identified in the tree diagram **902** for the design data **124** has not been
5 identified in the manufacturing planning data **126**. This underage is also indicated by the absence of a shop order instance tab, such as the shop order instance tab **910** displayed on the graphical user interface **900** in **Figure 9**.

This underage is further indicated by a difference indicator **1010** next to the
10 part **1006** in the tree diagram **902**. A partial match indicator **1012** is displayed next to the assembly **1002** to indicate that not all of the parts **1004** for the assembly **1002** have been identified in the manufacturing planning data **126**.

With reference now to **Figure 11**, an illustration of a graphical user interface
15 displaying results of a comparison between two data sets is depicted in accordance with an advantageous embodiment. In this illustrative example, the portion of the tree diagram **902** displayed on the graphical user interface **900** shows the components **903** that were identified in the manufacturing planning data **126** but not identified in the design data **124** in **Figure 1**.

20

In this illustrative example, information may be displayed under the shop order instance tab **910** in the information section **905** for a component identified in the manufacturing planning data **126**. Indicators **1100** next to the components
25 **903** identified in the tree diagram **902**, in this illustrative example, indicate that these components **903** have been identified in the manufacturing planning data **126** but not in the design data **124**.

With reference now to **Figure 12**, an illustration of a graphical user interface
30 displaying results of a comparison between two data sets is depicted in accordance with an advantageous embodiment. In this illustrative example, a part **1200** has been selected from the components **903** identified in the tree diagram **902**. In response to this selection, information for the part **1200** is displayed under a variance tab **1202** in the information section **905**.

When a difference is identified, an operator may determine whether the difference is an error. If the difference is an error, the operator may enter user input through the graphical user interface **900** that allows the operator to correct the error.

Information about this correction may be entered in a notes section **1206** and/or a user comments section **1208** under a dispositions tab **1210** under the variance tab **1202**. Further, when the difference is not an error, the operator may enter an explanation for the difference in the notes section **1206** and/or the user comments section **1208**.

As depicted in this example, a closed indicator **1204** next to the part **1200** indicates that a difference that was previously present between the design data **124** and the manufacturing planning data **126** in **Figure 1** has now been resolved. In other words, an explanation for the difference was entered in the notes section **1206** and the user comments section **1208**. Further, a status **1212** of this difference has been identified as closed. In other illustrative examples, when the difference has not yet been resolved, the status **1212** of the difference may be identified as open.

With reference now to **Figure 13**, an illustration of a flowchart of a process for identifying parts in a vehicle is depicted in accordance with an advantageous embodiment. The process illustrated in **Figure 13** may be implemented using the object manager **110** in **Figure 1**.

The process begins by identifying data sets for the vehicle structure (operation **1300**). Each data set identifies the components for the vehicle structure in a different phase in a lifecycle for the vehicle structure. In particular, each data set represents the configuration of the vehicle structure at a different phase in the lifecycle of the vehicle structure.

The process then compares the data sets for the vehicle structure (operation **1302**). Next, the process identifies differences between the identifications of the components in the data sets (operation **1304**). The operation **1304** may be performed by matching the unique keys for the different components in the different data sets.

Thereafter, the process establishes whether the differences between the identifications of the components in the data sets are errors (operation **1306**). For example, a difference may be the result of an error during the entry of data.

The process then records error descriptions of established errors and difference descriptions of correct but different identifications of the components between the data sets (operation **1308**). These error descriptions and difference descriptions are examples of the dispositions **144** in **Figure 1**. In the operation **1308**, when recorded, these error descriptions and difference descriptions are stored in a storage system, such as the storage system **113** in **Figure 3**.

Next, the process corrects the errors in the respective data set of the data sets and annotates correct differences in one or more of the data sets to establish a corrected correlation between identifications of the components in the data sets (operation **1310**), with the process terminating thereafter. In the operation **1310**, the corrections and annotations may be made by, for example, the object manager **110** from **Figure 1** and/or an operator. For example, an operator may correct the differences that are the results of errors and make annotations providing explanations for the differences that are correct differences using a graphical user interface.

With reference now to **Figure 14**, an illustration of a flowchart of a process for managing components used in a vehicle structure is depicted in accordance with an advantageous embodiment. The process illustrated in **Figure 14** may be implemented using, for example, the object manager **110** in **Figure 1**.

The process begins by the object manager identifying a first data set and a second data set for comparison (operation **1400**). The first data set may be, for example, the design data **124** in **Figure 1** or the manufacturing planning data **126** in **Figure 1**. The second data set may be, for example, the manufacturing planning data **126** in **Figure 1** or the as-built data **128** in **Figure 1**.

Next, the object manager compares the components identified in the first data set with the components identified in the second data set (operation **1402**). In operation **1402**, the components identified in the first data set and the components identified in the second data set are matched to form a list of components.

The components in this list of components may include matched components and/or unmatched components. In this illustrative example, a matched component is a component that is identified in both the first data set and the second data set. An unmatched component is a component that is identified in only one of these two data sets.

The object manager displays the list of components in the form of a tree diagram on a graphical user interface (operation **1404**). Next, the object manager selects a component from the list of components (operation **1406**).

The object manager then determines whether the component is a matched component or an unmatched component (operation **1408**). If the component is a matched component, the object manager determines whether any additional unprocessed components are present in the list of components (operation **1410**).

If additional unprocessed components are not present in the list of components, the object manager displays the results of the comparison in the graphical user interface (operation **1412**), with the process terminating

thereafter. However, if additional unprocessed components are present in the list of components, the process returns to operation **1406** as described above.

5 With reference again to operation **1408**, if the component is an unmatched component, the object manager determines whether a disposition has been previously provided for the difference between the first data set and the second data set with respect to this component (operation **1414**). If a disposition has been previously provided, the process proceeds to operation **1410** as described above.

10 Otherwise, if a disposition has not been previously provided, the object manager generates an indication on the graphical user interface that a disposition is needed for the component (operation **1416**). This indication may be, for example, a graphical indicator for display next to the component in
15 the tree diagram. As another example, the indication may be text for display in a section under a tab on the graphical user interface that is displayed in response to a selection of the component in the tree diagram. Thereafter, the process returns to operation **1410** as described above.

20 In these illustrative examples, an operator may view the results of the comparison on the graphical user interface to enter new data. The new data may include, for example, explanations for differences identified between the components identified in the first data set and the second data set, new data correcting errors in the manufacturing of the vehicle structure, and/or other
25 suitable data.

In these illustrative examples, the first data set and the second data set are considered fully matched or fully reconciled when no differences are present between the first data set and the second data set or when a disposition has
30 been provided for any differences that have been identified between the two data sets.

With reference now to **Figure 15**, an illustration of a flowchart of a process for manufacturing a vehicle is depicted in accordance with an advantageous embodiment. The process illustrated in **Figure 15** may be implemented in manufacturing facility **142** in **Figure 1**.

5

The process begins by generating manufacturing planning data for the vehicle (operation **1500**). The manufacturing planning data for the vehicle includes identifications of components for the vehicle. These components may include, for example, physical parts, tools, instructions, software components, and/or

10

other components that may be needed for manufacturing the vehicle.

The manufacturing planning data is compared to design data for the vehicle (operation **1502**). The design data also includes identifications of components for the vehicle as specified in a design for the vehicle. The process

15

determines whether any differences are present between the identifications of the components for the vehicle in these two data sets (operation **1504**). If no differences are present, the vehicle is manufactured (operation **1506**).

The process generates as-built data for the vehicle as the vehicle is manufactured (operation **1508**). The as-built data for the vehicle includes identifications of the components in the assembled configuration for the vehicle. The process then compares the as-built data with the manufacturing planning data (operation **1510**). The process determines whether any differences are present between the identification of components for the

20

25

vehicle in these two data sets (operation **1512**). If no differences are present, the process terminates.

Otherwise, if any differences are present, the process waits until a disposition has been provided for each of the differences present (operation **1514**). A disposition is a resolution for a difference. For example, if the difference is an error, then the disposition may be a correction to that error. In some cases, the disposition may be an explanation for the difference indicating that the difference is acceptable. The disposition may be provided by user input

30

entered by an operator, may be generated by an artificial intelligence system, or may be generated in some other suitable manner. Thereafter, the process terminates.

5 With reference again to operation **1504**, if any differences are present, the process waits until a disposition has been provided for each of the differences present (operation **1516**). The process then proceeds to operation **1506** as described above.

10 The flowcharts and block diagrams in the different depicted embodiments illustrate the architecture, functionality, and operation of some possible implementations of apparatus and methods in an advantageous embodiment. In this regard, each block in the flowcharts or block diagrams may represent a module, segment, function, and/or a portion of an operation or step. For
15 example, one or more of the blocks may be implemented as program code, in hardware, or a combination of the program code and hardware. When implemented in hardware, the hardware may, for example, take the form of integrated circuits that are manufactured or configured to perform one or more operations in the flowcharts or block diagrams.

20 In some alternative implementations of an advantageous embodiment, the function or functions noted in the block may occur out of the order noted in the figures. For example, in some cases, two blocks shown in succession may be executed substantially concurrently, or the blocks may sometimes be
25 performed in the reverse order, depending upon the functionality involved. Also, other blocks may be added in addition to the illustrated blocks in a flowchart or block diagram.

Turning now to **Figure 16**, an illustration of a data processing system is depicted in accordance with an advantageous embodiment. Data processing
30 system **1600** is an example of one implementation for one or more of computers **112** in **Figure 1**. In this illustrative example, a data processing system **1600** includes a communications framework **1602**, which provides

communications between a processor unit **1604**, memory **1606**, persistent storage **1608**, a communications unit **1610**, an input/output (I/O) unit **1612**, and a display **1614**.

5 The processor unit **1604** serves to execute instructions for software that may be loaded into the memory **1606**. The processor unit **1604** may be a number of processors, a multi-processor core, or some other type of processor, depending on the particular implementation. A number, as used herein with
10 **1604** may be implemented using a number of heterogeneous processor systems in which a main processor is present with secondary processors on a single chip. As another illustrative example, the processor unit **1604** may be a symmetric multi-processor system containing multiple processors of the same type.

15

 The memory **1606** and the persistent storage **1608** are examples of storage devices **1616**. A storage device is any piece of hardware that is capable of storing information, such as, for example, without limitation, data, program code in functional form, and/or other suitable information either on a
20 temporary basis and/or a permanent basis. The storage devices **1616** may also be referred to as computer readable storage devices in these examples. The memory **1606**, in these examples, may be, for example, a random access memory or any other suitable volatile or non-volatile storage device. The persistent storage **1608** may take various forms, depending on the particular
25 implementation.

 For example, the persistent storage **1608** may contain one or more components or devices. For example, the persistent storage **1608** may be a hard drive, a flash memory, a rewritable optical disk, a rewritable magnetic
30 tape, or some combination of the above. The media used by the persistent storage **1608** also may be removable. For example, a removable hard drive may be used for the persistent storage **1608**.

The communications unit **1610**, in these examples, provides for communications with other data processing systems or devices. In these examples, the communications unit **1610** is a network interface card. The communications unit **1610** may provide communications through the use of either or both physical and wireless communications links.

The input/output unit **1612** allows for input and output of data with other devices that may be connected to the data processing system **1600**. For example, the input/output unit **1612** may provide a connection for user input through a keyboard, a mouse, and/or some other suitable input device. Further, the input/output unit **1612** may send output to a printer. The display **1614** provides a mechanism to display information to a user.

Instructions for the operating system, applications, and/or programs may be located in the storage devices **1616**, which are in communication with the processor unit **1604** through the communications framework **1602**. In these illustrative examples, the instructions are in a functional form on the persistent storage **1608**. These instructions may be loaded into the memory **1606** for execution by the processor unit **1604**. The processes of the different embodiments may be performed by the processor unit **1604** using computer-implemented instructions, which may be located in a memory, such as the memory **1606**.

These instructions are referred to as program code, computer usable program code, or computer readable program code that may be read and executed by a processor in the processor unit **1604**. The program code in the different embodiments may be embodied on different physical or computer readable storage media, such as the memory **1606** or the persistent storage **1608**.

Program code **1618** is located in a functional form on computer readable media **1620** that is selectively removable and may be loaded onto or transferred to the data processing system **1600** for execution by the processor unit **1604**. The program code **1618** and the computer readable media **1620**

form a computer program product **1622** in these examples. In one example, the computer readable media **1620** may be computer readable storage media **1624** or computer readable signal media **1626**. The computer readable storage media **1624** may include, for example, an optical or magnetic disk that is inserted or placed into a drive or other device that is part of the persistent storage **1608** for transfer onto a storage device, such as a hard drive, that is part of the persistent storage **1608**. The computer readable storage media **1624** also may take the form of a persistent storage, such as a hard drive, a thumb drive, or a flash memory, that is connected to the data processing system **1600**. In some instances, the computer readable storage media **1624** may not be removable from the data processing system **1600**.

In these examples, the computer readable storage media **1624** is a physical or tangible storage device used to store the program code **1618** rather than a medium that propagates or transmits the program code **1618**. The computer readable storage media **1624** is also referred to as a computer readable tangible storage device or a computer readable physical storage device. In other words, the computer readable storage media **1624** is a media that can be touched by a person.

Alternatively, the program code **1618** may be transferred to the data processing system **1600** using the computer readable signal media **1626**. The computer readable signal media **1626** may be, for example, a propagated data signal containing the program code **1618**. For example, the computer readable signal media **1626** may be an electromagnetic signal, an optical signal, and/or any other suitable type of signal. These signals may be transmitted over communications links, such as wireless communications links, optical fiber cable, coaxial cable, a wire, and/or any other suitable type of communications link. In other words, the communications link and/or the connection may be physical or wireless in the illustrative examples.

In some advantageous embodiments, the program code **1618** may be downloaded over a network to the persistent storage **1608** from another

device or data processing system through the computer readable signal media **1626** for use within the data processing system **1600**. For instance, program code stored in a computer readable storage medium in a server data processing system may be downloaded over a network from the server to the data processing system **1600**. The data processing system providing the program code **1618** may be a server computer, a client computer, or some other device capable of storing and transmitting the program code **1618**.

The different components illustrated for the data processing system **1600** are not meant to provide architectural limitations to the manner in which different embodiments may be implemented. The different advantageous embodiments may be implemented in a data processing system including components in addition to or in place of those illustrated for the data processing system **1600**. Other components shown in **Figure 16** can be varied from the illustrative examples shown. The different embodiments may be implemented using any hardware device or system capable of running program code. As one example, the data processing system may include organic components integrated with inorganic components and/or may be comprised entirely of organic components excluding a human being. For example, a storage device may be comprised of an organic semiconductor.

In another illustrative example, the processor unit **1604** may take the form of a hardware unit that has circuits that are manufactured or configured for a particular use. This type of hardware may perform operations without needing program code to be loaded into a memory from a storage device to be configured to perform the operations.

For example, when the processor unit **1604** takes the form of a hardware unit, the processor unit **1604** may be a circuit system, an application specific integrated circuit (ASIC), a programmable logic device, or some other suitable type of hardware configured to perform a number of operations. With a programmable logic device, the device is configured to perform the number of operations. The device may be reconfigured at a later time or may be

permanently configured to perform the number of operations. Examples of programmable logic devices include, for example, a programmable logic array, programmable array logic, a field programmable logic array, a field programmable gate array, and other suitable hardware devices. With this type of implementation, the program code **1618** may be omitted, because the processes for the different embodiments are implemented in a hardware unit.

In still another illustrative example, the processor unit **1604** may be implemented using a combination of processors found in computers and hardware units. The processor unit **1604** may have a number of hardware units and a number of processors that are configured to run the program code **1618**. With this depicted example, some of the processes may be implemented in the number of hardware units, while other processes may be implemented in the number of processors.

In another example, a bus system may be used to implement the communications framework **1602** and may be comprised of one or more buses, such as a system bus or an input/output bus. Of course, the bus system may be implemented using any suitable type of architecture that provides for a transfer of data between different components or devices attached to the bus system.

Additionally, a communications unit may include a number of devices that transmit data, receive data, or transmit and receive data. A communications unit may be, for example, a modem or a network adapter, two network adapters, or some combination thereof. Further, a memory may be, for example, the memory **1606**, or a cache, such as found in an interface and memory controller hub that may be present in the communications framework **1602**.

Advantageous embodiments of the disclosure may be described in the context of an aircraft manufacturing and service method **1700** as shown in **Figure 17** and an aircraft **1800** as shown in **Figure 18**.

Turning first to **Figure 17**, an illustration of an aircraft manufacturing and service method is depicted in accordance with an advantageous embodiment. During pre-production, the aircraft manufacturing and service method **1700** may include a specification and design **1702** of the aircraft **1800** in **Figure 18** and a material procurement **1704**.

During production, component and subassembly manufacturing **1706** and system integration **1708** of the aircraft **1800** in **Figure 18** takes place. Thereafter, the aircraft **1800** in **Figure 18** may go through certification and delivery **1710** in order to be placed in service **1712**. While in service **1712** by a customer, the aircraft **1800** in **Figure 18** is scheduled for routine maintenance and service **1714**, which may include modification, reconfiguration, refurbishment, and other maintenance or service.

Each of the processes of the aircraft manufacturing and service method **1700** may be performed or carried out by a system integrator, a third party, and/or an operator. In these examples, the operator may be a customer. For the purposes of this description, a system integrator may include, without limitation, any number of aircraft manufacturers and major-system subcontractors; a third party may include, without limitation, any number of vendors, subcontractors, and suppliers; and an operator may be an airline, a leasing company, a military entity, a service organization, and so on.

With reference now to **Figure 18**, an illustration of an aircraft is depicted in which an advantageous embodiment may be implemented. In this example, the aircraft **1800** is produced by the aircraft manufacturing and service method **1700** in **Figure 17** and may include an airframe **1802** with a plurality of systems **1804** and an interior **1806**. Examples of the systems **1804** include one or more of a propulsion system **1808**, an electrical system **1810**, a hydraulic system **1812**, and an environmental system **1814**. Any number of other systems may be included. Although an aerospace example is shown,

different advantageous embodiments may be applied to other industries, such as the automotive industry.

5 Apparatuses and methods embodied herein may be employed during at least one of the stages of the aircraft manufacturing and service method **1700** in **Figure 17**.

10 In one illustrative example, components or subassemblies produced in the component and subassembly manufacturing **1706** in **Figure 17** may be fabricated or manufactured in a manner similar to components or subassemblies produced while the aircraft **1800** is in service **1712** in **Figure 17**. As yet another example, one or more apparatus embodiments, method embodiments, or a combination thereof may be utilized during production stages, such as the component and subassembly manufacturing **1706** and the
15 system integration **1708** in **Figure 17**. One or more apparatus embodiments, method embodiments, or a combination thereof may be utilized while the aircraft **1800** is in service **1712** and/or during the maintenance and service **1714** in **Figure 17**. The use of a number of the different advantageous embodiments may substantially expedite the assembly of and/or reduce the
20 cost of the aircraft **1800**.

Thus, the different advantageous embodiments provide a method and apparatus for managing a vehicle structure. In one advantageous embodiment, a method for managing a vehicle structure is provided. Data
25 sets for managing the vehicle structure are identified. Each data set includes identifications of the components for the vehicle structure in a different phase in a lifecycle of the vehicle structure. A determination is made as to whether a difference is present between the identifications of the components in the data sets. The difference between the data sets is indicated when the difference is
30 present between the identifications of the components in the data sets.

The description of the different advantageous embodiments has been presented for purposes of illustration and description and is not intended to be

exhaustive or limited to the embodiments in the form disclosed. Many modifications and variations will be apparent to those of ordinary skill in the art. Further, different advantageous embodiments may provide different advantages as compared to other advantageous embodiments. The
5 embodiment or embodiments selected are chosen and described in order to best explain the principles of the embodiments, the practical application, and to enable others of ordinary skill in the art to understand the disclosure for various embodiments with various modifications as are suited to the particular use contemplated.

10

EMBODIMENTS IN WHICH AN EXCLUSIVE PROPERTY OR PRIVILEGE IS CLAIMED ARE DEFINED AS FOLLOWS:

1. A method for managing a configuration of a vehicle structure, the method
5 comprising:

assigning a unique key to components in a plurality of components of
a vehicle structure in each of a plurality of data sets, the unique key
for a particular component in the plurality of components

10 distinguishing the particular component from other components in the
plurality of components for the vehicle structure, the unique key
including a component identifier and an instance identifier, the
instance identifier distinguishing components having the same
component identifier by describing a location in the vehicle structure
15 of each component having the same component identifier;

comparing a first data set with a second data set, the first data set
corresponding to the plurality of components of the vehicle structure
at a first phase in a lifecycle of the vehicle structure, and the second
20 data set corresponding to the plurality of components of the vehicle
structure at a second phase in the lifecycle of the vehicle structure,
the first data set comprising design data or manufacturing planning
data and the second data set comprising as-built data, wherein each
data set includes identifications of components for the vehicle
25 structure, the comparing including comparing first unique keys for the
identifications of the components in the first data set with second
unique keys for the identifications of the components in the second
data set; and

30 identifying differences between the identifications of the components
in the data sets;

wherein two or more of the data sets have different formats and include different pieces of information for different attributes for the components, and

5

wherein the unique key is common to all of the data sets and each of the data sets uses the unique key to distinguish between different components in the data sets.

10 **2.** The method of claim **1** further comprising:

establishing whether the differences between the identifications of the components in the data sets are errors, the differences determined by a policy and a comparison of the first data set and the second data set;

15

recording error descriptions of established errors and difference descriptions of correct but different identifications of the components between the data sets; and

20

correcting the error in the respective data set of the data sets and annotating correct differences in one or more of the data sets to establish a corrected correlation between identifications of the components in the data sets.

25

3. The method of any one of claims **1** or **2** further comprising:

visually presenting on a graphical user interface a display to represent the differences identified between the identifications of the components in the data sets.

30

4. The method of any one of claims 1 to 3 further comprising:

recording dispositions for the differences identified between the identifications of the components in the data sets.

5

5. The method of claim 4 further comprising:

repeating the steps of comparing the data sets; identifying the differences between the identifications of the components in the data sets; and recording the dispositions for the differences identified between the identifications of the components in the data sets until the differences are no longer present between the identifications of the components in the data sets.

10

- 15 6. The method of any one of claims 1 to 5, wherein comparing the data sets comprises:

determining whether an identification of a particular component in the first data set matches any of the identifications of the components in the second data set, wherein the particular component is an assembly of a plurality of components for the vehicle structure; and

20

assuming that all of the plurality of components for the assembly are present in the second data set if the identification for the particular component in the first data set matches one of the identifications of the components in the second data set.

25

7. The method of any one of claims 1 to 6, wherein the differences between the identifications of the components in the data sets indicate at least one of overages and underages in the components for the vehicle structure with

30

respect to the configuration of the vehicle structure at a particular phase in the lifecycle of the vehicle structure and further comprising:

visually presenting on a display graphical indicators indicating the overages and the underages in the components for the vehicle structure; and

rectifying components from the vehicle identified as overages or underages.

8. The method of any one of claims 1 to 7, wherein the first data set corresponds to the plurality of components of the vehicle structure at a design phase of the lifecycle of the vehicle structure and the second data set corresponds to the plurality of components of the vehicle structure at a manufacturing planning phase of the life cycle of the vehicle, and wherein the method further comprises:

comparing the second data set with a third data set, the third data set corresponding to the plurality of components of the vehicle structure at a manufacturing design phase of the lifecycle of the vehicle structure.

9. The method of any one of claims 1 to 8, wherein the unique key for the particular component is common to all of the data sets, and wherein unique keys for the identifications of the components in all of the data sets have a same format, and wherein the unique key further comprises information for a component including an installation tool for use with the component.

10. The method of any one of claims 1 to 9, wherein the steps of comparing the data sets and identifying the differences between the identifications of the components in the data sets are performed during one or more of the different phases of the lifecycle of the vehicle structure.

11. The method of any one of claims 1 to 10 further comprising:

5 updating at least one of the data sets based on the differences
between the identifications of the components in the data sets.

12. The method of any one of claims 1 to 11, wherein the vehicle structure is an
aircraft, an aircraft structure, a spacecraft, an automobile, a train, a surface
ship, a submarine, a jet engine, a wing box, or an assembly for a vehicle.

10 13. The method of claim 1, further comprising:

displaying a comparison of the first data set and the second data set
on a graphical user interface;

15 wherein the graphical user interface comprises a first table and a
second table;

20 wherein the first table provides a component number, a location index,
a vendor part number, at least one designation of material for the
component, a weight of the component, a drawing number associated
with the component, an installation side, and a maximum storage
temperature for the component; and

25 wherein the second table provides the component number, the location
index, an installation tool associated with the component, an indication
of a requirement for certification, a storage location, an assembly jig
number associated with the component, the installation side, and an
assembly cell.

30 14. An apparatus comprising:

a storage system including a unique key for each component in a plurality of components of a vehicle structure, the unique key stored in a plurality of data sets, the unique key for a particular component in the plurality of components distinguishing the particular component from other components in the plurality of components for the vehicle structure, the unique key including a component identifier and an instance identifier, the instance identifier distinguishing components having the same component identifier by describing a location in the vehicle structure of each component having the same component identifier; and

a computer system configured to:

compare a first data set with a second data set, the first data set corresponding to the plurality of components of the vehicle structure at a first phase in a lifecycle of the vehicle structure, and the second data set corresponding to the plurality of components of the vehicle structure at a second phase in the lifecycle of the vehicle structure, the first data set comprising design data or manufacturing planning data and the second data set comprising as-built data, wherein each data set includes identifications of components for the vehicle structure, wherein comparing comprises comparing first unique keys for the identification of the components in the first data set with second unique keys for the identification of the components in the second data set; and

identify differences between the identifications of the components in the data sets;

wherein two or more of the data sets have different formats and include different pieces of information for different attributes for the components, and

5 wherein the unique key is common to all of the data sets and each of the data sets uses the unique key to distinguish between different components in the data sets.

10 **15.** The apparatus of claim **14**, wherein the computer system is further configured to:

establish whether the differences between the identifications of the components in the data sets are errors based on a policy, the policy including a criteria for a component; and

15 record error descriptions of established errors and difference descriptions of correct but different identifications of the components between the data sets.

20 **16.** The apparatus of any one of claims **14** or **15**, wherein in being configured to identify the differences between the identifications of the components in the data sets, the computer system is configured to determine whether at least one of an overage and an underage in the components are present with respect to a particular data set in the data sets.

25 **17.** The apparatus of any one of claims **14** to **16**, further comprising:

30 a graphical user interface, wherein the computer system is further configured to visually present the differences identified on the graphical user interface and wherein the graphical user interface is

configured to receive user input providing dispositions for the differences in a storage system.

18. The apparatus of any one of claims **14** to **17**, wherein the computer system
5 is further configured to record dispositions for the differences identified between the identifications of the components in the data sets.

19. A vehicle manufacturing system comprising:

10 a storage system configured to store data sets each representing a configuration of a vehicle structure at different phases in a lifecycle of the vehicle structure, wherein each of the data sets includes identifications of components for the configuration of the vehicle structure, the storage system including a unique key for each of the
15 components of the vehicle structure in each of the data sets, the unique key for a particular component distinguishing the particular component from other components for the vehicle structure, the unique key for a particular component including a component identifier and an instance identifier, the instance identifier
20 distinguishing components having the same component identifier by describing a location in the vehicle structure of each component having the same component identifier; and

an object manager configured to:

25 compare a first data set representing the configuration of the vehicle structure at a first phase in the lifecycle of the vehicle structure with a second data set representing the configuration of the vehicle structure at a second phase in the lifecycle of the
30 vehicle structure, the first data set comprising design data or manufacturing planning data and the second data set

comprising as-built data, including to compare first unique keys for the identifications of the components in the first data set with second unique keys for the identifications of the components in the second data set;

5

identify differences between the identifications of the components for the vehicle structure in the first data set and the identifications of the components for the vehicle structure in the second data set; and

10

record dispositions provided for the differences in the storage system;

15

wherein the first data set and the second data set each have different formats and include different pieces of information for different attribute for the components; and

20

wherein the unique key is common to all of the data sets and each of the data sets uses the unique key to distinguish between different components in the data sets.

20. The vehicle manufacturing system of claim **19** further comprising:

25

a manufacturing facility configured to manufacture the vehicle structure.

21. The vehicle manufacturing system of any one of claims **19** or **20** further comprising:

30

a graphical user interface, wherein the object manager is configured to visually present the differences identified on the graphical user

interface and wherein the graphical user interface is configured to receive user input providing the dispositions for the differences in the storage system.

- 5 **22.** A method for managing a configuration of a vehicle structure, the method comprising:

10 selecting, using an object manager associated with a computer system, a first design data set identifying components in a design for a vehicle structure, and a second manufacturing data set identifying components used in manufacturing the vehicle structure;

15 assigning a unique key to components in a plurality of components of a vehicle structure in each of a plurality of data sets, the unique key for a particular component in the plurality of components distinguishing the particular component from other components in the plurality of components for the vehicle structure, the unique key including a component identifier and an instance identifier, the instance identifier distinguishing a location for each of the components having the same component identifier;

20

25 comparing using the object manager, the first design data set with the second manufacturing data set, the first design data set corresponding to a plurality of components in the design of the vehicle structure at a first phase in a lifecycle of the vehicle structure, and the second manufacturing data set corresponding to a plurality of components used in manufacturing of the vehicle structure at a second phase in the lifecycle of the vehicle structure, wherein each data set includes identifications of components and the unique key for the components

30 in the plurality of components for the vehicle structure,

the comparing including comparing first unique keys for the identifications of the components in the first design data set with second unique keys for the identifications of the components in the second manufacturing data set;

5

identifying differences between the identifications of the components in the data sets, wherein differences are identified where the unique keys in the first data set do not match the unique keys in the second data set, and where there is a discrepancy between the information associated with the unique key in the design data set and the information associated with the same unique key in the manufacturing data set;

10

generating and sending an output signal identifying the differences between the data sets to an operator at a manufacturing facility; and

15

recording the differences in a database.

- 23.** A computer-managed build process for a complex product, the process comprising causing at least one processor:

20

during a design phase of the product, to generate an as-specified data set containing engineering design requirements of the product, each engineering design requirement identified by a unique identifier;

25

during a manufacturing planning phase of the product, to generate an as-planned data set containing manufacturing planning requirements for building the product according to the engineering design requirements, the manufacturing planning requirements identifying the engineering design requirements by their unique identifiers;

30

to access at least one policy that identifies criteria for determining whether differences are acceptable;

to compare the identifiers in the data sets to identify differences between the identifiers in the data sets; and

upon determining that the identified differences resulting from the comparison are consistent with the criteria of the accessed policy, to output a first indication that the as-specified data set and the as-planned data set are reconciled; and

upon determining that the identified differences resulting from the comparison are not consistent with the criteria of the accessed policy, to output a second indication that the as-specified data set and the as-planned data set are not reconciled.

24. The process of claim **23**, wherein the manufacturing planning phase overlaps the design phase, the as-specified data set is modified repeatedly during the design phase, and the as-planned data set is modified to reflect modifications to the as-specified data set; and wherein the differences between the identifiers in the data sets are identified repeatedly throughout the manufacturing planning phase.

25. The process of claim **23**, wherein the product is a vehicle.

26. The process of claim **23**, wherein the product is an aircraft.

27. The process of claim **23**, wherein the engineering design requirements specify parts of the product, and wherein identifying the differences includes identifying parts that are included in only one of the data sets.

28. The process of claim **27**, wherein identifying the differences includes identifying a **1:1** correspondence of identifiers in the as-specified data set and the as-planned data set.

5 **29.** The process of claim **27**, wherein each part specified in the as-specified data set is identified by a unique key including part identification and part location information.

10 **30.** The process of claim **23**, wherein the as-specified data set expressly identifies an assembly and each assembly part in the assembly, wherein the as-planned data set does not expressly identify the assembly but does describe how the assembly is built from the assembly parts; and wherein comparing the identifiers in the data sets includes determining that the manufacturing planning requirements represents the assembly if all of the
15 assembly parts are included in the as-planned data set.

31. The process of claim **23**, wherein the as-specified data set includes data taken from engineering bills of material, and the as-planned data set includes data taken from manufacturing bills of material.

20

32. The process of claim **23**, further comprising:

25 during a build phase of the product, generating documents that describe build steps that have been completed, the documents identifying any engineering design requirements by their unique identifiers; and

30 during the build phase, identifying differences between the unique identifiers in the as-planned and as-built data sets to certify completion of the product.

33. The process of claim **32**, wherein the as-built data set grows during the build process and is repeatedly compared to the as-planned data set until the build process has been completed, and wherein the differences between the identifiers in the as-planned and as-built data sets are identified repeatedly throughout the build phase.

34. The process of claim **32**, wherein identifying the differences between the identifiers in the as-planned and as-built data sets includes identifying overages and underages in the as-built data set.

35. The process of claim **23**, wherein the as-specified data set includes identifiers for different parts included in the product, wherein the as-planned data set includes a definition for a sub-assembly that lists at least two of the different parts that are included in the sub-assembly and wherein the as-planned data set does not include identifiers for the at least two of the different parts included in the definition, and wherein comparing the identifiers in the data sets to identify differences between the identifiers in the data sets comprises:

assuming that the parts in the definition for the sub-assembly included in the as-planned data set are included in the sub-assembly; and

determining that no difference is present between the data sets with respect to the parts in the definition for the sub-assembly.

36. The process of claim **23**, wherein the manufacturing planning phase overlaps the design phase, the as-specified data set is modified repeatedly during the design phase, and the criteria in the policy reflect the modifications to the as-specified data set.

37. The process of claim **23**, wherein the policy includes criteria for changes to the design of the product between the design phase and the manufacturing planning phase.

5 **38.** The process of claim **23**, wherein the second indication is an error indication.

39. The process of claim **23**, wherein the engineering design requirements of the product include handling requirements for components of the product, wherein the manufacturing planning requirements includes handling conditions for
10 components of the product, wherein the policy includes criteria that the reconcile handling conditions with the handling requirements.

40. An object management system for building a complex product, the object management system comprising:
15

a computer processor;

a computer memory containing a program that, when executed on the computer processor, performs an operation for processing data,
20 comprising:

during a design phase of the product, generate an as-specified data set containing engineering design requirements of the product, each engineering design requirement identified by a unique identifier;
25

during a manufacturing planning phase of the product, generate an as-planned data set containing manufacturing planning requirements for building the product according to the engineering design requirements, the manufacturing planning requirements identifying
30 the engineering design requirements by their unique identifiers;

access at least one policy that identifies criteria for determining whether differences are acceptable;

5 compare the identifiers in the data sets to identify differences between the identifiers in the data sets; and

10 upon determining that the identified differences resulting from the comparison are consistent with the criteria of the accessed policy, output a first indication that the as-specified data set and the as-planned data set are reconciled; and

15 upon determining that the identified differences resulting from the comparison are not consistent with the criteria of the accessed policy, output a second indication that the as-specified data set and the as-planned data set are not reconciled.

20 **41.** The object management system of claim **35**, wherein the as-specified data set includes identifiers for different parts included in the product, wherein the as-planned data set includes a definition for a sub-assembly that lists at least two of the different parts that are included in the sub-assembly and wherein the as-planned data set does not include identifiers for the at least two of the different parts included in the definition, and wherein comparing the identifiers in the data sets to
25 identify differences between the identifiers in the data sets comprises:


 assuming that the parts in the definition for a sub-assembly are included in the sub-assembly; and

determining that no difference is present between the data sets with respect to the parts in the definition for the sub-assembly.

- 5 **42.** The object management system of claim **35**, wherein the policy includes criteria for changes to the design of the product between the design phase and the manufacturing planning phase.
- 10 **43.** The object management system of claim **35**, wherein the second indication is an error indication.
- 15 **44.** The object management system of claim **35**, wherein the engineering design requirements of the product include handling requirements for components of the product, wherein the manufacturing planning requirements includes handling conditions for components of the product, wherein the policy includes criteria that the reconcile handling conditions with the handling requirements.

1/16

FIG. 1



2/16




FIG. 2

3/16




FIG. 3

408 424 410		412		414	416	418	420	124	400	422
404		DESIGN DATA								
402		PART NUMBER	LOCATION INDEX	VENDOR PART NUMBER	MATERIAL	WEIGHT (kg)	DRAWING NUMBER	INSTALLATION SIDE	MAXIMUM STORAGE TEMPERATURE, (F)	

FIG. 4

508 524 510		512		514	516	518	520	128	500	522
504		AS-BUILT DATA								
502		PART NUMBER	LOCATION INDEX	INSTALLATION TOOL	CERTIFICATION REQUIRED	STORAGE LOCATION	ASSEMBLY JIG NUMBER	INSTALLATION SIDE	ASSEMBLY CELL	

FIG. 5

408 424 410		412	414	416	418	420	124 400	422
404		DESIGN DATA						
600	PART NUMBER	LOCATION INDEX	VENDOR PART NUMBER	MATERIAL	WEIGHT (kg)	DRAWING NUMBER	INSTALLATION SIDE	MAXIMUM STORAGE TEMPERATURE, (F)
	ABC	002345	78-321R	ALUMINUM	5.79	DWG-45.2	RIGHT	100
602		ABC	002346	ALUMINUM	5.79	DWG-45.2	LEFT	100
508 524 510		512	514	516	518	520	128 500	522
504		AS-BUILT DATA						
502	PART NUMBER	LOCATION INDEX	INSTALLATION TOOL	CERTIFICATION REQUIRED	STORAGE LOCATION	ASSEMBLY JIG NUMBER	INSTALLATION SIDE	ASSEMBLY CELL
	ABC	002345	TW-8786	YES	W-98	DWG-45.2	RIGHT	810

FIG. 6




FIG. 7





FIG. 8

FIG. 9






FIG. 11




FIG. 12

Part Tree

All

Filter by Group: All Groups

MA12Z234-1 {OPEN}

MA12Z678-2 {OPEN}

MfgComponents

OverSpecSOR

23Z986-1 (10987) {OPEN}

23Z987-1 (10567) {OPEN}

21Z245-3 (10654) {OPEN}

12Z345-2 (10234) {CLOSED}

12Z345-2 (10345) {CLOSED}

10Z654-19 (10123) {OPEN}

10Z101-123F (NA) {OPEN}

10Z221-345F (10224) {OPEN}

10Z221-346F (10224) {OPEN}

10Z678-909 (10976) {OPEN}

10Z678-910 (10987) {OPEN}

10Z678-911 (10775) {OPEN}

10Z678-912 (10897) {OPEN}

11Z345-112 (10112) {OPEN}

11Z345-114 (10123) {OPEN}

16Z246-12 (10579) {OPEN}

Comparison

Variance

SOI

1202

P/N: 12Z345-2

Status: CLOSED

Variance ID # 10000

Instance # 10234

Opened: 3/25/2011 2:58:23 PM

Closed: 5/11/2011 5:34:22 AM

Dispositions

History / Audit Log

12Z345-2

Assign Dispo

Un-Assign Dispo

Approve Dispos

REJECT Dispos

Status: CLOSED

Open: 3/25/2011 2:58:23 PM

Approved: 3/27/2011 8:05:31 AM

Closed: 5/20/2011 6:100:27 AM

ECD: 3/28/2011

P/N: 12Z345-2

Instance # 10234

Dispo ID # 98765

Dispo: BOM EXPORT ERROR [10]

Verify:

Notes:

Usage: OverSOR Only

For Use When:

- Item can be located in SPEC IP in DELMIA

User Comments

Other Lines

1206

Applied from original Line Unit 25

ORIGINAL COMMENT

03/25/11 08:27:44 (Thomas, Frank B): Part Number 12Z345-2

ID: 1234_ABC_SEC10-11_SEAT-TRACK-5DEF_GHI321

Part class: Engineering

Part Type: Detail

Instance number: 10234

Instance status: Approved (11/17/2009 10:47:09 PM)

1204

1208

11/16

905

902

900

12/16




FIG. 13




FIG. 14

14/16





FIG. 15

15/16

FIG. 16



16/16

