



(86) Date de dépôt PCT/PCT Filing Date: 2001/09/12

(87) Date publication PCT/PCT Publication Date: 2002/03/21

(85) Entrée phase nationale/National Entry: 2003/02/04

(86) N° demande PCT/PCT Application No.: US 2001/028450

(87) N° publication PCT/PCT Publication No.: 2002/022611

(30) Priorité/Priority: 2000/09/13 (60/232,573) US

(51) Cl.Int.⁷/Int.Cl.⁷ C07D 417/06, A61K 31/5415,
A61K 31/473, A61P 29/00, C07D 471/04, C07D 513/04,
C07D 495/04, C07D 413/06, C07D 401/06


(71) Demandeur/Applicant:
VERTEX PHARMACEUTICALS INCORPORATED, US

(72) Inventeurs/Inventors:
CHARRIER, JEAN-DAMIEN, GB;
KNEGTEL, RONALD, GB;
MORTIMORE, MICHAEL, GB

(74) Agent: SMART & BIGGAR

(54) Titre : INHIBITEURS DE CASPASE ET LEURS UTILISATIONS

(54) Title: CASPASE INHIBITORS AND USES THEREOF



(57) **Abrégé/Abstract:**

Described herein are compounds that are useful as caspase inhibitors having the formula (I): wherein Ring A is an optionally substituted piperidine, tetrahydroquinoline or tetrahydroisoquinoline ring; R¹ is hydrogen, CN, CHN², R, or CH²Y; R is an optionally substituted group selected from an aliphatic group, an aryl group, or an aralkyl group; Y is an electronegative leaving group; R² is CO²H, CH²CO²H, or esters, amides or isosteres thereof; and R³ is hydrogen, an optionally substituted aryl group, and optionally substituted aralkyl group, or an optionally substituted C₁₋₆ aliphatic group, R⁴ is an optionally substituted group selected from an aryl group or a heterocycle group, or R³ and R⁴ taken together with the nitrogen to which they are attached optionally form a substituted or unsubstituted monocyclic, bicyclic or tricyclic ring.

(12) INTERNATIONAL APPLICATION PUBLISHED UNDER THE PATENT COOPERATION TREATY (PCT)

(19) World Intellectual Property Organization
International Bureau



(43) International Publication Date
21 March 2002 (21.03.2002)

PCT

(10) International Publication Number
WO 02/022611 A3

(51) International Patent Classification⁷: **C07D 417/06**,
401/06, 413/06, 471/04, 495/04, 513/04, A61K 31/5415,
31/473, A61P 29/00

(74) Agents: **SILVERMAN, Ian** et al.; Vertex Pharmaceuticals Inc., 130 Waverly Street, Cambridge, MA 02139-4242 (US).

(21) International Application Number: PCT/US01/28450

(22) International Filing Date:
12 September 2001 (12.09.2001)

(25) Filing Language: English

(26) Publication Language: English

(30) Priority Data:
60/232,573 13 September 2000 (13.09.2000) US

(71) Applicant (for all designated States except US): **VERTEX PHARMACEUTICALS INCORPORATED** [US/US]; Patent Department, 130 Waverly Street, Cambridge, MA 02139-4242 (US).

(72) Inventors; and

(75) Inventors/Applicants (for US only): **CHARRIER, Jean-Damien** [FR/GB]; 2 The Spinney, Bishops Itchington, Southam, Oxfordshire CV472PZ (GB). **KNEGTEL, Ronald** [GB/GB]; 3 Bath Court, Bath Street, Abingdon, Oxfordshire OX1X1EE (GB). **MORTIMORE, Michael** [GB/GB]; 5 Tanistock Road, Westbridgeford, Nottinghamshire NG26HF (GB).

(81) Designated States (national): AE, AG, AL, AM, AT, AU, AZ, BA, BB, BG, BR, BY, BZ, CA, CH, CN, CO, CR, CU, CZ, DE, DK, DM, DZ, EC, EE, ES, FI, GB, GD, GE, GH, GM, HR, HU, ID, IL, IN, IS, JP, KE, KG, KP, KR, KZ, LC, LK, LR, LS, LT, LU, LV, MA, MD, MG, MK, MN, MW, MX, MZ, NO, NZ, PH, PL, PT, RO, RU, SD, SE, SG, SI, SK, SL, TJ, TM, TR, TT, TZ, UA, UG, US, UZ, VN, YU, ZA, ZW.

(84) Designated States (regional): ARIPO patent (GH, GM, KE, LS, MW, MZ, SD, SL, SZ, TZ, UG, ZW), Eurasian patent (AM, AZ, BY, KG, KZ, MD, RU, TJ, TM), European patent (AT, BE, CH, CY, DE, DK, ES, FI, FR, GB, GR, IE, IT, LU, MC, NL, PT, SE, TR), OAPI patent (BF, BJ, CF, CG, CI, CM, GA, GN, GQ, GW, ML, MR, NE, SN, TD, TG).


Published:

— with international search report

(88) Date of publication of the international search report:
31 October 2002

For two-letter codes and other abbreviations, refer to the "Guidance Notes on Codes and Abbreviations" appearing at the beginning of each regular issue of the PCT Gazette.

(54) Title: CASPASE INHIBITORS AND USES THEREOF



(57) Abstract: Described herein are compounds that are useful as caspase inhibitors having the formula (I): wherein Ring A is an optionally substituted piperidine, tetrahydroquinoline or tetrahydroisoquinoline ring; R¹ is hydrogen, CN, CHN², R, or CH²Y; R is an optionally substituted group selected from an aliphatic group, an aryl group, or an aralkyl group; Y is an electronegative leaving group; R² is CO²H, CH²CO²H, or esters, amides or isosteres thereof; and R³ is hydrogen, an optionally substituted aryl group, and optionally substituted aralkyl group, or an optionally substituted C₁₋₆ aliphatic group, R⁴ is an optionally substituted group selected from an aryl group or a heterocycle

group, or R³ and R⁴ taken together with the nitrogen to which they are attached optionally form a substituted or unsubstituted monocyclic, bicyclic or tricyclic ring.



WO 02/022611 A3

CASPASE INHIBITORS AND USES THEREOF

Cross-Reference to Related Applications

This application claims priority to US Provisional Patent Application 60/232,573, filed September 13, 2000.

Field of the Invention

This invention is in the field of medicinal chemistry and relates to novel compounds, and pharmaceutical compositions thereof, that inhibit caspases that mediate cell apoptosis and inflammation. The invention also relates to methods of using the compounds and pharmaceutical compositions of this invention to treat diseases where caspase activity is implicated.

Background of the Invention

Apoptosis, or programmed cell death, is a principal mechanism by which organisms eliminate unwanted cells. The deregulation of apoptosis, either excessive apoptosis or the failure to undergo it, has been implicated in a number of diseases such as cancer, acute inflammatory and autoimmune disorders, ischemic diseases and certain neurodegenerative disorders (see generally *Science*, 1998, 281, 1283-1312; Ellis et al., *Ann. Rev. Cell. Biol.*, 1991, 7, 663).

Caspases are a family of cysteine protease enzymes that are key mediators in the signaling pathways for apoptosis and cell disassembly (Thornberry, *Chem. Biol.*, 1998, 5, R97-R103). These signaling pathways vary depending on cell type and stimulus, but all apoptosis

-2-

pathways appear to converge at a common effector pathway leading to proteolysis of key proteins. Caspases are involved in both the effector phase of the signaling pathway and further upstream at its initiation. The upstream caspases involved in initiation events become activated and in turn activate other caspases that are involved in the later phases of apoptosis.

Caspase-1, the first identified caspase, is also known as interleukin converting enzyme or "ICE."

Caspase-1 converts precursor interleukin-1 β ("pIL-1 β ") to the pro-inflammatory active form by specific cleavage of pIL-1 β between Asp-116 and Ala-117. Besides caspase-1 there are also eleven other known human caspases, all of which cleave specifically at aspartyl residues. They are also observed to have stringent requirements for at least four amino acid residues on the N-terminal side of the cleavage site.

The caspases have been classified into three groups depending on the amino acid sequence that is preferred or primarily recognized. The group of caspases, which includes caspases 1, 4, and 5, has been shown to prefer hydrophobic aromatic amino acids at position 4 on the N-terminal side of the cleavage site. Another group which includes caspases 2, 3 and 7, recognize aspartyl residues at both positions 1 and 4 on the N-terminal side of the cleavage site, and preferably a sequence of Asp-Glu-X-Asp. A third group, which includes caspases 6, 8, 9 and 10, tolerate many amino acids in the primary recognition sequence, but seem to prefer residues with branched, aliphatic side chains such as valine and leucine at position 4.

-3-

The caspases have also been grouped according to their perceived function. The first subfamily consists of caspases-1 (ICE), 4, and 5. These caspases have been shown to be involved in pro-inflammatory cytokine processing and therefore play an important role in inflammation. Caspase-1, the most studied enzyme of this class, activates the IL-1 β precursor by proteolytic cleavage. This enzyme therefore plays a key role in the inflammatory response. Caspase-1 is also involved in the processing of interferon gamma inducing factor (IGIF or IL-18) which stimulates the production of interferon gamma, a key immunoregulator that modulates antigen presentation, T-cell activation and cell adhesion.

The remaining caspases make up the second and third subfamilies. These enzymes are of central importance in the intracellular signaling pathways leading to apoptosis. One subfamily consists of the enzymes involved in initiating events in the apoptotic pathway, including transduction of signals from the plasma membrane. Members of this subfamily include caspases-2, 8, 9 and 10. The other subfamily, consisting of the effector caspases 3, 6 and 7, are involved in the final downstream cleavage events that result in the systematic breakdown and death of the cell by apoptosis. Caspases involved in the upstream signal transduction activate the downstream caspases, which then disable DNA repair mechanisms, fragment DNA, dismantle the cell cytoskeleton and finally fragment the cell.

Knowledge of the four amino acid sequence primarily recognized by the caspases has been used to design caspase inhibitors. Reversible tetrapeptide inhibitors have been prepared having the structure

-4-

CH₃CO-[P4]-[P3]-[P2]-CH(R)CH₂CO₂H where P2 to P4 represent an optimal amino acid recognition sequence and R is an aldehyde, nitrile or ketone capable of binding to the caspase cysteine sulfhydryl. Rano and Thornberry, *Chem. Biol.* 4, 149-155 (1997); Mjalli, et al., *Bioorg. Med. Chem. Lett.* 3, 2689-2692 (1993); Nicholson et al., *Nature* 376, 37-43 (1995). Irreversible inhibitors based on the analogous tetrapeptide recognition sequence have been prepared where R is an acyloxymethylketone -COCH₂OCOR'.

10 R' is exemplified by an optionally substituted phenyl such as 2,6-dichlorobenzoyloxy and where R is COCH₂X where X is a leaving group such as F or Cl. Thornberry et al., *Biochemistry* 33, 3934 (1994); Dolle et al., *J Med. Chem.* 37, 563-564 (1994).

15 The utility of caspase inhibitors to treat a variety of mammalian diseases associated with an increase in cellular apoptosis has been demonstrated using peptidic caspase inhibitors. For example, in rodent models, caspase inhibitors have been shown to reduce

20 infarct size and inhibit cardiomyocyte apoptosis after myocardial infarction, to reduce lesion volume and neurological deficit resulting from stroke, to reduce post-traumatic apoptosis and neurological deficit in traumatic brain injury, to be effective in treating

25 fulminant liver destruction, and to improve survival after endotoxic shock. Yaoita et al., *Circulation*, 97, 276 (1998); Endres et al., *J Cerebral Blood Flow and Metabolism*, 18, 238, (1998); Cheng et al., *J. Clin. Invest.*, 101, 1992 (1998); Yakovlev et al., *J*


30 *Neuroscience*, 17, 7415 (1997); Rodriguez et al., *J. Exp. Med.*, 184, 2067 (1996); Grobmyer et al., *Mol. Med.*, 5, 585 (1999).

-5-

In general, the peptidic inhibitors described above are very potent against some of the caspase enzymes. However, this potency has not always been reflected in cellular models of apoptosis. In addition
 5 peptide inhibitors are typically characterized by undesirable pharmacological properties such as poor oral absorption, poor stability and rapid metabolism. Plattner and Norbeck, in *Drug Discovery Technologies*, Clark and Moos, Eds. (Ellis Horwood, Chichester, England,
 10 1990).


Recognizing the need to improve the pharmacological properties of the peptidic caspase inhibitors, peptidomimetic and non-natural amino acid peptide inhibitors have been reported.

15 WO 96/40647 discloses ICE inhibitors of the formula:



wherein B is H or an N-terminal blocking group; R₁ is the amino acid side chain of the P₁ amino acid residue wherein
 20 the P₁ amino acid is not Asp; P_n is an amino acid residue or a heterocyclic replacement of the amino acid; R₄ is hydroxyl, alkoxyl, acyl, hydrogen, alkyl or phenyl; m is 0 or a positive integer; and X is N, S, O, or CH₂.


US Patent 5,585,357 discloses compounds which
 25 inhibit interleukin-1 β protease. These inhibitors are represented by the formula:



-6-

wherein each AA is independently L-valine or L-alanine; n is 0-2; R₁ is certain groups; and R₈, R₉, R₁₀ are each independently hydrogen, lower alkyl, halo substituted methyl, carbalkoxy, benzyl, phenyl or phenyl mono- or
 5 disubstituted with fluoro, nitro, methoxy, chloro, trifluoromethyl or methanesulfonyl.


WO 98/16502 discloses aspartate ester inhibitors of interleukin-1 β converting enzyme of the formula:



10


wherein R¹ is, inter alia, R⁵N(R^a)CHR⁶CO-; R² is certain groups; R⁶ is H, C₁₋₆ alkyl, -(CH₂)_naryl, -(CH₂)_nCO₂R^a, hydroxyl substituted C₁₋₆ alkyl, or imidazole substituted C₁₋₆ alkyl; and R^a is independently hydrogen, C₁₋₆ alkyl or
 15 -(CH₂)_naryl

WO 99/18781 discloses dipeptide apoptosis inhibitors having the formula:



where R₁ is an N-terminal protecting group; AA is a
 20 residue of any natural α -amino acid, or β -amino acid; and R₂ and R₃ are defined in the application.

WO 00/023421 discloses (substituted)acyl dipeptide apoptosis inhibitors having the formula:




25 wherein n is 0, 1, or 2; q is 1 or 2; A is a residue of any natural or non-natural amino acid; B is a hydrogen

-7-

atom, a deuterium atom, C1-10 straight chain or branched alkyl, cycloalkyl, phenyl, substituted phenyl, naphthyl, substituted naphthyl, 2-benzoxazolyl, substituted 2-oxazolyl, (CH₂)_mcycloalkyl, (CH₂)_mphenyl, (CH₂)_m(substituted phenyl), (CH₂)_m(1- or 2-naphthyl), (CH₂)_mheteroaryl, halomethyl, CO₂R₁₃, CONR₁₄R₁₅, CH₂ZR₁₆, CH₂OCOaryl, CH₂OCO(substituted aryl), CH₂OCO(heteroaryl), CH₂OCO(substituted heteroaryl), or CH₂OPO(R₁₇)R₁₈, where R₁₃, R₁₄, R₁₅, R₁₆, R₁₇ and R₁₈ are defined in the application; R₂ is selected from a group containing hydrogen, alkyl, cycloalkyl, phenyl, substituted phenyl, (CH₂)_mNH₂; R₃ is hydrogen, alkyl, cycloalkyl, (cycloalkyl)alkyl, phenylalkyl, or substituted phenylalkyl; X is CH₂, C=O, O, S, NH, C=ONH or CH₂OCONH; and Z is an oxygen or a sulfur atom.

WO 00/061542 discloses dipeptide apoptosis inhibitors having the formula:



where R₁ is an optionally substituted alkyl or hydrogen group; R₂ is hydrogen or optionally substituted alkyl; Y is a residue of a natural or non-natural amino acid and R₃ is an alkyl, saturated carbocyclic, partially saturated carbocyclic, aryl, saturated heterocyclic, partially saturated heterocyclic or heteroaryl group, wherein said group is optionally substituted; X is O, S, NR₄, or (CR₄R₅)_n where R₄ and R₅ are, at each occurrence, independently selected from the group consisting of hydrogen, alkyl and cycloalkyl, and n is 0, 1, 2, or 3; or X is NR₄, and R₃ and R₄ are taken together with the nitrogen atom to which they are attached to form a


- 8 -

saturated heterocyclic, partially saturated heterocyclic or heteroaryl group, wherein said group is optionally substituted or X is CR₄R₅, and R₃ and R₄ are taken together with the carbon atom to which they are attached to form a
 5 saturated carbocyclic, partially saturated carbocyclic, aryl, saturated heterocyclic, partially saturated heterocyclic or oxygen-containing heteroaryl group, wherein said group is optionally substituted; and provided that when X is O, then R₃ is not unsubstituted
 10 benzyl or t-butyl; and when X is CH₂, then R₃ is not H.

While a number of caspase inhibitors have been reported, it is not clear whether they possess the appropriate pharmacological properties to be therapeutically useful. Therefore, there is a continued
 15 need for small molecule caspase inhibitors that are potent, stable, and penetrate membranes to provide effective inhibition of apoptosis *in vivo*. Such compounds would be extremely useful in treating the aforementioned diseases where caspase enzymes play a
 20 role.

Summary of the Invention

It has now been found that compounds of this invention and pharmaceutical compositions thereof are particularly effective as inhibitors of caspases and
 25 cellular apoptosis. These compounds have the general formula I:



I

wherein:

-9-


Ring A is an optionally substituted piperidine,
tetrahydroquinoline or tetrahydroisoquinoline ring;
R¹ is hydrogen, CN, CHN₂, R, or CH₂Y;
R is an optionally substituted group selected from an
5 aliphatic group, an aryl group, or an aralkyl group;
Y is an electronegative leaving group;
R² is CO₂H, CH₂CO₂H, or esters, amides or isosteres
thereof; and
R³ is hydrogen, an optionally substituted aryl group, an
10 optionally substituted aralkyl group, or an optionally
substituted C₁₋₆ aliphatic group, R⁴ is an optionally
substituted group selected from an aryl group or a
heterocyclyl group, or R³ and R⁴ taken together with
the nitrogen to which they are attached optionally form
15 a substituted or unsubstituted monocyclic, bicyclic or
tricyclic ring.

The compounds of this invention have potent
inhibition properties across a range of caspase targets
with good efficacy in cellular models of apoptosis. In
20 addition, these compounds are expected to have improved
cell penetration and pharmacokinetic properties and, as a
consequence of their potency, have improved efficacy
against diseases where caspases are implicated.

25 Detailed Description of the Invention

This invention provides novel compounds, and
pharmaceutically acceptable derivatives thereof, that are
particularly effective as caspase inhibitors. The
invention also provides methods for using the compounds
30 to treat caspase-mediated diseases in mammals. The
compounds have the general formula I:

-10-



I

wherein:

Ring A is an optionally substituted piperidine,

5 tetrahydroquinoline or tetrahydroisoquinoline ring;

R¹ is hydrogen, CN, CHN₂, R, or CH₂Y;

R is an optionally substituted group selected from an aliphatic group, an aryl group, or an aralkyl group;

Y is an electronegative leaving group;

10 R² is CO₂H, CH₂CO₂H, or esters, amides or isosteres thereof; and

R³ is hydrogen, an optionally substituted aryl group, an optionally substituted aralkyl group, or an optionally substituted C₁₋₆ aliphatic group, R⁴ is an optionally substituted group selected from an aryl group or a
 15 heterocyclyl group, or R³ and R⁴ taken together with the nitrogen to which they are attached optionally form a substituted or unsubstituted monocyclic, bicyclic or tricyclic ring.

20 As used herein, the following definitions shall apply unless otherwise indicated. The phrase "optionally substituted" may be used interchangeably with the phrase "substituted or unsubstituted" or with the term "(un)substituted." Unless otherwise indicated, an
 25 optionally substituted group may have one or more substituents that are independently selected.

The term "aliphatic" as used herein means straight chained, branched or cyclic C₁-C₁₂ hydrocarbons which are completely saturated or which contain one or

-11-

more units of unsaturation. For example, suitable aliphatic groups include substituted or unsubstituted linear, branched or cyclic alkyl, alkenyl, or alkynyl groups and hybrids thereof such as (cycloalkyl)alkyl, (cycloalkenyl)alkyl or (cycloalkyl)alkenyl. The term "alkyl" used alone or as part of a group or larger moiety refers to both straight and branched chains containing one to twelve carbon atoms.

The term "halogen" means F, Cl, Br, or I. The term "heteroatom" means nitrogen, oxygen or sulfur.

The term "aryl" refers to monocyclic or polycyclic aromatic groups, and monocyclic or polycyclic heteroaromatic groups containing one or more heteroatoms, having five to fourteen atoms. Such groups include, but are not limited to, phenyl, naphthyl, anthryl, furanyl, thienyl, pyrrolyl, oxazolyl, thiazolyl, imidazolyl, pyrazolyl, isoxazolyl, isothiazolyl, oxadiazolyl, triazolyl, thiadiazolyl, pyridinyl, pyridazinyl, pyrimidinyl, pyrazinyl, triazinyl, indolizinyll, indolyl, isoindolyl, indolinyl, benzofuranyl, benzothiophenyl, indazolyl, benzimidazolyl, benzthiazolyl, purinyl, quinolizinyll, quinolinyl, isoquinolinyl, cinnolinyl, phthalazinyl, quinazolinyl, quinoxalinyl, 1,8-naphthyridinyl, pteridinyl, carbazolyl, acridinyl, phenazinyl, phenothiazinyl, phenoxazinyl, tetrahydrofuranyl, phthalimidinyl, tetrazolyl, and chromanyl.

The term "heterocyclic group" refers to saturated and partially unsaturated monocyclic or polycyclic ring systems containing one or more heteroatoms, wherein a monocyclic ring preferably has 5-7 ring atoms and a polycyclic ring preferably has 8-14 ring

-12-

atoms. Such groups include, but are not limited to aziranyl, oxiranyl, azetidiny, tetrahydrofuranyl, pyrrolinyl, pyrrolidinyl, dioxolanyl, imidazolinyl, imidazolidinyl, pyrazolinyl, pyrazolidinyl, pyranyl, piperidinyl, dioxanyl, morpholinyl, dithianyl, thiomorpholinyl, piperazinyl, trithianyl, quinuclidinyl, oxepanyl, and thiepanyl. The term "heterocyclic ring", whether saturated or unsaturated, also refers to rings that are optionally substituted.

10 An aryl group (including heteroaryl groups) or an aralkyl group, such as benzyl or phenethyl, may contain one or more substituents. Examples of suitable substituents on the unsaturated carbon atom of an aryl group include halogen, $-R^o$, $-OR^o$, $-SR^o$, 1,2-methylene-
 15 dioxy, 1,2-ethylenedioxy, protected OH (such as acyloxy), phenyl (Ph), substituted Ph, $-O(Ph)$, substituted $-O(Ph)$, $-CH_2(Ph)$, substituted $-CH_2(Ph)$, $-CH_2CH_2(Ph)$, substituted $-CH_2CH_2(Ph)$, $-NO_2$, $-CN$, $-N(R^o)_2$, $-NR^oC(O)R^o$, $-NR^oC(O)N(R^o)_2$, $-NR^oCO_2R^o$, $-NR^oNR^oC(O)R^o$, $-NR^oNR^oC(O)N(R^o)_2$, $-NR^oNR^oCO_2R^o$,
 20 $-C(O)C(O)R^o$, $-C(O)CH_2C(O)R^o$, $-CO_2R^o$, $-C(O)R^o$, $-C(O)N(R^o)_2$, $-OC(O)N(R^o)_2$, $-S(O)_2R^o$, $-SO_2N(R^o)_2$, $-S(O)R^o$, $-NR^oSO_2N(R^o)_2$, $-NR^oSO_2R^o$, $-C(=S)N(R^o)_2$, $-C(=NH)-N(R^o)_2$, $-(CH_2)_yNHC(O)R^o$, $-(CH_2)_yNHC(O)CH(V-R^o)(R^o)$; wherein R^o is H, a substituted or unsubstituted aliphatic group, preferably having 1-3
 25 carbons, an unsubstituted heteroaryl or heterocyclic ring, phenyl (Ph), substituted Ph, $-O(Ph)$, substituted $-O(Ph)$, $-CH_2(Ph)$, or substituted $-CH_2(Ph)$; y is 0-6; and V is a linker group. Examples of substituents on the aliphatic group or the phenyl ring include amino,
 30 alkylamino, dialkylamino, aminocarbonyl, halogen, alkyl, alkylaminocarbonyl, dialkylaminocarbonyl,

-13-

alkylaminocarbonyloxy, dialkylaminocarbonyloxy, alkoxy, nitro, cyano, carboxy, alkoxycarbonyl, alkylcarbonyl, hydroxy, haloalkoxy, or haloalkyl.

An aliphatic group or a non-aromatic heterocyclic ring may contain one or more substituents. Examples of suitable substituents on the saturated carbon of an aliphatic group or of a non-aromatic heterocyclic ring include those listed above for the unsaturated carbon as well as the following: $=O$, $=S$, $=NNHR^*$, $=NN(R^*)_2$, $=N-$, $=NNHC(O)R^*$, $=NNHCO_2(\text{alkyl})$, $=NNHSO_2(\text{alkyl})$, or $=NR^*$, where each R^* is independently selected from hydrogen, an unsubstituted aliphatic group or a substituted aliphatic group. Examples of substituents on the aliphatic group include amino, alkylamino, dialkylamino, aminocarbonyl, halogen, alkyl, alkylaminocarbonyl, dialkylaminocarbonyl, alkylaminocarbonyloxy, dialkylaminocarbonyloxy, alkoxy, nitro, cyano, carboxy, alkoxycarbonyl, alkylcarbonyl, hydroxy, haloalkoxy, or haloalkyl.

A substitutable nitrogen on an aromatic or non-aromatic heterocyclic ring may be optionally substituted. Suitable substituents on the nitrogen include $-R^+$, $-N(R^+)_2$, $-C(O)R^+$, $-CO_2R^+$, $-C(O)C(O)R^+$, $-C(O)CH_2C(O)R^+$, $-SO_2R^+$, $-SO_2N(R^+)_2$, $-C(=S)N(R^+)_2$, $-C(=NH)-N(R^+)_2$, and $-NR^+SO_2R^+$; wherein R^+ is H, an aliphatic group, a substituted aliphatic group, phenyl (Ph), substituted Ph, $-O(Ph)$, substituted $-O(Ph)$, $CH_2(Ph)$, substituted $CH_2(Ph)$, or an unsubstituted heteroaryl or heterocyclic ring. Examples of substituents on the aliphatic group or the phenyl ring include amino, alkylamino, dialkylamino, aminocarbonyl, halogen, alkyl, alkylaminocarbonyl, dialkylaminocarbonyl, alkylaminocarbonyloxy, dialkylaminocarbonyloxy, alkoxy, nitro, cyano, carboxy,

-14-

alkoxycarbonyl, alkylcarbonyl, hydroxy, haloalkoxy, or haloalkyl. Nitrogen and sulfur may be in their oxidized form, and nitrogen may be in a quaternized form.

The term "electronegative leaving group" has
5 the definition known to those skilled in the art (see March, Advanced Organic Chemistry, 4th Edition, John Wiley & Sons, 1992). Examples of electronegative leaving groups include halogens such as F, Cl, Br, I, aryl- and alkylsulfonyloxy groups, trifluoromethanesulfonyloxy,
10 -SR, -OPO(R⁵)(R⁶), where R is an aliphatic group, an aryl group, an aralkyl group, a carbocyclyl group, a carbocyclylalkyl group, a heterocyclyl group, or a heterocyclylalkyl group, and R⁵ and R⁶ are independently selected from R or OR.


15 When the R² group is in the form of an ester or amide, the present compounds undergo metabolic cleavage to the corresponding carboxylic acids, which are the active caspase inhibitors. Because they undergo metabolic cleavage, the precise nature of the ester or
20 amide group is not critical to the working of this invention. The structure of the R² group may range from the relatively simple diethyl amide to a steroidal ester. Examples of the ester alcohol moiety of R² carboxylic acids include, but are not limited to, alcohols of C₁₋₁₂
25 aliphatic groups, such as C₁₋₆ alkyl or C₃₋₁₀ cycloalkyl, aryl groups, such as phenyl, aralkyl groups, such as benzyl or phenethyl, heterocyclyl or heterocyclylalkyl groups. Examples of suitable R² heterocyclyl groups include, but are not limited to, 5-6 membered
30 heterocyclic rings having one or two heteroatoms such as piperidinyl, piperazinyl, or morpholinyl.

-15-

Amides of R^2 carboxylic acids may be primary, secondary or tertiary. Suitable substituents on the amide nitrogen include, but are not limited to, one or more groups independently selected from the aliphatic, aryl, aralkyl, heterocyclyl or heterocyclalkyl groups described above for the R^2 ester alcohol. Likewise, other prodrugs are included within the scope of this invention. See Bradley D. Anderson, "Prodrugs for Improved CNS Delivery" in Advanced Drug Delivery Reviews (1996), 19, 171-202.

Isosteres or bioisosteres of carboxylic acids and esters or amides result from the exchange of an atom or group of atoms to create a new compound with similar biological properties to the parent carboxylic acid or ester. The bioisosteric replacement may be physicochemically or topologically based. An example of an isosteric replacement for a carboxylic acid is $\text{CONHSO}_2(\text{alkyl})$ such as CONHSO_2Me .

Compounds of this invention where R^2 is CO_2H or $\text{CH}_2\text{CO}_2\text{H}$, γ -ketoacids or δ -ketoacids respectively, may exist in solution as either the open form (a) or the cyclized hemiketal form (b) ($y=1$ for γ -ketoacids, $y=2$ for δ -ketoacids). The representation herein of either isomeric form is meant to include the other.




Likewise it will be apparent to one skilled in the art that certain compounds of this invention may

-16-

exist in tautomeric forms or hydrated forms, all such forms of the compounds being within the scope of the invention. Unless otherwise stated, structures depicted herein are also meant to include all stereochemical forms of the structure; i.e., the R and S configurations for each asymmetric center. Therefore, single stereochemical isomers as well as enantiomeric and diastereomeric mixtures of the present compounds are within the scope of the invention. Unless otherwise stated, structures depicted herein are also meant to include compounds that differ only in the presence of one or more isotopically enriched atoms. For example, compounds having the present structures except for the replacement of a hydrogen by a deuterium or tritium, or the replacement of a carbon by a ^{13}C - or ^{14}C -enriched carbon are within the scope of this invention.


One embodiment of this invention relates to compounds of formula I wherein Ring A is an optionally substituted piperidine ring, represented by formula Ia:




Ia

Another embodiment of this invention relates to compounds of formula I wherein Ring A is an optionally substituted tetrahydroquinoline ring, represented by formula Ib below:

-17-

**Ib**

Another embodiment of this invention relates to compounds of formula **I** wherein Ring A is an optionally substituted tetrahydroisoquinoline ring are represented by formula **Ic** below:

**Ic**

Ring A may be substituted or unsubstituted. Examples of suitable Ring A substituents include one or more groups selected from halogen, -R, -OR, -OH, -SR, protected OH (such as acyloxy), phenyl (Ph), substituted Ph, -OPh, substituted -OPh, -NO₂, -CN, -NH₂, -NHR, -N(R)₂, -NHCOR, -NHCONHR, -NHCON(R)₂, -NRCOR, -NHCO₂R, -CO₂R, -CO₂H, -COR, -CONHR, -CON(R)₂, -S(O)₂R, -SONH₂, -S(O)R, -SO₂NHR, -NHS(O)₂R, =O, =S, =NNHR, =NNR₂, =N-OR, =NNHCOR, =NNHCO₂R, =NNHSO₂R, or =NR, where R is an aliphatic group or a substituted aliphatic group. Preferably R is a C₁₋₆ aliphatic group.

A preferred R¹ group is CH₂Y where Y is an electronegative leaving group. Most preferably Y is F.

R³ and R⁴ may be taken together with the nitrogen to which they are attached to form a substituted

-18-

or unsubstituted monocyclic, bicyclic or tricyclic ring. The R^3R^4N ring system may be aromatic or non-aromatic and will have 1-6 heteroatoms selected from oxygen, nitrogen or sulfur. Preferably each ring of the R^3R^4N ring system
5 has 5-7 ring atoms. Examples of such rings include indole, isoindole, indoline, indazole, purine, benzimidazole, benzthiazole, imidazole, imidazoline, thiazole, pyrrole, pyrrolidine, pyrroline, pyrazole, pyrazoline, pyrazolidine, triazole, piperidine,
10 morpholine, thiomorpholine, piperazine, carbazole, phenothiazine, phenoxazine, phenanthridine, acridine, purine, quinolizine, quinoline, isoquinoline, cinnoline, phthalazine, quinazoline, quinoxaline, 1,8-naphthyridine, pteridine, quinuclidine, and phenazine.

15 Preferred compounds of this invention have one or more, and more preferably all, of the features selected from the group consisting of:

- (a) R^1 is CH_2Y wherein Y is an electronegative leaving group;
- 20 (b) R^2 is CO_2H or an ester or isosteres thereof; and
- (c) R^3 is hydrogen, an optionally substituted aryl group, an optionally substituted aralkyl group or an optionally substituted C_{1-6} aliphatic group, R^4 is an optionally substituted group selected from an aryl group
25 a heterocyclyl group, or R^3 and R^4 , taken together with the nitrogen to which they are attached, optionally form a ring selected from the group consisting of indole, isoindole, indoline, indazole, purine, benzimidazole, benzthiazole, imidazole, imidazoline, thiazole, pyrrole, benzimidazole, benzthiazole, imidazole, imidazoline, thiazole, pyrrole,
30 pyrrolidine, pyrroline, pyrazole, pyrazoline, pyrazolidine, triazole, piperidine, morpholine, thiomorpholine, piperazine, carbazole, phenothiazine,

-19-

phenoxazine, phenanthridine, acridine, purine,
quinolizine, quinoline, isoquinoline, cinnoline,
phthalazine, quinazoline, quinoxaline, 1,8-naphthyridine,
pteridine, quinuclidine, and phenazine. A preferred R^3 or
5 R^4 aryl group is phenyl or a 5-6 membered heteroaromatic
ring containing 1-3 heteroatoms selected from nitrogen,
oxygen or sulfur. A preferred R^3 aralkyl group is a C_{1-3}
alkylidene chain substituted with a preferred aryl group.
Preferred R^4 heterocyclyl groups include 5-6 membered
10 rings containing 1-3 heteroatoms selected from nitrogen,
oxygen or sulfur.

More preferred are compounds where Y is F and R^3
and R^4 , taken together with the nitrogen to which they are
attached, optionally form a ring selected from the group
15 consisting of indole, isoindole, indoline, indazole,
purine, benzimidazole, benzthiazole, imidazole,
imidazoline, thiazole, pyrrole, pyrrolidine, pyrroline,
pyrazole, pyrazoline, pyrazolidine, triazole, piperidine,
morpholine, thiomorpholine, piperazine, carbazole,
20 phenothiazine, phenoxazine, phenanthridine, acridine.
purine, quinolizine, quinoline, isoquinoline, cinnoline,
phthalazine, quinazoline, quinoxaline, 1,8-naphthyridine,
pteridine, quinuclidine, and phenazine. Even more
preferred are compounds wherein R^3R^4N - ring system is
25 carbazole, piperidine, indole, dihydroindole,
phenothiazine, dihydrophenanthridine, phenoxazine,
acridine, acridin-9-one, β -carboline, or 9-thia-2,10-
diazanthracene. Most preferred are compounds wherein
 R^3R^4N - ring system is carbazole, phenothiazine, or
30 dihydrophenanthridine.


The R^3R^4N - ring system may be optionally
substituted. Examples of suitable substituents on the




-20-

R^3R^4N - ring include one or more groups selected from halogen, $-R$, $-OR$, $-OH$, $-SR$, protected OH (such as acyloxy), phenyl (Ph), substituted Ph, $-OPh$, substituted $-OPh$, $-NO_2$, $-CN$, $-NH_2$, $-NHR$, $-N(R)_2$, $-NHCOR$, $-NHCONHR$,
 5 $-NHCON(R)_2$, $-NRCOR$, $-NHCO_2R$, $-CO_2R$, $-CO_2H$, $-COR$, $-CONHR$,
 $-CON(R)_2$, $-S(O)_2R$, $-SONH_2$, $-S(O)R$, $-SO_2NHR$, $-NHS(O)_2R$, $=O$,
 $=S$, $=NNHR$, $=NNR_2$, $=N-OR$, $=NNHCOR$, $=NNHCO_2R$, $=NNHSO_2R$, or
 $=NR$ where R is an aliphatic group or a substituted aliphatic group. Preferably R is a C_{1-6} aliphatic group.











10 Representative examples of compounds of the present invention are shown below in Table 1.

Table 1. Representative Compounds












No.	R^1	R^2	Ring A Type	R^3R^4N -
I-1	CH_2F	CO_2H	Ia	
I-2	CH_2F	CO_2H	Ia	
I-3	CH_2F	CO_2H	Ia	









-21-

No.	R ¹	R ²	Ring A Type	R ³ R ⁴ N-
I-4	CH ₂ F	CO ₂ H	Ia	
I-5	CH ₂ F	CO ₂ H	Ia	
I-6	CH ₂ F	CO ₂ H	Ia	
I-7	CH ₂ F	CO ₂ H	Ia	
I-8	CH ₂ F	CO ₂ H	Ia	
I-9	CH ₂ F	CO ₂ H	Ia	
I-10	CH ₂ F	CO ₂ H	Ia	
I-11	CH ₂ F	CO ₂ NH ₂	Ia	
I-12	CH ₂ F	CO ₂ NHEt	Ia	
I-13	CH ₂ F	CO ₂ NEt ₂	Ia	

-22-

No.	R ¹	R ²	Ring A Type	R ³ R ⁴ N-
I-14	CH ₂ F	CONHCH ₂ CH ₂ N(CH ₃) ₂	Ia	
I-15	CH ₂ F	CO ₂ H	Ib	
I-16	CH ₂ F	CO ₂ H	Ic	
I-17	CH ₂ F	CO ₂ H	Ib	
I-18	CH ₂ F	CO ₂ H	Ic	
I-19	CH ₂ F	CO ₂ H	Ia	
I-20	CH ₂ F	CO ₂ H	Ia	
I-21	CH ₂ F	CO ₂ H	Ia	
I-22	CH ₂ F	CO ₂ H	Ia	


-23-

No.	R ¹	R ²	Ring A Type	R ³ R ⁴ N-
I-23	CH ₂ F	CO ₂ H	Ia	
I-24	CH ₂ F	CO ₂ H	Ia	
I-25	CH ₂ F	CO ₂ H	Ia	
I-26	CH ₂ F	CO ₂ H	Ia	
I-27	CH ₂ F	CO ₂ H	Ia	
I-28	CH ₂ F	CO ₂ H	Ia	
I-29	CH ₂ F	CO ₂ H	Ia	
I-30	CH ₂ F	CO ₂ H	Ia	

The compounds of this invention may be prepared in general by methods known to those skilled in the art for analogous compounds, as illustrated by the general

5 Scheme I below and by the preparative examples that follow.

Scheme I



Reagents: (a) H-(Ring A)-CO₂R; (b) NaOH, THF, H₂O; (c)
10 H₂NCH(CH₂R²)CH(OH)R¹; EDC, N,N-dimethylaminopyridine,
1-hydroxybenzotriazole; (d) i. Dess-Martin periodinane;
ii. trifluoroacetic acid, dichloromethane.

Scheme I above shows a general route for preparing compounds of this invention. The carbamoyl chloride 1 (or an analogous isocyanate) may be coupled with an amino acid ester, H-(Ring A)-CO₂R to provide urea 2. Hydrolysis of the ester 2 provides acid 3. If the ester is a *tert*-butyl ester then it may be hydrolyzed with acid such as trifluoroacetic acid. The acid 3 may then be coupled with an appropriate amino alcohol, H₂NCH(CH₂R²)CH(OH)R¹ to provide 4. In step c, "EDC" is 1-(3-dimethylaminopropyl)-3-ethylcarbodiimide. Depending on the nature of R¹ an amino ketone may be used, in place of the amino alcohol, which avoids the subsequent oxidation step. In the case of fluoromethyl ketones where R² is CO₂tBu, the amino alcohol may be obtained

-25-

according to the method of Revesz et al., *Tetrahedron Lett.*, 1994, 35, 9693. The hydroxyl in compound 4 is oxidized to compound I which may be further modified, depending on the nature of R^2 , according to methods generally known in the art for analogous compounds. For example, if the product I requires R^2 to be a carboxylic acid, then R^2 in 4 is preferably an ester and the further step is a hydrolysis of the ester group.


Certain useful intermediates for making compounds of this invention may be obtained as follows. Substituted phenothiazines are either commercially available or may be prepared as described by J.I.G. Cadogan, S. Kulik, C. Thomson and M.J. Todd, *J. Chem. Soc.*, 1970, 2437-2441. 9,10-Dihydrophenanthridine was prepared according to G.M. Badger, J.H. Seidler and B. Thomson, *J. Chem. Soc.*, 1951, 3207-3211. Carbamoyl chlorides are either commercially available or may be prepared as described by R. Dahlbom and B. Bjorkqvist, *Acta Chem. Scand.*, 15, 1961, 2043-2046.

20

Synthetic Examples

Example 1


[3S/R, (2S)]-5-Fluoro-4-oxo-3-{[1-(phenothiazine-10-carbonyl)piperidine-2-carbonyl]amino}-pentanoic acid



-26-

Method A:

(S) - (1-Phenothiazine-10-carbonyl)piperidine-2-carboxylic acid methyl ester




5

To a stirred solution of methyl pipercolate hydrochloride (1g, 5.57 mmol) in THF (10 ml) was added phenothiazine carbonyl chloride (1.457g, 5.57 mmol) followed by diisopropylethylamine (2.02 mL, 11.68 mmol). The resulting solution was stirred for 16h before being partitioned between ethyl acetate and aq. sat. NH_4Cl . The organic layer was washed with brine, dried (MgSO_4), filtered and evaporated. The residue was purified by flash chromatography (15% ethyl acetate in hexane) to afford the sub-title compound as a colorless oil which crystallized upon standing (1.823g, 89%): ^1H NMR (400MHz, CDCl_3) δ 1.13-1.48 (3H, m), 2.57-2.69 (2H, m), 2.16 (1H, m), 3.00 (1H, m), 3.74 (4H, s+m), 5.00 (1H, m), 7.11 (2H, t), 7.22-7.34 (4H, m), 7.76 (2H, d); ^{13}C NMR (100MHz, CDCl_3) δ 21.3 (CH_2), 24.8 (CH_2), 27.3 (CH_2), 44.9 (CH_2), 52.5 (CH_3), 55.9 (CH), 122.8 (CH), 125.5 (CH), 127.8 (CH), 128.0 (CH), 129.2 (C), 141.7 (C), 158.4 (C), 172.2 (C).

Method B:

(S) - (1-Phenothiazine-10-carbonyl)piperidine-2-carboxylic acid


-27-



To a stirred solution of (S)-(1-phenothiazine-10-carbonyl)piperidine-2-carboxylic acid methyl ester (0.912g) in THF (15ml) and water (8ml) was added 2M NaOH (3.71 mL) and the reaction mixture was stirred for 16 hours. The reaction mixture was poured into sodium hydrogen carbonate solution (50 ml) and extracted with ethyl acetate (40 ml). Aqueous phase made acidic and extracted with ethyl acetate (2x75 ml). Organic extracts combined, dried (MgSO₄) and concentrated to leave the subtitle compound as a white solid (0.709g, 81%): ¹H NMR (400MHz, CDCl₃) δ 0.99-1.72 (5H, m), 2.23 (1H, m), 2.97 (1H, m), 3.58 (1H, m), 4.93 (1H, m), 7.16 (2H, t), 7.28 (2H, t), 7.37 (2H, d), 7.78 (2H, d); ¹³C NMR (100MHz, CDCl₃) δ 21.0 (CH₂), 24.2 (CH₂), 26.7 (CH₂), 45.7 (CH₂), 56.0 (CH), 123.8 (CH), 126.0 (CH), 127.9 (CH), 128.1 (CH), 130.3 (C), 141.2 (C), 160.1 (C), 175.9 (C).

20 Method C:

[3S/R, 4S/R (2S)]-5-Fluoro-4-hydroxy-3-{[1-(phenothiazine-10-carbonyl)piperidine-2-carbonyl]amino}-pentanoic acid tertbutyl ester




-28-

A stirred mixture of (S)-(1-phenothiazine-10-carbonyl)piperidine-2-carboxylic acid (233mg, 0.658mmol), 3-amino-5-fluoro-4-hydroxy-pentanoic acid tert-butyl ester (150mg, .724mmol), HOBT (98mg, 0.724mmol), DMAP (88mg, 0.724mmol) and anhydrous THF (10mL) was cooled to 0°C then EDC (139mg, 0.724mmol) was added. The mixture was allowed to warm to room temperature during 16h then concentrated under reduced pressure. The residue was purified by flash chromatography (50% ethyl acetate in hexane) to afford the sub-title compound as a pale pink foam (294mg, 82%): ¹H NMR (400MHz, CDCl₃) δ 1.96 (1H, m), 1.18-1.60 (13H, m), 2.10-2.25 (1H, m), 2.48-2.70 (2H, m), 2.78-2.94 (1H, m), 3.51-4.72 (7H, m), 7.03-7.36 (7H, m), 7.71-7.76 (2H, m); ¹⁹F (376MHz, CDCl₃) δ -228.9 (t), -229.3 (t), -230.1 (t), -230.2 (t).

Method D:

[3S/R, (2S)]-5-Fluoro-4-oxo-3-{[1-(phenothiazine-10-carbonyl)piperidine-2-carbonyl]amino}-pentanoic acid tert-butyl ester




A stirred solution of [3S/R, 4S/R (2S)]-5-fluoro-4-hydroxy-3-{[1-(phenothiazine-10-carbonyl)piperidine-2-carbonyl]amino}-pentanoic acid tertbutyl ester (294mg, 0.541mmol) in anhydrous DCM (10mL) was treated with 1,1,1-triacetoxy-1,1-dihydro-1,2-benziodoxol-3(1H)-one (344mg, 0.812mmol) at 0°C. The resulting mixture was allowed to warm to room temperature

-29-

over 2h, diluted with ethyl acetate, then poured into a 1:1 mixture of saturated aqueous sodium hydrogen carbonate and saturated aqueous sodium thiosulphate. The organic layer was removed and the aqueous layer re-extracted with ethyl acetate. The combined organic extracts were dried (Na₂SO₄) and concentrated. The residue was purified by flash chromatography (30% ethyl acetate in hexane) to afford the sub-title compound as a pale pink foam (220mg, 75%): ¹H NMR (400MHz, CDCl₃) δ 0.84-0.96 (1H, m), 1.20-1.40 (10H, m+2s), 1.51-1.56 (3H, m), 2.20-2.27 (1H, m), 2.70-2.98 (3H, m), 3.49-3.63 (1H, m), 4.74-5.24 (4H, m), 7.14-7.18 (2H, m), 7.28-7.38 (4H, m), 7.48-7.79 (3H, m); ¹³C (100MHz, CDCl₃) δ 20.8/21.0 (CH₂), 23.7/23.9 (CH₂), 25.8/25.9 (CH₂), 28.2/28.3 (CH₃), 36.8/36.9 (CH₂), 46.0/46.1 (CH₂), 52.9 (CH), 56.8 (CH), 82.6 (C), 84.4/84.5 (2d, J 184.0/183.3, CH₂F), 123.7/123.8 (CH), 126.1 (CH), 128.0/128.1 (CH), 128.2/128.3 (CH), 130.4/130.5 (C), 141.4 (C), 160.0 (C), 170.0 (C), 171.7 (C), 202.9 (C); ¹⁹F (376MHz, CDCl₃) δ -231.9 (t), -232.2 (t).

Method E:

[3S/R, (2S)]-5-Fluoro-4-oxo-3-{[1-(phenothiazine-10-carbonyl)piperidine-2-carbonyl]amino}-pentanoic acid



Trifluoroacetic acid (5mL) was added to a stirred ice cold solution of [3S/R, (2S)]-5-fluoro-4-oxo-3-{[1-(phenothiazine-10-carbonyl)piperidine-2-


-30-

carbonyl]amino}-pentanoic acid tert-butyl ester (130mg, 0.24mmol) in anhydrous DCM (5mL). The mixture was stirred at 0°C for 0.5h then at room temperature for 0.5h. The mixture was concentrated under reduced pressure and then the residue was dissolved in dry DCM. This process was repeated several times in order to remove excess trifluoroacetic acid. The gum was lyophilized twice from HPLC grade water to afford the title compound as a white powder (77mg, 66%): IR (solid) 1670, 1716, 1782 cm^{-1} ; ^1H NMR (400MHz, d_6 -DMSO) δ 0.96-0.99 (1H, m), 1.23-1.26 (2H, m), 1.42-1.44 (1H, m), 1.60 (1H, m), 1.91-1.98 (1H, m), 2.51-2.89 (2H, m), 3.11-3.22 (1H, m), 3.57-3.60 (1H, m), 4.30-4.72 and 5.05-5.29 (4H, 2m), 7.11-7.17 (2H, m), 7.24-7.30 (2H, m), 7.34-7.38 (2H, m), 7.57-7.63 (2H, m), 8.07-8.61 (1H, m); ^{13}C NMR (100MHz, DMSO) δ (DMSO+TFA) 18.8/18.9 (CH_2), 22.2/22.3 (CH_2), 25.8/26.1 (CH_2), 31.5/33.2 (CH_2), 43.2 (CH_2), 50.6/51.1 (CH), 54.4/54.5 (CH), 82.8/82.9 (2d, J 178.6/178.1, CH_2F), 119.9/120.0 (CH), 120.4/120.5 (CH), 124.0/124.1 m(CH), 125.9/126.0 (C), 126.4/126.5 (CH), 139.6/139.7 (C), 156.0/156.4 (CO), 170.3 (CO), 170.7/170.8 (CO), 202.2/202.3 (2d, J 14.6/15.1, CO).; ^{19}F (376MHz, DMSO) δ chemical shift (multiplicity, relative intensity) -226.7 (t, 3), -226.9 (t, 3), -230.4 (t, 1), -231.2 (t, 1), -232.7 (t, 10), -233.0 (t, 10).

Example 2

[3S/R, (2S)]-3-{[1-(2-Chlorophenothiazine-10-carbonyl)piperidine-2-carbonyl]amino}-4-fluoro-4-oxo-pentanoic acid

-31-




This was prepared from 2-chlorophenothiazine carbonyl chloride using procedures similar to those described above in Methods A-E (73mg, 69%): IR (solid, 5 cm⁻¹) 1738, 1660, 1555, 1363, 1224 ; ¹H NMR (400MHz, d₆-DMSO+TFA) δ 0.98-1.61 (4H, m), 1.94-2.03 (1H, m), 2.53-2.89 (2H, m), 3.12-3.24 (1H, m), 3.51-3.61 (1H, m), 4.31-4.73 and 5.10-5.24 (4H, 2m), 7.15-7.49 (6H, m), 7.77-7.81 (1H, m), 8.13-8.64 (1H, m) ; ¹³C NMR (100MHz, DMSO+TFA) δ 10 18.7/18.8 (CH₂), 22.3/22.6 (CH₂), 25.9/26.2 (CH₂), 31.5/33.2 (CH₂), 43.0/43.2 (CH₂), 50.6/51.1 (CH), 54.4/54.5 (CH), 82.8/82.9 (2d, J 178.7/178.3, CH₂F), 119.3/119.8 (CH), 120.2/120.3 (CH), 123.6/123.7 (CH), 124.4/124.5 (CH), 124.6/124.8 (C), 126.6 (CH), 126.9 15 (CH), 127.5 (CH), 131.0 (C), 139.2/139.2 (C), 140.7/140.7 (C), 155.5/155.9 (C), 170.1/170.2 (C), 170.7/170.8 (C), 201.2/201.3 (2d, J 14.3/13.9, CO) ; ¹⁹F NMR (376MHz, DMSO+TFA) δ -226.7 (t), -226.9 (t), -230.3 (t), -232.7 (t), -233.0 (t).

20

Example 3

[3S/R, (2S)]-3-{[1-(3-Chlorophenothiazine-10-carbonyl)piperidine-2-carbonyl]amino}-4-fluoro-4-oxopentanoic acid


-32-



This was prepared from 3-chlorophenothiazine carbonyl chloride using procedures similar to those described above in Methods A-E (108mg, 65%): IR (solid, 5 cm-1) 1737, 1655, 1455, 1373, 1224 ; ^1H NMR (400MHz, $\text{d}_6\text{-DMSO}+\text{TFA}$) δ 0.99-1.61 (5H, m), 1.91-2.04 (1H, m), 2.54-2.90 (2H, m), 3.12-3.24 (1H, m), 3.48-3.60 (1H, m), 4.26-5.28 (4H, m), 7.15-7.68 (7H, m), 8.10-8.62 (1H, m) ; ^{13}C NMR (100MHz, $\text{DMSO}+\text{TFA}$) δ 18.8 (CH_2), 22.2/22.3 (CH_2), 25.8 10 (CH_2), 33.1/33.2 (CH_2), 43.2 (CH_2), 50.6/51.0 (CH), 54.3/54.4 (CH), 82.7/82.8 (2d, CH_2F), 120.2/120.3 (CH), 121.3/121.4 (CH), 124.2/124.3 (CH), 124.8/125.0 (C), 125.7 (CH), 126.3 (CH), 126.6 (CH), 126.8 (CH), 127.7/127.9 (C), 127.9/128.0 (C), 138.5 (C), 139.3 (C), 15 156.0 (CO), 170.1 (CO), 170.6/170.7 (CO), 201.1/201.2 (2d, CO). ; ^{19}F NMR (376MHz, $\text{DMSO}+\text{TFA}$) δ -226.6 (t), -226.9 (t), -232.6 (t), -232.9 (t).

Example 4

20 [3S/R, (2S)]-3-{[1-(3,4-Dichlorophenothiazine-10-carbonyl)piperidine-2-carbonyl]amino}-4-fluoro-4-oxo-pentanoic acid




-33-

The title compound was prepared from 3,4-dichlorophenothiazine carbonyl chloride using procedures similar to those described above in Methods A-E (91mg, 66%): IR (solid, cm-1) 1737, 1439, 1363, 1219 ; ¹H NMR (400MHz, d₆-DMSO+TFA) δ 1.03-1.62 (5H, m), 1.97-2.06 (1H, m), 2.54-2.86 (2H, m), 3.14-3.28 (1H, m), 3.59-3.66 (1H, m), 4.30-5.26 (4H, m), 7.15-7.68 (6H, m), 8.14-8.96 (1H, m) ; ¹³C NMR (100MHz, DMSO+TFA) δ 20.2 (CH₂), 23.8 (CH₂), 27.3 (CH₂), 34.6/34.7 (CH₂), 44.5 (CH₂), 52.1/52.5 (CH), 55.7/55.9 (CH), 84.2/84.3 (2d, CH₂F), 120.2/120.3 (CH), 120.8/120.9 (CH), 124.2/124.4 (C), 125.9 (CH), 127.7/127.8 (C), 128.2 (CH), 128.4/128.5 (C), 128.8 (CH), 128.9 (CH), 140.0 (C), 140.1 (C), 140.6 (C), 156.8/156.8 (CO), 171.5 (CO), 172.1/172.1 (CO), 202.6/202.7 (2d, CO) ; ¹⁹F NMR (376MHz, DMSO+TFA) δ -226.6 (t), -226.8 (t), -232.6 (t), -232.9 (t).

Example 5

[3S/R, (2S)]-3-{[1-(2,6-Dichlorophenothiazine-10-carbonyl)piperidine-2-carbonyl]amino}-4-fluoro-4-oxopentanoic acid




The title compound was prepared from 2.7-dichlorophenothiazine carbonyl chloride using procedures similar to those described above in Methods A-E (91mg, 70%): IR (solid, cm-1) 1737, 1660, 1555, 1363, 1224 ; ¹H NMR (400MHz, d₆-DMSO+TFA) δ 1.02-1.62 (5H, m), 1.91-2.02

-34-

(1H, m), 2.53-2.90 (2H, m), 3.13-3.25 (1H, m), 3.51-3.62 (1H, m), 4.31-5.29 (4H, m), 7.22-7.75 (6H, m), 8.18-8.65 (1H, m); ^{13}C NMR (100MHz, DMSO+TFA) δ 20.2 (CH_2), 23.8 (CH_2), 27.3 (CH_2), 34.6 (CH_2), 44.7 (CH_2), 52.5 (CH), 55.8 (CH), 84.3 (d, J 178.2, CH_2F), 120.7/121.2 (CH), 122.7/122.8 (CH), 124.7/125.1 (C), 125.3/125.4 (CH), 127.4 (CH), 128.1 (CH), 128.7/128.9 (C), 129.1 (CH), 129.8 (C), 132.7 (C), 139.5/139.6 (C), 141.8/141.9 (C), 157.0 (CO), 171.5 (CO), 172.1 (CO), 202.6 (d, J 14.3, CO); ^{19}F NMR (376MHz, DMSO+TFA) δ -226.6 (t), -226.9 (t), -232.6 (t), -232.9 (t).

Example 6

[3S/R, (2S)]-3-{[1-(Carbazole-9-carbonyl)piperidine-2-carbonyl]amino}-4-fluoro-4-oxo-pentanoic acid




The title compound was prepared from 9-carbazole carbonyl chloride using procedures similar to those described above in Methods A-E (180mg, 75%): IR (solid, cm^{-1}) 1737, 1655, 1419, 1373, 1224; ^1H NMR (400MHz, d_6 -DMSO+TFA) δ 1.36-1.65 (6H, m), 1.94-1.99 (1H, m), 2.12-2.21 (1H, m), 2.59-2.89 (2H, m), 4.32-5.27 (4H, m), 7.30-7.36 (2H, m), 7.48-7.54 (2H, m), 7.63-7.76 (2H, m), 8.17-8.72 (3H, m); ^{13}C NMR (100MHz, DMSO+TFA) δ 19.0 (CH_2), 23.7/23.8 (CH_2), 26.5/26.8 (CH_2), 33.3/33.5 (CH_2), 44.1 (br, CH_2), 50.9/51.4 (CH), 54.5 (br, CH), 82.9/83.1 (2d, J 178.7/178.7, CH_2F), 111.0/111.1 (CH), 111.9 (CH), 119.5/119.7 (CH), 120.6/120.7 (CH), 122.5/122.7 (C),

-35-

125.8/125.9 (CH), 137.1/137.4 (C), 153.2/153.3 (C),
 170.3/170.4 (C), 170.8/170.9 (C), 201.4/201.5 (2d, J
 14.6/14.6, CO) ; ^{19}F NMR (376MHz, DMSO+TFA) δ d (J, %I)
 -226.6 (t, 3), -226.8 (t, 3), -230.0 (t, 1), -232.7 (t,
 5 10), -232.7 (t, 10).

Example 7

[3S/R, (2S)]-5-Fluoro-4-oxo-3-{[1-(6H-phenanthridine-5-
 carbonyl)-piperidine-2-carbonyl]amino}-pentanoic acid




10

The title compound was prepared from 9,10-
 dihydrophenanthrine carbonyl chloride using procedures
 similar to those described above in Methods A-E (115mg,
 61%): IR (solid, cm-1) 1731, 1419, 1363, 1219; ^1H NMR
 15 (400MHz; d_6 -DMSO+TFA) δ 1.27-1.69 (5H, m), 1.90-2.06 (1H,
 m), 2.55-2.87 (2H, m), 3.13-3.21 (2H, m), 4.31-5.26 (6H,
 m), 7.12-7.48 (6H, m), 7.84-7.86 (2H, m), 8.08-8.58 (1H,
 m) ; ^{13}C NMR (100MHz, DMSO+TFA) δ 20.5 (CH_2), 24.2 (CH_2),
 27.73 (CH_2), 34.6/34.8 (CH_2), 44.9 (CH_2), 48.5/48.7 (CH),
 20 52.1/52.5 (CH), 55.4/55.7 (CH), 84.2 (d, CH_2F), 120.2
 (CH), 123.3 (CH), 123.6 (CH), 124.7 (CH), 126.1
 (C), 126.3 (CH), 128.0 (CH), 128.3 (CH), 128.7 (CH), 131.6
 (C), 134.6 (C), 140.2 (C), 172.1/172.2 (CO), 172.4/172.4
 (CO), 203.0 (d, CO) ; ^{19}F NMR (376MHz, DMSO+TFA) δ -226.8
 25 (t), -226.9 (t), -232.7 (t), -232.9 (t).

-36-

Example 8

[3S/R, (2S)]-3-{[1-(2-Methylphenothiazine-10-carbonyl) piperidine-2-carbonyl]amino}-4-fluoro-4-oxo-pentanoic acid




5

The title compound was prepared from 2-methylphenothiazine carbonyl chloride using procedures similar to those described above in Methods A-E (3.7mg, 17%): ^1H NMR (400 MHz, d_6 -DMSO) δ 0.86-1.75 (7H, m), 1.91-2.80 (5H, m), 3.13-3.66 (2H, m), 4.13-4.77 (2H, m), 5.06-5.33 (1H, m), 6.96-8.61 (8H, m); ^{13}C NMR (100 MHz, d_6 -DMSO) δ 201.3, 201.2, 201.0, 171.8, 170.7, 170.6, 170.2, 169.8, 169.7, 156.2, 155.8, 139.7, 139.6, 139.6, 139.5, 136.1, 127.5, 125.9, 122.3, 122.2, 120.6, 119.8, 83.7, 83.6, 81.9, 81.8, 66.2, 53.8, 50.5, 43.1, 33.1, 28.6, 26.1, 25.9, 22.5, 22.3, 22.2, 22.1, 21.2 and 18.9; ^{19}F NMR (376 MHz, d_6 -DMSO) δ -226.7, -226.8, -230.2, -231.2, -232.7, -233.0.

20 Example 9

[3S/R, (2S)]-3-{[1-(2-Trifluoromethylphenothiazine-10-carbonyl) piperidine-2-carbonyl]amino}-4-fluoro-4-oxo-pentanoic acid


-37-



The title compound was prepared from 2-trifluoromethylphenothiazine carbonyl chloride using procedures similar to those described above in Methods A-E (1.78g, 98%):IR (solid, cm^{-1}) 1792.9, 1654.6, 1465.2, 1403.7, 1321.8, 1224.5, 1163.0, 1116.9; ^1H NMR (400 MHz, d_6 -DMSO) δ 0.76-1.09 (1H, m), 1.20-1.69 (4H, m), 1.87-2.10 (1H, m), 2.50-2.98 (2H, m), 3.18 (1H, m), 3.41-3.62 (1H, m), 4.26-4.80 (2.75H, m), 5.02-5.32 (1.25H, m), 7.17-7.64 (6H, m), 8.03-8.20 (1H, m), 8.43-8.68 (1H, brm), 12.50 (1H, brs); ^{19}F NMR (376 MHz, d_6 -DMSO) δ -61.6, -61.64, -61.7, -226.8, -226.9, -230.2, -231.3, -232.8, -233.1.

Example 10

[3S/R, (2S)]-3-{[1-(2-Methoxyphenothiazine-10-carbonyl)piperidine-2-carbonyl]amino}-4-fluoro-4-oxo-pentanoic acid




The title compound was prepared from 2-methoxyphenothiazine carbonyl chloride using procedures similar to those described above in Methods A-E (21mg, 4%):IR (solid, cm^{-1}) 1174.6, 1205.4, 1263.8, 1405.7,

-38-

1442.81, 1463.7, 1596.9, 1652.8; ^1H NMR (400 MHz, CDCl_3) δ 1.1 (1H, m), 1.3 (1H, m), 1.5-1.7 (3H, m), 2.15 (1H, m), 2.7-3.0 (3H, m), 3.60 (1H, t), 3.85 (3H, s), 4.6-4.9 (4H, m), 6.75 (1H, d), 7.1-7.7 (7H, m); ^{13}C NMR (100 MHz, CDCl_3) δ 20.9, 23.9, 26.0, 46.1, 56.1, 57.1, 109.8, 112.1, 112.2, 123.6, 126.9, 126.2, 127.9, 128.3, 128.6, 128.7, 141.1, 141.2, 142.4, 159.8, 159.9; ^{19}F NMR (376 MHz, CDCl_3) δ -231.09 and -230.76.

10 Example 11

[3S/R, (2S)]-5-Fluoro-4-oxo-3-{[1-(phenothiazine-10-carbonyl)piperidine-2-carbonyl]amino}-pentamide.




To a stirred mixture of [3S/R, (2S)]-5-Fluoro-4-oxo-3-{[1-(phenothiazine-10-carbonyl)piperidine-2-carbonyl]amino}-pentanoic acid (200mg, 0.4mmol), prepared as in Example 1, in anhydrous THF (4ml), was added EDC (84mg, 0.44mmol), and a solution of the ammonia in 1,4 dioxane (0.8 ml of a 0.5M solution, 4mmol). The mixture was stirred at room temperature for 16h then concentrated under reduced pressure. The residue was purified by flash chromatography (6% Methanol in dichloromethane) to afford the title compound as a white solid (35.5mg, 18%): ^1H NMR (400MHz, CDCl_3) δ 0.74-1.69 (6H, m), 2.02-3.63 (4H, m), 5.15-4.72 (4H, m), 6.05-6.79 (4H, 4xs) and 7.11-7.79 (8H, m). ^{19}F (376MHz, CDCl_3) δ -225.45, -225.60, -227.42, -228.07, -228.09 and -231.65.

-39-

Example 12

[3S/R, (2S)]-5-Fluoro-4-oxo-3-{[1-(phenothiazine-10-carbonyl)piperidine-2-carbonyl]amino}-pentanoic acid ethyl amide.



5


To a stirred mixture of [3S/R, (2S)]-5-fluoro-4-oxo-3-{[1-(phenothiazine-10-carbonyl)piperidine-2-carbonyl]amino}-pentanoic acid (196mg, 0.4mmol), prepared as in Example 1, in anhydrous DCM (8ml), was added
10 Polymer bound EDC (400mg, 0.8mmol) and a solution of the ethylamine in THF (0.6 ml of a 2M solution, 12mmol). The mixture was stirred at room temperature for 16h then concentrated under reduced pressure. The residue was purified by flash chromatography (2.5% methanol in
15 dichloromethane) to afford the title compound as a white solid (22.7mg, 11%): ¹H NMR (400MHz, CDCl₃) δ 1.09-1.39 (3H, m), 1.44-1.66 (6H, m), 2.04-3.66 (7H, m), 4.18-4.76 (6H, m) and 7.10-7.79 (8H, m). ¹⁹F NMR (376MHz, CDCl₃) δ -223.32, -223.73, -225.92 and -226.76.

20

Example 13

[3S/R, (2S)]-5-Fluoro-4-oxo-3-{[1-(phenothiazine-10-carbonyl)piperidine-2-carbonyl]amino}-pentanoic acid diethyl amide.


-40-



To a stirred mixture of [3S/R, (2S)]-5-fluoro-4-oxo-3-{[1-(phenothiazine-10-carbonyl)piperidine-2-carbonyl]amino}-pentanoic acid (200mg, 0.4mmol), prepared as in Example 1, in anhydrous DCM (4ml), was added carbodiimide (74mg, 0.44mmol) and a diethylamine (0.62ml, 6mmol). The mixture was stirred at room temperature for 16h then concentrated under reduced pressure. The residue was purified by flash chromatography (2.5% Methanol in dichloromethane) to afford the title compound as a white solid (25.3mg, 11%): ^1H NMR (400MHz, CDCl_3) δ 1.00-1.23 (6H, m), 1.45-1.67 (6H, m), 2.18 (1H, m), 2.74 (1H, m), 2.92 (1H, m), 3.21-3.33 (4H, m), 3.65 (1H, m), 4.68 (1H, m), 4.85 (1H, m), 4.98-5.36 (2H, m) and 7.12-7.95 (8H, m). ^{19}F NMR (376MHz, CDCl_3) δ -232.37 and -232.72.

Example 14

[3S/R, (2S)]-5-Fluoro-4-oxo-3-{[1-(phenothiazine-10-carbonyl)piperidine-2-carbonyl]amino}-pentanoic acid N,N-dimethyl aminoethylamide.




To a stirred mixture of [3S/R, (2S)]-5-fluoro-4-oxo-3-{[1-(phenothiazine-10-carbonyl)piperidine-2-

-41-

carbonyl]amino}-pentanoic acid (100mg, 0.2mmol), prepared as in Example 1, in anhydrous DCM (5ml), was added Polymer bound EDC (300mg, 0.6mmol) and N,N-dimethyl propylamide (0.88 ml, 6mmol). The mixture was stirred at room temperature for 16h then concentrated under reduced pressure. The residue was purified by flash chromatography (2% Methanol in dichloromethane) to afford the title compound as a white solid (16.5mg, 14%): ^1H NMR (400MHz, CDCl_3) δ 1.48-1.68 (6H, m), 2.20-2.40 (8H, m), 2.60 (1H, m), 2.71-3.06 (3H, m), 3.73 (1H, m), 4.01 (1H, m), 4.16-4.38 (2H, m), 4.62 (1H, m), 4.75 (1H, m), 6.96 (1H, m) and 7.11-7.77 (8H, m). ^{19}F NMR (376MHz, CDCl_3) δ -222.48 and -222.63.

15 Example 15

[3S/R, (2S)]-5-Fluoro-4-oxo-3-{[1-(phenothiazine-10-carbonyl)piperidine-2-carbonyl]amino}-pentanoic acid N methyl piperazine amide.



20 To a stirred mixture of [3S/R, (2S)]-5-fluoro-4-oxo-3-{[1-(phenothiazine-10-carbonyl)piperidine-2-carbonyl]amino}-pentanoic acid (200mg, 0.4mmol), prepared as in Example 1, in anhydrous THF (4ml), was added EDC (84mg, 0.44mmol) and N methyl piperazine (0.88 ml, 8mmol). The mixture was stirred at room temperature for 16h then concentrated under reduced pressure. The residue was purified by flash chromatography (2% Methanol in dichloromethane) to afford the title compound as a

-42-

white solid (33mg, 14%): ^1H NMR (400MHz, CDCl_3) δ 1.47-1.70 (6H, m), 2.13-2.50 (7H, m), 2.75 (1H, m), 2.90 (1H, m), 3.19 (1H, m), 3.41-3.65 (5H, m), 4.66 (1H, m), 4.86 (1H, m), 4.97-5.34 (2H, m), 7.12-7.18 (2H, m), 7.27-7.37 (3H, m), 7.23-7.54 (1H, m) and 7.74-7.78 (2H, m). ^{19}F NMR (376MHz, CDCl_3) δ -232.24 and -232.52.

The compounds of this invention are designed to inhibit caspases. Therefore, the compounds of this invention may be assayed for their ability to inhibit apoptosis, the release of IL- 1β or caspase activity directly. Assays for each of the activities are known in the art and are described below in detail in the Testing section.

According to another embodiment, the invention provides a composition comprising a compound of this invention or a pharmaceutically acceptable salt thereof, as described above, and a pharmaceutically acceptable carrier.

If pharmaceutically acceptable salts of the compounds of this invention are utilized in these compositions, those salts are preferably derived from inorganic or organic acids and bases. Included among such acid salts are the following: acetate, adipate, alginate, aspartate, benzoate, benzene sulfonate, bisulfate, butyrate, citrate, camphorate, camphor sulfonate, cyclopentanepropionate, digluconate, dodecylsulfate, ethanesulfonate, fumarate, glucoheptanoate, glycerophosphate, hemisulfate, heptanoate, hexanoate, hydrochloride, hydrobromide, hydroiodide, 2-hydroxyethanesulfonate, lactate, maleate, methanesulfonate, 2-naphthalenesulfonate, nicotinate, oxalate, pamoate, pectinate, persulfate,

-43-

3-phenyl-propionate, picrate, pivalate, propionate, succinate, tartrate, thiocyanate, tosylate and undecanoate. Base salts include ammonium salts, alkali metal salts, such as sodium and potassium salts, alkaline earth metal salts, such as calcium and magnesium salts, salts with organic bases, such as dicyclohexylamine salts, N-methyl-D-glucamine, and salts with amino acids such as arginine, lysine, and so forth.

Also, the basic nitrogen-containing groups may be quaternized with such agents as lower alkyl halides, such as methyl, ethyl, propyl, and butyl chloride, bromides and iodides; dialkyl sulfates, such as dimethyl, diethyl, dibutyl and diamyl sulfates, long chain halides such as decyl, lauryl, myristyl and stearyl chlorides, bromides and iodides, aralkyl halides, such as benzyl and phenethyl bromides and others. Water or oil-soluble or dispersible products are thereby obtained.

The compounds utilized in the compositions and methods of this invention may also be modified by appending appropriate functionalities to enhance selective biological properties. Such modifications are known in the art and include those which increase biological penetration into a given biological system (e.g., blood, lymphatic system, central nervous system), increase oral availability, increase solubility to allow administration by injection, alter metabolism and alter rate of excretion.

Pharmaceutically acceptable carriers that may be used in these compositions include, but are not limited to, ion exchangers, alumina, aluminum stearate, lecithin, serum proteins, such as human serum albumin, buffer substances such as phosphates, glycine, sorbic

-44-

acid, potassium sorbate, partial glyceride mixtures of saturated vegetable fatty acids, water, salts or electrolytes, such as protamine sulfate, disodium hydrogen phosphate, potassium hydrogen phosphate, sodium chloride, zinc salts, colloidal silica, magnesium trisilicate, polyvinyl pyrrolidone, cellulose-based substances, polyethylene glycol, sodium carboxymethylcellulose, polyacrylates, waxes, polyethylene-polyoxypropylene-block polymers, polyethylene glycol and wool fat.

According to a preferred embodiment, the compositions of this invention are formulated for pharmaceutical administration to a mammal, preferably a human being.

Such pharmaceutical compositions of the present invention may be administered orally, parenterally, by inhalation spray, topically, rectally, nasally, buccally, vaginally or via an implanted reservoir. The term "parenteral" as used herein includes subcutaneous, intravenous, intramuscular, intra-articular, intra-synovial, intrasternal, intrathecal, intrahepatic, intralesional and intracranial injection or infusion techniques. Preferably, the compositions are administered orally or intravenously.

Sterile injectable forms of the compositions of this invention may be aqueous or oleaginous suspension. These suspensions may be formulated according to techniques known in the art using suitable dispersing or wetting agents and suspending agents. The sterile injectable preparation may also be a sterile injectable solution or suspension in a non-toxic parenterally acceptable diluent or solvent, for example as a solution

-45-

in 1,3-butanediol. Among the acceptable vehicles and solvents that may be employed are water, Ringer's solution and isotonic sodium chloride solution. In addition, sterile, fixed oils are conventionally employed
5 as a solvent or suspending medium. For this purpose, any bland fixed oil may be employed including synthetic mono- or di-glycerides. Fatty acids, such as oleic acid and its glyceride derivatives are useful in the preparation of injectables, as are natural pharmaceutically-
10 acceptable oils, such as olive oil or castor oil, especially in their polyoxyethylated versions. These oil solutions or suspensions may also contain a long-chain alcohol diluent or dispersant, such as carboxymethyl cellulose or similar dispersing agents which are commonly
15 used in the formulation of pharmaceutically acceptable dosage forms including emulsions and suspensions. Other commonly used surfactants, such as Tweens, Spans and other emulsifying agents or bioavailability enhancers which are commonly used in the manufacture of
20 pharmaceutically acceptable solid, liquid, or other dosage forms may also be used for the purposes of formulation.

The pharmaceutical compositions of this invention may be orally administered in any orally
25 acceptable dosage form including, but not limited to, capsules, tablets, aqueous suspensions or solutions. In the case of tablets for oral use, carriers that are commonly used include lactose and corn starch. Lubricating agents, such as magnesium stearate, are also
30 typically added. For oral administration in a capsule form, useful diluents include lactose and dried cornstarch. When aqueous suspensions are required for

-46-

oral use, the active ingredient is combined with emulsifying and suspending agents. If desired, certain sweetening, flavoring or coloring agents may also be added.

5 Alternatively, the pharmaceutical compositions of this invention may be administered in the form of suppositories for rectal administration. These may be prepared by mixing the agent with a suitable non-irritating excipient which is solid at room
10 temperature but liquid at rectal temperature and therefore will melt in the rectum to release the drug. Such materials include cocoa butter, beeswax and polyethylene glycols.

 The pharmaceutical compositions of this
15 invention may also be administered topically, especially when the target of treatment includes areas or organs readily accessible by topical application, including diseases of the eye, the skin, or the lower intestinal tract. Suitable topical formulations are readily
20 prepared for each of these areas or organs.

 Topical application for the lower intestinal tract may be effected in a rectal suppository formulation (see above) or in a suitable enema formulation. Topically-transdermal patches may also be used.

25 For topical applications, the pharmaceutical compositions may be formulated in a suitable ointment containing the active component suspended or dissolved in one or more carriers. Carriers for topical administration of the compounds of this invention
30 include, but are not limited to, mineral oil, liquid petrolatum, white petrolatum, propylene glycol, polyoxyethylene, polyoxypropylene compound, emulsifying

-47-

wax and water. Alternatively, the pharmaceutical compositions may be formulated in a suitable lotion or cream containing the active components suspended or dissolved in one or more pharmaceutically acceptable carriers. Suitable carriers include, but are not limited to, mineral oil, sorbitan monostearate, polysorbate 60, cetyl esters wax, cetearyl alcohol, 2-octyldodecanol, benzyl alcohol and water.

For ophthalmic use, the pharmaceutical compositions may be formulated as micronized suspensions in isotonic, pH adjusted sterile saline, or, preferably, as solutions in isotonic, pH adjusted sterile saline, either with or without a preservative such as benzylalkonium chloride. Alternatively, for ophthalmic uses, the pharmaceutical compositions may be formulated in an ointment such as petrolatum.

The pharmaceutical compositions of this invention may also be administered by nasal aerosol or inhalation. Such compositions are prepared according to techniques well known in the art of pharmaceutical formulation and may be prepared as solutions in saline, employing benzyl alcohol or other suitable preservatives, absorption promoters to enhance bioavailability, fluorocarbons, and/or other conventional solubilizing or dispersing agents.

The above-described compositions are particularly useful in therapeutic applications relating to an IL-1 mediated disease, an apoptosis mediated disease, an inflammatory disease, an autoimmune disease, a destructive bone disorder, a proliferative disorder, an infectious disease, a degenerative disease, a disease associated with cell death, an excess dietary alcohol

-48-

intake disease, a viral mediated disease, uveitis, inflammatory peritonitis, osteoarthritis, pancreatitis, asthma, adult respiratory distress syndrome, glomerulonephritis, rheumatoid arthritis, systemic lupus erythematosus, scleroderma, chronic thyroiditis, Grave's disease, autoimmune gastritis, diabetes, autoimmune hemolytic anemia, autoimmune neutropenia, thrombocytopenia, chronic active hepatitis, myasthenia gravis, inflammatory bowel disease, Crohn's disease, psoriasis, atopic dermatitis, scarring, graft vs host disease, organ transplant rejection, osteoporosis, leukemias and related disorders, myelodysplastic syndrome, multiple myeloma-related bone disorder, acute myelogenous leukemia, chronic myelogenous leukemia, metastatic melanoma, Kaposi's sarcoma, multiple myeloma, haemorrhagic shock, sepsis, septic shock, burns, Shigellosis, Alzheimer's disease, Parkinson's disease, Huntington's disease, Kennedy's disease, prion disease, cerebral ischemia, epilepsy, myocardial ischemia, acute and chronic heart disease, myocardial infarction, congestive heart failure, atherosclerosis, coronary artery bypass graft, spinal muscular atrophy, amyotrophic lateral sclerosis, multiple sclerosis, HIV-related encephalitis, aging, alopecia, neurological damage due to stroke, ulcerative colitis, traumatic brain injury, spinal cord injury, hepatitis-B, hepatitis-C, hepatitis-G, yellow fever, dengue fever, or Japanese encephalitis, various forms of liver disease, renal disease, polyaptic kidney disease, H. pylori-associated gastric and duodenal ulcer disease, HIV infection, tuberculosis, and meningitis. The compounds and compositions are also useful in treating complications

-49-

associated with coronary artery bypass grafts and as a component of immunotherapy for the treatment of various forms of cancer.

The amount of compound present in the
5 above-described compositions should be sufficient to cause a detectable decrease in the severity of the disease or in caspase activity and/or cell apoptosis, as measured by any of the assays described in the examples.

The compounds of this invention are also useful
10 in methods for preserving cells, such as may be needed for an organ transplant or for preserving blood products. Similar uses for caspase inhibitors have been reported (Schierle et al., Nature Medicine, 1999, 5, 97). The method involves treating the cells or tissue to be
15 preserved with a solution comprising the caspase inhibitor. The amount of caspase inhibitor needed will depend on the effectiveness of the inhibitor for the given cell type and the length of time required to preserve the cells from apoptotic cell death.

20 According to another embodiment, the compositions of this invention may further comprise another therapeutic agent. Such agents include, but are not limited to, thrombolytic agents such as tissue plasminogen activator and streptokinase. When a second
25 agent is used, the second agent may be administered either as a separate dosage form or as part of a single dosage form with the compounds or compositions of this invention.

It should also be understood that a specific
30 dosage and treatment regimen for any particular patient will depend upon a variety of factors, including the activity of the specific compound employed, the age, body

-50-

weight, general health, sex, diet, time of
administration, rate of excretion, drug combination, and
the judgment of the treating physician and the severity
of the particular disease being treated. The amount of
5 active ingredients will also depend upon the particular
compound and other therapeutic agent, if present, in the
composition. As used herein, the term "patient" refers
to a warm-blooded animal, such as for example, rats,
mice, dogs, cats, guinea pigs, and primates such as
10 humans.

In a preferred embodiment, the invention
provides a method of treating a mammal, having one of the
aforementioned diseases, comprising the step of
administering to said mammal a pharmaceutically
15 acceptable composition described above. In this
embodiment, if the patient is also administered another
therapeutic agent or caspase inhibitor, it may be
delivered together with the compound of this invention in
a single dosage form, or, as a separate dosage form.
20 When administered as a separate dosage form, the other
caspase inhibitor or agent may be administered prior to,
at the same time as, or following administration of a
pharmaceutically acceptable composition comprising a
compound of this invention.

25 In order that this invention be more fully
understood, the following biological testing examples are
set forth. These examples are for the purpose of
illustration only and are not to be construed as limiting
the scope of the invention in any way.

-51-

Biological Testing ExamplesExample 16Enzyme Assays

5 The assays for caspase inhibition are based on
the cleavage of a fluorogenic substrate by recombinant,
purified human Caspases -1, -3, or -8. The assays are run
in essentially the same way as those reported by Garcia-
Calvo et al. (*J. Biol. Chem.* **273** (1998), 32608-32613),
10 using a substrate specific for each enzyme. The substrate
for Caspase-1 is Acetyl-Tyr-Val-Ala-Asp-amino-4-
methylcoumarin. The substrate for Caspases -3, and -8 is
Acetyl-Asp-Glu-Val-Asp-amino-4-methylcoumarin.

 The observed rate of enzyme inactivation at a
15 particular inhibitor concentration, k_{obs} , is computed by
direct fits of the data to the equation derived by
Thornberry et al. (*Biochemistry* **33** (1994), 3943-3939)
using a nonlinear least-squares analysis computer program
(PRISM 2.0; GraphPad software). To obtain the second
20 order rate constant, k_{inact} , k_{obs} values are plotted against
their respective inhibitor concentrations and k_{inact} values
are subsequently calculated by computerized linear
regression.

 The compounds tested under Example 16 possess
25 $k_{inact} > 50000 \text{ M}^{-1}\text{s}^{-1}$ against caspase-1, caspase-3 and
caspase-8.

Example 17

30 Inhibition of IL-1 β secretion from Mixed Population of
Peripheral Blood Mononuclear Cells (PBMC)

 Processing of pre-IL-1 β by caspase-1 may be
measured in cell culture using a variety of cell sources.

-52-

Human PBMC obtained from healthy donors provides a mixed population of lymphocyte and mononuclear cells that produce a spectrum of interleukins and cytokines in response to many classes of physiological stimulators.

5

Experimental procedure

The test compound is dissolved in Dimethyl Sulphoxide (DMSO, Sigma #D-2650) to give a 100 mM stock solution. This is diluted in complete medium consisting
10 of RPMI containing 10% heat inactivated FCS (Gibco BRL #10099-141), 2mM L-Glutamine (Sigma, #G-7513), 100U penicillin and 100 µg/ml streptomycin (Sigma #P-7539). The final concentration range of test compound is from 100 µM down to 6 nM over eight dilution steps. The
15 highest concentration of test compound is equivalent to 0.1% DMSO in the assay.

Human PBMC are isolated from Buffy Coats obtained from the blood bank using centrifugation on Ficoll-Paque leukocyte separation medium (Amersham, #17-
20 1440-02) and the cellular assay is performed in a sterile 96 well flat-bottomed plate (Nunc). Each well contains 100 µl of the cell suspension, 1×10^5 cells, 50 µl of compound dilutions and 50 µl of LPS (Sigma #L-3012) at 50 ng/ml final concentration. Controls consist of cells +/-
25 LPS stimulation and a serial dilution of DMSO diluted in the same way as compound. The plates are incubated for 16-18h at 37°C in 5% CO₂ & 95% humidity atmosphere.

After 16-18 h the supernatants are harvested after centrifuging the plates at 100 x g at 18°C for 15
30 min and assayed for their IL-1β content. Measurement of mature IL-1β in the supernatant is performed using the Quantikine kits (R&D Systems) according to manufacturer's

-53-

instructions. Mature IL-1 β levels of about 600-1500 pg/ml are observed for PBMCs in positive control wells.

The inhibitory potency of the compounds may be represented by an IC₅₀ value, which is the concentration
5 of inhibitor at which 50% of the mature IL-1 β is detected in the supernatant as compared to the positive controls.

Selected compounds from Table 1 were tested according to Example 17 and found to provide an IC₅₀ value less than 2 μ M for inhibition of IL-1 β secretion from PBMC.

Example 18

Anti-Fas Induced Apoptosis Assay

Cellular apoptosis may be induced by the
10 binding of Fas ligand (FasL) to its receptor, CD95 (Fas). CD95 is one of a family of related receptors, known as death receptors, which can trigger apoptosis in cells via activation of the caspase enzyme cascade. The process is initiated by the binding of the adapter molecule
15 FADD/MORT-1 to the cytoplasmic domain of the CD-95 receptor-ligand complex. Caspase-8 then binds FADD and becomes activated, initiating a cascade of events that involve the activation of downstream caspases and subsequent cellular apoptosis. Apoptosis can also be
20 induced in cells expressing CD95 eg the Jurkat E6.1 T cell lymphoma cell line, using an antibody, rather than FasL, to crosslink the cell surface CD95.

Anti-Fas-induced apoptosis is also triggered via the activation of caspase-8. This provides the basis of a
25 cell-based assay to screen compounds for inhibition of the caspase-8-mediated apoptotic pathway.

-54-

Experimental Procedure

Jurkat E6.1 cells are cultured in complete medium consisting of RPMI-1640 (Sigma No) + 10% foetal calf serum (Gibco BRL No.10099-141) + 2mM L-glutamine (Sigma No. G-7513). The cells are harvested in log phase of growth. 100ml Cells at $5-8 \times 10^5$ cells/ml are transferred to sterile 50ml Falcon centrifuge tubes and centrifuged for 5 minutes at 100xg at room temperature. The supernatant is removed and the combined cell pellets resuspended in 25ml of complete medium. The cells are counted and the density adjusted to 2×10^6 cells/ml with complete medium.

The test compound is dissolved in dimethyl sulphoxide (DMSO) (Sigma No. D-2650) to give a 100mM stock solution. This is diluted to 400µM in complete medium, then serially diluted in a 96-well plate prior to addition to the cell assay plate.

100µl of the cell suspension (2×10^6 cells) is added to each well of a sterile 96-well round-bottomed cluster plate (Costar No. 3790). 50µl of compound solution at the appropriate dilution and 50µl of anti-Fas antibody, clone CH-11 (Kamiya No.MC-060) at a final concentration of 10ng/ml, are added to the wells. Control wells are set up minus antibody and minus compound but with a serial dilution of DMSO as vehicle control. The plates are incubated for 16-18hrs at 37°C in 5% CO₂ and 95% humidity.

Apoptosis of the cells is measured by the quantitation of DNA fragmentation using a 'Cell Death Detection Assay' from Boehringer-Mannheim, No. 1544 675. After incubation for 16-18hrs the assay plates are centrifuged at 100xg at room temperature for 5 minutes.

-55-


150µl of the supernatant are removed and replaced by
150µl of fresh complete medium. The cells are then
harvested and 200µl of the lysis buffer supplied in the
assay kit are added to each well. The cells are
5 triturated to ensure complete lysis and incubated for 30
minutes at 4°C. The plates are then centrifuged at
1900xg for 10 minutes and the supernatants diluted 1:20
in the incubation buffer provided. 100µl of this
solution is then assayed exactly according to the
10 manufacturer's instructions supplied with the kit. OD_{405nm}
is measured 20 minutes after addition of the final
substrate in a SPECTRAmax Plus plate reader (Molecular
Devices). OD_{405nm} is plotted versus compound
concentration and the IC₅₀ values for the compounds are
15 calculated using the curve-fitting program SOFTmax Pro
(Molecular Devices) using the four parameter fit option.
Selected compounds from Table 1 were tested according to
Example 18 and found to provide an IC₅₀ value less than
100nM for the activity in the FAS induced apoptosis
20 assay.

While we have described a number of embodiments
of this invention, it is apparent that our basic examples
may be altered to provide other embodiments, which
utilize the compounds and methods of this invention.
25 Therefore, it will be appreciated that the scope of this
invention is to be defined by the appended claims rather
than by the specific embodiments, which have been
represented by way of example.

-56-

What is claimed is:

1. A compound of formula I:



wherein:

Ring A is an optionally substituted piperidine, tetrahydroquinoline or tetrahydroisoquinoline ring;

R¹ is hydrogen, CN, CHN₂, R, or CH₂Y;

R is an optionally substituted group selected from an aliphatic group, an aryl group, or an aralkyl group;

Y is an electronegative leaving group;

R² is CO₂H, CH₂CO₂H, or esters, amides or isosteres thereof; and

R³ is hydrogen, an optionally substituted aryl group, an optionally substituted aralkyl group or an optionally substituted C₁₋₆ aliphatic group, R⁴ is an optionally substituted group selected from an aryl group or a heterocyclyl group, or R³ and R⁴ taken together with the nitrogen to which they are attached optionally form a substituted or unsubstituted monocyclic, bicyclic or tricyclic ring.

2. The compound according to claim 1 having one or more features selected from the group consisting of:

(a) R¹ is CH₂Y where Y is an electronegative leaving group;

(b) R² is CO₂H, esters, amides or isosteres thereof; and

-57-

(c) R^3 is a hydrogen atom, an optionally substituted aryl group, an optionally substituted aralkyl group or an optionally substituted C_{1-6} aliphatic group, R^4 is an optionally substituted group selected from an aryl group or a heterocyclyl group, or R^3 and R^4 , taken together with the nitrogen to which they are attached, optionally form a ring selected from the group consisting of indole, isoindole, indoline, indazole, purine, benzimidazole, benzthiazole, imidazole, imidazoline, thiazole, pyrrole, pyrrolidine, pyrroline, pyrazole, pyrazoline, pyrazolidine, triazole, piperidine, morpholine, thiomorpholine, piperazine, carbazole, phenothiazine, phenoxazine, phenanthridine, acridine, purine, quinolizine, quinoline, isoquinoline, cinnoline, phthalazine, quinazoline, quinoxaline, 1,8-naphthyridine, pteridine, quinuclidine, and phenazine.

3. The compound of claim 2, wherein:

(a) R^1 is CH_2Y where Y is an electronegative leaving group;

(b) R^2 is CO_2H , esters, amides or isosteres thereof; and

(c) R^3 is a hydrogen atom, an optionally substituted aryl group, an optionally substituted aralkyl group or an optionally substituted C_{1-6} aliphatic group, R^4 is an optionally substituted group selected from an aryl group, or a heterocyclyl group; or R^3 and R^4 , taken together with the nitrogen to which they are attached, optionally form a ring selected from the group consisting of indole, isoindole, indoline, indazole, purine, benzimidazole, benzthiazole, imidazole, imidazoline, thiazole, pyrrole, pyrrolidine, pyrroline, pyrazole, pyrazoline,

-58-

pyrazolidine, triazole, piperidine, morpholine,
thiomorpholine, piperazine, carbazole, phenothiazine,
phenoxazine, phenanthridine, acridine. purine,
quinolizine, quinoline, isoquinoline, cinnoline,
5 phthalazine, quinazoline, quinoxaline, 1,8-naphthyridine,
pteridine, quinuclidine, and phenazine.

4. The compound according to claim 3 wherein $-CH_2Y$
is $-CH_2F$.


10

5. The compound according to claim 4 wherein R^3 and
 R^4 , taken together with the nitrogen to which they are
attached, form a ring selected from the group consisting
of indole, isoindole, indoline, indazole, purine,
15 benzimidazole, benzthiazole, imidazole, imidazoline,
thiazole, pyrrole, pyrrolidine, pyrroline, pyrazole,
pyrazoline, pyrazolidine, triazole, piperidine,
morpholine, thiomorpholine, piperazine, carbazole,
phenothiazine, phenoxazine, phenanthridine, acridine.
20 purine, quinolizine, quinoline, isoquinoline, cinnoline,
phthalazine, quinazoline, quinoxaline, 1,8-naphthyridine,
pteridine, quinuclidine, and phenazine.

6. A composition comprising a compound according to
25 any of claims 1-5 and a pharmaceutically acceptable
carrier.

7. A method for treating a disease in a patient
that is alleviated by treatment with a caspase inhibitor,
30 which method comprises administering to a patient in need
of such a treatment a therapeutically effective amount of
a compound of formula I:

-59-



I

wherein:

Ring A is an optionally substituted piperidine,

5 tetrahydroquinoline or tetrahydroisoquinoline ring;

R¹ is hydrogen, CN, CHN₂, R, or CH₂Y;

R is an optionally substituted group selected from an
aliphatic group, an aryl group or an aralkyl group;

Y is an electronegative leaving group;

10 R² is CO₂H, CH₂CO₂H, or esters, amides or isosteres
thereof; and

R³ is hydrogen, an optionally substituted aryl group, an
optionally substituted aralkyl group, or an optionally
substituted C₁₋₆ aliphatic group, R⁴ is an optionally

15 substituted group selected from an aryl group or a
heterocyclyl group, or R³ and R⁴ taken together with
the nitrogen to which they are attached optionally form
a substituted or unsubstituted monocyclic, bicyclic or
tricyclic ring.

20

8. The method according to claim 7 wherein the
compound has one or more of the following features:

(a) Ring A is an optionally substituted piperidine;

(b) R¹ is CH₂Y where Y is an electronegative leaving
25 group;

(c) R² is CO₂H, esters, amides or isosteres
thereof; and

(d) R³ is a hydrogen atom, an optionally substituted
aryl group, an optionally substituted aralkyl group or an

-60-

optionally substituted C₁₋₆ aliphatic group;; R⁴ is an optionally substituted group selected from an aryl group, a heterocyclyl group; or R³ and R⁴, taken together with the nitrogen to which they are attached, optionally form
5 aring selected from the group consisting of indole, isoindole, indoline, indazole, purine, benzimidazole, benzthiazole, imidazole, imidazoline, thiazole, pyrrole, pyrrolidine, pyrroline, pyrazole, pyrazoline, pyrazolidine, triazole, piperidine, morpholine,
10 thiomorpholine, piperazine, carbazole, phenothiazine, phenoxazine, phenanthridine, acridine. purine, quinolizine, quinoline, isoquinoline, cinnoline, phthalazine, quinazoline, quinoxaline, 1,8-naphthyridine, pteridine, quinuclidine, and phenazine.

15

9. The method according to claim 8 wherein:

- (a) Ring A is an optionally substituted piperidine;
- (b) R¹ is CH₂Y where Y is an electronegative leaving group;
- 20 (c) R² is CO₂H, esters, amides or isosteres thereof; and
- (d) R³ is a hydrogen atom, an optionally substituted aryl group, an optionally substituted aralkyl group or an optionally substituted C₁₋₆ aliphatic group, R⁴ is an
25 optionally substituted group selected from an aryl group or a heterocyclyl group, or R³ and R⁴, taken together with the nitrogen to which they are attached, optionally form aring selected from the group consisting of indole, isoindole, indoline, indazole, purine, benzimidazole,
30 benzthiazole, imidazole, imidazoline, thiazole, pyrrole, pyrrolidine, pyrroline, pyrazole, pyrazoline, pyrazolidine, triazole, piperidine, morpholine,

-61-

thiomorpholine, piperazine, carbazole, phenothiazine,
phenoxazine, phenanthridine, acridine. purine,
quinolizine, quinoline, isoquinoline, cinnoline,
phthalazine, quinazoline, quinoxaline, 1,8-naphthyridine,
5 pteridine, quinuclidine, and phenazine.

10. The method according to any of claims 7-9
wherein the compound is used to treat a disease selected
from an IL-1 mediated disease, an apoptosis mediated
10 disease, an inflammatory disease, an autoimmune disease,
a destructive bone disorder, a proliferative disorder, an
infectious disease, a degenerative disease, a disease
associated with cell death, an excess dietary alcohol
intake disease, a viral mediated disease, uveitis,
15 inflammatory peritonitis, osteoarthritis, pancreatitis,
asthma, adult respiratory distress syndrome,
glomerulonephritis, rheumatoid arthritis, systemic lupus
erythematosus, scleroderma, chronic thyroiditis, Grave's
disease, autoimmune gastritis, diabetes, autoimmune
20 hemolytic anemia, autoimmune neutropenia,
thrombocytopenia, chronic active hepatitis, myasthenia
gravis, inflammatory bowel disease, Crohn's disease,
psoriasis, atopic dermatitis, scarring, graft vs host
disease, organ transplant rejection, osteoporosis,
25 leukemias and related disorders, myelodysplastic
syndrome, multiple myeloma-related bone disorder, acute
myelogenous leukemia, chronic myelogenous leukemia,
metastatic melanoma, Kaposi's sarcoma, multiple myeloma,
haemorrhagic shock, sepsis, septic shock, burns,
30 Shigellosis, Alzheimer's disease, Parkinson's disease,
Huntington's disease, Kennedy's disease, prion disease,
cerebral ischemia, epilepsy, myocardial ischemia, acute

-62-

and chronic heart disease, myocardial infarction, congestive heart failure, atherosclerosis, coronary artery bypass graft, spinal muscular atrophy, amyotrophic lateral sclerosis, multiple sclerosis, HIV-related
5 encephalitis, aging, alopecia, neurological damage due to stroke, ulcerative colitis, traumatic brain injury, spinal cord injury, hepatitis-B, hepatitis-C, hepatitis-G, yellow fever, dengue fever, or Japanese encephalitis, various forms of liver disease, renal
10 disease, polyaptic kidney disease, H. pylori-associated gastric and duodenal ulcer disease, HIV infection, tuberculosis, meningitis, a treatment for complications associated with coronary artery bypass grafts, or an immunotherapy for the treatment of various forms of
15 cancer.

11. The method according to any of claims 7-9 wherein the compound is used to treat complications associated with coronary artery bypass grafts.

12. The method according to any of claims 7-9 wherein the compound is used for the preservation of cells, said method comprising the step of bathing the
20 cells in a solution of the compound or a pharmaceutically acceptable derivative thereof.

13. The method according to any of claims 7-9 wherein the compound is used for an organ transplant or
25 for preserving blood products.

-63-

14. The method according to any of claims 7-9 wherein the compound is used as a component of immunotherapy for the treatment of cancer.

