

(19) World Intellectual Property
Organization
International Bureau



(43) International Publication Date
10 February 2005 (10.02.2005)

PCT

(10) International Publication Number
WO 2005/012194 A1

(51) International Patent Classification⁷: **C02F 01/42**

George, F. [US/US]; 1714 Downey Street, Laramie, WY 82072 (US).

(21) International Application Number:

PCT/US2004/002373

(74) Agent: **RESSUE, Nicole, A.**; Santangelo Law Offices, P.C., 125 South Howes, Third Floor, Fort Collins, CO 80521 (US).

(22) International Filing Date: 28 January 2004 (28.01.2004)

(25) Filing Language: English

(26) Publication Language: English

(30) Priority Data:
60/443,548 28 January 2003 (28.01.2003) US

(71) Applicant (for all designated States except US): **THE UNIVERSITY OF WYOMING RESEARCH CORPORATION D/B/A WESTERN RESEARCH INSTITUTE** [US/US]; 365 North 9th Street, Laramie, WY 82072-3380 (US).

(81) Designated States (unless otherwise indicated, for every kind of national protection available): AE, AG, AL, AM, AT, AU, AZ, BA, BB, BG, BR, BW, BY, BZ, CA, CH, CN, CO, CR, CU, CZ, DE, DK, DM, DZ, EC, EE, EG, ES, FI, GB, GD, GE, GH, GM, HR, HU, ID, IL, IN, IS, JP, KE, KG, KP, KR, KZ, LC, LK, LR, LS, LT, LU, LV, MA, MD, MG, MK, MN, MW, MX, MZ, NA, NI, NO, NZ, OM, PG, PH, PL, PT, RO, RU, SC, SD, SE, SG, SK, SL, SY, TJ, TM, TN, TR, TT, TZ, UA, UG, US, UZ, VC, VN, YU, ZA, ZM, ZW.


(72) Inventors; and

(75) Inventors/Applicants (for US only): **JIN, Song** [CN/US]; 1902 Beaufort Street, Laramie, WY 82072 (US). **BROWN, Terry, H.** [US/US]; 4419 Viewpoint Court, Fort Collins, CO 80526 (US). **YOU, Youwen** [CN/US]; 231 Thornlane Court, Apt. #9, Newark, DE 19711 (US). **VANCE,**

(84) Designated States (unless otherwise indicated, for every kind of regional protection available): ARIPO (BW, GH, GM, KE, LS, MW, MZ, SD, SL, SZ, TZ, UG, ZM, ZW), Eurasian (AM, AZ, BY, KG, KZ, MD, RU, TJ, TM), European (AT, BE, BG, CH, CY, CZ, DE, DK, EE, ES, FI, FR, GB, GR, HU, IE, IT, LU, MC, NL, PT, RO, SE, SI, SK,

[Continued on next page]

(54) Title: CHARGE-BASED WATER FILTRATION SYSTEMS



(57) Abstract: Generally, systems for air and water purification using unpowered charged sorbent mediums (3) which may include layered double hydroxide (LDH) (1) compositions, lignin (2), and methods of sorbing inorganic or organic material(s) onto such mediums, including anionic contaminants (10), cationic contaminants (11), non ionic organic contaminants (20), and even biological agents (7) such as bacteria or viruses present in liquids or gases.



TR), OAPI (BF, BJ, CF, CG, CI, CM, GA, GN, GQ, GW, ML, MR, NE, SN, TD, TG).

For two-letter codes and other abbreviations, refer to the "Guidance Notes on Codes and Abbreviations" appearing at the beginning of each regular issue of the PCT Gazette.

Published:

— *with international search report*

CHARGE-BASED WATER FILTRATION SYSTEMS

I. CROSS-REFERENCES TO RELATED APPLICATIONS

5 This is an international application claiming the benefit of United States Provisional Application No. 60/443,548, filed 28 January 2003, hereby incorporated by reference.

II. TECHNICAL FIELD

10

Generally, filtration systems, layered double hydroxide (LDH) compounds and methods of sorbing inorganic or organic material(s) onto such LDH compounds, including biological agents such as bacteria or viruses present in liquids or gases.

15 III. BACKGROUND

Numerous species of biological agents, including, but not limited to, protozoans parasites, bacteria, fungi, or viruses enter water systems or enter the atmosphere from sources such as solid waste material, commercial processing wastes, sewage effluent, septic tanks effluents, sewage sludge, garbage disposal, urban runoff, medical facilities, agricultural runoff, human beings sneezing or coughing and the like.

25 Bacteria are well adapted to and are common biological agents in water systems. Bacteria may have ranges in size from about 1000 nanometers (nm) to about 10,000 nm in size and include species such as *Aeromonas*, *campylobacter*, *Escherichia coli*, *Helicobacter pylori*, *Legionella*, *Nontuberculosis mycobacteria*, *Psedomonas aeruginosa*, *salmonella*, *shigella*, *Vibrio vholerae*, *Yersinia enterocolitica*, and the like bacteria.

30

Major bacteria identified in ambient air include species such as: *Acinetobacter*, *Ordetella perfussis*, *Corynebacteria diphtheria*, *Mycobacterium avium*, *Pseudomonas aeruginosa*, *Staphylococcus aureus*, and the like bacteria.

Viruses have been detected in all environments including water systems as described by Gerba, C.P. and Rose, J.B., "Viruses in Source and Drinking Water", Drinking Water Microbiology (1990), incorporated by reference herein, and in
5 ambient air. Most viruses are small (about 20 nm to about 200 nm) and consist of nucleic acid encapsulated in protein molecules. In municipal sewage, more than 100 different viruses may be identified, and viruses such as poliovirus, hepatitis A, echo, coxsackie, rota, adeno, or Norwalk-like viruses are virulently hazardous at very low concentrations. In ambient air, viruses such as adenovirus, coronavirus, echovirus,
10 influenza, and rhinovirus have been widely detected.

Because the occurrence of pathogenic biological agents in water and air systems constitutes a serious threat to human health and can be the source of a variety of diseases, such as gastroenteritis, cholera, hepatitis, typhoid fever, giardiasis, or the
15 like, the United States Environmental Protection Agency is in the process of addressing the public health risk resulting from pathogenic contamination of water systems.

However, the use of conventional large-scale water purification technologies
20 such as ultraviolet irradiation or chlorination may allow concentrations of pathogenic biological agents to survive. As such, secondary treatment of conventionally treated water may be necessary to completely capture or remove biological agents in water systems. In addition, these technologies are largely not available in rural areas, military operations, tourism sites, etc. Under such circumstances, portable apparatus
25 with low or no power requirements are in need to remove bioagents from the water systems.

To meet the demand for secondary treatment technology, including, but not limited to, commercial or residential secondary water treatment, a variety of
30 distillation, reverse osmosis, and filtration systems have been developed which utilize evaporation, activated carbon, ion exchange resins, or reverse osmosis membranes to further purify water. However, even though these conventional technologies can be effective in the removal of certain organic compounds, and certain metals, such as

lead and mercury, a variety of problems remain yet to be addressed with respect to both primary and secondary treatment methods.

5 A significant problem with conventional water treatment technology can be that loading capacity of activated carbon or ion exchange resins, or the like, can be low requiring frequent changes or requiring the frequent use of reactivation procedures to maintain water quality. Similarly, reverse osmosis membranes may not be suitable for purification of water with high levels of dissolved solids because the reverse osmosis membrane can become saturated or clogged with solids resulting in
10 reduced efficiency.

Another significant problem with conventional water treatment technology can be that the amount of water processed may be low. Conventional evaporation technology and reverse osmosis technology are typically suitable only for those
15 applications in which small volumes of water are to be purified, such as in the residential setting to purify drinking water. In addition, the energy and pressurizing requirements of reverse osmosis treatment further limit its use.

Another significant problem with conventional water treatment technology can
20 be that sorbent materials used in conventional water treatment may possess a neutral or negatively charged surface. While some biological agents may nonspecifically interact with neutral or negatively charged sorbents, the low binding efficiency excludes the use of these sorbents to attract, capture, collect, or remove biological-agents from water systems.

25 These problems with conventional water treatment technology coupled with the increasing concerns over pathogenic microbial contamination of drinking water, and especially in view of recent concerns over the use of biological agents as weapons, warrant the imminent development of a cost-effective water treatment
30 technology that can be readily applied to remove biological agents from water systems.

Moreover significant problems remain unresolved with regard to conventional air or gas treatment technology. Prominent among these problems may be that conventional gas filtration systems may only remove relatively large particulates such as pollen while allowing pathogenic agents such as viruses to pass through without retention to the filter material.

The instant invention addresses each of these concerns with respect to attracting, capturing, inactivating, or removing metal ions, inorganic and organic compounds, or biological agents from aqueous systems or gas systems whether the treatment is primary or secondary.

On the basis of their structure and properties, specific applications for layered double hydroxide (LDH) compounds and compositions have been previously identified. These include the use of LDH compounds as catalysts and catalyst precursors, as antacids, as solid ionic conductors, in preparation of pigments, to interact with anionic contaminants such as $\text{Cr}_2\text{O}_7^{2-}$, trichlorophenol (TCP), and to interact with radioactive anionic pollutants TcO_4^- , ReO_4^- and I^- .

IV. DISCLOSURE OF THE INVENTION

Accordingly, a significant objective of the invention is to provide materials that, individually or in combination, interact with, capture, sorb, inactivate, or exchange a wide variety of materials in water or gas such as metal ions, inorganic compounds, organic compounds, biological agents, or the like materials.

Another significant object of the invention can be to provide layered double hydroxide compounds to treat water or gas by sorbing, absorbing, adsorbing, interacting with, attracting, sequestering, capturing, deactivating, or removing bacteria, including, but not limited to bacteria in the group consisting of: *Acinetobacter*, *Aeromonas*, *Campylobacter*, *Corynebacteria diphtheria*, *Escherichia coli*, *Helicobacter pylori*, *Legionella*, *Mycobacterium avium*, *Nontuberculosis mycobacteria*, *Ordetella perfussis*, *Pseudomonas aeruginosa*, *Salmonella*, *Shigella*,

Staphylococcus aureus, *Vibrio cholerae*, and *Yersinia* and other opportunistic bacteria.

Another significant object of the invention can be to provide layered double
5 hydroxide compounds to treat water or gas by sorbing, absorbing, adsorbing,
interacting with, attracting, sequestering, capturing, deactivating, or removing viruses,
including, but not limited to viruses in the group consisting of: *Adenovirus*,
Coronavirus, *Coxsackievirus*, *Echovirus*, *Enteroviruses*, *Hepatitis virus*, *Influenza*,
Norwalk-like virus, *Poliovirus*, *Reovirus*, *Rotavirus*, *Toravirus*, and the like viruses.

10

Another significant object of the invention can be to provide layered double
hydroxide compounds that exhibit positively charged surface areas or regions which
can interact with negatively charged surface areas or regions of biological agents to
attract, sorb, absorb, adsorb, sequester, capture, or remove them from water or air
15 systems.

Another significant object of the invention can be to provide layered double
hydroxide compounds having intercalated ions of sufficient size to maintain or orient
the sheets of the layered double hydroxide compounds a sufficient distance apart to
20 allow or optimize interaction of the positively charged surfaces of layered double
hydroxide compound with the numerous and varied biological agents, or materials, to
be attracted, sorbed, absorbed, adsorbed, captured, sequestered, or removed from
water or air systems.

25 Another significant object of the invention can be to provide layered double
hydroxide compounds for the removal of, both pathogenic biological agents and toxic
anionic trace elements, including, but not limited to, arsenic or selenium,
independently or at the same time.

30 Another significant object of the invention can be to provide layered double
hydroxide compounds which attract, sorb, absorb, adsorb, sequester, capture, or
remove pathogenic biological agents and toxic anionic compounds from water
systems at same time.

Another significant object of the invention can be to provide layered double hydroxide compounds for the removal of, both pathogenic and nonpathogenic biological agents and anions, including, but not limited to, phosphate, sulfate, and carbonate.

Another significant object of the invention can be to provide layered double hydroxide compounds (which exhibit positively charged surface areas or regions) attached to materials having negatively charged surface areas or regions whereby the presentation of both the positively charged surface of the layered double hydroxide in combination with the negatively charged surface of the attached material can attract, sorb, absorb, adsorb, capture, sequester, exchange, or remove materials (including mixtures of metal oxides and biological agents) in fluids that have either positively charged surface areas or regions or negatively charged surface areas or regions, or both.

Another significant object of the invention can be to provide layered double hydroxide-lignin compounds for the removal of, individually or in combination, biological agents or metals from liquids.

Another significant object of the invention can be to provide layered double hydroxide-lignin compounds for the removal of, individually or in combination, biological agents or metals from gases.

Another significant object of the invention can be to provide layered double hydroxide compounds that can be calcined to reactivate the layered double hydroxide compound, or destroy or deactivate the sorbed biological agents after use.

Another significant object of the invention can be to provide layered double hydroxide compounds that can be dissolved in acid solution and resynthesized by coprecipitation method(s) for recycle use after being first used for removing biological agents from water systems or gas systems.

Another significant object of the invention can be to provide water treatment apparatus including, but not limited to, batch process containers, flow through containers, columns, bags, tubes, or the like, whether disposable or reusable, filled with one or more layered double hydroxide compounds or one or more layered double hydroxides bound, attached, or coating support or carrier materials such as filters, membranes, or particles, to be used as water treatment apparatus for the removal of particulate, metals, inorganic compounds, organic compounds, or biological agents from water. The water treatment apparatus can be sized or configured to the particular application, the amount of water to be processed, and the location at which the water is processed.

Another significant object of the invention can be to provide water treatment apparatus for residential use configured to attach to or adapt to existing residential plumbing or water inlet or outlet fixtures to treat residential water by removal of metal, inorganic compounds, organic compounds, or biological agents.

Another significant object of the invention can be to provide easy-carry water treatment apparatus for United States army or military in the field to treat field water by removal of metal, inorganic compounds, organic compounds, or biological agents and obtain potable water.

Another significant object of the invention can be to provide fluid filtration systems that can be used for emergency response efforts to treat contaminated water or air.

Another significant object of the invention can be to provide layered double hydroxide compounds to biological scientists and environmental engineers to concentrate biological agents, including, but not limited to, bacteria and viruses, from liquid and gas samples.

Another significant object of the invention is to provide portable water or air treatment apparatus for military or other purposes which is discrete or can be combined with existing water or air treatment apparatus for use in the field.

Another significant object of the invention can be to provide layered double hydroxide compounds connected, attached or otherwise coated to a membrane or filter surface to collect or concentrate biological agents, such as bacteria, viruses, prions, proteins, nucleic acids, or other biological agents, components, or molecules in liquids. The biological agents collected or concentrated by the layered double hydroxide compound can serve as samples for qualification or quantification or otherwise analyzed to detect, identify, and characterize the collected biological agents.

Yet another object of the invention can be to provide gas treatment apparatus in batch process containers, flow through containers, columns, tubes, or the like, whether disposable or reusable, filled with one or more layered double hydroxide compounds or one or more layered double hydroxides bound, attached, or coating support or carrier materials such as filters, membranes, or particles, to be used to purify gases, or purify air or other partial pressures of gases, or otherwise treat gas by removal of particulate, metals, inorganic compounds, organic compounds, or biological agents. Specifically, layered double hydroxide compounds, including, but not limited to, layered double hydroxide-lignin compounds can be used to remove potential pathogens in the air delivered to residential or commercial buildings.

Naturally, further independent objects of the invention are disclosed throughout other areas of the specification.

V. BRIEF DESCRIPTION OF THE DRAWINGS

Figure 1 is an embodiment of the present invention for impurity sorption.

Figure 2 is a generic structure of layered double hydroxides in an embodiment of the present invention.

Figure 3 shows certain embodiments of the invention for layered double hydroxide compounds that can sorb certain inorganic or organic material(s).

Figure 4 shows certain embodiments of the invention for layered double hydroxide-lignin compounds.

5 Figure 5 shows certain embodiments of the invention which comprise a layered double hydroxide layer.

Figure 6 shows certain embodiments of the invention which comprise layered double hydroxide and lignin layers.

10

Figure 7 shows certain embodiments of the invention which comprise layered double hydroxide and lignin and organic compounds.

Figure 8 is an embodiment of the present invention of a mask.

15

Figure 9 is a representative view of an embodiment for water purification of the present invention.

Figure 10 shows certain embodiments of the invention which comprise layered
20 double hydroxide compounds that can sorb nonionic organic contaminants (NOCs).

Figure 11 is schematic view of an embodiment of the invention showing some of the more conceptual elements that may be included.

25 VI. MODE(S) FOR CARRYING OUT THE INVENTION

As mentioned earlier, the present invention includes a variety of aspects, which may be combined in different ways. The following descriptions are provided to list elements and describe some of the embodiments of the present invention.
30 These elements are listed with initial embodiments, however it should be understood that they may be combined in any manner and in any number to create additional embodiments. The variously described examples and preferred embodiments should not be construed to limit the present invention to only the explicitly described

systems, techniques, and applications. Further, this description should further be understood to support and encompass descriptions and claims of all the various embodiments, systems, techniques, methods, devices, and applications with any number of the disclosed elements, with each element alone, and also with any and all
5 various permutations and combinations of all elements in this or any subsequent application.

Generally, the present invention may provide a system for removal of impurities from any type of fluid. Impurities may include contaminants, pollutants, or
10 any type of undesired component that may be found in fluids. A fluid (40) may include any substance that is capable flowing, such as but not limited to liquid, gas, water, air, or the like. In some embodiments, the present invention may include establishing a fluid (40) which may include containing air or water in some sort of container, providing some type of indoor or enclosed area for air or water, providing
15 air or water from outdoors, among others.

Water may be used from a stream, any type of plumbing system, faucet, or any water source and air may be used from the outdoors, indoors, buildings, vehicles, and the like. Water may include raw water or even primarily treated water. Raw water is
20 to be understood as any water that is in a natural, uncultivated, or even unrefined state, it may be untreated water, or may be water from a river, ocean, stream, rain, and the like water sources. Primarily treated water may include water which may have been previously filtered, for example, water as received in a home or office, which may have gone through a municipal filtration system, such as water found in a
25 residential or commercial building or the like.


A fluid (40) may contain impurities that may be desired to be removed before a human, animal or the like consumes or may be exposed to those contaminants -- possibly for the prevention of an illness. In some embodiments, the present invention
30 may include the removal of nanostructural components from fluids. A nanostructural component may be any structure that is very small, minute, not visible or detectable by the eye, or the like.

In fluids, different types of impurities or contaminants may exist. For example, fluids may contain a first, second and third components, among others. A first component (4) may include any substance, chemical, or compound found in a fluid and may even include an anionic substance, such as but not limited to, an anionic contaminant (8), a biological agent, arsenic, selenium, dicamba, anionic surfactant, virus, bacteria, hormone, fungi, prions, proteins, nucleic acids, phosphate, sulfate, carbonate, MS2 virus, Phi-X 174, Escherichia coli strains, Pseudomonas aruginosa, and the like contaminants. A second component (5) may include any substance, chemical, or compound found in a fluid and may even include a cationic contaminant, lead, chromium, zinc, mercury, ammonium, sodium, calcium, iron, copper, and the like contaminants. A third component (6) may include any substance, chemical, or compound found in a fluid and may even include substances that are not anionic nor cationic that may exist in a fluid, such as but not limited to non-ionic organic contaminants (20), 1,2,4-trichlorobenzene, 1,1,1-trichloroethane, trichloroethylene, tetrachloroethylene, and the like contaminants. A bioagent may include any type of living organism, such as but not limited to virus, bacteria, hormone, fungi, MS2 virus, Phi-X 174, Escherichia coli strains, Pseudomonas aruginosa, and the like bioagents.

To remove various impurities or contaminants from fluids, the present invention may include providing an unpowered charged sorbent medium (3), shown in Figure 1. Previous attempts for filtration may include various types of filters that may be connected to a power source, such as a plug, battery, or the like, in order to create an electrostatic charge. Here, the present invention may include a medium that may not be connected to any sort of power source, yet contains a charge, either or both negative and positive, and which may be capable of sorbing various impurities. A sorbent may be any substance, compound, composition, chemical, or the like which can gather other substances and even gather other substances on a surface. Other substances may include impurities, contaminants and the like. Sorption of an impurity may include any kind of taking and holding of an impurity, possibly by absorption or adsorption.

A medium may include an intervening substance and may even include any type of porous support mediums which may be permeable by fluid, water, air, and the like and which holds or bears some sort of sorbent element. Mediums may include any substance that can be used for filtration or purification of fluids, such as but not limited to filter paper, plan paper, special paper fibers, cloth, fabric, water insoluble substances, coated particles, coating support, carrier materials and the like.

An unpowered charged sorbent medium (3) may include a layered double hydroxide ("LDH") composition (1) which may contain a net positive charge as shown in Figure 4. In embodiments, the present invention may include containing LDH compositions. Referring primarily to Figures 1 and 2, LDH (1) compounds are stacked positively charged octahedral sheets having a general formula of :



15

wherein M^{II} and M^{III} are bivalent and trivalent cations in octahedral positions and A^{n-} are anions intercalated with the octahedral sheets or anions bound in an intermediate layer. The interlayer spacing of the octahedral sheets can vary depending on the size and geometrical structure of the intercalated anions. The net positive charge on the surface of LDH compounds may be due to the isomorphic substitution of trivalent metals by divalent metals and this positive charge on the surface of LDH compound may be balanced by the intercalated anions. Due to their structure, LDH compounds can exhibit relatively large surface areas (0.02-0.12 km²/kg) and high anion exchange capacities (200-500 cmol/kg). LDH compounds also can exhibit high pH buffering capacities and are relatively stable under a wide range of pH values. Thermal stability of LDH compounds may be dependent on the intercalated anions and LDH compounds can may maintain their layered structure at temperatures under about 250°C.

As shown in figures 1, 2, and 3 a layered double hydroxide composition (1) may include interlayer anions (18), divalent and trivalent cations (19) and hydroxide (23). In embodiments, M^{II} may include divalent cations such as but not limited to Ca^{2+} , Mg^{2+} , Zn^{2+} , Co^{2+} , Ni^{2+} , Cu^{2+} , Mn^{2+} , and the like cations. M^{III} may include

trivalent cations such as but not limited to Al^{3+} , Cr^{3+} , Fe^{3+} , Co^{3+} , Mn^{3+} , and the like cations. A^n may include interlayer anions such as but not limited to Cl^- , NO_3^- , ClO_4^- , CO_3^{2-} , SO_4^{2-} , and the like interlayer anions. X may include a numerical number which can be, but is not limited to any number between about 0.1 to about 0.3. Of course, this number may vary. The number may determine the LDH anionic exchange capacity, which may also determine the removal ability of LDH. LDH compounds can be synthesized by coprecipitation of a solution of bivalent and trivalent metal salts with a base such as sodium hydroxide or potassium hydroxide, as known to those skilled in the art.

Referring to Figure 4, embodiments of the invention can include containing an amount of lignin (2) or even a lignin-dominant substance. An unpowered charged sorbent medium (3) may include lignin. Lignin may be used, in embodiments, as a pure substance or may be combined with other substances to create a lignin-dominated substance. A lignin-dominated substance may include any lignin-dominant waste, such as dried solids of "black liquor" (waste stream from paper industry), biowaste which may include, but it not limited to corn stalks, rice grains, and the like. Lignin (2) may be physically mixed with LDH or LDH can be precipitated on a lignin surface during the synthesis. Lignin is one of the most abundant biomass components on the planet and a numerous and wide variety of lignin compounds can be obtained through synthesis.

Lignin compounds generally carry negative charges on its surface, which offer numerous binding sites for cationic contaminants (9), positively charged compounds or even metals or the like. For example, toxic metals having ionic forms with positive charges are often present in water systems. Lignin compounds can remove about 99.9% of these metals from the aqueous phase. The combination of lignin (2) with LDH compounds can possess the affinity to both negatively charged contaminants as discussed above and to positively charged contaminants. Understandably, a lignin and LDH compound can be useful in attracting, collecting, sequestering, retaining, or removing either positively charged ions or negatively charged contaminants, individually or simultaneously.

In embodiments, the present invention may include moving at least some of a fluid in the vicinity of a sorbent or a medium having sorbents. Sorbents may include an anionic contaminant sorbent, a cationic contaminant sorbent (11), LDH composition, anionic compositions (13), cationic compositions (12), lignin, or any substance capable of sorbing. A movement may include a flow or current of any type including but not limited to physically moving a fluid, osmosis, mechanically moving a fluid, or the like fluid flow. A circulation element (50) may be used for a mechanical movement and may even be used to drive or force fluid movement, such as but not limited to an air blower, air conditioner, water or air pump, fan, an electronic apparatus, or any device for producing a current of fluid by movement of the device. Physically moving a fluid may include any type of movement made by a user or occurring naturally such as but not limited to stirring, breathing, wind, pouring water, river flow and the like.

As a fluid is moving, it may be near or in the proximity of a sorbent. Of course, not all of a fluid may be in the vicinity of a sorbent, but at least some of a fluid may get close enough to allow attraction of certain types of molecules to the sorbent. A fluid may pass through a medium and some fluid components may be prevented from moving through a medium due to the porous nature of a medium. For example, even without attraction, relatively larger substances may not pass through pores in a medium because of their size. Yet, smaller substances may fit through the pores and pass through a medium.

Accordingly, to remove a variety of impurities from fluids, the present invention, in embodiments, may provide attracting impurities to a charged component or sorbent. As previously discussed, impurities or contaminants may include first, second and third components, anionic contaminants, cationic contaminants, non-ionic organic contaminants and even biological agents. Anionic components having a net negative charge and even cationic compositions (12) having a net positive charge may be provided. By attraction, an impurity may be drawn by a physical force causing or tending to cause an impurity to approach, adhere, or unite to a charged component. This may include, but is not limited to the interactions between oppositely charged substances such as ionic interactions between a cation and an anion.

In embodiments, a dual sorbent medium may be provided in which any type of medium may sorb at least two types of contaminants. This may include an anionic component (13) and a cationic composition (12). Cationic composition (12) may
5 include layered double hydroxide compositions. Layered double hydroxides may include an anionic contaminant sorbent (10) due to the attraction of anions. Anionic components (13) may include lignin. Lignin may include a cationic contaminant sorbent due to the attraction of cations.

10 In other embodiments, the present invention may include sorbing at least some impurities to a component or sorbent. This may include, in various embodiments and as shown in Figure 7 sorbing a first component (4) on an anionic component (13), sorbing a second component (5) on a cationic composition (12), sorbing a third
15 component (6) on an organic component, sorbing an anionic contaminant (8) on LDH (1), sorbing cationic contaminants (9) on lignin (2), sorbing non-ionic organic contaminants (20) on organic components (17), sorbing biological agents on a unpowered sorbent medium and the like. Sorbing may include gathering or binding impurities to a component perhaps by absorption or adsorption or a combination of
20 the two processes, as known to those skilled in the art. Of course, some impurities or contaminants may not be sorbed. An impurity may be sorbed on a surface of a component, such as LDH as shown in figure 1.

After a fluid has been in some contact with a sorbent component, the present invention may providemoving a fluid with at least some reduction (42) of an impurity.
25 This may be further illustrated in figures 5, 6 and 8 where the fluid may be passed through some sort of filter and as it exits the filter or perhaps even as the fluid moves away from a filter (43) or purification apparatus, the fluid may be in a state of depletion of impurities. A fluid may have less impurities or contaminants then were originally present.

30

In certain embodiments, the present invention may include providing layered double hydroxide composition and containing an amount of LDH. This may include containing LDH in any way, and even a filtering device whether it be for air or water

filtration. The present invention may even include any type of medium that can hold LDH particles or solutions. Depending on how much fluid that may be desired to be filtered, an amount of LDH may be contained.

5 In embodiments, the present invention may include an anionic contaminant sorbent (10) which may include any type of sorbent that can sorb anionic contaminants (8). Accordingly, an anionic contaminant sorbent may include sorbing of inorganic and organic anionic contaminants. Some inorganic contaminants may include Cl^- , NO_3^- , ClO_4^- , CO_3^{2-} , SO_4^{2-} , CrO_4^{2-} , I^- , SeO_3^{2-} , SeO_4^{2-} , As(III) as well as
10 other anionic inorganic substances. Some organic contaminants may include trichlorophenol (TCP), trinitrophenol (TNP), 2,4-dichlorophenoxyacetic acid (2,4-D), 3,6 dichloro-2-methoxy benzoic acid (dicamba), octylsulfate (SOS), sodium dodecylsulfate (SDS), sodium 4-octylbenzenesulfonate (SOBS), sodium dodecylbenzenesulfonate (SDBS), as well as other cationic organic substances.
15 Anionic contaminant sorbents (10) may also sorb biological agents (7) such as viruses, bacteria, and the like. Some examples of these may include MS2, Phi-x 174, E coli, SO_2 , NO_x , H_2S , phenolic compounds, and other anionic organic vapors. Due to the number of different bacteria, any type of bacteria may be included and thus may be sorbed onto an anionic contaminant sorbent.

20

Certain embodiments of the invention comprise LDH compounds that can remove inorganic and organic material(s) from aqueous systems. For example, various LDH compounds and calcined-LDH compounds in accordance with the invention can be synthesized and used to sorb anionic selenium, arsenic, or dicamba
25 (3,6 dichloro-2-methoxy benzoic acid), and other inorganic and organic materials.

In embodiments, biological agents may be substantially sorbed on a surface of layered double hydroxide composition, as shown in Figure 1. At least some of the anionic contaminants may sorb on a surface of LDH, as shown in Figure 1. This may
30 occur due to the pore size on the surface of the LDH. Some anionic contaminants may be larger than the pore size of the LDH and may be sorbed on the surface of the LDH. Of course, some contaminants may fit through the pores and may even be sorbed in the intermediate layer of an LDH composition. The larger anionic

contaminants may remain sorbed to the surface of the LDH compound and these larger contaminants may include, but is not limited to viruses, fungi and any other large substances, bioagents, or compounds.

5 By substantially sorbed it is to be understood that LDH has a certain number of sites that it can sorb various anionic contaminants. At some point, the LDH surface may become full or mostly full of anionic contaminants and can no longer attract and sorb additional biological agents (7). A filter having LDH may be saturated when all or most of the LDH sorbing sites may be occupied by bioagents therefore no further
10 sorption could occur. At this point, the LDH may need to be removed from a filtration system and replaced with either new unsorbed LDH or even re-activated LDH. The lifespan for a filter may be calculated by the per unit sorbing capacity of LDH to certain bioagents. For example, for bacteria, typically 1 gram of LDH can sorb 10^8 bacteria. If it is determined that there are 10^{16} bacteria in certain volume
15 of pretreated medium, 2 grams of LDH could be the minimal requirement. To be conservative, a filter may be changed at about 60% to about 75% full. A percentage sorbent value may represent the amount of bioagents sorbed on a medium such as a filter having LDH. While this may include any percentage value, such possibilities may include:

- 20
- about 60%;
 - about 75%;
 - about 85%; and
 - about 95%.

Other values are certainly possible and all should be understood as represented within
25 the scope of this invention.

The present invention may include, in embodiments, chemically associating LDH and lignin. In embodiments, a chemical mixture (16) may include an anionic component (11) and a cationic component (12) and may even include LDH (1) and
30 lignin (2). A chemical mixture (16) may include an aggregate of two or more substances that are chemically united. A chemical association may include, but is not limited to ionic bonding, covalent bonding, tether molecule, hydrophobic interaction, and the like as known to those skilled in the art. In other embodiments, LDH and

lignin may be mixed where they are not chemically united and may even exist in no fixed proportion to each other.

LDH compounds, as described above, or otherwise described or synthesized,
5 can be associated directly with lignin through ion bonding, or can be associated with lignin through a tether molecule attached to lignin that presents a region sufficiently negatively charged to generate an ionic bond or covalent bond with LDH compound(s). LDH may be tethered to lignin with a variety of tether or linking molecules that may generate covalent bonds between the tether and lignin or between
10 the tether and LDH compound(s) or both, or LDH compounds may become associated with lignin by hydrophobic interaction, or the like. A wide variety of linking or tether molecules could be used to associate LDH compounds with lignin. The tether molecules could be selected on the basis of length, reactive groups, hydrophilicity, resistance to degradation, or the like. Understandably, numerous permutations and
15 combinations of lignin-LDH, or lignin-tether-LDH, can be generated. Each LDH, organo-LDH, lignin-LDH, or lignin-tether-LDH can be used in accordance with the invention to interact with, sequester, sorb, inactivate, or remove biological agents from various types of aqueous systems.

20 The present invention may provide, in embodiments, functionally situating unpowered charged sorbent medium (3) with lignin or even functionally situating an amount of LDH with an amount of lignin. This may include moving at least some of a fluid near or through LDH and some fluid may be moved near or through lignin. Depending on the type of environment, a fluid may be desired to first be filtered
25 through LDH and then through lignin. Or it may be desirable to first filter a fluid through lignin then through LDH. This may include stacking or layering LDH and lignin. In Figure 6, a LDH layer (14) and a lignin layer (15) in a column is shown. A fluid (40) having various contaminants such as anionic contaminants, biological agents, or cationic contaminants may move in a flow direction (36) through a column.
30 In embodiments, a fluid may pass through a LDH layer (14), a porous barrier (44) and a lignin layer (15). A fluid may move out of a column with a reduction (42) of contaminants. As illustrated in Figure 5, a column may contain at least LDH. While it can be used in columns, other embodiments may include layering with at least two

sheets of medium, such as paper, in which one is coated with LDH and the other is coated with lignin. These sheets may be layered, one in front of the other and may even be separated by a certain amount of distance -- such that the fluid may come into contact with both LDH and lignin. Functionally situating may include LDH compositions that are separate and distinct from lignin. By separate and distinct, LDH may not be mixed with lignin. This may include layers of LDH and layers of lignin and may even include separate filter with lignin and a separate filter with LDH. Contrarily, lignin and LDH may be intermixed with each other, in a solution or coated together on the same filter, and the like.

In embodiments, the present invention may include a cationic contaminant (9). A cationic contaminant (9) may be any cation and may include lead, chromium, zinc, mercury, ammonium, sodium, calcium, iron, copper, and the like. Lignin may include a cationic contaminant sorbent in which cationic contaminants may be attracted and sorbed on lignin.

In embodiments the present invention may include containing an amount of organic composition (17). Referring to Figure 10, LDH compounds or even organic compositions can sorb nonionic organic contaminants (NOCs) from aqueous systems. Various organo-LDH compounds in accordance with the invention can be synthesized by intercalation of a variety of organic anions in the alternative to intercalation of inorganic anions. The resulting organo-LDH compounds can have organophilic properties. These modified organo-LDH compounds can exhibit high sorption capacity for various NOCs, such as 1,2,4-trichlorobenzene, 1,1,1-trichloroethane, trichloroethylene, tetrachloroethylene in aqueous solutions. Compounds in accordance with the invention as shown in Figure 10, provide an interlayer arrangement of anionic surfactants such as octylsulfate, dodecylsulfate, octylbenzenesulfonate, dodecylbenzenesulfonate, or the like. These examples are meant to be illustrative of the wide variety of anionic surfactants that can be intercalated between brucite layers in accordance with the invention.

In embodiments, the present invention may provide for moving a fluid in the vicinity of an organic composition (17). Impurities in the fluid may be attracted and

may even be sorbed by the organic composition (17). Particularly, organic compositions may sorb non-ionic organic contaminants (20). For example, non-ionic organic contaminants may include benzene, ethylbenzene, toluene, xylenes, other aromatic compounds, perchloroethene, trichloroethene, dichloroethene and the like.

5 In embodiments, the present invention may include moving a fluid with a reduction of non-ionic organic contaminants (20).

In other embodiments, a percentage non-ionic organic contaminant reduction amount may be removed from a fluid. While any percentage of removal is possible,

10 such possibilities may include:

- about 70 % non-ionic contaminant reduction;
- about 75 % non-ionic contaminant reduction;
- about 80 % non-ionic contaminant reduction;
- about 85 % non-ionic contaminant reduction; and
- 15 - about 90 % non-ionic contaminant reduction;

Other percentage removals are certainly possible and all should be understood as represented within the scope of this invention.

20 In embodiments, the present invention may provide removing harmful biological agents from fluids such as air and water. Some harmful biological agents may include coronavirus, influenza, bacillus anthracis, measles, smallpox virus, among any disease that may cause a severe illness, perhaps even death.

25 In an embodiment, the present invention may include providing an amount of LDH functionally situated with lignin and organic compositions (17), as previously discussed. An organic composition may be mixed with lignin and LDH. In embodiments, the present invention may provide an organic composition layer, an LDH composition layer and even a lignin layer.

30

Unknown prior to the invention, was that the positive charges on the surface of LDH compounds make them ideal sorbents with respect to removing a wide range of biological agents, which as a whole or as regions, present negative charge. Although

biological agents, such as bacteria, viruses and fungi, may also present some localized positive charges at specific pH values, LDH compounds, organo-LDH compounds, lignin-LDH compositions and even surfactant modified LDH in accordance with the invention are capable of sorption of such bacteria and viruses to capture, to collect, to
5 retain, to sequester, to inactivate, or to remove, them from aqueous liquids or aqueous process systems.

In other embodiments, a percentage biological agent reduction amount may be removed from a fluid. While any percentage of removal is possible, such possibilities
10 may include:

- about 70% biological agent reduction;
- about 75% biological agent reduction;
- about 80% biological agent reduction;
- about 85% biological agent reduction;
- 15 - about 90% biological agent reduction;
- about 95% biological agent reduction; and
- about 100% biological agent reduction.

Other percentage removals are certainly possible and all should be understood as
20 represented within the scope of this invention.

The biological agent removal may be dependent on the contamination type, concentration, LDH type, competition anions and solution pH, among other factors. At a low anion concentration, the reduction rate may be about 100%. At a high
25 concentration, the reduction rate may be about 60%. Accordingly, such removal rates may vary.

In other embodiments, a percentage cationic contaminant reduction amount may be removed from a fluid. While any percentage of removal is possible, such
30 possibilities may include:

- about 80% cationic contaminant reduction;
- about 85% cationic contaminant reduction;
- about 90% cationic contaminant reduction; and

- about 95% cationic contaminant reduction.

Other percentage removals are certainly possible and all should be understood as represented within the scope of this invention.

5

As a non-limiting example, certain LDH compounds in accordance with the invention can be used to retain, sequester, or remove, MS2 (an indicator bacterial phage) virus, Phi-X 174, Escherichia coli strains (an indicator bacterium) or Pseudomonas aeruginosa from deionised water, tap water, or ground water having a pH range of 6.3-7.5, a residence time of 0 min to 3.0 hr, and temperature at 4-30 °C. Viral adsorption efficiency of LDH compounds in such aqueous systems can be 100% and 99.9% at viral concentrations of 2×10^6 plaque forming unit (PFU)/L and 2×10^8 PFU/L, respectively. The loading ratio in the case of MS2 adsorption is approximately 1.5×10^{11} to 8.0×10^{12} PFU /kg of LDHs. Bacterial adsorption efficiency can be 99.9% at an E. coli concentration of 3.7×10^8 colony forming unit (CFU)/L. The loading ratio in E.Coli adsorption can be approximately 2.2×10^{11} CFU/kg of LDHs.

As another non-limiting example, certain LDH compounds in accordance with the invention can be used to retain, sequester, or remove general bacteria from tap water and raw river and creek water having a pH range of 7.0-8.5, a residence time of 15 min to 45 min, and temperature at 20-30 °C. Bacterial adsorption efficiency of LDH compounds in such aqueous systems can be 75-100% at background bacterial concentrations of 5×10^5 - 2×10^7 CFU/ml.

25

In embodiments, LDH and even lignin can be packed or coated to carrier materials to make water filtration units. The filtered water, under this design, may be drinkable or potable. This type of apparatuses may be made as disposable tubes, pumps, columns, and other tools to produce drinkable water in the field where no potable water may be available.

30

In other embodiments, LDHs and even lignin can be packed into a unit that connects to a tap water faucet directly or even through an adaptor. The filtered water may be free or very low in metals and potential pathogenic agents.

5 In an embodiment, LDHs or even lignin may be used in a large scale column or vessel filter, which can be added to conventional drinking water or wastewater treatment process as a polishing step for disinfection.

10 In an embodiment, LDH can be coated to a membrane surface and used to concentrate bio-agents, such as viruses, bacteria, and other biological molecules. The collected LDH-bioagents may serve as samples for detection, identification, characterization and other applications. The LDH containing collector may highly concentrate bioagents present in water bodies; therefore it may increase the sensitivity of early detection of bioagents in waters.

15 In embodiments, LDH and even lignin can be used as air filters that possess high affinity to potential pathogens in the air. The filters can be used for both residential and commercial buildings.

20 In embodiments, the present invention may include a water treatment apparatus. A water treatment apparatus may include any type of device or apparatus or system that can be used to remove impurities from water. This may include, but is not limited to batch process containers, flow through containers, coated sand columns, columns, bags, tubes, coating support, and filters. The present invention may include establishing an amount of water desired to be filtered. LDH, lignin, organic
25 composition, individually or in any combination may be contained in a water treatment apparatus or even on a water filter. As previously discussed, different types of impurities may be attracted and even sorbed onto a water filter having various sorbents.

30 A water treatment apparatus may be attached to any type of plumbing system and may even be attached to a water outlet attachment. In other embodiments, the present invention may include attaching a water treatment apparatus to any type of plumbing such as a water inlet, outlet fixture, or the like. After attachment, the

present invention may include running water through the water treatment apparatus to remove any impurities or contaminants that may be in the water. A water outlet attachment may include any type of attachment configured to attach to a conduit, a sink faucet, outdoor conduit, and the like. Water treatment apparatus may be used to
5 treat different quantities of water. Some water treatment apparatus may include a high volume water filter in which large amounts of water may be treated. This may be useful for municipal applications.

In some embodiments, the water treatment apparatus may be portably used for
10 any type of water use perhaps even outdoor use. In other embodiments, the present invention may include a disposable semipermeable unit (27) as shown in Figure 9. A disposable semipermeable unit (27) may be a container of thin paper or cloth which may contain a measured amount of sorbents. A disposable semipermeable unit may be placed in an amount of water (22), may be placed in a water container (46), and
15 may even be in an amount of water sufficient for individual use. A disposable semipermeable unit may be a capsule or pouch, or any type of containment structure that may allow water to flow into and out of the disposable semipermeable unit while containing sorbents inside. A disposable semipermeable unit (27) may be manually handled during use. Manually handling may include a user holding the unit or even
20 holding a string attached to a unit, stirring water with a disposable semipermeable unit,, and the like. The disposable semipermeable unit may contain an anionic component, cationic components, LDH composition, lignin, organic compositions, and the like sorbents, individually or even in combination, as discussed previously.

In embodiments, the present invention may include removing impurities with
25 re-activated cationic composition or even re-activated LDH. In an embodiment, the present invention provides for a reactivation element (51). Once an cationic composition or even LDH has sorbed anionic contaminants, such as bioagents, they can be calcinated (e.g., heated) to convert the LDH compound retaining such
30 collected biological agents back to the original structural configuration which can then again be used to collect bio-agents. This makes LDH compounds in accordance with the invention ideal candidates for industrial applications. LDH compounds, along with the sorbed biological agents, can be incinerated at between about 400 °C to

about 450 °C for a duration of between about one hour to about three hours depending on the LDH compound (two hours typically being sufficient) to affect complete decomposition of retained organic materials, including bio-agents, and convert the structural configuration of the used LDH compound to the activated structural configuration capable again of attracting, collecting, retaining, or otherwise having an affinity for biological agents or organic compounds. The impurity, contaminant, and even biological agent that was sorbed on LDH may be removed by this process. After removal of the impurities, LDH may be rehydrated and used to sorb other impurities. The ability to regenerate, reactivate, or restore used LDH compounds allows LDH compositions and even organo and LDH compounds, in accordance with the invention, to be repeatedly regenerated and used over and over to attract or collect bio-agents or organic compounds.

After LDH compounds are used to collect bio-agents, they can be dissolved in acid solution and the collected bio-agents can be inactivated in acid solution. Then the LDH compounds can be resynthesized by coprecipitation of an acid solution with base, for example, sodium hydroxide or potassium hydroxide. The ability to regenerate, reactivate, or restore used LDH compounds allows LDH compounds, in accordance with the invention, to be repeatedly regenerated and used over and over to attract or collect bio-agents or organic compounds.

In other embodiments the present invention may include detecting any impurities that may have been sorbed on a sorbent, identifying an impurity or even a biological agent. A biological agent identification element (52) may include some type of sensor that may respond in some fashion when biological agents may be detected.

In an embodiment, the present invention may provide moving at least some of a fluid through a primary medium or even a primary filter. A primary filter (45) may be any kind of filter that is known in the art or even as discussed in this application that can be included in addition to a medium or filter as discussed above. Here, one could simply add a filter as discussed in this invention to a previous existing filtration system. The primary filter may be used as a first filtration system and may prevent at

least some of certain impurities, contaminants, components, such as but not limited to dust, dirt, and the like from moving through said primary filter. Then the fluid can pass through an unpowered charged sorbent medium, such as an LDH filter, a lignin filter, or even a combination of the two. This may provide extended use of such
5 unpowered charged sorbent medium. It may be desirable to replace the primary filter more often than the LDH filter, as an example.

In other embodiments, the present invention may include providing an air filter. A filter (43) may be represented in figure 11. An air filter may include any
10 type of substance in which air may be permeable. An air filter may include but is not limited to, a membrane, filter, batch process containers, flow through containers, columns, tubes, coating support, carrier materials, masks, particles and the like. Air filters may have a flat surface or may even have a pleated surface to add to the surface area to the filter. LDH, lignin, organic composition, or the like, individually,
15 separately or in any combination may be applied to an air filter. This may include spraying LDH, lignin, or even organic composition on paper, coating a filter with LDH, and the like.

As shown in figure 11, a fluid (40) may move in a flow direction (36) through
20 a filter (43). A filter may be any type of filter including, but not limited to a water or air filter. A filter (43) may include cationic compositions (12) and may even include anionic components (13). After passing through a filter (43), a fluid may have a reduction (42) of contaminants. A circulation element (50) may be included to circulate a fluid. Further, an identification element (52) may be included which may
25 detect and even identify contaminants, anionic contaminants, and even biological agents. A reactivation element (51) may be included which may be used to re-activate or even recycle an anionic composition, perhaps even a LDH composition.

In embodiments, the present invention may include electrostatically sorbing
30 contaminants. This may include creating any type of medium with electric charges or even currents in which impurities or contaminants may be sorbed.

The present invention may include establishing respiratory air in a confined community gathering location. Air or even respiratory air may include air that is intended or may be breathed by an animal or human being. A confined community gathering location may include any location in which a few or even several people
5 may meet and which contaminants may exist in the air. This may include a building, school, home, and the like. An air filter may include LDH so that when air may be moved near or through the air filter, anionic contaminants may be attracted and may even be sorbed to the LDH, as discussed above. The air may be moved and circulated in a confined community gathering location with a reduction in anionic contaminants,
10 for example, bioagents. As such, the present invention may provide for circulating purified air in an aircraft, commercial building, residential structure, vehicle or the like. Further, in embodiments, an air filter may contain lignin which may attract and sorb cationic contaminants, also discussed previously. Air filters may be used in a number of different applications. For example, but not limited to, an air filter may be
15 configured for an airplane, commercial building, a residential structure, a vehicle, and the like.

An individual may be contaminated with a communicable illness, such as the flu, severe acute respiratory syndrome (SARS), or the like. That individual may want
20 to prevent others from catching the illness, or even an individual may desire to protect themselves from breathing in contaminants. In embodiments, the present invention may provide for a wearable mask (37) having an amount of LDH composition on it. In Figure 8, a representation of a mask (37) is shown. A mask may include a cloth or even a paper material that may have a LDH layer (14). The air flow may include the
25 air one inhales or the air the one exhales. As the air flow may move in an air flow direction (36) through a mask, bioagents (7), as shown in Figure 8 may be sorbed onto LDH. Of course, any contaminant may be sorbed onto a wearable mask such as but not limited to anionic contaminants, cationic contaminants, and even non-ionic organic contaminants. In embodiments, a wearable mask may include individually, or
30 in combination, anionic components, cationic components, organic components, LDH composition, and even lignin. In embodiments, a wearable respirable mask may be a disposable mask. A mask may be any type of mask, as known to those skilled in the art and may be placed on at least part of a face that may allow the passage of air and

moisture. The present invention may provide covering at least a nose and mouth to ensure all or most of the air either exhaled or inhaled may be filtered. The mask may be attached to at least part of a head. This may include, but is not limited to, attaching strings or the like around the ears, providing an elastic band that goes around a
5 circumference of a head, and it may even include providing strings that can be tied together around the head. In embodiments, the wearable respirable mask may be removably sealingly attached to a user's face. To ensure that most of the air may be filtered, some sort of seal may be desirable where the mask and the face contact. This may simply be a tight securement of the mask to the head and may even have some
10 sort of elastic edge to the mask. It may be desirable to remove and possibly reattach the mask. A user may then respire or flow air through the mask. As a user is inhaling, the outside air may be passed through the mask, allowing any contaminants, and even bioagents to be attracted and sorbed onto LDH. Contrarily, a user may exhale air and any bioagents contained in the exhaled air may be attracted and sorbed
15 onto the LDH. In embodiments, a wearable mask (37) may include a primary filter (45), as discussed above.

After using a wearable mask, the mask may have biological agents substantially sorbed on the surface of the LDH composition, as discussed above. In
20 other embodiments, the wearable respirable mask may include providing lignin on a mask and the mask may even include other organic compositions. The wearable mask may include individually or in combination lignin, LDH or an organic compositions for the removal of cationic contaminants, anionic contaminants and non-ionic organic contaminants. As discussed above the lignin may be layered on the mask with LDH
25 or may even be chemically associated with LDH. Any or even all of the sorbents may be sprayed on paper. Of course, any way to attach the sorbents to some sort of filter is meant to be included in this disclosure.

In embodiments, the present invention may provide attracting a first
30 component to a vehicle air filter. In embodiments, an air filter may include a vehicle air filter in which a LDH composition may be provided on an air filter. In other embodiments, an air filter used in a vehicle may contain, but is not limited to a cationic composition, an anionic composition, LDH, lignin, organic compositions,

individually or in any combination. A vehicle air filter may be placed in a vehicle possibly near the air vents, or at any place in the car. A vehicle air filter may even include a mechanical device which may be plugged into a cigarette lighter for power. A vehicle may have an enclosed space in which air may be established in the vehicle.

5 Of course, a window or door may be opened in which air flow from the outside may occur. The air in a vehicle or even respiratory air in a vehicle may interact with a vehicle air filter. Any contaminants may be attracted and sorbed on the vehicle air filter. Of course, such contaminants may include anionic contaminants, cationic contaminants, biological agents, and even non-ionic contaminants, as previously

10 discussed. The air can be circulated in the vehicle with a reduction in contaminants and even a reduction in bioagents. Occupants of a vehicle may release contaminants when sneezing or coughing, or even simply breathing creating air which may need to be re-filtered and then re-circulated. In other embodiments, the vehicle air filter may include lignin and may even include other organic compositions to remove anionic

15 contaminants and non-ionic organic contaminants.

The present invention can be used in a wide variety of applications. For example, using an unpowered charged sorbent medium, LDH composition, lignin composition and even organic compositions for commercial use, residential use,

20 personal use, and the like.

EXAMPLE I.

25 Virus stocks were diluted in artificial groundwater (CaCl_2 0.075 mM, MgCl_2 0.082 mM, KCl 0.051 mM and NaHCO_3 1.5 mM) having pH 7.5. A 5 ml aliquot of LDH stock solution (ultrasonically dispersed) was transferred to sterilized 25 ml Screw-top Corex glass centrifuge tubes. To avoid generation of an air-water interface (AWI), 25 ml of virus solutions were transferred into such tubes to form a meniscus at

30 the tube opening and capped. Tubes containing the mixture of LDH solution and virus solution were mixed in an end-over-end shaker at 20 rpm for 3 hr at between 4-7 °C and then centrifuged at 9,000 g for 15 min. Virus concentration in LDH

suspensions was determined by plaque assay. All experiments were conducted with three replicates and using control blanks.

EXAMPLE II.

5

LDH-coated sand was generated by transferring 1000 g oxide-removed sand to a plastic beaker and 2 L 5% LDH solution was added. The mixture was autoclaved for 1 hr and oven dried at 80 °C with occasionally stirring. The LDH-coated sand was then washed extensively with distilled water to remove unbound LDH and oven-dried.

10 Acrylate columns having top and bottom plates sealed with O-rings were fitted with a stainless steel screen on the bottom plate. LDH-coated sand was transferred in 1-cm increments into the column prefilled with deaerated water and stirred to prevent layering and air entrapment. Around 100 pore volumes (PV) of buffer solution (AGW) are pumped into the sealed columns with a peristaltic pump to establish a

15 steady-state flow condition. Virus solutions were pumped into separate corresponding columns and outflow samples were collected in 4 ml glass tubes using a fraction collector. The concentrations of viruses in the various samples were determined by plaque assay.

20 EXAMPLE III.

Sand LDH-lignin columns were prepared and equilibrated as described in Example II. Bacteria solutions were pumped into separate columns prepared and outflow samples were collected in 4 ml glass tubes using a fraction collector. The

25 concentrations of bacteria in the various samples were determined by plaque assay.

EXAMPLE IV.

30 Sand LDH-lignin columns were prepared and equilibrated as described in Example II and III. Mixtures of virus and bacteria solutions were pumped into separate columns prepared and outflow samples were collected in 4 ml glass tubes

using a fraction collector. The concentrations of bacteria in the various samples were determined by plaque assay.

EXAMPLE V.

5

LDH was made in granular form with particle sizes (e.g., 0.3 mm -3 mm diameter) that facilitate reasonable water flow rate. One to five grams of LDH was packed into a 10 ml syringe sized column with glass wool at the outflow port. Bacteria/virus containing water flow into the column and the effluent concentrations were determined by colony/plaque assay. Approximately 200 mls of raw river water (98200 CFU/ml bacteria or 1.8×10^7 total bacteria) may be filtered with 5 g of LDH material. Effluent water from such a filtration system may be potable with sufficient removal of bioagents. An expanded example of this application is to increase the amount of LDH and column size proportionally to treat larger quantity of raw or partially treated bacteria/virus containing water.

15

EXAMPLE VI.

LDH was made in granular form with particle sizes (e.g., 0.3 mm -3 mm diameter) that facilitate reasonable water flow rate. LDH was packed into a sizable column with glass wool at the outflow port. The column may be attached to a pump. Bacteria/virus containing water flow into the column and the effluent concentrations were determined by colony/plaque assay. Approximately 200 mls of raw water (98200 CFU/ml bacteria or 1.8×10^7 total bacteria) may be filtered with 5 g of LDH column. Effluent water from such a filtration system may be potable with sufficient removal of bioagents. The sizes of the column and pump are flexible based on the amount and quality of water to be filtered. Such a system may be used for military personnel, field travelers, small municipality, rural farms, etc.

25

EXAMPLE VII

30

LDH was made in granular form with particle sizes (e.g., 0.3 mm -3 mm diameter) that prevents its leakage from a porous wrap such as double layered cheese

cloth. Five grams of LDH was packed into a doubled layered cheese cloth and put into a cup of 200 ml of raw river water (8200 CFU/ml bacteria or 1.8×10^7 total bacteria). The bagged LDH was placed in the water for 30 min with or without stirring. Treated water from such a system may be potable with sufficient removal of
5 bioagents. An expanded example of this application is to increase the amount of LDH material proportionally to treat larger quantity of raw or partially treated bacteria/virus containing water.

EXAMPLE VIII

10

LDH was made in powder or granular form and packed in a treatment tank, vessel or similar containers. Amount of LDH is determined based on the quality of the water to be treated. This system may be added to an existing water treatment process as a bioagent removal step. Applications include residential and industrial
15 water treatment facilities.

EXAMPLE IX.

Air-filter devices were prepared using acrylate columns as described in
20 Example II. Air or other partial pressures of gases are passed through a liquid solution to collect the bacteria or virus, or both, in the volume of gases. The liquid solutions were then pumped into separate columns prepared and outflow samples were collected in 4 ml glass tubes using a fraction collector. The concentrations of bacteria in the various samples were determined by plaque assay. Control blanks were run in a
25 substantially identical fashion to provide a baseline for comparison.

EXAMPLE X.

Gas filter devices can be prepared using a carrier material such as ceramic or
30 fabric material. LDH compounds can be used to coat a variety of carrier materials with an amount of LDH compound sufficient to afford nano-structural exclusion or electrostatic sorption of biological agents present in ambient air. Air flow through the gas filter devices can be facilitated with pressure differential generation devices such

as pumps or fans. Air or other partial pressure of gases are passed through the gas filter device to collect the bacteria or virus, or both, in the volume of gases. The concentrations of bacteria in various samples can be determined by plaque assay. Control blanks can be run in substantially identical fashion to provide a baseline for comparison. The LDH coated fabrics and particles can be used in one embodiment as an additional filter layer in a respirator canister or in household air purifiers, or the like.

EXAMPLE XI.

The data gathered may show that LDH in a bag can sorb bacteria such as *Pseudomonas aeruginosa* and extrapolately other bacteria in water samples (see Tables I-V). In most of the tests, the LDH bag (ranging from 1g of LDH to 4g) removed 90 percent of bacteria from the 500 mL bottle of water (250 mL in Table I) in 30 min or less (see Tables I-V excluding IV, the Zn-Al LDH).

Make LDH bags by sewing a 5x10 cm piece of cloth with fishing wire with a measured amount of LDH inside (size 2.36-4.75mm). When finished, autoclave the bags at 122 degrees C for 15 min to sterilize. Prepare dilution test tubes by putting 9 mL of sterile tap water in each one. Centrifuge the bacterial TSB solution for 15 min at 3400 rpm, decant the broth, add sterile water in its place. Dilute the bacterial solution with 1/10 dilutions until desired concentration is obtained. (For this case, 500 mL of $\sim 10^2$ CFU/mL is desired for each bottle so take 5 mL of 10^4 solution in 495 mL of sterile tap water). Take reference samples of the solutions in each of the 500 mL bottles before the LDH bag is added. Plate 100 uL of each bottle (usually do triplicates) onto TSA petri dishes. Place the LDH bags inside of the bottles and start timing. Collect and plate 100 uL of each at desired times. Dip a glass spreader into alcohol, flame, let cool, and use to spread the 100 uL solution on each of the TSA petri dishes. Seal with parafilm, set aside until later to put in an incubator overnight at 35 degrees C. Count the colonies in the morning.

As can be easily understood from the foregoing, the basic concepts of the present invention may be embodied in a variety of ways. It involves both water and

air purification techniques as well as devices to accomplish the appropriate filter. In this application, the water and air purification techniques are disclosed as part of the results shown to be achieved by the various devices described and as steps which are inherent to utilization. They are simply the natural result of utilizing the devices as intended and described. In addition, while some devices are disclosed, it should be understood that these not only accomplish certain methods but also can be varied in a number of ways. Importantly, as to all of the foregoing, all of these facets should be understood to be encompassed by this disclosure.

The discussion included in this application is intended to serve as a basic description. The reader should be aware that the specific discussion may not explicitly describe all embodiments possible; many alternatives are implicit. It also may not fully explain the generic nature of the invention and may not explicitly show how each feature or element can actually be representative of a broader function or of a great variety of alternative or equivalent elements. Again, these are implicitly included in this disclosure. Where the invention is described in device-oriented terminology, each element of the device implicitly performs a function. Apparatus claims may not only be included for the device described, but also method or process claims may be included to address the functions the invention and each element performs. Neither the description nor the terminology is intended to limit the scope of the claims.

It should also be understood that a variety of changes may be made without departing from the essence of the invention. Such changes are also implicitly included in the description. They still fall within the scope of this invention. A broad disclosure encompassing both the explicit embodiment(s) shown, the great variety of implicit alternative embodiments, and the broad methods or processes and the like are encompassed by this disclosure. This application seeks examination of as broad a base of claims as deemed within the applicant's right and will be designed to yield a patent covering numerous aspects of the invention both independently and as an overall system.

Further, each of the various elements of the invention and claims may also be achieved in a variety of manners. This disclosure should be understood to encompass each such variation, be it a variation of an embodiment of any apparatus embodiment, a method or process embodiment, or even merely a variation of any element of these.

5 Particularly, it should be understood that as the disclosure relates to elements of the invention, the words for each element may be expressed by equivalent apparatus terms or method terms -- even if only the function or result is the same. Such equivalent, broader, or even more generic terms should be considered to be encompassed in the description of each element or action. Such terms can be

10 substituted where desired to make explicit the implicitly broad coverage to which this invention is entitled. As but one example, it should be understood that all actions may be expressed as a means for taking that action or as an element which causes that action. Similarly, each physical element disclosed should be understood to encompass a disclosure of the action which that physical element facilitates.

15 Regarding this last aspect, as but one example, the disclosure of a "sor bent" should be understood to encompass disclosure of the act of "sorbing" -- whether explicitly discussed or not -- and, conversely, were there effectively disclosure of the act of "sorbing", such a disclosure should be understood to encompass disclosure of a "sor bent" and even a "means for sorbing" Such changes and alternative terms are to

20 be understood to be explicitly included in the description.

U.S. PATENT DOCUMENTS

DOCUMENT NO	DATE	NAME	CLASS	SUBCLASS	FILING DATE
4,511,710	04/16/1985	Wang et al	528	485	06/11/1984
5,079,203	01/07/1992	Pinnavaia et al.	502	84	05/25/1990
5,114,898	05/19/1992	Pinnavaia et al.	502	406	09/28/1990
5,116,587	05/26/1992	Pinnavaia et al.	423	244	01/18/1990
5,358,701	10/25/1994	Pinnavaia et al.	423	242.1	11/16/1992
5,539,135	07/23/1996	Breuer et al.	554	167	04/04/1991
5,765,556	06/16/1998	Brunson	128	206.19	07/17/1995
6,055,982	05/02/2000	Brunson et al.	128	206.12	12/18/1997
6,329,515	12/11/2001	Choy et al.	536	23.1	09/10/1999
6,365,661	04/02/2002	Fischer et al.	524	445	01/09/1998
6,372,837	04/16/2002	Fischer et al.	524	445	01/09/1998

6,656,382	12/02/2003	Kuhlmann et al.	252	184	10/02/1998
-----------	------------	-----------------	-----	-----	------------

FOREIGN PATENT DOCUMENTS

DOCUMENT NO	DATE	COUNTRY	CLASS	SUBCLASS
JP 2000086694	28 Mar 2000	Japan	C07h	21/04
WO 00/09599	24 Feb 2000	PCT Application	C08K	3/22,7/22,9/04
WO 92/17405	15 Oct 1992	PCT Application	CO1F	7/00
WO 99/17879	15 Apr 1999	PCT Application	B01J	41/00

5

OTHER DOCUMENTS (Including Author, title, Date, Pertinent Pages, Etc.)

Brindley, G.W. and S. Kikkawa. 1980. Thermal-behavior of hydrotalcite and of anion-exchanged forms of hydrotalcite. <i>Clays Clay Miner.</i> 28: 87-91.
Cavani, F., F. Trifiro and A. Vaccari. 1991. Hydrotalcite-type anionic clay: Preparation, properties and application. <i>Catal. Today.</i> 11:73-301.
Cervilla, A., E. Llopis, A. Ribera, A. Corma, V. Fornes and F. Rey. 1994. Intercalation of the oxo-transfer molybdenum (VI) complex $[\text{MoO}_2\{\text{O}_2\text{CC}(\text{S})\text{Ph}_2\}_2]^{2-}$ into a zinc(II)-aluminium(III) layered double hydroxide host. Catalysis of the air oxidation of thiols. <i>J. Chem. Soc. Dalton. Trans.</i> 20:2953-2957.
Chibwe, M. and T.J. Pinnavaia. 1993. Stabilization of cobalt(II) phthalocyanine oxidation catalyst by intercalation in a layered double hydroxide host. <i>J. Chem. Soc. Commun.</i> 278-280.
Constantino, V.R.L. and T.J. Pinnavaia. 1995. Basic properties of $\text{Mg}^{2+}_{1-x}\text{Al}^{3+}_x$ layered double hydroxides intercalated by carbonate, hydroxide, chloride, and sulfate anions. <i>Inorg. Chem.</i> 34:883-892.
Gerba, C.P. and J. B. Rose. 1990. Viruses in source and drinking water. P. 380-396. In: G.A. McFeters (ed.), <i>Drinking water microbiology</i> . Springer, NY.
Goswamee, R.L., P. Sengupta, K.G. Bhattacharyya and D.K. Dutta. 1998. Adsorption of Cr(VI) in layered double hydroxides. <i>Appl. Clay Sci.</i> 13:21-34.
Hermosin M.C., I. Pavlovic, M.A. Ulibarri and J. Cornejo. 1993. Trichlorophenol adsorption on layered double hydroxide: a potential sorbent. <i>J. Envir. Sci. Health A28</i> :1875-1888.
Itaya, K., H.C. Chang and I. Uchida. 1987. Anion-exchange hydrotalcite-like-clay-modified electrodes. <i>Inorg. Chem.</i> 26:624-626.
Kang M.J., K.S. Chun, S.W. Rhee and Y. Do. 1999. Comparison of sorption behavior of I ⁻ and TcO_4^- on Mg/Al layered double hydroxide. <i>Radiochim. Acta.</i> 85:57-63.
Kang, M.J., S.W. Rhee and H. Moon. 1996. Sorption of MO_4^- (M = Tc, Re) on Mg/Al layered double hydroxide by anion exchange. <i>Radiochimica Acta.</i> 75:169-173.
Lal, M. and Howe, A.T., "Studies of zinc-chromium hydroxy salts. II. Composite anion conductors of pressed disks of $[\text{Zn}_2\text{Cr}(\text{OH})_6]\text{X} \cdot n\text{H}_2\text{O}$, Where $\text{X}^- = \text{F}^-, \text{Cl}^-, \text{Br}^-, \text{I}^-, \text{NO}_3^-, \text{and } 1/2\text{CO}_3^{2-}$.", <i>J. Solid State Chem</i> (1983)
Martin, K.J. and T.J. Pinnavaia. 1986. Layered double hydroxide as support anionic reagent. Halide ion reactivity in $[\text{Zn}_2\text{Cr}(\text{OH})_6]\text{X} \cdot n\text{H}_2\text{O}$. <i>J. Am. Chem. Soc.</i> 108:541-542.


Miyata, S., 1975. The syntheses of hydrotalcite-like compounds and their structures and physico-chemical properties - I: The system $Mg^{2+}-Al^{3+}-NO_3^-$, $Mg^{2+}-Al^{3+}-Cl^-$, $Mg^{2+}-Al^{3+}-ClO_4^-$, $Ni^{2+}-Al^{3+}-Cl^-$, and $Zn^{2+}-Al^{3+}-Cl^-$. <i>Clays Clay Miner.</i> 23:369-375.
Miyata, S., 1980. Physico-chemical properties of synthetic hydrotalcites in relation to composition. <i>Clays Clay Miner.</i> 28:50-55.
Miyata, S., 1983. Anion-exchange properties of hydrotalcite-like compounds. <i>Clays Clay Miner.</i> 31:305-311.
Park, Y., K. Kuroda and C. Kato. 1990. Direct synthesis of intercalation compounds between a layered double hydroxide and an anionic dye. <i>J. Chem. Soc. Dalton Trans.</i> 10:3071-3074.
Rhee, S.W., M.J. Kang, H. Kim and C.H. Moon. 1997. Removal of aquatic chromate ion involving rehydration reaction of calcined layered double hydroxide ($Mg-Al-CO_3$). <i>Environ. Tech.</i> 18:231-236.
Schmidt, P.C. and K. Beneke. 1988. Untersuchungen zur adsorption und stabilität von konservierungstoffen in antaciduspensionen. 2. Mitteilung: Reaktionskinetische stabilitätsuntersuchungen. <i>Pharm. Acta. Helv.</i> 63:188-196.
Suzuki, E., M. Okamoto and Y. Ono. 1989. Catalysis by interlayer anions of a synthetic hydrotalcite-like mineral in a halide exchange between organic halides. 1485-1486.
U.S. Environmental Protection Agency. National Primary Drinking Water Regulations: Ground Water Rule; Proposed Rules. 40 CFR Parts 141 and 142, 30194-30274, 2000.
You, Y.W., H.T. Zhao and G.F. Vance. 2002a. Hybrid organic-inorganic derivatives of layered double hydroxides and dodecylbenzenesulfonate: Preparation and sorption characteristics. <i>J. Mater. Chem.</i> 12: 907-912
You, Y.W., H.T. Zhao and G.F. Vance. 2002b. Surfactant-enhanced adsorption of organic compounds by layered double hydroxides. <i>Colloids Surface A.</i> 205: 161-172.
You, Y.W., H.T. Zhao and G.F. Vance. 2002c. Adsorption of dicamba (3,6 dichloro-2-methoxy benzoic acid) in aqueous solution by calcined-layered double hydroxide. <i>Applied Clay Science.</i> 21:217-226.
You, Y.W., G.F. Vance and H.T. Zhao. 2001a. Selenium adsorption on Mg-Al and Zn-Al layered double hydroxides. <i>Appl. Clay. Sci.</i> 20:13-25.
You, Y.W., H.T. Zhao and G.F. Vance. 2001b. Removal of arsenite from aqueous solution by anionic clays. <i>Environmental Technology.</i> 22:1447-1457.
United States Provisional Application No. 60/443,548, filed 01/28/2003

All patents, publications, or other references mentioned in this application for patent or listed in the above listing are hereby incorporated by reference. In addition, as to each term used it should be understood that unless its utilization in this application is inconsistent with such interpretation, common dictionary definitions should be understood as incorporated for each term and all definitions, alternative terms, and synonyms such as contained in the Random House Webster's Unabridged Dictionary, second edition are hereby incorporated by reference. Finally, as to all references listed or specifically mentioned, each is hereby appended and hereby incorporated by reference, however, as to each of the above, to the extent that such information or statements incorporated by reference might be considered inconsistent

with the patenting of this/these invention(s) such statements are expressly not to be considered as made by the applicant(s).


Thus, the applicant(s) should be understood to claim at least: i) each of the
5 LDH, lignan-LDH or modified LDH compositions as herein disclosed and described,
ii) the related utilities, processes, or methods disclosed and described, iii) similar,
equivalent, and even implicit variations of each of these devices and methods, iv)
those alternative designs which accomplish each of the functions shown as are
disclosed and described, v) those alternative designs and methods which accomplish
10 each of the functions shown as are implicit to accomplish that which is disclosed and
described, vi) each feature, component, and step shown as separate and independent
inventions, vii) the applications enhanced by the various systems or components
disclosed, viii) the resulting products produced by such systems or components, and
ix) methods and apparatuses substantially as described hereinbefore and with
15 reference to any of the accompanying examples, x) the various combinations and
permutations of each of the elements disclosed, and xi) each potentially dependent
claim or concept as a dependency on each and every one of the independent claims or
concepts presented.

EXHIBITS



5

10



Column Filtration of Bacteria and Viruses



Sample No.	LDH	Organism	Starting Conc. (cfu/ml, pfu/ml)	Final Conc. (cfu/ml, puf/ml)	Sorbed virus or E. coli	
	1Mg-Al	Phix-174		2575	419	83.73%
	2Zn-Al	Phix-174		2575	63	97.55%
	3Mg-Al	MS2		4230	0	100.00%
	4Zn-Al	MS2		4230	128	96.97%
	5Mg-Al	E. coli (ATCC13760)		1235	0	100.00%
	6Zn-Al	E. coli (ATCC13760)		1235	140	88.66%
	7Mg-Al	E. coli (ATCC 15597)		429	0	100.00%
	8Zn-Al	E. coli (ATCC 15597)		429	0	100.00%


5


Experiment conditions:**Temperature: 20 °C**

Background solution: Artificial Ground Water (CaCl₂ 0.075 mM, MgCl₂ 0.082 mM, KCl 0.051 mM and NaHCO₃ 1.5 mM)

pH: 7.5**Sorption time: instantaneously flow through**








Time
(min)

Percent
sorbance

	still (series 1, 590 CFU/mL)	shake (series 2, 280 CFU/mL)
1	35	28
5	64	0
10	84	82
15	96	75
20	91	89
30	100	96
40	100	100
50	88	92



Initial conc. stock
solution

Mg-AL LDH Sorption of Bacteria and Virus in Suspended Solutions

	replicate	Dilution	Count	Concentration (pfu/ml)	Ave. of Conc.(pfu/ml)
Phix-174	1	2	66	6600	5925
	2	2	63	6300	
	3	2	52	5200	
	4	2	56	5600	
MS2	1	2	92	9200	9100
	2	2	87	8700	
	3	2	95	9500	
	4	2	90	9000	
E. coli (ATCC 13706)	1	5	107	10700000	16300000
	2	5	161	16100000	
	3	5	196	19600000	
	4	5	188	18800000	
E. coli (ATCC 15597)	1	5	236	23600000	26225000
	2	5	260	26000000	
	3	5	266	26600000	
	4	5	287	28700000	

Replicates	Solution Volume (ml)	LDH conc. (ppm)	Dilutions	Plate Count	Final Conc (pfu/ml)	Sorbed virus or E. coli (pfu)	Ave. of Sorbed virus or E. coli (pfu)	Adsorption Efficiency	Mass of LDH sorbed (pfu/kg)
1	29	431	0	77	77	169592	169954.5	98.91%	13597447.8
			0	61	61	170056			
2	29	431	0	49	49	170404			
			0	71	71	169766			
1	29	431	0	1	1	171796	171781.5	99.97%	13743619.5
			0	2	2	171767			
2	29	431	0	1	1	171796			
			0	2	2	171767			
1	29	431	0	15	15	263465	263363.5	99.80%	21070765.7
			0	22	22	263262			
2	29	431	0	11	11	263581			
			0	26	26	263146			
1	29	431	0	14	14	263494	263631.75	99.90%	21092227.4
			0	9	9	263639			
2	29	431	0	8	8	263668			
			0	6	6	263726			
1	25	500	3	191	191000	395225000	395956250	99.01%	2.7307E+10
			3	199	199000	395025000			
2	25	500	3	84	84000	397900000			
			3	173	173000	395675000			
1	25	500	3	160	160000	396000000	396093750	99.04%	2.7317E+10
			3	149	149000	396275000			
2	25	500	3	148	148000	396300000			
			3	168	168000	395800000			
1	25	500	3	478	478000	638050000	641650000	98.73%	4.4252E+10
			3	452	452000	638700000			
2	25	500	3	224	224000	644400000			
			3	182	182000	645450000			
1	25	500	3	134	134000	646650000	646343750	99.44%	4.4575E+10
			3	149	149000	646275000			
2	25	500	3	146	146000	646350000			
			3	156	156000	646100000			

5x10 cm LDH bag, 5g , 10g Mg-Al (2:1) LDH

09/19/2003counted, 9/20/03

200 mL Laramie River water

starting bacterial solution: 94000
CFU/mL for 5g
82000 CFU/mL for
10g

		CFUs (5g)	10g
ref		smear, 93, 95	smear, 79, 85
	30	374	210
	30	481	228
	30	427	168
average CFU/MI		4273	2020

	Percent sorbance	
Time (min)	5g	10g
30	95	97

Table I: Mg-Al (2:1) LDH bag test (1g LDH in 250 mL sterile tap water with *Pseudomonas aeruginosa*)

Time (min)	Percent sorbance of bacteria	
	still (original concentration 590 CFU/mL)	shake (original concentration 280 CFU/mL)
1	35	28
5	64	0
10	84	82
15	96	75
20	91	89
30	100	96
40	100	100

Table II: Mg-Al (2:1) LDH bag test (1g LDH in 500 mL sterile tap water with *Pseudomonas aeruginosa*)

Time (min)	Percent sorbance of bacteria		
	A (original concentration 20 CFU/mL)	B (original concentration 30 CFU/mL)	C (original concentration 40 CFU/mL)
10	100	100	100
30	100	0	75
45	100	33	100
60	100	100	100

Table III: Mg-Al (2:1) LDH bag test (1g, 2g, 4g LDH in 500 mL sterile tap water with *Pseudomonas aeruginosa*)

Time (min)	Percent sorbance		
	1g (original conc. 1560+ CFU/mL)	2g (original conc. 1060+ CFU/mL)	4g (original conc. 1890+ CFU/mL)
5	58	58	35
15	74	83	77
30	87	94	78

Table IV: Zn-Al (2:1) LDH bag test (1g, 2g, 4g LDH in 500 mL sterile tap water with *Pseudomonas aeruginosa*)

Time (min)	Percent sorbance		
	1g (original conc. 2180+ CFU/mL)	2g (original conc. 1780+ CFU/mL)	4g (original conc. 167+ CFU/mL)
5	0	0.56	0.59
15	0	57	24
30	42	81	0

Table V: Mg-Al (2:1) LDH bag test (1.5g LDH in 500 mL sterile tap water with *Pseudomonas aeruginosa*) starting bacterial conc. 96 CFU/mL

Percent sorbance

Time (min)	still	swirl every 6 min for 30 sec	upside down, right side up every 6 min for 30 sec
30	100	100	100
30	93	100	100

VII. CLAIMS

What is claimed is:

- 5 1. A method of removing impurities comprising the steps of:
 establishing an amount of water;
 containing an amount of cationic composition;
 moving at least some of said water in the vicinity of said cationic
 composition;
 10 attracting a first component to said cationic composition;
 sorbing at least some of said first component on said cationic
 composition;
 containing an amount of anionic composition;
 moving at least some of said water in the vicinity of said anionic
 15 composition;
 attracting a second component to said anionic composition;
 sorbing at least some of said second component on said anionic
 composition; and
 moving said water with at least some reduction of said first and second
 20 components.
2. A method of removing impurities of claim 1 wherein said step of
 containing an amount of cationic composition comprises the step of
 containing an amount of layered double hydroxide composition.
- 25 3. A method of removing impurities of claim 2 wherein said step of
 containing said amount of layered double hydroxide composition
 comprises the step of containing an amount of layered double
 hydroxide composition represented by the formula:
 30
$$[M^{II}_{1-x}M^{III}_x(OH)_2]^{z+}A^{n-}_{z/n} \cdot yH_2O,$$
 wherein M^{II} is a bivalent cation, M^{III} is a trivalent cation, and A^{n-} is an
 anion bound in an intermediate layer.
- 35 4. A method of removing impurities of claim 1 wherein said step of
 moving said water comprises the step of mechanically moving said
 water.
- 40 5. A method of removing impurities of claim 1 wherein said step of
 moving said water comprises the step of physically moving said water.
6. A method of removing impurities of claim 1 or 2 wherein said step of
 attracting and sorbing said first component on said cationic
 45 composition comprises the step of attracting and sorbing a first
 component selected from the group consisting of an anionic
 contaminant, a biological agent, inorganic anionic contaminant,

organic anionic contaminant, bacteria, hormone, fungi, virus, prions, proteins, nucleic acids, MS2 virus, Phi-X 174, Escherichia coli strains, and Pseudomonas aruginosa.

- 5 7. A method of removing impurities of claim 2 and further comprising the step of sorbing said first component on a surface of a layered hydroxide composition.
- 10 8. A method of removing impurities of claim 1 or 6 wherein said step of containing said amount of said anionic composition comprises the step of containing an amount of lignin.
- 15 9. A method of removing impurities of claim 8 and further comprising the step of functionally situating said cationic composition with said lignin.
- 20 10. A method of removing impurities of claim 9 wherein said step of functionally situating said cationic composition with said lignin comprises the step of separately and distinctly situating said cationic composition from said lignin.
- 25 11. A method of removing impurities of claim 9 or 10 wherein said step of functionally situating said cationic composition with said lignin comprises the step of layering said lignin and said cationic composition.
- 30 12. A method of removing impurities of claim 9 wherein said step of functionally situating cationic composition with said lignin comprises the step of chemically associating said cationic composition with said lignin.
- 35 13. A method of removing impurities of claim 8 or 9 and further comprising the step of removing said first component with reactivated cationic composition.
- 40 14. A method of removing impurities of claim 13 wherein said step of removing said cationic composition comprises the steps of:
calcinating said cationic composition;
removing said first component from said cationic composition; and
rehydrating said calcinated cationic composition.
- 45 15. A method of removing impurities of claim 1 or 13 and further comprising the steps of:
detecting said first component sorbed on said cationic composition;
and
identifying said first component.

16. A method of removing impurities of claim 1, 6 or 9 wherein said step of establishing said water comprises the step of establishing an amount of raw water.
- 5 17. A method of removing impurities of claim 1, 6 or 9 wherein said step of establishing said water comprises the step of establishing an amount of primarily treated water.
- 10 18. A method of removing impurities of claim 1 wherein said step of containing said amount of cationic composition and containing said amount of anionic composition comprises the step of containing said cationic composition and said anionic composition in a water treatment apparatus.
- 15 19. A method of removing impurities of claim 18 and further comprising the steps of:
attaching said water treatment apparatus to a plumbing system; and
running water through said water treatment apparatus.
- 20 20. A method of removing impurities of claim 18 and further comprising the step of portably using said water treatment apparatus.
- 25 21. A method of removing impurities of claim 1 wherein said step of containing said amount of cationic composition and containing said amount of anionic composition comprises the step of containing said cationic composition and said anionic composition in a disposable semipermeable unit.
- 30 22. A method of removing impurities of claim 21 and further comprising the step of placing said disposable semipermeable unit in said water.
23. A method of removing impurities of claim 22 and further comprising the step of manually handling said disposable semipermeable unit.
- 35 24. A method of removing impurities of claim 1 wherein said step of containing an amount of cationic composition comprises the step of providing an unpowered charged sorbent medium.
- 40 25. A method of removing impurities comprising the steps of:
establishing an amount of water;
providing an unpowered charged sorbent medium;
moving at least some of said water in the vicinity of said unpowered charged sorbent medium;
attracting a biological agent to said unpowered charged sorbent medium;
45 sorbing at least some of said biological agent on the surface of said unpowered charged sorbent medium; and
moving said water with at least some reduction of said biological agent.

26. A method of removing impurities of claim 25 wherein said step of providing said unpowered charged sorbent medium comprises the step of providing an cationic component.
27. A method of removing impurities of claim 25 wherein said step of providing said unpowered charged sorbent medium comprises the step of providing an anionic component.
28. A method of removing impurities of claim 25 wherein said step of providing said unpowered charged sorbent medium comprises the step of providing a layered double hydroxide composition.
29. A method of removing impurities of claim 28 wherein said step of providing said layered double hydroxide composition comprises the step of providing said layered double hydroxide composition represented by the formula:
- $$[M^{II}_{1-x}M^{III}_x(OH)_2]^{z+}A^{n-}_{z/n} \cdot yH_2O,$$
- wherein M^{II} is a bivalent cation, M^{III} is a trivalent cation, and A^{n-} is an anion bound in an intermediate layer.
30. A method of removing impurities of claim 25 wherein said step of moving at least some of said water in the vicinity of said unpowered charged sorbent medium comprises the step of mechanically moving at least some of said water in the vicinity of said unpowered charged sorbent medium.
31. A method of removing impurities of claim 25 wherein said step of moving at least some of said water in the vicinity of said unpowered charged sorbent medium comprises the step of physically moving at least some of said water in the vicinity of said unpowered charged sorbent medium.
32. A method of removing impurities of claim 25 or 28 and further comprising the steps of:
 containing an amount of lignin;
 moving at least some of said water in the vicinity of said lignin;
 attracting an cationic contaminant to said lignin;
 sorbing said cationic contaminant on said lignin; and
 moving said water with at least some reduction of said cationic contaminant.
33. A method of removing impurities of claim 32 and further comprising the step of functionally situating said unpowered charged sorbent medium with said lignin.


34. A method of removing impurities of claim 33 wherein said step of functionally situating said unpowered charged sorbent medium with said lignin comprises the step of separately and distinctly situating said unpowered charged sorbent medium from said lignin.
- 5 35. A method of removing impurities of claim 33 wherein said step of functionally situating said unpowered charged sorbent medium with said lignin comprises the step of layering said unpowered charged sorbent medium and said lignin.
- 10 36. A method of removing impurities of claim 33 wherein said step of functionally situating said unpowered charged sorbent medium with said lignin comprises the step of chemically associating said unpowered charged sorbent medium and said lignin.
- 15 37. A method of removing impurities of claim 25 or 33 wherein said step of establishing said water comprises the step of establishing an amount of raw water.
- 20 38. A method of removing impurities of claim 25 or 33 wherein said step of establishing said water comprises the step of establishing an amount of primarily treated water.
- 25 39. A method of removing impurities of claim 25 wherein said step of providing said unpowered charged sorbent medium comprises the step of providing a water treatment apparatus.
- 30 40. A method of removing impurities of claim 39 and further comprising the steps of:
attaching said water treatment apparatus to a plumbing system; and
running water through said water treatment apparatus.
- 35 41. A method of removing impurities of claim 39 and further comprising the step of portably using said water treatment apparatus.
- 40 42. A method of removing impurities of claim 25 wherein said step of providing said unpowered charged sorbent medium comprises the step of providing a disposable semipermeable unit.
43. A method of removing impurities of claim 42 and further comprising the step of placing said disposable semipermeable unit in said water.
44. A method of removing impurities of claim 43 and further comprising the step of manually handling said disposable semipermeable unit.
- 45 45. A method of removing impurities comprising the steps of:
establishing an amount of water;
containing an amount of layered double hydroxide composition;

- moving at least some of said water in the vicinity of said layered double hydroxide composition;
 attracting a first component to said layered double hydroxide composition;
 5 sorbing at least some of said first component on said layered double hydroxide composition;
 containing an amount of lignin;
 moving at least some of said water in the vicinity of said lignin;
 attracting a second component to said lignin;
 10 sorbing at least some of said second component on said lignin; and
 moving said water with at least some reduction of said first and second components.
46. A method of removing impurities of claim 45 wherein said step of
 15 containing said amount of layered double hydroxide composition comprises the step of containing an amount of layered double hydroxide composition represented by the formula:
- $$[M^{II}_{1-x}M^{III}_x(OH)_2]^{z+}A^{n-}_{z/n} \cdot yH_2O,$$
- 20 wherein M^{II} is a bivalent cation, M^{III} is a trivalent cation, and A^{n-} is an anion bound in an intermediate layer.
47. A method of removing impurities of claim 45 wherein said step of
 25 moving said water comprises the step of mechanically moving said water.
48. A method of removing impurities of claim 45 wherein said step of
 30 moving said water comprises the step of physically moving said water.
49. A method of removing impurities of claim 45 or 46 wherein said step
 of attracting and sorbing said first component on said layered double
 hydroxide composition comprises the step of attracting and sorbing a
 35 first component selected from the group consisting of an anionic
 contaminant, a biological agent, inorganic anionic contaminant,
 organic anionic contaminant, bacteria, hormone, fungi, virus, prions,
 proteins, nucleic acids, MS2 virus, Phi-X 174, Escherichia coli strains,
 and Pseudomonas aruginosa.
- 40 50. A method of removing impurities of claim 45 or 49 wherein said step
 of sorbing at least some of said first component on said layered double
 hydroxide composition comprises the step of sorbing said first
 component on a surface of said layered double hydroxide composition.
- 45 51. A method of removing impurities of claim 45 and further comprising
 the step of functionally situating said layered double hydroxide
 composition with said lignin.

52. A method of removing impurities of claim 51 wherein said step of functionally situating said layered double hydroxide composition with said lignin comprises the step of separately and distinctly situating said double layered hydroxide composition from said lignin.
53. A method of removing impurities of claim 51 or 52 wherein said step of functionally situating said layered double hydroxide composition with said lignin comprises the step of layering said lignin and said layered double hydroxide composition.
54. A method of removing impurities of claim 51 wherein said step of functionally situating said layered double hydroxide composition with said lignin comprises the step of chemically associating said layered double hydroxide composition with said lignin.
55. A method of removing impurities of claim 45 or 51 and further comprising the step of removing said first component with reactivated layered double hydroxide composition.
56. A method of removing impurities of claim 55 wherein said step of removing said layered double hydroxide composition comprises the steps of:
calcinating said layered double hydroxide composition;
removing said first component from said layered double hydroxide composition; and
rehydrating said calcinated layered double hydroxide composition.
57. A method of removing impurities of claim 45 or 55 and further comprising the steps of:
detecting said first component sorbed on said layered double hydroxide composition; and
identifying said first component.
58. A method of removing impurities of claim 45, 49 or 51 wherein said step of establishing said water comprises the step of establishing an amount of raw water.
59. A method of removing impurities of claim 45, 49 or 51 wherein said step of establishing said water comprises the step of establishing an amount of primarily treated water.
60. A method of removing impurities of claim 45 wherein said step of containing said amount of layered double hydroxide composition and containing said amount of lignin comprises the step of containing said layered double hydroxide composition and said lignin in a water treatment apparatus.
61. A method of removing impurities of claim 60 and further comprising the steps of:

attaching said water treatment apparatus to a plumbing system; and
running water through said water treatment apparatus.

- 5 62. A method of removing impurities of claim 60 and further comprising
the step of portably using said water treatment apparatus.
- 10 63. A method of removing impurities of claim 45 wherein said step of
containing said amount of layered double hydroxide composition and
containing said amount of lignin comprises the step of containing said
layered double hydroxide composition and said lignin in a disposable
semipermeable unit.
- 15 64. A method of removing impurities of claim 63 and further comprising
the step of placing said disposable semipermeable unit in said water.
- 20 65. A method of removing impurities of claim 64 and further comprising
the step of manually handling said disposable semipermeable unit.
- 25 66. A method of removing impurities of claim 45 wherein said step of
containing an amount of layered double hydroxide composition
comprises the step of providing an unpowered charged sorbent
medium.
- 30 67. A method for removal of impurities comprising the steps of:
establishing an amount of water;
containing an amount of layered double hydroxide composition in a
water treatment apparatus;
moving at least some of said water in the vicinity of said layered
double hydroxide composition;
35 attracting a biological agent to said layered double hydroxide
composition;
sorbing at least some of said biological agent on a surface of said
layered double hydroxide composition;
moving said water with at least some reduction of said biological
agent.
- 40 68. A method for removal of impurities of claim 67 wherein said step of
containing said amount of layered double hydroxide composition in
said water treatment apparatus comprises the step of containing an
amount of cationic composition in a water treatment apparatus.
- 45 69. A method for removal of impurities of claim 67 wherein said step of
containing an amount of layered double hydroxide composition in a
water treatment apparatus comprises the step of containing an amount
of layered double hydroxide composition represented by the formula:



wherein M^{II} is a bivalent cation, M^{III} is a trivalent cation, and A^{n-} is an anion bound in an intermediate layer.

- 5 70. A method for removal of impurities of claim 67 wherein said step of moving said water comprises the step of mechanically moving said water.
- 10 71. A method for removal of impurities of claim 67 wherein said step of moving said water comprises the step of physically moving said water.
- 15 72. A method for removal of impurities of claim 67 and further comprising the steps of:
containing an amount of lignin in said water treatment apparatus;
moving at least some of said water in the vicinity of said amount of lignin;
attracting a cationic contaminant to said amount of lignin;
sorbing at least some of said cationic contaminant on said amount of lignin; and
20 moving said water with at least some reduction of said cationic contaminant.
- 25 73. A method for removal of impurities of claim 72 wherein said step of containing said amount of lignin in said water treatment apparatus comprises the step of containing an amount of anionic composition in said water treatment apparatus.
- 30 74. A method for removal of impurities of claim 72 and further comprising the step of functionally situating said layered double hydroxide composition with said lignin.
- 35 75. A method for removal of impurities of claim 74 wherein said step of functionally situating said layered double hydroxide composition with said lignin comprises the step of separately and distinctly situating said double layered hydroxide composition from said lignin.
- 40 76. A method for removal of impurities of claim 74 wherein said step of functionally situating said layered double hydroxide composition with said lignin comprises the step of layering said lignin and said layered double hydroxide composition.
- 45 77. A method for removal of impurities of claim 74 wherein said step of functionally situating said layered double hydroxide composition with said lignin comprises the step of chemically associating said layered double hydroxide composition with said lignin.
78. A method for removal of impurities of claim 67, 72 or 74 wherein said step of establishing an amount of water comprises the step of establishing an amount of raw water.

79. A method for removal of impurities of claim 67, 72 or 74 wherein said step of establishing an amount of water comprises the step of establishing an amount of primarily treated water.
- 5 80. A method for removal of impurities of claim 67 and further comprising the steps of:
attaching said water treatment apparatus to a plumbing system; and
running water through said water treatment apparatus.
- 10 81. A method for removal of impurities of claim 67 and further comprising the step of portably using said water treatment apparatus.
82. A method for removal of impurities of claim 67 or 72 wherein said
15 step of containing an amount of layered double hydroxide composition in a water treatment apparatus comprises the step of containing said amount of layered double hydroxide composition in a disposable semipermeable unit.
83. A method for removal of impurities of claim 82 and further comprising
20 the step of placing said disposable semipermeable unit in said water.
84. A method for removal of impurities of claim 82 and further comprising the step of manually handling said disposable semipermeable unit.
- 25 85. A method for removal of impurities of claim 67 wherein said step of containing said amount of layered double hydroxide composition in said water treatment apparatus comprises the step of containing an unpowered charged sorbent medium in said water treatment apparatus.
- 30 86. A method as described in claim 3, 29, 46 or 67 wherein said M^{II} is selected from the group consisting of Ca^{2+} , Mg^{2+} , Zn^{2+} , Co^{2+} , Ni^{2+} , Cu^{2+} and Mn^{2+} .
87. A method as described in claim 3, 29, 46 or 69 wherein said M^{III} is
35 selected from the group consisting of Al^{3+} , Cr^{3+} , Fe^{3+} , Co^{3+} and Mn^{3+} .
88. A method as described in claim 3, 29, 46 or 69 wherein said A^{n-} is selected from the group consisting of Cl^- , NO_3^- , ClO_4^- , CO_3^{2-} and SO_4^{2-} .
- 40 89. A method as described in claim 8, 32, 45 or 72 wherein said step of containing said lignin comprises the step of containing a lignin-dominated substance.
- 45 90. A method as described in claim 25 or 67 wherein said biological agent is selected from the group consisting of virus, bacteria, hormone, fungi, prions, proteins, nucleic acids, MS2 virus, Phi-X 174, Escherichia coli strains and Pseudomonas aeruginosa.

91. A method as described in claim 32 or 72 wherein said cationic contaminant is selected from the group consisting of lead, chromium, zinc, mercury, ammonium, sodium, calcium, iron and copper.
- 5 92. A method as described in claim 1 or 45 wherein said second component is selected from the group consisting of cationic contaminants, lead, chromium, zinc, mercury, ammonium, sodium, calcium, iron and copper.
- 10 93. A method as described in claim 12, 36, 54 or 77 wherein said step of chemically associating said layered double hydroxide composition with said lignin comprises the step of selecting a chemical association from the group consisting of ionic bonds, covalent bonds, tether molecule and hydrophobic interaction.
- 15 94. A method as described in claim 1, 25, 45 or 67 wherein said step of moving said water comprises the step of removing a percentage biological agent reduction amount selected from the group consisting of:
- 20
 - about 85% biological agent reduction
 - about 90% biological agent reduction; and
 - about 95% biological agent reduction.
- 25 95. A method as described in claim 1, 25, 45 or 67 wherein said step of moving said water comprises the step of removing a percentage biological agent reduction amount selected from the group consisting of:
- 30
 - about 70% biological agent reduction;
 - about 75% biological agent reduction;
 - about 80% biological agent reduction;
 - about 85% biological agent reduction;
 - about 90% biological agent reduction;
 - about 95% biological agent reduction; and
 - 35 - about 100% biological agent reduction.
- 40 96. A method as described in claim 1, 32, 45 or 67 wherein said step of moving said water with at least some reduction of said cationic contaminant comprises the step removing a percentage cationic contaminant reduction amount selected from the group consisting of:
- 45
 - about 80% cationic contaminant reduction;
 - about 85% cationic contaminant reduction;
 - about 90% cationic contaminant reduction; and
 - about 95% cationic contaminant reduction.
97. A method as described in claim 28 or 67 and further comprising the step of removing said biological agent with reactivated layered double hydroxide composition.

98. A method of removing impurities of claim 97 wherein said step of removing said layered double hydroxide composition comprises the steps of:
5 calcinating said layered double hydroxide composition;
 removing said biological agent from said layered double hydroxide composition; and
 rehydrating said calcinated layered double hydroxide composition.
- 10 99. A method as described in claim 25 or 67 and further comprising the steps of:
 detecting said biological agent sorbed on said layered double hydroxide composition; and
 identifying said biological agent.
- 15 100. A method as described in claim 1, 8, 25, 32, 45, 67 or 77 and further comprising the steps of:
 containing an amount of organic composition;
 moving said water in the vicinity of said organic composition;
20 sorbing at least some of a non-ionic organic contaminant on said organic composition; and
 moving said water with at least some reduction of said non-ionic organic contaminant.
- 25 101. A method as described in claim 100 wherein said step of sorbing at least some of said non-ionic organic contaminant comprises the step of selecting said non-ionic organic contaminant from the group consisting of benzene, ethylbenzene, toluene, xylenes, aromatic compounds, perchloroethene, trichloroethene and dichloroethene.
- 30 102. A method as described in claim 100 wherein said step of sorbing at least some of said non-ionic organic contaminant comprises the step of removing a percentage non-ionic organic contaminant reduction amount selected from the group consisting of:
35 - about 70 % non-ionic contaminant reduction;
 - about 75 % non-ionic contaminant reduction;
 - about 80 % non-ionic contaminant reduction;
 - about 85 % non-ionic contaminant reduction; and
 - about 90 % non-ionic contaminant reduction;
- 40 103. A method as described in claim 10, 39, 60 or 67 wherein said water treatment apparatus is selected from the group consisting of batch process containers, flow through containers, coated sand columns, columns, bags, tubes, coating support, and filters.
- 45 104. A method as described in claim 1, 25, 45 or 67 and further comprising the step of removing nanostructural components.
105. A method as described in claim 1, 25, 45 or 67 and further comprising the steps of:

moving at least some of said water through a primary medium; and preventing at least some of a component of said water from moving through said primary medium.


- 5 106. A porous support medium comprising:
a water filter;
a layered double hydroxide composition on said water filter; and
biological agents substantially sorbed on a surface of said layered
double hydroxide composition.
- 10 107. A porous support medium of claim 106 wherein said biological agents
substantially sorbed on a surface of said layered double hydroxide
composition comprises percentage sorbent value selected from the
group consisting of:
15 - about 60%;
 - about 75%;
 - about 85%; and
 - about 95%.
- 20 108. A porous support medium of claim 106 wherein said layered double
hydroxide composition is represented by the formula:
$$[M^{II}_{1-x}M^{III}_x(OH)_2]^{z+}A^{n-}_{z/n} \cdot yH_2O,$$

25 wherein M^{II} is a bivalent cation, M^{III} is a trivalent cation, and A^{n-} is an
anion bound in an intermediate layer.
109. A porous support medium of claim 106 and further comprising amount
of lignin.
- 30 110. A porous support medium of claim 106 or 109 wherein said layered
double hydroxide composition comprises an anionic contaminant
sorbent.
- 35 111. A porous support medium of claim 109 wherein said lignin comprises
a cationic contaminant sorbent.
112. A porous support medium of claim 109 wherein said layered double
hydroxide composition is separate and distinct from lignin.
- 40 113. A porous support medium of claim 109 or 112 wherein said layered
double hydroxide composition and said lignin comprises layers of
layered double hydroxide composition and lignin.
- 45 114. A porous support medium of claim 109 wherein said layered double
hydroxide composition and said lignin comprises a chemical mixture
of layered double hydroxide composition and lignin.

115. A porous support medium of claim 106 wherein said water filter comprises a disposable semipermeable unit.
- 5 116. A porous support medium of claim 106 and further comprising a water outlet attachment.
117. A porous support medium of claim 106 wherein said water filter comprises a high volume water filter.
- 10 118. An apparatus as described in claim 106 wherein said M^{II} is selected from the group consisting of Ca^{2+} , Mg^{2+} , Zn^{2+} , Co^{2+} , Ni^{2+} , Cu^{2+} and Mn^{2+} .
- 15 119. An apparatus as described in claim 106 wherein said M^{III} is selected from the group consisting of Al^{3+} , Cr^{3+} , Fe^{3+} , Co^{3+} and Mn^{3+} .
120. An apparatus as described in claim 106 wherein said A^{n-} is selected from the group consisting of Cl^- , NO_3^- , ClO_4^- , CO_3^{2-} and SO_4^{2-} .
- 20 121. An apparatus as described in claim 109 wherein said lignin comprises a lignin-dominated substance.
- 25 122. An apparatus as described in claim 110 wherein said anionic contaminant sorbent is selected from the group consisting of a biological agent sorbent, an inorganic anionic contaminant sorbent, organic anionic contaminant sorbent, a virus sorbent, a bacteria sorbent, a fungi sorbent, a hormone sorbent, MS2 virus sorbent, a prion sorbent, a protein sorbent, a nucleic acid sorbent, Phi-X 174 sorbent, Escherichia coli strain sorbent, and Pseudomonas aeruginosa sorbent.
- 30 123. An apparatus as described in claim 111 wherein said cationic contaminant sorbent is selected from the group consisting of a lead sorbent, a chromium sorbent, a zinc sorbent, a mercury sorbent, an ammonium sorbent, a sodium sorbent, a calcium sorbent, an iron sorbent and a copper sorbent.
- 35 124. An apparatus as described in claim 114 wherein said chemical mixture is selected from the group consisting of ionic bonds, covalent bonds, tether molecules, and hydrophobic interaction.
- 40 125. An apparatus as described in claim 106 and further comprising a reactivation element.
- 45 126. An apparatus as described in claim 106 and further comprising a biological agent identification element.
127. An apparatus as described in claim 106 or 109 and further comprising an amount of organic composition.

128. An apparatus as described in claim 127 wherein said organic composition comprises a non-ionic organic contaminant sorbent.
- 5 129. An apparatus as described in claim 128 wherein said non-ionic organic contaminant sorbent is selected from the group consisting of a benzene sorbent, an ethylbenzene sorbent, a toluene sorbent, a xylene sorbent, an aromatic compound sorbent, a perchloroethene sorbent, a trichloroethene sorbent and a dichloroethene sorbent.
- 10 130. An apparatus as described in claim 106 wherein said water filter is selected from the group consisting of batch process containers, flow through containers, coated sand columns, columns, bags, tubes, coating support, and filters.
- 15 131. An apparatus as described in claim 106 and further comprising a circulation element.
- 20 132. An apparatus as described in claim 106 and further comprising a primary filter.

1/11

**Fig. 1**

2/11







Fig. 2

3/11

**Fig. 3**

4/11

**Fig. 4**

5/11




Fig. 5





Fig. 6

7/11

**Fig. 7**





Fig. 8

9/11

**Fig. 9**

11/11




Fig. 11

INTERNATIONAL SEARCH REPORT

International application No.

PCT/US04/02373

A. CLASSIFICATION OF SUBJECT MATTER

IPC(7) : C02F 01/42

US CL : 210/686

According to International Patent Classification (IPC) or to both national classification and IPC

B. FIELDS SEARCHED

Minimum documentation searched (classification system followed by classification symbols)

U.S. : 210/682-686,264,266,283,284,290,193,662,670,269,777,778; 502/414-417

Documentation searched other than minimum documentation to the extent that such documents are included in the fields searched

Electronic data base consulted during the international search (name of data base and, where practicable, search terms used)

C. DOCUMENTS CONSIDERED TO BE RELEVANT

Category *	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
A	US 6,479,024 A (O'HARE et al) 12 November 2002, see entire document.	1-132
A	US 4,752,397 A (SOOD et al) 21 June 1988, see entire document.	1-132
A	US 4,642,193 A (MIYATA et al) 10 February 1987, see entire document.	1-132
X	US 4,458,030 A (MANABE et al) 3 July 1984, see entire document.	1-132



Further documents are listed in the continuation of Box C.



See patent family annex.

* Special categories of cited documents:	
"A" document defining the general state of the art which is not considered to be of particular relevance	"T" later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the invention
"E" earlier application or patent published on or after the international filing date	"X" document of particular relevance; the claimed invention cannot be considered novel or cannot be considered to involve an inventive step when the document is taken alone
"L" document which may throw doubts on priority claim(s) or which is cited to establish the publication date of another citation or other special reason (as specified)	"Y" document of particular relevance; the claimed invention cannot be considered to involve an inventive step when the document is combined with one or more other such documents, such combination being obvious to a person skilled in the art
"O" document referring to an oral disclosure, use, exhibition or other means	"&" document member of the same patent family
"P" document published prior to the international filing date but later than the priority date claimed	

Date of the actual completion of the international search

12 November 2004 (12.11.2004)

Date of mailing of the international search report

23 NOV 2004

Name and mailing address of the ISA/US

Mail Stop PCT, Attn: ISA/US
Commissioner for Patents
P.O. Box 1450
Alexandria, Virginia 22313-1450

Facsimile No. (703) 305-3230

Authorized officer

Joseph W. Drodge

Telephone No. 571-272-1700

J. Whitfield
For