



US 20170146261A1

(19) **United States**(12) **Patent Application Publication**
Rogers et al.(10) **Pub. No.: US 2017/0146261 A1**(43) **Pub. Date: May 25, 2017**(54) **FLEXIBLE FUNCTIONALITY
PARTITIONING WITHIN
INTELLIGENT-THERMOSTAT-CONTROLLED
HVAC SYSTEMS**(71) Applicant: **Google Inc.**, Mountain View, CA (US)(72) Inventors: **Matthew Lee Rogers**, Los Gatos, CA (US); **Anthony Michael Fadell**, Portola Valley, CA (US); **Erik Charlton**, Palo Alto, CA (US); **Shigefumi Honjo**, Santa Cruz, CA (US); **Yoky Matsuoka**, Palo Alto, CA (US); **David Sloo**, Menlo Park, CA (US); **Isabel Thornton**, Housatonic, MA (US)(73) Assignee: **Google Inc.**, Mountain View, CA (US)(21) Appl. No.: **15/366,974**(22) Filed: **Dec. 1, 2016****Related U.S. Application Data**


- (63) Continuation of application No. 13/988,435, filed on Sep. 9, 2013, now Pat. No. 9,513,642, filed as application No. PCT/US12/00007 on Jan. 3, 2012.
- (60) Provisional application No. 61/415,771, filed on Nov. 19, 2010, provisional application No. 61/429,093, filed on Dec. 31, 2010, provisional application No. 61/627,996, filed on Oct. 21, 2011.

Publication Classification

- (51) **Int. Cl.**
F24F 11/00 (2006.01)
G05B 15/02 (2006.01)
G05D 23/19 (2006.01)
- (52) **U.S. Cl.**
CPC **F24F 11/0012** (2013.01); **F24F 11/0034** (2013.01); **F24F 11/006** (2013.01); **F24F 11/0086** (2013.01); **G05D 23/1917** (2013.01); **G05B 15/02** (2013.01); **F24F 2011/0035** (2013.01); **F24F 2011/0063** (2013.01); **F24F 2011/0071** (2013.01); **F24F 2011/0091** (2013.01); **G05B 2219/2614** (2013.01); **G05B 2219/25419** (2013.01)

(57) **ABSTRACT**

The current application is directed to an intelligent-thermostat-controlled environmental-conditioning system in which computational tasks and subcomponents with associated intelligent-thermostat functionalities are distributed to one or more of concealed and visible portions of one or more intelligent thermostats and, in certain implementations, to one or more intermediate boxes. The intelligent thermostats are interconnected to intermediate boxes by wired and/or wireless interfaces and intelligent thermostats intercommunicate with one another by wireless communications. wireless communications include communications through a local router and an ISP, 3G and 4G wireless communications through a mobile service provider. Components of the intelligent-thermostat-controlled environmental-conditioning system may also be connected by wireless communications to remote computing facilities.






FIG. 1A




FIG. 1B

FIG. 1C




FIG. 2A




FIG. 2B




FIG. 3A




FIG. 3B




FIG. 3C



FIG. 3D




FIG. 3E




FIG. 3F



FIG. 3G




FIG. 3H




FIG. 3I




FIG. 3J



FIG. 3K




FIG. 4




FIG. 5A




FIG. 5B



FIG. 6A




FIG. 6B







FIG. 6C






FIG. 10A




FIG. 10B




FIG. 10C





FIG. 10D






FIG. 11




FIG. 12




FIG. 13A




FIG. 13B




FIG. 14A




FIG. 14B




FIG. 15A




FIG. 15B




FIG. 15C




FIG. 15D

FIG. 16A




FIG. 16B










FIG. 16C






NEW "TUNED" NORMAL SETPOINT SCHEDULE (FOR ALL FOLLOWING WEDNESDAYS)

FIG. 16D










FIG. 19A




FIG. 19B




FIG. 20A




FIG. 20B




FIG. 21A




FIG. 21B




FIG. 22A




FIG. 22B




FIG. 23




FIG. 24




FIG. 25




FIG. 26A




FIG. 26B




FIG. 26C




FIG. 27




FIG. 28




FIG. 29




FIG. 30A








FIG. 30B






FIG. 32




FIG. 33A




FIG. 33B




FIG. 33C




FIG. 34




FIG. 35A




FIG. 35B







FIG. 36A











FIG. 36E







FIG. 36G






FIG. 37

FLEXIBLE FUNCTIONALITY PARTITIONING WITHIN INTELLIGENT-THERMOSTAT-CONTROLLED HVAC SYSTEMS

[0001] This application is a continuation of U.S. Non-Provisional Ser. No. 13/988,435 filed Sep. 9, 2013, which is an U.S. National Stage Application of PCT/US12/00007, filed Jan. 3, 2013, which claims the benefit of U.S. Provisional Application Ser. No. 61/415,771 filed 19 Nov. 2010, U.S. Provisional Application Ser. No. 61/429,093 filed 31 Dec. 2010, and U.S. Provisional Application Ser. No. 61/627,996 filed 21 Oct. 2011, the entire disclosures of which are hereby incorporated by reference, for all purposes, as if fully set forth herein.

FIELD

[0002] The current patent relates to intelligent-thermostat-controlled HVAC systems and other intelligently controlled environment-conditioning systems and, in particular, to intelligently controlled environment-conditioning systems in which intelligent-thermostat subcomponents and associated functionalities can be variously distributed among concealed and visible portions on intelligent thermostats to produce numerous implementations.

BACKGROUND AND SUMMARY

[0003] While substantial effort and attention continues toward the development of newer and more sustainable energy supplies, the conservation of energy by increased energy efficiency remains crucial to the world's energy future. According to an October 2010 report from the U.S. Department of Energy, heating and cooling account for 56% of the energy use in a typical U.S. home, making it the largest energy expense for most homes. Along with improvements in the physical plant associated with home heating and cooling (e.g., improved insulation, higher efficiency furnaces), substantial increases in energy efficiency can be achieved by better control and regulation of home heating and cooling equipment. By activating heating, ventilation, and air conditioning (HVAC) equipment for judiciously selected time intervals and carefully chosen operating levels, substantial energy can be saved while at the same time keeping the living space suitably comfortable for its occupants.

[0004] Historically, however, most known HVAC thermostatic control systems have tended to fall into one of two opposing categories, neither of which is believed to be optimal in most practical home environments. In a first category are many simple, non-programmable home thermostats, each typically consisting of a single mechanical or electrical dial for setting a desired temperature and a single HEAT-FAN-OFF-AC switch. While being easy to use for even the most unsophisticated occupant, any energy-saving control activity, such as adjusting the nighttime temperature or turning off all heating/cooling just before departing the home, must be performed manually by the user. As such, substantial energy-saving opportunities are often missed for all but the most vigilant users. Moreover, more advanced energy-saving settings are not provided, such as the ability to specify a custom temperature swing, i.e., the difference between the desired set temperature and actual current temperature (such as 1 to 3 degrees) required to trigger turn-on of the heating/cooling unit.

[0005] In a second category, on the other hand, are many programmable thermostats, which have become more prevalent in recent years in view of Energy Star (US) and TCO (Europe) standards, and which have progressed considerably in the number of different settings for an HVAC system that can be individually manipulated. Unfortunately, however, users are often intimidated by a dizzying array of switches and controls laid out in various configurations on the face of the thermostat or behind a panel door on the thermostat, and seldom adjust the manufacturer defaults to optimize their own energy usage. Thus, even though the installed programmable thermostats in a large number of homes are technologically capable of operating the HVAC equipment with energy-saving profiles, it is often the case that only the one-size-fits-all manufacturer default profiles are ever implemented in a large number of homes. Indeed, in an unfortunately large number of cases, a home user may permanently operate the unit in a "temporary" or "hold" mode, manually manipulating the displayed set temperature as if the unit were a simple, non-programmable thermostat.

[0006] At a more general level, because of the fact that human beings must inevitably be involved, there is a tension that arises between (i) the amount of energy-saving sophistication that can be offered by an HVAC control system, and (ii) the extent to which that energy-saving sophistication can be put to practical, everyday use in a large number of homes. Similar issues arise in the context of multi-unit apartment buildings, hotels, retail stores, office buildings, industrial buildings, and more generally any living space or work space having one or more HVAC systems. Other issues arise as would be apparent to one skilled in the art upon reading the present disclosure.

[0007] It is to be appreciated that although exemplary embodiments are presented herein for the particular context of HVAC system control, there are a wide variety of other resource usage contexts for which the embodiments are readily applicable including, but not limited to, water usage, air usage, the usage of other natural resources, and the usage of other (i.e., non-HVAC-related) forms of energy, as would be apparent to the skilled artisan in view of the present disclosure. Therefore, such application of the embodiments in such other resource usage contexts is not outside the scope of the present teachings.

[0008] Provided according to some embodiments is a programmable device, such as a thermostat, for controlling an HVAC system. The programmable device includes high-power consuming circuitry adapted and programmed to perform while in an active state a plurality of high power activities including interfacing with a user, the high-power consuming circuitry using substantially less power while in an inactive state or sleep state. The device also includes low-power consuming circuitry adapted and programmed to perform a plurality of low power activities, including for example causing the high-power circuitry to transition from the inactive to active states; polling sensors such as temperature and occupancy sensors; and switching on or off an HVAC functions. The device also includes power stealing circuitry adapted to harvest power from an HVAC triggering circuit for turning on and off an HVAC system function; and a power storage medium, such as a rechargeable battery, adapted to store power harvested by the power stealing circuitry for use by at least the high-power consuming circuitry such that the high-power consuming circuitry can temporarily operate in an active state while using energy at

a greater rate than can be safely harvested by the power stealing circuitry without inadvertently switching the HVAC function. Examples of the high power activities includes wireless communication; driving display circuitry; displaying a graphical information to a user; and performing calculations relating to learning.

[0009] According to some embodiments, the high-power consuming circuitry includes a microprocessor and is located on a head unit, and the low-power consuming circuitry includes a microcontroller and is located on a backplate. The current application is directed to an intelligent-thermostat-controlled environmental-conditioning system in which computational tasks and subcomponents with associated intelligent-thermostat functionalities are distributed to one or more of concealed and visible portions of one or more intelligent thermostats and, in certain implementations, to one or more intermediate boxes. The intelligent thermostats are interconnected to intermediate boxes by wired and/or wireless interfaces and intelligent thermostats intercommunicate with one another by wireless communications. Wireless communications include communications through a local router and an ISP, 3G and 4G wireless communications through a mobile service provider. Components of the intelligent-thermostat-controlled environmental-conditioning system may also be connected by wireless communications to remote computing facilities.

BRIEF DESCRIPTION OF THE DRAWINGS

[0010] FIG. 1A illustrates a perspective view of a versatile sensing and control unit (VSCU unit) according to an embodiment;

[0011] FIGS. 1B-1C illustrate the VSCU unit as it is being controlled by the hand of a user according to an embodiment;

[0012] FIG. 2A illustrates the VSCU unit as installed in a house having an HVAC system and a set of control wires extending therefrom;

[0013] FIG. 2B illustrates an exemplary diagram of the HVAC system of FIG. 2A;

[0014] FIGS. 3A-3K illustrate user temperature adjustment based on rotation of the outer ring along with an ensuing user interface display according to one embodiment;

[0015] FIG. 4 illustrates a data input functionality provided by the user interface of the VSCU unit according to an embodiment;

[0016] FIGS. 5A-5B illustrate a similar data input functionality provided by the user interface of the VSCU unit for answering various questions during the set up interview;

[0017] FIGS. 6A-6C illustrate some of the many examples of user interface displays provided by the VSCU unit according to embodiments;

[0018] FIG. 7 illustrates an exploded perspective view of the VSCU unit and an HVAC-coupling wall dock according to an embodiment;

[0019] FIGS. 8A-B illustrates conceptual diagrams of HVAC-coupling wall docks, according to some embodiments;

[0020] FIG. 9 illustrates an exploded perspective view of the VSCU unit and an HVAC-coupling wall dock according to an embodiment;

[0021] FIGS. 10A-10C illustrate conceptual diagrams representative of advantageous scenarios in which multiple VSCU units are installed in a home or other space according

to embodiments in which the home (or other space) does not have a wireless data network;

[0022] FIG. 10D illustrates cycle time plots for two HVAC systems in a two-zone home heating (or cooling) configuration, according to an embodiment;

[0023] FIG. 11 illustrates a conceptual diagram representative of an advantageous scenario in which one or more VSCU units are installed in a home that is equipped with WiFi wireless connectivity and access to the Internet;

[0024] FIG. 12 illustrates a conceptual diagram of a larger overall energy management network as enabled by the VSCU units and VSCU Efficiency Platform described herein;

[0025] FIGS. 13A-13B and FIGS. 14A-14B illustrate examples of remote graphical user interface displays presented to the user on their data appliance for managing their one or more VSCU units and/or otherwise interacting with their VSCU Efficiency Platform equipment or data according to an embodiment;

[0026] FIGS. 15A-15D illustrate time plots of a normal set point temperature schedule versus an actual operating set point plot corresponding to an exemplary operation of an “auto away/auto arrival” algorithm according to a preferred embodiment;

[0027] FIGS. 16A-16D illustrate one example of set point schedule modification based on occupancy patterns and/or corrective manual input patterns associated with repeated instances of “auto-away” mode and/or “auto-arrival” mode operation according to an embodiment;

[0028] FIGS. 17A-D illustrates a dynamic user interface for encouraging reduced energy use according to a preferred embodiment;

[0029] FIGS. 18A-B illustrate a thermostat having a user-friendly interface, according to some embodiments;

[0030] FIG. 18C illustrates a cross-sectional view of a shell portion of a frame of the thermostat of FIGS. 18A-B;

[0031] FIGS. 19A-19B illustrate exploded front and rear perspective views, respectively, of a thermostat with respect to its two main components, which are the head unit and the back plate;

[0032] FIGS. 20A-20B illustrate exploded front and rear perspective views, respectively, of the head unit with respect to its primary components;

[0033] FIGS. 21A-21B illustrate exploded front and rear perspective views, respectively, of the head unit frontal assembly with respect to its primary components;

[0034] FIGS. 22A-22B illustrate exploded front and rear perspective views, respectively, of the backplate unit with respect to its primary components;

[0035] FIG. 23 illustrates a perspective view of a partially assembled head unit front, according to some embodiments;

[0036] FIG. 24 illustrates a head-on view of the head unit circuit board, according to one embodiment;

[0037] FIG. 25 illustrates a rear view of the backplate circuit board, according to one embodiment;

[0038] FIGS. 26A-26C illustrate conceptual examples of the sleep-wake timing dynamic, at progressively larger time scales; according to one embodiment;

[0039] FIG. 27 illustrates a self-descriptive overview of the functional software, firmware, and/or programming architecture of the head unit microprocessor, according to one embodiment;

[0040] FIG. 28 illustrates a self-descriptive overview of the functional software, firmware, and/or programming architecture of the backplate microcontroller, according to one embodiment;

[0041] FIG. 29 illustrates a view of the wiring terminals as presented to the user when the backplate is exposed; according to one embodiment;

[0042] FIGS. 30A-30B illustrate restricting user establishment of a new scheduled set point that is within a predetermined time separation, according to one embodiment;

[0043] FIGS. 31A-31D illustrate time to temperature display to a user for one implementation;

[0044] FIG. 32 illustrates an example of a preferred thermostat readout when a second stage heating facility is invoked, according to one embodiment;

[0045] FIGS. 33A-33C illustrate actuating a second stage heat facility during a single stage heating cycle using time to temperature (T2T) information according to a preferred embodiment; and

[0046] FIG. 34 illustrates a user interface screen presented to a user by a thermostat in relation to a “selectably automated” testing for heat pump polarity according to a preferred embodiment.

[0047] FIGS. 35A-B illustrate certain components and architectural sources of flexibility of intelligent-thermostat-controlled HVAC systems to which the current application is directed.

[0048] FIGS. 36A-H illustrate an architecture-based flexibility in function partitioning of HVAC-control systems, to which the current application is directed, that provides for many alternative implementations.

[0049] FIG. 37 illustrates additional implementation flexibility arising from the computationally distributed nature of the intelligent-thermostat HVAC-control systems to which the current application is directed.

DETAILED DESCRIPTION

[0050] The subject matter of this patent specification relates to the subject matter of the following commonly assigned applications, each of which is incorporated by reference herein: U.S. Ser. No. 12/881,430 filed Sep. 14, 2010; U.S. Ser. No. 12/881,463 filed Sep. 14, 2010; U.S. Prov. Ser. No. 61/415,771 filed Nov. 19, 2010; U.S. Prov. Ser. No. 61/429,093 filed Dec. 31, 2010; U.S. Ser. No. 12/984,602 filed Jan. 4, 2011; U.S. Ser. No. 12/987,257 filed Jan. 10, 2011; U.S. Ser. No. 13/033,573 filed Feb. 23, 2011; U.S. Ser. No. 29/386,021, filed Feb. 23, 2011; U.S. Ser. No. 13/034,666 filed Feb. 24, 2011; U.S. Ser. No. 13/034,674 filed Feb. 24, 2011; U.S. Ser. No. 13/034,678 filed Feb. 24, 2011; U.S. Ser. No. 13/038,191 filed Mar. 1, 2011; U.S. Ser. No. 13/038,206 filed Mar. 1, 2011; U.S. Ser. No. 29/399,609 filed Aug. 16, 2011; U.S. Ser. No. 29/399,614 filed Aug. 16, 2011; U.S. Ser. No. 29/399,617 filed Aug. 16, 2011; U.S. Ser. No. 29/399,618 filed Aug. 16, 2011; U.S. Ser. No. 29/399,621 filed Aug. 16, 2011; U.S. Ser. No. 29/399,623 filed Aug. 16, 2011; U.S. Ser. No. 29/399,625 filed Aug. 16, 2011; U.S. Ser. No. 29/399,627 filed Aug. 16, 2011; U.S. Ser. No. 29/399,630 filed Aug. 16, 2011; U.S. Ser. No. 29/399,632 filed Aug. 16, 2011; U.S. Ser. No. 29/399,633 filed Aug. 16, 2011; U.S. Ser. No. 29/399,636 filed Aug. 16, 2011; U.S. Ser. No. 29/399,637 filed Aug. 16, 2011; U.S. Ser. No. 13/199,108, filed Aug. 17, 2011; U.S. Ser. No. 13/267,871 filed Oct. 6, 2011; U.S. Ser. No. 13/267,877 filed Oct. 6, 2011; U.S. Ser. No. 13/269,501, filed Oct. 7, 2011;

U.S. Ser. No. 29/404,096 filed Oct. 14, 2011; U.S. Ser. No. 29/404,097 filed Oct. 14, 2011; U.S. Ser. No. 29/404,098 filed Oct. 14, 2011; U.S. Ser. No. 29/404,099 filed Oct. 14, 2011; U.S. Ser. No. 29/404,101 filed Oct. 14, 2011; U.S. Ser. No. 29/404,103 filed Oct. 14, 2011; U.S. Ser. No. 29/404,104 filed Oct. 14, 2011; U.S. Ser. No. 29/404,105 filed Oct. 14, 2011; U.S. Ser. No. 13/275,307 filed Oct. 17, 2011; U.S. Ser. No. 13/275,311 filed Oct. 17, 2011; U.S. Ser. No. 13/317,423 filed Oct. 17, 2011; U.S. Ser. No. 13/279,151 filed Oct. 21, 2011; U.S. Ser. No. 13/317,557 filed Oct. 21, 2011; U.S. Prov. Ser. No. 61/627,996 filed Oct. 21, 2011; PCT/US11/61339 filed Nov. 18, 2011; PCT/US11/61344 filed Nov. 18, 2011; PCT/US11/61365 filed Nov. 18, 2011; PCT/US11/61379 filed Nov. 18, 2011; PCT/US11/61391 filed Nov. 18, 2011; PCT/US11/61479 filed Nov. 18, 2011; PCT/US11/61457 filed Nov. 18, 2011; and PCT/US11/61470 filed Nov. 18, 2011; PCT/US11/61339 filed Nov. 18, 2011; PCT/US11/61491 filed Nov. 18, 2011; PCT/US11/61437 filed Nov. 18, 2011; and PCT/US11/61503 filed Nov. 18, 2011. The above-referenced patent applications are collectively referenced herein as “the commonly assigned incorporated applications.”

[0051] Provided according to one or more embodiments are systems, methods, computer program products, and related business methods for controlling one or more HVAC systems based on one or more versatile sensing and control units (VSCU units), each VSCU unit being configured and adapted to provide sophisticated, customized, energy-saving HVAC control functionality while at the same time being visually appealing, non-intimidating, elegant to behold, and delightfully easy to use. Each VSCU unit is advantageously provided with a selectively layered functionality, such that unsophisticated users are only exposed to a simple user interface, but such that advanced users can access and manipulate many different energy-saving and energy tracking capabilities. Importantly, even for the case of unsophisticated users who are only exposed to the simple user interface, the VSCU unit provides advanced energy-saving functionality that runs in the background, the VSCU unit quietly using multi-sensor technology to “learn” about the home’s heating and cooling environment and optimizing the energy-saving settings accordingly.

[0052] The VSCU unit also “learns” about the users themselves, beginning with a congenial “setup interview” in which the user answers a few simple questions, and then continuing over time using multi-sensor technology to detect user occupancy patterns (e.g., what times of day they are home and away) and by tracking the way the user controls the set temperature on the dial over time. The multi-sensor technology is advantageously hidden away inside the VSCU unit itself, thus avoiding the hassle, complexity, and intimidation factors associated with multiple external sensor-node units. On an ongoing basis, the VSCU unit processes the learned and sensed information according to one or more advanced control algorithms, and then automatically adjusts its environmental control settings to optimize energy usage while at the same time maintaining the living space at optimal levels according to the learned occupancy patterns and comfort preferences of the user. Even further, the VSCU unit is programmed to promote energy-saving behavior in the users themselves by virtue of displaying, at judiciously selected times on its visually appealing user interface, information that encourages reduced energy usage, such as

historical energy cost performance, forecasted energy costs, and even fun game-style displays of congratulations and encouragement.

[0053] Advantageously, the selectively layered functionality of the VSCU unit allows it to be effective for a variety of different technological circumstances in home and business environments, thereby making the same VSCU unit readily saleable to a wide variety of customers. For simple environments having no wireless home network or internet connectivity, the VSCU unit operates effectively in a stand-alone mode, being capable of learning and adapting to its environment based on multi-sensor technology and user input, and optimizing HVAC settings accordingly. However, for environments that do indeed have home network or internet connectivity, the VSCU unit operates effectively in a network-connected mode to offer a rich variety of additional capabilities.

[0054] When the VSCU unit is connected to the internet via a home network, such as through IEEE 802.11 (Wi-Fi) connectivity, additional capabilities provided according to one or more embodiments include, but are not limited to: providing real time or aggregated home energy performance data to a utility company, VSCU data service provider, VSCU units in other homes, or other data destinations; receiving real time or aggregated home energy performance data from a utility company, VSCU data service provider, VSCU units in other homes, or other data sources; receiving new energy control algorithms or other software/firmware upgrades from one or more VSCU data service providers or other sources; receiving current and forecasted weather information for inclusion in energy-saving control algorithm processing; receiving user control commands from the user's computer, network-connected television, smart phone, or other stationary or portable data communication appliance (hereinafter collectively referenced as the user's "digital appliance"); providing an interactive user interface to the user through their digital appliance; receiving control commands and information from an external energy management advisor, such as a subscription-based service aimed at leveraging collected information from multiple sources to generate the best possible energy-saving control commands or profiles for their subscribers; receiving control commands and information from an external energy management authority, such as a utility company to whom limited authority has been voluntarily given to control the VSCU in exchange for rebates or other cost incentives (e.g., for energy emergencies, "spare the air" days, etc.); providing alarms, alerts, or other information to the user on their digital appliance (and/or a user designee such as a home repair service) based on VSCU-sensed HVAC-related events (e.g., the house is not heating up or cooling down as expected); providing alarms, alerts, or other information to the user on their digital appliance (and/or a user designee such as a home security service or the local police department) based on VSCU-sensed non-HVAC related events (e.g., an intruder alert as sensed by the VSCU's multi-sensor technology); and a variety of other useful functions enabled by network connectivity as disclosed in one or more of the examples provided further hereinbelow.

[0055] It is to be appreciated that while one or more embodiments is detailed herein for the context of a residential home, such as a single-family house, the scope of the present teachings is not so limited, the present teachings being likewise applicable, without limitation, to duplexes,

townhomes, multi-unit apartment buildings, hotels, retail stores, office buildings, industrial buildings, and more generally any living space or work space having one or more HVAC systems. It is to be further appreciated that while the terms user, customer, installer, homeowner, occupant, guest, tenant, landlord, repair person, and the like may be used to refer to the person or persons who are interacting with the VSCU unit or other device or user interface in the context of some particularly advantageous situations described herein, these references are by no means to be considered as limiting the scope of the present teachings with respect to the person or persons who are performing such actions. Thus, for example, the terms user, customer, purchaser, installer, subscriber, and homeowner may often refer to the same person in the case of a single-family residential dwelling, because the head of the household is often the person who makes the purchasing decision, buys the unit, and installs and configures the unit, and is also one of the users of the unit and is a customer of the utility company and/or VSCU data service provider. However, in other scenarios, such as a landlord-tenant environment, the customer may be the landlord with respect to purchasing the unit, the installer may be a local apartment supervisor, a first user may be the tenant, and a second user may again be the landlord with respect to remote control functionality. Importantly, while the identity of the person performing the action may be germane to a particular advantage provided by one or more of the embodiments—for example, the password-protected temperature governance functionality described further herein may be particularly advantageous where the landlord holds the sole password and can prevent energy waste by the tenant—such identity should not be construed in the descriptions that follow as necessarily limiting the scope of the present teachings to those particular individuals having those particular identities.

[0056] As used herein, "set point" or "temperature set point" refers to a target temperature setting of a temperature control system, such as one or more of the VSCU units described herein, as set by a user or automatically according to a schedule. As would be readily appreciated by a person skilled in the art, many of the disclosed thermostatic functionalities described hereinbelow apply, in counterpart application, to both the heating and cooling contexts, with the only different being in the particular set points and directions of temperature movement. To avoid unnecessary repetition, some examples of the embodiments may be presented herein in only one of these contexts, without mentioning the other. Therefore, where a particular embodiment or example is set forth hereinbelow in the context of home heating, the scope of the present teachings is likewise applicable to the counterpart context of home cooling, and vice versa, to the extent such counterpart application would be logically consistent with the disclosed principles as adjudged by the skilled artisan.

[0057] FIG. 1A illustrates a perspective view of a versatile sensing and control unit (VSCU unit) **100** according to an embodiment. Unlike so many prior art thermostats, the VSCU unit **100** preferably has a sleek, elegant appearance that does not detract from home decoration, and indeed can serve as a visually pleasing centerpiece for the immediate location in which it is installed. The VSCU unit **100** comprises a main body **108** that is preferably circular with a diameter of about 8 cm, and that has a visually pleasing outer finish, such as a satin nickel or chrome finish. Separated

from the main body **108** by a small peripheral gap **110** is a cap-like structure comprising a rotatable outer ring **106**, a sensor ring **104**, and a circular display monitor **102**. The outer ring **106** preferably has an outer finish identical to that of the main body **108**, while the sensor ring **104** and circular display monitor **102** have a common circular glass (or plastic) outer covering that is gently arced in an outward direction and that provides a sleek yet solid and durable-looking overall appearance. The sensor ring **104** contains any of a wide variety of sensors including, without limitation, infrared sensors, visible-light sensors, and acoustic sensors. Preferably, the glass (or plastic) that covers the sensor ring **104** is smoked or mirrored such that the sensors themselves are not visible to the user. An air venting functionality is preferably provided, such as by virtue of the peripheral gap **110**, which allows the ambient air to be sensed by the internal sensors without the need for visually unattractive “gills” or grill-like vents.

[0058] FIGS. 1B-1C illustrate the VSCU unit **100** as it is being controlled by the hand of a user according to an embodiment. In one embodiment, for the combined purposes of inspiring user confidence and further promoting visual and functional elegance, the VSCU unit **100** is controlled by only two types of user input, the first being a rotation of the outer ring **106** (FIG. 1B), and the second being an inward push on the outer ring **106** (FIG. 1C) until an audible and/or tactile “click” occurs. For one embodiment, the inward push of FIG. 1C only causes the outer ring **106** to move forward, while in another embodiment the entire cap-like structure, including both the outer ring **106** and the glass covering of the sensor ring **104** and circular display monitor **102**, move inwardly together when pushed. Preferably, the sensor ring **104**, the circular display monitor **102**, and their common glass covering do not rotate with outer ring **106**.

[0059] By virtue of user rotation of the outer ring **106** (referenced hereafter as a “ring rotation”) and the inward pushing of the outer ring **106** (referenced hereinafter as an “inward click”) responsive to intuitive and easy-to-read prompts on the circular display monitor **102**, the VSCU unit **100** is advantageously capable of receiving all necessary information from the user for basic setup and operation. Preferably, the outer ring **106** is mechanically mounted in a manner that provides a smooth yet viscous feel to the user, for further promoting an overall feeling of elegance while also reducing spurious or unwanted rotational inputs. For one embodiment, the VSCU unit **100** recognizes three fundamental user inputs by virtue of the ring rotation and inward click: (1) ring rotate left, (2) ring rotate right, and (3) inward click. For other embodiments, more complex fundamental user inputs can be recognized, such as “double-click” or “triple-click” inward presses, and such as speed-sensitive or acceleration-sensitive rotational inputs (e.g., a very large and fast leftward rotation specifies an “Away” occupancy state, while a very large and fast rightward rotation specifies an “Occupied” occupancy state).

[0060] Although the scope of the present teachings is not so limited, it is preferred that there not be provided a discrete mechanical HEAT-COOL toggle switch, or HEAT-OFF-COOL selection switch, or HEAT-FAN-OFF-COOL switch anywhere on the VSCU unit **100**, this omission contributing to the overall visual simplicity and elegance of the VSCU unit **100** while also facilitating the provision of advanced control abilities that would otherwise not be permitted by the

existence of such a switch. It is further highly preferred that there be no electrical proxy for such a discrete mechanical switch (e.g., an electrical push button or electrical limit switch directly driving a mechanical relay). Instead, it is preferred that the switching between these settings be performed under computerized control of the VSCU unit **100** responsive to its multi-sensor readings, its programming (optionally in conjunction with externally provided commands/data provided over a data network), and/or the above-described “ring rotation” and “inward click” user inputs.

[0061] The VSCU unit **100** comprises physical hardware and firmware configurations, along with hardware, firmware, and software programming that is capable of carrying out the functionalities described in the instant disclosure. In view of the instant disclosure, a person skilled in the art would be able to realize the physical hardware and firmware configurations and the hardware, firmware, and software programming that embody the physical and functional features described herein without undue experimentation using publicly available hardware and firmware components and known programming tools and development platforms. Similar comments apply to described devices and functionalities extrinsic to the VSCU unit **100**, such as devices and programs used in remote data storage and data processing centers that receive data communications from and/or that provide data communications to the VSCU unit **100**. By way of example, references hereinbelow to one or more pre-installed databases inside the VSCU unit **100** that are keyed to different ZIP codes can be carried out using flash memory technology similar to that used in global positioning based navigation devices. By way of further example, references hereinbelow to machine learning and mathematical optimization algorithms, as carried out respectively by the VSCU unit **100** in relation to home occupancy prediction and set point optimization, for example, can be carried out using one or more known technologies, models, and/or mathematical strategies including, but not limited to, artificial neural networks, Bayesian networks, genetic programming, inductive logic programming, support vector machines, decision tree learning, clustering analysis, dynamic programming, stochastic optimization, linear regression, quadratic regression, binomial regression, logistic regression, simulated annealing, and other learning, forecasting, and optimization techniques.

[0062] FIG. 2A illustrates the VSCU unit **100** as installed in a house **201** having an HVAC system **299** and a set of control wires **298** extending therefrom. The VSCU unit **100** is, of course, extremely well suited for installation by contractors in new home construction and/or in the context of complete HVAC system replacement. However, one alternative key business opportunity leveraged according to one embodiment is the marketing and retailing of the VSCU unit **100** as a replacement thermostat in an existing home, wherein the customer (and/or an HVAC professional) disconnects their old thermostat from the existing wires **298** and substitutes in the VSCU unit **100**.

[0063] In either case, the VSCU unit **100** can advantageously serve as an “inertial wedge” for inserting an entire energy-saving technology platform into the home. Simply stated, because most homeowners understand and accept the need for home to have a thermostat, even the most curmudgeonly and techno-phobic homeowners will readily accept the simple, non-intimidating, and easy-to-use VSCU unit **100** into their homes. Once in the home, of course, the

VSCU unit **100** will advantageously begin saving energy for a sustainable planet and saving money for the homeowner, including the curmudgeons. Additionally, however, as homeowners “warm up” to the VSCU unit **100** platform and begin to further appreciate its delightful elegance and seamless operation, they will be more inclined to take advantage of its advanced features, and they will furthermore be more open and willing to embrace a variety of compatible follow-on products and services as are described further hereinbelow. This is an advantageous win-win situation on many fronts, because the planet is benefitting from the propagation of energy-efficient technology, while at the same time the manufacturer of the VSCU unit and/or their authorized business partners can further expand their business revenues and prospects. For clarity of disclosure, the term “VSCU Efficiency Platform” refers herein to products and services that are technologically compatible with the VSCU unit **100** and/or with devices and programs that support the operation of the VSCU unit **100**.

[0064] FIG. 2B illustrates an exemplary diagram of the HVAC system **299** of FIG. 2A. HVAC system **299** provides heating, cooling, ventilation, and/or air handling for an enclosure, such as the single-family home **201** depicted in FIG. 2A. The HVAC system **299** depicts a forced air type heating system, although according to other embodiments, other types of systems could be used. In heating, heating coils or elements **242** within air handler **240** provide a source of heat using electricity or gas via line **236**. Cool air is drawn from the enclosure via return air duct **246** through filter **270** using fan **238** and is heated by the heating coils or elements **242**. The heated air flows back into the enclosure at one or more locations through a supply air duct system **252** and supply air grills such as grill **250**. In cooling, an outside compressor **230** passes a gas such as Freon through a set of heat exchanger coils to cool the gas. The gas then goes via line **232** to the cooling coils **234** in the air handlers **240** where it expands, cools and cools the air being circulated through the enclosure via fan **238**. According to some embodiments a humidifier **262** is also provided which moistens the air using water provided by a water line **264**. Although not shown in FIG. 2B, according to some embodiments the HVAC system for the enclosure has other known components such as dedicated outside vents to pass air to and from the outside, one or more dampers to control airflow within the duct systems, an emergency heating unit, and a dehumidifier. The HVAC system is selectively actuated via control electronics **212** that communicate with the VSCU **100** over control wires **298**.

[0065] FIGS. 3A-3K illustrate user temperature adjustment based on rotation of the outer ring **106** along with an ensuing user interface display according to one embodiment. For one embodiment, prior to the time depicted in FIG. 3A in which the user has walked up to the VSCU unit **100**, the VSCU unit **100** has set the circular display monitor **102** to be entirely blank (“dark”), which corresponds to a state of inactivity when no person has come near the unit. As the user walks up to the display, their presence is detected by one or more sensors in the VSCU unit **100** at which point the circular display monitor **102** is automatically turned on. When this happens, as illustrated in FIG. 3A, the circular display monitor **102** displays the current set point in a large font at a center readout **304**. Also displayed is a set point icon **302** disposed along a periphery of the circular display monitor **102** at a location that is spatially representative the

current set point. Although it is purely electronic, the set point icon **302** is reminiscent of older mechanical thermostat dials, and advantageously imparts a feeling of familiarity for many users as well as a sense of tangible control.

[0066] Notably, the example of FIG. 3A assumes a scenario for which the actual current temperature of **68** is equal to the set point temperature of **68** when the user has walked up to the VSCU unit **100**. For a case in which the user walks up to the VSCU unit **100** when the actual current temperature is different than the set point temperature, the display would also include an actual temperature readout and a trailing icon, which are described further below in the context of FIGS. 3B-3K.

[0067] Referring now to FIG. 3B, as the user turns the outer ring **106** clockwise, the increasing value of the set point temperature is instantaneously provided at the center readout **304**, and the set point icon **302** moves in a clockwise direction around the periphery of the circular display monitor **102** to a location representative of the increasing set point. Whenever the actual current temperature is different than the set point temperature, an actual temperature readout **306** is provided in relatively small digits along the periphery of the circular a location spatially representative the actual current temperature. Further provided is a trailing icon **308**, which could alternatively be termed a tail icon or difference-indicating, that extends between the location of the actual temperature readout **306** and the set point icon **302**. Further provided is a time-to-temperature readout **310** that is indicative of a prediction, as computed by the VSCU unit **100**, of the time interval required for the HVAC system to bring the temperature from the actual current temperature to the set point temperature.

[0068] FIGS. 3C-3K illustrate views of the circular display monitor **102** at exemplary instants in time after the user set point change that was completed in FIG. 3B (assuming, of course, that the circular display monitor **102** has remained active, such as during a preset post-activity time period, responsive to the continued proximity of the user, or responsive the detected proximity of another occupant). Thus, at FIG. 3C, the current actual temperature is about halfway up from the old set point to the new set point, and in FIG. 3D the current actual temperature is almost at the set point temperature. As illustrated in FIG. 3E, both the trailing icon **308** and the actual temperature readout **306** disappear when the current actual temperature reaches the set point temperature and the heating system is turned off. Then, as typically happens in home heating situations, the actual temperature begins to sag (FIG. 3F) until the permissible temperature swing is reached (which is 2 degrees in this example, see FIG. 3G), at which point the heating system is again turned on and the temperature rises to the set point (FIGS. 3H-3I) and the heating system is turned off. The current actual temperature then begins to sag again (FIGS. 3J-3K), and the cycle continues. Advantageously, by virtue of the user interface functionality of FIGS. 3A-3K including the time-to-temperature readout **310**, the user is provided with a fast, intuitive, visually pleasing overview of system operation, as well as a quick indication of how much longer the heating system (or cooling system in counterpart embodiments) will remain turned on. It is to be appreciated that the use of 2 degrees as the permissible temperature swing in FIGS. 3C-3K is only for purposes of example, and that different amounts of permissible temperature swing may be applicable at different times according to the particular automated

control algorithms, defaults, user settings, user overrides, etc. that may then be in application at those times.

[0069] For one embodiment, the VSCU unit **100** is designed to be entirely silent unless a user has walked up and begun controlling the unit. Advantageously, there are no clicking-type annoyances when the heating or cooling units are activated as with conventional prior art thermostats. Optionally, the VSCU unit **100** can be configured to synthesize artificial audible clicks, such as can be output through a piezoelectric speaker, to provide “tick” feedback as the user dials through different temperature settings.

[0070] FIG. 4 illustrates a data input functionality provided by the user interface of the VSCU unit **100** according to an embodiment, for a particular non-limiting example in which the user is asked, during a congenial setup interview (which can occur at initial VSCU unit installation or at any subsequent time that the user may request), to enter their ZIP code. Responsive to a display of digits 0-9 distributed around a periphery of the circular display monitor **102** along with a selection icon **402**, the user turns the outer ring **106** to move the selection icon **402** to the appropriate digit, and then provides an inward click command to enter that digit.

[0071] For one embodiment, the VSCU unit **100** is programmed to provide a software lockout functionality, wherein a person is required to enter a password or combination before the VSCU unit **100** will accept their control inputs. The user interface for password request and entry can be similar to that shown in FIG. 4. The software lockout functionality can be highly useful, for example, for Mom and Dad in preventing their teenager from making unwanted changes to the set temperature, for various landlord-tenant scenarios, and in a variety of other situations.

[0072] FIGS. 5A-5B illustrate a similar data input functionality provided by the user interface of the VSCU unit **100** for answering various questions during the set up interview. The user rotates the outer ring **106** until the desired answer is highlighted, and then provides an inward click command to enter that answer.

[0073] FIGS. 6A-6C illustrate some of the many examples of user interface displays provided by the VSCU unit **100** according to embodiments directed to influencing energy-conscious behavior on the part of the user. At judiciously selected times (for example, on the same day that the monthly utility bill is e-mailed to the homeowner), or upon user request, or at other times including random points in time, the VSCU unit **100** displays information on its visually appealing user interface that encourages reduced energy usage. In one example shown in FIG. 6A, the user is shown a message of congratulations regarding a particular energy-saving (and therefore money-saving) accomplishment they have achieved for their household. It has been found particularly effective to include pictures or symbols, such as leaf icons **602**, that evoke pleasant feelings or emotions in the user for providing positive reinforcement of energy-saving behavior. Although not believed to be as advantageous as positive reinforcement, it is within the scope of the present teachings for the VSCU unit **100** to show messages of negative reinforcement as well, such as by displaying unpleasant pictures of smokestacks churning out black smoke to depict energy-hogging performance.

[0074] FIG. 6B illustrates another example of an energy performance display that can influence user energy-saving behavior, comprising a display of the household's recent energy use on a daily basis (or weekly, monthly, etc.) and

providing a positive-feedback leaf icon **602** for days of relatively low energy usage. Notably, messages such as those of FIG. 6A can be displayed for customers who are not Wi-Fi enabled, based on the known cycle times and durations of the home HVAC equipment as tracked by the VSCU unit **100**. Indeed, although a bit more involved, messages such as those of FIG. 6A could also be displayed for customers who are not Wi-Fi enabled, based on the known HVAC cycle times and durations combined with pre-programmed estimates of energy costs for their ZIP code and/or user-entered historical energy cost information from their past utility bills as may be provided, for example, during the congenial setup interview.

[0075] For another example shown in FIG. 6C, the user is shown information about their energy performance status or progress relative to a population of other VSCU-equipped owners who are similarly situated from an energy usage perspective. For this type of display, and similar displays in which data from other homes and/or central databases is required, it is required that the VSCU unit **100** be network-enabled. It has been found particularly effective to provide competitive or game-style information to the user as an additional means to influence their energy-saving behavior. As illustrated in FIG. 6B, positive-feedback leaf icons **602** can be added to the display if the user's competitive results are positive. Optionally, the leaf icons **602** can be associated with a frequent flyer miles-type point-collection scheme or carbon credit-type business method, as administered for example by an external VSCU data service provider (see FIG. 12, *infra*) such there is a tangible, fiscal reward that is also associated with the emotional reward.

[0076] For some embodiments, the VSCU unit **100** is manufactured and sold as a single, monolithic structure containing all of the required electrical and mechanical connections on the back of the unit. For some embodiments, the VSCU **100** is manufactured and/or sold in different versions or packaging groups depending on the particular capabilities of the manufacturer(s) and the particular needs of the customer. For example, the VSCU unit **100** is provided in some embodiments as the principal component of a two-part combination consisting of the VSCU **100** and one of a variety of dedicated docking devices, as described further hereinbelow.

[0077] FIG. 7 illustrates an exploded perspective view of the VSCU unit **100** and an HVAC-coupling wall dock **702** according to an embodiment. For first-time customers who are going to be replacing their old thermostat, the VSCU unit **100** is provided in combination with HVAC-coupling wall dock **702**. The HVAC-coupling wall dock **702** comprises mechanical hardware for attaching to the wall and electrical terminals for connecting to the HVAC wiring **298** that will be extending out of the wall in a disconnected state when the old thermostat is removed. The HVAC-coupling wall dock **702** is configured with an electrical connector **704** that mates to a counterpart electrical connector **705** in the VSCU **100**.

[0078] For the initial installation process, the customer (or their handyman, or an HVAC professional, etc.) first installs the HVAC-coupling wall dock **702**, including all of the necessary mechanical connections to the wall and HVAC wiring connections to the HVAC wiring **298**. Once the HVAC-coupling wall dock **702** is installed, which represents the “hard work” of the installation process, the next task is relatively easy, which is simply to slide the VSCU unit **100** thereover to mate the electrical connectors **704/705**. Prefer-

ably, the components are configured such that the HVAC-connecting wall dock **702** is entirely hidden underneath and inside the VSCU unit **100**, such that only the visually appealing VSCU unit **100** is visible.

[0079] For one embodiment, the HVAC-connecting wall dock **702** is a relatively “bare bones” device having the sole essential function of facilitating electrical connectivity between the HVAC wiring **298** and the VSCU unit **100**. For another embodiment, the HVAC-coupling wall dock **702** is equipped to perform and/or facilitate, in either a duplicative sense and/or a primary sense without limitation, one or more of the functionalities attributed to the VSCU unit **100** in the instant disclosure, using a set of electrical, mechanical, and/or electromechanical components **706**. One particularly useful functionality is for the components **706** to include power-extraction circuitry for judiciously extracting usable power from the HVAC wiring **298**, at least one of which will be carrying a 24-volt AC signals in accordance with common HVAC wiring practice. The power-extraction circuitry converts the 24-volt AC signal into DC power (such as at 5 VDC, 3.3 VDC, etc.) that is usable by the processing circuitry and display components of the main unit **701**.

[0080] The division and/or duplication of functionality between the VSCU unit **100** and the HVAC-coupling wall dock **702** can be provided in many different ways without departing from the scope of the present teachings. For another embodiment, the components **706** of the HVAC-coupling wall dock **702** can include one or more sensing devices, such as an acoustic sensor, for complementing the sensors provided on the sensor ring **104** of the VSCU unit **100**. For another embodiment, the components **706** can include wireless communication circuitry compatible with one or more wireless communication protocols, such as the Wi-Fi and/or ZigBee protocols. For another embodiment, the components **706** can include external AC or DC power connectors. For another embodiment, the components **706** can include wired data communications jacks, such as an RJ45 Ethernet jack, an RJ11 telephone jack, or a USB connector.

[0081] The docking capability of the VSCU unit **100** according to the embodiment of FIG. 7 provides many advantages and opportunities in both a technology sense and a business sense. Because the VSCU unit **100** can be easily removed and replaced by even the most non-technically-savvy customer, many upgrading and upselling opportunities are provided. For example, many different versions of the VSCU unit **100** can be separately sold, the different versions having different colors, styles, themes, and so forth. Upgrading to a new VSCU unit **100** having more advanced capabilities becomes a very easy task, and so the customer will be readily able to take advantage of the newest display technology, sensor technology, more memory, and so forth as the technology improves over time.

[0082] Provided in accordance with one or more embodiments related to the docking capability shown in FIG. 7 are further devices and features that advantageously promote expandability of the number of sensing and control nodes that can be provided throughout the home. For one embodiment, a tabletop docking station (not shown) is provided that is capable of docking to a second instance of the VSCU unit **100**, which is termed herein an auxiliary VSCU unit (not shown). The tabletop docking station and the auxiliary VSCU unit can be separately purchased by the user, either at the same time they purchase their original VSCU unit **100**,

or at a later time. The tabletop docking station is similar in functionality to the HVAC-coupling wall dock **702**, except that it does not require connection to the HVAC wiring **298** and is conveniently powered by a standard wall outlet. For another embodiment, instead of being identical to the original VSCU unit **100**, the auxiliary VSCU unit can be a differently labeled and/or differently abled version thereof.

[0083] As used herein, the term “primary VSCU unit” refers to one that is electrically connected to actuate an HVAC system in whole or in part, which would necessarily include the first VSCU unit purchased for any home, while the term “auxiliary VSCU unit” refers to one or more additional VSCU units not electrically connected to actuate an HVAC system in whole or in part. An auxiliary VSCU unit, when docked, will automatically detect the primary VSCU unit and will automatically be detected by the primary VSCU unit, such as by Wi-Fi or ZigBee wireless communication. Although the primary VSCU unit will remain the sole provider of electrical actuation signals to the HVAC system, the two VSCU units will otherwise cooperate in unison for improved control heating and cooling control functionality, such improvement being enabled by virtue of the added multi-sensing functionality provided by the auxiliary VSCU unit, as well as by virtue of the additional processing power provided to accommodate more powerful and precise control algorithms. Because the auxiliary VSCU unit can accept user control inputs just like the primary VSCU unit, user convenience is also enhanced. Thus, for example, where the tabletop docking station and the auxiliary VSCU unit are placed on a nightstand next to the user’s bed, the user is not required to get up and walk to the location of the primary VSCU unit if they wish to manipulate the temperature set point, view their energy usage, or otherwise interact with the system.

[0084] A variety of different VSCU-compatible docking stations are within the scope of the present teachings. For example, in another embodiment there is provided an auxiliary wall dock (not shown) that allows an auxiliary VSCU unit to be mounted on a wall. The auxiliary wall dock is similar in functionality to the tabletop docking station in that it does not provide HVAC wiring connections, but does serve as a physical mounting point and provides electrical power derived from a standard wall outlet.

[0085] For one embodiment, all VSCU units sold by the manufacturer are identical in their core functionality, each being able to serve as either a primary VSCU unit or auxiliary VSCU unit as the case requires, although the different VSCU units may have different colors, ornamental designs, memory capacities, and so forth. For this embodiment, the user is advantageously able, if they desire, to interchange the positions of their VSCU units by simple removal of each one from its existing docking station and placement into a different docking station. Among other advantages, there is an environmentally, technically, and commercially appealing ability for the customer to upgrade to the newest, latest VSCU designs and technologies without the need to throw away the existing VSCU unit. For example, a customer with a single VSCU unit (which is necessarily serving as a primary VSCU unit) may be getting tired of its color or its TFT display, and may be attracted to a newly released VSCU unit with a different color and a sleek new OLED display. For this case, in addition to buying the newly released VSCU, the customer can buy a tabletop docking station to put on their nightstand. The customer can

then insert their new VSCU unit into the existing HVAC-coupling wall dock, and then take their old VSCU unit and insert it into the tabletop docking station. Advantageously, in addition to avoiding the wastefulness of discarding the old VSCU unit, there is now a new auxiliary VSCU unit at the bedside that not only provides increased comfort and convenience, but that also promotes increased energy efficiency by virtue of the additional multi-sensor information and processing power provided.

[0086] For other embodiments, different VSCU units sold by the manufacturer can have different functionalities in terms of their ability to serve as primary versus auxiliary VSCU units. This may be advantageous from a pricing perspective, since the hardware cost of an auxiliary-only VSCU unit may be substantially less than that of a dual-capability primary/auxiliary VSCU unit. In other embodiments there is provided distinct docking station capability for primary versus auxiliary VSCU units, with primary VSCU units using one kind of docking connection system and auxiliary VSCU units using a different kind of docking connection system. In still other embodiments there is provided the docking station capability of FIG. 7 for primary VSCU units, but no docking station capability for auxiliary VSCU units, wherein auxiliary VSCU units are simply provided in monolithic form as dedicated auxiliary tabletop VSCU units, dedicated auxiliary wall-mounted VSCU units, and so forth. One advantage of providing an auxiliary VSCU unit, such as a tabletop VSCU unit, without a docking functionality would be its simplicity and non-intimidating nature for users, since the user would simply be required to place it on a table (their nightstand, for example) and just plug it in, just as easily as they would a clock radio.

[0087] In still other embodiments, all VSCU units are provided as non-docking types, but are interchangeable in their abilities as primary and auxiliary VSCU units. In still other embodiments, all VSCU units are provided as non-docking types and are non-interchangeable in their primary versus auxiliary abilities, that is, there is a first set of VSCU units that can only serve as primary VSCU units and a second set of VSCU units that can only serve as auxiliary VSCU units. For embodiments in which primary VSCU units are provided as non-docking types, their physical architecture may still be separable into two components for the purpose of streamlining the installation process, with one component being similar to the HVAC-coupling wall dock 702 of FIG. 7 and the second component being the main unit as shown in FIG. 7, except that the assembly is not intended for docking-style user separability after installation is complete. For convenience of description hereinbelow and so as not to unnecessarily limit the scope of the present teachings, the classification of one or more described VSCU units as being of (i) a non-docking type versus a docking type, and/or (ii) a primary type versus an auxiliary type, may not be specified, in which case VSCU units of any of these classifications may be used with such embodiments, or in which case such classification will readily be inferable by the skilled artisan from the context of the description.

[0088] FIG. 8A illustrates a conceptual diagram of an HVAC-coupling wall dock 702' with particular reference to a set of input wiring ports 851 thereof, and which represents a first version of the HVAC-coupling wall dock 702 of FIG. 7 that is manufactured and sold in a "simple" or "DIY (do-it-yourself)" product package in conjunction with the VSCU unit 100. The input wiring ports 851 of the HVAC-

coupling wall dock 702' are judiciously limited in number and selection to represent a business and technical compromise between (i) providing enough control signal inputs to meet the needs of a reasonably large number of HVAC systems in a reasonably large number of households, while also (ii) not intimidating or overwhelming the do-it-yourself customer with an overly complex array of connection points. For one embodiment, the judicious selection of input wiring ports 851 consists of the following set: Rh (24 VAC heating call switch power); Rc (24 VAC cooling call switch power); W (heating call); Y (cooling call); G (fan); and O/B (heat pump).

[0089] The HVAC-coupling wall dock 702' is configured and designed in conjunction with the VSCU unit 100, including both hardware aspects and programming aspects, to provide a DIY installation process that is simple, non-intimidating, and perhaps even fun for many DIY installers, and that further provides an appreciable degree of foolproofing capability for protecting the HVAC system from damage and for ensuring that the correct signals are going to the correct equipment. For one embodiment, the HVAC-coupling wall dock 702' is equipped with a small mechanical detection switch (not shown) for each distinct input port, such that the insertion of a wire (and, of course, the non-insertion of a wire) is automatically detected and a corresponding indication signal is provided to the VSCU 100 upon initial docking. In this way, the VSCU 100 has knowledge for each individual input port whether a wire has, or has not been, inserted into that port. Preferably, the VSCU unit 100 is also provided with electrical sensors (e.g., voltmeter, ammeter, and ohmmeter) corresponding to each of the input wiring ports 851. The VSCU 100 is thereby enabled, by suitable programming, to perform some fundamental "sanity checks" at initial installation. By way of example, if there is no input wire at either the Rc or Rh terminal, or if there is no AC voltage sensed at either of these terminals, further initialization activity can be immediately halted, and the user notified on the circular display monitor 102, because there is either no power at all or the user has inserted the Rc and/or Rh wires into the wrong terminal. By way of further example, if there is a live voltage on the order of 24 VAC detected at any of the W, Y, and G terminals, then it can be concluded that the user has placed the Rc and/or Rh wire in the wrong place, and appropriate installation halting and user notification can be made.

[0090] One particularly advantageous feature from a safety and equipment preservation perspective provided according to one embodiment relates to automated opening versus automated shunting of the Rc and Rh terminals by the VSCU unit 100. In many common home installations, instead of there being separate wires provided for Rc (24 VAC heating call switch power) and Rh (24 VAC cooling call switch power), there is only a single 24 VAC call switch power lead provided. This single 24 VAC lead, which might be labeled R, V, Rh, or Rc depending on the unique history and geographical location of the home, provides the call switch power for both heating and cooling. For such cases, it is electrically necessary for any thermostat to have its Rc and Rh input ports shunted together so that the power from that single lead can be respectively accessed by the heating and cooling call switches. However, in many other common home installations, there are separate 24 VAC wires provided for Rc and Rh running from separate transformers and, when so provided, it is important not to shunt them together

to avoid equipment damage. These situations are resolved historically by (i) the professional installer examining the HVAC system and ensuring that a shunting lead (or equivalent DIP switch setting) is properly installed or not installed as appropriate, and/or (ii) the historical presence on most thermostats of a discrete user-toggled mechanical or electromechanical switch (e.g., HEAT-OFF-COOL) to ensure that heating and cooling are never simultaneously activated. Notably, it is desired to omit any discrete mechanical HEAT-OFF-COOL in most embodiments and to eliminate the need for a professional installer for the instant DIY product version environment. Advantageously, according to an embodiment, the VSCU **100** is advantageously equipped and programmed to (i) automatically test the inserted wiring to classify the user's HVAC system into one of the above two types (i.e., single call power lead versus dual call power leads), (ii) to automatically ensure that the Rc and Rh input ports remain electrically segregated if the user's HVAC system is determined to be of the dual call power lead type, and (iii) to automatically shunt the Rc and Rh input ports together if the user's HVAC system is determined to be of the single call power lead type. The automatic testing can comprise, without limitation, electrical sensing such as that provided by voltmeter, ammeters, ohmmeters, and reactance-sensing circuitry, as well as functional detection as described further below.

[0091] Also provided at installation time according to an embodiment, which is particularly useful and advantageous in the DIY scenario, is automated functional testing of the HVAC system by the VSCU unit **100** based on the wiring insertions made by the installer as detected by the small mechanical detection switches at each distinct input port. Thus, for example, where an insertion into the W (heating call) input port is mechanically sensed at initial startup, the VSCU unit **100** actuates the furnace (by coupling W to Rh) and then automatically monitors the temperature over a predetermined period, such as ten minutes. If the temperature is found to be rising over that predetermined period, then it is determined that the W (heating call) lead has been properly connected to the W (heating call) input port. However, if the temperature is found to be falling over that predetermined period, then it is determined that Y (cooling call) lead has likely been erroneously connected to the W (heating call) input port. For one embodiment, when such error is detected, the system is shut down and the user is notified and advised of the error on the circular display monitor **102**. For another embodiment, when such error is detected, the VSCU unit **100** automatically reassigns the W (heating call) input port as a Y (cooling call) input port to automatically correct the error. Similarly, according to an embodiment, where the Y (cooling call) lead is mechanically sensed at initial startup, the VSCU unit **100** actuates the air conditioner (by coupling Y to Rc) and then automatically monitors the temperature, validating the Y connection if the temperature is sensed to be falling and invalidating the Y connection (and, optionally, automatically correcting the error by reassigning the Y input port as a W input port) if the temperature is sensed to be rising. In view of the present disclosure, the determination and incorporation of other automated functional tests into the above-described method for other HVAC functionality would be achievable by the skilled artisan and are within the scope of the present teachings. By way of example, for one embodiment there can be a statistical study done on the electrical noise patterns

associated with the different control wires and a unique or partially unique "noise fingerprint" associated with the different wires, and then the VSCU unit **100** can automatically sense the noise on each of the existing control wires to assist in the automated testing and verification process.

[0092] Also provided at installation time according to an embodiment, which is likewise particularly advantageous in the DIY scenario, is automated determination of the homeowner's pre-existing heat pump wiring convention when an insertion onto the O/B (heat pump) input port is mechanically sensed at initial startup. Depending on a combination of several factors such as the history of the home, the geographical region of the home, and the particular manufacturer and installation year of the home's heat pump, there may be a different heat pump signal convention used with respect to the direction of operation (heating or cooling) of the heat pump. According to an embodiment, the VSCU unit **100** automatically and systematically applies, for each of a plurality of preselected candidate heat pump actuation signal conventions, a cooling actuation command and a heating actuation command, each actuation command being followed by a predetermined time period over which the temperature change is sensed. If the cooling command according to the presently selected candidate convention is followed by a sensed period of falling temperature, and the heating command according to the presently selected candidate convention is followed by a sensed period of rising temperature, then the presently selected candidate convention is determined to be the actual heat pump signal convention for that home. If, on the other hand, the cooling command was not followed by a sensed period of cooling and/or the heating command was not followed by a sensed period of heating, then the presently selected candidate convention is discarded and the VSCU unit **100** repeats the process for the next candidate heat pump actuation signal convention. For one example, a first candidate heat pump actuation signal convention is (a) for cooling, leave O/B open and connect Y to Rc, and (b) for heating, connect O/B to Rh, while a second candidate heat pump actuation signal convention is (a) for cooling, connect O/B to Rc, and (b) for heating, leave O/B open and connect W to Rh. In view of the present disclosure, the determination and incorporation of other candidate heat pump actuation signal conventions into the above-described method would be achievable by the skilled artisan and are within the scope of the present teachings.

[0093] FIG. **8B** illustrates a conceptual diagram of an HVAC-coupling wall dock **702** with particular reference to a set of input wiring ports **861** thereof, and which represents a second version of the HVAC-coupling wall dock **702** of FIG. **7** that is manufactured and sold in a "professional" product package in conjunction with the VSCU unit **100**. The professional product package is preferably manufactured and marketed with professional installation in mind, such as by direct marketing to HVAC service companies, general contractors involved in the construction of new homes, or to homeowners having more complex HVAC systems with a recommendation for professional installation. The input wiring ports **861** of the HVAC-coupling wall dock **702** are selected to be sufficient to accommodate both simple and complex HVAC systems alike. For one embodiment, the input wiring ports **861** include the following set: Rh (24 VAC heating call switch power); Rc (24 VAC cooling call switch power); W1 (first stage heating call); W2 (second

stage heating call); Y1 (first stage cooling call); Y2 (second stage cooling call); G (fan); O/B (heat pump); AUX (auxiliary device call); E (emergency heating call); HUM (humidifier call); and DEHUM (dehumidifier call). For one embodiment, even though professional installation is contemplated, the HVAC-coupling wall dock **702** is nevertheless provided with small mechanical detection switches (not shown) at the respective input wiring ports for wire insertion sensing, and the VSCU unit **100** is provided with one or more of the various automated testing and automated configuration capabilities associated with the DIY package described above, which may be useful for some professional installers and/or more technically savvy do-it-yourselfers confident enough to perform the professional-model installation for their more advanced HVAC systems.

[0094] FIG. 9 illustrates an exploded perspective view of the VSCU unit **100** and an HVAC-coupling wall dock **902** according to an embodiment. The HVAC-coupling wall dock **902** is similar to the HVAC-coupling wall dock **702** of FIG. 7, supra, except that it has an additional functionality as a very simple, elemental, standalone thermostat when the VSCU unit **100** is removed, the elemental thermostat including a standard temperature readout/setting dial **972** and a simple COOL-OFF-HEAT switch **974**. This can prove useful for a variety of situations, such as if the VSCU **100** needs to be removed for service or repair for an extended period of time over which the occupants would still like to remain reasonably comfortable. For one embodiment, the elemental thermostat components **972** and **974** are entirely mechanical in nature, such that no electrical power is needed to trip the control relays. For other embodiments, simple electronic controls such as electrical up/down buttons and/or an LCD readout are provided. For other embodiments, some subset of the advanced functionalities of the VSCU unit **100** can be provided, such as elemental network access to allow remote control, to provide a sort of “brain stem” functionality while the “brain” (the VSCU unit **100**) is temporarily away.

[0095] FIGS. 10A-10C illustrate conceptual diagrams representative of advantageous scenarios in which multiple VSCU units are installed in a home **201** (or other space such as retail stores, office buildings, industrial buildings, and more generally any living space or work space having one or more HVAC systems) according to embodiments in which the home (or other space) does not have a wireless data network. For the embodiment of FIG. 10A in which the home **201** has a single HVAC system **298**, a primary VSCU unit **100** is installed and connected thereto via the control wires **298**, which an auxiliary VSCU unit **100'** is placed, by way of example, on a nightstand **1202**. The primary VSCU unit **100** and auxiliary VSCU unit **100'** are each configured to automatically recognize the presence of the other and to communicate with each other using a wireless communication protocol such as Wi-Fi or ZigBee running in an ad hoc mode.

[0096] Many advantageous capabilities are programmed into the VSCU units **100** and **100'** to leverage their communication and multi-sensing capabilities such that they jointly, in a cooperative manner, perform the many VSCU unit functionalities described herein (e.g., “learning” about the home HVAC environment, performing occupancy sensing and prediction, “learning” user comfort preferences, etc.) that do not require Internet access. By way of simple example, in one embodiment the primary VSCU unit **100** receives temperature data from the auxiliary VSCU unit **100'**

and computes an average of the two temperatures, controlling the HVAC system **299** such that the average temperature of the home **201** is maintained at the current temperature set point level. One or more additional auxiliary VSCU units (not shown) may also be positioned at one or more additional locations throughout the home and can become part the ad hoc “home VSCU network.” The scope of the present teachings not being limited to any particular maximum number of auxiliary VSCU units. Among other advantages, adding more auxiliary VSCU units is advantageous in that more accurate occupancy detection is promoted, better determination of spatial temperature gradients and thermal characteristics is facilitated, and additional data processing power is provided.

[0097] Preferably, the primary/auxiliary VSCU units **100/100'** are programmed to establish a master/slave relationship, wherein any conflicts in their automated control determinations are resolved in favor of the master VSCU unit, and/or such that any user inputs at the master unit take precedence over any conflicting user inputs made at the slave VSCU unit. Although the primary VSCU unit **100** will likely be the “master” VSCU unit in a beginning or default scenario, the status of any particular VSCU unit as a “master” or “slave” is not dictated solely by its status as a primary or auxiliary VSCU unit. Moreover, the status of any particular VSCU unit as “master” or “slave” is not permanent, but rather is dynamically established to best meet current HVAC control needs as can be best sensed and/or predicted by the VSCU units. For one preferred embodiment, the establishment of “master” versus “slave” status is optimized to best meet the comfort desires of the human occupants as can be best sensed and/or predicted by the VSCU units. By way of example, if each VSCU unit is sensing the presence of multiple occupants in their respective areas, then the primary VSCU unit is established as the master unit and controls the HVAC system **299** such that the average temperature reading of the two VSCU units is maintained at the current set point temperature according to a currently active template schedule (i.e., a schedule of time intervals and set point temperatures for each time interval). However, if no occupants in the home are sensed except for a person in the bedroom (as sensed by the auxiliary VSCU unit **100'** which is positioned on a nightstand in this example), then the auxiliary VSCU unit **100'** becomes the “master” VSCU unit, which commands the “slave” VSCU unit **100** to control the HVAC system **299** such that the temperature in the bedroom, as sensed by the “master” unit, stays at a current set point temperature.

[0098] Many other automated master/slave establishment scenarios and control determinations based on human behavioral studies, statistical compilations, and the like are within the scope of the present teachings. In one example, the master-slave determination can be made and/or influenced or supported based on an automated determination of which thermostat is in a better place to more reliably govern the temperature, based on historical and/or testing-observed cycling behavior or other criteria. For example, sensors that are immediately over a heat register will not be reliable and will keep cycling the furnace too often. Nodes that are in bathrooms and in direct sunlight are also less reliable. When there are multiple sensors/nodes, there is an algorithm that determines which one is more reliable, and there is master-slave determination based on those determinations. For some related embodiments, VSCU units automatically

determined to be near bathrooms and dishwashers can be assigned custom templates designed to at least partially ameliorate the adverse effects of such placement.

[0099] The establishment of master-slave status for the primary/auxiliary VSCU units **100/100'** can also be based upon human control inputs. By way of example, if each VSCU unit is sensing the presence of multiple occupants in their respective areas, and then a user manually changes the current set point temperature on one of the two units, that VSCU unit can output the question, "Master Override?" on its circular display monitor **102** (analogous to the query capability shown at FIGS. **5A-5B**, supra), along with two answer options "Yes" and "Let VSCU Decide," with the latter being circled as the default response. On the other hand, if the two VSCUs collectively sense only the presence of that user in the home and no other occupants, then whichever unit was controlled by the user can be established as the master unit, without the need for asking the user for a resolution. By way of further example, the VSCU units **100/100'** can be programmed such that the establishment of master/slave status can be explicitly dictated by the user at system setup time (such as during a setup interview), or at a subsequent configuration time using the menu-driven user interface (see FIGS. **4-5B**, supra) of one of the two VSCU units. When combined with lockout functionality and/or user-specific identification as described elsewhere in the instant specification, this can be particularly useful where Mom and Dad wish to control the house temperature at night using the VSCU unit in their bedroom, and not for their teenage daughter to control the house temperature at night using the VSCU unit in her bedroom.

[0100] Also provided according to an embodiment is an ability for the multiple VSCU units to judiciously share computing tasks among them in an optimal manner based on power availability and/or circuitry heating criteria. Many of the advanced sensing, prediction, and control algorithms provided with the VSCU unit are relatively complex and computationally intensive, and can result in high power usage and/or device heating if carried out unthrottled. For one embodiment, the intensive computations are automatically distributed such that a majority (or plurality) of them are carried out on a subset of the VSCU units known to have the best power source(s) available at that time, and/or to have known to have the highest amount of stored battery power available. Thus, for example, because it is generally preferable for each primary VSCU unit not to require household AC power for simplicity of installation as well as for equipment safety concerns, the primary VSCU unit **100** of FIG. **10A** will often be powered by energy harvesting from one or more of the 24 VAC call relay power signals, and therefore may only have a limited amount of extra power available for carrying out intensive computations. In contrast, a typical auxiliary VSCU unit may be a nightstand unit that can be plugged in as easily as a clock radio. In such cases, much of the computational load can be assigned to the auxiliary VSCU unit so that power is preserved in the primary VSCU unit. In another embodiment, the speed of the intensive data computations carried out by the auxiliary VSCU unit (or, more generally, any VSCU unit to which the heavier computing load is assigned) can be automatically throttled using known techniques to avoid excessive device heating, such that temperature sensing errors in that unit are avoided. In yet another embodiment, the temperature sensing functionality of the VSCU unit(s) to which the heavier

computing load is assigned can be temporarily suspended for an interval that includes the duration of the computing time, such that no erroneous control decisions are made if substantial circuitry heating does occur.

[0101] Referring now to FIG. **10B**, it is often the case that a home or business will have two or more HVAC systems, each of them being responsible for a different zone in the house and being controlled by its own thermostat. Thus, shown in FIG. **10B** is a first HVAC system **299** associated with a first zone Z1, and a second HVAC system **299'** associated with a second zone Z2. According to an embodiment, first and second primary VSCU units **100** and **100''** are provided for controlling the respective HVAC units **299** and **299'**. The first and second primary VSCU units **100** and **100''** are configured to leverage their communication and multi-sensing capabilities such that they jointly, in a cooperative manner, perform many cooperative communication-based VSCU unit functionalities similar or analogous to those described above with respect to FIG. **10A**, and still further cooperative VSCU unit functionalities for multi-zone control as described herein. As illustrated in FIG. **10C**, the cooperative functionality of the first and second primary VSCU units **100** and **100''** can be further enhanced by the addition of one or more auxiliary VSCU units **100'** according to further embodiments.

[0102] It is to be appreciated that there are other multiple-thermostat scenarios that exist in some homes other than ones for which each thermostat controls a distinct HVAC system, and that multiple VSCU unit installations capable of controlling such systems are within the scope of the present teachings. In some existing home installations there may only be a single furnace or a single air conditioning unit, but the home may still be separated into plural "zones" by virtue of actuated flaps in the ductwork, each "zone" being controlled by its own thermostat. In such settings, two primary VSCU units can be installed and configured to cooperate, optionally in conjunction with one or more auxiliary VSCU units, to provide optimal HVAC system control according to the described embodiments.

[0103] FIG. **10D** illustrates cycle time plots for two HVAC systems in a two-zone home heating (or cooling) configuration, for purposes of illustrating an advantageous, energy-saving dual-zone control method implemented by dual primary VSCU units such as the VSCU units **100** and **100''** of FIGS. **10B-10C**, according to an embodiment. According to an embodiment, the VSCU units **100** and **100''** are configured to mutually cooperate such that their actuation cycle times are staggered with respect to each other to be generally about 180 degrees (TT radians) out of phase with each other. Shown in FIG. **10D** are two cycle time plots **1002** and **1004** that are identical with respect to the total percentage of time (e.g., the total number of minutes in an hour) that the heating (or cooling) units are "ON". For two adjacent zones such as Z1 and Z2 that are in thermal communication with each other, it has been found that running their heating (or cooling) units without mutually controlled operation can allow the system to stray into a sort of high frequency resonance response (FIG. **10D**, plot **1002**) characterized by rapid temperature fluctuations between the swing points and a relatively high number of cycles per hour, which can reduce energy efficiency due to inertial start-up and shut-down losses. In contrast, when purposely controlled to be mutually out of phase with each other according to an embodiment, it has been found that a more stable and lower

frequency response behavior occurs (FIG. 10D, plot 1004) characterized by fewer cycles per hour and correspondingly increased energy efficiency.

[0104] For one embodiment that is particularly advantageous in the context of non-network-connected VSCU units, the VSCU unit is configured and programmed to use optically sensed information to determine an approximate time of day. For a large majority of installations, regardless of the particular location of installation in the home (the only exceptions being perhaps film photography development labs or other purposely darkened rooms), there will generally be a cyclical 24-hour pattern in terms of the amount of ambient light that is around the VSCU unit. This cyclical 24-hour pattern is automatically sensed, with spurious optical activity such as light fixture actuations being filtered out over many days or weeks if necessary, and optionally using ZIP code information, to establish a rough estimate of the actual time of day. This rough internal clock can be used advantageously for non-network-connected installations to verify and correct a gross clock setting error by the user (such as, but not limited to, reversing AM and PM), or as a basis for asking the user to double-check (using the circular display monitor 102), or to establish a time-of-day clock if the user did not enter a time.

[0105] FIG. 11 illustrates a conceptual diagram representative of an advantageous scenario in which one or more VSCU units are installed in a home that is equipped with WiFi wireless connectivity and access to the Internet (or, in more general embodiments, any kind of data connectivity to each VSCU unit and access to a wide area network). Advantageously, in addition to providing the standalone, non-Internet connected functionalities described for FIGS. 10A-10C and elsewhere herein, the connection of one or more VSCU units to the Internet triggers their ability to provide a rich variety of additional capabilities. Shown in FIG. 11 is a primary VSCU unit 100 and auxiliary VSCU unit 100' having WiFi access to the Internet 1199 via a wireless router/Internet gateway 1168. Provided according to embodiments is the ability for the user to communicate with the VSCU units 100 and/or 100' via their home computer 1170, their smart phone 1172 or other portable data communication appliance 1172', or any other Internet-connected computer 1170'.

[0106] FIG. 12 illustrates a conceptual diagram of a larger overall energy management network as enabled by the VSCU units and VSCU Efficiency Platform described herein and for which one or more of the systems, methods, computer program products, and related business methods of one or more described embodiments is advantageous applied. The environment of FIG. 12, which could be applicable on any scale (neighborhood, regional, state-wide, country-wide, and even world-wide), includes the following: a plurality of homes 201 each having one or more network-enabled VSCU units 100; an exemplary hotel 1202 (or multi-unit apartment building, etc.) in which each room or unit has a VSCU unit 100, the hotel 1202 further having a computer system 1204 and database 1206 configured for managing the multiple VSCU units and running software programs, or accessing cloud-based services, provisioned and/or supported by the VSCU data service company 1208; a VSCU data service company 1208 having computing equipment 1210 and database equipment 1212 configured for facilitating provisioning and management of VSCU units, VSCU support equipment, and VSCU-related soft-

ware and subscription services; a handyman or home repair company 1214 having a computer 1216 and database 1218 configured, for example, to remotely monitor and test VSCU operation and automatically trigger dispatch tickets for detected problems, the computer 1216 and database 1218 running software programs or accessing cloud-based services provisioned and/or supported by the VSCU data service company 1208; a landlord or property management company 1220 having a computer 1222 and database 1224 configured, for example, to remotely monitor and/or manage the VSCU operation of their tenants and/or clients, the computer 1222 and database 1224 running software programs, or accessing cloud-based services, provisioned and/or supported by the VSCU data service company 1208; and a utility company 1226 providing HVAC energy to their customers and having computing equipment 1228 and database equipment 1230 for monitoring VSCU unit operation, providing VSCU-usable energy usage data and statistics, and managing and/or controlling VSCU unit set points at peak load times or other times, the computing equipment 1228 and database equipment 1230 running software programs or accessing cloud-based services provisioned and/or supported by the VSCU data service company 1208.

[0107] According to one embodiment, each VSCU unit provides external data access at two different functionality levels, one for user-level access with all of the energy gaming and home management functionality described herein, and another for an installer/vendor ("professional") that lets the professional "check in" on your system, look at all the different remote sensing gauges, and offer to provide and/or automatically provide the user with a service visit.

[0108] FIGS. 13A-13B and FIGS. 14A-14B illustrate examples of remote graphical user interface displays presented to the user on their data appliance for managing their one or more VSCU units and/or otherwise interacting with their VSCU Efficiency Platform equipment or data according to an embodiment. For one embodiment, one or more of the displays of FIGS. 13A-14B is provided directly by a designated one of the user's own VSCU units, the user logging directly into the device in the same way they can log on to their own home router. For another embodiment, one or more of the displays of FIGS. 13A-14B is displayed when the user logs on to a web site of a central, regional, or local service provider, such as the VSCU data service provider 1208 of FIG. 12, supra, which in turn communicates with the user's VSCU unit(s) over the Internet. Although the scope of the present teachings is not so limited, the examples of FIGS. 13A-13B are particularly suitable for display in a conventional browser window, the example of FIG. 14A is particularly suitable for display on a smaller portable data device such as an iPhone, and the example of FIG. 14B is particularly suitable for display on a larger portable data device such as an iPad. According to one embodiment, the remote user interface includes a relatively large image that is representative of what the user would actually see if they were standing in front of their VSCU unit at that time. Preferably, the user interface allows the user to enter "left ring rotate", "right ring rotate", and "inward press" commands thereon just as if they were standing in front of their VSCU unit, such as by suitable swipes, mouse click-and-drags, softbuttons, etc. The remote user interface can also graphically display, and allow the user to graphically manipulate, the set point temperatures and/or time interval limits of their template schedule(s) based on suitable graphs,

plots, charts, or other types of data display and manipulation. The remote user interface can also graphically display a variety of other information related to the user's energy usage including, but not limited to, their utility bills and historical energy usage costs and trends, weather information, game-style information showing their performance against other similarly situated households or other suitable populations, and helpful hints, advice, links, and news related to energy conservation.

[0109] Provided according to some embodiments is a direct e-mail or text message command functionality for the remote user, such that they can send a brief control command to an e-mail address of the VSCU unit without being required to perform the full remote login and enter the command using the more complete user interfaces of FIGS. 13A-14B. The remotely sent commands can be very brief and consistent with a small list of common commands such as "Heat 78" or "Heat 78 @ 8:00 PM". For another embodiment, a natural language interpretation capability is provided, such that a natural language e-mail can be sent to the VSCU's e-mail address, such as "I am away now, go into away mode" or "I will return at 8 PM tonight instead of 6 PM as usual so keep it at 65 until then and preheat to 72 for when I get home."

[0110] As could be realized by a person skilled in the art upon reading the present disclosure and based on system components and methods disclosed hereinabove and illustrated in the accompany drawings, provided in conjunction with the VSCU 100 and/or the VSCU Efficiency Platform are one or more devices, features or functionalities as described further hereinbelow.

[0111] According to some embodiments, various systems and methods for detecting occupancy of an enclosure, such as a dwelling, are provided by one or more of the installed VSCU units in the manner described in Ser. No. 12/881,430, supra. Examples include: detecting motion, monitoring communication signals such as network traffic and/or mobile phone traffic, monitoring sound pressure information such as in the audible and/or ultrasonic ranges, monitoring utility information such powerline information or information from Smart Meters, monitoring motion in close proximity to the sensor, monitoring infrared signals that tend to indicate operation of infrared controllable devices, sudden changes in ambient light, and monitoring indoor air pressure (to distinguish from pressure mats used in security applications) information which tends to indicate occupancy.

[0112] According to one embodiment that represents a combination of business method and technical method, acoustic monitoring is used to facilitate detect occupancy sensing, but the acoustic-to-electrical transducer equipment is purposely hampered in its ability to convert the acoustic energy of human speech into electrical form in a way that the actual human speech could be extracted therefrom. Stated differently, while the acoustic monitoring would be able to detect the presence of audible human activity, including speech, there would be no possibility of any actual words being "heard" by the VSCU unit even if those acousto-electric patterns were somehow recorded. In this way, privacy concerns of occupants and civil liberty groups are not problematic to the rollout and acceptance of the VSCU units and the VSCU Efficiency Platform. In one business method, this feature is actually used as a selling point for the product, being marketed with a moniker such as "privacy-preserving pressure wave sensing technology" or the like.

[0113] Particular examples of the above-described occupancy detection methods are now presented by way of example and not by way of limitation. One occupancy detection method is to incorporate a Wi-Fi sniffer capability into the VSCU units, i.e., when a lot of data traffic is seen on the user's home network, a conclusion can be made or supported that the house is occupied. Conversely, if the VSCU units are receiving remote control commands or other communications from a known user using a data communication device whose IP address is different than that of the home network, or a cell phone whose GPS location is different than that of the house, then a determination can be made or supported that that known user is not in the house. Other local electromagnetic signals associated with local user activity, such as cordless phone signals in the 900 MHz and 5.8 GHz, can also be used to make or support a determination that the house is occupied. Another occupancy detection method incorporated into the VSCU units is to sense infrared television remote control radiation as emitted from television remote control units. Another occupancy detection method uses the temperature and humidity readings of the VSCU units themselves. For example, a temperature/humidity change accompanies a pressure change, it is more likely that somebody opened an outside door and is therefore entering or leaving the building. Another occupancy detection method includes the consideration of user controls onto the VSCU units themselves. In a simplest example, if someone just adjusted the thermostat, there is certainly someone present in the house. In a more complex example, if a user just turned down the thermostat temperature in wintertime, and this is followed by a sensed sudden pressure change, then a determination can be made or supported that the occupants are leaving the building for some period of time. Also, if there are controls being made over the internet, by a cell phone or laptop or whatever, and the IP address corresponds to that of the home network, that you can conclude that the user is entering that information from inside the home, and therefore that the house is occupied.

[0114] For some embodiments, current energy-saving decisions based on current outside temperatures and predicted outside temperatures are provided. For example, if it is a really hot day but it is predicted that the outside temperature will be going down precipitously quite soon, the set point temperature may be raised at that time, or the amount of permissible swing raised or other action that causes a reduction in the number of cycles per hour. As another example, for a place like Arizona, if it is 40 degrees outside at 6 AM but it is expected that the outside temperature will be 100 degrees at 10 AM, the heat is not turned on at 6 AM even if the inside temperature is below the heating set point.

[0115] For some embodiments, anticipatory heating or cooling based on expected energy cost changes is provided. If a determination is made that the instantaneous cost of electricity will go up in a few hours based on current weather patterns and/or other aggregated data, the immediate cooling set point is lowered, and the set points for the subsequent hours are raised (and/or the acceptable swing is increased) so that more energy is used now and less energy is used later. Another concrete example is "spare the air" days which can be anticipated based on stored information and the recent and forecasted outside temperatures.

[0116] For some embodiments, centralized web-based communication with internet-connected VSCU units is provided to avoid blackouts during a heat wave. For “opt-in” VSCU-enabled customers who have so elected in exchange for financial incentives, the utility company (or VSCU data service provider on their behalf, optionally for a negotiated fee) can automatically issue a command that those VSCU units raise their set point temperatures by 5 degrees and it will automatically happen.

[0117] For some embodiments, there is provided user control over energy saving aggressiveness. Regarding the internal decisions made by the VSCU units, (e.g., weather-specific set points, anticipatory heating/cooling, compliance with external overrides, etc.), the user can be allowed to set this aggressiveness level during their setup interview, and also can be allowed change it later on. The setting can be “very aggressive savings,” “moderate savings,” “none,” and so forth. One example of automated weather-specific set point is that, for relatively cool days in which the outside temperature might be 84, the cooling set point is automatically set to 78, whereas if the outside temperature is greater than 95, the cooling set point is automatically set to 82. For some embodiments, the need for an increased (or decreased) level of aggressiveness can be automatically detected by the VSCU units and recommended to the user (e.g., on the circular user display **102** or on the remote control interface). In further embodiments, the level of aggressiveness can be automatically increased (or decreased) by the VSCU units, which then simply notify the user (e.g., on the circular user display **102** or on the remote control interface) that the aggressiveness change has been implemented.

[0118] According to some embodiments, the VSCU unit (s) installed in any particular home (or more generally “enclosure”) are automatically able to characterize its HVAC-related characteristics such as thermal mass, heating capacity, cooling capacity, and thermal conductivity metrics between the inside and the outside, for example using one or more methods described in Ser. No. 12/881,463, *supra*. For one embodiment, this characterization is made by operating the HVAC in various predetermined heating and cooling modes for predetermined time intervals at initial system installation testing, or at some other point in time, and then processing (i) the resultant temperature (and optionally humidity) profiles as sensed at the one or more VSCU units in conjunction with (ii) extrinsic information, such as building size, square footage, and so forth as provided by (a) the user during the congenial setup interview (or a separate interview) and/or (b) automatically scraped from public data sources, such as zillow.com, based on the home address as provided by the user. The installed VSCU units, optionally in conjunction with information provided by a VSCU data service provider, are configured to model the thermal and thermodynamic behavior of the enclosure for use in optimizing energy usage while also keeping the occupants comfortable. According to some embodiments, weather forecast data predicting future weather conditions for a region including the location of the enclosure are received. A model for the enclosure that describes the behavior of the enclosure for use by the control system is updated based on the weather forecast data. The HVAC system for the enclosure is then controlled using the updated model for the enclosure.

[0119] According to some embodiments, the weather forecast data includes predictions more than 24 hours in the

future, and can include predictions such as temperature, humidity and/or dew point, solar output, precipitation, wind and natural disasters. According to some embodiments the model for the enclosure is updated based also on historical weather data such as temperature, humidity, wind, solar output and precipitation. According to some embodiments, the model for the enclosure is updated based in part on the occupancy data, such as predicted and/or detected occupancy data. The model for the enclosure updating can also be based calendar data. According to some embodiments, the model for the enclosure is updated based also on the data from the one or more weather condition sensors that sense current parameters such as temperature, humidity, wind, precipitation, and/or solar output. According to some embodiments, the locations of the weather condition sensors can be automatically detected. According to some embodiments, the model for the enclosure is updated based also on an enclosure model stored in a database, and/or on enclosure information from a user.

[0120] According to some embodiments, the enclosure modeling includes actively inducing a change in the internal environment of the enclosure, measuring a response of the internal environment of the enclosure from the induced change, and updating a model for the enclosure that describes behavior of the enclosure for use by the control system based at least in part on the measurement of the response from the induced change. According to some embodiments the change is actively induced primarily for purposes of updating the model for the enclosure, rather than for conditioning the internal environment of the enclosure. The change can be actively induced in response to input by a user, or it can be induced automatically by the VSCU units for example due to the type of enclosure or a change in season. The change is preferably induced at a time when the enclosure is likely to be unoccupied.

[0121] As used herein the term “model” refers generally to a description or representation of a system. The description or representation can use mathematical language, such as in the case of mathematical models. Examples of types of models and/or characteristics of models, without limitation, include: lookup tables, linear, non-linear, deterministic, probabilistic, static, dynamic, and models having lumped parameters and/or distributed parameters. As used herein the terms “profile,” “structure profile,” “structure model,” “enclosure profile,” “enclosure model,” “building profile,” “building model” and the like refer to any numerical or mathematical description or models of at least some of thermodynamic behavioral characteristics of a building, enclosure and/or structure, for example for use in HVAC applications. As used herein the term “sensor” refers generally to a device or system that measures and/or registers a substance, physical phenomenon and/or physical quantity. The sensor may convert a measurement into a signal, which can be interpreted by an observer, instrument and/or system. A sensor can be implemented as a special purpose device and/or can be implemented as software running on a general-purpose computer system. As used herein the term “structure” includes enclosures and both non-buildings and buildings. As used herein the term “enclosure” means any structure having one or more enclosed areas, and also includes any building. Examples of structures and enclosures include, but are not limited to: residential buildings, commercial buildings and complexes, industrial buildings, sites and installations, and civil constructions. As used

herein the term “thermodynamic” includes all state variables that can be used to characterize a physical system. Examples of thermodynamic variables include, but are not limited to: pressure, temperature, airflow, humidity, and particulate matter.

[0122] According to some embodiments, the VSCU units are configured and programmed to automatically determine, based on sensed performance data, when one or more air filters of the HVAC system (see, for example, filter 246 of FIG. 2B, *supra*) needs to be changed. For one embodiment, this is performed using only the multi-sensor capability provided on the VSCU units themselves, such as by recognizing a gradual pattern over time that it is taking the house longer to heat up or cool down than normal. For other embodiments, additional sensors are provided, such as air flow sensors installed in one or more ventilation ducts, the sensors being equipped which communicate wirelessly with the VSCU units such as by using the low-power ZigBee protocol (or other wireless protocol), such that a gradual pattern over time of slowing airflow can be sensed that is indicative of a clogged air filter. For still other embodiments, custom filters that are specially equipped with air flow sensors or other sensors whose readings can be used to detect clog-related behavior are provided, and are equipped to communicate wirelessly with the VSCU units such as by using the low-power ZigBee protocol. For one embodiment, the additional sensors are power using energy harvesting technology, such as by harvesting energy from oscillations or vibrations caused by airflow thereby. In one embodiment, an e-mail, text message, or machine audio voice call is sent to the customer to alert them of the need for a new filter. In one embodiment, a business method is provided in which the need for a new filter is automatically communicated to an external service provider, such as the handyman/home repair company 1214 of FIG. 12, *supra*, which triggers an automated maintenance ticket event, or such as the VSCU data service provider 1208 of FIG. 12 or a commercial warehouse, which triggers an automated shipping of a new filter to the customer’s doorstep.

[0123] For other embodiments, similar automated detection, customer alerting, and maintenance event triggering as described in the preceding paragraph is provided for any type of HVAC system anomaly such as, but not limited to, the general failure of the house to heat or cool to the set point temperature or the clogging of a particular duct in the house (e.g., its airflow readings are grossly different than that of other sensors in other ducts). For one embodiment, acoustic signature sensing can be used to detect system anomalies, which takes advantage of the fact that a system’s heating and cooling start up and shut down activity will often be characterized by unique yet repeatable noise signatures (e.g., fan noises, particular creaks and moans for older installations, etc.), and that an onset of a variation in these noise signatures can be indicative of a system anomaly. In still other embodiments, baseline electrical noise patterns can be associated with each different HVAC control wire and stored, and then the VSCU unit 100 can automatically detect a potential system anomaly by sensing a significant variation in the noise pattern of one or more of the HVAC control wires.

[0124] For still other embodiments, other types of auxiliary sensors related to HVAC functionality, including both self-powering energy-harvesting sensors and those that get their power from other sources such as AC or batteries, are

provided that are capable of ZigBee communication and are compatible with the VSCU Efficiency Platform, and used to sense system anomalies and/or maintenance-related information that the VSCU units can then act upon. In one example, a replacement cap for an outside propane or heating oil tank is provided that is capable of wirelessly sending fuel levels to the VSCU units, the cap optionally being powered by energy harvesting from the wind. In another example, a replacement cap for a coolant loop check valve is provided that is capable of wirelessly sending coolant loop pressure readings or a low-coolant alarms to the VSCU units, the cap optionally being powered by energy harvesting from compressor vibrations or other air conditioning system vibrations.

[0125] According to some embodiments, the initial setup interview includes the following interactive questioning flow. The VSCU unit display format will look similar to FIGS. 5A-5B, with a first prompt being “Set-up VSCU for a: {Home} {Business}” where the notional “{X}” is used herein to denote that “X” is one of the user choices. If the user chooses “Home” then a first set of questions is asked, whereas if the user chooses “Business” then a second set of questions is asked. The first set of questions proceeds as follows: “Are you home at noon? {Usually} {Not Usually}” followed by “Are you home at 4 PM? {Usually} {Not Usually}” followed by “Do you have electric heat?” {Electric} {Not Electric} {I Don’t Know}” followed by a request for location information such as the ZIP code and street address of the home. The second set of questions applicable to a business proceeds as follows: “Is this business open evenings? {Usually} {Not Usually}” followed by “Open Saturdays? {Usually} {Not Usually}” followed by “Open Sundays? {Usually} {Not Usually}” followed by “Do you have electric heat?” {Electric} {Not Electric} {I Don’t Know}” followed by a request for location information such as the ZIP code and the street address of the business. It is to be appreciated that the above questions and selective answers are presented by way of example only, and not by way of limitation, and that many other questions and selective answers can be provided in addition to, or as an alternative to, these examples without departing from the scope of the present teachings.

[0126] According to some embodiments, the ZIP code of the household or business is asked at a point near the beginning of the setup interview, and then different setup interview questions can be asked that are pre-customized for different geographical regions based on the ZIP code. This is useful because the best set of interview questions for Alaskan homes or businesses, for example, will likely be different than the best set of interview questions for Floridian homes, for example.

[0127] According to some embodiments, the user’s responses to the questions at the initial setup interview are used to automatically “snap” that household onto one of a plurality of pre-existing template schedules, i.e. a schedule of time intervals and set point temperatures for each time interval, stored in the VSCU unit and corresponding to some of the most common household or business paradigms. Examples of different household paradigms, each of which can have its own pre-existing template schedule, can include: working couple without kids; working couple with infants or young children; working family; working spouse with stay-at-home spouse; young people with active night-life who work freelance from home; retired couple; and solo

retiree. The template schedules to which the household is “snapped” at system initialization based on the setup interview (or at some other time upon user request) serve as convenient starting points for the operational control of the HVAC system for a large number of installations. The users can then modify their template schedules (e.g., using the user on the VSCU unit itself, the web interface, or smart phone interface, etc.) to suit their individual desires. The VSCU units may also modify these template schedules automatically based on learned occupancy patterns and manual user temperature control setting patterns. By way of nonlimiting example, a typical template schedule for a working family would be, for heating in wintertime “Mo Tu We Th Fr: [7:00 68] [9:00 62] [16:00 68] [22:00 62] Sa Su [7:00 68] [22:00 62]” (meaning that, for all five weekdays the set point temperatures will be 68 degrees from 7 AM-9 AM, then 62 degrees from 9 AM-4 PM, then 68 degrees from 4 PM-10 PM, then 62 degrees from 10 PM-7 AM, and that for both weekend days the set point temperatures will be 68 degrees from 7 AM-10 PM, then 62 degrees from 10 PM-7 AM), and for cooling in summertime, “Mo Tu We Th Fr: [7:00 75] [9:00 82] [16:00 78] [22:00 75] Sa Su [7:00 75] [9:00 78] [22:00 75].” In other embodiments, permissible swing temperature amounts, humidity ranges, and so forth can also be included in the template schedules.

[0128] For one embodiment, template schedules can be shared, similar to the way iTunes music playlists can be shared, optionally in a social networking context. For example, a user can post their template schedule on their Facebook or MySpace page for other people to download. Custom or standardized template schedules can be provided based on house size or ZIP code. Templates schedules will preferably be calendar-based (e.g., scheduled differently for Christmastime when more people are home). This is superior to prior art scheduling in which all customers everywhere are given the same schedule or the same set of strictures within which to program their schedule.

[0129] For one embodiment, customized installation instructions can be provided to the user based on their previously installed thermostat model. The user can go to the VSCU manufacturer’s web site and enter their current thermostat make and model, and then a custom set of instructions based on the known wiring pattern of that model are provided for viewing, download, and printing. Optionally, customized videos on the user’s computer or smart phone are provided. For one more advanced preferred embodiment, the user can take a photo of their current thermostat and submit it to the VSCU manufacturer’s web site where its make and model will be automatically determined using machine vision techniques, so that the user does not need to figure out their current make and model.

[0130] For one embodiment, the VSCU units are configured and programmed to automatically detect and correct for exposure of one or more VSCU units to direct sunlight. Although users are advised, as with any thermostat, to avoid placing the VSCU units in areas of direct sunlight, it has been empirically found that many will place a VSCU unit where it will get direct sunlight for at least part of the day during at least a part of the year. Direct sunlight exposure can substantially confound HVAC system effectiveness because the temperature will be sensed as being incorrectly high, for example, the VSCU unit will measure 80 degrees when it is really only 68 degrees in the room. According to an embodiment, the one or more VSCU units are pro-

grammed to detect a direct sunlight exposure situation, such as by temperature tracking over periods of several days to several weeks and then filtering for periodic behaviors characteristic of direct sunlight exposure, and/or filtering for characteristic periodic discrepancies between multiple VSCU units. Correction is then implemented using one more correction methods.

[0131] By way of example and not by way of limitation, one simple method for correction for heating and cooling is to apply a direct numerical bias to the sunlight-bathed sensor reading during the direct sunlight interval based on knowledge from ambient light sensor reading, current time, current exact or approximate date, previous heat/cool cycle duration, temperature changes, and humidity changes. The VSCU unit learns from the first couple of occurrences the time and duration at which the sunlight falls on the device. For example, if the sunlight hit the sensor between 9:00-9:15 AM the day before in the spring, it will look for the sunlight occurrence around 8:58-9:13 AM the next day. If the heat/cool cycle is not needed during this time, one way to correct it would be to make an estimate of the temperature when the effect of the direct sunlight diminishes and make an interpolation between the current temperature and the predicted temperature between 8:58-9:13 AM. If the heat/cool cycle needs to be on, it learns from the previous cycles and make an estimate of cycle duration and temperature changes. It may use humidity and other sensors (in the device itself or in another device nearby) to verify the heat/cool cycle is on and remains on for an appropriate amount of time.

[0132] For some embodiments, the VSCU units provide optimal yet energy saving control based on human comfort modeling. In one example, if the user keeps turning up the thermostat above the set points provided in the template schedule, then VSCU units learn that and increase the set points in their template schedule. By way of further example, if the outside temperature has been 80 degrees for many days, and then for one day it is suddenly 60 degrees, the VSCU unit will keep the house at a warmer set point than if the outside temperature has been 60 degrees for many days. The reason is that humans are known to get accustomed to outside weather patterns that have been prevailing for a period of time, and so are more sensitive to sudden temperature changes than to longer term temperature changes. For example, if it has been 60 degrees for many days, the people will be more likely to dress warmer on an ongoing basis (put on sweatshirts and the like) and so the set point can be gradually lowered and/or the amount of swing can be gradually raised to save energy.

[0133] As another example of optimal yet energy saving control based on human comfort modeling, for one embodiment the VSCU is configured to perform in an advantageous way based on a predicted return time of the occupant. For this embodiment, the idea is to purposely pre-heat (or pre-cool in a counterpart example) the house, but only to a limited extent, perhaps only 60% of the difference between the “Away” and “Occupied” set points, until there is actually an occupancy detection event. For example, if the “Away” set point temperature is 64, and the “Occupied” set point temperature is 74, then the VSCU units start heating the house 20 minutes before the expected home arrival time, but only do so until the house heats up to 70 degrees. Then, when the occupant walks through the door, the remaining 4 degree heat-up is triggered by the VSCU units. In addition to saving energy, this can also be pleasing to the senses of

the returning occupant, because the heat will be blowing, which gives a sense of hominess and of feeling welcome, a sense of “it is great to be home, it is so nice.” Moreover, it has been found that people are a lot more tolerant to the lower temperature immediately after they have walked through door than if they have been home for a while.

[0134] As another example of optimal yet energy saving control provided by the VSCU units, there is a control algorithm found to provide good results for situations of extended but finite opening of an external door, such as cases in which an occupant is bringing in the Christmas Tree or the groceries. In particular, if it usually takes 5 minutes to heat from 68 to 72, and it suddenly has taken 5 minutes just to heat from 68 to 69 or there has been no change at all from 68 in 5 minutes of heating, the VSCU unit will immediately turn off the heat for 10-15 minutes, and then try again to raise the temperature back to 72, under the possibility that the anomaly was temporary. And if it was indeed temporary, then the situation has resolved itself. But if the failure to heat up happens again, then there can be an alarm (or text message) that requests the user’s attention, and if there is no response from the user the system is shut down because there is obviously something wrong. An e-mail message can be sent to the user such as “We have ruled out these things x-y-z from our sensor logs, maybe there is an outside door open or a-b-c is wrong.”

[0135] For another embodiment, there is provided a combined business and technical method relating to the “learning” process of the VSCU unit **100**. The VSCU units are programmed to provide substantial “learning” about user occupancy and temperature control patterns. The user will be advised at various times, such as by remote access, e-mail, SMS, VSCU unit display, etc., regarding the progress of the learning (e.g., “your occupancy information is 60 percent learned”). However, there will also be an ability for the users to turn off the learning function because they might not be comfortable with it. In one embodiment, the VSCU system will “act” like it is not learning (such as by stopping the progress messages), but will actually still be learning in the background, running in a simulation mode and continue to compile the learning data. Then, after some period has passed, the VSCU unit can compute the energy cost difference between the actual model it was running, versus the simulation model it was running in the background. If there is a substantial difference of “X” dollars, the user can be shown or sent a message such as, “You could have saved \$44 if you had enabled learning-driven control, are you sure that you do not want to turn it on now?”

[0136] For another embodiment, there is provided a combined business and technical method in which users are offered a subscription service by a VSCU data service provider. As the VSCU data service provider comes up with new types of algorithms, they can offer VSCU unit customers a subscription to an external control/optimization service. As part of the offering process, the VSCU data service provider can run the new algorithms on the historical internal and external temperature data for that customer, and then say to them (by VSCU unit display or remote access display, for example), “If you had subscribed to this optimization service, you would have saved \$88 last year”. Similar offerings can be made for discrete firmware version upgrades, e.g., “If you had purchased VSCU unit software

version 2.0 instead of staying with version 1.0, you would have saved \$90. Would you like to buy version 2.0 now for \$20?”

[0137] For another embodiment, there is provided a combined business and technical method in which users are given advisory messages (by VSCU unit display or remote access display, for example) such as follows: “A VSCU-capable house in your ZIP code having the same size as your house spent \$1000 for heating and cooling, whereas you spent \$2000. You may have a leak or weather-stripping problem. You may wish to call ABC HVAC Service Company at 650-555-1212 who can do an energy audit to help you figure out what is wrong.”

[0138] For another embodiment, the VSCU units are programmed and configured to provide the user with the ability to control their HVAC system exclusively on the basis of an HVAC budget rather than on target temperature settings. The user simply enters a dollar amount per month that they want to spend on HVAC, and the VSCU automatically adjusts the settings such that the selected amount will be spent, in the most comfortable (or least uncomfortable) manner possible according to the user’s known occupancy patterns and preferences. Optionally, the user can manually turn the set temperature up or down from the VSCU-established schedule, but if they do so, the VSCU unit will immediately display the difference in cost that will occur (For example, “Extra \$5 per day: Continue? {Yes} {No}”). The calculations can take into account seasonal weather patterns, what month it is now, weather forecasts, and so forth. For another embodiment, the VSCU unit can ask the user, on its own initiative, “Do you want to save \$100 this month by having VSCU manage your settings? {Yes} {No}” (as opposed to just asking “how about reducing temperature one degree”).

[0139] For another embodiment, the VSCU units are programmed and configured to provide the user with “pre-paid HVAC” and/or “pay as you go HVAC”. Based on a pre-paid amount or a pre-budgeted amount, the VSCU display will show the dollar amount that is remaining from that pre-paid or budgeted amount. This can be particularly useful in landlord-tenant environments or property management environments, wherein the landlord can program in the amount, and the tenant can see how much is left at any particular point in time. This can also be useful for vacation homes, allowing property managers to remotely manage power usage and settings. As part of this, the software locking mechanism described previously can determine who is using the thermostat based on personal codes, so the VSCU will know the identity of the user. This can still be useful in a single-family home setting, where certain targets can be set and the family can dynamically see a running tally as to how well they are performing relative to that target. The money amounts can be a set of default estimates, or can be based on actual usage as accessed from a utility company database using, for example, smart-meter readings.

[0140] For another embodiment, the VSCU units are programmed and configured to provide temperature setting governance based on user identity. The software locking functionality is used to ensure that only people with passcodes can change the VSCU temperature settings, and the VSCU unit furthermore recognizes a separate landlord (or other “governor”) password and one or more separate tenant (or other “governee”) passwords. The landlord can then login and set a maximum set temperature, such as 75. Thereafter, although the tenant can make temperature

changes, the VSCU unit will not allow the tenant to set the temperature above 75 degrees. Various tamper-proofing mechanisms can be provided. As a default tamper-proofing mechanism, the landlord would be able to access the VSCU data service provider web site to ensure that the VSCU unit is reporting in at regular intervals with its usage data, to request weather data, and so forth.

[0141] For another embodiment, with reference to the hotel 1202 of FIG. 12, the VSCU data service provider 1208 can provide the hotel front desk with a web-based, cloud-based, or custom software package that provides automated, comprehensive, dynamic control of the VSCU unit temperature settings in each guest room. For example, the room VSCU temperature set point can be adjusted to comfortable levels when the guest first checks in, and then returned to energy-saving levels when the guest has checked out. Also, during the guest's stay, intrinsic occupancy detection (using the unit's own sensors) and/or extrinsic occupancy detection (automated sensing the door being locked from the inside by a hotel computer connected to the VSCU hotel management system) can be used to activate comfort levels versus power-saving levels. This can be similarly useful for vacation homes as remotely managed by property management companies.

[0142] Further provided by the VSCU units is an automated override or overwriting of template schedule set point levels or time interval definitions that the user may have manually specified to the VSCU unit, either by remote control or direct entry into the VSCU unit (such as during the setup interview), based on their actual control behaviors after those inputs were made. For example, if the user specified in the setup interview that they come home at 5 PM every day, but then there are multiple days in a row (for example, 2 days or 3 days in a row) that the temperature was turned up from 62 to 65 at 4:30 PM, this is used to weight the schedule and turn the set point up to 65 at 4:20 PM thereafter, such that the temperature will be preheated to 65 by 4:30 PM when the user is expected to walk through the door. The automatic changes made by the VSCU units to the template schedule to conform around the actual occupancy behavior of the user, rather than the user's own estimates of their occupancy behavior, can take place gradual over a period of many days, or can be immediately effective on a single day, without departing from the scope of the present teachings.

[0143] For another embodiment, the VSCU units are programmed and configured to automatically switch over from heating to cooling functionality by resolving any ambiguity in user intent based on sensed information. Part of the elegance of the VSCU unit 100 of FIGS. 1A-1C is the absence of a HEAT-OFF-AC switch. One issue raised by this is potential ambiguity regarding user intent in the event of certain user control inputs. For example, if the user changes the set point from 78 to 65, there may be an ambiguity whether they simply wanted to turn off the heat or whether they want to turn on the air conditioning. According to an embodiment, the VSCU units resolve an ambiguity whether to switch over depending on the context of the set point change and the values of the old and new set point. In one embodiment, the method comprises the steps of: (a) maintaining an updated value for a drift temperature, defined as an estimated temperature to which the controlled space would drift if no HVAC heating or cooling were applied to the controlled space; (b) receiving the user set point change

from an old set point to a new set point, (c) evaluating the values of the old set point and new set point in view of the current temperature and the drift temperature (for example, place them on a state diagram having three regions segregated by the current and drift temperatures) to classify the set point change in terms of whether a mode switchover (i.e., a switchover from heating to cooling or cooling to heating) was (i) clearly not intended, (ii) clearly intended, or (iii) possibly intended by the user in making the set point change; and (d) if classified in step (c) as "possibly intended", and if the new set point lies between the current temperature and the drift temperature, request the user to choose between (i) an active switchover to achieve the new set point, and (ii) natural drifting to the new set point, along with a graphical illustration that the natural drifting option represents a more energy-saving option. Another related functionality is that whatever the user chooses in step (d), use this as a learning point and then the next time this happens, you can automatically make the determination based on what you learned from the user's choice. For this method, there can alternatively be a different parameter used instead of the drift temperature for the state diagram, for example, the outside temperature, the outside temperature plus 10 degrees, a "minimum comfort temperature", or the like. It may be that in California the best number to use is the drift temperature, whereas in Minnesota it may be the minimum comfort temperature.

[0144] For some embodiments, which are particularly applicable in view of ongoing improvements in automated sensing, a personalized control paradigm is promoted by the VSCU units, that is, the VSCU units function to automatically detect and identify individual users in the home and attempt to identify their current and upcoming individual needs and desires with respect to VSCU-related functionality. For one example, the VSCU units are programmed with a "fingerprinting" functionality to recognize a particular user who is making a current control adjustment at the face of the unit, and then adjusting its response if appropriate for that user. For example, the particular way the user has turned the VSCU unit outer ring, or where they put their fingers on the VSCU unit dial or body (using touch sensors), how much pressure they exert for an inward click, and how close their body is to the VSCU unit dial (using a proximity sensor) can be used as their "fingerprint". In one example, each user can be identified and initially "fingerprinted" in a separate question-and-answer session, and their personal preferences can thereafter be learned by virtue of their control inputs to the VSCU units from both remote locations and on the dial. At first, most of the fingerprinting can be done via user's commands from their mobile phone as well as the web. People will be controlling the thermostat a lot from their phone before getting home, or after they have left. Also, if they are somewhere else with an easier access to a computer (or even at home computer), they will use the web. Personalized control from VSCU units can be based on multiple maps of a "user comfort model" for the identified person. A model is built on what their preference/physical comfort zone is like. But if there are multiple users who have very different preferences, there may be a benefit in building two (or more) different models than to completely average them. The VSCU can learn to implement a comfortable temperature based on one model or the other based on who is at home, for example, based on which mobile device is at home (or other signatures) or which user is away by virtue of

having accessed the system from a remote IP address. A web service can be used to inform these differences, which is informative to the user (and may result in the user telling their spouse to put on a sweater). For one concrete example of individualized occupancy detection and set point adjustment according to an embodiment, the VSCU units can make a conclusion that a first occupant “M” likes it cooler, while a second occupant “W” likes it warmer based on their settings and their remote and direct controls to the VSCU units. When the system determines that “W” is home and “M” is not at home, then the temperature is set higher, or otherwise follows a separate template schedule customized for “W”. The presence of “W” and the absence of “M” can be detected, for example, using IP traffic analysis methods to determine that “M” is still at work while the home is sensed to have an occupant, which must be “W”.

[0145] Provided according to some embodiments is a gesture-based user interface for the VSCU units. For one embodiment, a touch-sensitive display is provided in which sliding touch controls are enabled, similar to swipe controls and other gestures used by the iPad and iPhone. Alternatively, a small camera can be placed on the VSCU unit, which is programmed with the ability to process the optical input information such that it can recognize hand gestures (clockwise hand rotation to turn up the temperature, counterclockwise to turn down the temperature), similar to the way that the Microsoft Kinect® sensor works in conjunction with the Xbox 360® video gaming console to provide controller-free, gesture-based user inputs (i.e., inputs based on hand, foot, or body motion without requiring the user to hold a controller device or to otherwise have a hardware input device on their person).

[0146] Provided according to some embodiments is an VSCU unit, which can function as either an auxiliary VSCU unit or primary VSCU unit, having a network-only user interface such that the physical unit itself has no controls whatsoever. The user must have a data appliance to access it and control it. The network-only VSCU unit may be useful for many situations such as college dormitories, or can be a very low-cost starter VSCU unit for a young but technically savvy apartment dweller.

[0147] Provided according to some embodiments is the use and functionality of installed VSCU units to serve as an HVAC-centric home energy hub based on the VSCU Energy Efficiency Platform with which many common home appliances will be compatible under license or other business arrangement with the VSCU unit manufacturer and/or VSCU data service provider. The VSCU units are functional as central “energy hub” for the whole house. The VSCU unit is a good way to instantiate such a “home energy network” because people need a thermostat anyway, and once it is installed it can be the core for such a network. For example, using wireless communications the VSCU unit can communicate with the dishwasher, or the refrigerator. If the user walks up to the dishwasher and attempts to start it, there can be a display on the dishwasher that says “Would you like to start the load now for \$1, or wait until 2 AM and do the load for 20 cents?” The VSCU units serve as the conduit and core for such a platform. In one example of many advantages, with occupancy sensing the VSCU unit can sense when the occupants are not home, and automatically command the refrigerator to turn up its set point by 2 degrees, and then command it to return to normal after the VSCU has sensed that the occupants have returned. Similar function-

alities can be provided in conjunction with any hot water heaters, hot tubs, pool heaters, and so forth that are equipped and licensed to be compatible with the VSCU Energy Efficiency Platform.

[0148] For some embodiments, business methods are provided for effective commercial introduction and rollout of the VSCU units and the evolution of the VSCU Efficiency Platform. At a start date of first product introduction, the simpler DIY packages of VSCU units are made available at a retail level including both online stores and brick-and-mortar stores. For buying a first primary VSCU unit, the customer gets free web access to the online tools of the VSCU data service provider (who can be the same entity as, or a partner entity to, the manufacturer of the VSCU unit), including for example the web-based remote control functionality as shown in FIGS. 13A-13B. A number of months into their usage, the web site shows the customer their energy usage and control history under the VSCU scheme, including how much money they have already saved because of their conversion. A number of months from the start date, the “professional” package VSCU units are released and professional installation made available, the first auxiliary units are made available, and fee-based subscriptions are made available to all users to a web-based service that provides them with opportunities for additional savings, such as to give them access to use special energy-saving schedule templates that have been developed based on more accurate building information, patterns detected in their particular occupancy history, or the particular weather history/forecasts around that home. Also a number of months from the start date, each user is provided with a reminder that they can save even more money by buying an auxiliary VSCU unit, and the above-described filter replacement program is also rolled out. Also a number of months from the start date, the users can get game-style rankings, including leaf icon rewards, of how they are doing in their neighborhood, or against some other population, with respect to energy efficiency. For example, the user can be presented with their percentile ranking against that population. They can try to be the number one with the most green leaves in that population. Web-based or cloud-based software that facilitates multi-tenant building control and hotel control can subsequently be rolled out. At a later point when there is enough user mass, the VSCU data service provider can provide web-based or cloud-based software to become a VSCU Efficiency Platform facilitator for utility companies, i.e., the utility companies will be clients of the VSCU data service provider, who will help them who can offer programs or services based on the VSCU Efficiency Platform. For one embodiment, the utility company will encourage its customers to switch over to VSCU unit-based control, for example by heavily subsidizing purchase of the VSCU units. Optionally, the utility company can offer energy discounts or other financial incentives for VSCU unit-based customers to “opt in” to a program that gives the utility company at least some degree of remote control over their VSCU units during times of peak loads or energy emergencies.

[0149] Provided in one embodiment is a filterless HVAC system. Instead of using a disposable filter, which can reduce HVAC efficiency when it starts to get clogged, the HVAC system is equipped with a filtering system similar to those used in one or more bagless vacuum cleaners and identified by various trade names such as “cyclonic” or “tornado” or “wind tunnel”, for example the Dyson DC25 Upright

Vacuum cleaner, the Hoover Windtunnel II Bagless Upright Vacuum Cleaner, the Bissell 5770 Healthy Home Bagless Upright Vacuum, the Electrolux EL 7055A Twin Clean Bagless Canister Vacuum, and/or the Hoover UH70010 Platinum Collection Cyclonic Bagless Upright Vacuum Cleaner. By designing the filter out of the HVAC system altogether, the homeowner simply needs to change a canister once in a while, and the HVAC system does not lose efficiency over time like a regular filter does.

[0150] Provided in some embodiments are VSCU units into which are integrally provided other essential home monitoring device functionalities combined smoke detection, heat detection, motion detection, and CO₂ detection. As an optional business method, such VSCU units can be sold at a deep discount or given away for free, with revenue being generated instead by subscriptions to the data services of the VSCU data service provider. Alternatively, they can be given away for free or heavily subsidized by a utility company that is partnered with the VSCU data service provider in exchange for customer “opt in” to voluntary data collection and/or remote VSCU setting programs applicable during periods of energy shortage or other energy emergency.

[0151] Provided according to some embodiments are algorithms for automated set point determination based on a set point temperature schedule and manual user set point modifications. As an ongoing rule for any manual user set point change, any set point entered by the user at a primary or auxiliary VSCU user interface will take effect for a maximum of four hours, at which point operation is then returned to the normal set point schedule. In the event that the normal set point schedule would call for a scheduled temperature change within that four hour interval (for example, a scheduled change to a sleeping temperature at 10:00 PM), then that scheduled temperature set point overrides the manual user set point input at that time.

[0152] Provided according to some embodiments are algorithms for set point schedule departure and/or set point schedule modification based on sensed enclosure occupancy and user set point modification behaviors. One example of such a set point schedule departure algorithm, termed herein an “auto away/auto arrival” algorithm, is described further hereinbelow.

[0153] FIGS. 15A-15D illustrate time plots of a normal set point temperature schedule versus an actual operating set point plot corresponding to an exemplary operation of an “auto away/auto arrival” algorithm according to a preferred embodiment. Shown in FIG. 15A, for purposes of clarity of disclosure, is a relatively simple exemplary thermostat schedule **1502** for a particular weekday, such as a Tuesday, for a user (perhaps a retiree, or a stay-at-home parent with young children). The schedule **1502** simply consists of an awake/at home interval between 7:00 AM and 9:00 PM for which the desired temperature is 76 degrees, and a sleeping interval between 9:00 PM and 7:00 AM for which the desired temperature is 66 degrees. For purposes of the instant description, the schedule **1502** can be termed the “normal” set point schedule. The normal set point schedule **1502** could have been established by any of a variety of methods described previously in the instant disclosure, described previously in one or more of the commonly assigned incorporated applications, or by some other method. For example, the normal set point schedule **1502** could have been established explicitly by direct user pro-

gramming (e.g., using the Web interface), by setup interview in which the set point schedule is “snapped” into one of a plurality of predetermined schedules (e.g., retiree, working couple without kids, single city dweller, etc.), by automated learning based on user set point modifications from a “flatline” starting schedule, or by any of a variety of other methods.

[0154] In accordance with a preferred “auto away” algorithm, an enclosure occupancy state is continuously and automatically sensed using the VSCU multi-sensing technology, the currently sensed state being classified as occupied (or “home” or “activity sensed”) or unoccupied (or “away” or “inactive”). If the currently sensed occupancy state has been “inactive” for a predetermined minimum interval, termed herein an away-state confidence window (ASCW), then an “auto-away” mode of operation is triggered in which an actual operating set point **1504** is changed to a predetermined energy-saving away-state temperature (AST), regardless of the set point temperature indicated by the normal thermostat schedule **1502**. The purpose of the “auto away” mode of operation is to avoid unnecessary heating or cooling when there are no occupants present to actually experience or enjoy the comfort settings of the schedule **1502**, thereby saving energy. The AST may be set, by way of example, to a default predetermined value of 62 degrees for winter periods (or outside temperatures that would call for heating) and 84 degrees for summer periods (or outside temperatures that would call for cooling). Optionally, the AST temperatures for heating and cooling can be user-settable.

[0155] The away-state confidence window (ASCW) corresponds to a time interval of sensed non-occupancy after which a reasonably reliable operating assumption can be made, with a reasonable degree of statistical accuracy, such that there are indeed no occupants in the enclosure. For most typical enclosures, it has been found that a predetermined period in the range of 90-180 minutes is a suitable period for the ASCW, to accommodate for common situations such as quiet book reading, stepping out to the corner mailbox, short naps, etc. in which there is no sensed movement or related indication for the occupancy sensors to sense.

[0156] In the example of FIG. 15A-15D, exemplary description is provided in the context of a heating scenario with an ASCW of 120 minutes, and an AST of 62 degrees, with it to be understood that counterpart examples for cooling and for other ASCW/AST value selection would be apparent to a person skilled in the art in view of the present description and are within the scope of the embodiments. Shown for purposes of illustration in FIG. 15B is the scheduled set point plot **1502** and actual operating set point plot **1504**, along with a sensed activity timeline (As) showing small black oval markers corresponding to sensed activity, that is current as of 11:00 AM. Notably, as of 11:00 AM, there was significant user activity sensed up until 10:00 AM, followed by a one-hour interval **1506** of inactivity. Shown in FIG. 15C are the scheduled and actual set point plots as of 4:00 PM. As illustrated in FIG. 15C, an “auto-away” mode was triggered at 12:00 PM after 120 minutes of inactivity, the actual operating set point **1504** departing from the normal scheduled set point **1502** to the AST temperature of 62 degrees. As of 4:00 PM, no activity has yet been sensed subsequent to the triggering of the “auto-away” mode, and therefore the “auto-away” mode remains in effect.

[0157] The “auto-away” mode can be terminated based on sensed events, the passage of time, and/or other triggers that are consistent with its essential purpose, the essential purpose being to save energy when no occupant, to a reasonably high statistical degree of probability, are present in the enclosure. For one embodiment, the “auto-away” mode of operation maintains the set point temperature at the energy-saving AST temperature until one of the following occurs: (i) a manual corrective input is received from the user; (ii) an “auto-return” mode of operation is triggered based on sensed occupancy activity; (iii) normal occupant sleeping hours have arrived and a determination for a “vacation” mode has not yet been reached; or (iv) the subsequent day’s “wake” or “at home” interval has arrived and a determination for a “vacation” mode has not yet been reached.

[0158] Thus, shown in FIG. 15D is the scheduled and actual set point plots as of 12:00 AM. As illustrated in FIG. 15D, occupancy activity started to be sensed for a brief time interval 1508 at about 5 PM, which triggered the “auto-return” mode, at which point the actual operating set point 1504 was returned to the normal set point schedule 1502.

[0159] Preferably, the user is provided with an ability (e.g., during initial setup interview, by the Web interface, etc.) to vary the ASCW according to a desired energy saving aggressiveness. For example, a user who selects a “highly aggressive” energy saving option can be provided with an ASCW of 45 minutes, with the result being that the system’s “auto-away” determination will be made after only 45 minutes of inactivity (or “away” or “unoccupied” sensing state).

[0160] Various methods for sub-windowing of the ASCW time period and filtering of sensed activity can be used to improve the reliability of the triggering of the “auto-away” mode. Various learning methods for “understanding” whether sensed activity is associated with human presence versus other causes (pets, for example) can also be used to improve the reliability of the triggering of the “auto-away” mode. For one embodiment, a “background” level of sensed activity (i.e., activity that can be attributed to sensed events that are not the result of human occupancy) can be interactively learned and/or confirmed based on the absence of corrective manual set point inputs during an “auto-away” mode period. For example, if there are no corrective manual set point changes for a period of time following after the “auto-away” mode is triggered, and such absence of corrective input repeats itself on several different occasions, then it can be concluded that the type and/or degree of sensed activity associated with those intervals can be confirmed as being “background” levels not associated with human presence, the reasoning being that if a human were indeed present, there would have been some type of corrective activity on one or more of such occasions.

[0161] In a manner similar to the “auto-away” occupancy evaluation, the triggering of an “auto-return” mode of operation is likewise preferably based on sub-windowed time windows and/or filtering of the sensed activity, such that spurious events or other events not associated with actual human presence do not unnecessarily trigger the “auto-return” mode. For one example, the sensing process involves separately evaluating 5-minute subwindows (or subwindows of other suitable duration) of time in terms of the presence or absence of sensed activity during those subwindows. If it is found that a threshold amount of activity is sensed in two adjacent ones of those time subwindows, then the “auto-

return” mode is triggered (see, for example, the time interval 1508 of FIG. 15D). Upon triggering, the “auto-return” mode operates by returning the set point to the normal set point schedule 1502.

[0162] Provided according to one embodiment is an algorithm for set point schedule modification based on occupancy patterns and/or corrective manual input patterns associated with repeated instances of “auto-away” mode and/or “auto-arrival” mode operation. Occupancy and/or corrective manual input behaviors associated with “auto-away/auto-arrival” mode are continuously monitored and filtered at multiple degrees of time periodicity in order to detect patterns in user occupancy that can, in turn, be leveraged to “trim” or otherwise “tune” the set point temperature schedule to better match actual occupancy patterns. By filtering at multiple levels of time periodicity, it is meant that associated patterns are simultaneously sought (i) on a contiguous calendar day basis, (ii) on a weekday by weekday basis, (iii) on a weekend-day by weekend-day basis, (iv) on a day-of-month by day-of-month basis, and/or on the basis of any other grouping of days that can be logically linked in terms of user behavior. Thus, for example, if a particular occupancy and/or corrective manual input behavior associated with “auto-away/auto-arrival” is observed for a series of successive Fridays, then the set point temperature schedule for Fridays is adjusted to better match the indicated occupancy pattern. If a particular occupancy and/or corrective manual input behavior associated with “auto-away/auto-arrival” is observed for both a Saturday and Sunday, and then for the next Saturday and Sunday, and then still for the following Saturday and Sunday, then the set point temperature schedule for Saturdays and Sundays is adjusted to better match the indicated occupancy pattern detected. As yet another example, if a particular occupancy and/or corrective manual input behavior associated with “auto-away/auto-arrival” is observed for the 2nd through 7th day of the month for several months in a row, then the set point temperature schedule for the 2nd through 7th day of the month is adjusted, and so on.

[0163] FIGS. 16A-16D illustrate one example of set point schedule modification based on occupancy patterns and/or corrective manual input patterns associated with repeated instances of “auto-away” mode and/or “auto-arrival” mode operation according to an embodiment. For this example, it is observed over time that, for a user whose normal set point temperature indicates they are home all day on weekdays, the “auto-away” mode is triggered near noon on Wednesday for multiple weeks (FIGS. 16A-16C) without any corrective manual user inputs, and then the “auto-arrival” mode is triggered near 5:00 PM for those days. This may correspond, for example, to a retiree who has decided to volunteer at the local library on Wednesdays. Once this pattern has been reliably established (for example, after having occurred three Wednesdays in a row), then as illustrated in FIG. 16D, the normal set point temperature schedule is automatically “tuned” or “trimmed” such that, for the following Wednesday and all Wednesdays thereafter, there is an “away” period scheduled for the interval between 10:00 AM and 5:00 PM, because it is now expected that the user will indeed be away for this time interval.

[0164] Importantly, if there had occurred a corrective user input (which can be called a “punishing” user input) on one of the days illustrated in FIGS. 16A-16C, then the set point schedule is not automatically “tuned” to that shown in FIG.

16D. Such corrective or “punishing” input could occur for circumstances in which (i) the auto-away mode has been triggered, (ii) there is not enough sensed occupancy activity (after filtering for “background” events) to trigger the “auto-return” mode, and (iii) the user is becoming uncomfortable and has walked up to the thermostat to turn up the temperature. By way of example, it may be the case that instead of going to the library on Wednesday at 10:00 AM, the user went upstairs to read a book, with a sole first-floor VSCU unit not sensing their presence and triggering auto-away at 12:00 PM, the user then becoming uncomfortable at about 12:45 PM and then coming downstairs to manually turn up the temperature. Because the user’s “punishing” input has made it clear that the algorithm is “barking up the wrong tree” for this potential pattern, the set point schedule is not automatically “tuned” to that shown in FIG. 16D, and, in one embodiment, this potential pattern is at least partially weighted in the negative direction such that an even higher degree of correlation will be needed in order to establish such pattern in the future. Advantageously, for the more general case, the user’s “punishing” inputs may also be used to adjust the type and/or degree of filtering that is applied to the occupancy sensing algorithms, because there has clearly been an incorrect conclusion of “inactivity” sensed for time interval leading up to the “punishing” corrective input.

[0165] Whereas the “auto away/auto arrival” algorithm of the above-described embodiments is triggered by currently sensed occupancy information, in another embodiment there is provided automated self-triggering of “auto away/auto arrival” algorithm based on an empirical occupancy probability time profile that has been built up by the VSCU unit(s) over an extended period of time. For one embodiment, the empirical occupancy probability time profile can be expressed as a time plot of a scalar value (an empirical occupancy probability or EOP) representative of the probability that one or more humans is occupying the enclosure at each particular point in time. Any of a variety of other expressions (e.g., probability distribution functions) or random variable representations that reflect occupancy statistics and/or probabilities can alternatively be used rather than using a single scalar metric for the EOP.

[0166] For one embodiment, the VSCU unit is configured to self-trigger into an “auto-away” mode at one or times during the day that meet the following criteria: (i) the normal set point schedule is indicative of a scheduled “at home” time interval, (ii) the empirical occupancy probability (EOP) is below a predetermined threshold value (e.g., less than 20%), (iii) the occupancy sensors do not sense a large amount of activity that would unambiguously indicate that human occupants are indeed present in the enclosure, and (iv) the occupancy sensors have not yet sensed a low enough level of activity for a sufficiently long interval (i.e., the away-state confidence window or ASCW) to enter into the “auto away” mode in the “conventional” manner previously described. Once these conditions are met and the “auto-away” mode has been self-triggered, reversion out of the “auto away” mode can proceed in the same manner (e.g., by “auto-arrival” triggering, manual corrective user input, etc.) as for the “conventional” auto-away mode. Automated tuning of the set point temperature schedule based on the “lessons learned” (i.e., based on occupancy patterns and/or corrective manual input patterns associated with repeated instances of “auto-away” mode) can be based on the com-

bined observations from the “conventionally” triggered auto-away mode and the self-triggered auto-away mode algorithms.

[0167] The above-described self-triggering of the “auto-away” mode, which is based at least in part on empirical occupancy probability (EOP), has been found to provide for more complete and more statistically precise “tuning” of the set point temperature schedule when capered to tuning that is based only on the “conventional” auto-away triggering method in which only current, instantaneous occupancy information is considered. One reason relates to the large number of activity-sensing data samples used in generating the EOP metric, making it a relevant and useful basis upon which to perform the occupancy “test” afforded by the “auto-away” process. From one perspective, the “auto-away” process can be thought of as a way to automatically “poke” or “prod” at the user’s ecosystem to learn more detail about their occupancy patterns, without needing to ask them detailed questions, without needing to rely on the correctness of their responses, and furthermore without needing to rely exclusively on the instantaneous accuracy of the occupancy sensing hardware.

[0168] FIGS. 17A-D illustrates a dynamic user interface for encouraging reduced energy use according to a preferred embodiment. The method of FIGS. 17A-D is preferably incorporated into the time-to-temperature user interface method of FIGS. 3A-3K, supra, although the scope of the present teachings is not so limited. As would be readily appreciated by a person skilled in the art, although disclosed in FIGS. 17A-17D in the heating context, application to the counterpart cooling context would be apparent to one skilled in the art in view of the present disclosure and is within the scope of the present teachings. Where, as in FIG. 17A, the heating set point is currently set to a value known to be within a first range known to be good or appropriate for energy conservation, a pleasing positive-reinforcement icon such as the green leaf **1742** is displayed. As the user turns up the heat (see FIG. 17B) the green leaf continues to be displayed as long as the set point remains in that first range. However, as the user continues to turn up the set point to a value greater than the first range (see FIG. 17C), there is displayed a negatively reinforcing icon indicative of alarm, consternation, concern, or other somewhat negative emotion, such icon being, for example, a flashing red version **1742'** of the leaf, or a picture of a smokestack, or the like. It is believed that the many users will respond to the negatively reinforcing icon **1742'** by turning the set point back down, and as illustrated in FIG. 17D, if the user returns the set point to a value lying in the first range, they are “rewarded” by the return of the green leaf **1742**. Many other types of positive-emotion icons or displays can be used in place of the green leaf **1742**, and likewise many different negatively reinforcing icons or displays can be used in place of the flashing red leaf **1742'**, while remaining within the scope of the present teachings.

[0169] FIGS. 18A-B illustrate a thermostat **1800** having a user-friendly interface, according to some embodiments. The term “thermostat” is used hereinbelow to represent a particular type of VSCU unit (Versatile Sensing and Control) that is particularly applicable for HVAC control in an enclosure. Although “thermostat” and “VSCU unit” may be seen as generally interchangeable for the contexts of HVAC control of an enclosure, it is within the scope of the present teachings for each of the embodiments hereinabove and

hereinbelow to be applied to VSCU units having control functionality over measurable characteristics other than temperature (e.g., pressure, flow rate, height, position, velocity, acceleration, capacity, power, loudness, brightness) for any of a variety of different control systems involving the governance of one or more measurable characteristics of one or more physical systems, and/or the governance of other energy or resource consuming systems such as water usage systems, air usage systems, systems involving the usage of other natural resources, and systems involving the usage of various other forms of energy. Unlike many prior art thermostats, thermostat **1800** preferably has a sleek, simple, uncluttered and elegant design that does not detract from home decoration, and indeed can serve as a visually pleasing centerpiece for the immediate location in which it is installed. Moreover, user interaction with thermostat **1800** is facilitated and greatly enhanced over known conventional thermostats by the design of thermostat **1800**. The thermostat **1800** includes control circuitry and is electrically connected to an HVAC system, such as is shown with thermostat **110** in FIGS. 1 and 2. Thermostat **1800** is wall mounted, is circular in shape, and has an outer rotatable ring **1812** for receiving user input. Thermostat **1800** is circular in shape in that it appears as a generally disk-like circular object when mounted on the wall. Thermostat **1800** has a large front face lying inside the outer ring **1812**. According to some embodiments, thermostat **1800** is approximately 80 mm in diameter. The outer rotatable ring **1812** allows the user to make adjustments, such as selecting a new target temperature. For example, by rotating the outer ring **1812** clockwise, the target temperature can be increased, and by rotating the outer ring **1812** counter-clockwise, the target temperature can be decreased. The front face of the thermostat **1800** comprises a clear cover **1814** that according to some embodiments is polycarbonate, and a metallic portion **1824** preferably having a number of slots formed therein as shown. According to some embodiments, the surface of cover **1814** and metallic portion **1824** form a common outward arc or spherical shape gently arcing outward, and this gentle arcing shape is continued by the outer ring **1812**.

[0170] Although being formed from a single lens-like piece of material such as polycarbonate, the cover **1814** has two different regions or portions including an outer portion **1814o** and a central portion **1814i**. According to some embodiments, the cover **1814** is painted or smoked around the outer portion **1814o**, but leaves the central portion **1814i** visibly clear so as to facilitate viewing of an electronic display **1816** disposed thereunderneath. According to some embodiments, the curved cover **1814** acts as a lens that tends to magnify the information being displayed in electronic display **1816** to users. According to some embodiments the central electronic display **1816** is a dot-matrix layout (individually addressable) such that arbitrary shapes can be generated, rather than being a segmented layout. According to some embodiments, a combination of dot-matrix layout and segmented layout is employed. According to some embodiments, central display **1816** is a backlit color liquid crystal display (LCD). An example of information displayed on the electronic display **1816** is illustrated in FIG. 18A, and includes central numerals **1820** that are representative of a current set point temperature. According to some embodiments, metallic portion **1824** has number of slot-like openings so as to facilitate the use of a passive infrared motion sensor **1830** mounted therebeneath. The metallic portion

1824 can alternatively be termed a metallic front grille portion. Further description of the metallic portion/front grille portion is provided in the commonly assigned U.S. Ser. No. 13/199,108, *supra*. The thermostat **1800** is preferably constructed such that the electronic display **1816** is at a fixed orientation and does not rotate with the outer ring **1812**, so that the electronic display **1816** remains easily read by the user. For some embodiments, the cover **1814** and metallic portion **1824** also remain at a fixed orientation and do not rotate with the outer ring **1812**. According to one embodiment in which the diameter of the thermostat **1800** is about 80 mm, the diameter of the electronic display **1816** is about 45 mm. According to some embodiments an LED indicator **1880** is positioned beneath portion **1824** to act as a low-power-consuming indicator of certain status conditions. For, example the LED indicator **1880** can be used to display blinking red when a rechargeable battery of the thermostat (see FIG. 4A, *infra*) is very low and is being recharged. More generally, the LED indicator **1880** can be used for communicating one or more status codes or error codes by virtue of red color, green color, various combinations of red and green, various different blinking rates, and so forth, which can be useful for troubleshooting purposes.

[0171] Motion sensing as well as other techniques can be used in the detection and/or predict of occupancy, as is described further in the commonly assigned U.S. Ser. No. 12/881,430, *supra*. According to some embodiments, occupancy information is used in generating an effective and efficient scheduled program. Preferably, an active proximity sensor **1870A** is provided to detect an approaching user by infrared light reflection, and an ambient light sensor **1870B** is provided to sense visible light. The proximity sensor **1870A** can be used to detect proximity in the range of about one meter so that the thermostat **1800** can initiate “waking up” when the user is approaching the thermostat and prior to the user touching the thermostat. Such use of proximity sensing is useful for enhancing the user experience by being “ready” for interaction as soon as, or very soon after the user is ready to interact with the thermostat. Further, the wake-up-on-proximity functionality also allows for energy savings within the thermostat by “sleeping” when no user interaction is taking place or about to take place. The ambient light sensor **1870B** can be used for a variety of intelligence-gathering purposes, such as for facilitating confirmation of occupancy when sharp rising or falling edges are detected (because it is likely that there are occupants who are turning the lights on and off), and such as for detecting long term (e.g., 24-hour) patterns of ambient light intensity for confirming and/or automatically establishing the time of day.

[0172] According to some embodiments, for the combined purposes of inspiring user confidence and further promoting visual and functional elegance, the thermostat **1800** is controlled by only two types of user input, the first being a rotation of the outer ring **1812** as shown in FIG. 18A (referenced hereafter as a “rotate ring” or “ring rotation” input), and the second being an inward push on an outer cap **1808** (see FIG. 18B) until an audible and/or tactile “click” occurs (referenced hereafter as an “inward click” or simply “click” input). For the embodiment of FIGS. 18A-18B, the outer cap **1808** is an assembly that includes all of the outer ring **1812**, cover **1814**, electronic display **1816**, and metallic portion **1824**. When pressed inwardly by the user, the outer cap **1808** travels inwardly by a small amount, such as 0.5

mm, against an interior metallic dome switch (not shown), and then springably travels back outwardly by that same amount when the inward pressure is released, providing a satisfying tactile “click” sensation to the user’s hand, along with a corresponding gentle audible clicking sound. Thus, for the embodiment of FIGS. 18A-18B, an inward click can be achieved by direct pressing on the outer ring 1812 itself, or by indirect pressing of the outer ring by virtue of providing inward pressure on the cover 1814, metallic portion 1814, or by various combinations thereof. For other embodiments, the thermostat 1800 can be mechanically configured such that only the outer ring 1812 travels inwardly for the inward click input, while the cover 1814 and metallic portion 1824 remain motionless. It is to be appreciated that a variety of different selections and combinations of the particular mechanical elements that will travel inwardly to achieve the “inward click” input are within the scope of the present teachings, whether it be the outer ring 1812 itself, some part of the cover 1814, or some combination thereof. However, it has been found particularly advantageous to provide the user with an ability to quickly go back and forth between registering “ring rotations” and “inward clicks” with a single hand and with minimal amount of time and effort involved, and so the ability to provide an inward click directly by pressing the outer ring 1812 has been found particularly advantageous, since the user’s fingers do not need to be lifted out of contact with the device, or slid along its surface, in order to go between ring rotations and inward clicks. Moreover, by virtue of the strategic placement of the electronic display 1816 centrally inside the rotatable ring 1812, a further advantage is provided in that the user can naturally focus their attention on the electronic display throughout the input process, right in the middle of where their hand is performing its functions. The combination of intuitive outer ring rotation, especially as applied to (but not limited to) the changing of a thermostat’s set point temperature, conveniently folded together with the satisfying physical sensation of inward clicking, together with accommodating natural focus on the electronic display in the central midst of their fingers’ activity, adds significantly to an intuitive, seamless, and downright fun user experience. Further descriptions of advantageous mechanical user-interfaces and related designs, which are employed according to some embodiments, can be found in U.S. Ser. No. 13/033,573, supra, U.S. Ser. No. 29/386,021, supra, and U.S. Ser. No. 13/199,108, supra.

[0173] FIG. 18C illustrates a cross-sectional view of a shell portion 1809 of a frame of the thermostat of FIGS. 18A-B, which has been found to provide a particularly pleasing and adaptable visual appearance of the overall thermostat 1800 when viewed against a variety of different wall colors and wall textures in a variety of different home environments and home settings. While the thermostat itself will functionally adapt to the user’s schedule as described herein and in one or more of the commonly assigned incorporated applications, supra, the outer shell portion 1809 is specially configured to convey a “chameleon” quality or characteristic such that the overall device appears to naturally blend in, in a visual and decorative sense, with many of the most common wall colors and wall textures found in home and business environments, at least in part because it will appear to assume the surrounding colors and even textures when viewed from many different angles. The shell

portion 1809 has the shape of a frustum that is gently curved when viewed in cross-section, and comprises a sidewall 1876 that is made of a clear solid material, such as polycarbonate plastic. The sidewall 1876 is backpainted with a substantially flat silver- or nickel-colored paint, the paint being applied to an inside surface 1878 of the sidewall 1876 but not to an outside surface 1877 thereof. The outside surface 1877 is smooth and glossy but is not painted. The sidewall 1876 can have a thickness T of about 1.5 mm, a diameter d1 of about 78.8 mm at a first end that is nearer to the wall when mounted, and a diameter d2 of about 81.2 mm at a second end that is farther from the wall when mounted, the diameter change taking place across an outward width dimension “h” of about 22.5 mm, the diameter change taking place in either a linear fashion or, more preferably, a slightly nonlinear fashion with increasing outward distance to form a slightly curved shape when viewed in profile, as shown in FIG. 18C. The outer ring 1812 of outer cap 1808 is preferably constructed to match the diameter d2 where disposed near the second end of the shell portion 1809 across a modestly sized gap g1 therefrom, and then to gently arc back inwardly to meet the cover 1814 across a small gap g2. It is to be appreciated, of course, that FIG. 18C only illustrates the outer shell portion 1809 of the thermostat 1800, and that there are many electronic components internal thereto that are omitted from FIG. 18C for clarity of presentation, such electronic components being described further hereinbelow and/or in other ones of the commonly assigned incorporated applications, such as U.S. Ser. No. 13/199,108, supra.

[0174] According to some embodiments, the thermostat 1800 includes a processing system 1860, display driver 1864 and a wireless communications system 1866. The processing system 1860 is adapted to cause the display driver 1864 and display area 1816 to display information to the user, and to receive user input via the rotatable ring 1812. The processing system 1860, according to some embodiments, is capable of carrying out the governance of the operation of the thermostat 1800 including the user interface features described herein. The processing system 1860 is further programmed and configured to carry out other operations as described further hereinbelow and/or in other ones of the commonly assigned incorporated applications. For example, processing system 1860 is further programmed and configured to maintain and update a thermodynamic model for the enclosure in which the HVAC system is installed, such as described in U.S. Ser. No. 12/881,463, supra. According to some embodiments, the wireless communications system 1866 is used to communicate with devices such as personal computers and/or other thermostats or HVAC system components, which can be peer-to-peer communications, communications through one or more servers located on a private network, or and/or communications through a cloud-based service.

[0175] FIGS. 19A-19B illustrate exploded front and rear perspective views, respectively, of the thermostat 1800 with respect to its two main components, which are the head unit 1900 and the back plate 2000. Further technical and/or functional descriptions of various ones of the electrical and mechanical components illustrated hereinbelow can be found in one or more of the commonly assigned incorporated applications, such as U.S. Ser. No. 13/199,108, supra. In the drawings shown, the “z” direction is outward from the

wall, the “y” direction is the head-to-toe direction relative to a walk-up user, and the “x” direction is the user’s left-to-right direction.

[0176] FIGS. 20A-20B illustrate exploded front and rear perspective views, respectively, of the head unit **1900** with respect to its primary components. Head unit **1900** includes a head unit frame **1910**, the outer ring **1920** (which is manipulated for ring rotations), a head unit frontal assembly **1930**, a front lens **1980**, and a front grille **1990**. Electrical components on the head unit frontal assembly **1930** can connect to electrical components on the backplate **2000** by virtue of ribbon cables and/or other plug type electrical connectors.

[0177] FIGS. 21A-21B illustrate exploded front and rear perspective views, respectively, of the head unit frontal assembly **1930** with respect to its primary components. Head unit frontal assembly **1930** comprises a head unit circuit board **1940**, a head unit front plate **1950**, and an LCD module **1960**. The components of the front side of head unit circuit board **1940** are hidden behind an RF shield in FIG. 21A but are discussed in more detail below with respect to FIG. 24. On the back of the head unit circuit board **1940** is a rechargeable Lithium-Ion battery **1944**, which for one preferred embodiment has a nominal voltage of 3.7 volts and a nominal capacity of 560 mAh. To extend battery life, however, the battery **1944** is normally not charged beyond 450 mAh by the thermostat battery charging circuitry. Moreover, although the battery **1944** is rated to be capable of being charged to 4.2 volts, the thermostat battery charging circuitry normally does not charge it beyond 3.95 volts. Also visible in FIG. 21B is an optical finger navigation module **1942** that is configured and positioned to sense rotation of the outer ring **1920**. The module **1942** uses methods analogous to the operation of optical computer mice to sense the movement of a texturable surface on a facing periphery of the outer ring **1920**. Notably, the module **1942** is one of the very few sensors that is controlled by the relatively power-intensive head unit microprocessor rather than the relatively low-power backplate microprocessor. This is achievable without excessive power drain implications because the head unit microprocessor will invariably be awake already when the user is manually turning the dial, so there is no excessive wake-up power drain anyway. Advantageously, very fast response can also be provided by the head unit microprocessor. Also visible in FIG. 21A is a Fresnel lens **1957** that operates in conjunction with a PIR motion sensor disposed thereunderneath.

[0178] FIGS. 22A-22B illustrate exploded front and rear perspective views, respectively, of the backplate unit **2000** with respect to its primary components. Backplate unit **2000** comprises a backplate rear plate **2010**, a backplate circuit board **2020**, and a backplate cover **2080**. Visible in FIG. 22A are the HVAC wire connectors **2022** that include integrated wire insertion sensing circuitry, and two relatively large capacitors **2024** that are used by part of the power stealing circuitry that is mounted on the back side of the backplate circuit board **2020** and discussed further below with respect to FIG. 25.

[0179] FIG. 23 illustrates a perspective view of a partially assembled head unit front **1900** showing the positioning of grille member **1990** designed in accordance with aspects of the present invention with respect to several sensors used by the thermostat. In some implementations, as described further in U.S. Ser. No. 13/199,108, supra, placement of grille

member **1990** over the Fresnel lens **1957** and an associated PIR motion sensor **334** conceals and protects these PIR sensing elements, while horizontal slots in the grille member **1990** allow the PIR motion sensing hardware, despite being concealed, to detect the lateral motion of occupants in a room or area. A temperature sensor **330** uses a pair of thermal sensors to more accurately measure ambient temperature. A first or upper thermal sensor **330a** associated with temperature sensor **330** tends to gather temperature data closer to the area outside or on the exterior of the thermostat while a second or lower thermal sensor **330b** tends to collect temperature data more closely associated with the interior of the housing. In one implementation, each of the temperature sensors **330a** and **330b** comprises a Texas Instruments TMP112 digital temperature sensor chip, while the PIR motion sensor **334** comprises PerkinElmer DigiPyro PYD 1998 dual element pyrodetector.

[0180] To more accurately determine the ambient temperature, the temperature taken from the lower thermal sensor **330b** is taken into consideration in view of the temperatures measured by the upper thermal sensor **330a** and when determining the effective ambient temperature. This configuration can advantageously be used to compensate for the effects of internal heat produced in the thermostat by the microprocessor(s) and/or other electronic components therein, thereby obviating or minimizing temperature measurement errors that might otherwise be suffered. In some implementations, the accuracy of the ambient temperature measurement may be further enhanced by thermally coupling upper thermal sensor **330a** of temperature sensor **330** to grille member **1990** as the upper thermal sensor **330a** better reflects the ambient temperature than lower thermal sensor **330b**. Details on using a pair of thermal sensors to determine an effective ambient temperature is disclosed in U.S. Pat. No. 4,741,476, which is incorporated by reference herein.

[0181] FIG. 24 illustrates a head-on view of the head unit circuit board **1940**, which comprises a head unit microprocessor **2402** (such as a Texas Instruments AM3703 chip) and an associated oscillator **2404**, along with DDR SDRAM memory **2406**, and mass NAND storage **2408**. For Wi-Fi capability, there is provided in a separate compartment of RF shielding **2434** a Wi-Fi module **2410**, such as a Murata Wireless Solutions LBWA19XSLZ module, which is based on the Texas Instruments WL1270 chipset supporting the 802.11 b/g/n WLAN standard. For the Wi-Fi module **2410** is supporting circuitry **2412** including an oscillator **2414**. For ZigBee capability, there is provided also in a separately shielded RF compartment a ZigBee module **2416**, which can be, for example, a C2530F256 module from Texas Instruments. For the ZigBee module **2416** there is provided supporting circuitry **2418** including an oscillator **2419** and a low-noise amplifier **2420**. Also provided is display backlight voltage conversion circuitry **2422**, piezoelectric driving circuitry **2424**, and power management circuitry **2426** (local power rails, etc.). Provided on a flex circuit **2428** that attaches to the back of the head unit circuit board by a flex circuit connector **2430** is a proximity and ambient light sensor (PROX/ALS), more particularly a Silicon Labs S11142 Proximity/Ambient Light Sensor with an 12C interface. Also provided is battery charging-supervision-disconnect circuitry **2432**, and spring/RF antennas **2436**. Also provided is a temperature sensor **2438** (rising perpendicular to the circuit board in the +z direction containing two

separate temperature sensing elements at different distances from the circuit board), and a PIR motion sensor **2440**. Notably, even though the PROX/ALS and temperature sensors **2438** and PIR motion sensor **2440** are physically located on the head unit circuit board **1940**, all these sensors are polled and controlled by the low-power backplate microcontroller on the backplate circuit board, to which they are electrically connected.

[0182] FIG. 25 illustrates a rear view of the backplate circuit board **2020**, comprising a backplate processor/microcontroller **2502**, such as a Texas Instruments MSP430F System-on-Chip Microcontroller that includes an on-board memory **2503**. The backplate circuit board **2020** further comprises power supply circuitry **2504**, which includes power-stealing circuitry, and switch circuitry **2506** for each HVAC respective HVAC function. For each such function the switch circuitry **2506** includes an isolation transformer **2508** and a back-to-back NFET package **2510**. The use of FETs in the switching circuitry allows for “active power stealing”, i.e., taking power during the HVAC “ON” cycle, by briefly diverting power from the HVAC relay circuit to the reservoir capacitors for a very small interval, such as 100 micro-seconds. This time is small enough not to trip the HVAC relay into the “off” state but is sufficient to charge up the reservoir capacitors. The use of FETs allows for this fast switching time (100 micro-seconds), which would be difficult to achieve using relays (which stay on for tens of milliseconds). Also, such relays would readily degrade doing this kind of fast switching, and they would also make audible noise too. In contrast, the FETs operate with essentially no audible noise. Also provided is a combined temperature/humidity sensor module **2512**, such as a Sensirion SHT21 module. The backplate microcontroller **2502** performs polling of the various sensors, sensing for mechanical wire insertion at installation, alerting the head unit regarding current vs. set point temperature conditions and actuating the switches accordingly, and other functions such as looking for appropriate signal on the inserted wire at installation.

[0183] In accordance with the teachings of the commonly assigned U.S. Ser. No. 13/269,501, *supra*, the commonly assigned U.S. Ser. No. 13/275,307, *supra*, and others of the commonly assigned incorporated applications, the thermostat **1800** represents an advanced, multi-sensing, microprocessor-controlled intelligent or “learning” thermostat that provides a rich combination of processing capabilities, intuitive and visually pleasing user interfaces, network connectivity, and energy-saving capabilities (including the presently described auto-away/auto-arrival algorithms) while at the same time not requiring a so-called “C-wire” from the HVAC system or line power from a household wall plug, even though such advanced functionalities can require a greater instantaneous power draw than a “power-stealing” option (i.e., extracting smaller amounts of electrical power from one or more HVAC call relays) can safely provide. By way of example, the head unit microprocessor **2402** can draw on the order of 250 mW when awake and processing, the LCD module **1960** can draw on the order of 250 mW when active. Moreover, the Wi-Fi module **2410** can draw 250 mW when active, and needs to be active on a consistent basis such as at a consistent 2% duty cycle in common scenarios. However, in order to avoid falsely tripping the HVAC relays for a large number of commercially used HVAC systems, power-stealing circuitry is often limited to

power providing capacities on the order of 100 mW-200 mW, which would not be enough to supply the needed power for many common scenarios.

[0184] The thermostat **1800** resolves such issues at least by virtue of the use of the rechargeable battery **1944** (or equivalently capable onboard power storage medium) that will recharge during time intervals in which the hardware power usage is less than what power stealing can safely provide, and that will discharge to provide the needed extra electrical power during time intervals in which the hardware power usage is greater than what power stealing can safely provide. In order to operate in a battery-conscious manner that promotes reduced power usage and extended service life of the rechargeable battery, the thermostat **1800** is provided with both (i) a relatively powerful and relatively power-intensive first processor (such as a Texas Instruments AM3703 microprocessor) that is capable of quickly performing more complex functions such as driving a visually pleasing user interface display and performing various mathematical learning computations, and (ii) a relatively less powerful and less power-intensive second processor (such as a Texas Instruments MSP430 microcontroller) for performing less intensive tasks, including driving and controlling the occupancy sensors. To conserve valuable power, the first processor is maintained in a “sleep” state for extended periods of time and is “woken up” only for occasions in which its capabilities are needed, whereas the second processor is kept on more or less continuously (although preferably slowing down or disabling certain internal clocks for brief periodic intervals to conserve power) to perform its relatively low-power tasks. The first and second processors are mutually configured such that the second processor can “wake” the first processor on the occurrence of certain events, which can be termed “wake-on” facilities. These wake-on facilities can be turned on and turned off as part of different functional and/or power-saving goals to be achieved. For example, a “wake-on-PROX” facility can be provided by which the second processor, when detecting a user’s hand approaching the thermostat dial by virtue of an active proximity sensor (PROX, such as provided by a Silicon Labs SI1142 Proximity/Ambient Light Sensor with I2C Interface), will “wake up” the first processor so that it can provide a visual display to the approaching user and be ready to respond more rapidly when their hand touches the dial. As another example, a “wake-on-PIR” facility can be provided by which the second processor will wake up the first processor when detecting motion somewhere in the general vicinity of the thermostat by virtue of a passive infrared motion sensor (PIR, such as provided by a PerkinElmer DigiPyro PYD 1998 dual element pyrodetector). Notably, wake-on-PIR is not synonymous with auto-arrival, as there would need to be N consecutive buckets of sensed PIR activity to invoke auto-arrival, whereas only a single sufficient motion event can trigger a wake-on-PIR wake-up.

[0185] FIGS. 26A-26C illustrate conceptual examples of the sleep-wake timing dynamic, at progressively larger time scales, that can be achieved between the head unit (HU) microprocessor and the backplate (BP) microcontroller that advantageously provides a good balance between performance, responsiveness, intelligence, and power usage. The higher plot value for each represents a “wake” state (or an equivalent higher power state) and the lower plot value for each represents a “sleep” state (or an equivalent lower power state). As illustrated, the backplate microcontroller is active

much more often for polling the sensors and similar relatively low-power tasks, whereas the head unit microprocessor stays asleep much more often, being woken up for “important” occasions such as user interfacing, network communication, and learning algorithm computation, and so forth. A variety of different strategies for optimizing sleep versus wake scenarios can be achieved by the disclosed architecture and is within the scope of the present teachings. For example, the commonly assigned U.S. Ser. No. 13/275,307, *supra*, describes a strategy for conserving head unit microprocessor “wake” time while still maintaining effective and timely communications with a cloud-based thermostat management server via the thermostat’s Wi-Fi facility.

[0186] FIG. 27 illustrates a self-descriptive overview of the functional software, firmware, and/or programming architecture of the head unit microprocessor 2402 for achieving its described functionalities. FIG. 28 illustrates a self-descriptive overview of the functional software, firmware, and/or programming architecture of the backplate microcontroller 2502 for achieving its described functionalities.

[0187] FIG. 29 illustrates a view of the wiring terminals as presented to the user when the backplate is exposed. As described in the commonly assigned U.S. Ser. No. 13/034,666, *supra*, each wiring terminal is configured such that the insertion of a wire therein is detected and made apparent to the backplate microcontroller and ultimately the head unit microprocessor. According to a preferred embodiment, if the insertion of a particular wire is detected, a further check is automatically carried out by the thermostat to ensure that signals appropriate to that particular wire are present. For one preferred embodiment, there is automatically measured a voltage waveform between that wiring node and a “local ground” of the thermostat. The measured waveform should have an RMS-type voltage metric that is above a predetermined threshold value, and if such predetermined value is not reached, then a wiring error condition is indicated to the user. The predetermined threshold value, which may vary from circuit design to circuit design depending on the particular selection of the local ground, can be empirically determined using data from a population of typical HVAC systems to statistically determine a suitable threshold value. For some embodiments, the “local ground” or “system ground” can be created from (i) the Rh line and/or Rc terminal, and (ii) whichever of the G, Y, or W terminals from which power stealing is being performed, these two lines going into a full-bridge rectifier (FWR) which has the local ground as one of its outputs.

[0188] FIGS. 30A-30B illustrate restricting user establishment of a new scheduled set point that is within a predetermined time separation (such as one hour) from a pre-existing scheduled set point, in a subtle manner that does not detract from the friendliness of the user interface. The ability to prevent new user-entered scheduled set points that take effect within one hour of pre-existing set points can be advantageous in keeping the overall schedule relatively “clean” from an overpopulation of set points, which in turn can make the schedule more amenable to comfort-preserving yet energy-conserving automated learning algorithms. In particular, the scheduling user interface of thermostat 1800 operates to bar the user from entering a new scheduled set point within one hour of a preexisting set point, but achieves this objective in a way such that the user does not feel like

they are being explicitly “forced” to place set points where they do not want to place them, nor are they being explicitly “punished” for trying to place a set point where one is not allowed. Even though this feature may only be subtly apparent to the user, and even though it may take several second looks to perceive what the thermostat user interface is actually doing to achieve this subtle objective, this feature contributes to the feeling of friendliness, the feeling of being free from intimidation, on the part of the user and therefore increases the likelihood that the user will want to “engage” with the thermostat and to “be a part of” its energy saving ecosystem. In FIG. 30A, the user is engaging with a scheduling screen 3050 of the thermostat 1800 in a manner that is further described in U.S. Ser. No. 13/269,501, *supra*, performing ring rotations to move the displayed time interval backward and forward in time relative to a timepoint line 3052, which remains static in the middle of the screen. As illustrated, a clock icon 3056 reflects the particular point in time indicated at the timepoint line 3052. If the user provides an inward click input at FIG. 30A when the timepoint line 3052 is not within one hour of a pre-existing set point (icon 3054), a menu 3058 appears that presents the options “New” and “Done”. The user will be allowed to enter a new set point for the particular point in time indicated by timepoint line 3052 by appropriate ring rotation and inward click to select “New.” However, according to a preferred embodiment as shown in FIG. 30B, if the timepoint line 3052 is within one hour of the preexisting set point 3054, then the icon 3054 grows in size according to an amount of overlap with the timepoint line 3052, going to a fully expanded size when the timepoint line 3052 is directly in the middle of icon 3054 (i.e., directly at the effective time of the pre-existing set point), and approaching a regular “background” size as the timepoint line 3052 moves one hour away from the time of that pre-existing set point. Importantly, if the user provides an inward click when the timepoint line 3052 is within one hour of the pre-existing set point, then the menu 3059 appears, which does not provide a “New” option but instead provides the options of “Change” (to change the effective time or temperature of the preexisting set point), “Remove” (to remove the pre-existing set point), and “Done” (to do neither). Advantageously, the user’s attention focuses on the expanding and contracting icon 3054, which in addition to being visually pleasing has a temperature value that is easier to read when it is enlarged, as the dial is rotated. When they provide the inward click, the user’s attention is focused on the fact that they can change or remove the existing set point, rather than any sort of “punishment” for trying to establish a new scheduled set point, which they have just been subtly prohibited from doing. Finally, in the event that the user does elect to change the effective time of the pre-existing set point icon 3054 (using an intuitive “pick up and carry” method, see U.S. Ser. No. 13/269,501, *supra*), they are allowed to “carry” the pre-existing set point left or right to a new point in time, but as the “carried” icon approaches any other pre-existing set point, it will simply stop moving any closer once it is one hour away from that other pre-existing set point even if the user keeps rotating the dial. This provides a subtle, non-punishing and nonthreatening cue to the user that they have reached the end of the permissible time shift of the “carried” pre-existing set point icon.

[0189] FIGS. 31A-31D illustrate time to temperature display to a user for one implementation. Other aspects of preferred time to temperature displays are described in the

commonly assigned U.S. Ser. No. 12/984,602, *supra*. Preferably, as illustrated FIG. 31B, the time to temperature (hereinafter “T2T”) display 3131 is provided immediately to the user based on a quick estimate derived from historical performance data for this particular HVAC system and this particular home as tracked by this particular thermostat. As illustrated in FIG. 31C, whenever the display is activated (such as when the user walks up to the thermostat to check on it and their close presence is detected by the thermostat’s active short-range proximity sensor or “PROX”), the T2T display 3131 shows the estimated number of minutes remaining according to an updated estimate of the time remaining. Notably, it has been found that due to an appreciable standard deviation of the T2T estimate in many cases, it is preferable to simply display “under 10 minutes” (or other suitable small threshold) if the T2T estimate is less than that amount, lest the user be disappointed or think there is a problem if there is a precise countdown provided that turns out not to be accurate.

[0190] FIG. 32 illustrates an example of a preferred thermostat readout when a second stage heating facility is invoked, such as AUX (auxiliary heat strip for heat pump systems) or W2 (conventional second stage heating). According to one preferred embodiment, if the initial time to temperature estimate (“T2T”) is more than 20 minutes (or some other threshold indicative of an uncomfortably long time) when the temperature is first turned up (i.e., when the user has turned the dial up or used the remote access facility to turn up the operating set point temperature), then the second stage heating facility is automatically invoked by the thermostat. For one embodiment the T2T display can simply be changed to HEATX2 to indicate that the second stage heat facility is activated. Optionally, there can be provided a T2T estimate in addition to the HEATX2 display, where the T2T computation is specially calibrated to take into account the second stage heating facility. The second stage heating facility will usually remain activated for the entire heating cycle until the target temperature is reached, although the scope of the present teachings is not so limited.

[0191] FIGS. 33A-33C illustrate actuating a second stage heat facility during a single stage heating cycle using time to temperature (T2T) information according to a preferred embodiment. For any of a variety of reasons ranging from an open window to a just-completed sunset, it may happen that the HVAC system is “falling behind” what was previously expected using the first heating stage. For one preferred embodiment, such a situation is automatically detected by the thermostat based on time to temperature (T2T) upon which the second stage heating facility is automatically invoked. For one preferred embodiment, if the thermostat determines that it is more than 10 minutes (or other suitable threshold) behind the initial T2T estimate (i.e., if the current T2T estimate reflects that the total time from the beginning of the cycle until the currently estimated end time of the cycle will be more than 10 minutes greater than the initial T2T estimate), then the second stage heating facility will be activated. Stated in terms of an equation, where “t” is the time since the start of the cycle and “T2T(t)” is the time to temperature estimate at the time “t”, then the second stage heating facility becomes invoked if $\{[t+T2T(t)]-T2T(0)\}$ becomes greater than 10 minutes (or other suitable threshold). As with the embodiment of FIG. 32, the T2T display can then simply be changed to HEATX2, or optionally there can also be provided a T2T estimate where the T2T com-

putation is specially calibrated to take into account the second stage heating facility. Preferably, if the cycle is almost complete (for example, T2T is only 5 minutes or less) at the point in time at which it is first determined that the system is more than 10 minutes behind the initial estimate, the second stage heating facility will not be invoked. For one preferred embodiment, since it is desirable to keep the head unit processor of thermostat 1800 asleep as often as possible, while at the same time it is desirable to be vigilant about whether the HVAC system is falling too far behind, there is an automated 15-minute wake-up timer that is set by the head unit processor before it goes to sleep whenever there is an active heating cycle in effect. In this way, in the event that the head unit processor is not woken up for some other purpose during the heating cycle, it will wake up every 15 minutes and perform the computations for determining whether the HVAC system is falling behind. The second stage heating facility will usually remain activated until the target temperature is reached, although the scope of the present teachings is not so limited.

[0192] Shown in FIGS. 33A-33C is a particular example in which the initial T2T estimate was 18 minutes (FIG. 33A), but the system starting lagging behind and by the time 15 minutes had elapsed (FIG. 33B), there was only modest progress toward the target temperature. As of FIG. 33B, the system is “behind” by 8 minutes since 15 minutes has elapsed and there are still 11 minutes left to go (that is, $T2T(15)=11$), so the total estimated cycle completion time (from start of cycle) is now 26 minutes, which is 8 minutes more than the initial 18 minute estimate. Finally, in FIG. 33C the system has fallen behind by more than 10 minutes, so the second stage heat facility is activated and the T2T estimate is replaced by HEATX2.

[0193] FIG. 34 illustrates a user interface screen presented to a user by the thermostat 100 (or 1800) in relation to a “selectably automated” testing for heat pump polarity according to a preferred embodiment. If the user has a heat pump system, as is automatically detected by virtue of the automated detection of a wire in the O/B port described elsewhere in this specification and/or the commonly assigned applications, the selectably automated test will usually occur at or near the end of a setup interview following initial installation for determining whether the heat pump operates according to the so-called “O” convention or the so-called “B” convention. For an “O” convention heat pump heating call, the cooling call (Y1) signal type is energized while the heat pump (O/B) signal type is not energized, while for an opposing “B” convention heat pump heating call the Y1 signal type is energized while the heat pump (O/B) signal type is also energized. As described in the commonly assigned U.S. Ser. No. 13/038,191, *supra*, the thermostat 100 is capable of performing a completely automated test, in which it first actuates heating (or cooling) according to the “O” convention (which is generally known to be more common for domestic HVAC systems), and then automatically senses by virtue of a rising temperature (or a falling temperature) whether the heat pump is operating according to that “O” convention. If not, then the less-common “B” convention is tried and similarly verified to see if the heat pump is operating according to that “B” convention.

[0194] According to some embodiments for further enhancing the user experience at initial setup, further automation and selectable automation is programmed into the

thermostat **100** as follows. For one embodiment, the user is not bothered with being required to select between which particular mode (heating versus cooling) will be used for the O/B orientation test, but rather this decision is made automatically by the thermostat based on one or more extrinsic and/or sensed criteria. In one example, based on the ZIP code and current date which has been received and/or downloaded, the thermostat can make an educated guess as to whether to use heating or cooling as the first O/B orientation test. In another example, the current outside weather (as received from the cloud based on ZIP code, for example) is used in conjunction with the current room temperature to make the determination. In yet another example that has been found particularly useful, just the current room temperature is used to make the decision based on a predetermined threshold temperature such as 70 degrees F., wherein the heating mode is first used during the O/B orientation test if the current temperature is below 70 degrees F., and the cooling mode is first used during the O/B orientation test if the current temperature is above 70 degrees F.

[0195] Notably, the fully automated O/B orientation test can take some time to finish, since it can take some time to reliably determine the actual temperature trend in the room. According to one preferred embodiment, at the outset of the automated O/B orientation test, the user is presented with the screen of FIG. **34** in which they are told that an automated heat pump test is occurring, but are also given the option of manually intervening to speed up the test, where the manual intervention simply consists of telling the thermostat which function is being performed by the HVAC system, that is, whether the heat is on or whether the cooling is on. Advantageously, the user can choose to intervene by feeling the air flow and answering the question, or they can simply walk away and not intervene, in which case the automated sensing make the determination (albeit over a somewhat longer interval). This “selectably automated” O/B orientation test advantageously enhances the user experience at initial setup.

[0196] In one optional embodiment, since it has been found that most users will indeed intervene to provide the right answer and shorten the test anyway, and since a large majority of systems are indeed of the “O” convention, the thermostat **100** can be programmed to default to the “O” convention in the event there is an indeterminate outcome in the automated test (due to an open window, for example, or thermostat internal electronic heating) when the user has indeed chosen not to intervene. This is because the “O” answer will indeed be correct in most cases, and so the number of actual incorrect determinations will be very small, and even then, it is generally not a determination that will cause damage but rather will be readily perceived by the user in relatively short order, and this very small number of users can call customer support to resolve the issue upon discovery. In other embodiments, an indeterminate outcome can raise a warning flag or other alarm that instructs the user to either manually intervene in the test, or to call customer support. In still other alternative embodiments, the “O” configuration is simply assumed to be the case if the user has not responded to the query of FIG. **34** after 10 minutes, regardless of the sensed temperature trajectory, which embodiment can be appropriate if device electronic heating concerns at initial installation and startup are expected to lead to wrong conclusions a substantial percentage of the

time, especially since estimates of the prevalence of the “O” configuration have in some cases exceeded 95%.

[0197] Provided according to one preferred embodiment is a method for selectively displaying the emotionally encouraging “leaf” described above in the instant application, to encourage the user when they are practicing good energy saving behavior. This algorithm has been found to provide good results in that it can be intuitive, rewarding, and encouraging for different kinds of users based on their individual temperature setting behaviors and schedules, and is not a straight, absolute, one-size-fits-all algorithm. These rules can be applied, without limitation, for walk-up manual dial set point changes, when the user is interacting over a remote network thermostat access facility, and when the user is adjusting set point entries using a scheduling facility (either walk-up or remote access). When an example is given for heating, it can be assumed that the same rule applies for cooling, except that the direction is opposite and the numerical threshold will be different. One useful set of rules is as follows. A set of judiciously selected predetermined constants for setting forth the rules is first described. Let a heat occupied default setting be $H_{od}=68$ F (representing a generally good “occupied” heat setting to be at or below). Let a cool occupied default setting be $C_{od}=76$ F (representing a generally good cool “occupied” setting to be at or above). Let a heat away default be $H_{ad}=H_{od}-6$ F= 62 F (representing a generally good heat “away” setting to be at or below). Let a cool away default be $C_{ad}=C_{od}+6$ F= 82 F (representing a generally good cool “away” setting to be at or above). Let a heat occupied wasting default be $H_{ow}=H_{od}+6$ F= 74 F (representing a generally bad heat “occupied” setting to be above). Finally, let a cool occupied wasting be $C_{ow}=C_{od}-6$ F= 70 F (representing a generally bad cool “occupied” setting to be below).

[0198] When the thermostat is new out of the box (“OOB”) and has just been installed, there is a default single set point of $H_{od}=68$ F for heating and $C_{od}=76$ F for cooling. For the first 7 days of operation, or some other default initial “OOB” period, if the user keeps the setting at or below H_{od} (heat) or at or above C_{od} (cool), the leaf will be shown, in order to encourage initial familiarity with the concept and feelings conveyed. Thus, if the user keeps a heat set point at 68 F or below in the first 7 days, then the leaf will be displayed. Preferably, as the user changes the set point temperature gradually above 68 F (for heating), the leaf will fade out gradually over the first degree F. such that it disappears as 69F is reached. Similar fadeout/fade-in behavior is preferably exhibited for all of the thresholds described herein.

[0199] Subsequent to the 7 day period, a set of steady state leaf display rules can apply. Any time the user changes the current set point to a temperature that is 2 degrees F. less “energetic” (i.e., 2 degrees F. cooler if heating or 2 degrees warmer if cooling) than the currently scheduled temperature set point, then the leaf will be displayed. Likewise, if the user creates a set point using the scheduling facility that is 2 degrees less energetic than the existing, previously effective set point in the schedule, the leaf will be displayed. Preferably, certain limits are overlaid onto these rules. First, any time the temperature set point is below $H_{ad}=62$ F for heat or above $C_{ad}=82$ F for cooling, or moved to these ranges, the leaf will always be displayed. Second, any time the temperature the set point is above $H_{ow}=74$ F for heat

or below $C_{ow}=70$ F for cooling, the leaf will never be displayed. The second “limit” rule can be omitted in some embodiments.

[0200] Provided according to one preferred embodiment is a self-qualification algorithm by which the thermostat **1800** determines whether it can, or cannot, reliably go into an auto-away state to save energy, i.e., whether it has “sensor confidence” for its PIR activity. For one preferred embodiment, the auto-away facility is disabled for a predetermined period such as 7 days after device startup (i.e., initial installation or factory reset). On days 5, 6, and 7 from startup (or other empirically predetermined suitable sample time period), the PIR activity is tracked by discrete sequential “time buckets” of activity, such as 5-minute buckets, where a bucket is either empty (if no occupancy event is sensed in that interval) or full (if one or more occupancy events is sensed in that interval). Out of the total number of buckets for that time period ($24 \times 12 \times 3 = 864$ for 5-minute buckets), if there is greater than a predetermined threshold percentage of buckets that are full, then “sensor confidence” is established, and if there is less than that percentage of full buckets, then there is no sensor confidence established. The predetermined threshold can be empirically determined for a particular model, version, or setting of the thermostat. In one example, it has been found that 3.5% is a suitable threshold, i.e., if there are 30 or more full buckets for the three-day sample, then “sensor confidence” is established, although this will vary for different devices models and settings.

[0201] Provided according to another preferred embodiment is a method for the automated computation of an optimal threshold value for the active proximity detector (PROX) of the thermostat **1800**, by virtue of additional occupancy information provided by its PIR sensor. In order to conserve power and extend the lifetime of the LCD display and the rechargeable battery, as well as for aesthetic advantages in preventing the thermostat from acting as an unwanted nightlight, the PROX detector is integrated into the thermostat **1800** and polled and controlled by the backplate microcontroller (hereinafter “BPμC”) on a consistent basis to detect the close proximity of a user, the LCD display being activated only if there is a walk-up user detected and remaining dark otherwise. Operationally, the PROX is polled by the BPμC at regular intervals, such as every $\frac{1}{60}$ th of a second, and a PROX signal comprising a DC-removed version of the PROX readings (to obviate the effects of changes in ambient lighting) is generated by the BPμC and compared to a threshold value, termed herein a “PROX threshold”. If the PROX signal is greater than the PROX threshold, the BPμC wakes up the head unit microprocessor (“hereinafter “HUμP”), which then activates the LCD display. It is desirable for the PROX threshold to be judiciously chosen such that (i) the PROX facility is not overly sensitive to noise and background activity, which would lead to over-triggering of the PROX and unnecessary waking of the power-intensive HUμP and LCD display, but that (ii) the PROX is not overly insensitive such that the quality of the user experience in walk-up thermostat use will suffer (because the user needs to make unnatural motion, for example, such as waving their hand, to wake up the unit).

[0202] According to one preferred embodiment, the PROX threshold is recomputed at regular intervals (or alternatively at irregular intervals coincident with other HUμP activity) by the HUμP based on a recent history of PROX signal readings, wherein PIR data is included as a

basis for selecting the historical time intervals over which the PROX signal history is processed. It has been found that the best PROX thresholds are calculated for sample periods in which the noise in the PROX signal is due to “natural” background noise in the room (such as household lamps), rather than when the PROX signal is cluttered with occupant activity that is occurring in the room which, generally speaking, can cause the determined PROX threshold to be higher than optimal, or otherwise sub-optimal. Thus, according to a preferred embodiment, the HUμP keeps a recent historical record of both PIR activity (which it is collecting anyway for the auto-away facility) as well as PROX signal readings, and then periodically computes a PROX threshold from the recent historical PROX data, wherein any periods of PIR-sensed occupant activity are eliminated from the PROX data sample prior to computation of the PROX threshold. In this way, a more reliable and suitably sensitive, but not overly sensitive, PROX threshold is determined. For one embodiment, the BPμC keeps one sample of the PROX signal data for every 5 minutes, and transfers that data to the HUμP each time the HUμP is woken up. For one embodiment, the HUμP keeps at least 24 hours of the PROX signal data that is received from the BPμC, and recomputes the PROX threshold at regular 24 hour intervals based on the most recent 24 hours of PROX data (together with a corresponding 24 hours of PIR-sensed occupancy data, such as the above-described auto-away “buckets” of activity). For another embodiment, the PROX threshold is recomputed by the HUμP every time it is about to enter into a sleep state. The recomputed PROX threshold is transferred to the BPμC, which then uses that new PROX threshold in determining whether a PROX event has occurred. In other preferred embodiments, the thermostat is further configured to harness the available ALS (ambient light sensor) data to generate an event better PROX threshold, since it is known that ambient light can add to the background PROX signal noise as well as to the DC value of the PROX readings.

[0203] Studies have shown that people (segmentations) react very differently to different styles of “nudges” or prompts to change their energy behavior. For one preferred embodiment, there is provided a way on the thermostat **1800** (and on the corresponding web facility) to measure people’s responses to different energy prompts. Not only can this provide the right energy saving prompts for an individual over time, but in aggregate, the data can be an enormously useful resource to drive greater efficiency nationwide. By prompt, it is meant that some people are motivated to act by comparing them to their neighbors, some by estimating the money they have lost by not taking certain steps (such as insulation), some by estimating numbers of barrels of oil saved, etc. According to a preferred embodiment, tracking software and algorithms for grouping different prompts are provided in conjunction with the thermostat **1800** (much like web portals use to target advertising or anticipate search results). By understanding what characterizes groups of people who respond to similar prompts, there could be achieved: save more energy for learning thermostat customers, further the marketing potential of the thermostat units, and contribute to some of the biggest questions governments, nonprofits, academics and utilities are dealing with today which is how to change behavior to save energy or otherwise affect the greater good?

[0204] The presently described embodiments relate to “closing the loop” on the visual reinforcement algorithms

provided by the thermostat by detecting, monitoring, and measuring what the user is doing—if anything—responsive to the operation of the visual reinforcement algorithm. Data can then be collected for a large number of users, and then analyzed to see if the visual reinforcement algorithm is effective. Correlations can be made between particular groupings of users (including but not limited to age, number of people in household, income, location, etc.) and particular visual reinforcement algorithms. Based on correlations that have been found to be successful, the visual reinforcement algorithms can then be changed or “tuned” for each individual household or other applicable customer grouping.

[0205] In one example, provided is a thermostatic control system with closed-loop management of user interface features that encourage energy saving behaviors. In a simplest example of the invention, the thermostat can operate according to the following steps: (1) Carry out a first visual reinforcement algorithm, such as the “leaf algorithm”. (2) When the customer earns a reward, display to them the “reward leaf”. (3) For the first minute (or hour, or day) after showing the “reward leaf”, monitor the customer’s inputs (if any) and report those inputs to the central Nest server over the internet. (4) Analyze the customer’s inputs (either separately or in conjunction with a similar group of customers) to determine if the basic “leaf algorithm” was a “success” for that customer (or that group of customers). (5) If the basic leaf algorithm was not a “success” for that customer or grouping of customers, then automatically download a different visual reinforcement algorithm to that customer’s thermostat (or grouping of customer thermostats). By way of a hypothetical example, if the positive-reinforcement “leaf algorithm” was not successful, the replacement visual reinforcement algorithm could be a negative-reinforcement “smokestack” algorithm. (6) Repeat steps (2)-(5) as needed to optimize energy saving behavior according to some optimization criterion.

[0206] In one more complex embodiment of the invention, the thermostats can operate according to the following steps: (1) Over a population of different installations, carry out many different visual reinforcement algorithms for many different customers, on a random basis or according to some predetermined distribution scheme; (2) Each time a user is shown a “reward” (or “punishment”) according to their particular visual reinforcement algorithm, monitor the customer’s inputs (if any) for the first minute (or hour, or day) after showing the “reward” (or “punishment”), and report those inputs to the central Nest server over the internet; (3) Analyze the collected data to determine correlations between the success of certain visual reinforcement algorithms and the classifications of customers, geographies, etc. for which they are successful; (4) Automatically download the successful visual reinforcement algorithms for the corresponding customers, geographies, etc. for which they are successful. (5) When commissioning new thermostat installations, automatically program in the particular visual reinforcement algorithms most likely to be successful for that particular customer (e.g., based on the setup interview, purchase data, customer address, and so forth).

[0207] For some embodiments, what can be measured is the result of efficiency “infosnacks” shown on the thermostat display, like “You are using 40% more energy than your neighbors” or “Nest has calculated that your home would be X % more efficient with proper insulation” or “By not using the AC one day a week you would save 120\$ a month.”

What people act on, what people ignore, what people want to get more information about can begin to be discovered. Messages could be sent to each user depending on what they respond to and in aggregate conclusions could be drawn about the kinds of efficiency information folks respond to and why. Studies have shown that when given timely and relevant information about their energy use, consumers can reduce their energy use by 4%-15%. The trouble is, no one quite sure what makes this info relevant and therefore effective. With all the data that can be gotten from users, the thermostat **1800** including its surrounding ecosystem as described hereinabove can help answer that question.

[0208] Platform Architecture.

[0209] According to some embodiments, further description regarding platform architecture for a VSCU unit will now be provided. The VSCU is a powerful, flexible wall-mounted energy management solution. The hardware platform is open and extensible, allowing the system to be used in many applications besides the ones that have been targeted initially.

[0210] Overview.

[0211] The VSCU unit is split into two halves. (1) A head unit: this unit contains the main processor, storage, local area wireless networking, display and user interface. Also included are a range of environmental sensors plus a rechargeable battery and power management subsystems. It is removable by the user and can be connected to a computer for configuration; and (2) a backplate: this unit installs on the wall and interfaces with the HVAC wiring. It provides power to the head unit and also facilitates control of the attached HVAC systems. Optionally, it may also include a cellular wireless interface. This split allows significant flexibility in terms of installation type whilst allowing the most complex part of the system to remain common and be mass-produced.

[0212] Head Unit.

[0213] The VSCU head unit is a powerful self-contained ARM Linux system, providing ample compute resource, local storage, and networking in addition to an elegant user interface. The design has been optimized for low power operation, taking advantage of processor power saving modes and mDDR self-refresh to reduce power consumption to minimal levels when the system isn’t actively being used. The main sections of the head unit are as follows.

[0214] Processor and Memory.

[0215] A Texas Instruments AM3703 system-on-chip is used as the CPU. This provides: (1) ARM Cortex A8 core with 32 k I-Cache, 32 k D-Cache and 256 k of L2, running at up to 800 MHz at 1.3 v. The intended operation point for this part is however 300 MHz/1.0 v in order to conserve power; and (2) mDDR interface, connected to a 32 Mb×16 mDDR (64 MBytes). When not actively in use, the processor will be forced into a STANDBY mode (likely Standby 1). This power and clock gates most of the SoC to minimize both leakage and dynamic power consumption whilst retaining DDR contents and being able to wake on any GPIO event or timer tick. In this mode, the SoC and memory are expected to dissipate less than 5 m W of power.

[0216] Power Management.

[0217] The AM3703 is powered by a TI TPS65921 PMU. This part is closely coupled to the CPU and provides power for the CPU, SoC, mDDR and 10. Peripherals that do not run from 1.8V are powered off discrete low dropout voltage regulators (LDOs) as this PMU is not intended to power the rest of the system. The PMU also provides a USB2-HS PHY

which connects to the USB-mini-B connector on the back of the head unit, used for PC-based configuration.

[0218] Mass Storage.

[0219] A single 256 MB/512 MB SLC NAND flash chip is used to provide the system's mass storage. SLC flash is used to ensure data integrity—we do not want to suffer from boot failures due to data degradation or read disturb. Most SLC flash retains data for 10 years and up to 100,000 cycles. In order to ensure that pages do not get worn out, MTD/JFFS2 is expected to be used for the partitions that are rewritten frequently—this is not required for area that are just read such as X-Loader, U-Boot, etc. Redundant copies of U-Boot, kernel and root file system are stored on the NAND to provide a fallback should a software update go awry.

[0220] Display & User Interface.

[0221] A memory-mapped RGB color display with 320×320 pixel resolution and LED backlight provides the primary user interface. The backlight brightness can be adjusted with a CPU-driven PWM and can be automatically adjusted based on light sensed by the ambient light sensor. To deal with situations where the head unit is not running (e.g.: head unit hardware failure, battery discharged, etc.), a single tricolor LED connected to the backplate MCU provides a secondary means of informing the user about the device state. A rotary control with push actuation provides user input functionality. If the device is pushed in for 10 seconds, the head unit will reboot; this is a hardcoded feature provided by the TI PMU.

[0222] Wireless Communications.

[0223] The primary communications interface is an 802.11 b/g Wi-Fi module based on the TI WLI271 chip, connected via MMC2. Through this interface the VSCU unit can communicate with the server farm and provide secure remote control of the HVAC system in addition to updating temperature and climate models, reporting problems and updating software. In addition to Wi-Fi, a ZigBee transceiver is provided to communicate both with other products (such as auxiliary thermostats, other VSCU head units, baseboard heater controllers) and also with Smart Energy profile devices. The ZigBee interface is capable of running as a coordinator (ZC) if there is sufficient power available. ZigBee uses the TI CC2533 ZigBee transceiver/controller and is connected to UART2.

[0224] Configuration Interface.

[0225] A mini-B USB socket, only visible when the head unit is removed from the backplate, is provided to allow configuration of the device from a PC or Mac. The device will appear to be a USB-MSC device when connected, so no drivers are required on the host side.

[0226] Reset.

[0227] The head unit can be reset by the MCU if required.

[0228] Sensors.

[0229] Most sensors are located in the backplate, and are read over the serial interface; this allows more flexibility with PD to ensure that they are ideally located. However, one sensor is located on the head unit as it needs to be in close proximity to the display—the Ambient Light Sensor/Proximity. A Silicon Labs ALS/proximity sensor senses ambient light (to adjust LCM backlighting) and also near-field proximity to activate the UI when a user approaches the device. The interrupt line of this device is capable of waking the CPU from standby modes.

[0230] Backplate Unit.

[0231] The backplate unit interfaces with the HV AC system, providing control of attached HV AC components and also supplying power to the head unit.

[0232] Power Supplies.

[0233] A high voltage LDO provides a 3.1 v bootstrap for the MCU; this can be disabled under MCU control but it is expected that this will be left enabled to provide a “safety net” if the head unit supply vanishes for any reason such as the head unit being removed unexpectedly. The input to this LDO is provided by diode-OR'ing the heat 1, cool 1 and common wire circuits together. In normal operation, a 3.3 v LDO on the head unit powers the backplate circuitry; because of the high input voltage to this LDO, it cannot supply significant current without a lot of heat dissipation. The second supply in the backplate is the high voltage buck. The input to this supply can be switched to heat 1, cool 1 or the common wire under MCU control—only one input is expected to be selected at a time. The HV buck can supply a maximum of 100 mA at 4.5 v.

[0234] The output current of the buck is not limited; however, the input on the head unit is current limited and can be set to one of 3 valid configurations: (1) 20 mA/4.5 v (90 mW)—low setting for troublesome HVAC systems (FORCE_100 mA low, DOUBLE_CURRENT low); (2) 40 mA/4.5 v (180 mW)—default setting for power stealing (FORCE_100 mA low, DOUBLE CURRENT high); and (3) 100 mA/4.5 v (450 mW)—highest setting, forced by backplate to bring a head unit with low battery back to operational state (FORCE_100 mA high, DOUBLE_CURRENT low).

[0235] The voltage on the buck's input capacitor can be measured by the MCU, allowing it to momentarily open the WI or YI contacts during an “enabled” phase in order to recharge the buck input cap and continue to power steal. This would only be used in a single circuit system (I heat OR 1 cool). When used with two circuits (heat and cool), the system would power steal from the non-shorted circuit; with a common wire circuit, the system would not power steal at all.

[0236] Switching.

[0237] The user install backplate provides switching for 1 heat (WI), 1 cool (YI), fan (G), aux heat (AUX) plus heat pump changeover control (O/B). The pro backplate adds secondary heat (W2), secondary cool (Y2), emergency heat (E), plus dry contacts for a humidifier and dehumidifier. The regular HV AC circuits are switched using source-to-source NFETs with transformer isolated gate drive, giving silent switching. The dry contact circuits use bistable relays with two coils (set and reset) to open and close the circuits.

[0238] Sensors.

[0239] Several sensors are connected to the MCU so that the device can sense the local environment. Temp/Humidity and pressure sensors are connected via the I2C bus and three PIR sensors are also connected on the development board (one analog, two digital). (1) Temperature and humidity: a Sensirion SHT21 sensor provides accurate temperature and humidity sensing whilst taking less than 150 uW of power (150 uW=1 reading per second). (2) Pressure: a Freescale MEMS pressure sensor allows measurement of air pressure whilst taking less than 40 uW of power (~1 high resolution reading per second). Fast air pressure changes can indicate occupancy (and HVAC activity). (3) Passive Infra-red movement sensors: three PIR sensors are present on the board according to some embodiments: (a) Murata PIR with

filter/preamp: this part is fed into an analog input on the MCU, and also to a window comparator to provide a digital output. The analog circuitry effectively provides the filtering required to remove the DC bias and provide a motion sense output to the MCU; and (b) Two Perkin-Elmer digital PIRs: these are connected to the MCU and are bit-banged to read the internal ADCs. This raw value has no DC offset but still requires software filtering to reveal motion activity.

[0240] MCU.

[0241] The backplate MCU processor is a TI MSP 430F5529 CPU, providing: (1) 12 ADC channels for: (a) Voltage measurement/presence detect for common wire and 8 HV AC circuits; (b) Voltage measurement of HV buck input capacitor; and (c) Head unit VBAT measurement; (2) 3 PWM channels for driving the tricolor LED on the head unit (backplate emergency status); (3) 1 PWM channel to provide the ~5 MHz transformer drive needed to switch HV AC circuits; (4) 8 GPIOs to enable the HVAC switches once the PWM is running; (5) 4 GPIOs to set and reset the two dry contact relays; (6) 3 GPIOs to select the HV buck's input source; (7) 2 GPIOs to enable/disable the LDO and HV buck; (8) 2 I2C buses, one for the temp/humidity sensor and one for the pressure sensor; (9) 1 GPIO connected to the pressure sensors end of conversion output; (10) 3 GPIOs for PIR connection; (11) 1 GPIO to detect head unit presence; (12) 1 GPIO to reset the head unit; (13) 1 GPIO to force the head unit's charger to take 100 mA; (14) One UART for head unit communication; and (15) One UART for debug (e.g. for a development board).

[0242] Reset and Watchdog.

[0243] The backplate MCU uses a watchdog to recover from any crashes or instabilities (e.g.: ESD related events that destabilize the MCU). In addition, the head unit can reset the backplate MCU under software control by driving the RESET_BACKPLATE line high. This signal is RC filtered to prevent false triggers from transient events.

[0244] Head Unit—Backplate Interface.

[0245] The Interface Between the Two Parts of the System consists of 20 pins: (1) Power input (2 pins): power is supplied from the backplate to the head unit to nm the system and charge the head unit's local battery, which provides both a buffer for high current peaks (including radio operation) and also battery-backup for continued operation during power failures; (2) Power output (3 pins): power is supplied from the head unit to the backplate to enable high current consumption when required (for example, switching a bistable relay). The VBAT supply is intended only for use by a cellular communication device and for MCU monitoring; (3) Signal ground (2 pins): ground reference for signaling; (4) Low speed communications (2 pins): a UART interface is used for head unit-backplate communications in all configurations. This interface provides identification/authentication, sensor sampling, and control. Typically, this interface runs at 115,200 bps and is connected to a small MCU in the backplate; (5) High speed communications (3 pins): a USB1.1 12 Mbps host interface is also presented by the head unit. This can be used by advanced backplates to enable high performance networking or HV AC control, at a small power penalty above and beyond what is required for the low speed interface. Advanced backplates are not typically power-limited; (6) Detection (2 pins): one grounded at the backplate and one grounded at the head unit, allow each end to detect mating or disconnection and behave appropriately; (7) Head and

backplate reset signals (active high: NFET gate drive via RC filter to pull reset lines low); (8) LED cathode connections for RGB LED mounted in head unit; and (9) 5× current limit switch to force fast charging in low battery situations

[0246] Boot Scenarios.

[0247] Some common boot scenarios will now be described, according to some embodiments:

[0248] Scenario 1: Out of Box Experience (Battery not Empty):

[0249] (1) User has wired backplate up correctly. MCU LDO has booted MCU; (2) User connects head unit (battery PCM in protection mode); (3) Default 20 mA limit in charger resets PCM protection mode, VBAT recovers to ~3.7 v; (4) PMU turns on; (5) MCU measures VBAT, releases head unit reset; and (6) Communications established with MCU.

[0250] Scenario 2: Out of Box Experience (Battery Empty):

[0251] (1) User has wired backplate up correctly. MCU LDO has booted MCU; (2) User connects head unit (battery PCM in protection mode); (3) Default 20 mA limit in charger resets PCM protection mode, VBAT is <3Av; (4) PMU samples battery voltage but it is below the EEPROM-stored VMBCH_SEL value of 3 Av so does not power on; (5) MCU measures VBAT, sees low voltage. MCU forces 100 mA charge and turns on indicator LED; (6) When VBAT passes VMBCH_SEL voltage of 3Av, head unit will power up; (7) Communications established with MCU; and (8) Head unit asks MCU to turn off LED.

[0252] Scenario 3: Head Unit Crashed:

[0253] (1) Head unit in zombie state, not talking to MCU, battery voltage ok; (2) MCU notes no valid commands within timeout period; (3) MCU turns HV buck off to cut power, then asserts head unit reset; (4) MCU turns HV buck on again, releases reset; and (5) Communications established with MCU.

[0254] Scenario 4: Backplate Unit Crashed:

[0255] (1) Backplate unit in zombie state, not replying to SoC; (2) SoC resets MCU; and (3) Communications established with MCU.

[0256] Scenario 5: Head unit VI lockup:

[0257] (1) Head Unit UI Locked Up, but Lower Levels are functioning (MCU comms still active, so MCU will not reset UI); (2) User notices no screen activity, presses and holds button for 10 seconds causing SoC reboot; and (3) Communications established with MCU.

[0258] Power Consumption.

[0259] The system's average power consumption is determined by a few variables: (1) Power in standby mode; (2) Power in active mode; and (3) Power in interactive mode.

[0260] Standby Mode.

[0261] This mode is the one in which the system will reside "most of the time". The definition of "most of the time" can vary, but it should be able to reside in this state for >95% of the product's life. In this mode, the MCU is running but the head unit is in standby mode. HVAC circuits can be active, and the head unit can be woken into active mode by several events: (1) Proximity sensor or rotary event: The interrupt line from the prox is directly connected to the SoC and so can cause a wake directly. (2) Wi-Fi: The WL IRQ line, connected to the SoC, can wake the head unit when a packet arrives over Wi-Fi (presumably, the chipset would be programmed to only interrupt the SoC on non-broadcast packets when it was in standby); (3) ZigBee: Data

from the ZigBee chip can wake the SoC (e.g.: incoming ZigBee packets); (4) Timer: The system can wake from the RTC timer. This is likely to be used for periodic events such as maintenance of push connections over Wi-Fi and data collection; and (5) Backplate comms: Incoming communications from the backplate will wake the head unit. This could be sensor data or alarm notifications from HV AC monitoring.

[0262] The MCU is expected to enter power saving states itself regularly in order to reduce power drain—even if it is waking at 10 Hz to sample the pressure sensor, for example. Because this part of the system is always powered, improvements in efficiency here can make more difference than optimization of rarely used head unit states. The expected ballpark for head unit power consumption in this mode is: 4 mW for CPU/DDR, 2 mW for PMU, 4 mW for Wi-Fi (estimated based on other known chip sets), 2 mW for other items=11 mW. The expected ballpark for backplate power consumption in this mode (with no HVAC loads switched) is ~5 mW, but will change slightly depending on what frequency sensors are polled.

[0263] Active Mode (Display Off).

[0264] In active mode, the head unit is powered up, but the display is off. This mode is expected to be in use hundreds of times per day, but for very short periods of time (hopefully <10 seconds each event). Typical reasons the system would transition to active mode include: (1) User activity: active mode would be transitioned through on the way to interactive mode; (2) Sensor data collection: the backplate may have buffered environmental data that needs to be fed to the control algorithm and processed in order to determine whether a response is needed; (3) Push connection: in order to maintain a TCP connection through most NAT routers, data must be transferred periodically. The head unit would use active mode to perform this connection maintenance; and (4) Website-initiated action: here, a user requested action on the servers would result in data being sent over the push connection, causing the Wi-Fi module to wake the SoC to process the data and perform any necessary actions.

[0265] Given the relatively high power nature of this mode, care should be taken to ensure that any action is completed and “tidied up” before the system is put back into standby mode. For example, if a command is sent to the MCU which generates a response, the response should be gathered before the standby transition is made, otherwise the system may end up bouncing between active and standby mode, wasting power unnecessarily. The same type of problem could also occur with network connections (e.g.: TCP closes). Average power dissipated in this mode could be in the 200 mW range depending on Wi-Fi activity and processor loading.

[0266] Interactive Mode (Display on):

[0267] This is the mode in which the user actually interacts with the device. Given that the system is fully active—screen on, backlight on, low latency performance desired—the power footprint is the largest of any of the operational modes. However, because user interactions are likely to be brief and infrequent—especially if the device is performing as intended—their impact on average system power is expected to be very low. It is expected that interactive mode will have a relatively long timeout (maybe as much as 60 seconds) before the unit transitions into active mode and then to standby. It would be worth having the unit stay in active mode for a significant time—maybe 30 seconds or

more—on the way down so that if the user starts to interact with the device again, the response is instantaneous. Average power in this mode is likely to be greater than 300 mW depending on Wi-Fi activity, processor loading, and display backlight brightness.

[0268] Example Power Consumption Calculation.

[0269] Table 1 shows how the total system power consumption might be calculated.

TABLE 1

Mode	Power	Time in mode	Times per day	%	Ave. Power per 24 h
Interactive	300 mW	60 s	4	0.28%	0.83 mW
Active	200 mW	10 s	192	2.22%	4.44 mW
Standby	11 mW	84,240 s	1	97.50%	10.73 mW
				Average Power	16 mW

[0270] As can be seen from Table 1, the dominant power is that of standby, though waking the head unit 8 times per hour (192 times per day) is also not insignificant. Switching each HVAC zone also takes power, estimated at ~1 mA @ 3.3 v (i.e., 4.5 mW of power at the HV buck output assuming the battery is full). We are likely to be switching multiple circuits concurrently—at least 1H/1C+fan. This can significantly increase our power consumption and hence also needs to be optimized appropriately.

[0271] Power Supply.

[0272] From surveys, it would appear that we are likely to be able to draw 40 mA @ 5 vdc from the HV buck; as this is a switching converter, this 200 mW power should translate directly to 44 mA @ 4.5 vdc in our system. Initially, it was thought that we may only be able to take 100 mW or less from the HV AC circuits, so this is good news. Note that in any system that has both heat and cool (but NOT heat pump), the system can power steal from the non-activated circuit ensuring that we have 200 mW of power available at all times.

[0273] Whereas many alterations and modifications of the present invention will no doubt become apparent to a person of ordinary skill in the art after having read the foregoing description, it is to be understood that the particular embodiments shown and described by way of illustration are in no way intended to be considered limiting. Therefore, reference to the details of the preferred embodiments are not intended to limit their scope.

Flexible Functionality Partitioning Within Intelligent-Thermostat-Controlled HVAC Systems

[0274] In the above discussion of the VSCU and VSCU-related components within HVAC systems, with reference to FIGS. 1A-34, many features and components of VSCU-based HVAC-control systems have been described, including the elegant and intuitively functional user interface provided by the VSCU, VSCU communications and cooperation with remote computational facilities, diverse types of environmental sensors incorporated within the VSCU, and intelligent learning and adaptation functionality distributed across VSCUs and remote computational facilities. While numerous different implementations have been described in the preceding discussion, the present subsection is directed to describing and characterizing a further range of implementations made possible by the architecture of VSCU-

based HVAC-control systems. This architecture provides extremely flexible partitioning of functionality between and among various different types of components, subcomponents, and computational facilities.

[0275] In the following discussion, the phrase “intelligent thermostat” is used to refer to a class of processor-controlled thermostats that communicate with remote computational facilities, that feature a broad range of sensors and sensing technologies, that provide elegant and intuitive electro-optico-mechanical user interfaces, and that includes the above-described VSCU. In this subsection, continued use is made of the acronym “HVAC” in the interest of clarity and consistency with the preceding discussion. However, it should be understood that the term “HVAC” is meant, in the present discussion, to refer not only to traditional heating, ventilation, and air-conditioning systems, but also to a broader range of environmental-conditioning systems that monitor and change physical characteristic of an environment, such as the interior of a building. As one example, a traditional HVAC system may sense temperature excursions above and below a desired temperature range and invoke air-conditioning and heating units, respectively, to return environmental temperatures to within the desired temperature range. The term “HVAC” is expanded, in the present subsection, to include environmental-conditioning systems that not only detect temperature excursions and appropriately invoke air-conditioning and heating units, but that also detect and ameliorate air contaminants, ingress of water and other fluids, undesirable acoustic phenomena, and other changes in normal environmental conditions. This is but one example of the broader scope of the environmental-conditioning systems which the term HVAC refers, in the current subsection.

[0276] FIGS. 35A-B illustrate certain components and architectural sources of flexibility of intelligent-thermostat-controlled HVAC systems to which the current application is directed. As shown in FIG. 35A, an intelligent-thermostat-controlled HVAC system includes one or more local HVAC units **3502**, may include one or more intermediate boxes **3504**, and includes one or more intelligent thermostats **3506-3508**. Each intelligent thermostat, such as intelligent thermostat **3506**, includes a base **3509**, or concealed portion, and a visible portion **3510**, as discussed above with reference to FIG. 7. The concealed portion may be either completely or partially concealed by the visible portion when the visible portion is mounted to the concealed portion to produce a fully installed and fully functional intelligent thermostat.

[0277] A traditional HVAC unit may have various input/output interfaces, as discussed above with reference to FIGS. 8A-D. In FIG. 35A, HVAC unit **3502** is shown to have a 12-wire input/output interface **3510**. However, different types of HVACs may have a greater number or smaller number of input/output wires. In addition, future HVAC units may additionally provide an RF antenna **3512** or other external transceiver component and corresponding internal communications functionalities to allow the HVAC unit to receive commands and transmit information over various communications media according to any of various different communications protocols. HVAC units are responsible for providing environment conditioning, such as heating, cooling, and other environmental-conditioning operations. HVAC units are generally directly wired into the power-distribution media within a building or other envi-

ronment. HVAC units are also often directly interconnected with various types of liquid or gas inputs and liquid or gas outputs.

[0278] An intelligent-thermostat-controlled HVAC system may also include one or more intermediate boxes, such as intermediate box **3504**, with certain routing and control functionality depending on the particular intelligent-thermostat-controlled HVAC system. In FIG. 35A, the intermediate box is shown with a 12-wire first input/output interface **3514** complementary to the 12-wire input/output interface **3510** of the HVAC unit and a second six-wire input/output interface **3516**. In certain cases, the intermediate box serves as a multiplexer/demultiplexer to provide an HVAC input/output interface comprising a particular number and type of control wires for compatibility with intelligent thermostats. In other cases, the intermediate box may include additional control functionality, including all or a portion of the control functionality of an intelligent thermostat. In certain cases, the intermediate box may be a third-party component or, alternatively, may be a subcomponent of the HVAC unit, in which cases the intermediate box may be enhanced with intelligent-thermostat interface and control functionality, shown as layer **3518** to the right-hand side of the dashed boundary **3520** of the third-party intermediate box or HVAC-component intermediate box. The intermediate box may have an RF antenna **3522** or other external transceiver component along with internal communications functionality to allow the intermediate box to communicate by various communications media to other intelligent-thermostat-controlled HVAC system components. In some cases, the intermediate box may have only an RF antenna or other external transceiver component **3522**, without the second input/output interface **3516**. Alternatively, the intermediate box may have only a second input/output interface **3516**, without the RF antenna or the transceiver components **3522**. Other implementations of intermediate boxes may include both an RF antenna or other external transceiver component **3522** as well as a second input/output interface **3516**.

[0279] There are many different possible configurations for intelligent thermostats that are within the scope of the present teachings, three of which are shown in FIG. 35A. The base, or concealed portion, of the intelligent thermostat may feature one or both of an RF antenna or other external transceiver component **3524** and an input/output wired interface **3526**, as in the case of intelligent thermostat **3506**, may alternatively have an RF antenna or other external transceiver component **3528** and a wired interface to a building power-distribution medium **3530**, as in the case of intelligent thermostat **3507**, or may have neither an RF antenna or other external transceiver component nor an input/output wired interface, and instead serve primarily as a structural baseplate, as in intelligent thermostat **3508**. The visible portions of the intelligent thermostat, as shown in FIG. 35A, may or may not have one or more RF antenna or other external transceiver components and may or may not have direct wire control and power connections to their complementary base portions.

[0280] FIG. 35B indicates a large variety of different types of implementations based on different types of interconnections between various components of an intelligent-thermostat-controlled HVAC system to which the current application is directed. FIG. 35B uses dashed double-headed arrows, such as dashed double-headed arrow **3532**, to indicate intercommunications between intelligent-thermostat-

controlled HVAC-system components. FIG. 35B also includes a cloud symbol 3534 to indicate interconnection to remote computing facilities via a local router and Internet-services provider ("ISP"), directly through RF-frequency communications to a mobile-service provider, such as a 3G or 4G cellular-telephone-service provider, or by other wireless communications. As can be seen by the plethora of dashed double-headed arrows interconnecting the small number of intelligent-thermostat-controlled HVAC-system components shown in FIG. 35B, many different types of interconnection architectures and strategies can provide the basis for many different types of implementations, all of which are within the scope of the present teachings. As one example, an intelligent-thermostat HVAC-control system may not include an intermediate box and may feature direct wire interconnection of an HVAC unit and the base portion of an intelligent thermostat, as represented by dashed double-headed arrow 3536, with direct electrical interconnection between the base portion and visible portion of the one or more intelligent thermostats and with either one or both of the base portions and visible portions interconnected by wireless communications to remote computational facilities via an ISP, mobile-service provider, or other wireless communications system, as indicated by bifurcated triple-headed dashed arrow 3538. Alternatively, an intelligent-thermostat HVAC-control may include only a wire interconnection between an HVAC unit and an intermediate box, represented by dashed double-headed arrow 3540 and wireless interconnection between an intermediate box and either or both of the concealed and visible portions of one or more intelligent thermostats, as represented by the bifurcated triple-headed dashed arrow 3642 in FIG. 35B. Two or more intelligent thermostats may intercommunicate with one another via direct, local wireless communications, via remote computational facilities reached through an ISP, mobile-service provider, or other wireless system, or through local wireless communications to one or more intermediate boxes.

[0281] As illustrated in FIGS. 35A-B, there are a very large number of different possible intelligent-thermostat HVAC-system-control systems that can be implemented based on the different types of communications interconnections between components, including wired interconnections, wireless interconnections with remote computational facilities, and local wireless communications such as ZigBee RF communications protocol and transceiver components. Every component in an intelligent-thermostat HVAC-control system can potentially be interconnected to remote computational facilities directly through an ISP or mobile-service provider. The flexibility provided by all of the various types of component interconnects facilitates flexibly partitioning of functionality among components, including distribution of computational overheads and tasks among local and remote computing facilities, as discussed further below.

[0282] FIGS. 36A-H illustrate an architecture-based flexibility in function partitioning of HVAC-control systems, to which the current application is directed, that provides for many alternative implementations. FIG. 36A illustrates a general implementation strategy, based on the above-described architecture for the intelligent-thermostat-controlled HVAC system, by which a large number of different implementations can be obtained, depending on various implementation goals and constraints. FIG. 36B-H use the same

illustration conventions as used in FIG. 36A. In a first, bottom portion of FIG. 36A 3602, many of the subcomponents of an intelligent-thermostat-controlled HVAC system to which the current application is directed are symbolically listed. These subcomponents are described in the preceding discussion of the VSCU and related intelligent-thermostat-controlled HVAC-system components and include a microprocessor 3604, such as the microprocessor that is included, in one implementation, in the VSCU to control various user-interface functions, control functions, and communications functions, and a microcontroller 3606 that, in one implementation discussed above, is included in the concealed portion of the VSCU to carry out numerous low-level, low-power-consuming tasks. The listed subcomponents additionally include many different types of sensors, including humidity sensors 3608, temperature sensors 3610, visible-light sensors 3612, proximity detectors 3614, and other environmental sensors. It should be noted that any of a wide variety of different particular types of sensors manufactured by different manufacturers can be incorporated into components of the intelligent-thermostat-controlled HVAC systems to which the current application is directed. The listed subcomponents also include a status indicator 3616, a mechanical user interface 3618, and an optico-electrical user interface 3620, along with a display driver 3622 for controlling the optico-electronic user interface 3620. The listed subcomponents additionally include a wireless module 3624, such as an RF module that communicates with a local wireless router or a 3G or 4G wireless module for direct communications with a mobile-service provider and a local wireless communications module, such as the above-described ZigBee RF transceiver components 3626. The listed subcomponents additionally include a protocol engine 3628, SDRAM memory 3630, mass NAND storage 3632, a long-term battery energy source 3634, a lithium-ion battery buffer or other type of battery buffer 3636, wire-insertion sensors 3638 and wire connectors 3640, power-supply circuitry 3642, power-management circuitry 3644, wake-on circuitry 3646, capacitors 3648, power-stealing circuitry 3650, and FET switches 3652. The subcomponents shown in the lower section 3602 of FIG. 36A are meant as a representative collection of subcomponents, but do not represent all of the different subcomponents of any particular intelligent-thermostat-controlled HVAC system. Moreover, many different possible instances of each of these subcomponents can be employed, including subcomponents manufactured by different manufacturers with different aggregate functionalities and having different interfaces. In certain cases, individually listed subcomponents may be aggregated together within a larger subcomponent, and the functionality of a listed subcomponent may instead be obtained from two or more less-functional subcomponents.

[0283] The middle portion 3654 of FIG. 36A represents constraint-and-goal-based functionality distribution or partitioning by which particular implementations of the intelligent-thermostat-controlled HVAC system are obtained. A number of different types of constraints and goals may direct functionality distribution among the components of an intelligent-thermostat-controlled HVAC system, including cost, maintainability, upgrade flexibility, reliability, ease of installation, overall functionality and robustness, and other such constraints and goals.

[0284] In a third portion 3656 of FIG. 36A, lists of subcomponents 3658, 3660, 3662, and 3664 correspond to

the partitioning of subcomponents and associated functionalities among the HVAC unit or units, one or more intermediate boxes, one or more intelligent-thermostat concealed portions, and one or more intelligent-thermostat visible portions, respectively. Symbolic representations of the HVAC, intermediate box, concealed portion, and visible portion are shown above lists **3665-3668**.

[0285] FIG. **36A** represents the starting point for the design process, rather than a particular implementation, and so the subcomponent and functionality distribution shown in the third portion **3656** of FIG. **36A** is largely empty. In FIG. **36A**, the visible portion of the intelligent thermostat is shown as necessarily including an external visible cover **3670** and the HVAC unit is shown to include heating/cooling/other environmental-conditioning functionalities **3672** and input/output wires and other HVAC unit connections **3674**. As noted above, in the future, the HVAC unit may not include a wire input/output interface. This represents the only initial constraint on the design process discussed with reference to FIGS. **36A-H**. The remaining subcomponents in the lower portion **3602** of FIG. **36A** may be distributed or replicated and distributed among the one or more HVAC units, one or more intermediate boxes, and one or more intelligent thermostats according to particular goals and constraints in order to produce particular intelligent-thermostat-controlled HVAC-system implementations. Many implementations do not include an intermediate box, which is therefore an optional component. It should also be noted that a particular intelligent-thermostat-controlled HVAC system may comprise two or more different types of implementations illustrated by a partitioning shown in a figure using the illustration conventions of FIG. **36A**.

[0286] FIGS. **36B-H** illustrate, using the illustration conventions of FIG. **36A**, seven different possible implementations of an intelligent-thermostat-controlled HVAC system or a portion of an intelligent-thermostat-controlled HVAC system to which the current application is directed. These seven different implementations are but only a very few of the many different possible implementations that can be obtained by the design process of FIG. **36A** under various specific design constraints and goals. In the implementation shown in FIG. **36B**, there is no intermediate box, and the HVAC unit is directly connected to a concealed portion of one of one or more intelligent thermostats, as represented by double-headed arrow **3676** in FIG. **36B**. As shown in list **3662** of FIG. **36B**, the concealed portion of each intelligent thermostat includes several sensors, a microcontroller, wake-on circuitry, switches, several capacitors, power-supply circuitry, and power-stealing circuitry, as represented by the icons or symbols in list **3662**. The visible portion of the intelligent thermostat includes the various subcomponents in list **3664** in FIG. **36B**. These include a microprocessor, wireless module, a local-wireless module, mechanical and optico-electrical user interface components, numerous environmental sensors, a display driver, protocol engine, battery buffer, various types of memory, and a power-management module. All of these components are discussed above with reference to FIGS. **1A-34**. The implementation shown in FIG. **36B** corresponds to an above-discussed implementation illustrated in FIGS. **18A-25**. In this implementation, the power-stealing circuitry, power-supply circuitry, and wire connectors are placed proximally to the wire input/output interface in the concealed portion of the intelligent thermostat, with the remaining intelligent-thermostat control func-

tionality placed into the visible portion of the intelligent thermostat. This implementation provides a reliable, easily-installed concealed portion with much of the more complex, higher-level functionality placed in the visible portion of the intelligent thermostat, which can be quickly removed and replaced during maintenance and repair, and which can be easily upgraded by replacement of the visible portion.

[0287] FIG. **36C** shows a different implementation obtained by a different partitioning of functionality between the main components of an intelligent-thermostat-controlled HVAC system to which the current application is directed. This implementation is similar to that shown in FIG. **36B**, except that most of the significant power-consuming subcomponents are shifted from the visible portion of the intelligent thermostat to the concealed portion of the intelligent thermostat. In this implementation, the visible portion of the intelligent thermostat, as shown in list **3664** in FIG. **36C**, includes only the mechanical and optico-electrical user interfaces, numerous sensors, and the battery buffer. The microprocessor, wireless modules, display driver, protocol engine, memory, power-management module, and other subcomponents have been shifted to the concealed portion of the intelligent thermostat as shown in list **3662** in FIG. **36C**. In this case, the functionality partitioning has been carried out to place as many of the significant power-consuming subcomponents as possible onto the concealed portion of the intelligent thermostat. In a related implementation, the battery buffer **3677** may be replaced by a long-term replaceable battery **3678** or may be supplemented with the long-term battery so that the visible portion becomes relatively power-independent from the concealed portion. In yet an additional related implementation, even the battery buffer may be transferred from the visible portion to the concealed portion, so that the visible portion includes only passive user-interface features and a few temperature sensors. The visible portion, in this implementation, becomes a relatively low-cost item that can be easily interchanged for stylistic or other purposes. Moreover, the visible portion, in such an implementation, can be removed from the concealed portion without interrupting or degrading intelligent-thermostat function.

[0288] FIG. **36D** shows yet a different implementation in which much of the functionality has been moved from the concealed portion, as shown in list **3662** in FIG. **36D**, to the visible portion of the intelligent thermostat, shown in list **3664** in FIG. **36D**. In this implementation, the concealed portion serves primarily to interconnect the visible portion with a building power-distribution system. Alternatively, rather than power-supply circuitry and capacitors, the concealed portion may, in an alternative implementation, contain a long-term battery **3678** as a power source for the visible portion of the intelligent thermostat. This implementation would be suitable for an auxiliary intelligent thermostat that intercommunicates with a main or primary intelligent thermostat, implemented according to the implementation shown in FIG. **36B**. The auxiliary and primary intelligent thermostats can intercooperate to control one or more HVAC units. Auxiliary thermostats, as one example, may be placed in various locations, as, for example, in bedrooms or basements, to allow occupants to control HVAC operation with respect to subregions of the entire environment or to conveniently control the entire environment from regions distant from the primary intelligent thermostat. The primary intelligent thermostat may be

directly coupled to a wire interface and may obtain operational power by the power-stealing mechanism, discussed above, while the auxiliary thermostats obtain power from building power-distribution systems, long-term, high-capacity batteries, or other power sources.

[0289] FIG. 36E illustrates yet another intelligent-thermostat-controlled HVAC system. This implementation is similar to the implementation shown in FIG. 36B, with the exception that an intermediate box is included to interface to a wire input/output interface of the HVAC with significantly more wires than can be conveniently accommodated by the concealed portion of certain intelligent thermostats. The intermediate box thus acts as a multiplexer/demultiplexer allowing the concealed portion of the intelligent thermostat to interface to a wire input/output interface with fewer wires. This may be important when the size of the intelligent thermostat is a significant constraint and when it is impractical or not cost-effective to increase the number of switches, wire connectors, and insertion sensors in concealed portion of the intelligent thermostat. The remaining functionality is partitioned in FIG. 36D similarly to the functionality partitioning shown in FIG. 36B.

[0290] FIG. 36F shows yet a different implementation of the intelligent-thermostat-controlled HVAC system to which the current application is directed. In this implementation, an intermediate box is employed, and much of the functionality of the concealed portion of the intelligent thermostat has been moved to the intermediate box, as can be seen by comparing lists 3662 and 3660 in FIG. 36F with the same lists in FIG. 36E. In this implementation, the concealed portion of the intelligent thermostat serves only to connect the visible portion of the intelligent thermostat to a building power-distribution system. The visible portion of the intelligent thermostat communicates directly with the intermediate box or through the cloud. In a similar implementation shown in FIG. 36G, the intermediate box assumes even more of the overall functionality, with the visible portion of the intelligent thermostat independently powered by a long-term battery. In both the implementation shown in FIGS. 36F and 36G, the intermediate box, either a third-party intermediate with a proprietary enhancement or a proprietary intermediate box, assume significant portions of the control functionality allowing the intelligent thermostats to function more as auxiliary intelligent thermostats and to be powered independently from HVAC wiring.

[0291] FIG. 36H shows another intelligent-thermostat-controlled HVAC system to which the current application is directed. In this embodiment, no intermediate box is used, the visible portion of the intelligent thermostat has similar functionality to the visible portion of the intelligent thermostat of the implementation shown in FIG. 36B, but the concealed portion of the intelligent thermostat has all of the functionality of the concealed portion of the thermostat in the implementation of FIG. 36B as well as much redundant functionality included in the visible portion. This can be seen by comparing list 3662 in FIG. 36H with list 3662 in FIG. 36B. In this implementation, the concealed portion of the intelligent thermostat is essentially a stand-alone intelligent thermostat with all of the capabilities of the intelligent thermostat in the implementation shown in FIG. 36D. The visible portion of the intelligent thermostat is mostly redundant. In this implementation, the visible portion may be removed and, at a later time, replaced with another visible portion, perhaps including a third-party visible portion, in

order to enhance or change the user interface and/or appearance of the intelligent thermostat. While including redundant functionality in the concealed and visible portions of the intelligent thermostat may not, by itself, be terribly cost-effective, the redundancy may provide many added benefits, including increased reliability, robustness, and configuration flexibility that offset the added cost of including redundant components.

[0292] As discussed above with reference to FIGS. 35A-B, the architecture for the intelligent-thermostat-controlled HVAC system provides for flexible distribution of communications and control between components of an intelligent-thermostat-controlled HVAC system which, in turn, provides for numerous different implementations that may be beneficial for particular environments, particular existing HVAC systems, and for other situations. As discussed above with reference to FIGS. 36A-H, the ability to partition subcomponents among the HVAC, intermediate box, concealed portion, and the visible portion of the intelligent thermostat provide for a very large number of different possible implementations that address many different implementation constraints and goals. However, the architecture of the intelligent-thermostat-controlled HVAC systems to which the current application is directed provides even greater overall implementation flexibility. FIG. 37 illustrates additional implementation flexibility arising from the computationally distributed nature of the intelligent-thermostat-controlled HVAC systems to which the current application is directed. As shown in FIG. 37, microcontrollers, microprocessors, and other computational engines can be incorporated into the concealed portions of intelligent thermostats 3702 and 3704, the visible portions of intelligent thermostats 3706 and 3708, future HVAC units 3710, and intermediate boxes 3712. In addition, all of these components may be directly or indirectly interconnected with remote computational facilities, such as remote cloud servers 3714 via an Internet service provider, mobile-service provider, or other intermediate communications facility. As a result, all of the computational tasks associated with HVAC control can be distributed in many different ways among all of the different processing entities within the intelligent-thermostat-controlled HVAC system, both statically and dynamically. As communications bandwidths continue to improve, and as the reliability and fault tolerance of communications media improve, it may become feasible to transfer increasing portions of the total computational load of HVAC control to remote computational facilities, simplifying the computational entities and control programs included in local intelligent-thermostat-controlled HVAC system components. By contrast, as microprocessors become more capable and as electronic memories become faster, denser, and more economical, a greater portion of the computational load may be shifted to local computational entities, rather than carried out by remote computational facilities. The computationally distributed nature of the intelligent-thermostat-controlled HVAC systems to which the current application is directed allow for many different static and dynamic partitionings of the overall computational load in order to optimize various implementation goals under any of many different constraint combinations. Furthermore, significant increases in robustness and fault tolerance can be achieved by dynamically shifting the computational load from remote computational facilities to local computational facilities and back again,

depending on the current status and throughput of communications interconnections, local power availability, and other factors.

[0293] It should be noted that the implementations shown in FIGS. 36A-H may pertain to only a portion of the intelligent thermostats, HVAC units, or intermediate boxes within any particular intelligent-thermostat-controlled HVAC system. In other words, certain of the intelligent thermostats may be implemented according to one implementation shown in one of FIGS. 36A-H, while another may be implemented according to another implementation shown in FIGS. 36A-H. As mentioned above, FIGS. 36A-H show only a very few of the many possible different implementations that can be achieved through alternative partitioning and functionality among intelligent-thermostat-controlled HVAC system components.

[0294] Although the present invention has been described in terms of particular embodiments, it is not intended that the invention be limited to these embodiments. Modifications within the spirit of the invention will be apparent to those skilled in the art. For example, as discussed above, there are many different possible implementations of the intelligent-thermostat-controlled HVAC systems and components of the intelligent-thermostat-controlled HVAC systems to which the current application is directed that can be obtained through functionality partitioning according to the implementation process discussed above with reference to FIGS. 36A-H. For example, as discussed above, the concealed portion of a certain class of intelligent thermostats may be stand-alone intelligent thermostats with electro-optico-mechanical user interfaces, full communications capabilities, and other subcomponents that together provide intelligent-thermostat functionality to the concealed portion alone, may be less-functional intelligent thermostats with less functional user interfaces, fewer sensors, and less-functional communications subcomponents, or may have very simple mechanical user interfaces and rudimentary thermostat functionality. By contrast, the concealed portion may be merely a structural docking unit or a structural docking unit that provides power to the visible portion of the intelligent thermostat, via direct wiring into a building power-distribution system, via an adapter that plugs into an electrical outlet, or via a battery or other internal energy source, allowing multiple auxiliary intelligent thermostats to be used in addition to a primary intelligent thermostat that is directly connected to an HVAC wire input/output interface.

[0295] In certain implementations, for example, the concealed and visible portions of the intelligent thermostat, particularly of intelligent thermostats used in auxiliary-intelligent-thermostat roles, may be combined to form a single, portable or semi-portable unit. In certain implementations, the intelligent thermostats may be dedicated auxiliary and primary intelligent thermostats, with the auxiliary and primary roles statically and dynamically configurable before and after installation, while, in other implementations, the roles may dynamically vary with usage and user input, with both auxiliary and primary intelligent thermostats similarly or identically equipped with functionality. In other implementations, an intermediate box interfaces to the wired input/output interface of an HVAC unit and provides a wireless or wired interface to an intelligent thermostat. The intermediate box may act primarily as a multiplexer/demultiplexer or bridge, or, in alternative implementations, may include a portion of, or all of, the functionality of an

intelligent thermostat. For any given communication interconnections between intelligent-thermostat-controlled HVAC-system components, many different alternative implementations may be obtained by differently distributing functionalities and computing tasks, including distributing computing tasks to remote computer facilities interconnected to the intelligent-thermostat-controlled HVAC system through local routers and ISPs, through 3G and 4G wireless modules and mobile service providers, and by other means.

[0296] Within the scope of the described embodiments is, in one example, a portable or semi-portable unit that, in many respects, physically resembles a radio boombox, a clock radio, or other desktop appliance or nightstand appliance or entertainment device, the unit serving as a docking station, the unit having integrated thereonto a concealed portion into which a visible portion of the intelligent thermostat is mateably connectable to form an auxiliary intelligent thermostat unit (i.e., one that is not directly connected to HVAC wiring). Within the scope of the described embodiments is for the docking station to include one or more temperature sensors, humidity sensors, occupancy sensors, wireless communications modules, auxiliary processor modules, or other thermostat-related sensors or modules, and to be powered by a conventional wall socket or AC/DC transformer. Because there will generally be fewer space limitations and power limitations on the docking station-mounted components, those components can be of higher-capacity, higher sensitivity, and/or reduced cost as compared to a compact wall-mounted unit, and furthermore there can be more spacing between components such that internal heating effects are substantially reduced as a design constraint. When the visible portion of the intelligent thermostat is mated with the docking station, one or more of the intelligent thermostat functions can be carried out by one or more of the docking station components for overall increased performance, either in a substituted context (e.g., the ambient temperature sensing functionality is performed fully by the temperature sensors in the docking station rather than in the visible portion) or in a supplemental context (e.g., the ambient temperature sensing functionality is performed jointly by the temperature sensors in both the docking station and the visible portion). Optionally, the docking station can indeed be operative as a radio boombox, clock radio, or other such appliance in addition to the thermostat docking functionality. Indeed, in one scenario, the docking station can have two docking connectors, one of the docking connectors corresponding to the concealed (partially concealed) portion of the intelligent thermostat for mating with the visible portion, the other of the docking connectors being a conventional iPod/iPhone/iPad docking connector (or other smart device connector) for mating with an iPod, iPhone, iPad, or other smart device. More generally, it is to be appreciated that while the concealed portions illustrated in FIGS. 35A-37 are illustrated in the form of a disc shaped backplate, which is particularly useful for wall-mount scenarios, it is to be appreciated that the concealed portions can be readily formed for installation onto, and/or for integration into, a wide variety of surfaces, places, positions, or vessels.

[0297] It is to be appreciated that the previous description of the disclosed embodiments is provided to enable any person skilled in the art to make or use the present disclosure. Various modifications to these embodiments will be readily apparent to those skilled in the art, and the generic

principles defined herein may be applied to other embodiments without departing from the spirit or scope of the disclosure. Thus, the present disclosure is not intended to be limited to the embodiments shown herein but is to be accorded the widest scope consistent with the principles and novel features disclosed herein.

What is claimed is:

1. A climate control system, comprising:
 - a heating, ventilation, and air conditioning (HVAC) unit that provides heating and/or cooling for an enclosure, wherein the HVAC unit is positioned at a first location in the enclosure;
 - an intermediate box comprising:
 - a first wireless communication module;
 - a plurality of HVAC wires coupled to the HVAC unit for controlling the HVAC unit; and
 - circuitry to convert commands received through the first wireless communication module to HVAC control signals on the plurality of HVAC wires; and
 - a thermostat positioned at a second location in the enclosure that is substantially apart from the first location, the thermostat comprising:
 - one or more memories;
 - a second wireless communication module in communication with the first wireless communication module of the intermediate box;
 - an occupancy sensor;
 - a temperature sensor; and
 - one or more processors configured to:
 - log thermal responses of the enclosure during HVAC cycles;
 - log occupancy data based on readings from the occupancy sensor;
 - send the thermal responses and the occupancy data to a cloud server, wherein the cloud server (i) generates a thermal model of the enclosure, and (ii) generates an optimized HVAC schedule based on the thermal model of the enclosure and the occupancy data;
 - receive the optimized HVAC schedule from the cloud server; and
 - operate the HVAC unit according to the optimized HVAC schedule by sending the commands to the intermediate box through the second wireless communication module for conversion to HVAC control signals on the plurality of HVAC wires.
2. The climate control system of claim 1, wherein the thermostat is powered at least in part by a battery.
3. The climate control system of claim 2, wherein the thermostat is not connected to a line power source, and the thermostat is not connected to a C wire from the HVAC system.
4. The climate control system of claim 1, wherein the thermal responses and the occupancy data are sent periodically to the cloud server.
5. The climate control system of claim 4, wherein the thermal responses and the occupancy data are sent once per day to the cloud server.
6. The climate control system of claim 1, wherein the optimized schedule is downloaded at least once per season.
7. The climate control system of claim 1, wherein the one or more processors comprise one or more low-power processors that can be used because the optimized HVAC schedule is generated at the cloud server.

8. The climate control system of claim 1, wherein the thermostat further comprises a long-distance wireless communications module that connects the thermostat through a local router to an Internet Service Provider (ISP), through which the thermostat communicates with the cloud server.

9. The climate control system of claim 1, wherein the thermostat comprises a mechanical user interface comprising a ring configured to track a rotational input motion of a user, wherein said ring is further configured to be inwardly pressable by the user.

10. The climate control system of claim 9, wherein the thermostat comprises an electronic display disposed within the ring.

11. A method of controlling a climate control system, the method comprising:

using a heating, ventilation, and air conditioning (HVAC) unit to provide heating and/or cooling for an enclosure, wherein the HVAC unit is positioned at a first location in the enclosure;

connecting an intermediate box to the HVAC unit, wherein the intermediate box comprises:

a first wireless communication module;

a plurality of HVAC wires coupled to the HVAC unit for controlling the HVAC unit; and

circuitry to convert commands received through the first wireless communication module to HVAC control signals on the plurality of HVAC wires; and

operating a thermostat positioned at a second location in the enclosure that is substantially apart from the first location, wherein the thermostat comprises:

one or more memories;

a second wireless communication module in communication with the first wireless communication module of the intermediate box;

an occupancy sensor;

a temperature sensor; and

one or more processors configured to:

log thermal responses of the enclosure during HVAC cycles;

log occupancy data based on readings from the occupancy sensor;

send the thermal responses and the occupancy data to a cloud server, wherein the cloud server (i) generates a thermal model of the enclosure, and (ii) generates an optimized HVAC schedule based on the thermal model of the enclosure and the occupancy data;

receive the optimized HVAC schedule from the cloud server; and

operate the HVAC unit according to the optimized HVAC schedule by sending the commands to the intermediate box through the second wireless communication module for conversion to HVAC control signals on the plurality of HVAC wires.

12. The method of claim 11, wherein the thermostat is powered at least in part by a battery.

13. The climate control system of claim 12, wherein the thermostat is not connected to a line power source, and the thermostat is not connected to a C wire from the HVAC system.

14. The method of claim 11, wherein the thermal responses and the occupancy data are sent periodically to the cloud server.

15. The climate control system of claim 14, wherein the thermal responses and the occupancy data are sent once per day to the cloud server.

16. The method of claim 11, wherein the optimized schedule is downloaded at least once per season.

17. The method of claim 11, wherein the one or more processors comprise one or more low-power processors that can be used because the optimized HVAC schedule is generated at the cloud server.

18. The method of claim 11, wherein the thermostat further comprises a long-distance wireless communications module that connects the thermostat through a local router to an Internet Service Provider (ISP), through which the thermostat communicates with the cloud server.

19. The method of claim 11, wherein the thermostat comprises a mechanical user interface comprising a ring configured to track a rotational input motion of a user, wherein said ring is further configured to be inwardly pressable by the user.

20. The method of claim 19, wherein the thermostat comprises an electronic display disposed within the ring.

* * * * *