




US 20170145677A1




(19) **United States**(12) **Patent Application Publication**
Coppola(10) **Pub. No.: US 2017/0145677 A1**(43) **Pub. Date: May 25, 2017**(54) **WATER INLET PROTECTION SYSTEM**(52) **U.S. Cl.**(71) Applicant: **FLO-WATER, LLC**, West Des Moines,
IA (US)CPC *E03F 5/16* (2013.01); *B01D 29/118*
(2013.01); *B01D 35/02* (2013.01); *C02F 1/001*
(2013.01); *B01D 2201/10* (2013.01); *C02F*
2103/001 (2013.01)(72) Inventor: **Corydon Coppola**, West Des Moines,
IA (US)

(57)

ABSTRACT(21) Appl. No.: **15/359,907**(22) Filed: **Nov. 23, 2016****Related U.S. Application Data**(60) Provisional application No. 62/259,985, filed on Nov.
25, 2015.**Publication Classification**(51) **Int. Cl.***E03F 5/16* (2006.01)*B01D 35/02* (2006.01)*C02F 1/00* (2006.01)*B01D 29/11* (2006.01)

A water inlet protection system and apparatus for removing sediment and/or chemical from water or other fluids is provided. The system may include a filtration material that is configured to be water permeable and to collect sediment within the water. The system may be configured to be removably secured to various types of storm drains or water inlets. The system may include a frame configured to be removably attached to a storm grate. The frame may also include a plurality of tabs extending from the frame and be slidably adjustable. The system may also include an s-clip member or magnets for removably securing the filtration material to a storm drain or water inlet. Furthermore, the water inlet protection system may include one or more over-flow protection openings. The over-flow protection openings may include a raised member or barrier to regulate the water level where over-flow occurs.








FIG. 3A




FIG. 3B




FIG. 3C




FIG. 3D




FIG. 3E




FIG. 4A




FIG. 4B




FIG. 5A




FIG. 5B




FIG. 6A




FIG. 6B




FIG. 6C




FIG. 7A




FIG. 7B




FIG. 8A







FIG. 8B





- INSTALLATION INSTRUCTIONS:
1. ATTACH THE REMOVABLE AND REPLACEABLE BAG TO THE ADJUSTABLE FRAME WITH THE ATTACHED VELCRO.
 2. REMOVE THE STORM GRATE.
 3. INSTALL THE FLOW-WATER EZ-CATCH INLET PROTECTION WITH TABS UP.
 4. REPLACE STORM GRATE

WATER INLET PROTECTION SYSTEM

CROSS REFERENCE TO RELATED APPLICATION

[0001] This application claims priority under 35 U.S.C. §119 to provisional application Ser. No. 62/259,985, filed Nov. 25, 2015, herein incorporated by reference in its entirety.

FIELD OF THE INVENTION

[0002] The invention relates generally to a water inlet protection system. More specifically, but not exclusively, the invention relates to a water filtration system for use with a water inlet.

BACKGROUND OF THE INVENTION

[0003] As the world continues to grow and expand, construction and the harvesting of natural resources has increased exponentially. These activities impact the environment.

[0004] Specifically, some of the Earth's greatest landscapes are threatened by increased road construction, oil and gas exploration, and mining. Soil erosion, run-off, and chemicals leaching into the soil or ground water supplies are just a few of the many things that can negatively impact the environment. Because impervious surfaces (parking lots, roads, buildings, compacted soil) do not allow rain to infiltrate into the ground, more runoff is generated than in the undeveloped condition. This additional runoff can erode watercourses (streams and rivers) as well as cause flooding after the storm water collection system is overwhelmed by the additional flow. Because the water is flushed out of the watershed during the storm event, little infiltrates the soil, replenishes groundwater, or supplies stream base flow in dry weather. The negative effect of these events can be greatly increased when improper or outdated erosion and sediment control systems are put into place.

[0005] Current erosion and sediment control systems include the use of silt fencing, sand bags, and storm drain covers. Silt fences are often perimeter controls, typically used in combination with sediment basins and sediment traps, as well as erosion controls, which are designed to retain sediment in place where soil is being disturbed by construction processes. A typical fence consists of a piece of synthetic filter fabric (also called a geotextile) stretched between a series of wooden or metal fence stakes along a horizontal contour level. The stakes are installed on the downhill side of the fence, and the bottom edge of the fabric can be trenched into the soil and backfilled on the uphill side, although it is quite difficult to move the trenched "soil" from the downside to the upside of the trench. The design/placement of the silt fence should create a pooling of runoff, which then allows sedimentation to occur. Water can seep through the silt fence fabric, but the fabric often becomes "blocked off" with fine soil particles. Sediment is captured by silt fences primarily through ponding of water and settling, rather than filtration by the fabric. Sand and silt tends to clog the fabric, and then the sediments settle in the temporary pond. Silt fence fabrics (geotextiles) tested in laboratory settings have shown to be effective at trapping sediment particles. Although there have been few field tests of silt fences installed at construction sites, these tests have shown generally poor results. Other studies and articles

about silt fence usage and practice document problems with installation and maintenance, implying poor performance.

[0006] Other forms of sediment control and erosion prevention include the use of sandbag barriers, fiber rolls, and storm drain inlet protection. Sandbag barriers may prevent or divert the flow of contaminated water away from a water source or storm drain, but they fail to provide a filter for removing contaminants from the water and allowing clean water to pass through. Fiber rolls are generally a temporary erosion control and sediment control device used on construction sites to protect water quality in nearby streams, rivers, lakes and seas from sediment erosion. Typically they will be made of straw, coconut fiber or similar material formed into a tubular roll. While these fiber rolls do provide a basic form of filtration, they generally provide only minimal filtration and are not reusable. Some of the disadvantages of fiber rolls are that they may be difficult to move once they become saturated with water, they should not be used on very steep land, and if the rolls are not properly staked into the ground, they may be carried away by high flows. Storm drain inlet protections typically only include a steel grate with large openings. While they prevent large items from entering a storm drain or inlet, they fail to prevent soil sediment and other contaminants from entering the drain. A sand barrier or fiber roll may be placed around a storm drain inlet to provide additional protection, but these items typically provide either extremely slow flow rates or else minimal filtration.

[0007] Therefore, there exists a need in the art for an apparatus and system that allows for improved filtration and removal of sediment and other pollutants from water, as well as providing an increased flow rate through the filtration system.

BRIEF SUMMARY OF THE INVENTION

[0008] Therefore, it is a primary object, feature, and/or advantage of the invention to improve on and/or overcome the deficiencies in the art.

[0009] It is another object, feature, and/or advantage of the invention to provide an apparatus and system that includes a frame with a plurality of tabs extending from the periphery of the frame.

[0010] It is yet another object, feature, and/or advantage of the invention to provide an apparatus and/or system for use with a storm drain or water inlet that is configured to remove sediment and other contaminants from water.

[0011] It is a further object, feature, and/or advantage of the invention to provide an apparatus with an adjustable frame and plurality of tabs extending from the frame, wherein the frame may be adjustably configured to fit multiple storm drain and inlet sizes.

[0012] It is still a further object, feature, and/or advantage of the invention to provide a system including a frame with a plurality of tabs extending from the periphery of the frame, wherein the tabs are configured to removably secure the frame via a friction fit to a grate of a storm drain.

[0013] It is still a further object, feature, and/or advantage of the invention to provide a drain inlet protection system including a frame, a plurality of tabs extending from the frame, and a filtration material removably secured to the frame. Wherein the filtration material is configured to be water permeable and to filter out sediment from the water.

[0014] It is still a further object, feature, and/or advantage of the invention to provide a drain inlet protection system

including a frame with one or more corner members that are slidably interconnected to one another, said frame adjustable to fit multiple storm drain opening and/or grate sizes.

[0015] It is still a further object, feature, and/or advantage of the invention to provide a drain inlet protection system including a filtration material removably secured to a storm drain opening by one or more magnets that are attached to the filter material.

[0016] It is still a further object, feature, and/or advantage of the invention to provide a drain inlet protection system including one or more s-clip members configured to secure a filtration material within an open throat drain inlet, said one or more s-clip members securing the material within the opening via a pressed or friction fit.

[0017] It is still a further object, feature, and/or advantage of the invention to provide a drain inlet protection system.

[0018] It is still a further object, feature, and/or advantage of the invention to provide a drain inlet protection system utilizing a filtration material with a water flow rate of approximately 190 gpm/ft².

[0019] It is still a further object, feature, and/or advantage of the invention to provide a drain inlet protection system utilizing a filtration material with a water flow rate of approximately 240 gpm/ft².

[0020] It is still a further object, feature, and/or advantage of the invention to provide a drain inlet protection system utilizing a filtration material with a water flow rate between approximately 190 gpm/ft² and approximately 240 gpm/ft² and a filtering efficiency of approximately 90%.

[0021] These and/or other objects, features, and advantages of the invention will be apparent to those skilled in the art. The invention is not to be limited to or by these objects, features and advantages. No single embodiment need provide each and every object, feature, or advantage.

BRIEF DESCRIPTION OF THE DRAWINGS

[0022] Appendix A is an example of a marketing piece that includes additional information on one embodiment according to at least some aspects of the present invention.

[0023] FIG. 1 is a perspective view of an example embodiment of a drain inlet protection system.

[0024] FIG. 2A is a top view of an alternative embodiment of a drain inlet protection system.

[0025] FIG. 2B is a perspective view of the drain inlet protection system of FIG. 2A.

[0026] FIG. 3A is a top view of an alternative embodiment of a drain inlet protection system.

[0027] FIG. 3B is a perspective view of the drain inlet protection system of FIG. 3A.

[0028] FIG. 3C is a top view of the inlet protection system frame of FIG. 3A.

[0029] FIG. 3D is a top view of an alternative embodiment of the inlet protection system frame of FIG. 3A.

[0030] FIG. 3E is a side view of the inlet protection system frame of FIG. 3D.

[0031] FIG. 4A is a top view of an alternative embodiment of a drain inlet protection system.

[0032] FIG. 4B is a perspective view of the drain inlet protection system of FIG. 4A.

[0033] FIG. 5A is a perspective view of an example embodiment of a drain inlet protection system.

[0034] FIG. 5B is a side view of the inlet protection system of FIG. 5A.

[0035] FIG. 6A is a perspective view of an alternative embodiment of a drain inlet protection system including overflow protection.

[0036] FIG. 6B is a perspective view of an alternative embodiment of a drain inlet protection system including overflow protection.

[0037] FIG. 6C is a top view of an alternative embodiment of a drain inlet protection system including overflow protection.

[0038] FIG. 7A is a perspective view of an alternative embodiment of a drain inlet protection system.

[0039] FIG. 7B is a perspective view of an alternative embodiment of a drain inlet protection system.

[0040] FIG. 8A is a top view of an alternative embodiment of a drain inlet protection system.

[0041] FIG. 8B is a side view of the drain inlet protection system of FIG. 8A.

[0042] FIG. 9A is a perspective view of a drain inlet protection system of FIG. 1 including a drain inlet back-stop.

[0043] FIG. 9B is a perspective view of the drain inlet back-stop of FIG. 9A in combination with the alternative embodiment of a drain inlet protection system of FIG. 2.

[0044] Various embodiments of the invention will be described in detail with reference to the drawings and appendices, wherein like reference numerals represent like parts throughout the several views. Reference to various embodiments does not limit the scope of the invention. Figures represented herein are not limitations to the various embodiments according to the invention and are presented for exemplary illustration of the invention.

DETAILED DESCRIPTION OF THE PREFERRED EMBODIMENTS

[0045] The invention is directed towards an apparatus and system for filtering water at a storm drain or water inlet. A water inlet protection system may be used to prevent unwanted sediment and other contaminants from entering a storm drain, water inlet, or the like. For example, a water inlet protection system may be inserted in a storm drain to filter water that enters the drain, the system removing unwanted sediment and contaminants. Generally a water inlet protection system may include a filter or filtering material. For example, the water protection system shown in Appendix A includes a filter material that is configured to trap sediment contained in water that passes through the storm drain grate and allow the filtered water to pass through into the drain.

[0046] Referring to FIG. 1, an example embodiment for an above grate water inlet protection system **30** is shown. The system **30** may be configured to fit any size, shape or configuration of above ground storm drain or water inlet. For example, the system may be configured to fit a square drain, a round drain, or a vertically oriented drain on the side of a curb. The embodiment shown in FIG. 1 includes a lower portion **33** or flap that may be tucked under the grate, wherein the grate creates a friction fit to help hold the system **30** in place. The embodiment shown in FIG. 1 may also be used in connection with the above grate systems shown in FIGS. 6A-7B (described in more detail below and shown in FIGS. 6A and 7A) and/or with the below grate systems shown in FIGS. 2A-3E (described in more detail below). The filter material **34** for the above grate system may be the same or similar to Grey Material, which will be described in

more detail below. The system **30** may be removably attached to the water inlet by one or more magnets **32**. The system may also include a neoprene or similar rubber-type material attached to the perimeter of the filtration material **34**. The neoprene may be configured to create a seal around the perimeter of the water inlet to prevent water from entering the inlet without first passing through the material **34** to be filtered.

[0047] Referring to FIGS. 2A-4B, example embodiments of a water inlet protection system that includes a frame **10** is shown. The frame **10** may be constructed of one or more corner members **12** and **14** that may be securely fastened to one another in a solid configuration. In a preferred embodiment, the frame **10** of the system may be configured to sit on the underside of the grate **44**, wherein the frame **10** is pinched between the grate and the drain opening. However, it should also be understood that it is contemplated that the frame may be configured to sit and/or be attached to the top of the grate **44**. The solid frame **10** configuration may be in the shape of a circle (as shown in FIG. 4A-4B), square (as shown in FIGS. 2A-2B and 3D), rectangle (as shown in FIGS. 3A-3C), or any other polygonal shape. While not shown in the figures, the corners may also be inverted or rounded to fit a specific drain opening or grate size. It is also contemplated that the corner members **12** and **14** may be adjustably connected. For example, opposing corners **12** and **14** may be slidably connected using a pin **18** and a track or slot **16**. The corners **12** and **14** may also be slidably connected by a solid member (not shown), wherein each of the corner section **12** and **14** includes a pin **18** that is configured to slidably attach to tracks at opposing ends of the solid member. The pins **18** in the corner sections may be configured to slide within the track or slot of the solid member connecting the corner members. In one example embodiment, the adjustable frame **10** may be configured to adjust the length and width of a square or rectangular shaped storm drain or water inlet. The frame **10** may include slidably adjustable members **12** and **14** that allow the length and width of the frame to be adjusted to correspond to the size of the drain. Furthermore, the frame **10** is configured for attachment of a filter or filter material **34**. As shown in the picture included in FIGS. 2A-4B, the filter material **34** may be attached by wrapping it around a portion of the corner members **12** and **14**. The filter material **34** may be secured by sewing the seam **46**, attaching Velcro® along the seam **46**, hooks, pins, or other similar means of securing the material **34** in place. An example filter material **34** is a High Flow Grey Material that includes the following approximate properties:

Properties	ASTM TEST	Value
Mass per Unit Area (oz/yd ²)	D 3776	5.2
Grab Tensile Strength, MD × CD (lbs)	D 4632	297 × 223
Grab Elongation, MD × CD (%)	D 4632	58/59
Trapezoid Tear, MD × CD (lbs)	D 4533	81 × 75
Puncture (lbs)	D 4833	99
Burst Strength (psi)	D 3786	340
Permittivity (sec-1)	D 4491	2.60
A.O.S. (U.S. sieve - (mm)	D 4751	60
Water Flow Rate (gpm/ft ²)	D 4491	192
Filtering Efficiency (%)	D 5141	91.6

While the High Flow Grey is given as an example above, any suitable filter or filtering material **34** may be used. An

example of an advantage provided by the referenced material, is that the material is reusable. The High Flow Grey Material may be removed from the storm drain, the sediment captured in the material may be removed from the material and disposed in a proper manner, and the material may be reinstalled in the drain. The material **34** may be rinsed and reused multiple times without compromising the filtering properties or flow properties. Also shown in the image included in FIGS. 2B, 3B, and 4B, it can be seen that at the corners of the frame **10**, there may be openings or cut-outs **42** the filter material **34**. These openings **42** are intended to provide overflow protection in the event the filter material **34** becomes plugged or clogged to the point water is unable to pass through the material **34**. If this occurs, the water may still be able to pass through the openings **42** in the corners to prevent water from backing up or flooding over into other areas because the drain is blocked. The frame **10** and/or material **34** may also include a loop or handle **38** for lifting and/or removing the system **10** from a storm drain/water inlet.

[0048] Referring to FIG. 3D, a top view of the adjustable frame **10** is shown. While FIGS. 2A-2B and 3D depict the frame **10** in a generally square configuration, it should be understood that other sizes and shapes are considered. For example, the frame **10** may be adjusted to be in the shape of a rectangle (FIGS. 3A-3C), or additional slidably adjustable sides may be added to create a pentagon, hexagon, or similar shapes that may be utilized to fit a round shaped storm drain or sewer opening. Each side of the frame includes a top member **14** and an opposing bottom member **12**. The top and bottom members **14** and **12** are slidably connected by one or more pins **18** or similar means of slideable or telescoping attachment or connection. For example, the top member **14** may include a fixed pin **18** extending downward through a slot or track **16** cut in the bottom member **12**. Conversely, the bottom member **12** may include a fixed pin **18** extending upward through a slot or track **16** in the top member **14**. The pins **18** and tracks or slots **16** are configured to allow the top and bottom members **14** and **12** to slide relative to one another, shortening or lengthening that side of the frame **10**. All sides of the frame **10** may be configured in a similar manner to allow the length of each side to be adjustable. It is also contemplated that the corners may be attached by a connection member that allows for slideable adjustment of the size and length of the frame **10**. The connection may be attached to the top or bottom of both opposing corner members **12** and **14**, or the connection member may connect to the top of one member **12** and the bottom of the opposing member **14**, or vice versa. The connection may be flat or may include one or more bends to achieve the required fit and/or adjustment. It is also contemplated that the adjustable frame may incorporate a telescoping mechanism to provide adjustment of the frame.

[0049] Referring to FIG. 3E, a side view of one side of the frame is shown. It can be seen how the top and bottom members **14** and **12** may be oriented relative to one another. Also shown are how the pins **18** extend from the top member **14** down through the bottom member **12** and vice versa. Furthermore, as shown in FIGS. 2A-4B, located in the corners of the frame **10** are tabs **20** that extend vertically from the frame. These tabs **20** are configured to hold the frame **10** in place when positioned in a storm drain or water inlet. For example, the frame **10** may be placed in a storm drain with a filter material **34** attached. The frame **10** may be

extended to fit the size of the drain. Once the frame 10 has been extended to fit the drain, the grate 44 may be placed on top of the frame 10. The tabs 20 may be configured to be outside the outer edge of the frame of the storm grate, therefore preventing the adjustable frame 10 from being pulled inward when a weight or force is applied to the filter material 34 by fluid or material trying to pass through the drain. The tabs 20 may create a friction fit with the grate to hold the system 10 in place. While the frame has been described as adjustable, it is contemplated that a solid frame may also utilize the tabs 20 for positioning, orienting, or holding in place the frame relative to a storm drain grate or sewer cover.

[0050] Referring to FIGS. 5A-5B, an example embodiment of a water inlet protection system 30 for use with an open throat inlet along a curb 50, or similar. This embodiment includes an s-shaped clip member 35 that may be sewn into the filtering material 34. The s-clips 35 may be located at the ends or edges 37 of the inlet system 30, but additional s-clips 35 may be located along the width of the system to provide additional support if needed.

[0051] The s-clips 35 generally may be constructed of a flexible material, such as a metal alloy or plastic polymer. The clips 35 should provide necessary strength and flexibility properties to be wedged into the open throat inlet opening along a curb 50 to create a pressed or friction fit with the inlet opening of the curb 50, as shown in the side view of FIG. 5B. This embodiment of the protection system 30 may include a neoprene strip 36 along the horizontally oriented edges to provide a seal to the curb or drain surface when the neoprene is wet. S-clips 35 may be attached to the filtration material 34 by sliding the clips 35 in between seams in the fabric or other similar means of removable attachment may be utilized. The edges of the material 34 may be configured to butt up end to end to attach additional open throat protection systems 30 together if a wider system is needed for a particular drain or inlet. The VelcroTM may also be configured for attaching a solid member that may be configured to directing the flow of the water through the filter material.

[0052] Referring to FIGS. 6A-6C, three example embodiments of an above grate system 30 are shown. Common components that may be included in all three embodiments include a handle or pull strap 38, magnets 32, and a neoprene strip 36. The handle or pull strap 38 may be used for lifting or removing the system 30 from a storm drain or water inlet. The magnets 32 may be sewn into or similarly attached to the filter material 34 and configured/positioned to magnetically/removably attach the system 30 to a steel grate 44 or inlet of a storm drain or similar water inlet. For example, in the square shaped embodiment, as shown in FIG. 6B, the magnets 32 may be located at the corners so as to magnetically attach the system 30 to the corner of square grate 44 of a storm drain. Generally the magnets 32 may be positioned anywhere within the confines of the protection system, but typically will be located proximate to the corners or edges so as to create a seal at the outer edge so that storm water may not enter the drain without first passing through the filter material 34. The magnets 32 also serve to hold the system 30 in place, such that it does not blow away or get swept away by flowing water. The magnets 32 may also be placed on top of the fabric. Similarly, a neoprene strip(s) 36 may be included or sewn into the outer edge of the material 34 of the system 30 and configured to create a seal at the outer edge

to prevent water from entering the drain 44 without first passing through the filter material 34. The neoprene 36 may be configured, such that when wet, it will increase in weight and create a seal with the grate 44 of the drain or the structure surrounding the drain.

[0053] FIG. 6A shows an example embodiment of the system 30 for use with a vertical water inlet on the side of a curb may also include a solid core, such as a polyethylene member, that is designed to give the system 30 structure and rigidity along the back edge along vertical inlet portion of the curb 50. The solid core may also serve to prevent the flow of water through the vertical portion of the inlet, which typically may not include any type of grate or screening, while directing the water to pass through the filter material 34 located on top of the horizontal portion of the drain/grate 44.

[0054] Referring to FIGS. 6A-8B, examples of the square and circular embodiments of the above grate protection system 30 are shown. In FIGS. 6B and 7B, the square system 30 is shown, include one or more handles 38, magnets 32, neoprene strips 36, and the filter material 34. Similarly, FIGS. 6C and 8A-8B show examples of round embodiments including one or more handles 38, magnets 32, neoprene strips 36, and the filter material 34. FIGS. 6A-6C show example embodiments of the system 30 including an overflow protection member 40 surrounding a cut-out portion 42 of the filtering material 34. The overflow protection member 40 may be included in any or all embodiments of the water inlet protection system 30. The overflow protection barrier shown in FIG. 6A-6C. may include an elevated ring or square member 40 with a hole in the center 42 that allows water to pass directly through to the drain 44. The overflow protection member 40 is intended to provide overflow protection in the event the filter material 34 becomes plugged or clogged to the point water is unable to pass through the material 34. If this occurs, the water may still be able to pass through the openings 42 in the center to prevent water from backing up or flooding over into other areas because the material 34 over the drain 44 is blocked.

[0055] As shown in FIG. 6A-6C, the overflow protection barrier may be elevated above the filter material 34 to facilitate or encourage water to pass through the filter material 34 as opposed to entering the drain 44 through the hole 42 in the center of the overflow barrier 40. The height of the overflow barrier 40 may be configured based on the specific needs at a particular drain site. For example, if a standing water level exceeding three inches (3") would be damaging or hazardous to the surrounding area, the protection member 40 may be configured to have a height of two inches to prevent standing water from ever reaching a height of three inches (3"). However, if it is more important that all water entering a particular drain pass through the filter material 34, the height of the protection member 40 may be increased.

[0056] FIGS. 7A-8B show alternative embodiments of a drain inlet protection system that may be attached to the top of the grate of a storm drain or similar water inlet. The embodiments shown in FIG. 7A-8B do not include the water over flow barrier or cut-out.

[0057] Referring to FIG. 9A, an alternative embodiment of the system 30 represented in FIG. 1 is shown. FIG. 9A shows an inlet protection system including a back-stop 31 that is not permeable. The system 30 shown in FIG. 9A may be configured to have a non-permeable backstop to direct the

flow of water elsewhere, and prevent water from entering an opening on the vertical portion of a curb 50. The embodiment shown in FIG. 9A may be utilized in combination with the other inlet protection systems 10 and/or 30 described above. For example, the system 30 of claim 9A may be used in connection with the below-grate inlet protection system 10 shown in FIGS. 2-3, wherein the lower portion of 33 of system 10 may be inserted underneath the grate 44 that the below-grate frame 12 and 14 of the inlet protection system 30 is attached to. In this example, the back-stop 31 will prevent water from flowing in the vertical inlet/opening on the curb 50, and will re-direct the water to flow down the grate 44, wherein the water will be filtered through the filter material 34 attached to the frame 12 and 14. The back-stop 31 may also be used in connection with the above-grate systems shown in FIGS. 6 and 7, as depicted in FIGS. 6A and 7A.

[0058] While not shown in the figures, it should be understood that alternative forms of water filtration and inlet protection systems have been contemplated. For example, the filtering material described above may be utilized to construct a dewatering bag to filter sediment out of water pumped through the bag prior to entering a drain or other water system. The dewatering bag may be made or constructed of a filter material similar to the material described above. Furthermore, the dewatering bag may be configured to be used in conjunction with a hose or pump. In preferred embodiment that dewater bag may be attached to a hose that is connected to the outlet of a pump. For example, the dewatering bag may include an opening or inlet that may be configured for attaching a hose to the dewatering bag. The bag may then be placed near or proximate to a drain or water inlet, and as the pump transfers water to the dewatering bag, the water will pass through the filter material, leaving sediment and other contaminants trapped in the dewatering bag. Furthermore, chemicals and/or other filtering elements may be inserted in the dewatering bag to aid with the removal or reduction of harmful chemicals, such as nitrates, from the water.

[0059] The dewatering bags may come in many shapes and sizes. For example, a short and wide shaped configuration may be utilized for a dewatering bag. Alternatively, the dewatering bag may be long and narrow. The size and shape of the dewatering bag may be configured based on the size of the drain or water inlet. The size of the dewatering bag may also be configured based on the size of the pump and/or the amount of fluid pumped. It may also be configured based on pump size and/or the size of the hose utilized to pump water into the dewatering bag. A strap may be utilized to removably secure the dewatering bag to a hose or pump. For example, a strap that includes a D-ring clip for fastening the strap may be used to removably secure the dewatering bag to a pump outlet.

[0060] This embodiment of the protection system will generally come in a predetermined length, for example ten feet (10') lengths. The ends of the protection system may include Velcro™, D-rings and a strap, or similar means of connection that are configured for attaching multiple lengths of the protection system together. A strap may also be used for attaching multiple lengths of the protection system together. The protection system may be configured to include handles that can be used in moving or placing the protection system.

[0061] It is also contemplated that the water inlet protection system may include filter material (as described above) attached to a plurality of wood or metal stakes or similar. The stakes may be utilized to orient the filter material in a vertical position. Furthermore, the stake can hold the filter material in place and attach the filter material to the ground and provide a boundary for filtering out sediment from water. The filter material may have a height of approximately 39.5 inches.

[0062] Another embodiment of a water inlet protection system may also be configured for use in the concrete or construction industry. For example, the water inlet protection system may be configured to separate the sediment and materials included in concrete from the water. When cleaning tools or rinsing out containers utilized in pouring concrete, any leftover or reaming concrete must be properly disposed of and should not be rinsed down a drain. The water inlet protection system may include a base and frame for attaching a filtering material to. The base and frame may be configured in a square, rectangular or generally round shape, but may be constructed in any shape that includes an opening at the top. The concrete may be rinsed into the filter material and water applied. Chemicals should also be added to aid the removal or reduction of PH levels and/or contaminants. For example, Bio-flucculant and PLO-flocculant enables filtering of fines. PH Stabilizer may also be added to relegate PH when needed. For use with concrete, an additional geotextile fabric is required to slow the filtration process and allow the chemicals to mix/interact with the concrete and water mixture. The filter material may be configured to remove the concrete material and other sediment, while allowing the water to pass through the material. The water passing through the filter material may then pass safely through the drain or water inlet without introducing the sediment and contaminants included in concrete. Filtering out the water from the concrete also allows the concrete material to dry faster and be properly disposed of once captured by the filter material.

[0063] While many embodiments of the filter material 34 to be used with the water inlet protection systems described above are contemplated, two example embodiments of the material are described in greater detail below. One example embodiment of filter material with the following properties and/or characteristics:

Properties	ASTM TEST	Value
Mass per Unit Area (oz/yd ²)	D 3776	5.2
Grab Tensile Strength, MD × CD (lbs)	D 4632	297 × 223
Grab Elongation, MD × CD (%)	D 4632	58/59
Trapezoid Tear, MD × CD (lbs)	D 4533	81 × 75
Puncture (lbs)	D 4833	99
Burst Strength (psi)	D 3786	340
Permittivity (sec-1)	D 4491	2.60
A.O.S. (U.S. sieve - (mm)	D 4751	60
Water Flow Rate (gpm/ft ²)	D 4491	192
Filtering Efficiency (%)	D 5141	91.6

An alternative embodiment of the filter material may include a filter material with the following properties and/or characteristics:

Properties	ASTM TEST	Value
Mass per Unit Area (oz/yd ²)	ISO 9073-1	3.84
Breaking Strength, MD (lbs/2 in)	ISO 9073-3	102.4
Breaking Strength, CMD (lbs/2 in)	ISO 9073-3	87.9
Elongation to break, MD (%)	ISO 9073-3	32.8
Elongation to break, CMD (%)	ISO 9073-3	34.7
Water Flow Rate (gpm/ft ²)	Mfg Testing	240

It is also contemplated that a filtering material **34** may be utilized that includes a flow rate somewhere in between the two materials referenced above.

[0064] A water inlet protection system including a filter material capable of removing sediment and other water contaminants, while allowing for an improved flow of water has thus been described. The present invention contemplates numerous variations, options and alternatives, and is not to be limited to the specific embodiments described herein. For example, any of the alternative embodiments described above may be modified or used in combination with one or more of the other embodiments. Other changes are considered to be part of the present invention.

What is claimed is:

1. A drain inlet protection system, said system comprising:
 - a frame;
 - a filtration material removably attached to the frame;
 - a plurality of tabs extending from the periphery of the frame; and
 - wherein the plurality of tabs are configured to removably secure the frame to a storm drain cover and/or grate.
2. The drain inlet protection system of claim 1, further comprising one or more handles attached to the filtration material and/or frame.
3. The drain inlet protection system of claim 1, wherein the frame comprises one or more corners.
4. The drain inlet protection system of claim 3, wherein the filtration material further comprises a cut-out section proximate to the one or more corners of the frame.
5. The drain inlet protection system of claim 3, wherein the plurality of tabs extending from the periphery of the frame proximate to the one or more corners.
6. The drain inlet protection system of claim 1, wherein the frame is an adjustable frame that further comprises a top member and an opposing bottom member, said top member and said bottom member in slideable communication with one another.
7. The drain inlet protection system of claim 1, wherein the frame is an adjustable frame that further comprises a plurality of solid corner members slidably interconnected by one or more flat members.
8. The drain inlet protection system of claim 1, wherein the plurality of tabs are configured to create friction fit with an outer edge of a storm drain grate.
9. The drain inlet protection system of claim 1, wherein a portion of the filtration material is wrapped about the frame.

10. The drain inlet protection system of claim 1, wherein the filtration material is configured to be water permeable and to collect sediment.

11. The drain inlet protection system of claim 1, wherein the frame is a solid frame.

12. The drain inlet protection system of claim 11, wherein the solid frame is a round shaped frame.

13. A drain inlet protection system, said system comprising:

- a filtration material;
- one or more magnets configured to removably secure the filtration material to a drain opening; and
- wherein the filtration material is configured to be water permeable and to collect sediment.

14. The drain inlet protection system of claim 13, wherein the filtration material comprises a water flow rate of 192 gpm/ft² and a filtering efficiency of 91%.

15. The drain inlet protection system of claim 13, further comprising an overflow opening.

16. The drain inlet protection system of claim 15, further comprising an overflow member proximate to the overflow opening, said overflow member configured to create an elevated barrier to the overflow opening.

17. The drain inlet protection system of claim 13, further comprising one or more handles.

18. The drain inlet protection system of claim 13, further comprising a sealing member proximate to an outer edge of the filtration material, said sealing member made of a neoprene material and configured to create a seal between the curb and the filtration material.

19. The drain inlet protection system of claim 13, wherein the filtration material comprises a water flow rate of 240 gpm/ft².

20. A drain inlet protection system, said system comprising:

- a filtration material;
- a plurality of s-clip members removably secured to the filtration material;
- wherein the plurality of s-clip members configured to secure the filtration material to an open throat water drain inlet positioned along a curb; and
- wherein the plurality of s-clip members are configured to create a friction fit with an opening of the open throat water drain inlet.

21. The drain inlet protection system of claim 20, wherein the at least one of the plurality of s-clip members is positioned proximate to each edge of the opening of the open throat water drain inlet.

22. The drain inlet protection system of claim 20, further comprising a sealing member along a top edge and/or a bottom edge of the filtration material, said sealing member made of a neoprene material and configured to create a seal between the curb and the filtration material.

* * * * *