



Office de la Propriété

Intellectuelle
du Canada

Un organisme
d'Industrie Canada

Canadian
Intellectual Property
Office

An agency of
Industry Canada

CA 2741764 A1 2010/06/03

(21) **2 741 764**

(12) **DEMANDE DE BREVET CANADIEN**
CANADIAN PATENT APPLICATION

(13) **A1**

(86) Date de dépôt PCT/PCT Filing Date: 2009/10/27
(87) Date publication PCT/PCT Publication Date: 2010/06/03
(85) Entrée phase nationale/National Entry: 2011/04/27
(86) N° demande PCT/PCT Application No.: US 2009/062147
(87) N° publication PCT/PCT Publication No.: 2010/062573
(30) Priorités/Priorities: 2008/10/27 (US61/108,595);
2009/10/26 (US12/605,584)

(51) Cl.Int./Int.Cl. *C07D 403/12*(2006.01),
A61K 31/506(2006.01), *A61P 31/00*(2006.01)


(71) Demandeur/Applicant:
POLYMEDIX, INC., US

(72) Inventeurs/Inventors:
DEGRADO, WILLIAM F., US;
LIU, DAHUI, US;
SCOTT, RICHARD W., US;
XU, YONGJIANG, US;
TANG, HAIZHONG, US;
KORCZAK, BOZENA, US

(74) Agent: RIDOUT & MAYBEE LLP


(54) Titre : MIMETIQUE SYNTHETIQUE DE DEFENSE D'HOTE ET SON UTILISATION

(54) Title: SYNTHETIC MIMETICS OF HOST DEFENSE AND USES THEREOF



Time in hours

Figure 1A



Time in hours

Figure 1B

(57) Abrégé/Abstract:

The present invention provides arylamide compounds and methods of making and using them as antibiotics.

(12) INTERNATIONAL APPLICATION PUBLISHED UNDER THE PATENT COOPERATION TREATY (PCT)

(19) World Intellectual Property Organization
International Bureau(43) International Publication Date
3 June 2010 (03.06.2010)(10) International Publication Number
WO 2010/062573 A1(51) International Patent Classification:
A61K 38/00 (2006.01)19087 (US). **XU, Yongjiang** [CN/US]; 651 Vassar Road, Wayne, PA 19087 (US). **TANG, Haizhong** [CN/US]; 161 Franklin Corner Road, G-1, Lawrenceville, NJ 08648 (US). **KORCZAK, Bozena** [CA/US]; 219 Sugartown Road, Building D, Suited 104, Wayne, PA 19087 (US).(21) International Application Number:
PCT/US2009/062147(74) Agent: **LEGAARD, Paul, K.**; Pepper Hamilton LLP, 400 Berwyn Park, 899 Cassatt Road, Berwyn, PA 19312 (US).(22) International Filing Date:
27 October 2009 (27.10.2009)(25) Filing Language:
English(26) Publication Language:
English(30) Priority Data:
61/108,595 27 October 2008 (27.10.2008) US
12/605,584 26 October 2009 (26.10.2009) US(71) Applicant (for all designated States except US): **POLY-MEDIX, INC.** [US/US]; 170 N. Radnor-Chester Road, Suite 300, Radnor, PA 19087-5221 (US).(72) Inventors; and
(75) Inventors/Applicants (for US only): **DEGRADO, William, F.** [US/US]; 502 Bancroft Road, Media, PA 19063 (US). **LIU, Dahui** [CN/US]; 822 Dover Road, Wynnewood, PA 19096 (US). **SCOTT, Richard, W.** [US/US]; 170 N. Radnor-Chester Road, Radnor, PA

(81) Designated States (unless otherwise indicated, for every kind of national protection available): AE, AG, AL, AM, AO, AT, AU, AZ, BA, BB, BG, BH, BR, BW, BY, BZ, CA, CH, CL, CN, CO, CR, CU, CZ, DE, DK, DM, DO, DZ, EC, EE, EG, ES, FI, GB, GD, GE, GH, GM, GT, HN, HR, HU, ID, IL, IN, IS, JP, KE, KG, KM, KN, KP, KR, KZ, LA, LC, LK, LR, LS, LT, LU, LY, MA, MD, ME, MG, MK, MN, MW, MX, MY, MZ, NA, NG, NI, NO, NZ, OM, PE, PG, PH, PL, PT, RO, RS, RU, SC, SD, SE, SG, SK, SL, SM, ST, SV, SY, TJ, TM, TN, TR, TT, TZ, UA, UG, US, UZ, VC, VN, ZA, ZM, ZW.

(84) Designated States (unless otherwise indicated, for every kind of regional protection available): ARIPO (BW, GH, GM, KE, LS, MW, MZ, NA, SD, SL, SZ, TZ, UG, ZM, ZW), Eurasian (AM, AZ, BY, KG, KZ, MD, RU, TJ,

[Continued on next page]

(54) Title: SYNTHETIC MIMETICS OF HOST DEFENSE AND USES THEREOF




Figure 1A

Figure 1B

(57) Abstract: The present invention provides arylamide compounds and methods of making and using them as antibiotics.

WO 2010/062573 A1

WO 2010/062573 A1



TM), European (AT, BE, BG, CH, CY, CZ, DE, DK, EE,
ES, FI, FR, GB, GR, HR, HU, IE, IS, IT, LT, LU, LV,
MC, MK, MT, NL, NO, PL, PT, RO, SE, SI, SK, SM,
TR), OAPI (BF, BJ, CF, CG, CI, CM, GA, GN, GQ, GW,
ML, MR, NE, SN, TD, TG).

Published:

— *with international search report (Art. 21(3))*

SYNTHETIC MIMETICS OF HOST DEFENSE AND USES THEREOF

Field Of The Invention

The present invention is directed, in part, to arylamide compounds and to methods of
5 making and using the same.

Background Of The Invention


Antimicrobial peptides (AMPs) represent a first line of defense against microbes for
many species. AMPs are typically small (12-80 amino acids) cationic amphiphiles. There are two
10 types of AMPs comprising ribosomally and nonribosomally synthesized peptides. Over 700
AMPs have been identified and are generally α -helical (magainin and cecropin) or disulfide-rich
 β -sheets (bactenecin and defensin). Although the peptides are composed of many different
sequences, their physiochemical properties are remarkably similar. They adopt an amphiphilic
architecture with positively charged groups segregated to one side of the secondary structure and
15 hydrophobic groups on the opposite surface. In mammals, the peptides are produced and secreted
in skin, mucosal surfaces and neutrophils, and act locally in response to infection. It is the overall
physiochemical properties that are largely responsible for biological activity of these peptides.

Some antimicrobial activities of host defense proteins have been linked to direct
cytotoxic actions and modulation of the innate immune system. Their direct antimicrobial
20 activities are proposed to involve both membrane and non-membrane effects. Antimicrobial
peptides have remained an effective weapon against bacterial infection over evolutionary time
indicating that their mechanism of action thwarts bacterial responses which lead to resistance
against toxic substances. This premise is supported by direct experimental data showing that no
appreciable resistance to the action of the antimicrobial peptides occurs after multiple serial
25 passages of bacteria in the presence of sub-lethal concentrations of the peptides.

There is a dire need for development of new antimicrobial agents that attack new targets
to evade resistance issues that limit the usefulness of many antibiotics. Furthermore, these new
agents should exert their antimicrobial activity via mechanisms that bacteria do not effectively
resist. A series of non-peptidic analogues have been developed that have many advantages over
30 peptides because of their small size, which increases stability and enhances tissue distribution,
and ability to fine-tune their physical properties for optimization of potency and safety. A series
of arylamide compounds that mimic structural properties of the antimicrobial peptides were
found to have potent antibacterial activities and wide selectivity ratios versus mammalian cells.

Summary Of The Invention

The present invention provides compounds of Formula I



I

5 wherein: each A is, independently, -C=O, -C=S, or -CH₂; each D is, independently, O or S; each R¹ is, independently, hydrogen, C₁₋₃alkyl, C₁₋₃alkoxy, halo, or haloC₁₋₃alkyl; each R² is, independently, hydrogen, C₁₋₃alkyl, C₁₋₃alkoxy, halo, or haloC₁₋₃alkyl; each R³ is, independently, hydrogen, C₁₋₄alkyl, C₁₋₄alkoxy, halo, or haloC₁₋₄alkyl; and each R⁴ is, independently, hydrogen, C₁₋₃alkyl, C₁₋₃alkoxy, halo, or haloC₁₋₃alkyl; or a pharmaceutically acceptable salt thereof.

10 In some embodiments, each A is -C=O.

In some embodiments, each D is O.

In some embodiments, each R¹ is, independently, hydrogen, methyl, ethyl, methoxy, ethoxy, halo, or haloC₁₋₃alkyl. In some embodiments, each R¹ is, independently, hydrogen, methyl, methoxy, halo, or haloC₁₋₃alkyl. In some embodiments, each R¹ is, independently, 15 hydrogen, methyl, or methoxy. In some embodiments, each R¹ is hydrogen.

In some embodiments, each R² is, independently, hydrogen, methyl, ethyl, methoxy, ethoxy, halo, or haloC₁₋₃alkyl. In some embodiments, each R² is, independently, hydrogen, methyl, methoxy, or halo. In some embodiments, each R² is hydrogen.

In some embodiments, each R³ is, independently, hydrogen, methyl, ethyl, methoxy, 20 ethoxy, halo, or haloC₁₋₃alkyl. In some embodiments, each R³ is, independently, methyl, methoxy, halo, or haloC₁₋₃alkyl. In some embodiments, each R³ is, independently, halo or haloC₁₋₃alkyl. In some embodiments, each R³ is, independently, haloC₁₋₃alkyl. In some embodiments, each R³ is trifluoromethyl.

In some embodiments, each R⁴ is, independently, hydrogen, methyl, ethyl, methoxy, 25 ethoxy, or haloC₁₋₃alkyl. In some embodiments, each R⁴ is, independently, hydrogen, methyl, methoxy, halo, or haloC₁₋₃alkyl. In some embodiments, each R⁴ is, independently, hydrogen, methyl, methoxy, or halo. In some embodiments, each R⁴ is hydrogen.

In some embodiments, each A is, independently, -C=O, -C=S, or CH₂; each D is, independently, O or S; each R¹ is, independently, hydrogen, methyl, ethyl, methoxy, ethoxy, 30 halo, halomethyl, or haloethyl; each R² is, independently, hydrogen, methyl, methoxy, halo, or

halomethyl; each R³ is, independently, C₁₋₃alkyl, C₁₋₃alkoxy, halo, or haloalkyl; and each R⁴ is, independently, hydrogen, methyl, ethyl, methoxy, ethoxy, halo, halomethyl, or haloethyl.

In some embodiments, each A is, independently, -C=O or -C=S; each D is, independently, O or S; each R¹ is, independently, hydrogen, methyl, methoxy, halo, or halomethyl; each R² is, independently, hydrogen, halo, or halomethyl; each R³ is, independently, methyl, ethyl, methoxy, ethoxy, halo, halomethyl, or haloethyl; and each R⁴ is, independently, hydrogen, methyl, ethyl, methoxy, ethoxy, halo, halomethyl, or haloethyl.


In some embodiments, each A is -C=O; each D is O; each R¹ is, independently, hydrogen, halo, or halomethyl; each R² is, independently, hydrogen or halo; each R³ is, independently, methyl, methoxy, halo, or halomethyl; and each R⁴ is, independently, hydrogen, methyl, methoxy, halo, or halomethyl.

In some embodiments, each A is -C=O; each D is O; each R¹ is, independently, hydrogen or halo; each R² is, independently, hydrogen or halo; each R³ is, independently, methyl, halo, or halomethyl; and each R⁴ is, independently, hydrogen, methyl, halo, or halomethyl.

In some embodiments, each A is -C=O; each D is O; each R¹ is, independently, hydrogen or halo; each R² is, independently, hydrogen or halo; each R³ is, independently, halo or halomethyl; and each R⁴ is, independently, hydrogen or halo.

In some embodiments, each A is -C=O; each D is O; each R¹ is, independently, hydrogen or halo; each R² is, independently, hydrogen or halo; each R³ is, independently, methyl, halo, or halomethyl; and each R⁴ is, independently, hydrogen, methyl, halo, or halomethyl.

In some embodiments, the compound is



25

Compound A


or a pharmaceutically acceptable salt thereof.

The present invention also provides pharmaceutical compositions comprising one or more of the compounds described above or salt of any of the compounds described above and a pharmaceutically acceptable carrier.

The present invention also provides formulations comprising one or more of the compounds described above, wherein the formulation comprises saline, water, a cyclodextrin solution, or a buffered solution of pH 3 to 9. In some embodiments, the formulation is an oral non-absorbed formulation. In some embodiments, the formulation comprises an excipient chosen 5 from purified water, propylene glycol, polyethyleneglycol 400 (PEG 400), glycerin, DMA, ethanol, benzyl alcohol, citric acid/sodium citrate (pH3), citric acid/sodium citrate (pH5), tris(hydroxymethyl)amino methane HCl (pH7.0), 0.9% saline, and 1.2% saline, or any combination thereof. In some embodiments, the formulation comprises an excipient chosen from propylene glycol, purified water, and glycerin. In some embodiments, the formulation comprises 10 an excipient chosen from 20% w/v propylene glycol in saline, 30% w/v propylene glycol in saline, 40% w/v propylene glycol in saline, 50% w/v propylene glycol in saline, 15% w/v propylene glycol in purified water, 30% w/v propylene glycol in purified water, 50% w/v propylene glycol in purified water, 30% w/v propylene glycol and 5 w/v ethanol in purified water, 15% w/v glycerin in purified water, 30% w/v glycerin in purified water, 50% w/v glycerin 15 in purified water, 20% w/v Kleptose in purified water, 40% w/v Kleptose in purified water, and 25% w/v Captisol in purified water.


The present invention also provides methods of preparing Compound A comprising:

a) reacting (R)-(-)-N-Boc-3-pyrrolidinol with a strong base to form a mixture; further reacting the mixture with 2-chloro-5-(trifluoromethyl)-1,3-dinitrobenzene to form a compound 20 having Formula II




II;

b) reacting the compound of Formula II with an alcohol and a transition metal catalyst in the presence of hydrogen to form a compound of Formula III



III;


c) adding the compound of Formula III and pyrimidine-4,6-dicarboxylic acid to a mixture of 2-chloro-4,6-dimethoxy-1,3,5-triazine and N-methylmorpholine to form a compound of Formula IV



5

IV;

d) reacting the compound of Formula IV with N-Boc- guanidine butyric acid to form a compound of Formula V



V; and

10 e) deprotecting the compound of Formula V to produce Compound A. In some embodiments, in a) the strong base is NaH; and in b) the transition metal catalyst is Pd/C and the alcohol is ethanol.

The present invention also provides alternate methods of preparing Compound A comprising:

15 a) deprotonating (R)-3-Hydroxypyrrolidine-1-carboxylic acid *tert*-butyl ester, and reacting the resultant compound with 2-chloro-1,3-dinitro-5-trifluoromethylbenzene to form (R)-3-(2,6-dinitro-4-trifluoromethylphenoxy)pyrrolidine-1-carboxylic acid *tert*-butyl ester;

b) reducing (R)-3-(2,6-dinitro-4-trifluoromethylphenoxy)pyrrolidine-1-carboxylic acid *tert*-butyl ester in the presence of an alcohol, a transition metal catalyst, and hydrogen to form

20 (R)-3-(2,6-diamino-4-trifluoromethylphenoxy)-pyrrolidine-1-carboxylic acid *tert*-butyl ester;

c) coupling (R)-3-(2,6-diamino-4-trifluoromethylphenoxy)-pyrrolidine-1-carboxylic acid *tert*-butyl ester with pyrimidine-4,6-dicarboxylic acid in the presence of 1-[(3-(dimethylamino)-propyl)]-3-ethylcarbodiimide hydrochloride to form pyrimidine-4,6-dicarboxylic acid bis-[3-amino-2-((R)-1-(*tert*-butoxycarbonyl)pyrrolidin-3-yloxy)-5-

25 trifluoromethyl-phenyl]amide};

d) reacting pyrimidine-4,6-dicarboxylic acid bis-[3-amino-2-((R)-1-(*tert*-butoxycarbonyl)pyrrolidin-3-yloxy)-5-trifluoromethyl-phenyl]amide} with ({{[*tert*-

butoxycarbonyl)amino][(tert-butoxycarbonyl)imino]methyl}amino)pentanoic acid in the presence of phosphorous oxychloride to form pyrimidine-4,6-dicarboxylic acid bis- {[3-(5-({[(tert-butoxycarbonyl)amino][(tert-butoxycarbonyl)imino]methyl}amino)-pentanoylamino)-2-((R)-1-(tert-butoxycarbonyl)-pyrrolidin-3-yloxy)-5-trifluoromethyl-phenyl]-amide};

5 e) deprotecting pyrimidine-4,6-dicarboxylic acid bis- {[3-(5-({[(tert- butoxycarbonyl)amino][(tert-butoxycarbonyl)imino]methyl}amino)-pentanoylamino)-2-((R)-1- (tert-butoxycarbonyl)-pyrrolidin-3-yloxy)-5-trifluoromethyl-phenyl]-amide} to form crude pyrimidine-4,6-dicarboxylic acid bis- {[3-(5-guanidino-pentanoylamino)-2-((R)-pyrrolidin-3- yloxy)-5-trifluoromethyl-phenyl]-amide}tetrahydrochloride; and

10 f) purifying crude pyrimidine-4,6-dicarboxylic acid bis- {[3-(5-guanidino- pentanoylamino)-2-((R)-pyrrolidin-3-yloxy)-5-trifluoromethyl-phenyl]- amide}tetrahydrochloride by, for example, reverse-phase chromatography.

The present invention also provides second alternate methods of preparing Compound A comprising:

15 a) deprotonating (R)-3-Hydroxypyrrolidine-1-carboxylic acid *tert*-butyl ester and further reacting the resultant compound with 2-chloro-1,3-dinitro-5-trifluoromethylbenzene to form (R)-3-(2,6-dinitro-4-trifluoromethylphenoxy)pyrrolidine-1-carboxylic acid *tert*-butyl ester;

20 b) reducing (R)-3-(2,6-dinitro-4-trifluoromethylphenoxy)pyrrolidine-1-carboxylic acid *tert*-butyl ester in the presence of an alcohol, a transition metal catalyst, and hydrogen, to form (R)-3-(2,6-diamino-4-trifluoromethylphenoxy)-pyrrolidine-1-carboxylic acid *tert*-butyl ester;

25 c) coupling (R)-3-(2,6-diamino-4-trifluoromethylphenoxy)-pyrrolidine-1-carboxylic acid *tert*-butyl ester with pyrimidine-4,6-dicarboxylic acid in the presence of 1-[(3- (dimethylamino)-propyl)-3-ethylcarbodiimide hydrochloride to form pyrimidine-4,6- dicarboxylic acid bis- {[3-amino-2-((R)-1-(tert-butoxycarbonyl)pyrrolidin-3-yloxy)-5- trifluoromethyl-phenyl]amide};

30 d) reacting pyrimidine-4,6-dicarboxylic acid bis- {[3-amino-2-((R)-1-(tert- butoxycarbonyl)pyrrolidin-3-yloxy)-5-trifluoromethyl-phenyl]amide} with N-Cbz acid in the presence of thionyl chloride;


35 e) reducing the resultant compound of d) in the presence of an alcohol, a transition metal catalyst, and hydrogen;

40 f) reacting the resultant compound of e) with di-Boc pyrazole; and

45 g) deprotecting the resultant compound of f) to produce Compound A.

The present invention also provides methods of preparing a pharmaceutically acceptable salt of Compound A comprising:


a) reacting (R)-(-)-N-Boc-3-pyrrolidinol with a strong base to form a mixture; further reacting the mixture with 2-chloro-5-(trifluoromethyl)-1,3-dinitrobenzene to form a compound having Formula II



5

II;


b) reacting the compound of Formula II with an alcohol and a transition metal catalyst in the presence of hydrogen to form a compound of Formula III



III;

10


c1) adding the compound of Formula III and pyrimidine-4,6-dicarboxylic acid to a mixture of 2-chloro-4,6-dimethoxy-1,3,5-triazine and N-methylmorpholine to form a compound of Formula IV



IV; or

15

c2) adding the compound of Formula III and pyrimidine-4,6-dicarboxylic acid to a mixture of 1-ethyl-3-[3-(dimethylamino)propyl]-carbodiimide hydrochloride (EDCl) and anhydrous pyridine to form a compound of Formula IV




IV;

20


d) adding the compound of Formula IV with an N-Cbz acid to a solution comprising anhydrous pyridine, dimethylaminopropylamine, and any one of thionyl chloride, POCl_3 , $(\text{EtO})_2\text{POCl}$, or oxalyl chloride to form a compound of Formula Va

- 8 -



Va;


e) hydrogenolysis of the Cbz group of the compound of Formula Va to produce the compound of formula VI



5

VI;

f) protecting the compound of Formula VI to produce the compound of formula VII



VII; and

10 g) deprotecting the compound of Formula VII to produce a pharmaceutically acceptable salt of Compound A.

The present invention also provides methods of inhibiting the growth of a microbe comprising contacting the microbe with any of the compounds described above, or pharmaceutically acceptable salts thereof.

15 The present invention also provides methods of treating a mammal having a microbial infection comprising administering to the mammal in need thereof an anti-microbial effective amount of any of the compounds described above, or pharmaceutically acceptable salts thereof.

In some embodiments, the microbe or microbial infection is a gram-negative aerobe, a gram-positive aerobe, a gram-negative anaerobe, a gram-positive anaerobe, a mycobacterium or 20 a yeast. In some embodiments, the gram-negative aerobe is *Escherichia coli*, *Citrobacter freundii*, *Citrobacter diverus*, *Citrobacter koseri*, *Enterobacter cloacae*, *Enterobacter faecalis*, *Klebsiella pneumonia*, *Klebsiella oxytoca*, *Morganella morganii*, *Providencia stuartii*, *Proteus vulgaris*, *Proteus mirabilis*, *Serratia marcescens*, *Acinetobacter haemolyticus*, *Acinetobacter junii*, *Acinetobacter lwoffii*, *Haemophilus influenzae*, *Stenotrophomonas maltophilia*, or 25 *Pseudomonas aeruginosa*. In some embodiments, the gram-positive aerobe is *Enterococcus*

faecalis, *Enterococcus faecium*, *Mycobacterium tuberculosis*, *Staphylococcus aureus*, *Staphylococcus pneumoniae*, *Staphylococcus epidermidis*, *Staphylococcus saprophyticus*, *Staphylococcus colmii*, *Staphylococcus sciuri*, *Staphylococcus warneri*, *Streptococcus agalactiae*, *Streptococcus pyogenes*, *Streptococcus anginosus*, *Streptococcus mitis*, or

5 *Streptococcus oralis*. In some embodiments, the gram-negative anaerobe is *Bacteroides fragilis*. In some embodiments, the gram-positive anaerobe is *Clostridium difficile* or *Clostridium perfringens*. In some embodiments, the mycobacterium is *Mycobacterium tuberculosis*, *Mycobacterium bovis*, *Mycobacterium africanum*, *Mycobacterium canetti*, or *Mycobacterium microti*. In some embodiments, the yeast is *Candida albicans* or *Candida krusei*.

10 The present invention also provides any of the compounds described above for treating a microbial infection.

The present invention also provides any of the compounds described above, or pharmaceutically acceptable salts thereof, for use in the manufacture of a medicament for the treatment of a microbial infection.

15 The present invention also provides use of any of the compounds described above, or pharmaceutically acceptable salts thereof, for inhibiting growth of a microbe.

The present invention also provides use of any of the compounds described above, or pharmaceutically acceptable salts thereof, for treatment of a microbial infection in a mammal.

20 Brief Description Of The Drawings

Figure 1A and Figure 1B show time-kill studies of Compound A versus *S. aureus* ATCC27660 (Figure 1B is expanded view of Figure 1A).

Figure 2 shows association of passage of *S. aureus* with norfloxacin with a significant rise in MIC values by passage 3 (4 doubling dilutions) for both MSSA and MRSA.

25 Figure 3 shows efficacy of Compound A against *S. aureus* in the Mouse Thigh Burden Model.

Figure 4 shows efficacy of Compound A versus vancomycin against *S. aureus* in the Rat Thigh Burden Model.

Figure 5 shows efficacy of Compound A against *S. aureus* in the Mouse Sepsis Model.

30

Description Of Embodiments

As used herein, the term “about” means $\pm 5\%$ of the value it describes. For example, about 100 means from 95 to 105.

As used herein, the terms “C₁₋₃alkyl”, “C₁₋₄alkyl”, and “(CH₂)₁₋₇” mean saturated, monovalent unbranched or branched hydrocarbon chains having from 1 to 3 carbons, from 1 to 4 carbons, and from 1 to 7 carbons, respectively. Examples of alkyl groups include, but are not limited to, (C_{1-C₇})alkyl groups, such as methyl, ethyl, propyl, isopropyl, 2-methyl-1-propyl, 5 2-methyl-2-propyl, 2-methyl-1-butyl, 3-methyl-1-butyl, 2-methyl-3-butyl, 2-methyl-1-pentyl, 2,2-dimethyl-1-propyl, 3-methyl-1-pentyl, 4-methyl-1-pentyl, 2-methyl-2-pentyl, 3-methyl-2-pentyl, 4-methyl-2-pentyl, 2,2-dimethyl-1-butyl, 3,3-dimethyl-1-butyl, 2-ethyl-1-butyl, butyl, isobutyl, t-butyl, pentyl, isopentyl, neopentyl, hexyl, and heptyl. An alkyl group can be unsubstituted or substituted with one or two suitable substituents.

10 As used herein, the terms “C₁₋₃alkoxy” and “C₁₋₄alkoxy” means -O-alkyl, with alkyl defined as above. An alkoxy group can be unsubstituted or substituted with one or two suitable substituents. The alkyl chain of an alkoxy group is from 1 to 3 or 1 to 4 carbon atoms in length.

As used herein, the term “halo” means a halogen such as fluorine, chlorine, bromine, or iodine.

15 As used herein, the terms “haloC₁₋₃alkyl” and “haloC₁₋₄alkyl” means alkyl groups as defined above, wherein one or more (i.e., 1, 2, 3, 4, 5, 6, 7, 8, 9, or 10) hydrogens are replaced with a halo, as defined above.

20 As used herein, “isolated” means that the compounds of Formula I are separated from other components of either (a) a natural source, such as a cell, such as a bacterial culture, or (b) a synthetic organic chemical reaction mixture, such as by conventional techniques, the compounds of Formula I are purified.

As used herein, the term “mammal” means a rodent (i.e., a mouse, a rat, or a guinea pig), a monkey, a cat, a dog, a cow, a horse, a pig, or a human. In some embodiments, the mammal is a human.

25 As used herein, the term “microbe” means a bacteria, fungi, protozoa, or virus.

As used herein, the phrase “pharmaceutically acceptable salt(s)” includes, but is not limited to, salts of acidic or basic groups.

30 As used herein, the term “purified” means that, when isolated, the isolate contains at least 90%, at least 95%, at least 98%, or at least 99% of a compound of Formula I by weight of the isolate.

As used herein, the phrase “suitable substituent” means a group that does not nullify the synthetic or pharmaceutical utility of the compounds of Formula I or the intermediates useful for preparing them. Examples of suitable substituents include, but are not limited to: (C_{1-C₄})alkyl, (C_{1-C₄})alkenyl, (C_{1-C₄})alkynyl, (C_{1-C₄})alkoxy, -CN, -OH, oxo, halo, -NO₂, -CO₂H, -NH₂,


-NH((C₁-C₄)alkyl), -N((C₁-C₄)alkyl)₂, -CHO, -CO((C₁-C₄)alkyl), and -CO₂((C₁-C₄)alkyl). One of skill in art can readily choose a suitable substituent based on the stability and pharmacological and synthetic activity of the compound of Formula I.

As used herein, the phrase “anti-microbial effective amount” of a compound comprising

5 Formula I is measured by the anti-microbial effectiveness of the compound. In some embodiments, an anti-microbial effective amount inhibits growth of a particular microbe by at least 10%, by at least 20%, by at least 30%, by at least 40%, by at least 50%, by at least 60%, by at least 70%, by at least 80%, by at least 90%, or by at least 95%. In some embodiments, an “anti-microbial effective amount” is also a “therapeutically effective amount” whereby the

10 compound reduces or eliminates at least one harmful effect of a microbe on a mammal.

The present invention provides compounds of Formula I



wherein:

15 each A is, independently, -C=O, -C=S, or CH₂;
 each D is, independently, O or S;
 each R¹ is, independently, hydrogen, C₁₋₃alkyl, C₁₋₃alkoxy, halo, or haloC₁₋₃alkyl;
 each R² is, independently, hydrogen, C₁₋₃alkyl, C₁₋₃alkoxy, halo, or haloC₁₋₃alkyl;
 each R³ is, independently, hydrogen, C₁₋₄alkyl, C₁₋₄alkoxy, halo, or haloC₁₋₄alkyl; and
 each R⁴ is, independently, hydrogen, C₁₋₃alkyl, C₁₋₃alkoxy, halo, or haloC₁₋₃alkyl;
 or a pharmaceutically acceptable salt thereof.

In some embodiments, at least one A is -C=O. In some embodiments, each A is -C=O.

In some embodiments, at least one D is O. In some embodiments, each D is O.

25 In some embodiments, each R¹ is, independently, hydrogen, methyl, ethyl, methoxy, ethoxy, halo, or haloC₁₋₃alkyl. In some embodiments, each R¹ is, independently, hydrogen, methyl, methoxy, halo, or haloC₁₋₃alkyl. In some embodiments, each R¹ is, independently, hydrogen, methyl, or methoxy. In some embodiments, at least one R¹ is hydrogen. In some embodiments, each R¹ is hydrogen.

30 In some embodiments, each R² is, independently, hydrogen, methyl, ethyl, methoxy, ethoxy, halo, or haloC₁₋₃alkyl. In some embodiments, each R² is, independently, hydrogen,

methyl, methoxy, or halo. In some embodiments, at least one R² is hydrogen. In some embodiments, each R² is hydrogen.

In some embodiments, each R³ is, independently, hydrogen, methyl, ethyl, methoxy, ethoxy, halo, or haloC₁₋₃alkyl. In some embodiments, each R³ is, independently, methyl, 5 methoxy, halo, or haloC₁₋₃alkyl. In some embodiments, each R³ is, independently, halo or haloC₁₋₃alkyl. In some embodiments, each R³ is, independently, haloC₁₋₃alkyl. In some embodiments, at least one R³ is trifluoromethyl. In some embodiments, each R³ is trifluoromethyl.

In some embodiments, each R⁴ is, independently, hydrogen, methyl, ethyl, methoxy, 10 ethoxy, or haloC₁₋₃alkyl. In some embodiments, each R⁴ is, independently, hydrogen, methyl, methoxy, halo, or haloC₁₋₃alkyl. In some embodiments, each R⁴ is, independently, hydrogen, methyl, methoxy, or halo. In some embodiments, at least one R⁴ is hydrogen. In some embodiments, each R⁴ is hydrogen.

In some embodiments, each A is, independently, -C=O or -C=S; each D is, 15 independently, O or S; each R¹ is, independently, hydrogen, methyl, ethyl, methoxy, ethoxy, halo, halomethyl, or haloethyl; each R² is, independently, hydrogen, methyl, methoxy, halo, or halomethyl; each R³ is, independently, C₁₋₃alkyl, C₁₋₃alkoxy, halo, or haloalkyl; and each R⁴ is, independently, hydrogen, methyl, ethyl, methoxy, ethoxy, halo, halomethyl, or haloethyl.

In some embodiments, each A is, independently, -C=O or -C=S; each D is, 20 independently, O or S; each R¹ is, independently, hydrogen, methyl, methoxy, halo, or halomethyl; each R² is, independently, hydrogen, halo, or halomethyl; each R³ is, independently, methyl, ethyl, methoxy, ethoxy, halo, halomethyl, or haloethyl; and each R⁴ is, independently, hydrogen, methyl, ethyl, methoxy, ethoxy, halo, halomethyl, or haloethyl.

In some embodiments, each A is -C=O; each D is O; each R¹ is, independently, 25 hydrogen, halo, or halomethyl; each R² is, independently, hydrogen or halo; each R³ is, independently, methyl, methoxy, halo, or halomethyl; and each R⁴ is, independently, hydrogen, methyl, methoxy, halo, or halomethyl.


In some embodiments, each A is -C=O; each D is O; each R¹ is, independently, 30 hydrogen or halo; each R² is, independently, hydrogen or halo; each R³ is, independently, methyl, halo, or halomethyl; and each R⁴ is, independently, hydrogen, methyl, halo, or halomethyl.

In some embodiments, each A is -C=O; each D is O; each R¹ is, independently, hydrogen or halo; each R² is, independently, hydrogen or halo; each R³ is, independently, halo or halomethyl; and each R⁴ is, independently, hydrogen or halo.

In some embodiments, each A is -C=O; each D is O; each R¹ is, independently, hydrogen or halo; each R² is, independently, hydrogen or halo; each R³ is, independently, methyl, halo, or halomethyl; and each R⁴ is, independently, hydrogen, methyl, halo, or halomethyl.

5 In some embodiments, each A is -C=O; each D is O; each R¹ is, independently, hydrogen or halo; each R² is, independently, hydrogen or halo; each R³ is, independently, halo or halomethyl; and each R⁴ is, independently, hydrogen, halo, or halomethyl.

In some embodiments, the compound is Compound A



10 or a pharmaceutically acceptable salt thereof.

Suitable examples of salts include, for example, hydrochloric acid and trifluoroacetic acid.

The compounds of Formula I can contain one or more chiral centers and/or double bonds and, therefore, exist as stereoisomers, such as double-bond isomers (i.e., geometric isomers), enantiomers, or diastereomers. According to the invention, the chemical structures depicted herein, and therefore the compounds of Formula I, encompass all of the corresponding compound's enantiomers and stereoisomers, that is, both the stereomerically pure form (e.g., geometrically pure, enantiomerically pure, or diastereomerically pure) and enantiomeric and stereoisomeric mixtures. Enantiomeric and stereoisomeric mixtures can be resolved into their component enantiomers or stereoisomers by well known methods, such as chiral-phase gas chromatography, chiral-phase high performance liquid chromatography, crystallizing the compound as a chiral salt complex, or crystallizing the compound in a chiral solvent. Enantiomers and stereoisomers can also be obtained from stereomerically- or enantiomerically-pure intermediates, reagents, and catalysts by well known asymmetric synthetic methods.

25 Compounds of Formula I further include hydrates and solvates.

Compounds containing an amine function can also form N-oxides. A reference herein to a compound that contains an amine function also includes the N-oxide. Where a compound contains several amine functions, one or more than one nitrogen atom can be oxidized to form an N-oxide. Examples of N-oxides include N-oxides of a tertiary amine or a nitrogen atom of a 30 nitrogen-containing heterocycle. N-Oxides can be formed by treatment of the corresponding

amine with an oxidizing agent such as hydrogen peroxide or a per-acid (e.g., a peroxy carboxylic acid) (see, Advanced Organic Chemistry, by Jerry March, 4th Edition, Wiley Interscience).

In some embodiments, the compounds of Formula I are isolated and/or purified.

The present invention also provides pharmaceutical compositions comprising one or 5 more of the compounds described above, or one or more salts thereof, and a pharmaceutically acceptable carrier.

Suitable compositions include, but are not limited to, oral non-absorbed compositions. Suitable compositions also include, but are not limited to saline, water, cyclodextrin solutions, and buffered solutions of pH 3-9.

10 The compounds described herein, including Compound A, or pharmaceutically acceptable salts thereof, can be formulated with numerous excipients including, but not limited to, purified water, propylene glycol, PEG 400, glycerin, DMA, ethanol, benzyl alcohol, citric acid/sodium citrate (pH3), citric acid/sodium citrate (pH5), tris(hydroxymethyl)amino methane HCl (pH7.0), 0.9% saline, and 1.2% saline, and any combination thereof. In some embodiments, 15 excipient is chosen from propylene glycol, purified water, and glycerin.

In some embodiments, the excipient is a multi-component system chosen from 20% w/v propylene glycol in saline, 30% w/v propylene glycol in saline, 40% w/v propylene glycol in saline, 50% w/v propylene glycol in saline, 15% w/v propylene glycol in purified water, 30% w/v propylene glycol in purified water, 50% w/v propylene glycol in purified water, 30% w/v 20 propylene glycol and 5 w/v ethanol in purified water, 15% w/v glycerin in purified water, 30% w/v glycerin in purified water, 50% w/v glycerin in purified water, 20% w/v Kleptose in purified water, 40% w/v Kleptose in purified water, and 25% w/v Captisol in purified water. In some embodiments, the excipient is chosen from 50% w/v propylene glycol in purified water, 15% w/v glycerin in purified water, 20% w/v Kleptose in purified water, 40% w/v Kleptose in 25 purified water, and 25% w/v Captisol in purified water. In some embodiments, the excipient is chosen from 20% w/v Kleptose in purified water, 20% w/v propylene glycol in purified water, and 15% w/v glycerin in purified water.

In some embodiments, the formulation comprises 50 mg/mL Compound A in 20% w/v Kleptose in purified water.

30 In some embodiments, the formulation can be lyophilized to a solid and reconstituted with, for example, water prior to use.

When administered to a mammal (e.g., to an animal for veterinary use or to a human for clinical use) the compounds of Formula I can be administered in isolated form. Alternately, the compounds of Formula I can be administered along with (i.e., as a combined formulation or as

separate formulations) with other antibiotics, such as, for example: 1) protein synthesis inhibitors including, but not limited to, amikacin, anisomycin, apramycin, azithromycin, blasticidin S, brefeldin A, butirosin, chloramphenicol, chlortetracycline, clindamycin, clotrimazole, cycloheximide, demeclocycline, dibekacin, dihydrostreptomycin, doxycycline, duramycin, 5 emetine, erythromycin, fusidic acid, G 418, gentamicin, helvolic acid, hygromycin B, josamycin, kanamycin, kirromycin, lincomycin, mecloxycline, mepartricin, midecamycin, minocycline, neomycin, netilmicin, nitrofurantoin, nourseothricin, oleandomycin, oxytetracycline, paromomycin, puromycin, rapamycin, ribostamycin, rifampicin, rifamycin, rosamicin, sisomicin, spectinomycin, spiramycin, streptomycin, tetracycline, thiamphenicol, thiostrepton, tobramycin, 10 tunicamycin, tylosin, viomycin, and virginiamycin; 2) DNA synthesis interfering agents including, but not limited to, camptothecin, 10-deacetylbaicatin III, azacytidine, 7-aminoactinomycin D, 8-quinolinol, 9-dihydro-13-acetylbaicatin III, aclarubicin, actinomycin D, actinomycin I, actinomycin V, bafilomycin A1, bleomycin, capreomycin, chromomycin, cinoxacin, ciprofloxacin, cis-diammineplatinum(II) dichloride, coumermycin A1, L(+)-lactic 15 acid, cytochalasin B, cytochalasin D, dacarbazine, daunorubicin, distamycin A, doxorubicin, echinomycin, enrofloxacin, etoposide, flumequine, formycin, fumagillin, ganciclovir, gliotoxin, lomefloxacin, metronidazole, mithramycin A, mitomycin C, nalidixic acid, netropsin, nitrofurantoin, nogalamycin, nonactin, novobiocin, ofloxacin, oxolinic acid, paclitaxel, phenazine, phleomycin, pipemidic acid, rebeccamycin, sinefungin, streptonigrin, streptozocin, 20 succinylsulfathiazole, sulfadiazine, sulfadimethoxine, sulfaguanidine purum, sulfamethazine, sulfamonomethoxine, sulfanilamide, sulfaquinoxaline, sulfasalazine, sulfathiazole, trimethoprim, tubercidin, 5-azacytidine, cordycepin, and formycin A; 3) cell wall synthesis interfering agents including, but not limited to, (+)-6-aminopenicillanic acid, 7-Aminodesacetoxycephalosporanic acid, amoxicillin, ampicillin, azlocillin, bacitracin, carbenicillin, cefaclor, cefamandole, 25 cefazolin, cefmetazole, cefoperazone, cefotaxime, cefsulodin, ceftriaxone, cephalexin, cephalosporin C, cephalothin, cephadrine, cloxacillin, D-cycloserine, dicloxacillin, D-penicillamine, econazole, ethambutol, lysostaphin, moxalactam, nafcillin, nikkomycin Z, nitrofurantoin, oxacillin, penicillic, penicillin G, phenethicillin, phenoxyethylpenicillanic acid, phosphomycin, pipemidic acid, piperacillin, ristomycin, and vancomycin; 4) cell membrane 30 permeability interfering agents (ionophores) including, but not limited to, 2-mercaptopypyridine, 4-bromocalcimycin A23187, alamethicin, amphotericin B, calcimycin A23187, chlorhexidine, clotrimazole, colistin, econazole, hydrocortisone, filipin, gliotoxin, gramicidin A, gramicidin C, ionomycin, lasalocid A, lonomycin A, monensin, N-(6-aminohexyl)-5-chloro-1-naphthalenesulfonamide, narasin, nigericin, nisin, nonactin, nystatin, phenazine, pimaricin,

polymyxin B, DL-penicillamine, polymyxin B, praziquantel, salinomycin, surfactin, and valinomycin; 5) enzyme inhibitors including, but not limited to, (+)-usnic acid, (±)-miconazole, (S)-(+)-camptothecin, 1-deoxymannojirimycin, 2-heptyl-4-hydroxyquinoline N-oxide, cordycepin, 1,10-phenanthroline, 6-diazo-5-oxo-L-norleucine, 8-quinolinol, antimycin, antipain, 5 ascomycin, azaserine, bafilomycin, cerulenin, chloroquine, cinoxacin, ciprofloxacin, mevastatin, concanamycin A, concanamycin C, coumermycin A1, L(+)-lactic acid, cyclosporin A, econazole, enrofloxacin, etoposide, flumequine, formycin A, furazolidone, fusaric acid, geldanamycin, gliotoxin, gramicidin A, gramicidin C, herbimycin A, indomethacin, irgasan, lomefloxacin, mycophenolic acid, myxothiazol, N-(6-aminoethyl)-5-chloro-1- 10 naphthalenesulfonamide, nalidixic acid, netropsin, niclosamide, nikkomycin, N-methyl-1-deoxynojirimycin, nogalamycin, nonactin, novobiocin, ofloxacin, oleandomycin, oligomycin, oxolinic acid, piericidin A, pipemidic acid, radicicol, rapamycin, rebeccamycin, sinefungin, staurosporine, stigmatellin, succinylsulfathiazole, succinylsulfathiazole, sulfadiazine, sulfadimethoxine, sulfaguanidine, sulfamethazine, sulfamonomethoxine, sulfanilamide, 15 sulfaquinoxaline, sulfasalazine, sulfathiazole, triacsin C, trimethoprim, and vineomycin A1; and 6) membrane modifiers including, but not limited to, paracelsin.

In some embodiments, the term "pharmaceutically acceptable" means approved by a regulatory agency of the Federal or a state government or listed in the U.S. Pharmacopeia or other generally recognized pharmacopeia for use in animals, and more particularly in humans.

20 The term "carrier" refers to a diluent, adjuvant, or excipient with which a compound of Formula I is administered. Such pharmaceutical carriers can be liquids, such as water and oils, including those of petroleum, animal, vegetable or synthetic origin, such as peanut oil, soybean oil, mineral oil, sesame oil and the like. The pharmaceutical carriers can also be saline, gum acacia, gelatin, starch paste, talc, keratin, colloidal silica, urea, and the like. In addition, auxiliary, stabilizing, 25 thickening, lubricating and coloring agents can be used. When administered to a human, the compounds of Formula I and pharmaceutically acceptable carriers can be sterile. Water is a suitable carrier when the compound of Formula I is administered intravenously. Saline solutions and aqueous dextrose and glycerol solutions can also be employed as liquid carriers, particularly for injectable solutions. Suitable pharmaceutical carriers also include excipients such as starch, 30 glucose, lactose, sucrose, gelatin, malt, rice, flour, chalk, silica gel, sodium stearate, glycerol monostearate, talc, sodium chloride, dried skim milk, glycerol, propylene, glycol, water, ethanol and the like. The present compositions, if desired, can also contain minor amounts of wetting or emulsifying agents, or pH buffering agents.

The compositions described herein can take the form of a solution, suspension, emulsion, tablet, pill, pellet, capsule, capsule containing a liquid, powder, sustained-release formulation, suppository, aerosol, spray, or any other form suitable for use. Examples of suitable pharmaceutical carriers are described in Remington's Pharmaceutical Sciences, A.R. Gennaro 5 (Editor) Mack Publishing Co.

In one embodiment, the compounds of Formula I are formulated in accordance with routine procedures as a pharmaceutical composition adapted for administration to humans. Typically, compounds of Formula I are solutions in sterile isotonic aqueous buffer. Where necessary, the compositions can also include a solubilizing agent. Compositions for intravenous 10 administration may optionally include a local anesthetic such as lidocaine to ease pain at the site of the injection. Generally, the ingredients are supplied either separately or mixed together in unit dosage form, for example, as a dry lyophilized powder or water free concentrate in a hermetically sealed container such as an ampoule or sachette indicating the quantity of active agent. Where the compound of the invention is to be administered by infusion, it can be 15 dispensed, for example, with an infusion bottle containing sterile pharmaceutical grade water or saline. Where the compound of Formula I is administered by injection, an ampoule of sterile water for injection or saline can be provided so that the ingredients may be mixed prior to administration.


The compounds of Formula I, and compositions comprising the same, can be 20 administered orally. Compounds and compositions for oral delivery can be in the form of, for example, tablets, lozenges, aqueous or oily suspensions, granules, powders, emulsions, capsules, syrups, or elixirs. Orally administered compositions can contain one or more optional agents, for example, sweetening agents such as fructose, aspartame or saccharin; flavoring agents such as peppermint, oil of wintergreen, or cherry; coloring agents; and preserving agents, to provide a 25 pharmaceutically palatable preparation. Moreover, where in tablet or pill form, the compositions may be coated to delay disintegration and absorption in the gastrointestinal tract thereby providing a sustained action over an extended period of time. Selectively permeable membranes surrounding an osmotically active driving compound are also suitable for orally administered compounds of Formula I. Oral compositions can include standard vehicles such as mannitol, 30 lactose, starch, magnesium stearate, sodium saccharine, cellulose, magnesium carbonate, etc. Such vehicles are suitably of pharmaceutical grade.

The pharmaceutical compositions can be in unit dosage form. In such form, the composition can be divided into unit doses containing appropriate quantities of the active component. The unit dosage form can be a packaged preparation, the package containing discrete

quantities of the preparations, for example, packeted tablets, capsules, and powders in vials or ampules. The unit dosage form can also be a capsule, cachet, or tablet itself, or it can be the appropriate number of any of these packaged forms.


The present invention also provides methods of preparing Compound A comprising:

5 1a) reacting (R)-(-)-N-Boc-3-pyrrolidinol with a strong base to form a mixture; further reacting the mixture with 2-chloro-5-(trifluoromethyl)-1,3-dinitrobenzene to form a compound having Formula II




II;

10 1b) reacting the compound of Formula II with an alcohol and a transition metal catalyst in the presence of hydrogen to form a compound of Formula III




III;

15 1c) adding the compound of Formula III and pyrimidine-4,6-dicarboxylic acid to a mixture of 2-chloro-4,6-dimethoxy-1,3,5-triazine and N-methylmorpholine to form a compound of Formula IV



IV;

20 1d) reacting the compound of Formula IV with N-Boc- guanidine butyric acid to form a compound of Formula V



V; and

1e) deprotecting the compound of Formula V to produce Compound A.

In some embodiments, in a) the strong base is NaH; and in b) the transition metal catalyst is Pd/C and the alcohol is ethanol. In particular, this method is described below in more detail in Example 1.

5 The present invention also provides alternate methods of preparing Compound A comprising:

a) deprotonating (R)-3-Hydroxypyrrolidine-1-carboxylic acid *tert*-butyl ester, and reacting the resultant compound with 2-chloro-1,3-dinitro-5-trifluoromethylbenzene to form (R)-3-(2,6-dinitro-4-trifluoromethylphenoxy)pyrrolidine-1-carboxylic acid *tert*-butyl ester;

10 b) reducing (R)-3-(2,6-dinitro-4-trifluoromethylphenoxy)pyrrolidine-1-carboxylic acid *tert*-butyl ester in the presence of an alcohol, a transition metal catalyst, and hydrogen to form (R)-3-(2,6-diamino-4-trifluoromethylphenoxy)-pyrrolidine-1-carboxylic acid *tert*-butyl ester;

15 c) coupling (R)-3-(2,6-diamino-4-trifluoromethylphenoxy)-pyrrolidine-1-carboxylic acid *tert*-butyl ester with pyrimidine-4,6-dicarboxylic acid in the presence of 1-[(3-(dimethylamino)-propyl)-3-ethylcarbodiimide hydrochloride to form pyrimidine-4,6-dicarboxylic acid bis-[3-amino-2-((R)-1-(*tert*-butoxycarbonyl)pyrrolidin-3-yloxy)-5-trifluoromethyl-phenyl]amide];

20 d) reacting pyrimidine-4,6-dicarboxylic acid bis-[3-amino-2-((R)-1-(*tert*-butoxycarbonyl)pyrrolidin-3-yloxy)-5-trifluoromethyl-phenyl]amide with ({{(*tert*-butoxycarbonyl)amino}[(*tert*-butoxycarbonyl)imino]methyl}amino)pentanoic acid in the presence of phosphorous oxychloride to form pyrimidine-4,6-dicarboxylic acid bis-[3-(5-({{(*tert*-butoxycarbonyl)amino}[(*tert*-butoxycarbonyl)imino]methyl}amino)-pentanoylamino)-2-((R)-1-(*tert*-butoxycarbonyl)-pyrrolidin-3-yloxy)-5-trifluoromethyl-phenyl]-amide;

25 e) deprotecting pyrimidine-4,6-dicarboxylic acid bis-[3-(5-({{(*tert*-butoxycarbonyl)amino}[(*tert*-butoxycarbonyl)imino]methyl}amino)-pentanoylamino)-2-((R)-1-(*tert*-butoxycarbonyl)-pyrrolidin-3-yloxy)-5-trifluoromethyl-phenyl]-amide] to form crude pyrimidine-4,6-dicarboxylic acid bis-[3-(5-guanidino-pantanoylamino)-2-((R)-pyrrolidin-3-yloxy)-5-trifluoromethyl-phenyl]-amide; and

30 f) purifying crude pyrimidine-4,6-dicarboxylic acid bis-[3-(5-guanidino-pantanoylamino)-2-((R)-pyrrolidin-3-yloxy)-5-trifluoromethyl-phenyl]-amide]tetrahydrochloride by reverse-phase chromatography.

In some embodiments, in b) the transition metal catalyst is Pd/C and the alcohol is ethanol. In particular, this method is described below in more detail in Example 2.

The present invention also provides second alternate methods of preparing Compound A comprising:


- a) deprotonating (R)-3-Hydroxypyrrolidine-1-carboxylic acid *tert*-butyl ester and further reacting the resultant compound with 2-chloro-1,3-dinitro-5-trifluoromethylbenzene to 5 form (R)-3-(2,6-dinitro-4-trifluoromethylphenoxy)pyrrolidine-1-carboxylic acid *tert*-butyl ester;
- b) reducing (R)-3-(2,6-dinitro-4-trifluoromethylphenoxy)pyrrolidine-1-carboxylic acid *tert*-butyl ester in the presence of an alcohol, a transition metal catalyst, and hydrogen, to form (R)-3-(2,6-diamino-4-trifluoromethylphenoxy)-pyrrolidine-1-carboxylic acid *tert*-butyl ester;
- c) coupling (R)-3-(2,6-diamino-4-trifluoromethylphenoxy)-pyrrolidine-1-carboxylic 10 acid *tert*-butyl ester with pyrimidine-4,6-dicarboxylic acid in the presence of 1-[(3-(dimethylamino)-propyl]-3-ethylcarbodiimide hydrochloride to form pyrimidine-4,6-dicarboxylic acid bis-[3-amino-2-((R)-1-(*tert*-butoxycarbonyl)pyrrolidin-3-yloxy)-5-trifluoromethyl-phenyl]amide};
- d) reacting pyrimidine-4,6-dicarboxylic acid bis-[3-amino-2-((R)-1-(*tert*-butoxycarbonyl)pyrrolidin-3-yloxy)-5-trifluoromethyl-phenyl]amide} with N-Cbz acid in the 15 presence of thionyl chloride;
- e) reducing the resultant compound of d) in the presence of an alcohol, a transition metal catalyst, and hydrogen;
- f) reacting the resultant compound of e) with di-Boc pyrazole; and
- 20 g) deprotecting the resultant compound of f) to produce Compound A.

In some embodiments, in b) and e) the transition metal catalyst is Pd/C and the alcohol is ethanol. In particular, this method is described below in more detail in Example 3.

One skilled in the art will be able to substitute suitable reagents for the reagents recited in the methods described herein to produce Compound A as well as additional compounds of 25 Formula I.

The present invention also provides methods of preparing a pharmaceutically acceptable salt of Compound A comprising:


- a) reacting (R)-(-)-N-Boc-3-pyrrolidinol with a strong base to form a mixture; further reacting the mixture with 2-chloro-5-(trifluoromethyl)-1,3-dinitrobenzene to form a compound 30 having Formula II



- 21 -

II;


b) reacting the compound of Formula II with an alcohol and a transition metal catalyst in the presence of hydrogen to form a compound of Formula III



5

III;


c1) adding the compound of Formula III and pyrimidine-4,6-dicarboxylic acid to a mixture of 2-chloro-4,6-dimethoxy-1,3,5-triazine and N-methylmorpholine to form a compound of Formula IV



10

IV; or


c2) adding the compound of Formula III and pyrimidine-4,6-dicarboxylic acid to a mixture of 1-ethyl-3-[3-(dimethylamino)propyl]-carbodiimide hydrochloride (EDCI) and anhydrous pyridine to form a compound of Formula IV



15

IV;


d) adding the compound of Formula IV with an N-Cbz acid to a solution comprising anhydrous pyridine, dimethylaminopropylamine, and any one of thionyl chloride, POCl_3 , $(\text{EtO})_2\text{POCl}$, or oxalyl chloride to form a compound of Formula Va



20


Va;

e) hydrogenolysis of the Cbz group of the compound of Formula Va to produce the compound of formula VI



VI;

f) protecting the compound of Formula VI to produce the compound of formula VII



5

VII; and

g) deprotecting the compound of Formula VII to produce a pharmaceutically acceptable salt of Compound A.

Preparation of compounds of Formula I can involve the protection and deprotection of various chemical groups. The need for protection and deprotection, and the selection of 10 appropriate protecting groups, can be readily determined by one skilled in the art. The chemistry of protecting groups can be found, for example, in T. W. Greene and P. G. M. Wuts, *Protective Groups in Organic Synthesis*, 3rd Ed., Wiley & Sons, Inc., New York (1999), which is incorporated herein by reference in its entirety.

The present invention also provides methods of inhibiting the growth of a microbe 15 comprising contacting the microbe with one or more compounds described above, or a pharmaceutically acceptable salt thereof. In some embodiments, the compound of Formula I can act as an antiseptic agent for cleansing surfaces, such as in, for example, kitchens and bathrooms. In these embodiments, the compound of Formula I can be formulated for such uses by procedures well known to the skilled artisan.

20 The present invention also provides methods of treating a mammal having a microbial infection comprising administering to the mammal in need thereof an anti-microbial effective amount of one or more compounds described above, or a pharmaceutically acceptable salt thereof. In some embodiments, the mammal can be pre-diagnosed with a microbial infection prior to treatment. In some embodiments, no formal diagnosis may have been made; in such 25 embodiments, the mammal may be suspected of having a microbial infection for which treatment is recognized as being desirable.

In one embodiment, “treatment” or “treating” refers to an amelioration of a microbial infection, or at least one discernible symptom thereof; or to an amelioration of at least one

measurable physical parameter, not necessarily discernible by the patient; or to inhibiting the progression of a microbial infection; or to delaying the onset of a microbial infection.

In some embodiments, the microbe is, or the microbial infection is due to, a gram-negative aerobe, a gram-positive aerobe, a gram-negative anaerobe, a gram-positive anaerobe, or 5 a yeast. In some embodiments, the gram-negative aerobe is selected from, but not limited to, *Escherichia coli*, *Citrobacter freundii*, *Citrobacter diverus*, *Citrobacter koseri*, *Enterobacter cloacae*, *Enterobacter faecalis*, *Klebsiella pneumonia*, *Klebsiella oxytoca*, *Morganella morganii*, *Providencia stuartii*, *Proteus vulgaris*, *Proteus mirabilis*, *Serratia marcescens*, *Acinetobacter haemolyticus*, *Acinetobacter junii*, *Acinetobacter lwoffii*, *Haemophilus influenzae*, 10 *Stenotrophomonas maltophilia*, and *Pseudomonas aeruginosa*. In some embodiments, the gram-positive aerobe is selected from, but not limited to, *Enterococcus faecalis*, *Enterococcus faecium*, *Mycobacterium tuberculosis*, *Staphylococcus aureus*, *Staphylococcus pneumoniae*, *Staphylococcus epidermidis*, *Staphylococcus saprophyticus*, *Staphylococcus colmii*, *Staphylococcus sciuri*, *Staphylococcus warneri*, *Streptococcus agalactiae*, *Streptococcus 15 pyogenes*, *Streptococcus anginosus*, *Streptococcus mitis*, and *Streptococcus oralis*. In some embodiments, the gram-negative anaerobe is *Bacteroides fragilis*. In some embodiments, the gram-positive anaerobe is *Clostridium difficile* or *Clostridium perfringens*. In some embodiments, the mycobacterium is *Mycobacterium tuberculosis*, *Mycobacterium bovis*, *Mycobacterium africanum*, *Mycobacterium canetti*, or *Mycobacterium microti*. In some 20 embodiments, the yeast is selected from, but not limited to, *Candida albicans* and *Candida krusei*.

In some embodiments, the microbe is an antibiotic-resistant strain of bacteria, such as those recited in the Examples below.

The compounds of Formula I, or a pharmaceutically acceptable salt thereof, and 25 compositions comprising the same, can be administered in a variety of routes, such as, for example, by infusion or bolus injection, and can be administered together with another biologically active agent, such as another antibiotic. Administration can be systemic or local. Various delivery systems are known, e.g., encapsulation in liposomes, microparticles, microcapsules, capsules, etc., and can be used to administer a compound of Formula I. Routes of 30 administration include, but are not limited to, intradermal, intramuscular, intraperitoneal, intravenous, subcutaneous, intranasal, epidural, oral, sublingual, intranasal, intracerebral, intravaginal, transdermal, rectally, pulmonary, by inhalation, or topically, particularly to the ears, nose, eyes, or skin. In some embodiments, suitable routes of administration include intravenous, topical, and subcutaneous. The desired route of administration is left to the discretion of the

practitioner, and will depend, in part, upon the site of the microbial infection and medical condition of the mammal or human being treated. In most instances, administration can result in the release of the compounds of Formula I into the bloodstream.

In some embodiments, it may be desirable to administer one or more compounds of

5 Formula I, or a pharmaceutically acceptable salt thereof, locally to an area in need of treatment. This may be achieved, for example, and not by way of limitation, by local infusion during surgery, topical application, e.g., in conjunction with a wound dressing after surgery, by injection, by means of a catheter, by means of a suppository, or by means of an implant, wherein the implant is of a porous, non-porous, or gelatinous material, including membranes, such as
10 sialastic membranes, or fibers.

The amount of a compound of Formula I, or a pharmaceutically acceptable salt thereof, that will be effective in the treatment of a particular microbial infection will depend on the nature of the disorder or condition, and can be determined by standard clinical techniques. In addition, *in vitro* or *in vivo* assays may optionally be employed to help identify optimal dosage ranges.

15 The precise dose to be employed in the compositions will also depend on the route of administration, and the seriousness of the infection, and should be decided according to the judgment of the practitioner and each patient's circumstances. However, suitable dosage ranges for administration are generally about 0.001 milligrams to about 200 milligrams per kilogram of body weight. In some embodiments, the dose is from about 0.01 milligrams to about 70
20 milligrams per kilogram of body weight, or from about 0.1 milligrams to about 50 milligrams per kilogram of body weight, or from about 0.5 milligrams to about 20 milligrams per kilogram of body weight, or from about 1 milligram to about 10 milligrams per kilogram of body weight. In some embodiments, the dose is about 5 milligrams per kilogram of body weight. The dosage amounts described herein refer to total amounts administered; that is, if more than one compound
25 of Formula I is administered, the dosages correspond to the total amount of the compounds of Formula I administered. Compositions can contain 10% to 95% active ingredient by weight. Effective doses can be extrapolated from dose-response curves derived from *in vitro* or animal model test systems. Such animal models and systems are well known in the art.

The present invention also provides one or more compounds described above, or a

30 pharmaceutically acceptable salt thereof, or a pharmaceutical composition comprising one or more compounds described above, for treating a microbial infection.

The present invention also provides one or more compounds described above, or a pharmaceutically acceptable salt thereof, or a pharmaceutical composition comprising one or

more compounds described above, for use in the manufacture of a medicament for the treatment of a microbial infection.

The present invention also provides the use of one or more compounds described above, or a pharmaceutically acceptable salt thereof, or a pharmaceutical composition comprising one or 5 more compounds described above, in the inhibition of growth of a microbe.

The present invention also provides the use of one or more compounds described above, or a pharmaceutically acceptable salt thereof, or a pharmaceutical composition comprising one or more compounds described above, in the treatment of a microbial infection in a mammal.

In order that the invention disclosed herein may be more efficiently understood, 10 examples are provided below. It should be understood that these examples are for illustrative purposes only and are not to be construed as limiting the invention in any manner. Throughout these examples, molecular cloning reactions, and other standard recombinant DNA techniques, were carried out according to methods described in Maniatis et al., *Molecular Cloning - A Laboratory Manual*, 2nd ed., Cold Spring Harbor Press (1989), using commercially available 15 reagents, except where otherwise noted.

Examples

Briefly, the results generated from the examples below indicate that Compound A is active against *Staphylococci spp.* and other Gram-positive and Gram-negative organisms. For 20 example, susceptibility screens were performed against 150 isolates of *S. aureus* and coagulase-negative *Staphylococci* with defined antibacterial susceptibilities to other antimicrobials. Generally, MIC₉₀ values of 0.5 to 2.0 µg/ml have been obtained in a screen of 150 *Staphylococci* organisms, and was not affected by susceptibility phenotypes to other antibiotics. Serial passage 25 of methicillin-susceptible (MSSA ATCC 29213) and resistant (MRSA ATCC 33591) strains of *S. aureus* at 0.5x MIC concentrations for 17 passages did not result in any change in MIC values. Generally, Compound A was bactericidal with time-kills ranging from 30 minutes to 6 hours.

Compound A was efficacious *in vivo* in a mouse thigh burden model against MSSA 29213 and MRSA 33591 and in a mouse peritonitis/sepsis model against MSSA 27660. In the mouse thigh burden model with MSSA 27660, Compound A achieved reductions 24 hours post-30 infection of up to 4¹⁰ in cfu/thigh relative to untreated, infected control mice at dosages that were well-tolerated in repeat dose toxicity studies. Thus, robust efficacy against MSSA and MRSA was observed in a mouse thigh burden model, and against MSSA in a rat thigh burden model and a mouse peritonitis model. Compound A was stable in the presence of plasma and isolated hepatocytes from multiple species.


Compound A was better tolerated in acute toxicity studies when administered by IV infusion. The MTD (IV bolus) for Compound A in the mouse (30 mg/kg) is significantly higher than the static efficacy dose in the thigh burden model (2-4 mg/kg).

Compound A is currently in Phase 1 human clinical trials for development as an IV pan-

5 Staphylococcal agent.


Example 1: Synthesis of Compound A

Step 1:




10 Sodium hydride (1.12 g, 60% in mineral oil, 28 mmol) was added in portion to anhydrous DMF (24 mL) solution of (R)-(-)-N-Boc-3-pyrrolidinol (5.0 g, 27.6 mmol) at room temperature. The resulting mixture was stirred for an additional 15 minutes. This mixture was then added dropwise to a DMF (20 mL) solution of 2-chloro-5-(trifluoromethyl)-1,3-dinitrobenzene (7.45 g, 27.6 mmol) at 0°C. The deep red solution was stirred at room 15 temperature for 4 hours. The reaction was quenched by ice-water and extracted by ethyl acetate. The organic layer was washed by brine and water, and dried over Na₂SO₄. After removal of the solvent, the residue was purified by flash column (ethyl acetate/hexanes = 1/4, v/v). The yield was 54%.

20 Step 2:



25 (R)-tert-butyl 3-(4-(trifluoromethyl)-2,6-dinitrophenoxy)pyrrolidine-1-carboxylate (4.84 g, 9.8 mmol) and Pd/C (0.78 g, 10% on carbon) and ethanol (140 mL) were placed in a Parr bottle. The mixture was flashed under hydrogen three times and stirred under 40 psi hydrogen at room temperature overnight. The mixture was filtrated through celite. The cake was washed twice with ethanol (2x20 mL). The filtrate was evaporated under vacuum. An off-white solid was obtained and used as such for the subsequent reaction. The yield was 100%.


Step 3:



2-Chloro-4,6-dimethoxy-1,3,5-triazine (5.97 g, 34 mmol) was stirred in anhydrous THF (200 mL). N-Methylmorpholine (7.5 ml, 68 mmol) was added. The resulting mixture was stirred at room temperature for 30 minutes. Then, (R)-tert-butyl 3-(2,6-diamino-4-(trifluoromethyl)phenoxy)pyrrolidine-1-carboxylate (10.84 g, 30 mmol) and pyrimidine-4,6-dicarboxylic acid (2.48 g, 14.8 mmol) were added. The mixture was stirred at room temperature for 24 hours. The solvent was evaporated completely in vacuum. Water (250 mL) was added and the mixture was stirred for 4 hours. After filtration, the yellow cake was washed with water (3x100 mL) and stirred in water (250 mL) for 4 hours. The filtration and washing procedure was repeated twice. The solid was dried in the air and stirred in dichloromethane (20 mL) for 30 minutes, followed by ultrasonic treatment for 1 hour. After filtration, the yellow cake was quickly washed with cold dichloromethane (2x10 mL). The product (10.0 g, yield: 79.1%) was used as such for subsequent reaction.


15

Step 4:



The starting material (6.5 g, 7.6 mmol), N-Boc guanidine butyric acid (10.9 g, 30.4 mmol) were stirred in anhydrous pyridine (40 mL) at 0°C. POCl_3 (2.78 mL, 30.4 mmol) in pyridine (4 mL) was added dropwise. The resulting mixture was stirred at 0°C for 1.5 hours. The reaction mixture was evaporated under vacuum. Water (140 mL) was added to the residue. The mixture was extracted with ethyl acetate (260 mL). The organic layer was washed with brine (100 mL) and dried over Na_2SO_4 . After evaporation, the residue was purified by column (Eluent: ethyl acetate/hexanes/dichloromethane = 1/1/1, v/v/v then 2%~4% methanol in dichloromethane). The yield was 29.1%. The R_f was same as the standard sample which was characterized by NMR.


Step 5:



The starting material (3.4 g, 2.3 mmol) was stirred in 4N HCl in dioxane (34 mL) at

5 room temperature overnight. The solvent was removed under vacuum. The residue was titrated in ether. The solid was filtered and purified by C18 reverse-phase C18 column. A light yellow solid was obtained as product with a purity of 98% (HPLC); LC-MS (M+1): 937. Yield: 51%.

Example 2: Synthesis Of Compound A



Step 1: (R)-3-hydroxypyrrolidine-1-carboxylic acid *tert*-butyl ester is de-protonated with potassium *tert*-butoxide (KOtBu) in tetrahydrofuran (THF). The resulting anion is reacted with 2-chloro-1,3-dinitro-5-trifluoromethylbenzene in *tert*-butyl methyl ether (MTBE)/THF. When the reaction is complete, the reaction mixture is quenched with water and partitioned with 5 more MTBE. The organic layer is washed with brine and water and concentrated on a rotary evaporator. The solid concentrate is re-dissolved in methanol and re-precipitated with water. The resulting precipitate is filtered and dried to afford (R)-3-(2,6-dinitro-4-trifluoromethylphenoxy)pyrrolidine-1-carboxylic acid *tert*-butyl ester which can be used in the next step without further purification.

10 Step 2: The product from Step 1 is dissolved in methanol and hydrogenated at 100-200 psi and 30-50 °C in the presence of 10% Pd/C until the reduction is deemed complete by HPLC. The reaction mixture is filtered through Celite. The filtrate is concentrated and dried to afford (R)-3-(2,6-diamino-4-trifluoromethylphenoxy)-pyrrolidine-1-carboxylic acid *tert*-butyl ester which can be used in the next step without further purification.

15 Step 3: The product from Step 2 is coupled with pyrimidine-4,6-dicarboxylic acid, in the approximate ratio of 2 mol diamine:1 mol diacid, in the presence of 1-[(3-(dimethylamino)-propyl)-3-ethylcarbodiimide hydrochloride (EDCI), in pyridine, under inert atmosphere, at ambient temperature. When the reaction is complete, the reaction mixture is diluted in water. The resulting precipitate is separated and re-dissolved in MTBE. The MTBE solution is washed with 20 water, 0.2 N HCl, and brine, dried over anhydrous sodium sulfate, separated, and diluted in heptane. The resulting precipitate is isolated by filtration and dried to afford pyrimidine-4,6-dicarboxylic acid bis- {[3-amino-2-((R)-1-(*tert*-butoxycarbonyl)pyrrolidin-3-yloxy)-5-trifluoromethyl-phenyl]amide} which can be used in the next step without further purification.


Step 4: The product from Step 3 is reacted with 2.5-3 molar equivalents of {[*(tert*-butoxycarbonyl)amino][(*tert*-butoxycarbonyl)imino]methyl}amino)pentanoic acid in pyridine, in the presence of phosphorous oxychloride, at a temperature around -5 to -10 °C. The reaction is quenched with water at temperature of 15 °C. The supernatant is separated from the amorphous precipitate, which is re-dissolved in MTBE, washed with water and brine, dried over anhydrous sodium sulfate, separated, and diluted in heptane. The resulting precipitate is isolated by 30 filtration and dried to afford pyrimidine-4,6-dicarboxylic acid bis- {[3-(5- {[*(tert*-butoxycarbonyl)amino][(*tert*-butoxycarbonyl)imino]methyl}amino)-pentanoylamino)-2-((R)-1-(*tert*-butoxycarbonyl)-pyrrolidin-3-yloxy)-5-trifluoromethyl-phenyl]-amide} which is used in the next step without further purification.


Step 5: The product from Step 4 is de-protected (removal of six *tert*-butoxycarbonyl groups) with 4M HCl/1,4-dioxane in formic acid at ambient temperature. The reaction mixture is diluted with 1,4-dioxane. The resulting precipitate is filtered, washed with 1,4-dioxane and dried to afford crude pyrimidine-4,6-dicarboxylic acid bis- {[3-(5-guanidino-pentanoylamino)-2-((R)-5-pyrrolidin-3-yl)-5-trifluoromethyl-phenyl]-amide} tetrahydrochloride (crude Compound A). The crude product is further purified by re-precipitation from methanol solution with THF (50 °C to ambient temperature) and/or re-precipitation from water/methanol solution with THF at ambient temperature.

Step 6 (chromatographic purification): The final purification of Compound A is achieved by reverse-phase chromatography (RP-HPLC) using YMC ODS-AQ phase, 50 micron, 120 Angstrom, slurry packed into a ProChrom dynamic axial compression column. The mobile phase is a gradient of solvent B in solvent A, where solvent A is water with 0.05% trifluoroacetic acid (TFA) and solvent B is acetonitrile with 0.05% TFA. Fractions containing purified product are concentrated by rotary evaporation to afford Compound A as the trifluoroacetate salt. The final hydrochloride salt form is re-generated by passing a water/methanol solution of the trifluoroacetate salt through a Dowex 1x2-400 (Cl- form) ion-exchange column, collecting the API-containing eluate, concentrating, and drying.


Compound A bulk drug substance is stored at 2-8 °C, protected from light and air, in amber HDPE containers or in double polyethylene bags in a fiber drum.

Example 3: Synthesis Of Compound A






Step 1: (R)-3-Hydroxypyrrolidine-1-carboxylic acid *tert*-butyl ester (compound 20) is de-protonated with potassium *tert*-butoxide (KOtBu) in tetrahydrofuran (THF). The resulting anion is reacted 2-chloro-1,3-dinitro-5-trifluoromethylbenzene (compound 2) in *tert*-butyl methyl ether (MTBE)/THF. When the reaction is complete, the reaction mixture is quenched with water and partitioned with more MTBE. The organic layer is washed with brine and water and concentrated on a rotary evaporator. The solid concentrate is re-dissolved in methanol and re-precipitated with water. The resulting precipitate is filtered and dried to afford (R)-3-(2,6-dinitro-4-trifluoromethylphenoxy)pyrrolidine-1-carboxylic acid *tert*-butyl ester which can be used in the next step without further purification. This reaction has been carried out at a scale using 4.2 Kg of compound 2.




Step 2: Compound 21 is dissolved in methanol and hydrogenated at 100-200 psi and 30-50 °C in the presence of 10% Pd/C until the reduction is deemed complete by HPLC. The reaction mixture is filtered through Celite. The filtrate is concentrated and dried to afford (R)-3-(2,6-diamino-4-trifluoromethylphenoxy)-pyrrolidine-1-carboxylic acid *tert*-butyl ester (compound 22) with HPLC purity of 92.2%. The reaction is done in four batches with a scale of 1.64 kg of compound 21 for each batch.




Step 3: Compound 22 is coupled with pyrimidine-4,6-dicarboxylic acid (compound 8), in the approximate ratio of 2 mol diamine:1 mol diacid, in the presence of 1-[3-(dimethylamino)-propyl]-3-ethylcarbodiimide hydrochloride (EDCI), in pyridine, under inert atmosphere, at ambient temperature. When the reaction is complete, the reaction mixture is


diluted in water. The resulting precipitate is separated and re-dissolved in MTBE. The MTBE solution is washed with water, 0.2 N HCl, and brine, dried over anhydrous sodium sulfate, separated, and diluted in heptane. The resulting precipitate is isolated by filtration and dried to afford pyrimidine-4,6-dicarboxylic acid bis-{[3-amino-2-((R)-1-(tert-butoxycarbonyl)pyrrolidin-5-3-yloxy)-5-trifluoromethyl-phenyl]amide} (compound 23) which can be used in the next step without further purification. The reaction is carried out at a scale using 3.15 kg of compound 22.




Step 4: The solution of 3.66 g of DMAP in 60 ml anhydrous pyridine was cooled to 0 °C with ice bath. 3.60 g of thionyl chloride was added slowly. The resulting solution was stirred 10 for 10 minutes. The starting material N-Cbz acid (7.53 g, 30 mmol), Cpd 23 (8.54 g, 10 mmol), were added to the solution respectively. The resulting mixture was stirred at RT for 4 hours. Water (500 mL) was added. After the mixture was stirred vigorously at room temperature for 2 hours, the solid was filtered and washed with 250 mL of water. The solid was dissolved in ethyl acetate (300 mL). The organic layer was washed with 10% citric acid solution (100 mL) and 15 brine (100 mL) and dried over Na₂SO₄. After evaporation, the residue was dissolved in 40 mL DCM, then 250 mL hexane was added. The precipitate was collected and dry under vacuum. 13.20 g of product was obtained in 95% purity. Yield: 100%.



Step 5: Compound 26 (13.20 g) was dissolved in MeOH with 2 equiv. of 1 N HCl, and 20 the catalyst Pd/C (10%) 1.0 g was added. The reaction mixture was put on a Parr hydrogenator and shaken for 2 hours under 60 psi of hydrogen. LCMASS showed no progress and another 1.0 g of catalyst was added. The reaction mixture was put on a Parr hydrogenator and shaken for 3 hours under 60 psi of hydrogen. The mixture was filtered through celite to remove the catalyst. The filtrate was concentrated to dryness on a rotovap at 30 °C. 11.50 g of product was obtained 25 in 95% purity. Yield: 100%.




Step 6: Compound 27 (11.50 g, 10 mmol) was dissolved in 60 ml methanol and DCM (1:1). Then, 4.04 g triethylamine (40 mmol) was added. di-Boc pyrazole 9.3 gram (30 mmol) was added and the resulting mixture was stirred at room temperature for 1 hour. After removing 95% of the solvent, 300 mL water was added and the mixture was stirred vigorously for 2 hours.




10 Step 7: Compound 28 (1.5 g) was purified on 80 g silica gel column by using a gradient of 10-88 % EtOAc in DCM. Fractions with purity above 95% were collected, evaporated under vacuum, and dried. Recovery was 50-60%. Compound 28 with 95% purity (0.3 g) was dissolved and stirred in ethyl acetate (3 mL) at room temperature (22 °C) under argon. HCl gas was bubbling into the solution for 20 minutes. The color of the solution was turning deep yellow as 15 the bubbling was ongoing. The solid started crushing out in 15 minutes. The solution was stirred at room temperature for another 1 hour. Additional 4 mL of ethyl acetate was introduced into the reaction mixture because of a loss of ethyl acetate. The mixture was bubbling with HCl gas for 20 minutes. The mixture was stirred for 2.5 hours. One third of the mixture was filtered and washed with ethyl acetate. Two thirds of the mixture was stirred at room temperature overnight. Then, 30 mL of ethyl acetate was added to the mixture. After filtration, the cake was washed with ethyl acetate twice (2x140 mL) and dried. The solid was immersed in ethyl acetate (8 mL) and kept in a freezer. The reaction process was performed in 4 hours. Overnight stirring did not show much change. The purity of the final product was 98% with one major impurity of 1.2%.

Example 4: Synthesis Of Compound A




- 36 -



Step 1: To a nitrogen purged 4-necked 12 L RBF was added 305.32 g of compound 2, 700 mL of MTBE with stirring and the mixture was cooled in an ice/water bath. Compound 20 5 (212.43 g) was dissolved with the potassium tert-butoxide (1.31 L of 1 M solution in THF) providing a slightly turbid mixture. This mixture was added to compound 21 solution in the RBF over 86 minutes with stirring while maintaining <9.0 °C internal temperature. The reaction was removed from the cold bath 30 minutes later and allowed to stir at ambient temperature for 15.5 hours. Upon stirring, several small ice chips were added with a temperature decrease from 21.4 10 °C to 18.4 °C. Then water was added (1.5 L) and MTBE (1.5 L) and the mixture was stirred for 10 minutes. The mixture was phase-split and separated in a 6 L separatory funnel. The aqueous layer was re-extracted with MTBE (500 mL). The organic layers were combined and washed with 2:1 water/saturated brine (3 x 900 mL), and concentrated to a reddish/rust colored solid under reduced pressure. This solid was dissolved in 2.45 L of MeOH and the solution was 15 transferred to a 4 L Erlenmeyer flask. Then water (1L) was added with stirring, in portions, resulting in thick slurry. The mixture was covered and placed in a refrigerator (1-5 °C) for 16 hours. The solid was collected by filtration and dried under vacuum. The dried product was a bright yellow powder. Yield: 395.3 g, HPLC purity 94.0%.

The potassium tert-butoxide can be replaced with, for example, any alkoxide, sodium 20 hydride, potassium hydride, or any base that can deprotonate the hydroxyl of compound 20. Compound 2 can be substituted at the 2 position by any halide.




25 Step 2: To a stainless steel 2 gal Parr stirrer unit was added the catalyst Pd/C (10 wt%, 20 g), compound 21 from Step 1 (394.37 g) and then 2 L of MeOH carefully with swirling. The vessel was charged with hydrogen and vented twice. The mixture was then stirred starting at 82

psi hydrogen; the pressure dropped to 0 psi. The vessel was repeatedly filled to 62 psi, 28 psi and 36 psi, respectively, each time allowing the pressure to go back to 0 psi (total uptake of 208 psi in 51 minutes). The internal temperature started at 16 °C and the mixture showed a gradual but rapid exotherm to maximum of 38 °C. The internal temperature was maintained at 33-38 °C.

5 The vessel was pressurized to 49 psi with uptake of 23 psi. The vessel was pressurized to 90 psi with uptake of 12 psi over 1 hour. The vessel was pressurized to 120 psi with uptake of 82 psi over 6 hours. The vessel was then re-pressurized to 51 psi with uptake of 37 psi over 14.33 hours (the total uptake of hydrogen was 362 psi). The reactor was dismantled and the mixture was filtered through a pad of celite 545 pre-moistened with MeOH (11.0 cm diameter Büchner 10 funnel). The reactor and pad were rinsed with MeOH and the pad was suctioned until slow dripping and colorless filtrate (~3.0 L total volume). The filtrate was further filtered through a fluted paper disk to remove some fine dark powders. The clear filtrate was transferred to a 5 L RBF and concentrated to orange/brown colored viscous oil which was chilled to 3-4 °C overnight, during which time the material partially solidified/crystallized. The material was 15 warmed and further suctioned under reduced pressure to form a solid rust/brown gummy/waxy hard solid chunk. To the RBF were added heptanes (2 x 700 mL) and MTBE (700 mL). The mixture was stirred with overhead mechanical stirring for 3.5 hours. The liquid layer was decanted from the solid, the chunk was broken into smaller pieces, the liquid was placed back into the RBF and the suspension was stirred vigorously for 16.75 hours. Then the small pieces 20 left were further crushed using the end of a glass stir shaft and the mixture was vigorously stirred for 70 minutes. The suspension was filtered through a tared fritted glass funnel using the filtrate to complete the transfer. The funnel was covered and vacuum dried with low heat (41 °C) for 4 hours providing the product as a faint peachy/beige powder. Yield 270.60 g, HPLC purity 98.5%.


25 The Pd/C catalyst can be replaced by, for example, any catalyst suitable for the hydrogenation of a nitro group.



Step 3 (Option 1): 2-Chloro-4,6-dimethoxy-1,3,5-triazine (4.0 g) was stirred in 30 anhydrous THF (60 mL). N-Methylmorpholine (4.4 g) was added. The resulting mixture was stirred at room temperature for 30 minutes. Then compound 22 (7.2 g) and pyrimidine-4,6-


dicarboxylic acid (1.68 g) were added. The mixture was stirred at room temperature for 24 hours. Then the solvent was evaporated completely in vacuum. Water (250 mL) was added and the mixture was stirred for 4 hours. After filtration, the yellow cake was washed with water (3x100 mL) and stirred in water (250 mL) for 4 hours again. The filtration and washing procedure was 5 repeated twice. Then the solid was dry in the air. The solid was dissolved in 15 mL of DCM:Hexane:Acetone (5:5:1) solution. The mixture was kept at room temperature for 2 days. The solid was filtered and washed with 10 mL of DCM:Hexane (1:1) solution twice. The recrystallization procedure was repeated one more time to give light yellow solid. Yield 70%, HPLC purity 100%.

10




Step 3 (Option 2): EDCI (6.0 g) was stirred in anhydrous Pyridine (60 mL). Then compound 22 (7.2 g) and compound 9 (0.56 g) were added. The mixture was stirred at room temperature for 2 hours. Then another portion pyrimidine-4,6-dicarboxylic acid (0.56 g) was 15 added. After the mixture was stirred at room temperature for another 2 hours, the third portion pyrimidine-4,6-dicarboxylic acid (0.56 g) was added. The resulting mixture was stirred at room temperature for 24 hours. Then the solvent was evaporated completely in vacuum. Water (250 mL) was added and the mixture was stirred for 4 hours. After filtration, the yellow cake was washed with water (3x100 mL) and stirred in water (250mL) for 4 hours again. The filtration and 20 washing procedure was repeated twice. Then the solid was dry in the air. The solid was dissolved in 15 mL DCM:Hexane:Acetone (5:5:1) solution. The mixture was kept at room temperature for 2 days. The solid was filtered and washed with 10 mL DCM:Hexane (1:1) solution twice. The recrystallization procedure was repeated one more time to give light yellow solid. Yield 70%, HPLC purity 100%.

25 EDCI can be replaced with, for example, any amide coupling reagents that generate acid anhydride or activated ester such as CDI, DCC, HOBt, HOAt, POCl₃.




Step 4: The solution of DMAP (3.66 g) in 60 mL anhydrous pyridine was cooled to 0 °C with ice bath. Thionyl chloride (3.60 g) was added slowly. Then the resulting solution was stirred for 10 minutes. The starting material N-Cbz acid (7.53 g, 30 mmol), Cpd 5 (8.54 g, 10 mmol), were added to the solution respectively. The resulting mixture was stirred at room temperature for 4 hours. Then water (500 mL) was added. After the mixture was stirred vigorously at room temperature for 2 hours, the solid was filtered and washed with 250 mL water. The solid was dissolved in ethyl acetate (300 mL). The organic layer was washed with 10% citric acid solution (100 mL) and brine (100 mL) and dried over Na₂SO₄. After evaporation, the residue was dissolved in 40 mL DCM, then 250 mL hexane was added. The precipitate was collected and dry under vacuum. 13.20 g product was obtained in 95% purity. Yield: 100%.

The thionyl chloride can be replaced with, for example, POCl₃, (EtO)₂POCl, or oxalyl chloride.



Step 5: Compound 26 (13.20 g) was dissolved in MeOH with 2 equiv. of 1 N HCl, and the catalyst Pd/C (10%) 1.0 gram was added. The reaction mixture was put on a Parr hydrogenator and shaking for 2 hours under 60 psi of hydrogen. LCMASS showed no progress and another 1.0 gram catalyst was added. The reaction mixture was put on a Parr hydrogenator and shaking for 3 hours under 60 psi of hydrogen. The mixture was filtered through celite to remove the catalyst. The filtrate was concentrated to dryness on a rotovap at 30 °C. 11.50 g product was obtained in 95% purity. Yield: 100%.

The Pd/C catalyst can be replaced with, for example, any catalyst suitable for the hydrogenolysis of CBZ group.




25

Step 6: Compound 27 (11.50 g, 10 mmol) was dissolved in 60 mL methanol and DCM (1:1). Then 4.04 g triethylamine (40 mmol) was added. di-Boc pyrazole 9.3 gram (30 mmol) was added and the resulting mixture was stirred at room temperature for 1 hour. After removing 95% of the solvent, 300 mL water was added and the mixture was stirred vigorously for 2 hours. The

solid was filtered and washed with 300 mL water. The solid was dissolved in 300 mL ethyl acetate and dried over Na_2SO_4 . After evaporating the solvent, the solid was dissolved in 40 mL DCM, then 500 mL hexane was used to precipitate the product out. The solid was collected and dried under vacuum. 13.0 g product was obtained in 85% yield (95% purity).

5 The di-Boc pyrazole can be replaced with, for example, isourea or di-Boc isourea.



Step 7: Compound 28 (1.17 kg, 0.76 mol) was dissolved in 24 L of EtOAc, followed by addition of 281 mL of water. HCl gas was added to the solution while the temperature of 10 reaction was controlled below 45 °C by adjust addition speed. The total reaction time is 5 hours among which 1.5 hour is the time of HCl addition. HPLC indicated the starting material is less than 1% and the precipitated product was collected by filtration under nitrogen. The solid was rinsed with EtOAc, triturated with MeOH/THF (1:1) and dried under vacuum. Yield 84%.

The HCl/EtOAc can be replaced with, for example, HCl/dioxane.

15

Example 5: Antimicrobial Activity vs. Gram-Positive Clinical Isolates (Table 1A) and Gram-Negative Clinical Isolates (Table 1B)

Compound A was evaluated *in vitro* in accordance with defined CLSI documents specific to the organisms (aerobic, anaerobic or yeast) tested in this study. Ampicillin, 20 ceftazidime, cefuroxime, ciprofloxacin, linezolid, and vancomycin were tested alongside as comparator agents for aerobic bacteria; clindamycin and metronidazole were tested as comparators for anaerobes; fluconazole was tested as a comparator for yeast isolates. Stock solutions of Compound A were prepared in dimethyl sulfoxide (DMSO). Ampicillin, ceftazidime, cefuroxime, ciprofloxacin, linezolid, vancomycin, metronidazole, clindamycin, and 25 fluconazole were prepared each according to its manufacturer's guideline.

Aerobes (M7-A7) I

Minimum inhibitory concentrations (MICs) in $\mu\text{g}/\text{ml}$ were determined according to CLSI guideline M7-A7 by broth microdilution. All aerobes were tested using Mueller-Hinton broth medium with the exception of *Streptococcus spp.*, which were tested using cation-adjusted 30 Mueller-Hinton broth supplemented with 2-5% lysed horse blood. Results are shown in Table 1A and Table 1B.

Table 1A

Organism	MIC (µg/mL)* 2-3 isolates/organism			
	Compound A	Linezolid	Vancomycin	Ceftazidime
<i>Enter. faecalis</i>	1	1-2	1	>64
<i>Enter. faecium</i> (VRE)	1	1-2	>128	>64
<i>Staph. aureus</i> (MRSA)	0.5-1	1-2	0.5-1	32
<i>Staph. spidermidis</i>	0.25-0.5	0.5-1	2	16-32
<i>Staph. saprophyticus</i>	0.25-0.5	1-2	1-2	32->64
<i>Staph. spp.</i> (coagulase -)	0.25-0.5	1	1-2	16-32
<i>Strept. agalactiae</i>	2	1	0.5	0.5
<i>Strept. pneumoniae</i>	4-8	1	0.5	0.25
<i>Strept. pyogenes</i>	1-4	1	0.5	0.12
<i>Strept. viridians</i>	2-8	1	0.5-1	0.5-4

*Broth microdilution assays performed according to standard CLSI guidelines.

Table 1B

Organism	MIC (µg/mL)* 2-3 isolates/organism			
	Compound A	Ceftazidime	Linezolid	Vancomycin
<i>Citrobacter freundii</i>	2-4	0.25-2	>16	>128
<i>Citrobacter koseri</i>	1-2	0.12-0.25	>16	>128
<i>Enterobacter cloacae</i>	0.5-4	0.25	>16	>128
<i>Escherichia coli</i>	1-2	0.06	>16	>128
<i>Klebsiella oxytoca</i>	2-8	0.06-0.12	>16	>128
<i>Klebsiella pneumoniae</i>	1-2	0.06-0.12	>16	>128
<i>Morganella morganii</i>	2->64	2-16	>16	>128
<i>Proteus mirabilis</i>	64->64	0.03-0.06	>16	>128
<i>Proteus vulgaris</i>	64->64	0.12	>16	>128
<i>Providencia stuartii</i>	16-64	0.12-0.64	>16	>128
<i>Acinetobacter spp.</i>	4	2-64	>16	128->128
<i>Pseudomonas aeruginosa</i>	32	1-8	>16	>128

<i>Serratia marcescens</i>	32	0.12-0.25	>16	>128
<i>Stenotrophomonas maltophilia</i>	8->64	4-8	>16	32-128
<i>Haemophilus influenzae</i>	4-8	0.06-0.12	16->16	128

*Broth microdilution assays performed according to standard CLSI guidelines.

Compound A exhibited broad coverage against the Gram-positive pathogens with *S. aureus* and coagulase-negative *Staphylococcal species* showing the lowest MICs. Compound A 5 was active against the Gram-negative pathogens but overall coverage was less than for the Gram-positive organisms.

Example 6: MICs with *Staphylococcus* Species with Defined Resistance Phenotypes

Evaluation of the susceptibility profiles of Compound A against selected isolates was 10 carried out *in vitro* by broth microdilution methodology using Mueller-Hinton broth medium according to CLSI document M7-A7. CLSI interpretive breakpoints were applied where applicable as directed by CLSI document M100-S17. Results are shown in Table 2.

Table 2

	Drug-suscept.	OXA-R	VRSA/VISA OXA-R	LZD-NS OXA-R	DAP-NS OXA-R	VRSA/VISA DAP-NS OXA-R
isolates	59	69	7	5	5	3
Compound A MIC range	0.25-1	0.25-2	0.5-1	0.5-1	0.5-2	0.5-1

15 *Broth microdilution assays performed according to standard CLSI guidelines.

OXA-R: oxacillin-resistant; VRSA: vancomycin-resistant *S. aureus*; VISA: vancomycin intermediate *S. aureus*; LZD-NS: linezolid non-susceptible ; DAP-NS : daptomycin non-susceptible.

Compound A was active *in vitro* against all isolates of *S. aureus* and coagulase-negative 20 staphylococci, including isolates of *S. aureus* with characterized resistance to daptomycin, linezolid, and vancomycin (last-line therapeutics for the treatment of resistant *S. aureus* such as MRSA). Against *S. aureus* isolates, there was no alteration in activity against resistant isolates relative to susceptible isolates. Against coagulase-negative staphylococci, activity was not affected by resistance to methicillin.

Example 7: Cytotoxicity and Selectivity

Cytotoxicity of Compound A was evaluated in a colorimetric assay using a transformed human liver cell line (HepG2, HB-8065) and an embryonic mouse cell line (NIH/3T3 cells, CRL-1658). This assay measures the bioreduction of a novel tetrazolium compound to a soluble 5 formazan product by viable cells. HepG2 cells were seeded in 96 well plates at 2×10^4 cells/well in MEM medium with 10% fetal bovine serum (FBS) 24 hours prior to use. NIH/3T3 cells were seeded in 96 well plates at 2×10^4 cells/well in DMEM medium with 10% bovine calf serum (BCS) 24 hours prior to use. Cell monolayers were rinsed in serum-free media and incubated for one hour with Compound A in serum-free media. After incubation, the media was replaced with 10 serum supplemented media and live cells were measured using the Cell Titer 96 Aqueous Non-Proliferation Assay kit (Promega, Madison, WI). EC₅₀ values were determined using a four parameter logistic equation: $Y = \text{Bottom} + (\text{Top} - \text{Bottom}) / (1 + 10^{((\text{LogEC}_{50}) - X) * \text{HillSlope}})$.

Cytotoxicity of Compound A was also evaluated in a hemolysis assay using human erythrocytes. Pooled whole human blood was centrifuged to separate the red blood cells (RBC). 15 The isolated RBCs were rinsed and diluted in Tris-buffered saline (TBS buffer, pH 7.4) to obtain a 0.22% RBC stock suspension. 5 µL of Compound A stock solution was added to 45 µL of RBC suspension and incubated with shaking for 1 hour at 37°C. At the conclusion of the incubation time, samples were centrifuged and 30 µL of the supernatant was added to 100 µL of water. OD₄₁₄ measurements were read for hemoglobin concentration. The bee venom peptide melittin 20 was used as a positive control. EC₅₀ values were determined as described above. Results are shown in Table 3.

Table 3

Compound	MIC or MIC ₉₀ * (µg/mL)	Cytotoxicity (EC ₅₀ µg/mL)			Selectivity (EC ₅₀ /MIC)		
		<i>S. aureus</i>	RBCs	3T3	HepG2	RBCs	3T3
Compound A	1.0*	>500	430	1,031	>500	430	1,031
melittin	2	2	4	1	1	2	0.5

Compound A demonstrates great overall selectivity.

25

Example 8: Time-Kill vs *S. Aureus* (ATCC 27660)

Time-kill studies of Compound A versus *E. coli* ATCC25922, *E. coli* (lab strain) D31, and *S. aureus* ATCC27660 were determined in a standard protocol by measuring the time it takes to reduce the initial inoculum 3 log units. Three ml of cation-adjusted Mueller-Hinton

medium was inoculated with 20 μ L of frozen bacterial stock and incubated at 37 °C on a shaker platform (250 rpm) overnight. The suspension was diluted to approximately 5×10^5 cfu/mL and treated with 2x, 5x, 10x, and 20xMIC (MIC = 1 μ g/mL). Compound A stock solution was prepared at 10 mg/mL in DMSO. Time points were collected and viable bacteria were counted 5 on MH Agar plates after an 18 hour incubation. Studies examining time-kill kinetics of Compound A against *S. aureus* ATCC 27660 at 2x MIC concentrations show that reductions of 3 \log_{10} units in the initial inoculum occur in 5 hours. No re-growth is observed in the cultures over 72 hours at 1x MIC concentrations. See, Figure 1A and Figure 1B.

10 **Example 9: Serial Passage Resistance in MSSA (ATCC 29213) and MRSA (ATCC 33591)**

Frozen bacterial stocks (20 μ L) of *S. aureus* ATCC29213 or methicillin-resistant *S. aureus* (MRSA ATCC 33591) were inoculated into 3 mL cation-adjusted Mueller-Hinton medium and incubated at 37 °C on a shaker platform (250 rpm) overnight. The suspension was diluted to approximately 5×10^5 cfu/mL and inoculated into a polypropylene (Costar) 96-well 15 round bottom plate (90 μ L volumes). Compound stock solutions of Compound A and norfloxacin (Sigma Aldrich, St. Louis, MO; Catalogue# N9890) were prepared in DMSO and serial two-fold dilutions of compound were made in 0.01% acetic acid, 0.2% bovine serum albumin directly in the wells of the polypropylene plate at 10 μ L/well. Final concentrations of Compound A were 50, 25, 12.5, 6.25, 3.13, 1.56, 0.78, 0.39, 0.19, 0.098, 0.049, and 0.024 20 μ g/mL. Final concentration ranges of norfloxacin were 100, 50, 25, 12.5, 6.25, 3.13, 1.56, 0.78, 0.39, 0.19, 0.098, and 0.049 μ g/mL. DMSO concentrations did not exceed 1% in the assay. All samples were performed in triplicate. Following a 24 hour incubation at 37 °C, cell growth was assessed by observing the presence of “acceptable growth”, defined by CLSI as a ≥ 2 mm button or definite turbidity. The MIC wells were defined as the lowest concentration where acceptable 25 growth was not observed. For serial passage, 50 μ L aliquots were taken from 2 of 3 replicate wells at 0.5x MIC and combined into 900 μ L of fresh cation-adjusted Mueller-Hinton medium. The OD₆₀₀ was measured and the cell suspensions were inoculated into polypropylene 96-well round bottom plates (90 μ L volumes) at approximately 5×10^5 cfu/mL. Ten μ L of compound stock solutions were added previously to the wells to achieve the concentration ranges for each 30 compound described above. All samples were performed in triplicate. The plates were incubated for 24 hours at 37 °C. This process was repeated for a total of 17 passages and MIC values were recorded at each passage.

Passage of *S. aureus* with norfloxacin was associated with a significant rise in MIC values by passage 3 (4 doubling dilutions) for both MSSA and MRSA that reached 128-fold and

64-fold increases, respectively, by passage 15. Conversely, there was no change in the MICs for Compound A against MSSA ATCC 29213 or MRSA ATCC 33591 over the entire 17 passage time course. See, Figure 2.

5 **Example 10: *In Vitro* Metabolic Stability of Compound A -- Blood Plasma**

Pooled plasma samples from human (mixed gender), rat (mixed breed and gender) and dog (mixed breed and gender) were incubated with Compound A (5 μ M) at 37 °C for 0 and 60 minutes (duplicate samples). Incubations were terminated by addition of ice-cold precipitation solvent (acetonitrile: glacial acetic acid, 9:1 v/v). Supernatants were diluted with equal volume of 10 0.1% formic acid and analyzed by HPLC-MS/MS. Plasma stability is reported as % parent compound at 60 minutes relative to amount of parent at 0 minutes. Results are shown in Table 4.

Table 4

Species	Plasma Stability (%)
Human	96
Rat (mixed breeds)	102
Dog (mixed breeds)	100

15 There is little to no loss of Compound A in human, rat and dog plasma following 1 hour incubation at 37 °C, indicating high plasma stability. There was also little to no loss of Compound A in humans, cynomolgus monkeys, and rabbits, (data not shown).

Example 11: Efficacy of Compound A in the Mouse Thigh Burden Model

Female 6-7-week old CD-1 mice were made neutropenic with cyclophosphamide (150 20 mg/kg, i.p.) on days 4 and 1 before i.m. inoculation with *S. aureus* (ATCC 13709). *S. aureus* inoculum was prepared by transferring colonies from 18-20-hour tryptic soy agar (TSA) cultures to sterile PBS. The density was adjusted to approximately 10^6 cfu/mL with the aid of a spectrophotometer, and the inoculum concentration was determined by the dilution plate count method. Mice were inoculated by injecting each posterior thigh with 0.1 mL of inoculum. 25 Compound A was given to separate groups of mice (4 females/group) by i.v. bolus doses of 1 or 2 mg/kg/dose at 1 and 5, 1 and 9, or 1 and 13 hours post inoculation as shown in Table 5. A separate control group of 4 mice received the inoculum without antibiotic treatment. Compound A was dissolved 50%/50% v/v sterile USP purified water/PBS. Thighs were harvested at 25 hours after inoculation. Thigh muscle and bone tissue were homogenized, aliquots of serial

dilutions were plated on TSA and incubated at 37 °C for 20 hours, and colony counts were obtained to calculate cfu/thigh. The parameters are shown in Table 5.

Table 5

Group No.	Treatment	Dose (mg/kg/dose)	Total Dose (mg/kg)	Volume (ml/kg)	Treatment (hr after inoculation)	Thigh Harvest (hr after inoculation)	No. Mice
1	Inoc. control	NA	NA	NA	NA	25	4
2	Compound A	1	2	4	1 and 5	25	4
3	Compound A	2	4	4	1 and 5	25	4
4	Compound A	1	2	4	1 and 9	25	4
5	Compound A	2	4	4	1 and 9	25	4
6	Compound A	1	2	4	1 and 13	25	4
7	Compound A	2	4	4	1 and 13	25	4

5 Compound A was most effective in reducing the bacterial population in inoculated thighs when administered at 2 mg/kg/dose at either 1 and 5 or 1 and 9 hours after inoculation. Bacterial reductions in these 2 groups were 3.96 and 3.93 logs lower, respectively, than those of the inoculated control group. See, Figure 3.

10 Example 12: Efficacy vs. Vancomycin in The Rat Thigh Burden Model

For each experiment, female 8-9-week old femoral vein cannulated Crl:CD(SD) rats were made neutropenic with cyclophosphamide (150 mg/kg, i.p.) on days 4 and 1 before i.m. inoculation with *S. aureus* (ATCC 13507). A suspension of *S. aureus* was prepared from colonies obtained from an overnight culture, placed in PBS, and adjusted to approximately 10⁷ 15 cfu/mL with the aid of a spectrophotometer. Each rat was injected 0.2 mL of inoculum into the thigh muscle of the right hind leg. Thighs were harvested at 25 hours after inoculation and processed to determine cfu/thigh. Compound A was given by i.v. bolus injection into a tail vein or 1-hour i.v. infusion, or 4-hour i.v. infusion via the femoral vein cannulae at different time intervals following inoculation. Separate inoculation control groups were included in each 20 experiment, and vancomycin groups were included as comparative agents in the first and second experiments. Each group, including the controls and comparative agent, consisted of 4 rats.

For Compound A, i.v. bolus (10 mg/kg/dose, 20 mg/kg total dose) and 1 hour i.v. infusions (10 mg/kg/dose, 20 mg/kg total dose) reduced the bacterial load by 3.2 and 3.0 logs, respectively, in comparison to inoculated controls. Reductions relative to inoculum levels at 1

hour post-infection were approximately 2.2 to 2.0 logs, respectively. Efficacy was comparable to vancomycin. See, Figure 4.

Example 13: Efficacy Compound A in Mouse Sepsis Model: *S. aureus* Infection

5 Sterile saline, vancomycin, or Compound A were administered to separate groups of 8-week old female CD-1 mice (8 mice/group) 1 and 7 hours after i.p. injections of *S. aureus* (ATCC 13709, 5×10^7 cfu/mL in 5% mucin, 0.5 mL/mouse). Compound A was dissolved in 50%/50% v/v sterile USP purified water/TBS. A suspension of *S. aureus* was prepared from colonies transferred from the TSA plate to sterile PBS. An aliquot of the stock suspension was
10 added to 5% mucin for a final concentration of about 5×10^7 cfu/mL. Study design and doses are shown in Table 6. The mice were observed for 6 days following inoculation for mortality.

Table 6

Treatment	Dose (mg/kg/dose)	Total Dose (mg/kg)	Route of Test Compound	Volume (ml/kg)	Test Compound Injection Schedule (hr after inoculation)	No. Mice
Inoc. control	NA	NA	NA	NA	NA	8
Vancomycin	10	10	s.c.	10	1	8
Compound A	3	6	i.v.	4	1 & 7	8
Compound A	5	10	i.v.	4	1 & 7	8
Compound A	10	20	i.v.	4	1 & 7	8

15 Dose-dependent efficacy was observed with Compound A that was comparable to the vancomycin treatment group. All untreated mice died within the first day of treatment. At the 2x5 and 2x10 mg/kg doses of Compound A, full protection was achieved with Compound A. See, Figure 5.

Example 14: Acute Toxicity Studies -- Maximum Tolerated Doses

20 Maximum tolerated dose (MTD) determinations were made in ascending/descending dose studies in mice and rats. Compound A was administered by either i.v. bolus injection in the tail vein of mice and rats or by i.v. infusion via catheter in the femoral vein of rats. At each dose, two to three animals were administered compound and clinical signs were recorded over a 4 to 7 day period. Gross necropsy was performed at the conclusion of the study. Results are shown in
25 Table 7.

Table 7

Dosage Compound A	MTD (mg/kg)	
	mouse	rat
i.v. bolus	30	N.D.
i.v. infusion – 1 hour	N.D.	>24

The MTD for Compound A in the rat was > 24 mg/kg when administered by i.v. infusion for 1 hour.

5

Example 15: Pharmacokinetics of Compound A in Rats

Crl:CD (SD) rats were administered Compound A by i.v. bolus injection at the indicated dosages. Plasma was prepared from blood samples taken at 9 time points (n=3) over 28 hours. Compound levels were determine by HPLC-MS/MS. All animals were fitted with two jugular 10 vein cannula (JVC), one each for dose administration and blood collection. Each route of administration was dosed as N=3. Animals were supplied with a commercial rodent diet and water *ad libitum*. Each rat received a bolus dosed via the appropriate route of administration at time zero on the day of dosing. Blood sampling times are shown in Table 8.

Each blood sample was collected from the rats via a JVC and placed into chilled 15 polypropylene tubes containing sodium EDTA as an anticoagulant. Samples were centrifuged at a temperature of 4 °C and at a speed of 13,000 rpm for 5 minutes. Samples were maintained chilled throughout processing. Each plasma sample was then transferred into labeled polypropylene tubes, placed on dry ice, and stored in a freezer set to maintain -60 °C to -80 °C.

Plasma study samples were extracted and analyzed using a previously developed 20 method. A single standard curve and six replicates of quality control samples at three concentrations were extracted using DMSO containing 0.1% formic acid. Plasma samples (50 µL) were added to 150 µL solvent and centrifuged. Supernatants were analyzed by LC/MSMS using a Perkin Elmer series 200 micropump and PE Sciex API4000 Electrospray mass spectrometer. Standard curves were prepared at concentrations of 10000, 5000, 1000, 500, 250, 25 100, 50 and 25 ng/mL. Quality control samples were prepared at concentrations of 5000, 500, and 50 ng/mL. The standard curve and quality control samples were prepared from independently prepared stock solutions. At least 5/8 of standards must have accuracy within ±15%, except at the LLOQ where ±20% is acceptable. Two thirds of the batch QCs must have accuracy within ±15% of nominal, and at least one QC must pass at each level in order for the 30 run to be accepted.

Individual plasma concentration versus time data for Compound A was subjected to non-compartmental analysis using the pharmacokinetic program WinNonlin v4.1. Plasma concentrations below the limit of quantitation (25 ng/ml) were assigned a value of zero for pharmacokinetic analysis. Nominal dosing concentrations were used in all calculations.

5

Table 8

Treatment Group	Test Compound	Animals (N)	Dose (mg/kg, free base)	Dosing Solution Conc. (mg/mL)	Dosing Volume (mL/kg)	Vehicle	Sampling Time Points
1	Compound A	3	5	1.25	4	Tris-Buffered Saline, pH 7.4	Predose, 2, 5, 15, 30 minutes, 1, 2, 4 and 8 hours postdose

Results are shown below in Table 9.

Table 9

PK parameter	Compound A (5 mg/kg, i.v. bolus)
C_{max} (μ g/mL)	89.2
$T_{1/2}$ (hours)	3
V_D (mL/kg)	110
C_L (mL/hr/kg)	28

10 The plasma half-life for Compound A in rat plasma was significantly long and clearance values are low.

Example 16: Formulations

15 The saturation solubility of Compound A in various excipients was investigated at 25°C and the results are reported in Table 10 (saturation solubility of Compound A as the free base).

Table 10

Excipient	Functional Category	Compound A (free base) saturation solubility at 25°C (mg/mL)
Purified Water	Control	65
Propylene Glycol	Cosolvents	90
PEG 400		18.5

Glycerin		53
DMA		0.60
Ethanol		1.13
Benzyl alcohol		1.83
Citric Acid/ Sodium Citrate (pH3)	Buffers	65.5
Citric Acid/ Sodium Citrate (pH5)		11.2
Tris(hydroxymethyl)amino methane HCl (pH7.0)		61.4
0.9% Saline	Diluent	N/A
1.2% Saline		N/A

N/A: Not available as the formulation formed a viscous yellow gel

Preliminary investigations indicated that benzyl alcohol, ethanol and DMA were poor vehicles for Compound A with a saturation solubility value of 1.83, 1.13 and 0.60 mg/mL respectively. On the other hand, good saturation solubility of 90 mg/mL, 65 mg/mL and 53 mg/mL were achieved in propylene glycol, purified water and glycerin and were consequently investigated further. Good solubility values were achieved at pH 3 and 7.4 with values of 65.5 and 61.4 mg/ml respectively. The solubility however, appeared to drop at pH5 with a value of 12.1 mg/mL. The saturation solubility of Compound A in 0.9% and 1.2% sodium chloride solution could not be detected as the formulation formed a viscous yellow gel.

The saturation solubility of Compound A in various multi-component systems was investigated at 25 °C and the results are reported in Table 11 (saturation solubility of Compound A as the free base).

Table 11

Excipient	Diluent	Compound A (free base) saturation solubility at 25°C (mg/mL)
20% w/v propylene glycol	saline	N/A
30% w/v propylene glycol	saline	N/A
40% w/v propylene glycol	saline	N/A
50% w/v propylene glycol	saline	N/A
15% w/v propylene glycol	purified water	64.9
30% w/v propylene glycol	purified water	59.1*
50% w/v propylene glycol	purified water	74.7
30%w/v propylene glycol and 5w/v ethanol	purified water	43.9
15% w/v glycerin	purified water	63.5
30% w/v glycerin	purified water	63.1
50% w/v glycerin	purified water	56.8

20% w/v Kleptose	purified water	79.7
40%w/v Kleptose	purified water	102.0
25%w/v Captisol	purified water	64.3

N/A: Not available as the formulation formed a viscous yellow gel

*: The formulation gelled during centrifugation but liquefied on standing.


The formulations which exhibited suitable results included 50% w/v propylene glycol

5 and 15% w/v glycerin in purified water with a saturation solubility value at 25 °C of 74.7 mg/mL and 63.5 mg/mL respectively. Good saturation solubility was also achieved with various complexing agents with values of 79.7, 102.0 and 64.3 mg/mL for 20% w/v Kleptose, 40% w/v Kleptose and 25% w/v Captisol respectively. Results also indicated that addition of Compound A to 20-50% w/v propylene glycol in saline resulted in the formation of a viscous yellow gel and 10 consequently could not be analyzed by UV. However, the gelling phenomenon was concentration dependent and was observed in formulations as the Compound A concentration in the formulation approached the saturation solubility value of the drug. Additionally, the gelling process could be easily reversed by adding a small volume of the excipient formulation or a few drops of ethanol. Addition of 5% w/v ethanol into the formulation did not inhibit the gelling 15 phenomenon but it was still easily reversible and able to be analyzed by UV spectrophotometry. Following an evaluation of preliminary excipient screening data, three suitable formulations were chosen for further formulation development. These formulations are 20% w/v Kleptose solution, 20% w/v propylene glycol in purified water, and 15% w/v glycerin in purified water. The formulation of 50 mg/mL Compound A in 20% w/v Kleptose was selected in phase I 20 clinical trial. In addition, solutions of Compound A in water, Kleptose, or Mannitol can be aliquoted out and lyophilized to a solid. The solid can be reconstituted with water before use.

Various modifications of the invention, in addition to those described herein, will be apparent to those skilled in the art from the foregoing description. Such modifications are also 25 intended to fall within the scope of the appended claims. This application claims priority to U.S. provisional application Serial No. 61/108,595 filed October 27, 2008, which is incorporated herein by reference in its entirety. The present invention was supported by funds from the U.S. Government (NIH Grant Nos. AI74866 and 1R43AI058407) and the U.S. Government may therefore have certain rights in the invention.

What is Claimed is:

1. A compound of Formula I



5 wherein:

each A is, independently, -C=O, -C=S, or -CH₂;

each D is, independently, O or S;

each R¹ is, independently, hydrogen, C₁₋₃alkyl, C₁₋₃alkoxy, halo, or haloC₁₋₃alkyl;

each R² is, independently, hydrogen, C₁₋₃alkyl, C₁₋₃alkoxy, halo, or haloC₁₋₃alkyl;

10 each R³ is, independently, hydrogen, C₁₋₄alkyl, C₁₋₄alkoxy, halo, or haloC₁₋₄alkyl; and

each R⁴ is, independently, hydrogen, C₁₋₃alkyl, C₁₋₃alkoxy, halo, or haloC₁₋₃alkyl;

or a pharmaceutically acceptable salt thereof.

2. The compound or salt of claim 1 wherein each A is -C=O.

15

3. The compound or salt of claim 1 or claim 2 wherein each D is O.

4. The compound or salt of any one of claims 1 to 3 wherein each R¹ is, independently, hydrogen, methyl, ethyl, methoxy, ethoxy, halo, or haloC₁₋₃alkyl.

20

5. The compound or salt of any one of claims 1 to 3 wherein each R¹ is, independently, hydrogen, methyl, methoxy, halo, or haloC₁₋₃alkyl.

25

6. The compound or salt of any one of claims 1 to 3 wherein each R¹ is, independently, hydrogen, methyl, or methoxy.

7. The compound or salt of any one of claims 1 to 3 wherein each R¹ is hydrogen.

30

8. The compound or salt of any one of claims 1 to 7 wherein each R² is, independently, hydrogen, methyl, ethyl, methoxy, ethoxy, halo, or haloC₁₋₃alkyl.

9. The compound or salt of any one of claims 1 to 7 wherein each R² is, independently, hydrogen, methyl, methoxy, or halo.

10. The compound or salt of any one of claims 1 to 7 wherein each R² is hydrogen.

5

11. The compound or salt of any one of claims 1 to 10 wherein each R³ is, independently, hydrogen, methyl, ethyl, methoxy, ethoxy, halo, or haloC₁₋₃alkyl.

12. The compound or salt of any one of claims 1 to 10 wherein each R³ is, independently, 10 methyl, methoxy, halo, or haloC₁₋₃alkyl.

13. The compound or salt of any one of claims 1 to 10 wherein each R³ is, independently, halo or haloC₁₋₃alkyl.

15 14. The compound or salt of any one of claims 1 to 10 wherein each R³ is, independently, haloC₁₋₃alkyl.

15. The compound or salt of any one of claims 1 to 10 wherein each R³ is trifluoromethyl.

20 16. The compound or salt of any one of claims 1 to 15 wherein each R⁴ is, independently, hydrogen, methyl, ethyl, methoxy, ethoxy, or haloC₁₋₃alkyl.

17. The compound or salt of any one of claims 1 to 15 wherein each R⁴ is, independently, hydrogen, methyl, methoxy, halo, or haloC₁₋₃alkyl.

25

18. The compound or salt of any one of claims 1 to 15 wherein each R⁴ is, independently, hydrogen, methyl, methoxy, or halo.

30

19. The compound or salt of any one of claims 1 to 15 wherein each R⁴ is hydrogen.

20. The compound or salt of claim 1 wherein:
each A is, independently, -C=O or -C=S;
each D is, independently, O or S;

each R¹ is, independently, hydrogen, methyl, ethyl, methoxy, ethoxy, halo, halomethyl, or haloethyl;

each R² is, independently, hydrogen, methyl, methoxy, halo, or halomethyl;

each R³ is, independently, C₁₋₃alkyl, C₁₋₃alkoxy, halo, or haloalkyl; and

5 each R⁴ is, independently, hydrogen, methyl, ethyl, methoxy, ethoxy, halo, halomethyl, or haloethyl.

21. The compound or salt of claim 1 wherein:

each A is, independently, -C=O or -C=S;

10 each D is, independently, O or S;

each R¹ is, independently, hydrogen, methyl, methoxy, halo, or halomethyl;

each R² is, independently, hydrogen, halo, or halomethyl;

each R³ is, independently, methyl, ethyl, methoxy, ethoxy, halo, halomethyl, or haloethyl; and

15 each R⁴ is, independently, hydrogen, methyl, ethyl, methoxy, ethoxy, halo, halomethyl, or haloethyl.

22. The compound or salt of claim 1 wherein:

each A is -C=O;

20 each D is O;

each R¹ is, independently, hydrogen, halo, or halomethyl;

each R² is, independently, hydrogen or halo;

each R³ is, independently, methyl, methoxy, halo, or halomethyl; and

each R⁴ is, independently, hydrogen, methyl, methoxy, halo, or halomethyl.

25

23. The compound or salt of claim 1 wherein:

each A is -C=O;

each D is O;

each R¹ is, independently, hydrogen or halo;

30 each R² is, independently, hydrogen or halo;

each R³ is, independently, methyl, halo, or halomethyl; and

each R⁴ is, independently, hydrogen, methyl, halo, or halomethyl.

24. The compound or salt of claim 1 wherein:

- each A is -C=O;
- each D is O;
- each R¹ is, independently, hydrogen or halo;
- each R² is, independently, hydrogen or halo;
- each R³ is, independently, halo or halomethyl; and
- each R⁴ is, independently, hydrogen or halo.

25. The compound or salt of claim 1 wherein:

10 each A is -C=O;

each D is O;


each R¹ is, independently, hydrogen or halo;

each R² is, independently, hydrogen or halo;

each R³ is, independently, methyl, halo, or halomethyl; and

15 each R⁴ is, independently, hydrogen, methyl, halo, or halomethyl.

26. The compound



or a pharmaceutically acceptable salt thereof.

20

27. A pharmaceutical composition comprising the compound of any one of claims 1 to 26, or a pharmaceutically acceptable salt thereof, and a pharmaceutically acceptable carrier.

28. A formulation comprising a compound of any one of claims 1 to 26, or

25 pharmaceutically acceptable salt thereof, wherein the formulation comprises an excipient chosen from purified water, propylene glycol, PEG 400, glycerin, DMA, ethanol, benzyl alcohol, citric acid/sodium citrate (pH3), citric acid/sodium citrate (pH5), tris(hydroxymethyl)amino methane HCl (pH7.0), 0.9% saline, and 1.2% saline, or any combination thereof.

29. A formulation comprising a compound of any one of claims 1 to 26, or pharmaceutically acceptable salt thereof, wherein the formulation comprises an excipient chosen from propylene glycol, purified water, and glycerin.

5 30. A formulation comprising a compound of any one of claims 1 to 26, or pharmaceutically acceptable salt thereof, wherein the formulation comprises an excipient chosen from 20% w/v propylene glycol in saline, 30% w/v propylene glycol in saline, 40% w/v propylene glycol in saline, 50% w/v propylene glycol in saline, 15% w/v propylene glycol in purified water, 30% w/v propylene glycol in purified water, 50% w/v propylene glycol in purified water, 30% w/v propylene glycol and 5 w/v ethanol in purified water, 15% w/v glycerin in purified water, 30% w/v glycerin in purified water, 50% w/v glycerin in purified water, 20% w/v Kleptose in purified water, 40% w/v Kleptose in purified water, and 25% w/v Captisol in purified water.


10 15 31. A formulation comprising a compound of any one of claims 1 to 26, or pharmaceutically acceptable salt thereof, wherein the formulation comprises an excipient chosen from 50% w/v propylene glycol in purified water, 15% w/v glycerin in purified water, 20% w/v Kleptose in purified water, 40% w/v Kleptose in purified water, and 25% w/v Captisol in purified water.

20

32. A formulation comprising a compound of any one of claims 1 to 26, or pharmaceutically acceptable salt thereof, wherein the formulation comprises an excipient chosen from 20% w/v Kleptose in purified water, 20% w/v propylene glycol in purified water, and 15% w/v glycerin in purified water.

25

33. A formulation comprising




, or a pharmaceutically acceptable salt thereof, in 20% w/v Kleptose in purified water.

34. The formulation of claim 33 wherein the compound is present at 50 mg/mL.

35. A method of preparing the compound of claim 26 comprising:

a) reacting (R)-(-)-N-Boc-3-pyrrolidinol with a strong base to form a mixture; further


5 reacting the mixture with 2-chloro-5-(trifluoromethyl)-1,3-dinitrobenzene to form a compound having Formula II



II;

b) reacting the compound of Formula II with an alcohol and a transition metal catalyst

10 in the presence of hydrogen to form a compound of Formula III




III;

c) adding the compound of Formula III and pyrimidine-4,6-dicarboxylic acid to a

mixture of 2-chloro-4,6-dimethoxy-1,3,5-triazine and N-methylmorpholine to form a compound


15 of Formula IV



IV;

d) reacting the compound of Formula IV with N-Boc- guanidine butyric acid to form a

compound of Formula V



20

V; and

e) deprotecting the compound of Formula V to produce the compound of claim 26.

36. The method of claim 35 wherein:
 in step a) the strong base is NaH; and
 in step b) the transition metal catalyst is Pd/C and the alcohol is ethanol.

5 37. A method of preparing the compound of claim 26 comprising:
 a) deprotonating (R)-3-Hydroxypyrrolidine-1-carboxylic acid *tert*-butyl ester, and
 reacting the resultant compound with 2-chloro-1,3-dinitro-5-trifluoromethylbenzene to form (R)-
 3-(2,6-dinitro-4-trifluoromethylphenoxy)pyrrolidine-1-carboxylic acid *tert*-butyl ester;
 b) reducing (R)-3-(2,6-dinitro-4-trifluoromethylphenoxy)pyrrolidine-1-carboxylic acid
 10 *tert*-butyl ester in the presence of an alcohol, a transition metal catalyst, and hydrogen to form
 (R)-3-(2,6-diamino-4-trifluoromethylphenoxy)-pyrrolidine-1-carboxylic acid *tert*-butyl ester;
 c) coupling (R)-3-(2,6-diamino-4-trifluoromethylphenoxy)-pyrrolidine-1-carboxylic
 acid *tert*-butyl ester with pyrimidine-4,6-dicarboxylic acid in the presence of 1-[(3-
 (dimethylamino)-propyl)-3-ethylcarbodiimide hydrochloride to form pyrimidine-4,6-
 15 dicarboxylic acid bis- {[3-amino-2-((R)-1-(*tert*-butoxycarbonyl)pyrrolidin-3-yloxy)-5-
 trifluoromethyl-phenyl]amide};
 d) reacting pyrimidine-4,6-dicarboxylic acid bis- {[3-amino-2-((R)-1-(*tert*-
 butoxycarbonyl)pyrrolidin-3-yloxy)-5-trifluoromethyl-phenyl]amide} with ({[(*tert*-
 butoxycarbonyl)amino][(*tert*-butoxycarbonyl)imino]methyl}amino)pentanoic acid in the
 20 presence of phosphorous oxychloride to form pyrimidine-4,6-dicarboxylic acid bis- {[3-(5-
 ({[(*tert*-butoxycarbonyl)amino][(*tert*-butoxycarbonyl)imino]methyl}amino)-pentanoylamino)-2-
 ((R)- 1-(*tert*-butoxycarbonyl)-pyrrolidin-3-yloxy)-5-trifluoromethyl-phenyl]-amide};
 e) deprotecting pyrimidine-4,6-dicarboxylic acid bis- {[3-(5-({[(*tert*-
 butoxycarbonyl)amino][(*tert*-butoxycarbonyl)imino]methyl}amino)-pentanoylamino)-2-((R)- 1-
 25 (*tert*-butoxycarbonyl)-pyrrolidin-3-yloxy)-5-trifluoromethyl-phenyl]-amide} to form crude
 pyrimidine-4,6-dicarboxylic acid bis- {[3-(5-guanidino-pantanoylamino)-2-((R)-pyrrolidin-3-
 yloxy)-5-trifluoromethyl-phenyl]-amide}tetrahydrochloride; and
 f) purifying crude pyrimidine-4,6-dicarboxylic acid bis- {[3-(5-guanidino-
 30 pentanoylamino)-2-((R)-pyrrolidin-3-yloxy)-5-trifluoromethyl-phenyl]-
 amide}tetrahydrochloride by reverse-phase chromatography.

38. A method of preparing the compound of claim 26 comprising:

a) deprotonating (R)-3-Hydroxypyrrolidine-1-carboxylic acid *tert*-butyl ester and further reacting the resultant compound with 2-chloro-1,3-dinitro-5-trifluoromethylbenzene to form (R)-3-(2,6-dinitro-4-trifluoromethylphenoxy)pyrrolidine-1-carboxylic acid *tert*-butyl ester;

5 b) reducing (R)-3-(2,6-dinitro-4-trifluoromethylphenoxy)pyrrolidine-1-carboxylic acid *tert*-butyl ester in the presence of an alcohol, a transition metal catalyst, and hydrogen, to form (R)-3-(2,6-diamino-4-trifluoromethylphenoxy)-pyrrolidine-1-carboxylic acid *tert*-butyl ester;

10 c) coupling (R)-3-(2,6-diamino-4-trifluoromethylphenoxy)-pyrrolidine-1-carboxylic acid *tert*-butyl ester with pyrimidine-4,6-dicarboxylic acid in the presence of 1-[(3-dimethylamino)-propyl]-3-ethylcarbodiimide hydrochloride to form pyrimidine-4,6-dicarboxylic acid bis-[3-amino-2-((R)-1-(*tert*-butoxycarbonyl)pyrrolidin-3-yloxy)-5-trifluoromethyl-phenyl]amide};

15 d) reacting pyrimidine-4,6-dicarboxylic acid bis-[3-amino-2-((R)-1-(*tert*-butoxycarbonyl)pyrrolidin-3-yloxy)-5-trifluoromethyl-phenyl]amide} with N-Cbz acid in the presence of thionyl chloride;

e) reducing the resultant compound of d) in the presence of an alcohol, a transition metal catalyst, and hydrogen;

f) reacting the resultant compound of e) with di-Boc pyrazole;


20 g) deprotecting the resultant compound of f) to produce the compound of claim 26.

25

39. A method of preparing a pharmaceutically acceptable salt of the compound of claim 26 comprising:


a) reacting (R)-(-)-N-Boc-3-pyrrolidinol with a strong base to form a mixture; further reacting the mixture with 2-chloro-5-(trifluoromethyl)-1,3-dinitrobenzene to form a compound

25 having Formula II




II;

b) reacting the compound of Formula II with an alcohol and a transition metal catalyst in the presence of hydrogen to form a compound of Formula III




III;

c1) adding the compound of Formula III and pyrimidine-4,6-dicarboxylic acid to a mixture of 2-chloro-4,6-dimethoxy-1,3,5-triazine and N-methylmorpholine to form a compound of Formula IV




IV; or

c2) adding the compound of Formula III and pyrimidine-4,6-dicarboxylic acid to a mixture of 1-ethyl-3-[3-(dimethylamino)propyl]-carbodiimide hydrochloride (EDCl) and anhydrous pyridine to form a compound of Formula IV



IV:


d) adding the compound of Formula IV with an N-Cbz acid to a solution comprising anhydrous pyridine, dimethylaminopropylamine, and any one of thionyl chloride, POCl_3 , 15 $(\text{EtO})_2\text{POCl}$, or oxalyl chloride to form a compound of Formula Va



Va;


e) hydrogenolysis of the Cbz group of the compound of Formula Va to produce the compound of formula VI

- 61 -



VI;

f) protecting the compound of Formula VI to produce the compound of formula VII



5

VII; and

g) deprotecting the compound of Formula VII to produce a pharmaceutically acceptable salt of the compound of claim 26.

40. A method of inhibiting the growth of a microbe comprising contacting the microbe with
10 a compound of any one of claims 1-26.

41. A method of treating a mammal having a microbial infection comprising administering to the mammal in need thereof an anti-microbial effective amount of a compound of any one of claims 1-26.

15

42. The method of claim 40 or claim 41 wherein the microbe or microbial infection is a gram-negative aerobe, a gram-positive aerobe, a gram-negative anaerobe, a gram-positive anaerobe, or a yeast.

20 43. The method of claim 42 wherein the gram-negative aerobe is *Escherichia coli*,
Citrobacter freundii, *Citrobacter diverus*, *Citrobacter koseri*, *Enterobacter cloacae*,
Enterobacter faecalis, *Klebsiella pneumonia*, *Klebsiella oxytoca*, *Morganella morganii*,
Providencia stuartii, *Proteus vulgaris*, *Proteus mirabilis*, *Serratia marcescens*, *Acinetobacter*
haemolyticus, *Acinetobacter junii*, *Acinetobacter lwoffii*, *Haemophilus influenzae*,
25 *Stenotrophomonas maltophilia*, or *Pseudomonas aeruginosa*.44. The method of claim 42 wherein the gram-positive aerobe is *Enterococcus faecalis*,
Enterococcus faecium, *Mycobacterium tuberculosis*, *Staphylococcus aureus*, *Staphylococcus*

pneumoniae, Staphylococcus epidermidis, Staphylococcus saprophyticus, Staphylococcus colmii, Staphylococcus sciuri, Staphylococcus warneri, Streptococcus agalactiae, Streptococcus pyogenes, Streptococcus anginosus, Streptococcus mitis, or Streptococcus oralis.

5 45. The method of claim 42 wherein the gram-negative anaerobe is *Bacteroides fragilis*.

46. The method of claim 42 wherein the gram-positive anaerobe is *Clostridium difficile* or *Clostridium perfringens*.

10 47. The method of claim 42 wherein the yeast is *Candida albicans* or *Candida krusei*.


48. A compound according to any one of claims 1 to 26 for treating a microbial infection.

49. A compound according to any one of claims 1 to 26 for use in the manufacture of a
15 medicament for the treatment of a microbial infection.

50. Use of a compound of any one of claims 1 to 26 in the inhibition of growth of a
microbe.


20 51. Use of a compound of any one of claims 1 to 26 in the treatment of a microbial
infection in a mammal.

1/5



Time in hours

Figure 1A



Time in hours

Figure 1B

2/5




Figure 2

3/5




Figure 3

4/5




Figure 4

5/5






Figure 5



Time in hours

Figure 1A



Time in hours

Figure 1B