



US007108124B2

(12) **United States Patent**  
**Bernard et al.**

(10) **Patent No.:** **US 7,108,124 B2**  
(45) **Date of Patent:** **Sep. 19, 2006**

(54) **METHOD FOR MULTIPLE LIFT STACKING  
USING MOBILE CONVEYOR SYSTEM**

(75) Inventors: **George M Bernard**, Chula Vista, CA  
(US); **Ronald R Kelly**, Poway, CA  
(US)

(73) Assignee: **Terra Nova Technologies**, Santee, CA  
(US)

(\*) Notice: Subject to any disclaimer, the term of this  
patent is extended or adjusted under 35  
U.S.C. 154(b) by 198 days.

(21) Appl. No.: **10/847,639**

(22) Filed: **May 17, 2004**

(65) **Prior Publication Data**

US 2005/0183930 A1 Aug. 25, 2005

**Related U.S. Application Data**

(62) Division of application No. 10/058,949, filed on Jan.  
28, 2002, now Pat. No. 6,782,993.

(51) **Int. Cl.**

**B65G 47/00** (2006.01)

**E21C 37/00** (2006.01)

(52) **U.S. Cl.** ..... **198/617**; 198/508; 299/18

(58) **Field of Classification Search** ..... 198/508,  
198/585, 588, 617; 37/239; 172/1; 299/18;  
414/133

See application file for complete search history.

(56) **References Cited**

**U.S. PATENT DOCUMENTS**

1,996,488 A \* 4/1935 Philips ..... 198/508

3,887,061 A \* 6/1975 Hopkins ..... 198/304  
4,103,972 A \* 8/1978 Kochanowsky ..... 299/18  
4,150,852 A \* 4/1979 McCoy ..... 299/18  
4,345,680 A \* 8/1982 Kay ..... 198/304  
4,828,431 A \* 5/1989 Chen ..... 405/217  
4,979,781 A \* 12/1990 Bothwell et al. .... 299/18  
5,033,795 A \* 7/1991 Farrar et al. .... 299/18  
5,515,961 A \* 5/1996 Murphy et al. .... 198/302  
5,833,043 A \* 11/1998 Schmidgall et al. .... 198/302  
6,085,890 A \* 7/2000 Kelly et al. .... 198/303  
6,119,375 A \* 9/2000 Wilson et al. .... 37/195  
6,782,993 B1 \* 8/2004 Bernard et al. .... 198/585

\* cited by examiner

*Primary Examiner*—Douglas A. Hess

(74) *Attorney, Agent, or Firm*—Patterson & Sheridan, LLP

(57) **ABSTRACT**

Mobile conveyor modules are used for transporting aggregate over a long distance, or for transferring the aggregate to other modules, and for stacking the aggregate either linearly or radially. These modules may be used in various combinations by themselves or in combination with existing conveyor systems and bridge stackers to stack aggregate on and off multi-lift leach pads and on multi-lift dump sites. Multiple stacking methods may be used with mobile conveyor modules either separately, or at the same time, advance and retreat stacking, the stacking of a berm, or the filling in or a corridor, may be accomplished on a variety of terrain.

**19 Claims, 22 Drawing Sheets**




Figure 1




Figure 2





Figure 3






Figure 4




Figure 5






Figure 6










Figure 9




Figure 10








Figure 11














Figure 16






Figure 18

Figure 19







Figure 20







1

# METHOD FOR MULTIPLE LIFT STACKING USING MOBILE CONVEYOR SYSTEM

## CROSS REFERENCE TO RELATED APPLICATIONS

This application is a divisional application of U.S. application Ser. No. 10/058,949 filed Jan. 28, 2002, now U.S. Pat. No. 6,782,993 entitled MOBILE CONVEYOR SYSTEM AND METHOD FOR MULTIPLE LIFT STACKING.

## STATEMENT REGARDING FEDERALLY SPONSORED RESEARCH OR DEVELOPMENT

Not Applicable

## REFERENCE TO SEQUENCE LISTING, A TABLE, OR A COMPUTER PROGRAM LISTING COMPACT DISK APPENDIX

Not Applicable

## BACKGROUND OF THE INVENTION

The present invention relates to the movement of bulk materials, and more particularly, pertains to moving and stacking material, such as ore, coal, granite, clay, salt, and potash, generally referred to herein as "aggregate", by mobile belt conveyor modules.

The present invention is concerned with depositing aggregate into piles, and more particularly is an improved method for depositing aggregate into multi-lift dump sites, such as heap leach stacks, waste dump sites, or material dump sites, for example.

In the past, very long, endless conveyor belt assemblies have been used for transporting loose particulate material over long distances. Bridge conveyors or mobile stacking conveyors have also been used. One of the problems with the conveyor systems of the prior art is that such systems take time to move any appreciable distance when a new stack is to be started. This is especially true when stacking aggregate ore which is to be subjected to heap leach processes used, for example, to extract copper or gold from the stacked piles of aggregate or leach pads.

In today's world, mining is a basic industry in a global economy. Thus, regardless of the site of the mining or leaching operation, it must be conducted in a manner that minimizes capital costs, minimizes operating costs, and minimizes the delay time between stacking heaps and recovering the metals or mineral of interest.

Prior art multiple lift stacking systems using bridges, with either advance or retreat stacking, require considerable down time, a great deal of additional earth work effort, and a considerable amount of labor to extend and retract the overland conveyor used in the process. The prior art stacking processes delay recovery of the metals or minerals of interest from the aggregate. In an ongoing leaching operation, for example, a major concern is to leach the newly stacked aggregate immediately. Thus, at the completion of any lift, a complete leach cycle time is scheduled before stacking the next lift so that the material can be leached to full economic advantage at each lift.

These concerns, in general, require movement of the prior art systems that could be both wasteful and unnecessary.

A prior art attempt to solve such a problem is described in U.S. Pat. No. 6,085,890 granted Jul. 11, 2000 to Ronald R. Kelly, et al. for Heap Leach Stacking Process. However,

2

even this approach requires down time, a shortcoming which the present invention overcomes.

## BRIEF SUMMARY OF THE INVENTION

Multiple lift pad and dump site stacking is enhanced in flexibility and speed by the use of mobile stackers, mobile trippers, and mobile conveyor modules, which are carried by rolling stock, such as wheels or crawler tracks which are steerable. Some of these modules are also self-powered so they are driveable to the required locations. The combination of mobile conveyor modules bringing aggregate to a tripper for distribution to a bridge stacker and a radial stacker provides efficient multiple lift stacking of a leach pad or a general dump site. Berm building and corridor filling occur at about the same time as the lift stacking. Moreover, the self-powered mobility of the mobile conveyor modules and tripper modules considerably reduces down time when the modules must be relocated.

The invention utilizes a mobile belt conveyor module mounted for movement with respect to the ground on steerable rolling stock. A mobile belt conveyor with a tripper, "mobile tripper module" mounted for movement with respect to the ground on steerable rolling stock is fed aggregate by the mobile belt conveyor module. A mobile stacker is fed aggregate by the mobile tripper module to stack the aggregate to lift level. The stacking method of the present invention comprises advance stacking a lift berm for conveyor travel at about the same time the extension-half of the lift -is being-advance stacked. The retraction half of the lift is also advance stacked, leaving a completely stacked lift without corridors to be filled. Alternatively, the stacking method of the present invention comprises advance and retreat stacking in the extension phase, creating a corridor for conveyor travel. Advance and retreat stacking in the retraction phase while also stacking the corridor, leaves a completely stacked lift without a corridor to fill.

## BRIEF DESCRIPTION OF THE DRAWINGS

The exact nature of this invention, as well as its objects and its advantages, will become readily apparent from consideration of the following detailed description in conjunction with the accompanying drawings, in which like reference numerals designate like parts throughout the figures thereof and wherein:

FIG. 1 is a partial perspective schematic layout of an on/off leach pad and waste dump stacking scheme;

FIG. 2 is a perspective illustration of a stacking scheme utilizing the radial stacker, the self-powered mobile tripper module, and the self-powered mobile belt conveyor;

FIG. 3 is an isometric illustration indicating an area topography before heap stacking has begun;

FIG. 4 is an isometric illustration indicating the disposition of stacking system components on an area topography at the beginning of a stacking cycle for the first lift;

FIG. 5 is an isometric illustration indicating the disposition of stacking system components on an area topography after the extension phase of first lift stacking has begun;

FIG. 6 is an isometric illustration indicating the disposition of the stacking system components on an area topography wherein a stacker is building a berm to lift grade elevation;

FIG. 7 is an isometric illustration indicating the disposition of stacking system components on an area topography when the first lift cycle has reached the end of the area furthest away from the material supply;



FIG. 8 is an isometric illustration indicating the disposition of stacking system components on an area topography during the retraction phase of first lift stacking;

FIG. 9 is an isometric illustration indicating the disposition of the stacking system components on an area topography when the first lift cycle is being completed;

FIG. 10 is an isometric illustration indicating the disposition of stacking system components on an area topography after the first lift cycle has completed and the stacking bridge is being rotated into a starting position for the second lift cycle;

FIG. 11 is an isometric illustration indicating the disposition of stacking system components on an area topography after the extension phase of the second lift cycle has begun;

FIG. 12 is an isometric illustration indicating the disposition of stacking system components on an area topography during the extension phase of the second lift cycle;

FIG. 13 is an isometric illustration indicating the disposition of stacking system components on an area topography when the second lift cycle has reached the end of the area furthest away from the material supply and the stacking bridge is being rotated and translated around the end of the area to prepare to begin retraction;

FIG. 14 is an isometric illustration indicating the disposition of stacking system components on an area topography during the retraction phase of a second lift cycle;

FIG. 15 is an isometric illustration indicating the disposition of stacking system components and the area topography during the retraction phase with a radial stacker filling in the corridor to lift grade elevation;

FIG. 16 is an isometric illustration indicating the disposition of stacking system components on an area topography when the second lift cycle is completed and the grade elevation is being tapered out against the topographic slope;

FIG. 17 is a schematic illustration of a stacking layout for a dump site showing disposition of the stacking system components during the extension phase of a lift cycle;

FIG. 18 is a schematic illustration showing the disposition of stacking system components on a dump site when stacking has reached the end of the area furthest away from the material supply and the stacking bridge is being rotated and translated around the end of the area to prepare to begin retraction;

FIG. 19 is a schematic illustration showing the disposition of stacking system components on a dump site during retraction;

FIG. 20 is a schematic illustration showing the disposition of stacking system components on a dump site at about completion of the retraction phase with a radial stacker stacking the corridor;

FIG. 21 is a schematic illustration showing the relocation of the stacking system components to an adjacent dump site; and

FIG. 22 is a schematic illustration showing disposition of the stacking system components in the retraction phase of a multiple lift stacking cycle on a third adjacent dump site.

#### DETAILED DESCRIPTION OF THE PREFERRED EMBODIMENTS

FIG. 1 illustrates in three dimensions and schematically one of many possible layouts for an on/off leach pad stacking scheme adjacent to a dump site. The stacking of the leach pad and dump site is being accomplished by prior art equipment. The conveyor modules of the present invention are not being used. Leach pad 11 is typically designed to capture the leach liquid and the contained dissolved recov-

erable minerals or metals. A discharge conveyor 13 delivers aggregate to a stacking overland conveyor 15, which is aligned parallel to the longer axis of the leach pad 11. Overland conveyor 15 supplies the aggregate to bridge stacker 21, which is shown retreat stacking a lift 27.

Ahead of bridge stacker 21, a reclaim bridge conveyor and associated equipment 19, removes the leached aggregate lift 29 from its path. This reclaimed aggregate is mostly unwanted residue. The removed aggregate is supplied to reclaim overland conveyor 17. Overland conveyor 17 transfers the aggregate to conveyor 23, which, in turn, supplies it to an extendible overland conveyor 31. The extendible overland conveyor 31 is shown fully extended to the area 33 furthest away from the material supply. The extendible overland conveyor 31 supplies its aggregate to a stacking bridge 35, which is shown radially stacking the dump aggregate.

A normal dump stacking process would start with segment 41. Then segment 43 would be stacked. Then segment 45 and segment 47 would be stacked sequentially. After this five segment area is radially stacked, the extendible overland conveyor 31 would be moved to another area, indicated by phantom lines 37 following a path generally indicated by phantom lines 49, for example. The stacking of each area may take up to a year. A third waste dump stack, area 39, is also illustrated in phantom lines. A possible path of the extendible overland conveyor 31 for this area is illustrated by phantom lines 53.

FIG. 2 represents a retreat stacking system utilizing modular conveyors. In place of an overland conveyor, for example, a series of mobile conveyor modules 87 are positioned along a center line of a stack pad. The entire assembly is stacking and retreating in the direction of arrows 109 and 103.

As the series of mobile conveyor modules 87 retreats along the corridor 106 in direction 109, aggregate is being fed to tripper module 53a, which supplies the aggregate through its tripper unit 61, to another mobile conveyor module 87b. The tripper unit 61 is a reversible discharge conveyor capable of aggregate discharge to both sides. Tripper module 53a is shown loading aggregate into mobile belt conveyor module 87b which is displaced laterally 107 from tripper 53a by approximately ten to twelve feet. Mobile belt conveyor module 87b unloads the aggregate into the receiving hopper of a radial stacker 41a which retreat stacks the aggregate 99 in corridor 106, thereby filling the corridor.

At the same time that corridor 106 is being stacked, tripper module 53a is supplying aggregate by way of its reversible shuttle discharge tripper 61 to another mobile conveyor unit 87c which provides its aggregate to another tripper conveyor 53b which supplies aggregate by way of its shuttle discharge conveyor 61 to another mobile belt conveyor module 87d, which in turn, feeds another radial stacker 41b. Radial stacker 41b stacks aggregate 105 radially in a retreat direction 103 that is lateral to corridor 106.

FIG. 3 shows an isometric view of the topography of an area 112 along with a fixed conveyor belt 101 which is intended to supply all the bulk prepared materials which are to be stacked on the heap stacking area 112. Fixed conveyor belt 101 will discharge its aggregate at discharge point 100.

The topography of the leach stacking area 112 includes two relatively small ridges, 113 and three relatively small valleys 114 which may be naturally occurring or have been prepared by earth moving equipment. For illustration purposes, area 112 will be shown as stacked using two lift cycles. The first lift will be at an elevation that intersects the near side topography along first lift intersection contour 115.

5

The second lift will be at an elevation that intersects the near side topography along second lift intersection contour **116**. The final crest of the entire heap is to be the final heap crest contour **117**. The final toe is to be the final heap toe contour **118**.

The center line axis **119** of the heap area **112** will be the center line axis for the corridors of the two lift cycles according to the preferred embodiment of the present invention. It should be understood, however, that the present invention includes any reasonable number of lifts or lift cycles with the center line axis changing from lift to lift as desired. Center line axis **119** intersects the discharge point **100** of the fixed conveyor belt **101** so that conveyor belt **101** transfers its material into the system at discharge point **100** during the entire heap stacking process for area **112**.

An area, like area **112** with its unique geometry, is suitable for a leach pad since it allows the aggregate to be stacked so that the top of the first lift clears the ridges **113**, thereby allowing the valleys **114** to be used to collect the lixiviant, or leaching liquids containing the recovered metals or minerals, after it has passed through the heap. This choice of a natural topography alleviates the requirement for prior earth-work preparation. This site is also suitable for dump stacking aggregate.

FIG. **4** illustrates the topography of FIG. **3** with the stacking system components according to the present invention located to begin the stacking process. The view of the area topography is from the far side looking back towards the near side of material supply at discharge point **100** before the first lift cycle begins. The system components are a tripper module **53**, a stacker **41**, and a bridge stacker **67**. All the components are located to begin stacking the extension phase of a lift cycle in an advance stacking mode. The aggregate will begin to be stacked in front of bridge **67** in a tapered fashion outward so that the bridge **67** can travel on top of the newly deposited lift material. In addition, stacker **41** will be building a berm in corridor area **122** during this extension phase of the lift stacking cycle. Stacker **41** may be a radial stacker or a regular conveyor stacker, which can not radial stack, but is capable of stacking a berm (berm stacker).

FIG. **5** illustrates the location of the stacking system components with respect to the area topography after stacking has begun. Radial stacker **41** is stacking aggregate in corridor area **122** building a berm to first lift elevation **131**, while at the same time advancing to remain abreast of bridge stacker **67**. Bridge stacker **67** is being supplied with material from tripper module **53**, which is also supplying stacker **41**. Bridge stacker **67** stacks the aggregate in front to its lift elevation **131**. Bridge stacker **67** and stacker **41** extend out on top of the newly stacked aggregate at lift level **131**.

FIG. **6** illustrates the position of the stacking system components after the advance stacking mode has progressed, as can be seen by the number of mobile belt conveyor modules **87** needed to carry the aggregate from transfer point **100** to tripper module **53**. Tripper module **53** continues to supply the aggregate to bridge stacker **67** and stacker **41**. Stacker **41** continues to deposit material to build the berm **122** to grade level **131**. Bridge stacker **67** continues to deposit aggregate material in front of bridge **67** to stack aggregate in its path to lift elevation **131**. Bridge stacker **67** could be operating in both the advance stacking and retreat stacking mode, if desired. This process is described and illustrated hereinafter.

The mobile belt conveyor belt modules **87** are moved into position as needed during the extension phase of a lift stock cycle to keep up with the pace of tripper **53**, bridge stacker

6

**67**, and berm stacker **41**. Because the mobile belt conveyors are very mobile and maneuverable, it becomes more or less like adding links to a chain.

FIG. **7** illustrates the disposition of stacking system components on the area topography when the first lift cycle extension phase has reached the end of the area furthest away from the material supply point **100**. At this time, the bridge stacker **67** is rotating and translating around the end of area **112** to radially stack the end area and prepare to begin the retraction phase of the first lift cycle. The tripper **53** has been extended full length by using as many of the 250 feet long mobile belt conveyor modules **87** as required to supply aggregate from the discharge point **100** to tripper **53**. Tripper **53**, in turn, supplies the aggregate to stacking bridge **67**, which is now rotating and translating around the area **112** by moving on its track units **85** while continuing to deposit aggregate in front of it. In this way, the far end semi-circle portion of lift **131** is stacked before retraction begins.

FIG. **8** indicates the disposition of the stacking system components of the present invention on the area topography during first lift retraction. The number of mobile belt conveyor modules **87** has been reduced, because the distance between the aggregate discharge point **100** and the tripper **53** is being reduced during retraction. Tripper **53** feeds bridge stacker **67**, which continues to deposit aggregate to lift level **131**. Bridge stacker **67** continues to travel on top of the newly stacked lift level **132**. Tripper **53** is retracting on the berm that was stacked during the extension phase. No berm stacker is required during this retraction phase.

FIG. **9** illustrates the disposition of the stacking system components of the present invention on the area topography when the first lift retraction cycle is almost completed. The conveyor modules **87** have been reduced considerably because the distance between discharge point **100** and tripper **53** has been reduced to a minimum. Bridge stacker **67** continues to deposit materials in front as it translates over the newly deposited aggregate towards the lift contour **115**.

FIG. **10** illustrates the disposition of the stacking system components of the present invention on the area topography when the first lift cycle has been completed. As can be seen, the bridge stacker **67** is rotating and translating on its tracks **85** to the starting position behind contour **116** for the start of the second lift cycle. The distance between the bridge stacker **67** and the discharge point **100** is quite small, only requiring one conveyor module **87** and tripper module **53**.

FIG. **11** illustrates the disposition of the stacking system components on the area topography when the second lift cycle has begun by tapering the current lift **132** into area **122** from the second lift intersection contour **116**. An alternative approach would be to build a berm for the bridge stacker **67** to ride up on and then proceed to advance and retreat stack the second lift in a manner more specifically illustrated and described hereinafter. Aggregate is discharged at point **100** from fixed conveyor **101** onto mobile belt conveyor module **87** and then to tripper module **53**. Tripper module **53** supplies bridge stacker **67** which stacks the aggregate behind the bridge stacker **67** as it advances in this extension phase, in a typical retreat stacking method.

Bridge **67** travels on top of the previously stacked lift **131**, which is at the same grade elevation that newly stacked lift **132** is being deposited on. As bridge **67** continues outward in this extension phase of retreat stacking, a corridor **122** is being formed.

FIG. **12** illustrates the disposition of the stacking system components of the present invention on the area topography when the extension phase of the second lift is half way completed. Bridge stacker **67** is stacking material behind it,

7

as it moves forward towards the end of the stack area. Additional mobile belt conveyor modules **87** have been added as needed. The mobile belt conveyors **87** feed tripper module **53** which feeds bridge stacker **67**. The mobile belt conveyors **87** and tripper module **53** are traveling on the previously stacked heap, which is at a level lower than the second lift **132** thereby creating a corridor **122**.

FIG. **13** shows the disposition of the stacking system components of the present invention on the area topography when the second lift extension cycle has reached the end of area **112**, which is furthest away from the material supply point **100**. At this point, the maximum number of mobile belt conveyor modules **87** are being utilized. Stacker bridge **67** is, at this time, rotating and translating on its tracks **85** in order to complete the far end semicircle portion of lift **132**. Tripper module **53** receives aggregate from the last in the line of mobile belt conveyor modules **87** to feed bridge stacker **67** as it continues to stack material in the retreat mode.

FIG. **14** illustrates the stacking system modules of the present invention in the area topography when the second lift is in retraction. The bridge stacker **67** is stacking material on the heap **131** to the second lift level **132**. In retraction, the mobile belt conveyor modules **87** are being removed, as they are no longer needed. The aggregate material is supplied to the tripper module **53**. During retraction, according to the present invention, the tripper module **53** supplies the aggregate to a bridge stacker **67** and to a radial stacker **41**. Bridge stacker **67** continues to retreat and stack the aggregate while the radial stacker **41** starts to stack aggregate into corridor **122**.

FIG. **15** illustrates continued retraction of bridge stacker **67** towards the supply point **100**. Radial stacker **41** continues to fill corridor **122** as the second lift retraction cycle continues. The mobile conveyor modules **87** continue to be removed as they are no longer needed.

FIG. **16** illustrates the placement of the stacking system components on the area of topography when the second lift cycle is being completed by tapering the current lift level **132** out against the topographic slope contour **116** on the material supply side. At this point, only one mobile belt conveyor module **87** is needed to feed tripper module **53**, which feeds bridge stacker **67**. Bridge stacker **67** is shown as traveling in front of a newly stacked lift **132** and about to pass over the contour **116** on to the topographical slope nearest the material supply point **100**, thereby completing the second lift cycle.

The complete process for applying two lifts has been illustrated. It should be kept in mind that more than two lifts are contemplated and are well within the capability of the stacking system components of the present invention. Only two lifts have been illustrated because it was felt this was sufficient to show the smooth and swift stacking sequence obtainable by the present invention. Moreover, although only retreat stacking and advance stacking modes have been shown used separately, the present invention contemplates use of both modes together.

Referring now to FIG. **17**, a system and method according to the present invention of stacking aggregate on a dump is illustrated. A transfer or reclaim conveyor **139** conveys the aggregate to be dump stacked from an on/off pad **137**, for example, to a transfer point **141** where it is transferred to a conventional extendible conveyor **145**. FIG. **17** illustrates a pair of radially stacked areas **143**, each with a **220** meter radius **163** and **165**, which were radially stacked by a bridge stacker in a manner well known in the art.

8

FIG. **17** shows that after the **440** meter mark, the system and method of the present invention is utilized to finish stacking the dump site. At the end of the **440** meter mark, the end of the extendible conveyor **145** and second section **165**, the aggregate is transferred to a mobile belt conveyor module **87**. The mobile belt conveyor module transfers aggregate to a mobile tripper module **53**. Tripper module **53** supplies the aggregate to a bridge stacker **67** that stacks the aggregate to a first lift level **153** in front, in an advance stacking mode, and also stacks the aggregate behind in a retreat stack stacking mode. The bridge stacker **153** is shown advancing in the direction shown by arrows **161** in the extension phase of the dual lift stacking cycle.

The berm **151** on which tripper module **53** travels must be at the same level as the first lift **153**. This berm can be created by utilizing a berm stacker (not shown) or by truck hauled aggregate.

FIG. **18** illustrates the end of the extension cycle wherein the system of the present invention is utilizing the maximum number of mobile belt conveyor modules **87** needed to feed tripper module **53**, which feeds bridge stacker **67** that is traversing the end area in an arc to form the curved end of the first dual lift. Bridge stacker **67** continues to stack in the advance and retreat mode depositing aggregate **153** in front of its path and aggregate **159** behind it, thereby effectively creating two lifts in one pass.

FIG. **19** illustrates the bridge stacker **67** in the extraction phase of the dual lift cycle. Bridge stacker **67** continues to stack material **153** in front and material **159** in back as it travels toward the transfer point **141**. The mobile belt conveyor modules **87** that feed tripper **53** are removed as they are not needed. Tripper module **53**, besides feeding bridge stacker **67**, is now also feeding another mobile belt conveyor module **87** that in turn feeds a radial stacker **41**. Radial stacker **41** lags behind bridge stacker **67** as it fills in newly created corridor **152**.

FIG. **20** shows the position of the system components of the present invention at the completion of the stacking cycle of bridge stacker **67**. At this point, although the stack has been completed to lift level **171**, the corridor **152** still needs to be stacked. Tripper module **53** supplies the aggregate to a radial stacker **41** to stack corridor **152** as it is being retracted in direction **173**.

Once this first pad has been stacked to lift level **171**, the extendible conveyor **145** is moved from transfer point **141** to a second stack area **175** (FIG. **21**) for a second phase of stacking. A bridge tripper **53** located in this second area **175** feeds relocated bridge stacker **67**, which is again operating in both a retreat and advance stacking mode, stacking aggregate **153** in front and aggregate **159** in back at the same time. Extendible conveyor **145** was moved to the position shown from its initial position shown in phantom lines **146**. Bridge stacker **67** likewise is moved to its new starting position on the second dump stack **175**. The second dump stack **175** is completed in the same manner as described above for the first dump stack **171**.

FIG. **22** illustrates the placement of the system components on a third dump stack **185** while constructing a third dual lift. The extendible conveyor **145** has been relocated to the third dump stack area **185**. In order to get to the lift level, equipment ramps **179** were cut into the first and second dump stacks **171** and **175**. Equipment ramp **181** is cut into the third dump stack **185**. Each of these ramps are approximately at 12 degree lift or a 22.25% slope.

The mobile belt conveyor modules **87** traverse this ramp **181** from the discharge point of the extendible conveyor **145** all the way to the tripper module **53**. Tripper module **53**

9

feeds bridge stacker **67** which stacks in a retreat and advance mode. The corridor being built during the retraction phase shown will be stacked in the same manner as explained above in connection with FIG. **20**.

Although only two or three lifts have been shown for purposes of keeping the explanation as short as possible, it should be remembered that the system components of the present invention are capable of stacking many more lifts.

What is claimed is:

**1.** A method for multiple lift stacking of aggregate, the method comprising:

advance stacking a berm for conveyor system travel;  
advance stacking an extension phase in conjunction with the berm stacking, wherein aggregate is placed outward from a supply point during the extension phase; and  
advance stacking a retraction phase, wherein aggregate is placed inward toward the supply point during the retraction phase.

**2.** The method of claim **1**, further comprising:

retreat stacking a second lift extension phase creating a corridor;

retreat stacking a second lift retraction phase; and  
stacking the corridor in conjunction with stacking the retraction phase.

**3.** The method of claim **2** wherein the second lift retreat stacking phase is stacked by a bridge stacker.

**4.** The method of claim **2** wherein the second lift corridor is stacked by a radial stacker.

**5.** The method of claim **1** wherein the berm is stacked by a radial stacker.

**6.** The method of claim **1** wherein the extension phase is stacked by a bridge stacker.

**7.** A method for stacking aggregate, the method comprising:

stacking one half of a site creating a portion of a corridor;  
stacking the other half of the site creating another portion of the corridor; and  
stacking the corridor in conjunction with stacking the other half of the site.

10

**8.** The method of claim **7** wherein the one half and other half of a site is stacked by a bridge stacker.

**9.** The method of claim **7** wherein the corridor is stacked by a radial stacker.

**10.** A method for multiple lift stacking of aggregate, the method comprising:

advance and retreat stacking an extension phase creating a corridor, wherein aggregate is placed outward from a supply point during the extension phase;

advance and retreat stacking a retraction phase, wherein aggregate is placed inward toward the supply point during the retraction phase; and

stacking the corridor.

**11.** The method of claim **10** further comprising stacking a berm in conjunction with the extension phase.

**12.** The method of claim **10** wherein the corridor is stacked in conjunction with the retraction phase.

**13.** The method of claim **10** further comprising repeating the steps of claim **10** on a second adjacent site.

**14.** The method of claim **13** further comprising repeating the steps of claim **10** on a third adjacent site.

**15.** The method of claim **14** further comprising repeating the steps of claim **10** as a second lift on top of the adjacent sites.

**16.** The method of claim **15** further comprising repeating the steps of claim **10** as a third lift.

**17.** The method of claim **15** further comprising the step of building an equipment corridor to the top of the second lift.

**18.** The method of claim **10** wherein a portion of a first lift and a portion of a second lift are formed concurrently during the extension phase.

**19.** The method of claim **10** wherein a portion of a first lift and a portion of a second lift are formed concurrently during the retraction phase.

\* \* \* \* \*

UNITED STATES PATENT AND TRADEMARK OFFICE  
**CERTIFICATE OF CORRECTION**

PATENT NO. : 7,108,124 B2  
APPLICATION NO. : 10/847639  
DATED : September 19, 2006  
INVENTOR(S) : Bernard et al.

Page 1 of 1

It is certified that error appears in the above-identified patent and that said Letters Patent is hereby corrected as shown below:

Column 2, Line 29: Change "extension-half-of" to --extension half of--

Column 2, Line 30: Change "-is being-advance stacked" to --is being advance stacked--

Column 2, Line 57: Change "FIG. Sis" to --FIG. 5 is--

Column 4, Line 15: Change "it's" to --its--


Column 4, Line 60: Change "it's" to --its--

Column 5, Line 14: Change "it's" to --its--

Column 5, Line 16: Change "it's" to --its--

Signed and Sealed this

Thirteenth Day of March, 2007

A handwritten signature in black ink on a light gray dotted background. The signature reads "Jon W. Dudas" in a cursive, stylized script. The first name "Jon" is written with a large, looping initial "J". The last name "Dudas" is written with a large, looping initial "D".

JON W. DUDAS

*Director of the United States Patent and Trademark Office*