

Aug. 21, 1956




B. H. THURMAN

2,759,883

PROCESS FOR DEODORIZATION OF GLYCERIDE OILS

Filed Aug. 15, 1950

2 Sheets-Sheet 1



INVENTOR

Benjamin H. Thurman

BY *Bacon + Thomas*

ATTORNEYS

Aug. 21, 1956

B. H. THURMAN

2,759,883

PROCESS FOR DEODORIZATION OF GLYCERIDE OILS

Filed Aug. 15, 1950

2 Sheets-Sheet 2

Fig. 4.





Fig. 5.

Fig. 6.





Fig. 7.



INVENTOR

Benjamin H. Thurman

BY Bacon & Thomas

ATTORNEYS

1

2,759,883

PROCESS FOR DEODORIZATION OF GLYCERIDE OILS

Benjamin H. Thurman, New York, N. Y., assignor to Kraft Foods Company, Chicago, Ill., a corporation of Delaware

Application August 15, 1950, Serial No. 179,499

8 Claims. (Cl. 202-46)

This invention relates to the deodorization of glyceride oils, and more particularly, to an improved vaporizing step particularly applicable to high temperature continuous deodorization processes.

In my copending applications, Serial No. 744,846, filed April 30, 1947, now abandoned, Serial No. 57,114, filed October 28, 1948 and Serial No. 103,059, filed July 5, 1949, now U. S. Patent Nos. 2,621,197 and 2,621,196, respectively, which issued Dec. 4, 1954, I have disclosed processes of continuously deodorizing glyceride oils by passing the oil through a plurality of vaporizing and steam treating stages in which different oil temperatures are maintained in the various stages. In each of the vaporizing and steam treating stages the oil is maintained in a shallow body, steam is passed upwardly through the oil and a high vacuum is maintained above the oil. The passage of steam upwardly through the shallow body of oil tends to cause intense splashing and surging of the oil and a baffle structure is positioned above the shallow body of oil to not only prevent the splashing referred to but to first cause more intimate mixing of the oil and steam, and then effective separation of the steam and vapors from the oil. Efficient deodorization is obtained and higher temperatures and shorter time of treatment of the oil can be employed. It is possible to produce non-reverting oils from even such difficultly deodorizable oils as soyabean oil.

In accordance with the present invention, it has been found that a combination of two different types of vaporizing procedures in each stage of the continuous process results in even more efficient deodorization. That is to say, it has been found that first filming the oil over surfaces exposed to the high vacuum enables a considerable portion of the vaporizable impurities to be rapidly released from the oil so that the amount of vaporization required during the passage of steam upwardly through the shallow baths referred to above is reduced and that the total time of treatment required in each stage of the process is correspondingly reduced. The present process therefore contemplates first flowing a thin film of the oil downwardly over surfaces while the film of oil is exposed to the high vacuum and thereafter collecting the oil into a shallow bath while still under the high vacuum and passing steam upwardly through the oil.

It is therefore an object of the present invention to provide an improved deodorization step having particular utility in a continuous deodorization process involving a plurality of deodorizing stages.

Another object of the invention is to provide an improved deodorization step in which the oil at elevated temperatures is first exposed in the form of a thin film to a high vacuum and is then collected in a shallow bath while still under a high vacuum and steam passed upwardly through the shallow bath.

A further object of the invention is to provide improved apparatus for carrying out a deodorizing step in a continuous process involving a plurality of deodorizing stages.

2

Other objects and advantages of the invention will appear in the following detailed description thereof in which reference is made to the accompanying drawing, of which:

Fig. 1 is a vertical section through a deodorizing chamber in accordance with the present invention;

Fig. 2 is a vertical section taken on the line 2-2 of Fig. 1;

Fig. 3 is a fragmentary vertical section of a modified type of deodorizing chamber;

Fig. 4 is a vertical section taken on the line 4-4 of Fig. 3;

Fig. 5 is a view similar to Fig. 3 showing a modified apparatus;

Fig. 6 is a horizontal section taken on the line 6-6 of Fig. 5; and

Fig. 7 is a schematic diagram illustrating a process in which the deodorizing step of the present invention is particularly useful.

Referring more particularly to the drawings, the vaporizing chamber of Fig. 1 may include a housing 10 provided with a manhole 11 at one end thereof and with a plurality of domes 12 extending upwardly from the casing 10. The domes 12 in conjunction with vapor discharge pipes 13 entering through the sides of the domes and having portions extending upwardly toward the tops of the domes constitute entrainment traps. The pipes 13 are connected to a vacuum system such that steam and vapors withdrawn from the casing 10 at relatively high velocity are caused to make rapid changes in direction so as to throw out any liquid material entrained therein.

The chamber of Fig. 1 may also be provided with a steam pipe 14 positioned in the lower portion thereof and extending longitudinally of the chamber. Steam pipe 14 may be provided with a plurality of small perforations 16 preferably directed downwardly, as shown in Fig. 2. The chamber of Figs. 1 and 2 is also preferably provided with a baffle structure 17 preferably in the form of a screen made of a thin metal plate having a plurality of perforations 18 extending therethrough. The size of the perforations 18 in the screen 17 as well as the size of the perforations 16 in the pipe 14 are greatly exaggerated in the drawings, as such perforations are preferably of small size, those in the steam pipe being much smaller than those in the screen. The oil level in the vaporizing chamber is preferably maintained by an overflow pipe 19 positioned just below the baffle 17. The oil depth maintained by the over flow pipe 19 in the absence of the introduction of steam through the pipe 14 will usually range from about 10 to 20 inches, depending upon the size of the deodorizing chamber employed, oil depths in the lower portion of this range being preferred.

Steam passing upwardly through the shallow body of oil causes intense agitation of the oil below the baffle 17 and a considerable portion of the oil is carried upwardly through the perforations 18 in the baffle 17. Small bubbles of foam are thereby produced and a substantial layer of foam collects on the upper surfaces of the baffle 17. The steam contained within the bubbles is in intimate contact with the films of oil forming the walls of the bubbles such that vaporizable materials escape from the liquid films into the steam. As additional foam is produced adjacent the center portion of the baffle 17, as viewed in Fig. 2, the foam flows laterally on top of the baffle. The bubbles constantly break to liberate steam and vapors from the oil and the oil thus separated from the vapors and steam flows downwardly through perforations 18 adjacent the sides of the screen into the body of oil below the baffle 17. A constant lateral circulation of oil is therefore produced such that all of the oil is

3

substantially uniformly and repeatedly treated with steam.

Oil enters the vaporizing chamber through the pipe 21 and is first caused to flow downwardly in the form of a film over the upper surface of a conical member 22 supported within the chamber by cross-members 23 secured to the casing 10. That is to say, the pipe 21 may be connected to an upwardly extending pipe section 24 so that the oil entering through the pipe 21 is directed against a cap member 26 positioned above the conical member 22 and thereby directed downwardly as a film on the upper surfaces of the conical member 22. The conical member 22 may be provided with an upwardly turned rim 27 for collecting the oil which may be delivered downwardly through a pipe 28, to the upper surface of one end of the baffle 17. The oil flowing down the upper surface of the conical member 22 in the form of a film is exposed to the high vacuum in the vaporizing chamber and a substantial portion of the vaporizable materials are immediately released and withdrawn through the pipes 13 to the vacuum system. The oil delivered to the top of the screen 17 is therefore partially denuded of vaporizable materials but further vaporization of such materials is effected in the shallow bath of oil by steam treatment under vacuum as above described. The oil progresses gradually along the length of the vaporizing chamber while being repeatedly contacted with steam and forced upwardly through the apertures 18 in the baffle 17.

A complete process which may employ a plurality of the vaporizing chambers 9 of Figs. 1 and 2 is diagrammatically illustrated in Fig. 7. Five chambers 9 of the type illustrated in Fig. 2 may, for example, be employed although the number of such chambers may vary depending upon the precise deodorizing schedule followed and the amount of oil passed through the process. In the specific system shown in Fig. 7 the oil to be treated is first passed through a heater 29, then through a vaporizing chamber 9, through another heater 29, through another vaporizing chamber 9, etc. In the preferred process, the temperature of the oil is increased in each of the heaters 29 which may be any suitable type of indirect heat exchange devices in which the oil may be heated without danger of local overheating. For example, the thin fin tube heaters of the applications above referred to may be employed. After being passed through a plurality of vaporizing steps at progressively increasing temperatures the oil may then be passed through a plurality of vaporizing steps at progressively lowering temperatures. That is to say, the oil may then be passed through coolers 31 before each of the next vaporizing chambers in the system. Steam may be introduced into each of such vaporizing chambers through pipes 14 as above described and vapors and steam may be withdrawn from each of the deodorizing chambers through pipes 13 as also above described. As stated above, the number of vaporizing steps may be varied and also the schedule of temperatures and times of treatment may be varied depending upon the oil being treated and the extent of deodorization desired as well as the amount of oil which it is desired to pass through the system.

As a specific example illustrated in Fig. 7, the oil may be heated to a deodorizing temperature in the lower portion of the deodorization range in the first heater 29 and thereafter heated to higher temperatures in the subsequent heaters 29. An example of such temperatures particularly applicable to soyabean oil may be 400 to 450° F. in the first heater, 470 to 510° F. in the second heater and 540 to 600° F. in the third heater. The oil may then be cooled in the first cooler 31 to a temperature between 400 and 425° F. and cooled in the second cooler 31 to a temperature between 325 and 350° F., the final cooler being employed to reduce the temperature of the oil to 90 to 100° F. so that it can be exposed to the atmosphere without damage to the oil.

The above temperatures are particularly suitable for

4

a difficult oil to deodorize such as soyabean oil and will produce a non-reverting edible soyabean oil when the time of treatment in each chamber 9 is between approximately 10 and 20 minutes with a time in each heater or cooler of approximately 5 minutes so that the oil is at a temperature above 400° F. for a time between approximately 1 to 2 hours. For more easily deodorized oils the temperatures and time of treatment may be reduced, for example, the highest temperature reached may be in the neighborhood of 475 to 525° F. The number of chambers employed for deodorization at progressively higher temperatures may be varied and the number of chambers 9 employed during the cooling sequence may be correspondingly varied. In fact, it is entirely possible to initially raise the temperature of the oil in the first heater 29 to the highest temperature employed in the process and then progressively decrease the temperature employed in the remaining chambers 9 although it is preferred to employ at least one intermediate vaporizing step before reaching the highest temperature. In any event, the temperature of the oil should be decreased to approximately 320 to 350° F. before steam treatment of the oil is discontinued and it should be cooled to a temperature in the neighborhood of 90 to 100° F. before being discharged from the process into contact with the air. The vacuum employed will usually range between 1.5 and 5 mm. of mercury with a preferred range between 1.5 and 3 mm. of mercury. At the high vacuum and high temperatures mentioned, a relatively large amount of materials are vaporized from the oil and such materials may be condensed and recovered in the form of valuable by-products.

The modified treating chamber 32 shown in Figs. 3 and 4 is provided with a casing 33 which may be generally similar to the casing 10 of the chamber 9 of Figs. 1 and 2. A different type of structure for providing a film of oil exposed to the vacuum is, however, illustrated and may include an inclined plate member 34 extending laterally across one end of the deodorizing chamber in the upper portion thereof and a curved plate member 36 partially surrounding the plate member 34 and providing a lower portion 37. The plate members 34 and 36 may be supported by side walls 38 shown more clearly in Fig. 4 secured to the end wall of the casing 33. Oil enters the deodorizing chamber 32 through a pipe 39 which may be provided with a distributing nozzle 41 spreading the oil in the form of a film upon the upper surface of the plate member 34. The oil flows down the plate member 34 on to the lower portion 37 of the plate member 36. This oil is largely protected from contact with steam and vapors in the main portion of the vaporizing chamber 32 by reason of the curved plate member 36 and side walls 38 and is therefore not subject to contamination by absorbing vapors liberated from the oil in the remaining portion of the chamber. A small amount of steam which is free from vaporized impurities may be introduced through the pipe 42 so as to contact the film of oil on the members 34 and 36 and such steam carrying vapors liberated from the oil film may be discharged from the chamber through one of the domes 12 and vapor discharge pipes 13.

The vaporizing chamber 32 of Figs. 3 and 4 may be employed in a system such as shown in Fig. 7 in which the heaters 29 and coolers 31 are omitted. That is to say, the chamber 32 may be provided with a plurality of pipes 43 extending longitudinally through the lower portion of the vaporizing chamber so as to be in contact with the oil therein. These pipes may be connected to a suitable header 44 into which a suitable heating or cooling medium may be introduced through a pipe 46, it being understood that the other end of the pipe (not shown) will likewise be connected to a suitable header provided with a pipe for discharging heating or cooling medium. The pipes 43 may each be provided with a plurality of fins 47 positioned relatively close together so as to transmit heat from the pipes 43 to the oil or vice

5

versa, depending upon whether the oil is being heated or cooled. By positioning the fins 47 on each of the pipes close together and also positioning the respective pipes 43 sufficiently close together that the fins of the respective pipes are substantially in contact with each other, the fins 47 may take the place of the baffle 17 of Figs. 1 and 2 so that the baffle 17 may be omitted. In employing the vaporizing chambers 32 of Figs. 3 and 4 the oil will ordinarily be initially heated to a temperature within the deodorizing range in an external heater, for example, a heater similar to the first heater 29 of Fig. 7 although all of the heating may be done in the chambers 32. Thereafter the temperature of the oil may be increased or decreased as described above without employing heaters or coolers between the various vaporizing chambers. That is to say, an appropriate heating medium may be passed through the pipes 43 to increase the temperature of the oil progressively through a portion of the process and then a suitable cooling medium may be passed through the pipes 43 of the succeeding vaporizing chambers to progressively cool the oil. Ordinarily a final cooler 31 will be employed to reduce the temperature of the oil from approximately 325 to 350° F. down to 90 to 100° F. although again, a chamber 32 can be employed for this purpose.

The vaporizing chamber 48 of Figs. 5 and 6 may be similar to the vaporizing chambers of Figs. 3 and 4 in that it is provided with a plurality of pipes 43 having fins 47. The pipes 43 may be connected to a header 49 at one end of the vaporizing chamber and to a similar header (not shown) at the other end of the vaporizing chamber, a pipe 46 being employed to introduce the heating or cooling medium into the header 49. The vaporizing chamber 48 is shown as also being provided with a baffle 17 which may be of the same type as that described with reference to Figs. 1 and 2. The heating pipes 43 of Fig. 5, however, have the fins 47 of the respective pipes substantially in contact in the same manner as shown in Fig. 4 so that the effects of both the fins 47 and the perforations 18 in the baffle 17 may be employed to produce improved contact between the oil and steam and separation of the steam and vapors from the oil.

The vaporizing chamber 48 of Figs. 5 and 6 is shown as being provided with an external chamber 51 for subjecting films of oil to the vacuum. The chamber 51 may have a closed casing 52 which may be rectangular in horizontal section, as shown in Fig. 6, and may be further provided with a plurality of internal inclined plate members 53 extending alternately from opposite sides of the chamber 51. Oil may enter the chamber 51 through a pipe 54 provided with a distributing nozzle 56 which spreads the oil in the form of a film on the upper plate member 53 such that the oil flows down over the respective plate members 53 in the form of a thin film. A small amount of steam may be introduced into the lower portion of the chamber 51 through a pipe 57 and vapors and steam may be withdrawn from the chamber 51 through a vapor discharge pipe 58 which may be similar to the vapor discharge pipes 13. The oil may flow from the chamber 51 through a pipe 59 into the vaporizing chamber 48 so as to be discharged at one end of the upper surface of the baffle 17.

Thus in all of the modifications above described, the oil in each vaporizing step is first filmed over a surface so as to be exposed to a high vacuum in the form of a thin film, and is then subjected to treatment with steam in a shallow pool. As stated above, a relatively large portion of the vaporizable impurities are immediately released from the oil, thus reducing the amount of time required for vaporizing in the main portions of the vaporizing chambers wherein steam is passed upwardly through a shallow body of oil maintained under a high vacuum. It has been found impracticable to attempt to remove all of the vaporizable materials required for effective deodorization while the oil is in the form of a thin film upon a supporting surface and although all of the vapor-

6

izable materials which it is necessary to remove to produce effective deodorization may be removed by passing steam upwardly through shallow bodies of the oil under the conditions described above, it has been found that the total time required to remove a sufficient amount of vaporizable materials at a given temperature is substantially reduced, or conversely, the temperature required for a given time of treatment is substantially reduced by a combination of the two types of vaporization operations. By alternately filming the oil over surfaces and treating with steam in a baffled shallow pool, a better quality deodorized oil is produced. The oil is heat sensitive and damage to the oil, for example by cracking and polymerization, is decreased both by a permissible decrease in temperature and by a decreased time of treatment at such temperature.

I claim:

1. In a process of deodorizing glyceride oils, the steps which comprise, heating said oil to a deodorizing temperature, flowing said oil in the form of a thin film over a surface while said film is exposed to a high vacuum to vaporize a portion of the vaporizable materials contained in said oil, collecting the oil from said film in a shallow pool of said oil, maintaining said high vacuum above said pool while passing steam upwardly through said pool whereby said steam causes oil to be carried upwardly, and obstructing substantially the entire path of said oil and steam adjacent the surface of said pool by a baffle structure having a plurality of openings therethrough for effecting increased contact between said oil and steam and separation of steam and vapors of additional vaporizable material from said oil.

2. In a process of deodorizing glyceride oils, the steps which comprise, heating said oil to a deodorizing temperature, flowing said oil in the form of a thin film over a surface while said film is exposed to a high vacuum to vaporize a portion of the vaporizable materials contained in said oil, collecting the oil from said film in a shallow pool of said oil, maintaining said high vacuum above said pool while passing steam upwardly through said pool whereby said steam causes oil to be carried upwardly, and subdividing the path of said steam and oil being carried upwardly thereby into a plurality of paths of restricted area adjacent the surface of said pool to produce increased contact between said steam and oil and effect separation of steam and vapors of additional vaporizable materials from said oil.

3. In a process of deodorizing glyceride oils, the steps which comprise, heating said oil to a deodorizing temperature, flowing said oil in the form of a thin film over a downwardly inclined surface while said film is exposed to a high vacuum to vaporize a portion of the vaporizable materials contained in said oil, collecting the oil from said film in a shallow pool of said oil, maintaining said high vacuum above said pool while passing steam upwardly through said pool whereby said steam causes oil to be carried upwardly, subdividing the path of said steam and oil being carried upwardly thereby into a plurality of paths of restricted area adjacent the surface of said pool to produce increased contact between said steam and oil and effect separation of steam and vapors of additional vaporizable materials from said oil, and exchanging heat between said oil and a heat exchange medium in indirect heat exchange relation with said oil while said oil and steam is subdivided into said plurality of paths.

4. In a process of deodorizing glyceride oils, the steps which comprise, heating said oil to a deodorizing temperature, flowing said oil in the form of a thin film over a surface while said film is exposed to a high vacuum to vaporize a portion of the vaporizable materials contained in said oil, collecting the oil from said film in a shallow pool of said oil, maintaining said high vacuum above said pool while passing steam upwardly through said pool whereby said steam causes oil to be carried upwardly, subdividing the path of said steam and oil being carried

7

upwardly thereby into a plurality of paths of restricted area adjacent the surface of said pool to produce increased contact between said steam and oil and effect separation of steam and vapors of additional vaporizable materials from said oil, and heating said oil by indirect heat exchange with a heating medium while said oil and steam is subdivided into said plurality of paths.

5. In a process of deodorizing glyceride oils, the steps which comprise, heating said oil to a deodorizing temperature, flowing said oil in the form of a thin film over a surface while said film is exposed to a high vacuum to vaporize a portion of the vaporizable materials contained in said oil, collecting the oil from said film in a shallow pool of said oil, maintaining said high vacuum above said pool while passing steam upwardly through said pool whereby said steam causes oil to be carried upwardly, subdividing the path of said steam and oil being carried upwardly thereby into a plurality of paths of restricted area adjacent the surface of said pool to produce increased contact between said steam and oil and effect separation of steam and vapors of additional vaporizable materials from said oil, and cooling said oil by indirect heat exchange with a cooling medium while said oil and steam is subdivided into said plurality of paths.

6. In a process of deodorizing glyceride oils, the steps which comprise, heating said oil to a deodorizing temperature, flowing said oil in the form of a thin film over a surface while said film is exposed to a high vacuum to vaporize a portion of the vaporizable materials contained in said oil, collecting the oil from said film in a shallow pool of said oil, maintaining said high vacuum above said pool while passing steam upwardly through said pool whereby said steam causes oil to be carried upwardly, subdividing the path of said steam and oil being carried upwardly thereby into a plurality of paths of restricted area adjacent the surface of said pool to produce increased contact between said steam and oil and effect separation of steam and vapors of additional vaporizable materials from said oil, and varying the temperature of said oil in said shallow pool during passage of steam upwardly therethrough by indirect heat exchange with a heat exchange medium.

7. In a process of deodorizing glyceride oils, the steps which comprise, heating said oil to a deodorizing temperature, flowing said oil in the form of a thin film over a

8

surface while said film is exposed to a high vacuum to vaporize a portion of the vaporizable materials contained in said oil, collecting the oil from said film in a shallow pool of said oil, maintaining said high vacuum above said pool while passing steam upwardly through said pool whereby said steam causes oil to be carried upwardly, subdividing the path of said steam and oil being carried upwardly thereby into a plurality of paths of restricted area adjacent the surface of said pool to produce increased contact between said steam and oil and effect separation of steam and vapors of additional vaporizable materials from said oil, and heating said oil in said shallow pool during passage of steam upwardly therethrough by indirect heat exchange with a heating medium.

8. In a process of deodorizing glyceride oils, the steps which comprise, heating said oil to a deodorizing temperature, flowing said oil in the form of a thin film over a surface while said film is exposed to high vacuum to vaporize a portion of the vaporizable materials contained in said oil, collecting the oil from said film in a shallow pool of said oil, maintaining said high vacuum above said pool while passing steam upwardly through said pool whereby said steam causes oil to be carried upwardly, subdividing the path of said steam and oil being carried upwardly thereby into a plurality of paths of restricted area adjacent the surface of said pool to produce increased contact between said steam and oil and effect separation of steam and vapors of additional vaporizable materials from said oil, and cooling said oil in said shallow pool during passage of steam upwardly therethrough by indirect heat exchange with a cooling medium.

References Cited in the file of this patent

UNITED STATES PATENTS

1,059,820	Besem Felder	Apr. 22, 1913
1,351,629	Eden Born	Aug. 31, 1920
2,041,059	French	May 19, 1936
2,049,247	Burkhard	July 28, 1936
2,078,841	Fauth	Apr. 27, 1937
2,163,303	Bonotto	June 20, 1939
2,261,939	Morlock	Nov. 11, 1941
2,489,509	Straight	Nov. 29, 1949
2,621,196	Thurman	Dec. 9, 1952
2,621,197	Thurman	Dec. 9, 1952