



(19) **United States**

(12) **Patent Application Publication**

Hongo et al.

(10) **Pub. No.: US 2002/0002948 A1**

(43) **Pub. Date: Jan. 10, 2002**

(54) **PLASMA PROCESSING APPARATUS
HAVING AN EVACUATING ARRANGEMENT
TO EVACUATE GAS FROM A
GAS-INTRODUCING PART OF A PROCESS
CHAMBER**

(76) Inventors: **Toshiaki Hongo**, Amagasaki-shi (JP);
Tetsu Osawa, Tsukui-Gun (JP)

Correspondence Address:
PILLSBURY WINTHROP LLP
1600 TYSONS BOULEVARD
MCLEAN, VA 22102 (US)

(21) Appl. No.: **09/815,305**

(22) Filed: **Mar. 23, 2001**

(30) **Foreign Application Priority Data**


Mar. 24, 2000 (JP) 2000-085351

Publication Classification

(51) **Int. Cl.⁷** **C23C 16/00**
(52) **U.S. Cl.** **118/723 R; 156/345; 118/723 MW**

(57) **ABSTRACT**

A plasma processing apparatus can apply a high-quality process to an object to be processed by removing impurities from a gas-introducing part of a process chamber. The gas-introducing part connected to the process chamber so as to introduce a reactant gas into the process chamber. A first vacuum pump is connected to the process chamber so as to evacuate gas from the process chamber so that the process chamber is maintained at a negative pressure. A gas-evacuating arrangement is connected to the gas-introducing part so as to exclusively evacuate the reactant gas from the gas-introducing part. The gas-evacuating arrangement includes a second vacuum pump directly connected to the gas introducing part or a bypass passage connecting the gas-introducing par to the first vacuum pump by bypassing the process chamber.






FIG.2




FIG.3




FIG.4




FIG.5




FIG.6A




FIG.6B




FIG.7




FIG.8

200b




FIG.9




FIG.10

200d




FIG.11




FIG.12




FIG.13




FIG.14




FIG.15




FIG.16




FIG.17




FIG.18





FIG.19







FIG.21



**PLASMA PROCESSING APPARATUS HAVING AN
EVACUATING ARRANGEMENT TO EVACUATE
GAS FROM A GAS-INTRODUCING PART OF A
PROCESS CHAMBER**

BACKGROUND OF THE INVENTION

[0001] 1. Field of the Invention

[0002] The present invention relates to plasma processing apparatuses and, more particularly, to a plasma processing apparatus having a gas-introducing part, which introduces a reactant gas into a process chamber.

[0003] 2. Description of the Related Art

[0004] In recent years, a plasma processing apparatus is used to perform a film deposition process, an etching process or an ashing process in a manufacturing process of semiconductor devices since the semiconductor devices have become more densified and a finer structure. For example, in a typical microwave plasma processing apparatus, a 2.45 GHz microwave is introduced into a process chamber through a slot electrode. An object to be processed such as a semiconductor wafer or an LCD substrate is placed inside the process chamber, which is maintained under a negative pressure environment by a vacuum pump. Additionally, a reactant gas is also introduced into the process chamber so that the process gas is converted into plasma by the microwave. Thus, active radicals and ions are generated, and the radicals and ions react with the object to be processed, which achieves a film deposition process or an etching process.

[0005] The reactant gas is introduced into the process chamber through gas supply nozzles provided on a sidewall of the process chamber. Alternatively, the reactant gas is introduced into the process chamber through a dielectric plate provided under a slot electrode, which is provided on a top of the process chamber. The gas supply arrangement including such a gas supply nozzle or a dielectric plate is subjected to an evacuating process by a vacuum pump, which is provided to evacuate gas inside the process chamber.

[0006] However, there is a problem in the conventional plasma processing apparatus in that residual impurities such as a water component cannot be completely removed from inside the process chamber. A water component adhering on the inner wall of the process chamber is evaporated due to a vacuum being formed in the process chamber, and the water vapor is released to the atmosphere inside the process chamber. The water vapor is exhausted out of the process chamber by a vacuum pump. However, since the gas-introducing part provided to the process chamber has gas-introducing holes (nozzles) each having a very small diameter, a removal speed of the water component remaining inside the gas-introducing part is low. Accordingly, some amount of water component tends to remain inside the gas-introducing part of the process chamber.

[0007] The water component remaining inside the gas-introducing part may enter and close the gas-introducing holes, which interrupts the introduction of the reactant gas into the process chamber. Thus, a yield rate of the object to be processed is deteriorated. Additionally, if some of the gas-introducing holes are closed, this may deteriorate a uniform distribution of the reactant gas in the process chamber, which may result in an uneven degree of process-

ing of the object to be processed. Further, if the water component in the gas-introducing holes is ejected into the process chamber, the water component acts as an impurity, which deteriorates a high-quality process to be applied to the object to be processed.

SUMMARY OF THE INVENTION

[0008] It is a general object of the present invention to provide an improved and useful plasma processing apparatus in which the above-mentioned problems are eliminated.

[0009] A more specific object of the present invention is to provide a plasma processing apparatus which can apply a high-quality process to an object to be processed by removing impurities from a gas-introducing part of a process chamber.

[0010] In order to achieve the above-mentioned objects, there is provided according to one aspect of the present invention a plasma processing apparatus for applying a plasma process to an object to be processed, the plasma processing apparatus comprising: a process chamber in which the object to be processed is subjected to the plasma process; a gas-introducing part connected to the process chamber so as to introduce a reactant gas into the process chamber; a first vacuum pump connected to the process chamber so as to evacuate gas from the process chamber so that the process chamber is maintained at a negative pressure; and a gas-evacuating arrangement connected to the gas-introducing part so as to evacuate the reactant gas from the gas-introducing part.

[0011] According to the above-mentioned invention, the gas-evacuating arrangement is connected exclusively to the gas-introducing part so as to evacuate the reactant gas remaining in the gas-introducing part. Thus, impurities such as a water component existing in the gas-introducing part can be evacuated from the gas-introducing part together with the reactant gas being evacuated by the gas-evacuating arrangement that is exclusively provided to the gas introducing part.

[0012] In one embodiment of the present invention, the gas-evacuating arrangement may comprise a second vacuum pump connected to the gas-introducing part. That is, the second vacuum pump, which is different from the first vacuum pump, exclusively evacuates the reactant gas remaining in the gas-introducing part, which results in a rapid and efficient evacuation of the reactant gas remaining in the gas-introducing part.

[0013] In another embodiment of the present invention, the gas-evacuating arrangement may comprise a bypass passage, which connects the gas-introducing part to the first vacuum pump by bypassing the process chamber. Accordingly, the gas-introducing part can be directly connected to the first vacuum pump by the bypass passage by bypassing the process chamber, which results in a rapid and efficient evacuation of the reactant gas remaining in the gas-introducing part.

[0014] The gas-introducing part may have an annular shape and may be incorporated into a sidewall of the process chamber, and the gas-introducing part may have a plurality of circumferentially arranged nozzles through which the reactant gas is introduced into the process chamber.

[0015] Additionally, the gas-introducing part may comprise: at least one inlet port from which the reactant gas is supplied; an annular gas passage connected to the inlet port so that the reactant gas supplied from the inlet port is supplied to the plurality of nozzles by flowing through the annular gas passage; and an outlet port provided to the annular gas passage so that the gas-evacuating arrangement is connected thereto.

[0016] Alternatively, the gas-introducing part may comprise a dielectric plate and a shower plate provided on a top of the process chamber so as to introduce the reactant gas from the top of the process chamber, a gas passage being formed between the dielectric plate and the shower plate so that the reactant gas flows through the gas passage and is introduced into the process chamber through the shower plate. The dielectric plate may have an inlet port connected to the gas passage so as to supply the reactant gas to the gas passage, and the gas passage may have an outlet port to which the gas-evacuating arrangement is connected.

[0017] The plasma processing apparatus according to the present invention may further comprise a slot antenna having a plurality of slits so as to guide a microwave having a predetermined frequency which is determined by the plasma process to be applied to the object to be processed. A density of the slits may be substantially uniform in a radial direction of the slot antenna.

[0018] Additionally, there is provided according to another aspect of the present invention a gas supply ring adapted to introduce a reactant gas into a process chamber of a processing apparatus, the gas supply ring comprising: a plurality of circumferentially arranged nozzles through which the reactant gas is introduced into the process chamber; at least one inlet port from which the reactant gas is supplied; an annular gas passage connected to the inlet port so that the reactant gas supplied from the inlet port is supplied to the plurality of nozzles by flowing through the annular gas passage; and an outlet port provided to the annular gas passage so that the reactant gas is evacuated from the gas supply ring through the outlet port.

[0019] According to the above-mentioned invention, a gas-evacuating arrangement can be connected to the outlet port of the gas supply ring so as to evacuate the reactant gas remaining in the gas-introducing part. Thus, impurities such as a water component existing in the gas supply ring can be evacuated from the gas supply ring together with the reactant gas being evacuated by the gas-evacuating arrangement that is exclusively provided to the gas supply ring.

[0020] Additionally, there is provided according to another aspect of the present invention a dielectric plate adapted to be attached to a process chamber of a plasma processing apparatus, the dielectric plate comprising: a plurality of nozzles through which a reactant gas is introduced into the process chamber; at least one inlet port from which the reactant gas is supplied; a gas passage connected to the inlet port so that the reactant gas supplied from the inlet port is supplied to the plurality of nozzles by flowing through the gas passage; and an outlet port provided to the gas passage so that the reactant gas is evacuated from the gas passage through the outlet port.

[0021] According to the above-mentioned invention, a gas-evacuating arrangement can be connected to the outlet

port of the dielectric plate so as to evacuate the reactant gas remaining in the gas passage formed in the dielectric plate. Thus, impurities such as a water component existing in the gas passage can be evacuated from the gas passage together with the reactant gas being evacuated by the gas-evacuating arrangement that is exclusively provided to the dielectric plate.

[0022] Additionally, there is provided according to another aspect of the present invention a plasma processing method comprising the steps of: evacuating gas from a process chamber by a first vacuum pump connected to the process chamber; introducing a reactant gas into the process chamber through a gas-introducing part; applying a plasma process to an object placed in the process chamber by generating plasma from the reactant gas; stopping the introduction of the reactant gas into the process chamber after ending the plasma process; and evacuating the reactant gas remaining in the gas-introducing part by a second vacuum pump connected to the gas-introducing part.

[0023] Accordingly, the reactant gas remaining in the gas-introducing part can be rapidly and efficiently evacuated from the gas-introducing part by the second vacuum pump exclusive provided to the gas-introducing part.

[0024] Additionally, there is provided according to another aspect of the present invention a plasma processing method comprising the steps of: evacuating gas from a process chamber by a vacuum pump connected to the process chamber; introducing a reactant gas into the process chamber through a gas-introducing part having a plurality of nozzles; applying a plasma process to an object placed in the process chamber by generating plasma from the reactant gas; stopping the introduction of the reactant gas into the process chamber after ending the plasma process; and evacuating the reactant gas remaining in the gas-introducing part by the vacuum pump by connecting the gas-introducing part to the vacuum pump by bypassing the process chamber.

[0025] Accordingly, the reactant gas remaining in the gas-introducing part can be rapidly and efficiently evacuated from the gas-introducing part by the first vacuum pump by a bypass passage that bypasses the process chamber.

[0026] Other objects, features and advantages of the present invention will become more apparent from the following detailed description when read in conjunction of the accompanying drawings.

BRIEF DESCRIPTION OF THE DRAWINGS

[0027] FIG. 1 is an illustration of a structure of a microwave plasma processing apparatus according to a first embodiment of the present invention;

[0028] FIG. 2 is a block diagram of a temperature-adjusting device shown in FIG. 1;

[0029] FIG. 3 is a graph showing a nitrogen distribution in a direction of a depth when a multi-layered structure is formed on an object to be processed at a high temperature;

[0030] FIG. 4 is a graph showing a nitrogen distribution in a direction of a depth when a multi-layered structure is formed on an object to be processed at an appropriate temperature;

[0031] FIG. 5 is a graph showing a relationship between a defect density and a temperature of a silicon nitride film;

[0032] FIG. 6A is a plan view of a gas supply ring shown in FIG. 1; FIG. 6B is a cross-sectional view taken along a line VI-VI of FIG. 6A;

[0033] FIG. 7 is a plan view of an example of a slot antenna shown in FIG. 1;

[0034] FIG. 8 is a plan view of another example of the slot antenna shown in FIG. 1;

[0035] FIG. 9 is a plan view of a further example of the slot antenna shown in FIG. 1;

[0036] FIG. 10 is a plan view of another example of the slot antenna shown in FIG. 1;

[0037] FIG. 11 is a graph showing a relationship between a transmission power of a microwave and a thickness of a dielectric plate;

[0038] FIG. 12 is a graph showing a relationship between the thickness of the dielectric plate and an amount of isolation (sputtering rate) of the dielectric plate;

[0039] FIG. 13 is a graph shown in FIG. 11 with indication of ranges of the thickness of the dielectric plate;

[0040] FIG. 14 is a cross-sectional view of a showerhead having a gas supply arrangement;

[0041] FIG. 15 is an enlarged cross-sectional view of a part of a shower plate which part includes one of nozzles provided to the shower plate;

[0042] FIG. 16 is an enlarged cross-sectional view of an eject member provided with a nozzle passage having a single nozzle opening;

[0043] FIG. 17 is an enlarged cross-sectional view of an eject member provided with a nozzle passage having two nozzle openings;

[0044] FIG. 18 is an enlarged cross-sectional view of an eject member provided with a nozzle passage having three nozzle openings;

[0045] FIG. 19 is an illustrative plan view of a cluster tool, which is connectable to the microwave plasma processing apparatus shown in FIG. 1;

[0046] FIG. 20 is an illustration of a structure of a microwave plasma processing apparatus according to a second embodiment of the present invention; and

[0047] FIG. 21 is an illustration of an evacuating arrangement shown in FIG. 20.

BRIEF DESCRIPTION OF THE PREFERRED EMBODIMENTS

[0048] A description will now be given, with reference to FIG. 1, of a first embodiment of the present invention. FIG. 1 is an illustration of a structure of a microwave plasma processing apparatus 100 according to the first embodiment of the present invention. The first embodiment of the present invention is specifically related to an evacuating arrangement to evacuate gas from a gas-introducing part provided in a process chamber of the microwave plasma processing apparatus 100.

[0049] The microwave plasma processing apparatus 100 shown in FIG. 1 comprises: a gate valve 101 connected to a cluster tool 300; a process chamber 102 which can

accommodate a susceptor 104 on which an object to be processed such as a semiconductor wafer or an LCD substrate; a high-vacuum pump 106 connected to the process chamber; a microwave supply source 110; an antenna member 120; and gas supply systems 130 and 160. It should be noted that a control system of the plasma processing apparatus 100 is not illustrated in FIG. 1 for the sake of simplification.

[0050] The process chamber 102 is made of a conductive material such as an aluminum alloy. In the present embodiment, the process chamber 102 has a generally cylindrical shape. However the shape of the process chamber 102 is not limited to the cylindrical shape, and any shape can be adopted unless the process chamber 102 is deformed by a vacuum formed in the process chamber 102. The susceptor 104 is provided in the process chamber 102 so as to support the object W to be processed. It should be noted that an electrostatic chuck or a clamping mechanism to fix the object W on the susceptor 104 is not illustrated in FIG. 1 for the sake of simplification.

[0051] The susceptor 104 controls a temperature of the object W to be processed in the process chamber 102. The temperature of the susceptor 104 is adjusted to a value within a predetermined temperature range by a temperature-adjusting device 190. FIG. 2 is a block diagram of the temperature-adjusting device 190 shown in FIG. 1. The temperature-adjusting device 190 comprises, as shown in FIG. 2, a control unit 191, a cooling jacket 192, a sealing member 194, a temperature sensor 196 and a heater unit 198. Cooling water is supplied to the temperature control device 190 from a water source 199 such as a water line. The control unit 191 controls the temperature of the object W to fall within a predetermined temperature range. In order to achieve an easy control, it is preferable that the temperature of the cooling water supplied by the water source 199 is constant.

[0052] For example, in a case in which a silicon nitride film (Si_3N_4) is to be formed on a silicon substrate as the object W (single layer nitride film), the control unit 191 controls the heater unit 198 so that the temperature of the silicon substrate falls within a range from about 450° C. to about 500° C. If the silicon substrate is not maintained at a temperature above 450° C., a dangling bond may occur which is not preferable since a threshold voltage may vary as described later.

[0053] A consideration will be given of a case in which a silicon nitride film is formed on a silicon oxidation film (SiO_2) after the silicon oxidation film is formed on the silicon substrate. In this case, an upper portion of the silicon oxidation film is converted into the silicon nitride film by a plasma process by introducing nitrogen into the silicon oxidation film. In such a process, the control unit 191 controls the heater unit 198 so that the temperature of the silicon substrate falls within a range from about 250° C. to about 350° C.

[0054] The reason for setting the temperature of the silicon substrate below about 350° C. is explained below with reference to FIG. 3. FIG. 3 is a graph showing a nitrogen distribution in a direction of a depth when a multi-layered structure is formed on an object to be processed at a high temperature (for example, about 500° C.). As shown in FIG. 3, when the temperature of the silicon substrate is set to a

value greater than 350° C. by controlling the heater **198**, a large amount of nitrogen is introduced into an inner portion of the silicon oxidation film as well as a surface (an upper portion) of the silicon oxidation film. It can be appreciated from **FIG. 3** that nitrogen reaches a position 20 Å distant from the surface of the silicon oxidation film.

[**0055**] In such a case, nitrogen reaches a boundary between the silicon substrate and the silicon oxidation film, and a compound of silicon, oxygen and nitrogen is formed. The formation of the compound is not preferable since the compound may deteriorate a performance of a semiconductor element formed on the silicon substrate. A rate of nitrogen reaching the boundary between the silicon oxidation film and the silicon substrate depends on the size of the semiconductor element. If a gate length is in the range of 0.18 μm to 0.3 μm as in the conventional semiconductor element, an influence of the nitrogen may be negligible. However, recent semiconductor element is reduced in its size and thus the gate length is reduced to, for example, 0.13 μm or 0.10 μm. Thus, the influence of the nitrogen will not be negligible.

[**0056**] On the other hand, if the temperature of the silicon substrate controlled by the heater unit **198** is set to below 350° C., the nitrogen is distributed to an inner portion of the silicon oxidation film as well as the surface (an upper portion) of the silicon oxidation film. **FIG. 4** is a graph showing a nitrogen distribution in a direction of a depth when a multi-layered structure is formed on an object to be processed at an appropriate temperature (for example, about 350° C.). It can be appreciated from **FIG. 4** that the depth of the nitrogen is within an allowable range (less than 10 Å), and, therefore, the above-mentioned problem can be eliminated by setting the temperature of the silicon substrate below 350° C.

[**0057**] The reason for setting the temperature of the susceptor **104** greater than about 250° C. is explained below. A CV characteristic which indicates a relationship between a gate voltage V and a gate capacitance C is often used as an index representing an operational characteristic of the object W to be processed (semiconductor element). The CV characteristic has a hysteresis at a time when the gate voltage V is applied and released. If the hysteresis width is large, threshold voltages (voltage at which a semiconductor element turns on and off) of the gate voltage V is varied, which deteriorates reliability. Accordingly, the hysteresis width is preferably maintained within a predetermined voltage range such as less than 0.02 V. This may be applied to a layered structure. The hysteresis width becomes larger as the number of defects (dangling bond) of the silicon nitride film increases. **FIG. 5** is a graph showing a relationship between defect density of the silicon nitride film and the temperature of the susceptor **104**. In **FIG. 5**, a dotted line indicates an allowable defect density. In order to maintain the hysteresis width, the defect density of the silicon nitride film must be maintained as indicated by a dotted line in **FIG. 5**. The inventors found that the allowable defect density is about 250° C. as interpreted from **FIG. 5**.

[**0058**] The control unit **191** controls the temperature of the susceptor **104** to be about 450° C. for a CVD process and about at least 80° C. for an etching process. In any case, the object W to be processed is maintained at a temperature at which a water component does not adhere to the object W.

[**0059**] The cooling jacket **192** is provided for supplying a cooling water so as to cool the object W to be processed during a plasma process. The cooling jacket **192** is made of a selected material such as a stainless steel which has high heat conductivity and an easy machinability to form a water passage **193**. The water passage **193** extends in longitudinal and transverse directions of the cooling jacket **192** having a square shape, and the sealing members **194** are screwed into openings of the water passage **193**. However, the shape of the cooling jacket **192** is not limited to the square shape, and the cooling jacket **192** and the water passage can be formed with any shape. It should be noted that a coolant such as alcohol, gulden or fluorocarbon may be used instead of the cooling water. The temperature sensor **196** can be a known sensor such as a PTC thermister an infrared sensor or a thermocouple. The temperature sensor may either be connected or not connected to the water passage **193**.

[**0060**] The heater unit **198** is comprised of a heater wire wound on a water pipe connected to the water passage of the cooling jacket **192**. By controlling an electric current supplied to the heater wire, the temperature of the cooling water flowing through the water passage **193** of the cooling jacket **192** can be adjusted. Since the cooling jacket **192** has high heat conductivity, the temperature of the cooling jacket is substantially equal to the temperature of the cooling water flowing through the water passage **193**.

[**0061**] The susceptor **104** is movable in a vertical direction inside the process chamber. A vertically moving system of the susceptor **104** comprises a vertically moving member, a bellows and a vertically moving mechanism. The vertically moving system can be achieved by any known structure in this art. The susceptor **104** is moved up and down between a home position and a process position. When the plasma processing apparatus **100** is not in operation or a waiting state, the susceptor **104** is located at the home position. The object W to be processed is transferred to the susceptor **104** at the home position from the cluster tool **300** via the gate valve **101**, and vice versa. A transfer position other than the home position may be defined so as to communicate with the gate valve **101**. A vertical travel of the susceptor **104** can be controlled by a controller of the vertically moving mechanism or a control unit of the plasma processing apparatus **100**, and the susceptor can be observed through a view port (not shown in the figure) provided to the process chamber **102**.

[**0062**] The susceptor **104** is connected to a lifter pin vertically moving system (not shown in the figure). The lifter pin vertically moving system comprises a vertically moving member, a bellows and a vertically moving device. The vertically moving system can be achieved by any known structure in this art. The vertically moving member is made of aluminum, for example, and is connected to three lifter pins, which vertically extend from vertices of an equilateral triangle. The lifter pins are vertically movable by penetrating the susceptor **104** so as to vertically move the object W to be processed placed on the susceptor **104**. The object W is moved in the vertical direction at a time when the object W is put into the process chamber **102** from the cluster tool **300**, and at a time when the object W after processing is taken out of the process chamber **102** and transferred to the cluster tool **300**. The vertically moving mechanism may be arranged to allow the vertical movement of the lifter pins alone when the susceptor **104** is at a predetermined position such as the

home position. Additionally, a vertical travel of the lifter pins can be controlled by a controller of the vertically moving mechanism or a control unit of the plasma processing apparatus **100**, and the movement of the lifter pins can be observed through a view port (not shown in the figure) provided to the process chamber **102**.

[0063] A baffle plate may be provided to the susceptor **104** if necessary. The baffle plate may be vertically moveable together with the susceptor **104**, or may be brought in engagement with the susceptor **104** at the process position. The baffle plate separates a process space in which the object **W** to be processed is placed from an exhaust space underneath the process space. The baffle plate mainly serves to maintain a potential of the process space (that is, maintain a microwave in the process space) and maintain a predetermined degree of vacuum (for example, 50 mTorr). The baffle plate is formed of pure aluminum, and has a hollow disk-like shape. The baffle plate has a thickness of 2 mm, and has many through holes arranged at random. Each of the through holes has a diameter of about 2 mm so that an open area ratio of the baffle plate is more than 50%. It should be noted that the baffle plate could have a meshed structure. Additionally, the baffle plate may have a function to prevent a reverse flow from the exhaust space to the process space or a function to create a pressure difference between the process space and the exhaust space.

[0064] The susceptor **104** is connected to a bias radio frequency power supply **282** and a matching box (matching circuit) **284**, and constitutes an ion-plating device together with an antenna member **120**. The bias radio frequency power source **282** applies a negative direct current bias (for example, a 13.5 MHz radio frequency) to the object **W** to be processed. The matching box **284** is provided to eliminate influences of a stray capacitance and a stray inductance of an electrode in the process chamber **102**. The matching box, for example, uses a variable condenser arranged parallel and serial to a load. As a result, ions are accelerated by the bias voltage toward the object **W** to be processed, resulting in promotion of the process by ions. The energy of the ions is determined by the bias voltage, and the bias voltage can be controlled by the radio frequency power. The frequency of the radio frequency applied by the power source **283** is adjustable in response to slits **210** of a slot electrode **200**.

[0065] The inside of the process chamber **102** is maintained at a predetermined negative pressure by a high-vacuum pump **106**. The high-vacuum pump **106** uniformly evacuate gas from the process chamber **102** so as to maintain the plasma density uniform so that the plasma is prevented from being locally concentrated to prevent a local change in a depth of a processed portion of the object **W**. Although the high-vacuum pump **106** is provided at a corner of a bottom of the process chamber **102** in FIG. 1, a plurality of high-vacuum pumps may be provided to the process chamber **102**, and the position of the high-vacuum pump **106** is not limited to the position indicated in FIG. 1. The high-vacuum pump **106** is constituted, for example, by a turbomolecular pump (TMP), and is connected to the process chamber **102** via a pressure adjust valve (not shown in the figure). The pressure adjust valve is a known valve such as a so-called conductance valve, gate valve or high-vacuum valve. The pressure adjust valve is closed when the apparatus **100** is not in operation, and is open in operation so as

to maintain the process chamber **102** at a predetermined pressure (for example, 0.1 to 10 mTorr) created by the high-vacuum pump **106**.

[0066] It should be noted that, in the present embodiment shown in FIG. 1, the high-vacuum pump **106** is directly connected to the process chamber. The term "directly connected" means that the high-vacuum pump is connected to the process chamber without a connecting member between the high-vacuum pump **106** and the process chamber **102**. However, a pressure adjust valve can be provided between the high-vacuum pump **106** and the process chamber **102**.

[0067] Gas supply rings **140** and **170** made of quartz pipes are provided to a sidewall of the process chamber **102**. The gas supply ring **140** is connected to a reactant gas supply system **130**. The gas supply ring **170** is connected to a discharge gas supply system **170**. The gas supply system **130** comprises a gas supply source **131**, a valve **132**, a mass flow controller **134** and a gas supply line **136** interconnecting the aforementioned parts. Similarly, the gas supply system **140** comprises a gas supply source **161**, a valve **162**, a mass flow controller **164** and a gas supply line **166** interconnecting the aforementioned parts.

[0068] For example, in order to deposit a silicon nitride film, the gas supply source **131** supplies a reactant gas (or material gas) such as NH_3 or SiH_4 , and the gas supply source supplies a discharge gas such as a mixture gas produced by adding N_2 and H_2 to at least one of neon, xenon, argon, helium, radon and krypton. However, the gas supplied to the process chamber **102** is not limited to the above-mentioned gasses, and Cl_2 , HCl , HF , BF_3 , SiF_3 , GeH_3 , AsH_3 , PH_3 , C_2H_2 , C_3H_8 , SF_6 , Cl_2 , CCl_2F_2 , CF_4 , H_2S , CCl_4 , BCl_3 , PCl_3 or SiCl_4CO may be supplied.

[0069] The gas supply system **160** may be omitted by replacing the gas supply source **131** with a gas supply source, which can supply a mixture gases supplied by the gas supply sources **131** and **161**. The valves **132** and **162** are open during a plasma processing period of the object **W** to be processed, and is closed during a period other than the plasma processing period.

[0070] Each of the mass flow controllers **134** and **164** comprises a bridge circuit, an amplifying circuit, a comparator circuit and a flow control valve, and controls a gas flow. That is, each of the mass flow controllers **134** and **164** controls the flow control valve based on a measurement of flow by detecting a transfer of heat from upstream to downstream due to the gas flow. However, any known structure other than the above-mentioned structure may be used for the mass flow controllers **134** and **164**.

[0071] Each of the gas supply passages **136** and **166** is formed of a seamless pipe and a bite type coupling or a gasket coupling is used so that impurities are prevented from entering the system through the gas supply passages **136** and **166**. Additionally, in order to prevent generation of particles due to dirt or corrosion inside the pipes, the gas supply passages **136** and **166** may be coated by an insulating material such as PTFE, PFA, polyimide or PBI. Additionally, an electropolishing may be applied to an inner surface of the pipes forming the gas supply lines **136** and **166**. Further, a dust particle trap filter may be provided to the gas supply lines **136** and **166**.

[0072] FIG. 6A is a plan view of a gas supply ring **140**, and FIG. 6B is a cross-sectional view taken along a line

VI-VI of FIG. 6A. As shown in FIGS. 6A and 6B, the gas supply ring 140 comprises: a ring-like housing or main part 146 which is made of quartz and attached to the sidewall of the process chamber 102; an inlet port 141 connected to the gas supply passage 136; an annular gas passage 142 connected to the inlet port 141; a plurality of gas supply nozzles 143 connected to the gas passage 142; an outlet port 144 connected to the gas passage 142 and a gas exhaust passage 138; and a nozzle part 145 which is made of quartz and fixed to the sidewall of the process chamber 102.

[0073] The gas supply nozzles 143 arranged at an equal interval in a circumferential direction contribute to form an even gas flow within the process chamber 102. The gas-introducing means is not limited the gas supply ring 140, and a radial flow type or a showerhead type may be applied as described later.

[0074] Gas inside the gas supply ring 140 can be evacuated through the outlet port 144 connected to the gas exhaust passage 138. Since each of the gas supply nozzles has a diameter of about 0.1 mm, a water component remaining inside the gas supply ring 140 cannot be effectively removed by evacuating the gas by the high-vacuum pump 106 connected to the process chamber 102 through the gas supply nozzles. Accordingly, the gas supply ring 140 according to the present embodiment effectively remove the remainder such as a water component within the gas passage 142 and the gas supply nozzles 143 through the outlet port 144 having an opening diameter much greater than that of the gas supply nozzles 143.

[0075] Similar to the gas supply nozzles 143, the gas supply nozzles 173 are provided to the gas supply ring 170, which has the same structure as the gas supply ring 140. Accordingly, the gas supply ring 170 comprises a main part 176; an inlet port 171, an annular gas passage 172, a plurality of gas supply nozzles 173, an outlet port 174 and a nozzle part 175. Similar to the gas supply ring 140, gas inside the gas supply ring 170 can be evacuated through the outlet port 174 connected to the gas exhaust passage 168. Since each of the gas supply nozzles has a diameter of about 0.1 mm, a water component remaining inside the gas supply ring 170 cannot be effectively removed by evacuating the gas by the high-vacuum pump 106 connected to the process chamber 102 through the gas supply nozzles. Accordingly, the gas supply ring 170 according to the present embodiment effectively remove the remainder such as a water component within the gas passage 172 and the gas supply nozzles 173 through the outlet port 174 having an opening diameter much greater than that of the gas supply nozzles 173.

[0076] In the present embodiment, a vacuum pump 152 is connected to the gas exhaust passage 138, which is connected to the outlet port 144 of the gas supply ring 140, via a pressure adjust valve 151. Similarly, a vacuum pump 154 is connected to the gas exhaust passage 168, which is connected to the outlet port 164 of the gas supply ring 170, via a pressure adjust valve 153. Each of the vacuum pumps 152 and 154 can be a turbo-molecular pump, a sputter ion pump, a getter pump, a sorption pump or a cryopump.

[0077] The pressure adjust pumps 151 and 153 are closed when the respective valves 132 and 162 are open, and are opened when the respective valves 132 and 162 are closed. As a result, when a plasma process is performed by opening the valves 132 and 162, the vacuum pumps 152 and 154 are

disconnected from the respective gas supply system by the pressure control valve 151 and 153 being closed so that the reactant gas and the discharge gas are introduced into the process chamber 102. The vacuum pumps 152 and 154 are connected to the gas supply system by the pressure adjust valves 151 and 153 being open after completion of the plasma process. That is, the vacuum pumps 152 and 154 can evacuate gas from the respective gas supply rings 140 and 170 during a period other than a period when the plasma process is performed. Specifically, the vacuum pumps 152 and 154 can be operated during a period for carrying the object W into the process chamber or taking out of the process chamber 102 or a period for moving the susceptor 104. Accordingly, the vacuum pumps 152 and 154 can evacuate the remaining gas from the gas supply rings 140 and 170 to an extent that an influence of the remaining gas is negligible. Thereby, the gas supply nozzles 143 and 173 are prevented from being closed by impurities such as a water component remaining in the gas supply rings, thereby preventing an uneven introduction of the gas from the gas supply rings 140 and 170. Additionally, the object W to be processed is prevented from being contaminated by impurities discharged from the gas supply rings 140 and 170. Thus, the vacuum pumps 152 and 154 enables a high-quality plasma process being applied to the object W to be processed.

[0078] In the present embodiment, a microwave is generated by a microwave generator 110. The microwave generator 110 comprises a magnetron, which can generate, for example, a 2.45-GHz microwave (for example, 5 kW). The microwave generated by the microwave generator 110 is converted into a TM mode, a TE mode or a TEM mode by a mode converter 112. It should be noted that, in FIG. 1, an isolator for absorbing a microwave returning to the microwave generator 110 and a stub tuner for load matching are not shown for the sake of simplification of the figure.

[0079] The antenna member 120 comprises a temperature control plate 122, an antenna-accommodating member 123 and a dielectric plate 230. The temperature control plate 122 is connected to a temperature control unit 121. The antenna-accommodating member 123 accommodates a slow-wave member 124 and a slot electrode 200 that contacts the slow-wave member 124. The dielectric plate 230 is positioned under the slot electrode 200. The antenna-accommodating member 123 is made of a material having high heat conductivity such as stainless steel. A temperature of the antenna accommodating member 123 can be controlled nearly equal to the temperature of the temperature control plate 122.

[0080] The slow-wave member 124 is made of a material having a predetermined permittivity to reduce the wavelength of the microwave transmitted therethrough. In order to make the plasma density in the process chamber 102 uniform, many slits must be formed in the slot electrode 200. Thus, the slow-wave member 124 has a function to enable the formation of many slits in the slot electrode 200. Ceramics such as SiN or AlN can be used for the slow-wave member 124. For example, the specific permittivity ϵ_r of AlN is about 9 and, thus, the wavelength reducing rate n is 0.33 ($n=1/(\epsilon_r)^{1/2}=0.33$). Accordingly, the transmission rate of the microwave after passing through the slow-wave member 124 becomes 0.33 times the original transmission rate, and, thus, the wavelength also becomes 0.33 times the original wavelength. Accordingly, a distance between adjacent slits

210 of the slot electrode **200** can be reduced, resulting in a larger number of slits **210** being provided in the slot electrode **200**. The slot electrode **200** is formed of a copper plate having a circular shape whose diameter is, for example, about 50 cm and thickness is less than 1 mm. The slot electrode **200** is fixed to the slow-wave member **124** by screws.

[0081] The slot electrode **200** may be referred to as a radial inline slot antenna (RLSA) or an ultra high efficiency flat antenna. The present invention is not limited to such an antenna, and other type antenna such as a single layer waveguide flat antenna or a dielectric substrate parallel slot array may be used.

[0082] FIGS. 7, 8, 9 and 10 are plan views of examples of the slot antenna **200** shown in FIG. 1. Hereinafter, the reference numerals such as **200** generally represent all the reference numerals having a suffix such as **200a**, **200b**, **200c** and **200d**. Any one of the slot electrodes **200a**, **200b**, **200c** and **200d** can be used in the plasma processing apparatus **100** shown in FIG. 1.

[0083] The slot electrode **200** has a plurality of T-slits **210** consisting of a pairs of slits **212** and **214** arranged in a T-shape with a predetermined distance therebetween. The T-slits **210** are arranged in a plurality of areas or sections defined by virtually dividing the surface of the slot electrode **200** on a one-to-one basis. In the slot electrode **200a** shown in FIG. 7, each of the virtually divided areas has a hexagonal shape. In the slot electrodes **200b**, **200c** and **200d** shown in FIGS. 8, 9 and 10, each of the virtually divided areas has a square shape. It should be noted that each of the T-slits **210d** of the slot electrode **200d** shown in FIG. 10 is a variation of the T-slit **210**, and the actual shape formed by the slits **211d** and **214d** is similar to V-shape.

[0084] The T-slits **210** are arranged on the surface of the slot electrode **200** so that the density of the T-slits **210** is substantially uniform over the entire surface of the electrode **200**. This is to prevent an isolation of the material forming the dielectric plate **230** so as to prevent the isolated material as impurities from being mixed to a reactant gas. Since the slot electrode **200** can provide a substantially uniform distribution of ion energy to the dielectric plate **230**, the dielectric plate **230** is prevented from being isolated which results in a high-quality plasma process being achieved.

[0085] As mentioned above, each T-slit **210** comprises a pair of slits **212** and **214** forming a T-shape with a predetermined distance therebetween. More specifically, each of the slits **212** and **214** has a length **L1** which is in the range of about one half of the wavelength λ_0 of the microwave to 2.5 times a free space wavelength. The width of each of the slits **212** and **214** is about 1 mm. A distance **L2** between two adjacent pairs of slits along a radial direction is approximately equal to the wavelength λ_0 . That is, the length **L1** of each of the slits **212** and **214** is set to satisfy the following relationship.

$$(\lambda_0/\sqrt{2 \times 1/\epsilon_r}) \leq L1 \leq (\lambda_0 \times 2.5)$$

[0086] By setting each of the slits **212** and **214** to the above-mentioned structure, a uniformly distributed microwave can be achieved in the process chamber **102**.

[0087] Each of the slits **212** and **214** is slanted with respect to a radial line connecting the center of the slot electrode **200**

and an intersecting point between longitudinal axes of the slits **214** and **214**. The size of the T-slits **210** becomes larger as a distance from the center of the slot electrode **200** increases. For example, if the distance from the center is twice, the size of each of the slits **212** and **214** is increased to about 1.2 to 2 times.

[0088] It should be noted that the shape of the slits **210** and their arrangement are not limited to that shown in FIGS. 7, 8, 9 and 10 as long as the density of the slits can be uniform over the surface of the slot electrode **200**. That is, the configuration of the pair of slits **212** and **214** is not limited to the above-mentioned shape, and, for example, L-shaped slits may be used for the slot electrode **200**. Additionally, the shape of each of the virtually divided areas is not limited to the hexagonal shape or the square shape, and an arbitrary shape such as a triangular shape may be adopted. Accordingly, the virtually divided areas may be different in their shape and size. Further, the slits **210** may be arranged along a plurality of concentric circles or a spiral although the density of the slits may not be uniform.

[0089] A radiation element having a width of a few millimeters may be provided on the periphery of the slot electrode **200** so as to prevent reflection of the microwave transmitted toward the periphery of the slot electrode **200**. The radiation element provided for increasing an antenna efficiency of the slot electrode **200**.

[0090] The temperature control plate **122** serves to control the temperature change of the antenna-accommodating member **123** and component parts near the antenna-accommodating member **123** to fall within a predetermined range. A temperature sensor and a heater unit (both not shown in the figure) are connected to the temperature control plate **122**. The temperature control unit **121** controls a temperature of the temperature control plate **122** to be a predetermined temperature by introducing a cooling water or a coolant such as alcohol, gulden or flon into the temperature control plate **122**. The temperature control plate **122** is made of a material such as stainless steel, which has high heat conductivity and can be machined to form a fluid passage for the cooling water therein.

[0091] The temperature control plate **122** contacts the antenna-accommodating member **123**, and each of the antenna accommodating member **123** and the slow-wave member **124** has high heat conductivity. Accordingly, the temperature of each of the slow-wave member **124** and the slot electrode **200** can be controlled by merely controlling the temperature of the temperature control plate **122**. The temperature of each of the slow-wave member **124** and the slot electrode **200** is increased due to energy absorption when the microwave of the microwave generator **110** is supplied thereto for a long period of time. As a result, each of the slow-wave member **124** and the slot electrode **200** may deform due to thermal expansion.

[0092] For example, if the slot electrode **200** thermally deforms, the length of each slit is changed, which results in a decrease in the plasma density or localization of the plasma in the process chamber **102**. The decrease in the plasma density may slow down a plasma processing speed such as an etching rate or a film deposition rate. As a result, if the plasma processing is controlled based on a processing time, there may be a case in which a desired result of the plasma processing (such as plasma etching depth or plasma depo-

sition thickness) cannot be obtained when the plasma processing is applied for a predetermined time period (for example, two minutes), that is, for example, if the object W is processed for a predetermined time (for example, two minutes) and thereafter removed from the process chamber 102. Additionally, if the plasma density in the process chamber 102 is localized, the magnitude of plasma processing applied to the semiconductor wafer may vary. As mentioned above, if a deformation occurs in the slot electrode 200, the quality of plasma processing may deteriorate.

[0093] Further, if the temperature control plate 122 is not provided, the slot electrode 200 may warp since the materials of the slow-wave member 124 and the slot electrode 200 are different from each other and both members are fixed to each other by screws. In such a case, the quality of plasma processing may deteriorate for a reason similar to the above-mentioned reason.

[0094] A dielectric plate 230 is provided between the slot electrode 200 and the process chamber 102 so as to close the top opening of the process chamber 102. The slot electrode 200 is tightly joined to the surface of the dielectric plate 230 by brazing. Alternatively, the slot electrode 200 can be formed by a copper plate applied to the surface of the dielectric plate 230.

[0095] It should be noted that the function of the temperature control plate 122 may be provided to the dielectric plate 230. That is, the temperature of the dielectric plate 230 can be controlled by integrally forming a temperature control plate with the dielectric plate 230, which temperature control plate has a coolant passage near the side of the dielectric plate 230. By controlling the temperature of the dielectric plate 230, the temperature of the slow-wave member 124 and the slot electrode 200 can be controlled. The dielectric plate 230 is mounted to the process chamber 102 with an O-ring provided therebetween. Accordingly, the temperature of the dielectric plate 230 can be controlled by controlling a temperature of the O-ring, and, thereby controlling the temperature of the slow-wave member 124 and the slot electrode 200.

[0096] The dielectric plate 230 is made of a dielectric material such as aluminum nitride (AlN). The dielectric plate 230 prevents the slot electrode 200 from being deformed due to a negative pressure generated in the process chamber 102. Additionally, the dielectric plate 230 prevents the slot electrode 200 from being exposed to the atmosphere inside the process chamber 102 so that the environment inside the process chamber 102 is prevented from being contaminated by copper. If necessary, the dielectric plate 230 may be formed of a dielectric material having a low heat conductivity so as to prevent the slot electrode 200 from being influenced by heat from the process chamber 102.

[0097] In the present embodiment, the thickness of the dielectric plate 230 is greater than 0.5 times the wavelength of the microwave in the dielectric plate 230 and smaller than 0.75 times the wavelength of the microwave in the dielectric plate 230. Preferably, the thickness is in the range of 0.6 to 0.7 times the wavelength of the microwave in the dielectric plate 230. The 2.45 GHz microwave has a wavelength of about 122.5 mm in a vacuum. If the dielectric plate 230 is made of aluminum nitride (AlN), the wavelength reducing rate n is equal to 0.33 since the specific permittivity ϵ_r is about 9 as mentioned above. Accordingly, the wavelength of

the microwave in the dielectric plate 230 is about 40.8 mm. Thus, if the dielectric plate 230 is formed of AlN, the thickness of the dielectric plate 230 is preferably greater than about 20.4 mm and smaller than about 30.6 mm, and, more preferably within a range from about 24.5 mm to about 28.6 mm. In general, the thickness H of the dielectric plate 230 preferably satisfies a relationship $0.5\lambda < H < 0.75\lambda$, and, more preferably, $0.6\lambda \leq H \leq 0.7\lambda$. The wavelength λ of the microwave in the dielectric material 230 satisfies $\lambda = \lambda_0/n$, where λ_0 is a wavelength of the microwave in the vacuum and n is a wavelength reducing rate ($n = 1/\epsilon_r^{1/2}$).

[0098] When the thickness of the dielectric plate 230 is 0.5 times the wavelength of the microwave in the dielectric plate 230, a standing wave is generated as a resultant wave of a synthesis of a progressing wave traveling along the front surface of the dielectric plate 230 and a regressive wave reflected by the back surface of the dielectric plate 230. Thereby, the reflection is maximized and a power of the microwave transmitted to the process chamber 102 is minimized as shown in FIG. 11, which is a graph showing a relationship between a transmission power of the microwave and the thickness of the dielectric plate. In such a case, generation of plasma is insufficient, and, thereby a desired process speed cannot be achieved.

[0099] On the other hand, when thickness of the dielectric plate 230 is 0.75 times the wavelength of the microwave in the dielectric plate 230, the transmission power of the microwave is maximized but ion energy in the plasma is also maximized. The inventors found that the dielectric material of the dielectric plate 230 isolates by a plasma ion energy applied by transmission of a microwave isolates the material of the dielectric plate 230 as shown in FIG. 12. FIG. 12 is a graph showing a relationship between the thickness of the dielectric plate 230 and an amount of isolation (sputtering rate) of the dielectric plate 230. If the material of the dielectric plate 230 isolates, the material enters the object W to be processed as impurities, thereby deteriorating a high-quality plasma process.

[0100] Accordingly in the present embodiment, the thickness H of the dielectric plate 230 is set to a value ranging from 0.3λ to 0.4λ ($0.3\lambda \leq H \leq 0.4\lambda$) or a value ranging from 0.6λ to 0.7λ ($0.6\lambda \leq H \leq 0.7\lambda$) as shown in FIG. 13. The thickness H of the dielectric plates 230 may be set to a value ranging from 0.8λ to 0.9λ ($0.8\lambda \leq H \leq 0.9\lambda$) or a value ranging from 1.1λ to 1.2λ ($1.1\lambda \leq H \leq 1.2\lambda$) although the thickness H of the dielectric plates 230 is increased. In more general form, the thickness H of the dielectric plate 230 is set to a value ranging from $(0.1+0.5N)\lambda$ to $(0.2+0.5N)\lambda$ or a value ranging from $(0.6+0.5N)\lambda$ to $(0.7+0.5N)\lambda$, where N is an integer. In other words, the thickness H of the dielectric plate 230 satisfies a relationship $(0.1+0.5N)\lambda \leq H \leq (0.2+0.5N)\lambda$ or $(0.6+0.5N)\lambda \leq H \leq (0.7+0.5N)\lambda$. Considering a mechanical strength of the dielectric plate 230, the thickness H of the dielectric plate 230 is preferably set to a value ranging from 0.6λ to 0.7λ . However, for example, if the dielectric plate 230 is made of quartz having a specific permittivity of 3.8, a value ranging from 0.3λ to 0.4λ or a value ranging from 0.1λ to 0.2λ may be used. Additionally, the above-mentioned relationship in general form is applicable to a wave used for generating plasma other than a microwave.

[0101] Since the gas supply systems 130 and 160 are arranged to supply a reactant gas and a discharge gas from

the nozzles 143 and 173, respectively, the gasses may traverse the surface of the object W to be processed. Accordingly, a uniform plasma density cannot be achieved even if the nozzles 143 and 173 are arranged in symmetric positions with respect to the center of the susceptor 104. In order to solve such a problem, it is considered to provide a showerhead structure made of glass above the susceptor 104. A description will be given, with reference to FIG. 14, of such a showerhead structure. FIG. 14 is an illustrative cross-sectional view of a showerhead having a gas supply arrangement.

[0102] The showerhead shown in FIG. 14 comprises a dielectric plate 240 and a shower plate 250. It should be noted that the dielectric plate 240 and the shower plate 250 may be integrally formed with each other by a dielectric material. The dielectric plate 240 is formed of an aluminum nitride (AlN) plate having a thickness of 30 mm. The shower plate 250 is attached to a bottom surface of the dielectric plate 240. The dielectric plate 240 has an inlet port 241, a gas passage 242 and an outlet port 244.

[0103] The gas supply passage 136 of the gas supply system 130 is connected to the inlet port of the dielectric plate 240. The gas exhaust passage 138 is connected to the outlet port 144 of the dielectric plate 240. Although the dielectric plate 240 shown in FIG. 14 is applied to the gas supply system 130, a mixture of the gasses supplied by the gas supply systems 130 and 160 may be supplied to the inlet port 141 of the dielectric plate 240. A plurality of the inlet ports 141 may be provided to the dielectric plate 241 so that a gas supplied through the inlet ports 241 is uniformly introduced into the process chamber through the showerhead. Additionally, a part of the inlet ports 241 may be connected to the gas supply passage 136, and the rest of the inlet ports 241 may be connected to the gas supply passage 166.

[0104] Alternatively, the gas supply system 160 may be provided to the sidewall of the process chamber as shown in FIG. 1. This is because the discharge gas such as argon is not easily decomposed as compared to silane or methane, and, thus, the uniformity of the plasma density is not so deteriorated if the discharge gas is introduced into the process chamber 102 from the side.

[0105] As shown in FIG. 14, the outlet port 144 of the dielectric plate 240 is connected to the gas exhaust passage 138, which is connected to the vacuum pump 152 via the pressure adjust valve 151. The function of the vacuum pump 151 is the same as that described above, and a description thereof will be omitted.

[0106] A description will now be given, with reference to FIG. 15, of a structure of the shower plate 250 shown in FIG. 14. FIG. 15 is an enlarged cross-sectional view of a part of the shower plate 250 which part includes one of nozzles 253 provided to the shower plate 250. As shown in FIG. 15, the dielectric plate 240 has recessed portions 246 at positions corresponding to the nozzles 253 of the shower plate 250.

[0107] The shower plate 250 is made of an aluminum nitride (AlN) plate having a thickness of about 6 mm. The shower plate 250 has a plurality of nozzles 253 positioned in a predetermined uniform arrangement. As shown in FIG. 15, each of the nozzles 253 is provided with an eject member 260. The eject member 260 is constituted by a screw (262 and 264) and a nut 266.

[0108] The screw head 262 has a height of about 2 mm. A pair of eject passages 269 are formed in the screw head 262. Each of the eject passages 269 extends from the center of the screw head 262 in a direction inclined 45 degrees with respect to the bottom surface 256 of the shower plate 250. An end of each of the eject passages 269 is connected to a nozzle passage 268 formed in the screw part 254. Each of the eject passages 269 has a diameter of about 0.1 mm. The eject passages 269 are inclined so as to achieve a uniform introduction of the reaction gas. Accordingly, the number of the eject passages 269 and their angle with respect to the shower plate 250 may be changed so as to achieve uniform distribution of the reaction gas. It should be noted that, according to experiments conducted by the inventors, uniform distribution of the reaction gas was not achieved by a single ejecting passage extending in a direction perpendicular to the surface 256 of the shower plate 250. It was found that the eject passage 269 is preferably inclined so as to achieve uniform distribution of the reaction gas.

[0109] The nozzle passage 268 formed in the screw part 264 has a diameter of about 1 mm, and extends in a longitudinal direction of the screw part 264. An end of the nozzle passage 268 is open to a gap space 242 formed between the dielectric plate 240 and the shower plate 250. The screw part 264 is inserted into a through hole formed in the shower plate 250, and the screw is fastened to the shower plate 250 by the nut 266 being engaged with the end of the screw part 264. The nut 266 is accommodated in the recessed portion 246 formed on the surface of the dielectric plate 240 facing the shower plate 250.

[0110] The gap space 242 is provided for preventing generation of plasma. The thickness of the gap space 242 required for preventing generation of plasma varies according to a pressure of the reactant gas. That is, for example, the thickness of the gap space 242 is set to about 0.5 mm when the pressure is 10 Torr. In this case, the process space under the shower plate 250 in the process chamber 102 is set to a pressure of about 50 mTorr. The reactant gas is introduced into the process chamber 102 at a predetermined speed by controlling the pressure difference between the reactant gas and the atmosphere in the process chamber 102.

[0111] According to the shower plate 250 provided in the present embodiment, the reactant gas can be uniformly introduced and distributed in the process space in the process chamber 102 without generation of plasma before reaching the process space. An amount of flow of the reaction gas can be controlled according to the pressure difference between the gap space 242 and the process space in the process chamber 102, the number of eject passages 269, the inclination angle of the eject passages 269 and the size of each of the eject passages 269.

[0112] The eject member 260 may be integrally formed with a part or a whole of the shower plate 250, and can be any shape. For example, the eject member 260 may be replaced by eject members shown in FIGS. 16, 17 and 18. FIG. 16 is an enlarged cross-sectional view of the eject member 350a provided with a nozzle passage 352a having a single nozzle opening 354a. FIG. 17 is an enlarged cross-sectional view of the eject member 350b provided with a nozzle passage 352b having two nozzle openings 354b. FIG. 18 is an enlarged cross-sectional view of the eject member 350c provided with a nozzle passage 352c having three nozzle openings 354c.

[0113] A description will now be given, with reference to FIG. 19, of a cluster tool that can be connected to the plasma processing apparatus 100 shown in FIG. 1. FIG. 19 is an illustrative plan view of the cluster tool 300 that is connectable to the microwave plasma processing apparatus 100 shown in FIG. 1. As mentioned above, the temperature of the object W can be controlled by the susceptor 104. However, in a CVD process, it takes a considerable time to raise the temperature of the object W from a room temperature to about 250° C. to 350° C. by the susceptor 104. In order to eliminate such a problem, the cluster tool 300 heats the object W prior to providing the object W to the process chamber 102 of the microwave plasma processing apparatus 100. Similarly, it takes a considerable time to decrease the temperature of the object W from 250° C. to 350° C. to a room temperature by the susceptor 104 after the plasma processing is completed. In order to eliminate such a problem, the cluster tool 300 cools the object W prior to starting another process after the object W is taken out of the process chamber 102 of the microwave plasma processing apparatus 100.

[0114] As illustratively shown in FIG. 19, the cluster tool 300 comprises: a conveyor section 320 including a conveyor arm which holds and conveys the object W to be processed; a preheating section 340 for heating the object W; a cooling section 360 for cooling the object W; and load-lock (L/L) chambers 380. In FIG. 19, two process chambers 102A and 102B are shown. Each of the process chambers 102A and 102B can be the process chamber 102 of the microwave plasma processing apparatus 100 shown in FIG. 1. The number of process chambers provided in the cluster tool 300 is not limited to two.

[0115] The conveyor section 320 is provided with the conveyor arm which holds the object W and a rotating mechanism for rotating the conveyor arm. The preheating section 340 is provided with a heater so as to heat the object W to a temperature close to a process temperature before the object W is placed in the process chamber 102A or 102B. The cooling section 360 is provided with a cooling chamber, which is cooled by a coolant so as to cool the object W taken out of the process chamber 102A or 102B to a room temperature before the object W is conveyed to a subsequent apparatus such as an ion implantation apparatus or an etching apparatus. Preferably, the cluster tool 300 comprises a rotational angle sensor, a temperature sensor, at least one control unit and a memory for storing control programs so as to control the rotation of the conveyor arm of the conveyor section 320 and control a temperature of each of the preheating section 340 and cooling section 360. Such a sensor, a control unit and a control program are known in the art, and descriptions thereof will be omitted. Additionally, the conveyor arm of the conveyor section 320 places the object W in the process chamber 102A or 102B through the gate valve 101.

[0116] A description will now be given of an operation of the microwave plasma processing apparatus 100 shown in FIG. 1. First, the conveyor arm of the conveyor section 320 shown in FIG. 19 holds the object W to be processed so as to place the object W in the process chamber 102 (in FIG. 19, one of the process chambers 102A and 102B corresponds to the process chamber 102). It is assumed that the object W is subjected to a CVD process in the process chamber 102. In such a case, the control unit (not shown in the figure) of

the cluster tool 300 sends an instruction to the conveyor section 320 to convey the object W to the preheating section 340 so as to heat the object W to a temperature of about 300° C. before placing the object W in the process chamber 102.

[0117] For example, the cluster tool 300 forms a silicon oxidation film on a silicon substrate in the process chamber 102A by applying a plasma process. Thereafter the cluster tool 300 transfers the silicon substrate to the process chamber B so as to form a silicon nitride film by plasma processing the silicon oxidation film by introducing nitrogen into the process chamber 102B. A reactant gas introduced into the process chamber 102A so as to form the silicon oxidation film is typically $\text{SiH}_4\text{—N}_2\text{O}$. However, instead of SiH_4 , TEOS (tetraethylorthosilicate), TMCTS (tetramethylcyclotetrasiloxane) or DADBS (diacetoxyditeriarybutoxysilane) may be used. The reactant gas introduced into the process chamber 102B is typically $\text{SiH}_4\text{—NH}_3$. However, instead of SiH_4 , SiF_6 , NF_3 or SiF_4 may be used.

[0118] Upon receiving the instruction, the conveyor section 320 moves the object W to the preheating section 340 so as to heat the object W. When the temperature sensor (not shown in the figure) of the cluster tool 300 detects that the object W to be processed is heated to a temperature of about 300° C., the control unit of the cluster tool 300 sends an instruction to the conveyor section 320 to move the object W to be processed from the preheating section 340 to the process chamber 102 through the gate valve 101. Accordingly, the conveyor arm of the conveyor section 320 conveys the heated object W to the process chamber 102 through the gate valve 101. When the heated object W reaches a position above the susceptor 104 in the process chamber 102, the lifter pin vertically moving system moves the lifter pins (not shown in the figure) so as to support the object W by the three lifter pins (not shown in the figure) protruding from the upper surface of the susceptor 104. After the object W is transferred from the conveyor arm to the lifter pins, the conveyor arm returns through the gate valve 101. Thereafter, the conveyor arm may be moved to a home position (not shown in the figure).

[0119] After the object W is transferred to the lifter pins, the vertical moving unit 146 moves the vertical moving member 142 downward so as to return the lifter pins inside the susceptor 104 and place the object W on the susceptor 104. At this time, a susceptor moving member can be moved while maintaining the hermetic seal of the process chamber 102 by a bellows (not shown in the figure). The susceptor 104 heats the object W placed thereon to a temperature of 300° C. At this time, since the object W is preheated, it takes a short time to completely the process preparation. More specifically, the heater control unit 191 controls the heater unit 198 so as to raise the temperature of the susceptor 104 to 300° C.

[0120] Thereafter, the high-vacuum pump 106 maintains the pressure in the process chamber 102 at 50 mTorr by being controlled by the pressure adjust valve. Additionally, the valves 151 and 153 are opened, and the vacuum pumps 152 and 154 evacuate gas from the gas supply rings 140 and 170. As a result, a water component remaining in the gas supply rings 140 and 170 is sufficiently removed therefrom.

[0121] Additionally, the susceptor vertically moving system moves the susceptor 104 and the object W to a predetermined process position from a home position. The bel-

lows (not shown in the figure) maintains the negative pressure environment in the process chamber **102** during the vertically moving operation, and prevents an atmosphere from exiting outside the process chamber **102**. Thereafter, the valves **151** and **153** are closed.

[0122] Thereafter, the valves **132** and **162** are opened so as to introduce a mixture of NH_3 , helium, nitrogen and hydrogen into the process chamber **102** from the gas supply rings **140** and **170** via the mass flow controllers **134** and **164**. Since the valves **151** and **153** are closed, the vacuum pump **152** and **154** do not evacuate the gases in the gas supply systems **130** and **160** from being introduced into the process chamber **102**.

[0123] When the shower plate **250** shown in FIG. 14 is used, the process chamber **102** is maintained, for example, at 50 mTorr, and a mixture of helium, nitrogen, hydrogen and NH_3 , for example, is supplied to the dielectric plate **240**. Thereafter, the mixture gas is introduced into the process chamber by being passed through the gap space **242**, the recessed portions **246** and the nozzle passages **268** and **269** of the eject members **260**. The mixture gas is not converted into plasma, and is introduced into the process chamber **102** with a high controllability of flow and a uniform density.

[0124] The temperature of the process space of the process chamber **102** is adjusted to be 300° C. A microwave is generated by the microwave generator **110**, and is supplied to the wavelength-reducing member **124** of the antenna member **120** in a TEM mode via a square waveguide or a coaxial waveguide. The microwave passing through the wavelength-reducing member **124** is reduced in its wavelength, and enters the slot electrode **200**. The microwave is then introduced into the process chamber **102** via the slits **210** and the dielectric material plate **230**. Since a temperature of the wavelength reducing member **124** and the slot electrode **200** is controlled, there is no deformation due to thermal expansion. Accordingly, an optimum length of the slits **210** can be maintained. Thus, the microwave can be introduced into the process chamber **102** at a desired density without local concentration.

[0125] Thereafter, the reactant gas in the process chamber **102** is converted into plasma by the microwave, and a plasma CVD process is performed on the object W placed on the susceptor **104**. If the baffle plate **194** is used, the baffle plate maintains the potential in the process space so as to prevent the microwave from exiting the process space. Thus, a desired process speed can be maintained.

[0126] If a temperature of the susceptor **104** is raised higher than a predetermined upper limit temperature due to continuous use, the susceptor **104** is cooled by the temperature control unit **191**. On the other hand, if the temperature of the susceptor **104** is below a predetermined lower limit temperature at an initial stage of the operation of the apparatus or when the susceptor **104** is over cooled, the temperature control unit **191** heats the susceptor **104**.

[0127] The plasma CVD process is continued for a predetermined period of time (for example, about 2 minutes). Thereafter, the object W is taken out of the process chamber **102** through the gate valve **101** by the conveyor section **320** of the cluster tool **300** in a reversed way of the above-mentioned procedure. When the susceptor **104** is taken out, the vertically moving mechanism (not shown in the figure)

returns the susceptor **104** and the object W to the home position. The predetermined process time of 2 minutes is determined by a CVD processing time generally required for forming the layered nitride film. That is, even if the temperature control unit **190** sets the temperature to about 250° C. to 350° C., a long time deposition process may cause a problem similar to when the temperature is set higher than 350° C. Additionally, if the process time is too short, there may be a case in which a semiconductor element produced from the object W cannot effectively prevent a leak current.

[0128] Since the microwave is uniformly supplied to the process chamber **102** with a predetermined density, a silicon oxidation film and a silicon nitride film having a desired thickness are formed on the object W to be processed. Additionally, since the temperature of the process chamber **102** is maintained in the predetermined range so that a water component (impurities) does not enter the object W, the deposited film can be maintained at a desired quality. The object W taken out of the process chamber **102** is transferred to the cooling section **360** and the object W is cooled to a room temperature in a short time. Then, if necessary, the object W is conveyed by the conveyor section **320** to a next stage apparatus such as an ion implantation apparatus.

[0129] A description will now be given, with reference to FIG. 20, of a second embodiment of the present invention. FIG. 20 is an illustration of a structure of a microwave plasma processing apparatus **400** according to the second embodiment of the present invention. In FIG. 20, parts that are the same as the parts shown in FIG. 1 are given the same reference numerals, and descriptions thereof will be omitted.

[0130] Similar to the first embodiment, the second embodiment of the present invention is specifically related to an evacuating arrangement to evacuate gas from a gas-introducing part provided in a process chamber of the microwave plasma processing apparatus **400**. In the first embodiment, the evacuating arrangement is comprised of the vacuum pump **151** or **153**, which evacuates gas remaining in the gas supply ring **140** or **170**. On the other hand, in the second embodiment, the evacuating arrangement is comprised of a bypass passage, which directly connects the gas supply ring **140** or **170** to the vacuum pump **106** by bypassing the process chamber **102**.

[0131] More specifically, in the plasma processing apparatus **400** according to the second embodiment, the outlet port of the gas supply ring **140** is connected to an end of a bypass passage **182**, and the other end of the bypass passage **182** is connected to the vacuum pump **106**, which is originally provided to the plasma processing apparatus **400** so as to evacuate gas from the process chamber **102**. Additionally, a valve **181** is provided to the bypass passage **182** so as to open or close the bypass passage **182**. Similarly, the outlet port of the gas supply ring **170** is connected to an end of a bypass passage **184**, and the other end of the bypass passage **184** is connected to the vacuum pump **106**. Additionally, a valve **183** is provided to the bypass passage **184** so as to open or close the bypass passage **184**. FIG. 21 is an illustration of the evacuating arrangement of the above-mentioned gas-evacuating arrangement.

[0132] In the present embodiment, each of the bypass passages **182** and **184** has a diameter of 25 mm to 40 mm, which is greater than the diameter of the gas supply nozzles **143** and **172**. Thus, the vacuum pump **106** can evacuate gas

remaining in the gas supply rings **140** and **170** more efficiently and more rapidly than when the gas is evacuated through the gas supply nozzles **143** and **173**. It should be noted that although the bypass passages **182** and **184** are connected to the high-vacuum pump **106**, the bypass passages **182** and **184** may be connected to a roughing pump or other vacuum pumps originally provided to the plasma processing apparatus **400**.

[0133] In the present embodiment, the gas supply system **130** or **160** may be arranged to use the dielectric plate **240** and the shower plate **250** as shown in FIG. 14. In such a case, the outlet port **244** of the dielectric plate is connected to the bypass passage **182** or **184** so that the gas passage **242** is connected to the vacuum pump **6** by bypassing the process chamber **102**.

[0134] It should be noted that the microwave plasma processing apparatuses **100** and **400** can utilize an electron cyclotron resonance, and therefore, an electromagnetic coil may be provided so as to generate a magnetic field in the process chamber **102**. Additionally, although the microwave plasma processing apparatus **100** according to the present embodiment performs the plasma CVD process as plasma processing, the plasma processing is not limited to the plasma CVD process. That is, for example, a plasma etching process or a plasma cleaning process may be performed by the microwave plasma processing apparatus **100**. Additionally, the present invention is not limited to the RLSA type plasma processing apparatus, and may be applied to a parallel plate plasma processing apparatus utilizing a glow discharge. Further, the object **W** to be processed by the microwave plasma processing apparatus **100** is not limited to the wafer for producing a semiconductor device, and the microwave plasma processing apparatus **100** may be used to process an LCD substrate or a glass substrate.

[0135] The present invention is not limited to the specifically disclosed embodiments, and variations and modifications may be made without departing from the scope of the present invention.

[0136] The present application is based on Japanese priority application No. 2000-085351 filed on Mar. 24, 2000, the entire contents of which are hereby incorporated by reference.

What is claimed is:

1. A plasma processing apparatus for applying a plasma process to an object to be processed, the plasma processing apparatus comprising:

- a process chamber in which the object to be processed is subjected to the plasma process;
- a gas-introducing part connected to said process chamber so as to introduce a reactant gas into said process chamber;
- a first vacuum pump connected to said process chamber so as to evacuate gas from said process chamber so that said process chamber is maintained at a negative pressure; and
- a gas-evacuating arrangement connected to said gas-introducing part so as to evacuate the reactant gas from said gas-introducing part.

2. The plasma processing apparatus as claimed in claim 1, wherein said gas-evacuating arrangement comprises a second vacuum pump connected to said gas-introducing part.

3. The plasma processing apparatus as claimed in claim 1, wherein said gas-evacuating arrangement comprises a bypass passage which connects said gas-introducing part to said first vacuum pump by bypassing said process chamber.

4. The plasma processing apparatus as claimed in claim 1, wherein said gas-introducing part has an annular shape and is incorporated into a sidewall of said process chamber, said gas-introducing part has a plurality of circumferentially arranged nozzles through which the reactant gas is introduced into said process chamber.

5. The plasma processing apparatus as claimed in claim 4, wherein said gas-introducing part comprises:

at least one inlet port from which the reactant gas is supplied;

an annular gas passage connected to said inlet port so that the reactant gas supplied from the inlet port is supplied to said plurality of nozzles by flowing through said annular gas passage; and

an outlet port provided to said annular gas passage so that said gas-evacuating arrangement is connected thereto.

6. The plasma processing apparatus as claimed in claim 1, wherein said gas-introducing part comprises a dielectric plate and a shower plate provided on a top of said process chamber so as to introduce the reactant gas from the top of said process chamber, a gas passage being formed between said dielectric plate and said shower plate so that the reactant gas flows through the gas passage and is introduced into said process chamber through said shower plate.

7. The plasma processing apparatus as claimed in claim 6, wherein dielectric plate has an inlet port connected to said gas passage so as to supply the reactant gas to said gas passage, and said gas passage has an outlet port to which said gas-evacuating arrangement is connected.

8. The plasma processing apparatus as claimed in claim 1, further comprising a slot antenna having a plurality of slits so as to guide a microwave having a predetermined frequency which is determined by the plasma process to be applied to the object to be processed.

9. The plasma processing apparatus as claimed in claim 8, wherein a density of the slits is substantially uniform in a radial direction of said slot antenna.

10. A gas supply ring adapted to introduce a reactant gas into a process chamber of a processing apparatus, the gas supply ring comprising:

a plurality of circumferentially arranged nozzles through which the reactant gas is introduced into said process chamber;

at least one inlet port from which the reactant gas is supplied;

an annular gas passage connected to said inlet port so that the reactant gas supplied from the inlet port is supplied to said plurality of nozzles by flowing through said annular gas passage; and

an outlet port provided to said annular gas passage so that the reactant gas is evacuated from said gas supply ring through said outlet port.

11. A dielectric plate adapted to be attached to a process chamber of a plasma processing apparatus, the dielectric plate comprising:

- a plurality of nozzles through which a reactant gas is introduced into said process chamber;
- at least one inlet port from which the reactant gas is supplied;
- a gas passage connected to said inlet port so that the reactant gas supplied from the inlet port is supplied to said plurality of nozzles by flowing through said gas passage; and
- an outlet port provided to said gas passage so that the reactant gas is evacuated from said gas passage through said outlet port.

12. A plasma processing method comprising the steps of: evacuating gas from a process chamber by a first vacuum pump connected to said process chamber;

introducing a reactant gas into said process chamber through a gas-introducing part;

applying a plasma process to an object placed in said process chamber by generating plasma from the reactant gas;

stopping the introduction of the reactant gas into said process chamber after ending the plasma process; and

evacuating the reactant gas remaining in said gas-introducing part by a second vacuum pump connected to said gas-introducing part.

13. A plasma processing method comprising the steps of:

evacuating gas from a process chamber by a vacuum pump connected to said process chamber;

introducing a reactant gas into said process chamber through a gas-introducing part having a plurality of nozzles;

applying a plasma process to an object placed in said process chamber by generating plasma from the reactant gas;

stopping the introduction of the reactant gas into said process chamber after ending the plasma process; and

evacuating the reactant gas remaining in said gas-introducing part by said vacuum pump by connecting said gas-introducing part to said vacuum pump by bypassing said process chamber.

* * * * *