

665305

The Commissioner of Patents
PO Box 200
WODEN ACT 2606

F B RICE & CO
SYDNEY NSW
Speed Dial 511

PATENTS

Our Ref: 63224

AUSTRALIA
Patents Act 1990
PATENT REQUEST: STANDARD PATENT

We, YKK CORPORATION being the person(s) identified below as the Applicant, request the grant of a standard patent to the person identified below as the Nominated Person, for an invention described in the accompanying complete specification.

Full application details follow.

Applicant and
Nominated Person:

YKK CORPORATION
A Japanese company

Address:

No 1 Kanda Izumi-Cho, Chiyoda-Ku
Tokyo Japan

Invention Title:

Synthetic resin pelletizing machine

Name(s) of Actual Inventor(s): Akiyoshi KANDO; Hiroshi YOSHIDA;
Kazuki KUSE

Address for Service in Australia:

F B RICE & CO
Patent Attorneys
28A Montague St
BALMAIN NSW 2041

Attorney Code: RI

BASIC CONVENTION APPLICATION(S) DETAILS

<u>Application No</u>	<u>Country</u>	<u>Country Code</u>	<u>Date of Application</u>
5-88754	Japan	JP	15 April 1993

Applicant(s): Yoshida Kogyo K.K.

We are not an opponent/eligible person described in Section 33 - 36 of the Act.

Drawing number recommended to accompany the abstract Figure 1.

Dated this 7th day of April 1995

YOSHIDA KOGYO KK

Registered Patent Attorney

FLS/tmm/d6/63224



Australia Patents Act 1990

Notice of Entitlement

(to be filed before acceptance)

I/We Susumu ISHII
 being authorised by YOSHIDA KOGYO K. K.
 of No.1, Kanda Izumi-cho, Chiyoda-ku, Tokyo, Japan
 the applicant in respect of an application for a patent for an invention entitled Synthetic resin pelletizing machine
 filed under Australian Application No. _____, state the following:-

Part 1 - Must be completed for all applications.

☐ The person(s) nominated for the grant of the patent:
~~is/are the actual inventor(s)~~
 or
☒ has, for the following reasons, gained entitlement from the actual inventor(s):
The nominated person is a person who would if a patent were granted
upon an application made by the actual inventors be entitled
to have the patent assigned to it

Part 2 - Must be completed if the application is a Convention application.

☒ The person(s) nominated for the grant of the patent is/are:
 the applicant(s) of the basic application(s) listed on the patent request form
 or
☐ entitled to rely on the basic application(s) listed on the patent request form by reason of the following:

The basic application(s) listed on the request form is/are the first application(s) made in a Convention country in respect of the invention.

Part 3 - must be completed if the application was made under the PCT and claims priority.

☐ The person(s) nominated for the grant of the patent is/are:
 the applicant(s) of the application(s) listed in the declaration under Article 8 of the PCT
 or
☐ entitled to rely on the application(s) listed in the declaration under Article 8 of the PCT by reason of the following:-

~~The basic application(s) listed in the declaration made under Article 8 of the PCT is/are the first application(s) made in a Convention country in respect of the invention.~~

Signed: Susumu Ishii Date: March 25, 1994
 Susumu ISHII

Status: Patent Manager



AU9459416

(12) PATENT ABRIDGMENT (11) Document No. AU-B-59416/94
(19) AUSTRALIAN PATENT OFFICE (1C) Acceptance No. 665305

- (54) Title
SYNTHETIC RESIN PELLETTIZING MACHINE
- International Patent Classification(s)
(51)⁵ B29C 047/08 B29B 009/06 B29C 047/10 B29C 047/88
- (21) Application No. : 59416/94 (22) Application Date : 12.04.94
- (30) Priority Data
- (31) Number (32) Date (33) Country
5-88754 15.04.93 JP JAPAN
- (43) Publication Date : 03.11.94
- (44) Publication Date of Accepted Application : 21.12.95
- (71) Applicant(s)
YKK CORPORATION
- (72) Inventor(s)
AKIYOSHI KANDO; HIROSHI YOSHIDA; KAZUKI KUSE
- (74) Attorney or Agent
F B RICE & CO , 28A Montague Street, BALMAIN NSW 2041
- (56) Prior Art Documents
JP 57-178809
JP 55-074821
JP 54-052161
- (57) Claim

1. A synthetic resin pelletizing machine of the type having a molding portion in which a raw material including a synthetic resin, a pigment and various additives is melted and kneaded and then shaped by extrusion into a strand, and the extruded strand is cooled, wherein said pelletizing machine includes.

an extrusion cylinder having at its lower end a die head and forming, with a horizontal plane, an installation angle θ which is in the range of $0^\circ < \theta < 90^\circ$;

a raw material feed passage extending upwardly from said extrusion cylinder at a predetermined angle relative to a longitudinal axis of said extrusion cylinder; and

a cooling unit disposed below said die head for cooling the strand, said cooling unit having a double bath construction composed of a first cooling bath and a second cooling bath disposed in said first cooling bath.

AUSTRALIA

Patents Act 1990

YOSHIDA KOGYO K.K.

**ORIGINAL
COMPLETE SPECIFICATION
STANDARD PATENT**

Invention Title:

"Synthetic resin pelletizing machine"

The following statement is a full description of this invention including the best method of performing it known to us:-

BACKGROUND OF THE INVENTION

1. Field of the Invention

5 The present invention relates to a synthetic resin pelletizing machine or pelletizer that shapes by extruding a raw material, such as synthetic resin powder, granules or pellets, into a continuous form of extrudate and, after cooling the continuous extrudate, cuts off the same into small pellets.

2. Description of the Prior Art:

10 In the synthetic resin molding industry, it is a customary practice to mix a plurality of synthetic resin materials of different properties to form a molded product of desired characteristics. In this instance, if the mixing is not homogeneous, the final product has undesired characteristics. To avoid this problem, as disclosed in Japanese Patent Publication No. 63-32604, each of various synthetic resins are separately supplied to an extrusion unit in which the each kind of resin is melted with heat and extruded as a strand into a cooling water bath. The cooled strand is cut into fine granules or pellets. The fine pellets thus produced are then mixed with similar pellets of different kinds of synthetic resins to form a molded article.

20

In general, the conventional pelletizing machine of the type concerned is, as also mentioned in the above-referenced Japanese patent publication, a large-sized machine to cope with the mass-production system. Accordingly, the
5 extrusion unit incorporated in such a large-sized pelletizing machine is necessarily large in size, and taking the maintenance into account, it is composed of a horizontal-type extrusion unit having an extrusion cylinder horizontally mounted on a machine frame.

10 The known pelletizing machine of the foregoing construction occupies a large space in a horizontal direction and, hence, uses the space inefficiently. In addition, the known pelletizing machine is not adaptable to the multi-product, small-quantity production system which has recently
15 been required for various molded articles. An attempted use of the conventional pelletizing machine in the multi-product, small-quantity production system would produce an excessive stock of molded articles, requiring a complicated stock control operation. Accordingly, there is a keen demand for a
20 pelletizing machine which is compact in size and readily adaptable to the multi-product, small-quantity production system. Furthermore, since the raw resin is supplied to the horizontal-type extrusion cylinder at right angles to the axis of an extrusion screw, the raw resin is likely to get
25 clogged at an inlet of the extrusion cylinder. In addition,

the strand, as it is extruded from the horizontal-type extrusion cylinder into a cooling bath, is subjected to a lateral bending force which will exert negative influence on the quality of the pellets produced from the extruded strand.

SUMMARY OF THE INVENTION

It is, therefore, an object of the present invention to provide a synthetic resin pelletizing machine which is compact in size, readily adaptable to the multi-product, small-quantity production system, and capable of assuring a smooth feed of raw resin to an extrusion unit as well as a smooth passage of an extruded strand through a cooling bath.

According to the present invention, there is provided a synthetic resin pelletizing machine of the type having a molding portion in which a raw material including a synthetic resin, a pigment and various additives is melted and kneaded and then shaped by extrusion into a strand, and the extruded strand is cooled, ^{where the pelletizing machine includes} ~~characterized in that~~ an extrusion cylinder having at its lower end a die head forms, with a horizontal plane, an installation angle θ which is in the range of $0^\circ < \theta < 90^\circ$, a raw material feed passage extends upwardly from said extrusion cylinder at a predetermined angle relative to a longitudinal axis of the extrusion cylinder, and a cooling unit is disposed below the die head



for cooling the strand, the cooling unit having a double bath construction composed of a first cooling bath and a second cooling bath disposed in the first cooling bath.

5 The extrusion cylinder is generally arranged vertically and not horizontally, so that the pelletizing machine as a whole is compact in size and occupies a relatively small space in the horizontal direction. Since the raw material is supplied obliquely from the raw material feed passage into the extrusion unit and enters toward the extrusion direction, the extrusion cylinder is free from a clogging problem which would otherwise occurs at an inlet of the extrusion cylinder.

10 The pelletizing machine ordinarily includes a cutting unit disposed at a downstream end of a strand feed path in the cooling unit, for cutting the strand into pellets of a predetermined size.

15 The installation angle θ of the extrusion cylinder relative to the horizontal plane is preferably in the range of $45^\circ < \theta < 90^\circ$. In connection with the installation angle θ , the angle between the synthetic resin-chip feed passage and the longitudinal axis of the extrusion cylinder is set in the range of 0° to 45° .

20 In addition, the first and second cooling baths contain cooling water, and the cooling water is circulated through the first and second cooling baths by means of a

pump. With this circulation, the cooling water can be used efficiently. The strand extruded from the extrusion cylinder toward the cooling unit is not subjected to a lateral bending force and can enter into the cooling unit by its own weight. Accordingly, pellets cut off from the strand are extremely uniform in quality.

The above and other objects, features and advantages of the present invention will become manifest to those versed in the art upon making reference to the detailed description and the accompanying sheets of drawings in which preferred structural embodiments incorporating the principles of the present invention are shown by way of illustrative example.

BRIEF DESCRIPTION OF THE DRAWINGS

FIG. 1 is a front elevational view showing the general construction of a synthetic resin fine pelletizing machine according to a first embodiment of the present invention, with main parts shown in cross section;

FIG. 2 is a perspective view showing on enlarged scale a cooling unit of the pelletizing machine; and

FIG. 3 is a front elevational view showing the general construction of a synthetic resin fine pelletizing machine according to a second embodiment of the present invention, with main parts shown in cross section.

DETAILED DESCRIPTION

Referring now to FIGS. 1 and 2, there is shown a synthetic resin pelletizing machine according to a first embodiment of the present invention. The pelletizing machine is so constructed as to reduce the overall machine size.

S To this end, these parts of the pelletizing machine which must be arranged horizontally are minimized to increase those parts having a vertical construction. A typical example of the vertically arranged parts is an extrusion unit 1. As shown in FIG. 1, the extrusion unit 1 of the pelletizing machine comprises an extrusion cylinder 10, an extrusion screw 11, a driving member 12 for the extrusion screw 11, and a raw material loading hopper 13. These parts 10 - 13 of the extrusion unit 1 are structurally and functionally similar to those of the conventional extrusion unit. The extrusion unit 1 of this embodiment differs from the conventional one in that the extrusion unit 1 as a whole is disposed vertically. As a result, the driving member 12 is disposed directly above the extrusion cylinder 10, a die head 14 is attached to a lower end of the extrusion cylinder 10, and the raw material loading hopper 13 is disposed parallel to the extrusion cylinder 10 via a raw material feed pipe 15 which extends obliquely and upwardly from a raw material inlet 10a of the extrusion cylinder 10. The feed pipe 15 defines therein a raw material feed passage. In the illustrated embodiment, the extrusion unit 1 is upright. However, it is possible to dispose the

extrusion unit 1 obliquely at an angle θ to a horizontal plane, the angle θ being in the range of 0° to 90° . Taking the efficient use of the space and the function of the extrusion unit 1 into account, the angle θ is preferably in the range of 45° to 90° .

The pelletizing machine further includes a cooling unit 2 disposed directly below the die head 14. The cooling unit 2, as clearly shown in FIGS. 1 and 2, is composed of a double cooling bath 20 which includes a rectangular first cooling bath 21 and a rectangular second cooling bath 22 received in the first cooling bath 21. A pair of freely rotatable, grooved guide rollers 23, 23 are disposed in the second cooling bath 22. The guide rollers 23 are located respectively adjacent to the front and rear ends (left and right ends in FIG. 1) of the second cooling bath 22 so as to define a main portion of a strand feed path along which a strand S is advanced. A water discharge pipe 24 is connected via a discharge hole (not designated) to the bottom wall of a front end portion (left end portion in FIG. 1) of the first cooling bath 21. Similarly, a water supply pipe 25 is connected via a supply hole (shown in FIG. 2 not designated) to a side wall of a rear end portion (right end portion in FIG. 1) of the second cooling bath 22. The water supply pipe 25 has a receiving end connected to a feed-water pump 27 (FIG. 1). The water discharge pipe 24 has a discharge

end which is disposed in a water storage tank 26 as well as the feed-water pump 27. The water storage tank 26 is disposed below the double cooling bath 20 and mounted on a machine frame 3.

5 The machine frame 3 is composed of a table having a top support plate 31 and an intermediate support plate 32. The extrusion unit 1 and the double cooling bath 20 are mounted on the top support plate 31, and the water storage tank 26 is mounted on the intermediate support plate 32.

10 According to the first embodiment, a cutting unit 4 is disposed along a front end wall (left end wall in FIG. 1) of the machine frame 3 such that the cutting unit 4 is located substantially at a downstream end of the strand feed path extending through the cooling unit 2. To facilitate
15 the reduction of the overall size of the pelletizing machine, a longitudinal extent of the cutting unit 4 which projects from the front end of the machine frame 3 is reduced as much as possible so that the cutting unit 4 has a horizontally contracted, vertically elongated construction. As shown in
20 FIG. 1, a cooperating pair of feed rollers 41 is mounted on the front end portion of the top support plate 31. A fixed cutter 42 is disposed adjacent to a strand discharge side of the feed roller pair 41, and a rotary cutter 43 is disposed in confrontation with the fixed cutter 42. The fixed
25 cutter 42 and the rotary cutter 43 are located in a vertically

extending, rectangular tube-like discharge chute 44. The chute 44 has a top lid or cover. A pellet collecting case 45 is disposed below the discharge chute 44 for receiving therein granules or pellets produced by cutting the strand S. A strand guide member 46 formed of an elastic material, such as a foamed plastics plate, is disposed immediately upstream of the feed roller pair 41 for guiding the strand S. The strand guide member 46 also has a function to remove water which has adhered to the strand S while the strand S is cooled. In FIG. 1, numeral 5 denotes tie rods and 6 a control panel.

It is obvious that the structure of the cutting unit 4 is not restricted to the illustrated embodiment. Furthermore, the cutting unit 4 may not be continuous with the front end wall of the machine frame 3. As an alternative, the cutting unit 4 in the foregoing embodiment may be replaced by a strand case or container for receiving therein the extruded strand S, in which instance a cutting unit is provided separately from the machine frame 3.

The synthetic resin pelletizing machine of the foregoing construction operates as follows. The raw material loading hopper 13 is charged with a raw material composed of a synthetic resin and various additives, such as a pigment having a predetermined color and a plastiziging agent, mixed in predetermined ratios with the synthetic resin.

The raw material loaded in the raw material loading hopper 13 passes through the raw material feed pipe 15 and then is supplied obliquely from the raw material inlet 10a into the extrusion cylinder 10 at a predetermined angle to the axis of the extrusion screw 11 and toward the extrusion direction.

It is to be noted that in the case of the conventional extrusion unit, the raw material is supplied into the extrusion cylinder at right angles to the axis of the extrusion cylinder, whereas in the case of the present invention, the raw material is supplied obliquely into the extrusion cylinder 10 at a predetermined angle to the longitudinal axis of the extrusion cylinder 10 and toward the extrusion direction of the extrusion screw 11. Accordingly, in the pelletizing machine of the invention, the raw material is smoothly forced in the extrusion direction by the extrusion screw 11 without clogging at the raw material inlet 10a of the extrusion cylinder 10. The raw material is melted and kneaded homogeneously while being advanced in the extrusion cylinder 10, so that fine granules or pellets formed as a final product are extremely uniform in quality.

The inside temperature of the extrusion cylinder 10 is properly controlled, so that the raw material supplied in the extrusion cylinder 10 is plasticated and kneaded as it is progressively advanced toward the die head 14 by the rotation of the extrusion screw 11. From the die head 14 which

is attached to the lower end of the extrusion cylinder 10, the raw material is extruded downwardly into the second cooling bath 22 in the form of the strand S having a predetermined thickness. In this instance, since the
5 extrusion direction of the strand S is equal to the direction of its own weight acting on the strand S, the extruded strand S, as opposed to the strand formed by the conventional horizontal-type extrusion unit, is not subjected to a lateral bending force and can enter by its own weight
10 into the second cooling bath 22.

The strand S passes through cooling water W in the second cooling bath 22 while it is being guided by the grooved guide rollers 23. The strand S is thus cooled with water W. Then, the cooled strand S passes through the
15 strand guide member 46 during which time water adhering to the surface of the strand S is removed. Subsequently, the strand S is continuously advanced by the feed roller pair 41 toward the fixed cutter 42 and the rotary cutter 43. Between the fixed cutter 42 and the rotary cutter 43, the
20 strand S is cut into granules or pellets of a predetermined size. The pellets thus produced fall within the discharge chute 44 and then are received in the collecting case 45 disposed below the discharge chute 44.

In the cooling unit 2, the feed-water pump 27 disposed in the water storage tank 26 feeds cooling water W
25

from the storage tank 26 through the water supply pipe 25 to the second cooling bath 22. The cooling water W then overflows from the second cooling bath 22 into the first cooling bath 21 from which the cooling water W is discharged via the water discharge pipe 24 into the water storage tank 26 where the cooling water W is stored. With this circulation, the cooling water W is used efficiently.

FIG. 3 illustrates a second embodiment of the present invention. In this embodiment, the extrusion cylinder 10 is disposed obliquely at an angle of about 45° , and the raw material loading hopper 13 and the raw material supply pipe 15 are disposed vertically. Also in this embodiment, the raw material supply pipe 15 is connected with the extrusion cylinder 10 in a crossing manner at an angle of about 45° . Similarly, the die head 14 faces obliquely at the same angle (viz., 45°) to the cooling unit 2, so that the extruded strand S enters obliquely into the second cooling bath 22. In this instance, the strand S is subjected to a force tending to bend the strand S. However, the bending force is considerably smaller than that produced in the case of the conventional horizontal-type extrusion unit and can only exert negligible influence on the quality of the strand S. Other structural and functional details of the second embodiment are substantially the same as those of the first embodiment previously mentioned.

The present invention thus constructed makes it possible to reduce the overall size of the pelletizing machine and hence use the space efficiently on condition that the pelletizing machine has the same production capacity as the conventional pelletizing machine. In particular, the extrusion unit 1 is of the vertical type so that when the overall size of the pelletizing machine is reduced to cope with the multi-product, small-quantity production system, various maintenance works can be achieved easily.

As is apparent from the foregoing description, the synthetic resin pelletizing machine of the present invention is compact as a whole and, hence, is able to use the space efficiently. In addition, the pelletizing machine can respond to the need for downsizing, is able to obviate the need for troublesome maintenance even though a vertical-type extrusion unit is used, and is adaptable to the multi-product, small-quantity production system. The vertical-type extrusion unit provides a smooth extrusion mechanism for a melted resin. More specifically, since the raw material is supplied obliquely into the extrusion cylinder and toward the extrusion direction, the raw material is smoothly advanced by the extrusion screw without clogging at the inlet of the extrusion cylinder. The raw material while being advanced in the extrusion cylinder is plasticated and kneaded homogeneously.

The strand extruded from the die head reaches the cooling

unit by its own weight, so that an extruded, incompletely solidified strand is not subjected to undue bending forces. Thus, pellets produced from the strand has high dimensional accuracy.

S Obviously, various minor changes and modifications of the present invention are possible in the light of the above teaching. It is therefore to be understood that within the scope of the appended claims the invention may be practiced otherwise than as specifically described.

THE CLAIMS DEFINING THE INVENTION ARE AS FOLLOWS:-

5 1. A synthetic resin pelletizing machine of the type having a molding portion in which a raw material including a synthetic resin, a pigment and various additives is melted and kneaded and then shaped by extrusion into a strand, and the extruded strand is cooled, wherein said pelletizing machine includes.

an extrusion cylinder having at its lower end a die head and forming, with a horizontal plane, an installation angle θ which is in the range of $0^\circ < \theta < 90^\circ$;

10 a raw material feed passage extending upwardly from said extrusion cylinder at a predetermined angle relative to a longitudinal axis of said extrusion cylinder; and

15 a cooling unit disposed below said die head for cooling the strand, said cooling unit having a double bath construction composed of a first cooling bath and a second cooling bath disposed in said first cooling bath.

20 2. A synthetic resin pelletizing machine according to claim 1, wherein said cooling unit has a strand feed path for the passage therealong the strand, further including a cutting unit disposed substantially at a downstream end of said feed strand path for cutting the strand into pellets of a predetermined size.

3. A synthetic resin pelletizing machine according to claim 1 or 2, wherein said installation angle θ of said



extrusion cylinder relative to said horizontal plane is in the range of $45^\circ < \theta < 90^\circ$.

4. A synthetic resin pelletizing machine according to claim 1 or 2, wherein said predetermined angle between said raw material feed passage and said longitudinal axis of said extrusion cylinder ranges from 0° to 45° .

5. A synthetic resin pelletizing machine according to claim 1 or 2, wherein said first and second cooling baths contain cooling water, and said cooling water is circulated through said first and second cooling baths by means of a pump.

6. A synthetic resin pelletizing machine substantially as hereinbefore described with reference to the accompanying drawings.

DATED this 1st day of September 1995

YOSHIDA KOGYO K.K.

Patent Attorneys for the Applicant:

F.B. RICE & CO.




ABSTRACT

A synthetic resin pelletizing machine includes an extrusion cylinder forming, with a horizontal plane, an installation angle θ which is in the range of $0^\circ < \theta < 90^\circ$, a raw material feed passage extending upwardly from said
5 extrusion cylinder at a predetermined angle relative to a longitudinal axis of said extrusion cylinder, and a cooling unit disposed below a die head and having a double bath construction composed of a first cooling bath and a second cooling bath disposed in the first cooling bath. The
10 pelletizing machine thus constructed is compact in size and is capable of assuring a smooth feed of a raw material to the extrusion cylinder as well as a smooth passage of an extruded strand through the cooling unit.

12 04 94 59415

FIG. 2



2/3

3/3

FIG. 3

