(12) INTERNATIONAL APPLICATION PUBLISHED UNDER THE PATENT COOPERATION TREATY (PCT)

(19) World Intellectual Property Organization
International Bureau

(43) International Publication Date
18 September 2014 (18.09.2014)

WIPO | PCT

(10) International Publication Number
WO 2014/145958 A2

(51) International Patent Classification:
A61K 39/08 (2006.01)

(21) International Application Number:
PCT/US2014/030817

(22) International Filing Date:
17 March 2014 (17.03.2014)

(25) Filing Language: English

(26) Publication Language: English

(30) Priority Data:
61/798,666 15 March 2013 (15.03.2013) US

(71) Applicant: **SERES HEALTH, INC.** [US/US]; 161 First Street, Suite 1A, Cambridge, MA 02142 (US).

(72) Inventors: **HENN, Matthew, R.**; C/o Seres Health, Inc., 161 First Street, Suite 1A, Cambridge, MA 02142 (US). **COOK, David, N.**; C/o Seres Health, Inc., 161 First Street, Suite 1A, Cambridge, MA 02142 (US). **OHSUMI, Toshiro, K.**; C/o Seres Health, Inc., 161 First Street, Suite 1A, Cambridge, MA 02142 (US). **MCKENZIE, Mary-Jane, Lombardo**; C/o Seres Health, Inc., 161 First Street, Suite 1A, Cambridge, MA 02142 (US). **LITCOFSKY, Kevin, D.**; C/o Seres Health, Inc., 161 First Street, Suite 1A, Cambridge, MA 02142 (US). **ZHANG, Han**; C/o Seres Health, Inc., 161 First Street, Suite 1A, Cambridge, MA 02142 (US). **AUNINS, John, Grant**; C/o Seres Health, Inc., 161 First Street, Suite 1A, Cambridge, MA 02142 (US). **BERRY, David**; C/o Seres Health, Inc., 161 First Street, Suite 1A, Cambridge, MA 02142 (US).

(74) Agents: **SHUSTER, Michael, J.** et al.; FENWICK & WEST LLP, Silicon Valley Center, 801 California Street, Mountain View, CA 94041 (US).

(81) Designated States *(unless otherwise indicated, for every kind of national protection available)*: AE, AG, AL, AM, AO, AT, AU, AZ, BA, BB, BG, BH, BN, BR, BW, BY, BZ, CA, CH, CL, CN, CO, CR, CU, CZ, DE, DK, DM, DO, DZ, EC, EE, EG, ES, FI, GB, GD, GE, GH, GM, GT, HN, HR, HU, ID, IL, IN, IR, IS, JP, KE, KG, KN, KP, KR, KZ, LA, LC, LK, LR, LS, LT, LU, LY, MA, MD, ME, MG, MK, MN, MW, MX, MY, MZ, NA, NG, NI, NO, NZ, OM, PA, PE, PG, PH, PL, PT, QA, RO, RS, RU, RW, SA,

[Continued on next page]

(54) Title: NETWORK-BASED MICROBIAL COMPOSITIONS AND METHODS

(57) Abstract: Provided are therapeutic compositions containing combinations of bacteria, for the maintenance or restoration of a healthy microbiota in the gastrointestinal tract of a mammalian subject, and methods for use thereof.




Figure 19

WO 2014/145958 A2

SC, SD, SE, SG, SK, SL, SM, ST, SV, SY, TH, TJ, TM, TN, TR, TT, TZ, UA, UG, US, UZ, VC, VN, ZA, ZM, ZW.

(84) **Designated States** *(unless otherwise indicated, for every kind of regional protection available)*: ARIPO (BW, GH, GM, KE, LR, LS, MW, MZ, NA, RW, SD, SL, SZ, TZ, UG, ZM, ZW), Eurasian (AM, AZ, BY, KG, KZ, RU, TJ, TM), European (AL, AT, BE, BG, CH, CY, CZ, DE, DK, EE, ES, FI, FR, GB, GR, HR, HU, IE, IS, IT, LT, LU, LV, MC, MK, MT, NL, NO, PL, PT, RO, RS, SE, SI, SK, SM, TR), OAPI (BF, BJ, CF, CG, CI, CM, GA, GN, GQ, GW, KM, ML, MR, NE, SN, TD, TG).

Published:

— *without international search report and to be republished upon receipt of that report (Rule 48.2(g))*

— *with sequence listing part of description (Rule 5.2(a))*

TITLE

[001] Network-Based Microbial Compositions and Methods

RELATED APPLICATIONS

[002] This application claims the benefit of U.S. Provisional Application No. 61/798,666, filed March 15, 2013, which is incorporated by reference in its entirety.

REFERENCE TO A SEQUENCE LISTING

[003] This application includes a Sequence Listing submitted electronically as a text file named 26184PCT_sequencelisting.txt, created on March 10, 2014, with a size of 4,196,066 bytes. The sequence listing is incorporated by reference.

BACKGROUND

[004] Mammals are colonized by microbes in the gastrointestinal (GI) tract, on the skin, and in other epithelial and tissue niches such as the oral cavity, eye surface and vagina. The gastrointestinal tract harbors an abundant and diverse microbial community. It is a complex system, providing an environment or niche for a community of many different species or organisms, including diverse strains of bacteria. Hundreds of different species can form a commensal community in the GI tract in a healthy person, and this complement of organisms evolves from birth to ultimately form a functionally mature microbial population by about 3 years of age. Interactions between microbial strains in these populations and between microbes and the host (*e.g.* the host immune system) shape the community structure, with availability of and competition for resources affecting the distribution of microbes. Such resources may be food, location and the availability of space to grow or a physical structure to which the microbe may attach. For example, the host's diet is involved in shaping the GI tract flora.

[005] A healthy microbiota provides the host with multiple benefits, including colonization resistance to a broad spectrum of pathogens, essential nutrient biosynthesis and absorption, and immune stimulation that maintains a healthy gut epithelium and an appropriately controlled systemic immunity. In settings of 'dysbiosis' or disrupted symbiosis, microbiota functions can be lost or deranged, resulting in increased susceptibility to pathogens, altered metabolic profiles, or induction of proinflammatory signals that can result in local or systemic inflammation or autoimmunity. Thus, the intestinal microbiota plays a significant role in the pathogenesis of many diseases and disorders. Many of these diseases and disorders are chronic conditions that significantly decrease a subject's quality of life and can be ultimately fatal.

[006] Manufacturers of probiotics have asserted that their preparations of bacteria promote mammalian health by preserving the natural microflora in the GI tract and reinforcing the normal controls on aberrant immune responses. *See, e.g.,* U.S. Patent No. 8,034,601. Probiotics, however, have been limited to a very narrow group of genera and a correspondingly limited number of species.

As such, they do not adequately replace the missing natural microflora nor correct dysbioses of the GI tract in many situations.

[007] Therefore, in response to the need for durable, efficient, and effective compositions and methods for prevention, diagnosis and/or treatment of prediabetes and diabetes by way of restoring or enhancing microbiota functions, we address these and other shortcomings of the prior art by providing compositions and methods for treating subjects.

SUMMARY OF THE INVENTION

[008] Disclosed herein are methods for treating, preventing, or reducing the severity of a disorder selected from the group consisting of Clostridium difficile Associated Diarrhea (CDAD), Type 2 Diabetes, Obesity, Irritable Bowel Disease (IBD), colonization with a pathogen or pathobiont, and infection with a drug-resistant pathogen or pathobiont, comprising: administering to a mammalian subject in need thereof an effective amount of a therapeutic bacterial composition, said therapeutic bacterial composition comprising a plurality of isolated bacteria or a purified bacterial preparation, the plurality of isolated bacteria or the purified bacterial preparation capable of forming a network ecology selected from the group consisting of N262.S, N290.S, N284.S, N271.S, N282.S, N288.S, N302.S, N279.S, N310.S, N323.S, N331.S, N332.S, N301.S, N312.S, N339.S, N325.S, N340.S, N341.S, N346.S, N338.S, N336.S, N345.S, N355.S, N356.S, N343.S, N329.S, N361.S, N353.S, N381.S, N344.S, N352.S, N357.S, N358.S, N369.S, N372.S, N375.S, N380.S, N374.S, N377.S, N368.S, N370.S, N373.S, N376.S, N389.S, N394.S, N431.S, N434.S, N390.S, N397.S, N387.S, N440.S, N396.S, N399.S, N403.S, N414.S, N430.S, N432.S, N436.S, N437.S, N457.S, N545, N386.S, N402.S, N405.S, N415.S, N421.S, N422.S, N423.S, N458.S, N459.S, N493.S, N416.S, N439.S, N447.S, N490.S, N526, N429.S, N433.S, N448.S, N488.S, N508.S, N509.S, N510.S, N511.S, N408.S, N446.S, N451.S, N474.S, N520.S, N521.S, N535.S, N516.S, N463.S, N518.S, N586, N450.S, N465.S, N519.S, N537.S, N419.S, N468.S, N477.S, N514.S, N382.S, N460.S, N462.S, N512.S, N517.S, N523.S, N547.S, N548.S, N577.S, N581.S, N585.S, N616.S, N466.S, N469.S, N480.S, N482.S, N484.S, N515.S, N533.S, N709, N730, N478.S, N572.S, N400.S, N543.S, N582.S, N621.S, N689, N769, N481.S, N525.S, N528.S, N534.S, N574.S, N580.S, N590.S, N591.S, N597.S, N664, N693, N530.S, N687, N470.S, N529.S, N539.S, N546.S, N570.S, N579.S, N602.S, N614.S, N648.S, N652.S, N655.S, N672.S, N681.S, N690.S, N692.S, N698.S, N737.S, N738.S, N785, N841, N878, N880, N881, N987, N988, N996, N1061, N479.S, N538.S, N542.S, N578.S, N609.S, N611.S, N617.S, N666.S, N675.S, N682.S, N844, N845, N846, N852, N876, N982, N1008, N649.S, N657.S, N678.S, N686.S, N710.S, N522.S, N651.S, N653.S, N654.S, N680.S, N712.S, N792, N802, N804, N807, N849, N858, N859, N875, N885, N942, N961, N972, N1051, N587.S, N589.S, N612.S, N625.S, N656.S, N714.S, N779, N781, N828, N829, N860, N894, N925, N927, N935, N947, N983, N1023, N441.S, N584.S, N794, N788, N524.S, N604.S, N610.S, N623.S, N663.S, N669.S, N676.S, N703.S, N775.S, N777.S, N780.S, N817.S, N827.S, N836.S, N871.S, N874.S, N898.S, N907.S, N998.S, N1088, N1089, N660.S, N665.S, N667.S, N733.S, N734.S,

N739.S, N741.S, N782.S, N789.S, N796.S, N798.S, N800.S, N809.S, N816.S, N842.S, N843.S, N869.S, N986.S, N995.S, N1002.S, N1004.S, N1019.S, N1093, N668.S, N685.S, N835.S, N851.S, N464.S, N695.S, N776.S, N793.S, N815.S, N833.S, N891.S, N1070.S, N1092, N795.S, N797.S, N808.S, N811.S, N826.S, N830.S, N832.S, N840.S, N945.S, N960.S, N968.S, N1091, N805.S, N822.S, N928.S, N936.S, N1078.S, and N913.S.

[009] In some embodiments, the therapeutic bacterial composition comprises at least one bacterial entity, wherein said bacterial entity is capable of forming the network ecology in combination with one more bacterial entities present in the gastrointestinal tract of the mammalian subject at the time of the administering or thereafter. In certain embodiments, the network ecology is selected from the group consisting of N1008, N1023, N1051, N1061, N1070.S, N1088, N1089, N1092, N381.S, N382.S, N387.S, N399.S, N400.S, N402.S, N403.S, N414.S, N429.S, N430.S, N432.S, N433.S, N436.S, N437.S, N439.S, N441.S, N447.S, N448.S, N457.S, N460.S, N462.S, N463.S, N464.S, N470.S, N474.S, N488.S, N490.S, N493.S, N508.S, N509.S, N510.S, N511.S, N512.S, N514.S, N515.S, N517.S, N518.S, N519.S, N520.S, N523.S, N524.S, N529.S, N539.S, N543.S, N546.S, N547.S, N548.S, N570.S, N574.S, N577.S, N579.S, N580.S, N582.S, N584.S, N585.S, N589.S, N591.S, N597.S, N602.S, N604.S, N609.S, N610.S, N611.S, N612.S, N614.S, N616.S, N621.S, N623.S, N625.S, N648.S, N651.S, N652.S, N653.S, N654.S, N655.S, N660.S, N663.S, N664, N665.S, N666.S, N669.S, N672.S, N676.S, N681.S, N687, N689, N690.S, N692.S, N693, N695.S, N698.S, N703.S, N709, N712.S, N714.S, N730, N734.S, N737.S, N738.S, N769, N775.S, N777.S, N779, N780.S, N781, N785, N788, N792, N793.S, N794, N797.S, N798.S, N802, N804, N807, N817.S, N827.S, N828, N830.S, N832.S, N833.S, N836.S, N840.S, N841, N844, N845, N849, N852, N858, N859, N860, N869.S, N871.S, N874.S, N875, N878, N880, N881, N885, N894, N898.S, N907.S, N913.S, N925, N927, N942, N947, N961, N968.S, N972, N982, N983, N986.S, N987, N988, N996, and N998.S.

[010] In one embodiment, the network ecology consists essentially of N1008, N1023, N1051, N1061, N1070.S, N1088, N1089, N1092, N381.S, N382.S, N387.S, N399.S, N400.S, N402.S, N403.S, N414.S, N429.S, N430.S, N432.S, N433.S, N436.S, N437.S, N439.S, N441.S, N447.S, N448.S, N457.S, N460.S, N462.S, N463.S, N464.S, N470.S, N474.S, N488.S, N490.S, N493.S, N508.S, N509.S, N510.S, N511.S, N512.S, N514.S, N515.S, N517.S, N518.S, N519.S, N520.S, N523.S, N524.S, N529.S, N539.S, N543.S, N546.S, N547.S, N548.S, N570.S, N574.S, N577.S, N579.S, N580.S, N582.S, N584.S, N585.S, N589.S, N591.S, N597.S, N602.S, N604.S, N609.S, N610.S, N611.S, N612.S, N614.S, N616.S, N621.S, N623.S, N625.S, N648.S, N651.S, N652.S, N653.S, N654.S, N655.S, N660.S, N663.S, N664, N665.S, N666.S, N669.S, N672.S, N676.S, N681.S, N687, N689, N690.S, N692.S, N693, N695.S, N698.S, N703.S, N709, N712.S, N714.S, N730, N734.S, N737.S, N738.S, N769, N775.S, N777.S, N779, N780.S, N781, N785, N788, N792, N793.S, N794, N797.S, N798.S, N802, N804, N807, N817.S, N827.S, N828, N830.S, N832.S, N833.S, N836.S, N840.S, N841, N844, N845, N849, N852, N858, N859, N860, N869.S, N871.S,

N874.S, N875, N878, N880, N881, N885, N894, N898.S, N907.S, N913.S, N925, N927, N942, N947, N961, N968.S, N972, N982, N983, N986.S, N987, N988, N996, or N998.S.

[011] In another embodiment, the network ecology is selected from the group consisting of N387.S, N399.S, N512.S, N462.S, N651.S, N982, and N845. In one embodiment, network ecology comprises N387.S and the therapeutic bacterial composition comprises at least one bacterium selected from each of clade_262, clade_396, clade_444, clade_478, clade_500, and clade_553. In another embodiment, the network ecology comprises N387.S and the therapeutic bacterial composition consists essentially of at least one bacterium selected from each of clade_262, clade_396, clade_444, clade_478, clade_500, and clade_553. In certain embodiments, clade_262 comprises one or more bacteria selected from the group consisting Clostridium glycyrrhizinilyticum, Clostridium nexile, Coprococcus comes, Lachnospiraceae bacterium 1_1_57FAA, Lachnospiraceae bacterium 1_4_56FAA, Lachnospiraceae bacterium 8_1_57FAA, Ruminococcus lactaris, and Ruminococcus torques, wherein clade_396 comprises one or more bacteria selected from the group consisting Acetivibrio ethanolgignens, Anaerosporobacter mobilis, Bacteroides pectinophilus, Clostridium aminovalericum, Clostridium phytofermentans, Eubacterium hallii, and Eubacterium xylanophilum, wherein clade_444 comprises one or more bacteria selected from the group consisting Butyrivibrio fibrisolvens, Eubacterium rectale, Eubacterium sp. oral clone GI038, Lachnobacterium bovis, Roseburia cecicola, Roseburia faecalis, Roseburia faecis, Roseburia hominis, Roseburia intestinalis, Roseburia inulinivorans, Roseburia sp. 11SE37, Roseburia sp. 11SE38, Shuttleworthia satelles, Shuttleworthia sp. MSX8B, and Shuttleworthia sp. oral taxon G69, wherein clade_478 comprises one or more bacteria selected from the group consisting Faecalibacterium prausnitzii, Gemmiger formicilis, and Subdoligranulum variabile, wherein clade_500 comprises one or more bacteria selected from the group consisting Alistipes finegoldii, Alistipes onderdonkii, Alistipes putredinis, Alistipes shahii, Alistipes sp. HGB5, Alistipes sp. JC50, and Alistipes sp. RMA 9912, and wherein clade_553 comprises one or more bacteria selected from the group consisting Collinsella aerofaciens, Collinsella intestinalis, Collinsella stercoris, and Collinsella tanakaei.

[012] In one embodiment, clade_262 comprises one or more bacteria of Ruminococcus torques, wherein clade_396 comprises one or more bacteria of Eubacterium hallii, wherein clade_444 comprises one or more bacteria selected from the group consisting of Eubacterium rectale and Roseburia inulinivorans, wherein clade_478 comprises one or more bacteria of Faecalibacterium prausnitzii, wherein clade_500 comprises one or more bacteria of Alistipes putredinis, and wherein clade_553 comprises one or more bacteria of Collinsella aerofaciens.

[013] In another embodiment, clade_262 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1048, Seq. ID No.: 1049, Seq. ID No.: 1057, Seq. ID No.: 1663, Seq. ID No.: 1670, Seq. ID No.: 588, Seq. ID No.: 607, and Seq. ID No.: 674, wherein clade_396 comprises one more bacteria selected from the

group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 161, Seq. ID No.: 288, Seq. ID No.: 551, Seq. ID No.: 6, Seq. ID No.: 613, Seq. ID No.: 848, and Seq. ID No.: 875, wherein clade_444 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1045, Seq. ID No.: 1634, Seq. ID No.: 1635, Seq. ID No.: 1636, Seq. ID No.: 1637, Seq. ID No.: 1638, Seq. ID No.: 1639, Seq. ID No.: 1640, Seq. ID No.: 1641, Seq. ID No.: 1728, Seq. ID No.: 1729, Seq. ID No.: 1730, Seq. ID No.: 456, Seq. ID No.: 856, and Seq. ID No.: 865, wherein clade_478 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1896, Seq. ID No.: 880, and Seq. ID No.: 932, wherein clade_500 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 129, Seq. ID No.: 131, Seq. ID No.: 132, Seq. ID No.: 133, Seq. ID No.: 134, Seq. ID No.: 135, and Seq. ID No.: 136, and wherein clade_553 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 659, Seq. ID No.: 660, Seq. ID No.: 661, and Seq. ID No.: 662.

[014] In other embodiments, clade_262 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1048, Seq. ID No.: 1049, Seq. ID No.: 1057, Seq. ID No.: 1663, Seq. ID No.: 1670, Seq. ID No.: 588, Seq. ID No.: 607, and Seq. ID No.: 674, wherein clade_396 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 161, Seq. ID No.: 288, Seq. ID No.: 551, Seq. ID No.: 6, Seq. ID No.: 613, Seq. ID No.: 848, and Seq. ID No.: 875, wherein clade_444 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1045, Seq. ID No.: 1634, Seq. ID No.: 1635, Seq. ID No.: 1636, Seq. ID No.: 1637, Seq. ID No.: 1638, Seq. ID No.: 1639, Seq. ID No.: 1640, Seq. ID No.: 1641, Seq. ID No.: 1728, Seq. ID No.: 1729, Seq. ID No.: 1730, Seq. ID No.: 456, Seq. ID No.: 856, and Seq. ID No.: 865, wherein clade_478 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1896, Seq. ID No.: 880, and Seq. ID No.: 932, wherein clade_500 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 129, Seq. ID No.: 131, Seq. ID No.: 132, Seq. ID No.: 133, Seq. ID No.: 134, Seq. ID No.: 135, and Seq. ID No.: 136, and wherein clade_553 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 659, Seq. ID No.: 660, Seq. ID No.: 661, and Seq. ID No.: 662.

[015] In one embodiment, clade_262 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1670, wherein clade_396 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 848, wherein clade_444 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1639 and Seq. ID No.: 856, wherein clade_478 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences

having 97% or greater identity to Seq. ID No.: 880, wherein clade_500 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 132, and wherein clade_553 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 659.

[016] In other embodiments, clade_262 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1670, wherein clade_396 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 848, wherein clade_444 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1639 and Seq. ID No.: 856, wherein clade_478 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 880, wherein clade_500 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 132, and wherein clade_553 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 659.

[017] In another embodiment, network ecology comprises N399.S and the therapeutic bacterial composition comprises at least one bacterium selected from each of clade_262, clade_360, clade_396, clade_444, clade_478, and clade_494. In yet another embodiment, the network ecology comprises N399.S and the therapeutic bacterial composition consists essentially of at least one bacterium selected from each of clade_262, clade_360, clade_396, clade_444, clade_478, and clade_494.

[018] In some embodiments, clade_262 comprises one or more bacteria selected from the group consisting of Clostridium glycyrrhizinilyticum, Clostridium nexile, Coprococcus comes, Lachnospiraceae bacterium 1_1_57FAA, Lachnospiraceae bacterium 1_4_56FAA, Lachnospiraceae bacterium 8_1_57FAA, Ruminococcus lactaris, and Ruminococcus torques, wherein clade_360 comprises one or more bacteria selected from the group consisting of Dorea formicigenerans, Dorea longicatena, Lachnospiraceae bacterium 2_1_46FAA, Lachnospiraceae bacterium 2_1_58FAA, Lachnospiraceae bacterium 4_1_37FAA, Lachnospiraceae bacterium 9_1_43BFAA, Ruminococcus gnavus, and Ruminococcus sp. ID8, wherein clade_396 comprises one or more bacteria selected from the group consisting of Acetivibrio ethanolgignens, Anaerosporobacter mobilis, Bacteroides pectinophilus, Clostridium aminovalericum, Clostridium phytofermentans, Eubacterium hallii, and Eubacterium xylanophilum, wherein clade_444 comprises one or more bacteria selected from the group consisting of Butyrivibrio fibrisolvens, Eubacterium rectale, Eubacterium sp. oral clone GI038, Lachnobacterium bovis, Roseburia cecicola, Roseburia faecalis, Roseburia faecis, Roseburia hominis, Roseburia intestinalis, Roseburia inulinivorans, Roseburia sp. 11SE37, Roseburia sp. 11SE38, Shuttleworthia satelles, Shuttleworthia sp. MSX8B, and Shuttleworthia sp. oral taxon G69, wherein clade_478 comprises one or more bacteria selected from the group consisting of Faecalibacterium prausnitzii, Gemmiger formicilis, and Subdoligranulum variabile, and wherein clade_494 comprises one or more bacteria selected from the group consisting of Clostridium orbiscindens, Clostridium sp.

NML 04A032, Flavonifractor plautii, Pseudoflavonifractor capillosus, and Ruminococcaceae bacterium D16.

[019] In another embodiment, clade_262 comprises one or more bacteria of Ruminococcus torques, wherein clade_360 comprises one or more bacteria of Dorea longicatena, wherein clade_396 comprises one or more bacteria of Eubacterium hallii, wherein clade_444 comprises one or more bacteria of Eubacterium rectale, wherein clade_478 comprises one or more bacteria of Faecalibacterium prausnitzii, and wherein clade_494 comprises one or more bacteria of Pseudoflavonifractor capillosus.

[020] In one embodiment, clade_262 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1048, Seq. ID No.: 1049, Seq. ID No.: 1057, Seq. ID No.: 1663, Seq. ID No.: 1670, Seq. ID No.: 588, Seq. ID No.: 607, and Seq. ID No.: 674, wherein clade_360 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1050, Seq. ID No.: 1051, Seq. ID No.: 1053, Seq. ID No.: 1058, Seq. ID No.: 1661, Seq. ID No.: 1668, Seq. ID No.: 773, and Seq. ID No.: 774, wherein clade_396 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 161, Seq. ID No.: 288, Seq. ID No.: 551, Seq. ID No.: 6, Seq. ID No.: 613, Seq. ID No.: 848, and Seq. ID No.: 875, wherein clade_444 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1045, Seq. ID No.: 1634, Seq. ID No.: 1635, Seq. ID No.: 1636, Seq. ID No.: 1637, Seq. ID No.: 1638, Seq. ID No.: 1639, Seq. ID No.: 1640, Seq. ID No.: 1641, Seq. ID No.: 1728, Seq. ID No.: 1729, Seq. ID No.: 1730, Seq. ID No.: 456, Seq. ID No.: 856, and Seq. ID No.: 865, wherein clade_478 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1896, Seq. ID No.: 880, and Seq. ID No.: 932, and wherein clade_494 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1591, Seq. ID No.: 1655, Seq. ID No.: 609, Seq. ID No.: 637, and Seq. ID No.: 886.

[021] In some embodiments, clade_262 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1048, Seq. ID No.: 1049, Seq. ID No.: 1057, Seq. ID No.: 1663, Seq. ID No.: 1670, Seq. ID No.: 588, Seq. ID No.: 607, and Seq. ID No.: 674, wherein clade_360 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1050, Seq. ID No.: 1051, Seq. ID No.: 1053, Seq. ID No.: 1058, Seq. ID No.: 1661, Seq. ID No.: 1668, Seq. ID No.: 773, and Seq. ID No.: 774, wherein clade_396 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 161, Seq. ID No.: 288, Seq. ID No.: 551, Seq. ID No.: 6, Seq. ID No.: 613, Seq. ID No.: 848, and Seq. ID No.: 875, wherein clade_444 comprises one more bacteria selected from the group

consisting of bacteria having 16S sequences Seq. ID No.: 1045, Seq. ID No.: 1634, Seq. ID No.: 1635, Seq. ID No.: 1636, Seq. ID No.: 1637, Seq. ID No.: 1638, Seq. ID No.: 1639, Seq. ID No.: 1640, Seq. ID No.: 1641, Seq. ID No.: 1728, Seq. ID No.: 1729, Seq. ID No.: 1730, Seq. ID No.: 456, Seq. ID No.: 856, and Seq. ID No.: 865, wherein clade_478 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1896, Seq. ID No.: 880, and Seq. ID No.: 932, and wherein clade_494 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1591, Seq. ID No.: 1655, Seq. ID No.: 609, Seq. ID No.: 637, and Seq. ID No.: 886.

[022] In other embodiments, clade_262 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1670, wherein clade_360 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 774, wherein clade_396 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 848, wherein clade_444 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 856, wherein clade_478 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 880, and wherein clade_494 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1591.

[023] In one aspect, clade_262 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1670, wherein clade_360 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 774, wherein clade_396 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 848, wherein clade_444 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 856, wherein clade_478 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 880, and wherein clade_494 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1591.

[024] In another aspect, the network ecology comprises N462.S and the therapeutic bacterial composition comprises at least one bacterium selected from each of clade_262, clade_360, and clade_478. In yet another aspect, the network ecology comprises N462.S and the therapeutic bacterial composition consists essentially of at least one bacterium selected from each of clade_262, clade_360, and clade_478.

[025] In other aspects, clade_262 comprises one or more bacteria selected from the group consisting of Clostridium glycyrrhizinilyticum, Clostridium nexile, Coprococcus comes, Lachnospiraceae bacterium 1_1_57FAA, Lachnospiraceae bacterium 1_4_56FAA, Lachnospiraceae

bacterium 8_1_57FAA, Ruminococcus lactaris, and Ruminococcus torques, wherein clade_360 comprises one or more bacteria selected from the group consisting of Dorea formicigenerans, Dorea longicatena, Lachnospiraceae bacterium 2_1_46FAA, Lachnospiraceae bacterium 2_1_58FAA, Lachnospiraceae bacterium 4_1_37FAA, Lachnospiraceae bacterium 9_1_43BFAA, Ruminococcus gnavus, and Ruminococcus sp. ID8, and wherein clade_478 comprises one or more bacteria selected from the group consisting of Faecalibacterium prausnitzii, Gemmiger formicilis, and Subdoligranulum variabile.

[026] In another aspect, clade_262 comprises one or more bacteria of Coprococcus comes, wherein clade_360 comprises one or more bacteria of Dorea longicatena, and wherein clade_478 comprises one or more bacteria selected from the group consisting Faecalibacterium prausnitzii and Subdoligranulum variabile.

[027] In yet another aspect, clade_262 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1048, Seq. ID No.: 1049, Seq. ID No.: 1057, Seq. ID No.: 1663, Seq. ID No.: 1670, Seq. ID No.: 588, Seq. ID No.: 607, and Seq. ID No.: 674, wherein clade_360 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1050, Seq. ID No.: 1051, Seq. ID No.: 1053, Seq. ID No.: 1058, Seq. ID No.: 1661, Seq. ID No.: 1668, Seq. ID No.: 773, and Seq. ID No.: 774, and wherein clade_478 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1896, Seq. ID No.: 880, and Seq. ID No.: 932.

[028] In certain aspects, clade_262 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1048, Seq. ID No.: 1049, Seq. ID No.: 1057, Seq. ID No.: 1663, Seq. ID No.: 1670, Seq. ID No.: 588, Seq. ID No.: 607, and Seq. ID No.: 674, wherein clade_360 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1050, Seq. ID No.: 1051, Seq. ID No.: 1053, Seq. ID No.: 1058, Seq. ID No.: 1661, Seq. ID No.: 1668, Seq. ID No.: 773, and Seq. ID No.: 774, and wherein clade_478 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1896, Seq. ID No.: 880, and Seq. ID No.: 932.

[029] In another aspect, clade_262 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 674, wherein clade_360 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 774, and wherein clade_478 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1896 and Seq. ID No.: 880.

[030] In other aspects, clade_262 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 674, wherein clade_360 comprises one or

more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 774, and wherein clade_478 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1896 and Seq. ID No.: 880.

[031] In another embodiment, network ecology comprises N512.S and the therapeutic bacterial composition comprises at least one bacterium selected from each of clade_262, clade_360, and clade_444. In one embodiment, the network ecology comprises N512.S and the therapeutic bacterial composition consists essentially of at least one bacterium selected from each of clade_262, clade_360, and clade_444.

[032] In other embodiments, clade_262 comprises one or more bacteria selected from the group consisting of Clostridium glycyrrhizinilyticum, Clostridium nexile, Coprococcus comes, Lachnospiraceae bacterium 1_1_57FAA, Lachnospiraceae bacterium 1_4_56FAA, Lachnospiraceae bacterium 8_1_57FAA, Ruminococcus lactaris, and Ruminococcus torques, wherein clade_360 comprises one or more bacteria selected from the group consisting of Dorea formicigenerans, Dorea longicatena, Lachnospiraceae bacterium 2_1_46FAA, Lachnospiraceae bacterium 2_1_58FAA, Lachnospiraceae bacterium 4_1_37FAA, Lachnospiraceae bacterium 9_1_43BFAA, Ruminococcus gnavus, and Ruminococcus sp. ID8, and wherein clade_444 comprises one or more bacteria selected from the group consisting of Butyrivibrio fibrisolvens, Eubacterium rectale, Eubacterium sp. oral clone GI038, Lachnobacterium bovis, Roseburia cecicola, Roseburia faecalis, Roseburia faecis, Roseburia hominis, Roseburia intestinalis, Roseburia inulinivorans, Roseburia sp. 11SE37, Roseburia sp. 11SE38, Shuttleworthia satelles, Shuttleworthia sp. MSX8B, and Shuttleworthia sp. oral taxon G69.

[033] In certain embodiments, clade_262 comprises one or more bacteria selected from the group consisting of Coprococcus comes and Ruminococcus torques, wherein clade_360 comprises one or more bacteria of Dorea longicatena, and wherein clade_444 comprises one or more bacteria of Eubacterium rectale.

[034] In one embodiment, clade_262 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1048, Seq. ID No.: 1049, Seq. ID No.: 1057, Seq. ID No.: 1663, Seq. ID No.: 1670, Seq. ID No.: 588, Seq. ID No.: 607, and Seq. ID No.: 674, wherein clade_360 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1050, Seq. ID No.: 1051, Seq. ID No.: 1053, Seq. ID No.: 1058, Seq. ID No.: 1661, Seq. ID No.: 1668, Seq. ID No.: 773, and Seq. ID No.: 774, and wherein clade_444 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1045, Seq. ID No.: 1634, Seq. ID No.: 1635, Seq. ID No.: 1636, Seq. ID No.: 1637, Seq. ID No.: 1638, Seq. ID No.: 1639, Seq. ID No.: 1640, Seq. ID No.: 1641, Seq. ID No.: 1728, Seq. ID No.: 1729, Seq. ID No.: 1730, Seq. ID No.: 456, Seq. ID No.: 856, and Seq. ID No.: 865.

[035] In another embodiment, clade_262 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1048, Seq. ID No.: 1049, Seq. ID No.: 1057, Seq. ID No.: 1663, Seq. ID No.: 1670, Seq. ID No.: 588, Seq. ID No.: 607, and Seq. ID No.: 674, wherein clade_360 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1050, Seq. ID No.: 1051, Seq. ID No.: 1053, Seq. ID No.: 1058, Seq. ID No.: 1661, Seq. ID No.: 1668, Seq. ID No.: 773, and Seq. ID No.: 774, and wherein clade_444 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1045, Seq. ID No.: 1634, Seq. ID No.: 1635, Seq. ID No.: 1636, Seq. ID No.: 1637, Seq. ID No.: 1638, Seq. ID No.: 1639, Seq. ID No.: 1640, Seq. ID No.: 1641, Seq. ID No.: 1728, Seq. ID No.: 1729, Seq. ID No.: 1730, Seq. ID No.: 456, Seq. ID No.: 856, and Seq. ID No.: 865.

[036] In certain embodiments, clade_262 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1670 and Seq. ID No.: 674, wherein clade_360 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 774, and wherein clade_444 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 856.

[037] In one aspect, clade_262 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1670 and Seq. ID No.: 674, wherein clade_360 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 774, and wherein clade_444 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 856.

[038] In another aspect, the network ecology comprises N845 and the therapeutic bacterial composition comprises at least one bacterium selected from each of clade_262, clade_360, and clade_378. In certain aspects, the network ecology comprises N845 and the therapeutic bacterial composition consists essentially of at least one bacterium selected from each of clade_262, clade_360, and clade_378.

[039] In other aspects, clade_262 comprises one or more bacteria selected from the group consisting of Clostridium glycyrrhizinilyticum, Clostridium nexile, Coprococcus comes, Lachnospiraceae bacterium 1_1_57FAA, Lachnospiraceae bacterium 1_4_56FAA, Lachnospiraceae bacterium 8_1_57FAA, Ruminococcus lactaris, and Ruminococcus torques, wherein clade_360 comprises one or more bacteria selected from the group consisting of Dorea formicigenerans, Dorea longicatena, Lachnospiraceae bacterium 2_1_46FAA, Lachnospiraceae bacterium 2_1_58FAA, Lachnospiraceae bacterium 4_1_37FAA, Lachnospiraceae bacterium 9_1_43BFAA, Ruminococcus gnavus, and Ruminococcus sp. ID8, and wherein clade_378 comprises one or more bacteria selected from the group consisting of Bacteroides barnesiae, Bacteroides coprocola, Bacteroides coprophilus,

Bacteroides dorei, Bacteroides massiliensis, Bacteroides plebeius, Bacteroides sp. 3_1_33FAA, Bacteroides sp. 3_1_40A, Bacteroides sp. 4_3_47FAA, Bacteroides sp. 9_1_42FAA, Bacteroides sp. NB_8, and Bacteroides vulgatus.

[040] In certain aspects, clade_262 comprises one or more bacteria of Coprococcus comes, wherein clade_360 comprises one or more bacteria of Dorea longicatena, and wherein clade_378 comprises one or more bacteria of Bacteroides dorei.

[041] In another aspect, clade_262 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1048, Seq. ID No.: 1049, Seq. ID No.: 1057, Seq. ID No.: 1663, Seq. ID No.: 1670, Seq. ID No.: 588, Seq. ID No.: 607, and Seq. ID No.: 674, wherein clade_360 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1050, Seq. ID No.: 1051, Seq. ID No.: 1053, Seq. ID No.: 1058, Seq. ID No.: 1661, Seq. ID No.: 1668, Seq. ID No.: 773, and Seq. ID No.: 774, and wherein clade_378 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 267, Seq. ID No.: 272, Seq. ID No.: 273, Seq. ID No.: 274, Seq. ID No.: 284, Seq. ID No.: 289, Seq. ID No.: 309, Seq. ID No.: 310, Seq. ID No.: 313, Seq. ID No.: 314, Seq. ID No.: 323, and Seq. ID No.: 331.

[042] In certain aspects, clade_262 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1048, Seq. ID No.: 1049, Seq. ID No.: 1057, Seq. ID No.: 1663, Seq. ID No.: 1670, Seq. ID No.: 588, Seq. ID No.: 607, and Seq. ID No.: 674, wherein clade_360 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1050, Seq. ID No.: 1051, Seq. ID No.: 1053, Seq. ID No.: 1058, Seq. ID No.: 1661, Seq. ID No.: 1668, Seq. ID No.: 773, and Seq. ID No.: 774, and wherein clade_378 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 267, Seq. ID No.: 272, Seq. ID No.: 273, Seq. ID No.: 274, Seq. ID No.: 284, Seq. ID No.: 289, Seq. ID No.: 309, Seq. ID No.: 310, Seq. ID No.: 313, Seq. ID No.: 314, Seq. ID No.: 323, and Seq. ID No.: 331.

[043] In one embodiment, clade_262 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 674, wherein clade_360 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 774, and wherein clade_378 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 274.

[044] In another embodiment, clade_262 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 674, wherein clade_360 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 774,

and wherein clade_378 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 274.

[045] In some embodiments, the network ecology comprises N982 and the therapeutic bacterial composition comprises at least one bacterium selected from each of clade_172, clade_262, and clade_396. In another embodiment, the network ecology comprises N982 and the therapeutic bacterial composition consists essentially of at least one bacterium selected from each of clade_172, clade_262, and clade_396.

[046] In certain aspects, clade_172 comprises one or more bacteria selected from the group consisting of Bifidobacteriaceae genomosp. C1, Bifidobacterium adolescentis, Bifidobacterium angulatum, Bifidobacterium animalis, Bifidobacterium breve, Bifidobacterium catenulatum, Bifidobacterium dentium, Bifidobacterium gallicum, Bifidobacterium infantis, Bifidobacterium kashiwanohense, Bifidobacterium longum, Bifidobacterium pseudocatenulatum, Bifidobacterium pseudolongum, Bifidobacterium scardovii, Bifidobacterium sp. HM2, Bifidobacterium sp. HMLN12, Bifidobacterium sp. M45, Bifidobacterium sp. MSX5B, Bifidobacterium sp. TM_7, and Bifidobacterium thermophilum, wherein clade_262 comprises one or more bacteria selected from the group consisting of Clostridium glycyrrhizinilyticum, Clostridium nexile, Coprococcus comes, Lachnospiraceae bacterium 1_1_57FAA, Lachnospiraceae bacterium 1_4_56FAA, Lachnospiraceae bacterium 8_1_57FAA, Ruminococcus lactaris, and Ruminococcus torques, and wherein clade_396 comprises one or more bacteria selected from the group consisting of Acetivibrio ethanolgignens, Anaerosporobacter mobilis, Bacteroides pectinophilus, Clostridium aminovalericum, Clostridium phytofermentans, Eubacterium hallii, and Eubacterium xylanophilum.

[047] In another aspect, clade_172 comprises one or more bacteria of Bifidobacterium longum, wherein clade_262 comprises one or more bacteria of Coprococcus comes, and wherein clade_396 comprises one or more bacteria of Eubacterium hallii.

[048] In one aspect, clade_172 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 345, Seq. ID No.: 346, Seq. ID No.: 347, Seq. ID No.: 348, Seq. ID No.: 350, Seq. ID No.: 351, Seq. ID No.: 352, Seq. ID No.: 353, Seq. ID No.: 354, Seq. ID No.: 355, Seq. ID No.: 356, Seq. ID No.: 357, Seq. ID No.: 358, Seq. ID No.: 359, Seq. ID No.: 360, Seq. ID No.: 361, Seq. ID No.: 362, Seq. ID No.: 363, Seq. ID No.: 364, and Seq. ID No.: 365, wherein clade_262 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1048, Seq. ID No.: 1049, Seq. ID No.: 1057, Seq. ID No.: 1663, Seq. ID No.: 1670, Seq. ID No.: 588, Seq. ID No.: 607, and Seq. ID No.: 674, and wherein clade_396 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 161, Seq. ID No.: 288, Seq. ID No.: 551, Seq. ID No.: 6, Seq. ID No.: 613, Seq. ID No.: 848, and Seq. ID No.: 875.

[049] In another aspect, clade_172 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 345, Seq. ID No.: 346, Seq. ID No.: 347, Seq. ID No.: 348, Seq. ID No.: 350, Seq. ID No.: 351, Seq. ID No.: 352, Seq. ID No.: 353, Seq. ID No.: 354, Seq. ID No.: 355, Seq. ID No.: 356, Seq. ID No.: 357, Seq. ID No.: 358, Seq. ID No.: 359, Seq. ID No.: 360, Seq. ID No.: 361, Seq. ID No.: 362, Seq. ID No.: 363, Seq. ID No.: 364, and Seq. ID No.: 365, wherein clade_262 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1048, Seq. ID No.: 1049, Seq. ID No.: 1057, Seq. ID No.: 1663, Seq. ID No.: 1670, Seq. ID No.: 588, Seq. ID No.: 607, and Seq. ID No.: 674, and wherein clade_396 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 161, Seq. ID No.: 288, Seq. ID No.: 551, Seq. ID No.: 6, Seq. ID No.: 613, Seq. ID No.: 848, and Seq. ID No.: 875.

[050] In another aspect, clade_172 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 356, wherein clade_262 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 674, and wherein clade_396 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 848.

[051] In certain aspects, clade_172 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 356, wherein clade_262 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 674, and wherein clade_396 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 848.

[052] In another embodiment, the network ecology comprises N651.S and the therapeutic bacterial composition comprises at least one bacterium selected from each of clade_444, clade_516, and clade_522. In yet another embodiment, the network ecology comprises N651.S and the therapeutic bacterial composition consists essentially of at least one bacterium selected from each of clade_444, clade_516, and clade_522.

[053] In one embodiment, clade_444 comprises one or more bacteria selected from the group consisting of Butyrivibrio fibrisolvens, Eubacterium rectale, Eubacterium sp. oral clone GI038, Lachnobacterium bovis, Roseburia cecicola, Roseburia faecalis, Roseburia faecis, Roseburia hominis, Roseburia intestinalis, Roseburia inulinivorans, Roseburia sp. 11SE37, Roseburia sp. 11SE38, Shuttleworthia satelles, Shuttleworthia sp. MSX8B, and Shuttleworthia sp. oral taxon G69, wherein clade_516 comprises one or more bacteria selected from the group consisting of Anaerotruncus colihominis, Clostridium methylpentosum, Clostridium sp. YIT 12070, Hydrogenoanaerobacterium saccharovorans, Ruminococcus albus, and Ruminococcus flavefaciens, and wherein clade_522 comprises one or more bacteria selected from the group consisting of Bacteroides galacturonicus,

Eubacterium eligens, Lachnospira multipara, Lachnospira pectinoschiza, and Lactobacillus rogosae. In another embodiment, clade_444 comprises one or more bacteria of Roseburia inulinivorans, wherein clade_516 comprises one or more bacteria of Anaerotruncus colihominis, and wherein clade_522 comprises one or more bacteria of Eubacterium eligens. In some embodiments, clade_444 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1045, Seq. ID No.: 1634, Seq. ID No.: 1635, Seq. ID No.: 1636, Seq. ID No.: 1637, Seq. ID No.: 1638, Seq. ID No.: 1639, Seq. ID No.: 1640, Seq. ID No.: 1641, Seq. ID No.: 1728, Seq. ID No.: 1729, Seq. ID No.: 1730, Seq. ID No.: 456, Seq. ID No.: 856, and Seq. ID No.: 865, wherein clade_516 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1005, Seq. ID No.: 164, Seq. ID No.: 1656, Seq. ID No.: 1660, Seq. ID No.: 606, and Seq. ID No.: 642, and wherein clade_522 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1046, Seq. ID No.: 1047, Seq. ID No.: 1114, Seq. ID No.: 280, and Seq. ID No.: 845.

[054] In other embodiments, clade_444 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1045, Seq. ID No.: 1634, Seq. ID No.: 1635, Seq. ID No.: 1636, Seq. ID No.: 1637, Seq. ID No.: 1638, Seq. ID No.: 1639, Seq. ID No.: 1640, Seq. ID No.: 1641, Seq. ID No.: 1728, Seq. ID No.: 1729, Seq. ID No.: 1730, Seq. ID No.: 456, Seq. ID No.: 856, and Seq. ID No.: 865, wherein clade_516 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1005, Seq. ID No.: 164, Seq. ID No.: 1656, Seq. ID No.: 1660, Seq. ID No.: 606, and Seq. ID No.: 642, and wherein clade_522 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1046, Seq. ID No.: 1047, Seq. ID No.: 1114, Seq. ID No.: 280, and Seq. ID No.: 845.

[055] In one embodiment, clade_444 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1639, wherein clade_516 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 164, and wherein clade_522 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 845.

[056] In one aspect, clade_444 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1639, wherein clade_516 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 164, and wherein clade_522 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 845.

[057] In another aspect, the composition further comprises a pharmaceutically-acceptable excipient. In one aspect, the therapeutic bacterial composition is substantially depleted of a residual

habitat product of a fecal material. In certain aspects, the composition is formulated for oral administration. In other embodiemtns, the composition is capable of inducing the formation of IgA, RegIII-gamma, IL-10, regulatory T cells, TGF-beta, alpha-defensin, beta-defensin, or an antimicrobial peptide in the mammalian subject. In another embodiment, the composition is comestible.

[058] The invention provides a composition, comprising any of the compositions administered according to the methods described above. The invention also includes a dosage unit comprising predetermined ratios of the isolated bacteria present in the network ecology as described above.

[059] The invention provides a method for producing short chain fatty acids (SCFA) within a mammalian subject, comprising:administering to said mammalian subject in need thereof an effective amount of a therapeutic bacterial composition, said therapeutic bacterial composition comprising a plurality of isolated bacteria or a purified bacterial preparation, the plurality of isolated bacteria of the purified bacterial preparation capable of forming one or a plurality of bacterial functional pathways, the one or plurality of bacterial functional pathways capable of forming a functional network ecology selected from the group consisting of N262.S, N290.S, N284.S, N271.S, N282.S, N288.S, N302.S, N279.S, N310.S, N323.S, N331.S, N332.S, N301.S, N312.S, N339.S, N325.S, N340.S, N341.S, N346.S, N338.S, N336.S, N345.S, N355.S, N356.S, N343.S, N329.S, N361.S, N353.S, N381.S, N344.S, N352.S, N357.S, N358.S, N369.S, N372.S, N375.S, N380.S, N374.S, N377.S, N368.S, N370.S, N373.S, N376.S, N389.S, N394.S, N431.S, N434.S, N390.S, N397.S, N387.S, N440.S, N396.S, N399.S, N403.S, N414.S, N430.S, N432.S, N436.S, N437.S, N457.S, N545, N386.S, N402.S, N405.S, N415.S, N421.S, N422.S, N423.S, N458.S, N459.S, N493.S, N416.S, N439.S, N447.S, N490.S, N526, N429.S, N433.S, N448.S, N488.S, N508.S, N509.S, N510.S, N511.S, N408.S, N446.S, N451.S, N474.S, N520.S, N521.S, N535.S, N516.S, N463.S, N518.S, N586, N450.S, N465.S, N519.S, N537.S, N419.S, N468.S, N477.S, N514.S, N382.S, N460.S, N462.S, N512.S, N517.S, N523.S, N547.S, N548.S, N577.S, N581.S, N585.S, N616.S, N466.S, N469.S, N480.S, N482.S, N484.S, N515.S, N533.S, N709, N730, N478.S, N572.S, N400.S, N543.S, N582.S, N621.S, N689, N769, N481.S, N525.S, N528.S, N534.S, N574.S, N580.S, N590.S, N591.S, N597.S, N664, N693, N530.S, N687, N470.S, N529.S, N539.S, N546.S, N570.S, N579.S, N602.S, N614.S, N648.S, N652.S, N655.S, N672.S, N681.S, N690.S, N692.S, N698.S, N737.S, N738.S, N785, N841, N878, N880, N881, N987, N988, N996, N1061, N479.S, N538.S, N542.S, N578.S, N609.S, N611.S, N617.S, N666.S, N675.S, N682.S, N844, N845, N846, N852, N876, N982, N1008, N649.S, N657.S, N678.S, N686.S, N710.S, N522.S, N651.S, N653.S, N654.S, N680.S, N712.S, N792, N802, N804, N807, N849, N858, N859, N875, N885, N942, N961, N972, N1051, N587.S, N589.S, N612.S, N625.S, N656.S, N714.S, N779, N781, N828, N829, N860, N894, N925, N927, N935, N947, N983, N1023, N441.S, N584.S, N794, N788, N524.S, N604.S, N610.S, N623.S, N663.S, N669.S, N676.S, N703.S, N775.S, N777.S, N780.S, N817.S, N827.S, N836.S, N871.S, N874.S, N898.S, N907.S, N998.S, N1088, N1089, N660.S, N665.S, N667.S, N733.S, N734.S, N739.S, N741.S, N782.S, N789.S, N796.S, N798.S, N800.S, N809.S, N816.S, N842.S, N843.S, N869.S, N986.S, N995.S,

N1002.S, N1004.S, N1019.S, N1093, N668.S, N685.S, N835.S, N851.S, N464.S, N695.S, N776.S, N793.S, N815.S, N833.S, N891.S, N1070.S, N1092, N795.S, N797.S, N808.S, N811.S, N826.S, N830.S, N832.S, N840.S, N945.S, N960.S, N968.S, N1091, N805.S, N822.S, N928.S, N936.S, N1078.S, and N913.S.

[060] In one embodiment, the functional network ecology is selected from the group consisting of N1008, N1023, N1051, N1061, N1070.S, N1088, N1089, N1092, N381.S, N382.S, N399.S, N400.S, N402.S, N403.S, N414.S, N429.S, N430.S, N432.S, N433.S, N436.S, N437.S, N439.S, N441.S, N447.S, N448.S, N457.S, N460.S, N462.S, N463.S, N464.S, N470.S, N474.S, N488.S, N490.S, N493.S, N508.S, N509.S, N510.S, N511.S, N512.S, N514.S, N515.S, N517.S, N518.S, N519.S, N520.S, N523.S, N524.S, N528.S, N529.S, N539.S, N543.S, N546.S, N547.S, N548.S, N570.S, N574.S, N577.S, N579.S, N580.S, N582.S, N584.S, N585.S, N589.S, N591.S, N597.S, N602.S, N604.S, N609.S, N610.S, N611.S, N612.S, N614.S, N616.S, N621.S, N623.S, N625.S, N648.S, N651.S, N652.S, N653.S, N654.S, N655.S, N660.S, N663.S, N664, N665.S, N666.S, N669.S, N672.S, N676.S, N681.S, N687, N689, N690.S, N692.S, N693, N695.S, N698.S, N703.S, N709, N712.S, N714.S, N730, N734.S, N737.S, N738.S, N769, N775.S, N777.S, N779, N780.S, N781, N785, N788, N792, N793.S, N794, N797.S, N798.S, N802, N804, N807, N817.S, N827.S, N828, N830.S, N832.S, N833.S, N836.S, N840.S, N841, N844, N845, N849, N852, N858, N859, N860, N869.S, N871.S, N874.S, N875, N878, N880, N881, N885, N894, N898.S, N907.S, N913.S, N925, N927, N942, N947, N961, N968.S, N972, N982, N983, N986.S, N987, N988, N996, and N998.S. In another embodiment, the functional network ecology is N528.S, and the plurality of bacterial functional pathways comprises the functional pathways of of KO:K00656, KO:K01069, KO:K01734, KO:K03417, KO:K03778, KO:K07246.

[061] The invention includes a method for catalyzing secondary metabolism of bile acids within a mammalian subject, comprising: administering to said mammalian subject in need thereof an effective amount of a therapeutic bacterial composition, said therapeutic bacterial composition comprising a plurality of isolated bacteria or a purified bacterial preparation, the plurality of isolated bacteria of the purified bacterial preparation capable of forming one or a plurality of bacterial functional pathways, the one or plurality of bacterial functional pathways capable of forming a functional network ecology selected from the group consisting of N262.S, N290.S, N284.S, N271.S, N282.S, N288.S, N302.S, N279.S, N310.S, N323.S, N331.S, N332.S, N301.S, N312.S, N339.S, N325.S, N340.S, N341.S, N346.S, N338.S, N336.S, N345.S, N355.S, N356.S, N343.S, N329.S, N361.S, N353.S, N381.S, N344.S, N352.S, N357.S, N358.S, N369.S, N372.S, N375.S, N380.S, N374.S, N377.S, N368.S, N370.S, N373.S, N376.S, N389.S, N394.S, N431.S, N434.S, N390.S, N397.S, N387.S, N440.S, N396.S, N399.S, N403.S, N414.S, N430.S, N432.S, N436.S, N437.S, N457.S, N545, N386.S, N402.S, N405.S, N415.S, N421.S, N422.S, N423.S, N458.S, N459.S, N493.S, N416.S, N439.S, N447.S, N490.S, N526, N429.S, N433.S, N448.S, N488.S, N508.S, N509.S, N510.S, N511.S, N408.S, N446.S, N451.S, N474.S, N520.S, N521.S, N535.S, N516.S, N463.S, N518.S, N586,

N450.S, N465.S, N519.S, N537.S, N419.S, N468.S, N477.S, N514.S, N382.S, N460.S, N462.S, N512.S, N517.S, N523.S, N547.S, N548.S, N577.S, N581.S, N585.S, N616.S, N466.S, N469.S, N480.S, N482.S, N484.S, N515.S, N533.S, N709, N730, N478.S, N572.S, N400.S, N543.S, N582.S, N621.S, N689, N769, N481.S, N525.S, N528.S, N534.S, N574.S, N580.S, N590.S, N591.S, N597.S, N664, N693, N530.S, N687, N470.S, N529.S, N539.S, N546.S, N570.S, N579.S, N602.S, N614.S, N648.S, N652.S, N655.S, N672.S, N681.S, N690.S, N692.S, N698.S, N737.S, N738.S, N785, N841, N878, N880, N881, N987, N988, N996, N1061, N479.S, N538.S, N542.S, N578.S, N609.S, N611.S, N617.S, N666.S, N675.S, N682.S, N844, N845, N846, N852, N876, N982, N1008, N649.S, N657.S, N678.S, N686.S, N710.S, N522.S, N651.S, N653.S, N654.S, N680.S, N712.S, N792, N802, N804, N807, N849, N858, N859, N875, N885, N942, N961, N972, N1051, N587.S, N589.S, N612.S, N625.S, N656.S, N714.S, N779, N781, N828, N829, N860, N894, N925, N927, N935, N947, N983, N1023, N441.S, N584.S, N794, N788, N524.S, N604.S, N610.S, N623.S, N663.S, N669.S, N676.S, N703.S, N775.S, N777.S, N780.S, N817.S, N827.S, N836.S, N871.S, N874.S, N898.S, N907.S, N998.S, N1088, N1089, N660.S, N665.S, N667.S, N733.S, N734.S, N739.S, N741.S, N782.S, N789.S, N796.S, N798.S, N800.S, N809.S, N816.S, N842.S, N843.S, N869.S, N986.S, N995.S, N1002.S, N1004.S, N1019.S, N1093, N668.S, N685.S, N835.S, N851.S, N464.S, N695.S, N776.S, N793.S, N815.S, N833.S, N891.S, N1070.S, N1092, N795.S, N797.S, N808.S, N811.S, N826.S, N830.S, N832.S, N840.S, N945.S, N960.S, N968.S, N1091, N805.S, N822.S, N928.S, N936.S, N1078.S, and N913.S.

[062] In one embodiment, the functional network ecology is selected from the group consisting of N1008, N1023, N1051, N1061, N1070.S, N1088, N1089, N1092, N381.S, N382.S, N399.S, N400.S, N402.S, N403.S, N414.S, N429.S, N430.S, N432.S, N433.S, N436.S, N437.S, N439.S, N441.S, N447.S, N448.S, N457.S, N460.S, N462.S, N463.S, N464.S, N470.S, N474.S, N488.S, N490.S, N493.S, N508.S, N509.S, N510.S, N511.S, N512.S, N514.S, N515.S, N517.S, N518.S, N519.S, N520.S, N523.S, N524.S, N529.S, N539.S, N543.S, N546.S, N547.S, N548.S, N570.S, N574.S, N577.S, N579.S, N580.S, N582.S, N584.S, N585.S, N589.S, N591.S, N597.S, N602.S, N604.S, N609.S, N610.S, N611.S, N612.S, N614.S, N616.S, N621.S, N623.S, N625.S, N648.S, N651.S, N652.S, N653.S, N654.S, N655.S, N660.S, N663.S, N664, N665.S, N666.S, N669.S, N672.S, N676.S, N681.S, N687, N689, N690.S, N692.S, N693, N695.S, N698.S, N703.S, N709, N712.S, N714.S, N730, N734.S, N737.S, N738.S, N769, N775.S, N777.S, N779, N780.S, N781, N785, N788, N792, N793.S, N794, N797.S, N798.S, N802, N804, N807, N817.S, N827.S, N828, N830.S, N832.S, N833.S, N836.S, N840.S, N841, N844, N845, N849, N852, N858, N859, N860, N869.S, N871.S, N874.S, N875, N878, N880, N881, N885, N894, N898.S, N907.S, N913.S, N925, N927, N942, N947, N961, N968.S, N972, N982, N983, N986.S, N987, N988, N996, and N998.S. In another embodiment, the functional network ecology is N660.S and the plurality of bacterial functional pathways comprises the functional pathways of of KO:K00656, and KO:K01442.

[063] In some embodiment, the invention includes a composition further comprising a pharmaceutically-acceptable excipient. In one embodiment, the composition is formulated for oral administration. In another embodiment, the composition is capable of inducing the formation of butyrate, propionate, acetate, 7-deoxybile acids, deoxycholate acide (DCA) and lithocholic acid (LCA)in the mammalian subject. In other embodiments, the composition is capable of inducing the depletion of glucose, pyruvate, lactate, cellulose, fructans, starch, xylans, pectins, taurocholate, glycocholate, ursocholate, cholate, glycochenodeoxycholate, taurochenodeoxycholate, ursodeoxycholate, or chenodeoxycholate; or the formation and depletion of intermediary metabolites acetyl-CoA, butyryl-CoA, propanoyl-CoA, chenodeoxycholoyl-CoA, or ursodeoxycholoyl-CoA in the mammalian subject. In another embodiment, the composition is formulated with one or more prebiotic compounds. In some embodiment,s the composition is comestible.

[064] The invention includes a composition, comprising any of the compositions administered according to the methods described above.

[065] The invention also includes a dosage unit comprising predetermined ratios of the isolated bacteria present in the network ecology described above.

[066] The invention comprises a pharmaceutical formulation comprising a purified bacterial population consisting essentially of a bacterial network capable of forming germinable bacterial spores, wherein the bacterial network is present in an amount effective to populate the gastrointestinal tract in a mammalian subject in need thereof to whom the formulation is administered, under conditions such that at least one type of bacteria not detectably present in the bacterial network or in the gastrointestinal tract prior to administration is augmented.

[067] The invention also includes a pharmaceutical formulation comprising a purified bacterial population comprising a plurality of bacterial entities, wherein the bacterial entities are present in an amount effective to induce the formation of a functional bacterial network in the gastrointestinal tract in a mammalian subject in need thereof to whom the formulation is administered. In some embodiments, the functional bacterial network comprises bacterial entities present in the formulation. In other embodiments, the functional bacterial network comprises bacterial entities present in the gastrointestinal tract at the time of administration. In another embodiment, the functional bacterial network comprises bacterial entities not present in the formulation or the gastrointestinal tract at the time of administration. In one embodiment, the formulation can be provided as an oral finished pharmaceutical dosage form including at least one pharmaceutically acceptable carrier In some embodiments, the formulation of claim 83 or claim 84, wherein the mammalian subject suffers from a dysbiosis comprising a gastrointestinal disease, disorder or condition selected from the group consisting of *Clostridium difficile* Associated Diarrhea (CDAD), Type 2 Diabetes, Type 1 Diabetes, Obesity, Irritable Bowel Syndrome (IBS), Irritable Bowel Disease (IBD), Ulcerative Colitis, Crohn's

Disease, colitis, colonization with a pathogen or pathobiont, and infection with a drug-resistant pathogen or pathobiont.

[068] In another embodiment, the bacterial network is purified from a fecal material subjected to a treatment step that comprises depleting or inactivating a pathogenic material. In one embodiment, the bacterial network is substantially depleted of a detectable level of a first pathogenic material. In some embodiments, the bacterial network is substantially depleted of a residual habitat product of the fecal material.

[069] In one embodiment, the invention provides a method of treating or preventing a dysbiosis in a human subject, comprising administering to the human subject the formulation of claim 83 or claim 84 in an amount effective to treat or prevent a dysbiosis or to reduce the severity of at least one symptom of the dysbiosis in the human subject to whom the formulation is administered.

[070] In another embodiment, the formulation is provided as an oral finished pharmaceutical dosage form including at least one pharmaceutically acceptable carrier, the dosage form comprising at least about $1x10^4$ colony forming units of bacterial spores per dose of the composition, wherein the bacterial spores comprise at least two bacterial entities comprising 16S rRNA sequences at least 97% identical to the nucleic acid sequences selected from the group consisting of Seq. ID No.: 674, Seq. ID No.: 1670, Seq. ID No.: 774, Seq. ID No.: 848, Seq. ID No.: 856, Seq. ID No.: 1639, Seq. ID No.: 880, Seq. ID No.: 1896, Seq. ID No.: 1591, Seq. ID No.: 164, Seq. ID No.: 845, and Seq. ID No.: 659.

[071] In yet another embodiment, the administration of the formulation results in a reduction or an elimination of at least one pathogen and/or pathobiont present in the gastrointestinal tract when the therapeutic composition is administered. In one embodiment, the administration of the formulation results in engraftment of at least one type of spore-forming bacteria present in the therapeutic composition.

[072] In one aspect, the administration of the formulation results in augmentation in the gastrointestinal tract of the subject to whom the formulation is administered of at least one type of bacteria not present in the formulation. In another aspect, the at least one type of spore-forming bacteria are not detectably present in the gastrointestinal tract of the subject to whom the formulation is administered when the formulation is administered. In yet another aspect, the administration of the formulation results in at least two of: i) reduction or elimination of at least one pathogen and/or pathobiont present in the gastrointestinal tract when the formulation is administered; ii) engraftment of at least one type of spore-forming bacteria present in the therapeutic composition; and iii) augmentation of at least one type of spore-forming or non-spore forming bacteria not present in the therapeutic composition.

[073] In some aspects, the administration of the therapeutic composition results in at reduction or elimination of at least one pathogen and/or pathobiont present in the gastrointestinal tract when the therapeutic composition is administered and at least one of: i) engraftment of at least one type of

spore-forming bacteria present in the therapeutic composition; and ii) augmentation of at least one type of bacteria not present in the therapeutic composition.

[074] In another aspect, the method of inducing engraftment of a bacterial population in the gastrointestinal tract of a human subject, comprising the step of administering to the human subject an orally acceptable pharmaceutical formulation comprising a purified bacterial network, under conditions such that at least i) a subset of the spore-forming bacteria sustainably engraft within the gastrointestinal tract, or ii) at least one type of bacteria not present in the therapeutic composition is augmented within the gastrointestinal tract.

[075] The invention provides a pharmaceutical formulation comprising a purified first bacterial entity and a purified second bacterial entity, wherein the first bacterial entity comprises a first nucleic acid sequence encoding a first polypeptide capable of catalyzing a first chemical reaction, wherein the second bacterial entity comprises a second nucleic acid sequence encoding a second polypeptide capable of catalyzing a second chemical reaction, wherein the pharmaceutical formulation is formulated for oral administration to a mammalian subject in need thereof, wherein the first chemical reaction and the second chemical reaction are capable of occurring in the gastrointestinal tract of the mammalian subject under conditions such that a first product of the first chemical reaction, a substance present within said mammalian subject, or a combination of said first product with the substance is used as a substrate in the second chemical reaction to form a second product, wherein the second product induces a host cell response. In one embodiment, the substance is a mammalian subject protein or a food-derived protein. In another embodiment, the host cell response comprises production by the host cell of a biological material. In certain embodiments, the biological material comprises a cytokine, growth factor or signaling polypeptide.

[076] In one embodiment, the host cell response comprises an immune response. In another embodiment, the host cell response comprises decreased gastric motility. In yet another embodiment, the host cell response comprises change in host gene expression, increased host metabolism, reduced gut permeability, enhanced epithelial cell junction integrity, reduced lipolysis by the action of Lipoprotein Lipase in adipose tissue, decreased hepatic gluconeogenesis, increased insulin sensitivity, increased production of FGF-19, or change in energy harvesting and/or storage.

[077] The invention includes a pharmaceutical formulation comprising a purified first bacterial entity and a purified second bacterial entity, wherein the first bacterial entity and the second bacterial entity form a functional bacterial network in the gastrointestinal tract of a mammalian subject to whom the pharmaceutical formulation is administered, wherein the functional network modulates the level and/or activity of a biological material capable of inducing a host cell response.

[078] The invention also includes a pharmaceutical formulation comprising a purified first bacterial entity and a purified second bacterial entity, wherein the first bacterial entity and the second bacterial entity form a functional bacterial network in the gastrointestinal tract of a mammalian

subject to whom the pharmaceutical formulation is administered, wherein the functional network induces the production of a biological material capable of inducing a host cell response.

[079] The invention comprises a therapeutic composition, comprising a network of at least two bacterial entities, wherein the network comprises at least one keystone bacterial entity and at least one non-keystone bacterial entity, wherein the at least two bacterial entities are each provided in amounts effective for the treatment or prevention of a gastrointestinal disease, disorder or condition in a mammalian subject. In one aspect, the network comprises at least three bacterial entities. In another aspect, the network comprises at least three bacterial entities including at least two keystone bacterial entities.

[080] The invention comprises a therapeutic composition, comprising a network of at least two keystone bacterial entities capable of forming germination-competent spores, wherein the at least two keystone bacterial entities are each provided in amounts effective for the treatment or prevention of a gastrointestinal disease, disorder or condition in a mammalian subject. In one aspect, the comprision comprises a network of at least two keystone bacterial entities capable of forming germination-competent spores.

[081] In one embodiment, the invention comprises a therapeutic composition, comprising: a first network of at least two bacterial entities, wherein the first network comprises a keystone bacterial entity and a non-keystone bacterial entity; and a second network of at least two bacterial entities, wherein the second network comprises at least one keystone bacterial entity and at least one non-keystone bacterial entity, wherein the networks are each provided in amounts effective for the treatment or prevention of a gastrointestinal disease, disorder or condition in a mammalian subject.

[082] The invention includes a therapeutic composition, comprising a network of at least two bacterial entities, wherein the network comprises a first keystone bacterial entity and a second keystone bacterial entity, wherein the two bacterial entities are each provided in amounts effective for the treatment or prevention of a gastrointestinal disease, disorder or condition in a mammalian subject. In one aspect, the first and second keystone bacterial entities are present in the same network. In another aspect, the first and second keystone bacterial entities are present in different networks.

[083] In some aspects, the invention comprises a diagnostic composition for the detection of a dysbiosis, comprising a first detection moiety capable of detecting a first keystone bacterial entity and a second detection moiety capable of detecting a first non-keystone bacterial entity, wherein the keystone bacterial entity and the non-keystone bacterial entity comprise a network, wherein the absence of at least one of the keystone bacterial entity and the non-keystone bacterial entity in a mammalian subject is indicative of a dysbiosis.

[084] The invention comprises a method of altering a microbiome population present in a mammalian subject, comprising the steps of determining the presence of an incomplete network of bacterial entities in the gastrointestinal tract of the mammalian subject, and introducing to the

gastrointestinal tract of the mammalian subject an effective amount of one or more supplemental bacterial entities not detectable in the gastrointestinal tract of the mammalian subject prior to such administration, under conditions such that the incomplete network is completed, thereby altering the microbiome population.

[085] In one embodiment, the one or more supplemental bacterial entities become part of the incomplete network, thereby forming a complete network. In another embodiment, the one or more supplemental bacterial entities alter the microbiota of the mammalian subject such that one or more additional bacterial entities complete the incomplete network. In yet another embodiment, the one or more supplemental bacterial entities comprise a network.

[086] The invention includes a method for detection and correction of a dysbiosis in a mammalian subject in need thereof, comprising the steps of: providing a fecal sample from the mammalian subject comprising a plurality of bacterial entities; contacting the fecal sample with a first detection moiety capable of detecting a first bacterial entity present in an network; detecting the absence of the first bacterial entity in the fecal sample, thereby detecting a dysbiosis in the mammalian subject; and administering to the mammalian subject a composition comprising an effective amount of the first bacterial entity. In one embodiment, the method includes confirming that the dysbiosis in the mammalian subject has been corrected.

[087] The invention comprises a system for predicting a dysbiosis in a subject, the system comprising: a storage memory for storing a dataset associated with a sample obtained from the subject, wherein the dataset comprises content data for at least one network of bacterial entities; and a processor communicatively coupled to the storage memory for determining a score with an interpretation function wherein the score is predictive of dysbiosis in the subject.

[088] The invention also comprises a kit for diagnosis of a state of dysbiosis in a mammalian subject in need thereof, comprising a plurality of detection means suitable for use in detecting (1) a first bacterial entity comprising a keystone bacterial entity and (2) a second bacterial entity, wherein the first and second bacterial entities comprise a functional network ecology.

BRIEF DESCRIPTION OF THE DRAWINGS

[089] Figure 1 provides a schematic of 16S rRNA gene and denotes the coordinates of hypervariable regions 1-9 (V1-V9), according to an embodiment of the invention. Coordinates of V1-V9 are 69-99, 137-242, 433-497, 576-682, 822-879, 986-1043, 1117-1173, 1243-1294, and 1435-1465 respectively, based on numbering using E. coli system of nomenclature defined by Brosius et al., Complete nucleotide sequence of a 16S ribosomal RNA gene (16S rRNA) from Escherichia coli, PNAS 75(10):4801-4805 (1978).

[090] Figure 2 highlights in bold the nucleotide sequences for each hypervariable region in the exemplary reference E. coli 16S sequence described by Brosius et al.

[091] Figure 3 provides the OTU and clade composition of networks tested in experiment SP-376, according to an embodiment of the invention.

[092] Figure 4 illustrates the results of a nutrient utilization assay with Clostridium difficile and potential competitors of the pathogen. A plus sign (+) indicates that it is a nutrient for the isolate tested. A minus sign (-) indicates that it is not a nutrient for the isolate tested.

[093] Figure 5 demonstrates the microbial diversity measured in the ethanol-treated spore treatment sample and patient pre- and post-treatment samples, according to an embodiment of the invention. Total microbial diversity is defined using the Chao1 Alpha-Diversity Index and is measured at the same genomic sampling depths to confirm adequate and comparable sequence coverage of the target samples. The patient pretreatment (purple) harbored a microbiome that was significantly reduced in total diversity as compared to the ethanol-treated spore treatment (red) and patient post treatment at days 5 (blue), 14 (orange), and 25 (green).

[094] Figure 6 demonstrates how patient microbial ecology is shifted by treatment with an ethanol-treated spore treatment from a dysbiotic state to a state of health. Principal coordinates analysis based on the total diversity and structure of the microbiome (Bray Curtis Beta Diversity) of the patient pre- and post-treatment delineates that the combination of engraftment of the OTUs from the spore treatment and the augmentation of the patient microbial ecology leads to a microbial ecology that is distinct from both the pretreatment microbiome and the ecology of the ethanol-treated spore treatment.

[095] Figure 7 demonstrates the augmentation of Bacteroides species in patients treated with the spore population, according to an embodiment of the invention.

[096] Figure 8 shows species engrafting versus species augmenting in patients microbiomes after treatment with a bacterial composition such as but not limited to an ethanol-treated spore population, according to an embodiment of the invention. Relative abundance of species that engrafted or augmented as described were determined based on the number of 16S sequence reads. Each plot is from a different patient treated with the bacterial composition such as but not limited to an ethanol-treated spore population for recurrent C. difficile.

[097] Figure 9 shows a set of survival curves demonstrating efficacy of the ethanol enriched spore population in a mouse prophylaxis model of C. difficile, according to an embodiment of the invention.

[098] Figure 10 illustrates an in vivo hamster Clostridium difficile relapse prevention model to validate efficacy of ethanol-treated spores and ethanol treated, gradient purified spores, according to an embodiment of the invention.

[099] Figure 11 shows an in vivo hamster Clostridium difficile relapse prevention model to validate efficacy of network ecology bacterial composition, according to an embodiment of the invention.

[0100] Figure 12 shows secondary bile acid metabolism KEGG Orthology Pathway and associated enzymatic gene products defined by EC numbers.

[0101] Figure 13 shows Butyrate (a.k.a butanoate) production KEGG Orthology Pathway and associated enzymatic gene products defined by EC numbers.

[0102] Figure 14 shows Propionate (a.k.a. propanoate) production KEGG Orthology Pathway and associated enzymatic gene products defined by EC numbers.

[0103] Figure 15 shows Acetate production KEGG Orthology Pathway and associated enzymatic gene products defined by EC numbers.

[0104] Figure 16 is an overview of a method to computationally derive network ecologies, according to an embodiment of the invention.

[0105] Figure 17 is a schematic representation of how Keystone OTUs (nodes 2 and 4, shaded circles) are central members of many network ecologies that contain non-Keystone OTUs (nodes 1, 3, and 5-9). Distinct network ecologies include [node 2--node 7], [node--3--node 2--node--4], [node 2--node 4--node 5--node 6--node 7], [node 1--node 2--node 8--node 9], and [node --node 3].

[0106] Figure 18 exemplifies a Derivation of Network Ecology Classes, according to an embodiment of the invention. Subsets of networks are selected for use in defining Network Classes based on key biological criteria. Hierarchical Network clusters are defined by the presence (white) and absence (blue) of OTUs and/or Functional Metabolic Pathways and Classes are defined as branches of the hierarchical clustering tree based on the topological overlap measure.

[0107] Figure 19 shows phenotypes assigned to samples for the computational derivation of Network Ecologies that typify microbiome states of health (Hpost, Hdon, & Hgen) and states of disease (DdonF & DpreF). The composition of the microbiome of samples in different phenotypes can overlap with the intersections, defined by H, HD, D designations, having different biological meanings.

[0108] Figure 20 shows an exemplary phylogenetic tree and the relationship of OTUs and Clades. A, B, C, D, and E represent OTUs, also known as leaves in the tree. Clade 1 comprises OTUs A and B, Clade 2 comprises OTUs C, D and E, and Clade 3 is a subset of Clade 2 comprising OTUs D and E. Nodes in a tree that define clades in the tree can be either statistically supported or not statistically supported. OTUs within a clade are more similar to each other than to OTUs in another clade and the robustness the clade assignment is denoted by the degree of statistical support for a node upstream of the OTUs in the clade.

[0109] Figure 21 is a high-level block diagram illustrating an example of a computer for use as a server or a user device, in accordance with one embodiment.

[0110] The figures depict various embodiments of the present invention for purposes of illustration only. One skilled in the art will readily recognize from the following discussion that alternative

embodiments of the structures and methods illustrated herein may be employed without departing from the principles of the invention described herein.

DETAILED DESCRIPTION

OVERVIEW

[0111] Disclosed herein are therapeutic compositions containing combinations of bacteria for the prevention, control, and treatment of gastrointestinal diseases, and other disorders and conditions that result in or are caused by a dysbiotic microbiome in a niche of a host. Such indications include, but are not limited to Clostridium difficile associated diarrhea (CDAD), Type 2 Diabetes, Ulcerative colitis, as well as infection by antibiotic resistant bacteria such as Carbapenem resistant Klebsiella pneomoniae (CRKp) and Vancomycin Resistant Enterococcus (VRE). These compositions are advantageous in being suitable for safe administration to humans and other mammalian subjects and are efficacious in numerous gastrointestinal diseases, disorders and conditions and in general nutritional health. While bacterial compositions are known, these are generally single bacterial strains or combinations of bacteria that are combined without understanding the ecology formed by a consortium of bacterial organisms, resulting in poor efficacy, instability, substantial variability and lack of adequate safety.

[0112] The human body is an ecosystem in which the microbiota and the microbiome play a significant role in the basic healthy function of human systems (*e.g.* metabolic, immunological, and neurological). The microbiota and resulting microbiome comprise an ecology of microorganisms that co-exist within single subjects interacting with one another and their host (*i.e.*, the mammalian subject) to form a dynamic unit with inherent biodiversity and functional characteristics. Within these networks of interacting microbes (*i.e.* ecologies), particular members can contribute more significantly than others; as such these members are also found in many different ecologies, and the loss of these microbes from the ecology can have a significant impact on the functional capabilities of the specific ecology. Robert Paine coined the concept "Keystone Species" in 1969 (see Paine RT. 1969. A note on trophic complexity and community stability. The American Naturalist 103: 91–93.) to describe the existence of such lynchpin species that are integral to a given ecosystem regardless of their abundance in the ecological community. Paine originally describe the role of the starfish Pisaster ochraceus in marine systems and since the concept has been experimentally validated in numerous ecosystems.

[0113] The present invention provides methods to define important network ecologies and functional network ecologies that occur in healthy and diseased subjects, and provides the compositional constituents of these network ecologies. The method enables the derivation of ecological modules (*i.e.* groups or networks of organisms and metabolic functions) within a broader ecology that can catalyze a change from a dysbiotic microbiome to one that represents a state of health. In another embodiment the methods enable the de novo construction of a network ecology

based on desired biological characteristics, including functional characteristics, e.g. a functional network ecology. The methods further provide keystone species (*i.e.* operational taxonomic units, or OTUs) and keystone metabolic functions that are members of these microbial communities based on their ubiquitous appearance in many different networks. Importantly, this method is distinguished from previous computational approaches by being the first method to define actual network ecologies that are found in many healthy subjects. Network ecologies comprise consortia of bacterial OTUs (*i.e.* genera, species, or strains) that form coherent intact biological communities with defined phylogenetic and/or functional properties. In other words, the structure-function relationships contained within any Network Ecology possess an inherent biodiversity profile and resulting biological functional capabilities. The specific bacterial combinations and functional capabilities of the resulting microbiome are efficacious for the treatment or prevention of diseases, disorders and conditions of the gastrointestinal tract or for the treatment or prevention of systemic diseases, disorders and conditions that are influenced by the microbiota of the gastrointestinal tract. Further the network ecologies have a modularity to their structure and function with specific nodes (as example OTUs, phylogenetic clades, functional pathways) comprising a backbone of the network onto which different r-groups (as example OTUs, phylogenetic clades, functional pathways) can be incorporated to achieve specific biological properties of the network ecology. Network Ecologies defined in terms of functional modalities are referred to as Functional Network Ecologies.

[0114] The network ecologies provided herein are useful in settings where a microbial dysbiosis is occurring, given their capacities to achieve one or more of the following actions: i) disrupting the existing microbiota and/or microbiome; ii) establishing a new microbiota and/or microbiome; and (iii) stabilizing a functional microbiota and/or microbiome that supports health. Such network ecologies may be sustainably present upon introduction into a mammalian subject, or may be transiently present until such time as the functional microbiota and/or microbiome are re-established. In therapeutic settings, treatment with a consortium of microbial OTUs will change the microbiome of the treated host from a state of disease to a state of health. This change in the total diversity and composition can be mediated by both: (i) engraftment of OTUs that comprise the therapeutic composition into the host's ecology (Engrafted Ecology), and (ii) the establishment of OTUs that are not derived from the therapeutic composition, but for which the treatment with the therapeutic composition changes the environmental conditions such that these OTUs can establish. This Augmented Ecology is comprised of OTUs that were present at lower levels in the host pre-treatment or that were exogenously introduced from a source other than the therapeutic composition itself.

[0115] Provided herein are computational methods based at least in part on network theory (Proulx SR, Promislow DEL, Phillips PC. 2005. Network thinking in ecology and evolution. Trends in Ecology & Evolution 20: 345–353.), that delineate ecological and functional structures of a group of microorganisms based on the presence or absence of the specific OTUs (*i.e.* microbial orders, families, genera, species or strains) or functions inherent to those OTUs in a population of sampled

mammalian subjects. Notably, these network ecologies and functional network ecologies are not simply inferred based on the clustering of OTUs according to binary co-occurrences computed from average relative abundances across a set of subject samples (*See e.g.* Faust K, Sathirapongsasuti JF, Izard J, Segata N, Gevers D, Raes J, and Huttenhower C. 2012. Microbial co-occurrence relationships in the human microbiome. PLoS Computational Bioliology 8: e1002606. Lozupone C, Faust K, Raes J, Faith JJ, Frank DN, Zaneveld J, Gordon JI, and Knight R. 2012. Identifying genomic and metabolic features that can underlie early successional and opportunistic lifestyles of human gut symbionts. Genome Research 22: 1974–1984), but instead the ecologies represent actual communities of bacterial OTUs that are computationally derived and explicitly exist as an ecological network within one or more subjects. Further, we provide methods by which to characterize the biological significance of a given ecological network in terms of its phylogenetic diversity, functional properties, and association with health or disease. The present invention delineates ecologies suitable for the treatment or prevention of diseases, disorders, and conditions of the gastrointestinal tract or which are distal to the gastrointestinal tract but caused or perpetuated by a dysbiosis of the gut microbiota.

DEFINITIONS

[001] As used herein, the term "purified bacterial preparation" refers to a preparation that includes bacteria that have been separated from at least one associated substance found in a source material or any material associated with the bacteria in any process used to produce the preparation.

[002] A "bacterial entity" includes one or more bacteria. Generally, a first bacterial entity is distinguishable from a second bacterial entity

[003] As used herein, the term "formation" refers to synthesis or production.

[004] As used herein, the term "inducing" means increasing the amount or activity of a given material as dictated by context.

[005] As used herein, the term "depletion" refers to reduction in amount of.

[006] As used herein, a "prebiotic" is a comestible food or beverage or ingredient thereof that allows specific changes, both in the composition and/or activity in the gastrointestinal microbiota that confers benefits upon host well-being and health. Prebiotics may include complex carbohydrates, amino acids, peptides, or other essential nutritional components for the survival of the bacterial composition. Prebiotics include, but are not limited to, amino acids, biotin, fructooligosaccharide, galactooligosaccharides, inulin, lactulose, mannan oligosaccharides, oligofructose-enriched inulin, oligofructose, oligodextrose, tagatose, trans-galactooligosaccharide, and xylooligosaccharides.

[007] As used herein, "predetermined ratios" refer to ratios determined or selected in advance.

[008] As used herein, "germinable bacterial spores" are spores capable of forming vegetative cells under certain environmental conditions.

[009] As used herein, "detectably present" refers to present in an amount that can be detected using assays provided herein or otherwise known in the art that exist as of the filing date.

[010] As used herein, "augmented" refers to an increase in amount and/or localization within to a point where it becomes detectably present.

[011] As used herein, a "fecal material" refers to a solid waste product of digested food and includes feces or bowel washes.

[012] As used herein, a "host cell response" is a response produced by a cell comprising a host organism.

[013] As used herein, a "mammalian subject protein" refers to a protein produced by a mammalian subject and encoded by the mammalian subject genome.

[014] As used herein, the term "food-derived" refers to a protein found in a consumed food.

[015] As used herein, the term "biological material" refers to a material produced by a biological organism.

[016] As used herein, the term "detection moiety" refers to an assay component that functions to detect an analyte.

[017] As used herein, the term "incomplete network" refers to a partial network that lacks the entire set of components needed to carry out one or more network functions.

[018] As used herein, the term "supplemental" refers to something that is additional and non-identical.

[019] As used herein, the term "Antioxidant" refers to, without limitation, any one or more of various substances such as beta-carotene (a vitamin A precursor), vitamin C, vitamin E, and selenium that inhibit oxidation or reactions promoted by Reactive Oxygen Species ("ROS") and other radical and non-radical species. Additionally, antioxidants are molecules capable of slowing or preventing the oxidation of other molecules. Non-limiting examples of antioxidants include astaxanthin, carotenoids, coenzyme Q10 ("CoQ10"), flavonoids, glutathione, Goji (wolfberry), hesperidin, lactowolfberry, lignan, lutein, lycopene, polyphenols, selenium, vitamin A, vitamin C, vitamin E, zeaxanthin, or combinations thereof.

[020] "Backbone Network Ecology" or simply "Backbone Network" or "Backbone" are compositions of microbes that form a foundational composition that can be built upon or subtracted from to optimize a Network Ecology or Functional Network Ecology to have specific biological characteristics or to comprise desired functional properties, respectively. Microbiome therapeutics can be comprised of these "Backbone Networks Ecologies" in their entirety, or the "Backbone Networks" can be modified by the addition or subtraction of "R-Groups" to give the network ecology desired characteristics and properties. "R-Groups" can be defined in multiple terms including, but not limited to: individual OTUs, individual or multiple OTUs derived from a specific phylogenetic clade or a desired phenotype such as the ability to form spores, or functional bacterial compositions that comprise. "Backbone Networks" can comprise a computationally derived Network Ecology in its entirety or can be subsets of the computed network that represent key nodes in the network that

contributed to efficacy such as but not limited to a composition of Keystone OTUs. The number of organisms in the human gastrointestinal tract, as well as the diversity between healthy individuals, is indicative of the functional redundancy of a healthy gut microbiome ecology. *See* The Human Microbiome Consortia. 2012. Structure, function and diversity of the healthy human microbiome. Nature 486: 207-214. This redundancy makes it highly likely that non-obvious subsets of OTUs or functional pathways (*i.e.* "Backbone Networks") are critical to maintaining states of health and or catalyzing a shift from a dysbiotic state to one of health. One way of exploiting this redundancy is through the substitution of OTUs that share a given clade (see below) or of adding members of a clade not found in the Backbone Network.

[021] "Bacterial Composition" refers to a consortium of microbes comprising two or more OTUs. Backbone Network Ecologies, Functional Network Ecologies, Network Classes, and Core Ecologies are all types of bacterial compositions. A "Bacterial Composition" can also refer to a composition of enzymes that are derived from a microbe or multiple microbes. As used herein, Bacterial Composition includes a therapeutic microbial composition, a prophylactic microbial composition, a Spore Population, a Purified Spore Population, or ethanol treated spore population.

[022] "Clade" refers to the OTUs or members of a phylogenetic tree that are downstream of a statistically valid node in a phylogenetic tree (Figure 20). The clade comprises a set of terminal leaves in the phylogenetic tree (i.e. tips of the tree) that are a distinct monophyletic evolutionary unit and that share some extent of sequence similarity. Clades are hierarchical. In one embodiment, the node in a phylogenetic tree that is selected to define a clade is dependent on the level of resolution suitable for the underlying data used to compute the tree topology.

[023] The "Colonization" of a host organism includes the non-transitory residence of a bacterium or other microscopic organism. As used herein, "reducing colonization" of a host subject's gastrointestinal tract (or any other microbiotal niche) by a pathogenic or non-pathogenic bacterium includes a reduction in the residence time of the bacterium the gastrointestinal tract as well as a reduction in the number (or concentration) of the bacterium in the gastrointestinal tract or adhered to the luminal surface of the gastrointestinal tract. The reduction in colonization can be permanent or occur during a transient period of time. Reductions of adherent pathogens can be demonstrated directly, *e.g.*, by determining pathogenic burden in a biopsy sample, or reductions may be measured indirectly, *e.g.*, by measuring the pathogenic burden in the stool of a mammalian host.

[024] A "Combination" of two or more bacteria includes the physical co-existence of the two bacteria, either in the same material or product or in physically connected products, as well as the temporal co-administration or co-localization of the two bacteria.

[025] "Cytotoxic" activity of bacterium includes the ability to kill a bacterial cell, such as a pathogenic bacterial cell. A "cytostatic" activity or bacterium includes the ability to inhibit, partially

or fully, growth, metabolism, and/or proliferation of a bacterial cell, such as a pathogenic bacterial cell. Cytotoxic activity may also apply to other cell types such as but not limited to Eukaryotic cells.

[026] "Dysbiosis" refers to a state of the microbiota or microbiome of the gut or other body area, including mucosal or skin surfaces in which the normal diversity and/or function of the ecological network is disrupted. Any disruption from the preferred (*e.g.*, ideal) state of the microbiota can be considered a dysbiosis, even if such dysbiosis does not result in a detectable decrease in health. This state of dysbiosis may be unhealthy, it may be unhealthy under only certain conditions, or it may prevent a subject from becoming healthier. Dysbiosis may be due to a decrease in diversity, the overgrowth of one or more pathogens or pathobionts, symbiotic organisms able to cause disease only when certain genetic and/or environmental conditions are present in a patient, or the shift to an ecological network that no longer provides a beneficial function to the host and therefore no longer promotes health.

[027] "Ecological Niche" or simply "Niche" refers to the ecological space in which an organism or group of organisms occupies. Niche describes how an organism or population or organisms responds to the distribution of resources, physical parameters (*e.g.*, host tissue space) and competitors (*e.g.*, by growing when resources are abundant, and when predators, parasites and pathogens are scarce) and how it in turn alters those same factors (*e.g.*, limiting access to resources by other organisms, acting as a food source for predators and a consumer of prey).

[028] "Germinant" is a material or composition or physical-chemical process capable of inducing vegetative growth of a bacterium that is in a dormant spore form, or group of bacteria in the spore form, either directly or indirectly in a host organism and/or in vitro.

[029] "Inhibition" of a pathogen or non-pathogn encompasses the inhibition of any desired function or activity y the bacterial compositions of the present invention. Demonstrations of inhibition, such as decrease in the growth of a pathogenic bacterium or reduction in the level of colonization of a pathogenic bacterium are provided herein and otherwise recognized by one of ordinary skill in the art. Inhibition of a pathogenic or non-pathogenic bacterium's "growth" may include inhibiting the increase in size of the pathogenic or non-pathogenic bacterium and/or inhibiting the proliferation (or multiplication) of the pathogenic or non-pathogenic bacterium. Inhibition of colonization of a pathogenic or non-pathogenic bacterium may be demonstrated by measuring the amount or burden of a pathogen before and after a treatment. An "inhibition" or the act of "inhibiting" includes the total cessation and partial reduction of one or more activities of a pathogen, such as growth, proliferation, colonization, and function. Inhibition of function includes, for example, the inhibition of expression of pathogenic gene products such as a toxin or invasive pilus induced by the bacterial composition.

[030] "Isolated" encompasses a bacterium or other entity or substance that has been (1) separated from at least some of the components with which it was associated when initially produced (whether

in nature or in an experimental setting), and/or (2) produced, prepared, purified, and/or manufactured by the hand of man. Isolated bacteria include those bacteria that are cultured, even if such cultures are not monocultures. Isolated bacteria may be separated from at least about 10%, about 20%, about 30%, about 40%, about 50%, about 60%, about 70%, about 80%, about 90%, or more of the other components with which they were initially associated. In some embodiments, isolated bacteria are more than about 80%, about 85%, about 90%, about 91%, about 92%, about 93%, about 94%, about 95%, about 96%, about 97%, about 98%, about 99%, or more than about 99% pure. As used herein, a substance is "pure" if it is substantially free of other components. The terms "purify," "purifying" and "purified" refer to a bacterium or other material that has been separated from at least some of the components with which it was associated either when initially produced or generated (*e.g.*, whether in nature or in an experimental setting), or during any time after its initial production. A bacterium or a bacterial population may be considered purified if it is isolated at or after production, such as from a material or environment containing the bacterium or bacterial population, or by passage through culture, and a purified bacterium or bacterial population may contain other materials up to about 10%, about 20%, about 30%, about 40%, about 50%, about 60%, about 70%, about 80%, about 90%, or above about 90% and still be considered "isolated." In some embodiments, purified bacteria and bacterial populations are more than about 80%, about 85%, about 90%, about 91%, about 92%, about 93%, about 94%, about 95%, about 96%, about 97%, about 98%, about 99%, or more than about 99% pure. In the instance of bacterial compositions provided herein, the one or more bacterial types present in the composition can be independently purified from one or more other bacteria produced and/or present in the material or environment containing the bacterial type. Bacterial compositions and the bacterial components thereof are generally purified from residual habitat products.

[031] "Keystone OTU" or "Keystone Function" refers to one or more OTUs or Functional Pathways (*e.g.* KEGG or COG pathways) that are common to many network ecologies or functional network ecologies and are members of networks that occur in many subjects (*i.e.* are pervasive). Due to the ubiquitous nature of Keystone OTUs and their associated Functions Pathways, they are central to the function of network ecologies in healthy subjects and are often missing or at reduced levels in subjects with disease. Keystone OTUs and their associated functions may exist in low, moderate, or high abundance in subjects. "Non-Keystone OTU" or "non-Keystone Function" refers to an OTU or Function that is observed in a Network Ecology or a Functional Network Ecology and is not a keystone OTU or Function.

[032] "Microbiota" refers to the community of microorganisms that occur (sustainably or transiently) in and on an animal subject, typically a mammal such as a human, including eukaryotes, archaea, bacteria, and viruses (including bacterial viruses *i.e.*, phage).

[033] "Microbiome" refers to the genetic content of the communities of microbes that live in and on the human body, both sustainably and transiently, including eukaryotes, archaea, bacteria, and

viruses (including bacterial viruses (*i.e.*, phage)), wherein "genetic content" includes genomic DNA, RNA such as ribosomal RNA, the epigenome, plasmids, and all other types of genetic information.

[034] "Microbial Carriage" or simply "Carriage" refers to the population of microbes inhabiting a niche within or on humans. Carriage is often defined in terms of relative abundance. For example, OTU1 comprises 60% of the total microbial carriage, meaning that OTU1 has a relative abundance of 60% compared to the other OTUs in the sample from which the measurement was made. Carriage is most often based on genomic sequencing data where the relative abundance or carriage of a single OTU or group of OTUs is defined by the number of sequencing reads that are assigned to that OTU/s relative to the total number of sequencing reads for the sample. Alternatively, Carriage may be measured using microbiological assays.

[035] "Microbial Augmentation" or simply "augmentation" refers to the establishment or significant increase of a population of microbes that are (i) absent or undetectable (as determined by the use of standard genomic and microbiological techniques) from the administered therapeutic microbial composition, (ii) absent, undetectable, or present at low frequencies in the host niche (for example: gastrointestinal tract, skin, anterior-nares, or vagina) before the delivery of the microbial composition, and (iii) are found after the administration of the microbial composition or significantly increased, for instance 2-fold, 5-fold, $1x10^2$, $1x10^3$, $1x10^4$, $1x10^5$, $1x10^6$, $1x10^7$, or greater than $1x10^8$, in cases where they were present at low frequencies. The microbes that comprise an augmented ecology can be derived from exogenous sources such as food and the environment, or grow out from micro-niches within the host where they reside at low frequency. The administration of a bacterial microbial composition induces an environmental shift in the target niche that promotes favorable conditions for the growth of these commensal microbes. In the absence of treatment with a bacterial composition, the host can be constantly exposed to these microbes; however, sustained growth and the positive health effects associated with the stable population of increased levels of the microbes comprising the augmented ecology are not observed.

[036] "Microbial Engraftment" or simply "engraftment" refers to the establishment of OTUs present in the bacterial composition in a target niche that are absent in the treated host prior to treatment. The microbes that comprise the engrafted ecology are found in the therapeutic microbial composition and establish as constituents of the host microbial ecology upon treatment. Engrafted OTUs can establish for a transient period of time, or demonstrate long-term stability in the microbial ecology that populates the host post treatment with a bacterial composition. The engrafted ecology can induce an environmental shift in the target niche that promotes favorable conditions for the growth of commensal microbes capable of catalyzing a shift from a dysbiotic ecology to one representative of a health state.

[037] As used herein, the term "Minerals" is understood to include boron, calcium, chromium, copper, iodine, iron, magnesium, manganese, molybdenum, nickel, phosphorus, potassium, selenium, silicon, tin, vanadium, zinc, or combinations thereof.

[038] "Network Ecology" refers to a consortium of clades or OTUs that co-occur in some number of subjects. As used herein, a "network" is defined mathematically by a graph delineating how specific nodes (*i.e.* clades or OTUs) and edges (connections between specific clades or OTUs) relate to one another to define the structural ecology of a consortium of clades or OTUs. Any given Network Ecology will possess inherent phylogenetic diversity and functional properties. A Network Ecology can also be defined in terms of its functional capabilities where for example the nodes would be comprised of elements such as, but not limited to, enzymes, clusters of orthologous groups (COGS; http://www.ncbi.nlm.nih.gov/books/NBK21090/), or KEGG Orthology Pathways (www.genome.jp/kegg/); these networks are referred to as a "Functional Network Ecology". Functional Network Ecologies can be reduced to practice by defining the group of OTUs that together comprise the functions defined by the Functional Network Ecology.

[039] "Network Class" and "Network Class Ecology" refer to a group of network ecologies that in general are computationally determined to comprise ecologies with similar phylogenetic and/or functional characteristics. A Network Class therefore contains important biological features, defined either phylogenetically or functionally, of a group (*i.e.*, a cluster) of related network ecologies. One representation of a Network Class Ecology is a designed consortium of microbes, typically non-pathogenic bacteria, that represents core features of a set of phylogenetically or functionally related network ecologies seen in many different subjects. In many occurrences, a Network Class, while designed as described herein, exists as a Network Ecology observed in one or more subjects. Network Class ecologies are useful for reversing or reducing a dysbiosis in subjects where the underlying, related Network Ecology has been disrupted. Exemplary Network Classes are provided in Table 12 and examples of phylogenetic signature by family of Network Classes are given in Table 13.

[040] To be free of "non-comestible products" means that a bacterial composition or other material provided herein does not have a substantial amount of a non-comestible product, *e.g.*, a product or material that is inedible, harmful or otherwise undesired in a product suitable for administration, *e.g.*, oral administration, to a human subject. Non-comestible products are often found in preparations of bacteria from the prior art.

[041] "Operational taxonomic units" and "OTU" (or plural, "OTUs") refer to a terminal leaf in a phylogenetic tree and is defined by a nucleic acid sequence, *e.g.*, the entire genome, or a specific genetic sequence, and all sequences that share sequence identity to this nucleic acid sequence at the level of species. In some embodiments the specific genetic sequence may be the 16S sequence or a portion of the 16S sequence. In other embodiments, the entire genomes of two entities are sequenced and compared. In another embodiment, select regions such as multilocus sequence tags (MLST),

specific genes, or sets of genes may be genetically compared. In 16S embodiments, OTUs that share ≥ 97% average nucleotide identity across the entire 16S or some variable region of the 16S are considered the same OTU. *See e.g.* Claesson MJ, Wang Q, O'Sullivan O, Greene-Diniz R, Cole JR, Ross RP, and O'Toole PW. 2010. Comparison of two next-generation sequencing technologies for resolving highly complex microbiota composition using tandem variable 16S rRNA gene regions. Nucleic Acids Res 38: e200. Konstantinidis KT, Ramette A, and Tiedje JM. 2006. The bacterial species definition in the genomic era. Philos Trans R Soc Lond B Biol Sci 361: 1929–1940. In embodiments involving the complete genome, MLSTs, specific genes, other than 16S, or sets of genes OTUs that share ≥ 95% average nucleotide identity are considered the same OTU. *See e.g.,* Achtman M, and Wagner M. 2008. Microbial diversity and the genetic nature of microbial species. Nat. Rev. Microbiol. 6: 431–440. Konstantinidis KT, Ramette A, and Tiedje JM. 2006. The bacterial species definition in the genomic era. Philos Trans R Soc Lond B Biol Sci 361: 1929–1940. OTUs are frequently defined by comparing sequences between organisms. Generally, sequences with less than 95% sequence identity are not considered to form part of the same OTU. OTUs may also be characterized by any combination of nucleotide markers or genes, in particular highly conserved genes (*e.g.*, "house-keeping" genes), or a combination thereof. Such characterization employs, *e.g.*, WGS data or a whole genome sequence.

[042] Table 1 below shows a List of Operational Taxonomic Units (OTU) with taxonomic assignments made to Genus, Species, and Phylogenetic Clade. Clade membership of bacterial OTUs is based on 16S sequence data. Clades are defined based on the topology of a phylogenetic tree that is constructed from full-length 16S sequences using maximum likelihood methods familiar to individuals with ordinary skill in the art of phylogenetics. Clades are constructed to ensure that all OTUs in a given clade are: (i) within a specified number of bootstrap supported nodes from one another, and (ii) within 5% genetic similarity. OTUs that are within the same clade can be distinguished as genetically and phylogenetically distinct from OTUs in a different clade based on 16S-V4 sequence data, while OTUs falling within the same clade are closely related. OTUs falling within the same clade are evolutionarily closely related and may or may not be distinguishable from one another using 16S-V4 sequence data. Members of the same clade, due to their evolutionary relatedness, play similar functional roles in a microbial ecology such as that found in the human gut. Compositions substituting one species with another from the same clade are likely to have conserved ecological function and therefore are useful in the present invention. All OTUs are denoted as to their putative capacity to form spores and whether they are a Pathogen or Pathobiont (see Definitions for description of "Pathobiont"). NIAID Priority Pathogens are denoted as 'Category-A', 'Category-B', or 'Category-C', and Opportunistic Pathogens are denoted as 'OP'. OTUs that are not pathogenic or for which their ability to exist as a pathogen is unknown are denoted as 'N'. The 'SEQ ID Number' denotes the identifier of the OTU in the Sequence Listing File and 'Public DB Accession' denotes the identifier of the OTU in a public sequence repository.

[043] "Pathobiont" refer to specific bacterial species found in healthy hosts that may trigger immune-mediated pathology and/or disease in response to certain genetic or environmental factors (Chow et al. 2011. Curr Op Immunol. Pathobionts of the intestinal microbiota and inflammatory disease. 23: 473-80). Thus, a pathobiont is an opportunistic microbe that is mechanistically distinct from an acquired infectious organism. Thus, the term "pathogen" includes both acquired infectious organisms and pathobionts.

[044] "Pathogen", "pathobiont" and "pathogenic" in reference to a bacterium or any other organism or entity that includes any such organism or entity that is capable of causing or affecting a disease, disorder or condition of a host organism containing the organism or entity, including but not limited to pre-diabetes, type 1 diabetes or type 2 diabetes.

[045] "Phenotype" refers to a set of observable characteristics of an individual entity. As example an individual subject may have a phenotype of "health" or "disease". Phenotypes describe the state of an entity and all entities within a phenotype share the same set of characteristics that describe the phenotype. The phenotype of an individual results in part, or in whole, from the interaction of the entity's genome and/or microbiome with the environment, especially including diet.

[046] "Phylogenetic Diversity" is a biological characteristic that refers to the biodiversity present in a given Network Ecology or Network Class Ecology based on the OTUs that comprise the network. Phylogenetic diversity is a relative term, meaning that a Network Ecology or Network Class that is comparatively more phylogenetically diverse than another network contains a greater number of unique species, genera, and taxonomic families. Uniqueness of a species, genera, or taxonomic family is generally defined using a phylogenetic tree that represents the genetic diversity all species, genera, or taxonomic families relative to one another. In another embodiment phylogenetic diversity may be measured using the total branch length or average branch length of a phylogenetic tree. Phylogenetic Diversity may be optimized in a bacterial composition by including a wide range of biodiversity.

[047] "Phylogenetic tree" refers to a graphical representation of the evolutionary relationships of one genetic sequence to another that is generated using a defined set of phylogenetic reconstruction algorithms (*e.g.* parsimony, maximum likelihood, or Bayesian). Nodes in the tree represent distinct ancestral sequences and the confidence of any node is provided by a bootstrap or Bayesian posterior probability, which measures branch uncertainty.

[048] "Prediabetes" refers a condition in which blood glucose levels are higher than normal, but not high enough to be classified as diabetes. Individuals with pre-diabetes are at increased risk of developing type 2 diabetes within a decade. According to CDC, prediabetes can be diagnosed by fasting glucose levels between 100-125 mg/dL, 2 hour post-glucose load plasma glucose in oral glucose tolerance test (OGTT) between 140 and 199 mg/dL, or hemoglobin A1c test between 5.7%-6.4%.

[049] "rDNA", "rRNA", "16S-rDNA", "16S-rRNA", "16S", "16S sequencing", "16S-NGS", "18S", "18S-rRNA", "18S-rDNA", "18S sequencing", and "18S-NGS" refer to the nucleic acids that encode for the RNA subunits of the ribosome. rDNA refers to the gene that encodes the rRNA that comprises the RNA subunits. There are two RNA subunits in the ribosome termed the small subunit (SSU) and large subunit (LSU); the RNA genetic sequences (rRNA) of these subunits is related to the gene that encodes them (rDNA) by the genetic code. rDNA genes and their complementary RNA sequences are widely used for determination of the evolutionary relationships amount organisms as they are variable, yet sufficiently conserved to allow cross organism molecular comparisons. Typically 16S rDNA sequence (approximately 1542 nucleotides in length) of the 30S SSU is used for molecular-based taxonomic assignments of Prokaryotes and the 18S rDNA sequence (approximately 1869 nucleotides in length) of 40S SSU is used for Eukaryotes. 16S sequences are used for phylogenetic reconstruction as they are in general highly conserved, but contain specific hypervariable regions that harbor sufficient nucleotide diversity to differentiate genera and species of most bacteria.

[050] "Residual habitat products" refers to material derived from the habitat for microbiota within or on a human or animal. For example, microbiota live in feces in the gastrointestinal tract, on the skin itself, in saliva, mucus of the respiratory tract, or secretions of the genitourinary tract (*i.e.*, biological matter associated with the microbial community). Substantially free of residual habitat products means that the bacterial composition no longer contains the biological matter associated with the microbial environment on or in the human or animal subject and is 100% free, 99% free, 98% free, 97% free, 96% free, or 95% free of any contaminating biological matter associated with the microbial community. Residual habitat products can include abiotic materials (including undigested food) or it can include unwanted microorganisms. Substantially free of residual habitat products may also mean that the bacterial composition contains no detectable cells from a human or animal and that only microbial cells are detectable. In one embodiment, substantially free of residual habitat products may also mean that the bacterial composition contains no detectable viral (including bacterial viruses (*i.e.*, phage)), fungal, mycoplasmal contaminants. In another embodiment, it means that fewer than 1x10-2%, 1x10-3%, 1x10-4%, 1x10-5%, 1x10-6%, 1x10-7%, 1x10-8 of the viable cells in the bacterial composition are human or animal, as compared to microbial cells. There are multiple ways to accomplish this degree of purity, none of which are limiting. Thus, contamination may be reduced by isolating desired constituents through multiple steps of streaking to single colonies on solid media until replicate (such as, but not limited to, two) streaks from serial single colonies have shown only a single colony morphology. Alternatively, reduction of contamination can be accomplished by multiple rounds of serial dilutions to single desired cells (*e.g.*, a dilution of 10-8 or 10-9), such as through multiple 10-fold serial dilutions. This can further be confirmed by showing that multiple isolated colonies have similar cell shapes and Gram staining behavior. Other methods for confirming adequate purity include genetic analysis (*e.g.* PCR, DNA sequencing), serology and antigen analysis, enzymatic

and metabolic analysis, and methods using instrumentation such as flow cytometry with reagents that distinguish desired constituents from contaminants.

[051] "Spore" or a population of "spores" includes bacteria (or other single-celled organisms) that are generally viable, more resistant to environmental influences such as heat and bacteriocidal agents than vegetative forms of the same bacteria, and typically capable of germination and out-growth. Spores are characterized by the absence of active metabolism until they respond to specific environmental signals, causing them to germinate. "Spore-formers" or bacteria "capable of forming spores" are those bacteria containing the genes and other necessary abilities to produce spores under suitable environmental conditions. A Table of preferred spore-forming bacterial compositions is provided in Table 11.

[052] "Spore population" refers to a plurality of spores present in a composition. Synonymous terms used herein include spore composition, spore preparation, ethanol-treated spore fraction and spore ecology. A spore population may be purified from a fecal donation, *e.g.* via ethanol or heat treatment, or a density gradient separation or any combination of methods described herein to increase the purity, potency and/or concentration of spores in a sample. Alternatively, a spore population may be derived through culture methods starting from isolated spore former species or spore former OTUs or from a mixture of such species, either in vegetative or spore form.

[053] In one embodiment, the spore preparation comprises spore forming species wherein residual non-spore forming species have been inactivated by chemical or physical treatments including ethanol, detergent, heat, sonication, and the like; or wherein the non-spore forming species have been removed from the spore preparation by various separations steps including density gradients, centrifugation, filtration and/or chromatography; or wherein inactivation and separation methods are combined to make the spore preparation. In yet another embodiment, the spore preparation comprises spore forming species that are enriched over viable non-spore formers or vegetative forms of spore formers. In this embodiment, spores are enriched by 2-fold, 5-fold, 10-fold, 50-fold, 100-fold, 1000-fold, 10,000-fold or greater than 10,000-fold compared to all vegetative forms of bacteria. In yet another embodiment, the spores in the spore preparation undergo partial germination during processing and formulation such that the final composition comprises spores and vegetative bacteria derived from spore forming species.

[054] "Sporulation induction agent" is a material or physical-chemical process that is capable of inducing sporulation in a bacterium, either directly or indirectly, in a host organism and/or in vitro.

[055] To "increase production of bacterial spores" includes an activity or a sporulation induction agent. "Production" includes conversion of vegetative bacterial cells into spores and augmentation of the rate of such conversion, as well as decreasing the germination of bacteria in spore form, decreasing the rate of spore decay in vivo, or ex vivo, or to increasing the total output of spores (*e.g.* via an increase in volumetric output of fecal material).

[056] "Subject" refers to any animal subject including humans, laboratory animals (*e.g.*, primates, rats, mice), livestock (*e.g.*, cows, sheep, goats, pigs, turkeys, and chickens), and household pets (*e.g.*, dogs, cats, and rodents). The subject may be suffering from a dysbiosis, that contributes to or causes a condition classified as diabetes or pre-diabetes, including but not limited to mechanisms such as metabolic endotoxemia, altered metabolism of primary bile acids, immune system activation, or an imbalance or reduced production of short chain fatty acids including butyrate, propionate, acetate, and branched chain fatty acids.

[057] As used herein the term "Vitamin" is understood to include any of various fat-soluble or water-soluble organic substances (non-limiting examples include Vitamin A, Vitamin B1 (thiamine), Vitamin B2 (riboflavin), Vitamin B3 (niacin or niacinamide), Vitamin B5 (pantothenic acid), Vitamin B6 (pyridoxine, pyridoxal, or pyridoxamine, or pyridoxine hydrochloride), Vitamin B7 (biotin), Vitamin B9 (folic acid), and Vitamin B12 (various cobalamins; commonly cyanocobalamin in vitamin supplements), Vitamin C, Vitamin D, Vitamin E, Vitamin K, K1 and K2 (*i.e.*, MK-4, MK-7), folic acid and biotin) essential in minute amounts for normal growth and activity of the body and obtained naturally from plant and animal foods or synthetically made, pro-vitamins, derivatives, analogs.

[058] "V1-V9 regions" or "16S V1-V9 regions" refers to the 16S rRNA refers to the first through ninth hypervariable regions of the 16S rRNA gene that are used for genetic typing of bacterial samples. These regions in bacteria are defined by nucleotides 69-99, 137-242, 433-497, 576-682, 822-879, 986-1043, 1117-1173, 1243-1294 and 1435-1465 respectively using numbering based on the E. coli system of nomenclature. Brosius et al., Complete nucleotide sequence of a 16S ribosomal RNA gene from Escherichia coli, PNAS 75(10):4801-4805 (1978). In some embodiments, at least one of the V1, V2, V3, V4, V5, V6, V7, V8, and V9 regions are used to characterize an OTU. In one embodiment, the V1, V2, and V3 regions are used to characterize an OTU. In another embodiment, the V3, V4, and V5 regions are used to characterize an OTU. In another embodiment, the V4 region is used to characterize an OTU. A person of ordinary skill in the art can identify the specific hypervariable regions of a candidate 16S rRNA by comparing the candidate sequence in question to a reference sequence and identifying the hypervariable regions based on similarity to the reference hypervariable regions, or alternatively, one can employ Whole Genome Shotgun (WGS) sequence characterization of microbes or a microbial community.

Interactions Between Microbiome and Host

[059] Interactions between the human microbiome and the host shape host health and disease via multiple mechanisms, including the provision of essential functions by the microbiota. . Examples of these mechanisms include but are not limited to the function of the microbiota in ensuring a healthy level of bile acid metabolism, energy harvesting and storage, and regulation of immune responses, and reducing deleterious and unhealthy levels of gut permeability or metabolic endotoxemia.

Importance of Bile Acids to Human Health and Role of Microbiota

[060] Primary bile acids, cholic acid (CA) and chenodeoxycholic acid (CDCA) are synthesized from cholesterol in the liver in humans. The synthesized primary bile acids are conjugated to glycine, taurine, or sulfate before secretion into the bile by specific transporters located in the basolateral membrane of the hepatocyte. The ingestion of a meal triggers the release of bile from the gallbladder into the intestinal lumen, where bile acids form micelles with dietary lipids and lipid-soluble vitamins, facilitating their absorption. ~95% of bile acids are reabsorbed via specific transporters expressed in the distal ileum, and the remaining 5% escapes the enterohepatic cycle and travels towards the large intestine to be excreted in the feces. In the colon, the bile acids may undergo deconjugation and dehydroxylation by the gut microflora. The resulting secondary bile acids are mainly deoxycholic acid (DCA) and lithocholic acid (LCA). The bile acid pool undergoes this enterohepatic cycle around 12x/day in humans. Although the bile acid pool size is constant, the flux of bile acids varies during the day; bile acid flux and plasma bile acid concentrations are highest postprandially (See reviews Prawitt, J et al. 2011 Curr Diab Rep Bile acid metabolism and the pathogenesis of type 2 diabetes 11: 160-166; Nieuwdorp et al. 2014 Gastroenterology. Role of the Microbiome in Energy Regulation and Metabolism. pii: S0016-5085(14)00219-4. doi: 10.1053/j.gastro.2014.02.008).

[061] Commensal bacteria are involved in processing primary bile acids to secondary bile acids in the colon. Known biotransformations of bile acids by commensal GI bacteria include deconjugation of the conjugated bile salts to liberate free bile acids and amino acid moieties, removal of hydroxyl groups principally the C-7 hydroxyl group of the cholic acid moiety, oxidative and reductive reactions of the existing hydroxyl groups, and epimerization of bile acids.

[062] The canonical first step in bile acid metabolism is deconjugation of the taurine or glycine group through enzymes termed bile salt hydrolases, to yield CA and CDCA. These bile acids are then substrates for a series of enzymatic steps that remove the 7-alphahydroxy group to form deoxycholic acid (DCA) and lithocholic acid (LCA). LCA has particularly low solubility due to the loss of hydrophilic side chains compared to any of the other bile acids. It is also feasible for microbes to dehydroxylate the conjugated primary bile acids, giving rise to gluco-DCA; gluco-LCA; tauro-DCA; and tauro-LCA. Further modifications are possible, including the microbial conversion of CDCA to a 7-betahydroxy epimer, ursodeoxycholic acid (UDCA). Many other secondary bile acids are made in smaller amounts by the gut microbiota, for example, alpha-, beta-, gamma-, and omega-muricholic acids and many others (see Swann JR et al., 2011 PNAS Systemic gut microbial modulation of bile acid metabolism in host tissue compartments 108: 4523-30).

[063] Intestinal microbiota play a key role in bile acid metabolism. Germ-free mice have altered metabolism of bile acids, including increased levels of conjugated bile acids throughout the intestine, with no deconjugation, and strongly decreased fecal excretion. Provision of ampicillin to mice increases biliary bile acid output 3-fold and decreases fecal output by 70%.

[064] Dysbiosis of the gut microbiome affecting bile acid metabolism may affect adiposity, glucose regulation, and inflammation, among other effects. Bile acids are essential solubilizers of lipids, fats, and lipid soluble vitamins to enhance absorption of nutrients in the small intestine, and are also signaling molecules that regulate metabolism, including glucose homeostasis and basal metabolic rate. *See* Houten, SM *et al.* 2006 EMBO J. Endocrine function of bile acids. 25: 1419-25; Prawitt, J et al. 2011 Curr Diab Rep. Bile acid metabolism and the pathogenesis of type 2 diabetes. 11: 160-166. For example, bile acid sequestrants (non-absorbable polymers that complex bile acids in the intestinal lumen and divert them from the enterohepatic cycle) can improve glycemic control in Type 2 diabetes patients. Prawitt, J *et al.* 2011 Curr Diab Rep Bile acid metabolism and the pathogenesis of type 2 diabetes 11: 160-166.

[065] The most prominent targets of action by bile acids and their metabolites include FXR (farnesoid X receptor), an orphan nuclear receptor within the liver and intestine, and TGR5, a G-protein coupled receptor found on gallbladder, ileum, colon, brown and white adipose tissue. FXR is preferentially activated by CDCA, and in turn upregulates the expression of gene products including FGF-19 (fibroblast growth factor 19) in humans. FGF-15 (the murine analogue of FGF-19) increases basal metabolic rate and reverses weight gain in mice given a high fat diet. FXR activation also down-regulates hepatic gluconeogenesis. Although both conjugated and unconjugated bile acids can bind to FXR, the conjugated forms must be actively transported into the cell to initiate signaling whereas the unconjugated bile acids can diffuse through the membrane owing to their lower molecular weight, higher pKa and tendency to exist in the protonated form.

[066] TGR5 is preferentially activated by the secondary bile acid LCA and tauro-LCA with downstream effects, among others, on expression of incretin hormones such as GLP-1 that modulate insulin production and help maintain glucose homeostasis.

[067] Bile acids are therefore important metabolic regulators. Additional insight into the importance of the interplay between the gut microbiome, bile acid metabolism, and glucose homeostasis is provided by the observation that treating obese male patients with a 7-day course of vancomycin decreases total microbiota diversity, specifically depleting species in the diverse Clostridium IV and XIVa clusters. Among the Clostridia are various organisms that metabolize bile acids as well as others that produce short chain fatty acids, including butyrate and propionate. In contrast, treatment with a 7-day course of amoxicillin produces a trend toward increased microbiota diversity. Moreover, fecal bile acid composition is markedly changed following vancomycin treatment; secondary bile acids DCA, LCA and iso-LCA decrease whereas primary bile acids CA and CDCA increase. Amoxicillin treatment does not alter the ratio of bile acids in fecal samples. FGF-19 levels in serum are also decreased following vancomycin treatment, but not amoxicillin treatment. Peripheral insulin sensitivity changes following vancomycin but not amoxicillin treatment. Vrieze, A

et al., 2013 J Hepatol Impact of oral vancomycin on gut microbiota, bile acid metabolism, and insulin sensistivity dx.doi.org/10.1016/j.jhep.2013.11.034.

[068] While the study by Vrieze et al. points out the potential for microbes to improve insulin homeostasis through enhanced secondary bile acid metabolism, the authors point out several limitations of their work. Most importantly, while the HIT-Chip analysis used to generate fecal microbial profiles provides valuable information regarding classes of organisms, it does not provide mechanistic information or identify specific species or functional enzymatic pathways responsible for the observed effects. Moreover, the HIT-Chip is a hybridization based assay and the similarity of sequences among the organisms in the Clostridial clusters may lead to mis-assignments. As a result, others have failed to define specific compositions that can be used to modulate insulin sensitivity via bile acid metabolism.

[069] In addition to the role for bile acids as metabolic regulators, bile acids are also linked to inflammatory disease. Crohn's Disease patients in the Metagenomics of the Human Intestinal Tract (MetaHIT) cohort show reduced bile salt hydrolase (BSH) gene abundance compared to patients without disease, and increased primary bile acids in inflammatory bowel syndrome patients is correlated with stool frequency and consistency (Duboc et al. 2012 Neurogastroenterol Motil. Increase in fecal primary bile acids and dysbiosis in patients with diarrhea-predominant irritable bowel syndrome. doi: 10.1111/j.1365-2982.2012.01893.x). Furthermore, TGR5 is expressed on immune monocytes and macrophages in addition to GI and liver tissues, and FXR and TGR5 are known to be involved in regulation of inflammation in enterohepatic tissues (Jones et al., 2014 Expert Opin Biol Ther The human microbiome and bile acid metabolism: dysbiosis, dysmetabolism, disease and intervention doi:10.1517/14712598.2014.880420)

[070] Multiple methods are available for determination of bile acids in serum, bile and faces of individuals. As reviewed by Sharma (Sharma, KR, Review on bile acid analysis, Int J Pharm Biomed Sci 2012, 3(2), 28-34), a variety of methods can be used, such as chemical (Carey JB, et al, 1958, The bile acids in normal human serum with comparative observations in patients with jaundice. J Lab Clin Med 1958, 46, 860-865), thin layer chromatography (Fausa O, and Shalhegg BA. 1976 Quantitative determination of bile acids and their conjugates using thin-layer chromatography and a purified 3-α hydroxysteroid dehydrogenase. Scand J Gastroenterol 9, 249-254.), high performance liquid chromatography (Islam S, et al Fasting serum bile acid level in cirrhosis "A semi quantitative index of hepatic function". J Hepatol 1985, 1, 609-617; Paauw JD, at al. Assay for taurine conjugates of bile acids in serum by reversed phase high performance liquid chromatography. J Chromatograph B Biomed Appl 1996, 685, 171-175), radioimmunoassay (Wildgrube J, Stockhausan H, Peter M, Mauritz G, Mahdawi R. Radioimmunoassay of bile acids in tissues, bile and urine. Clin Chem 1983, 29, 494-498), enzyme linked colorimetric and radioimmunoassay (Guo W, et al. A study on detection of serum fasting total bile acid and cholog lycin in neonates for cholestasis. Chin Med Sci J 1996, 11,

244-247.), mass spectrometry (Sjovell J, et al. Mass spectrometry of bile acids. Method in enzymology. Vol. III, Academic Press, New York 1985.), tandem mass spectrometry (Griffiths WJ. Tandem mass spectrometry in study of fatty acids, bile acids and steroids. Mass Spectrum Rev 2003, 22, 81-152.), gas chromatography using high resolution glass capillary columns and mass spectrometry (Setchell KDR, Matsui A. Serum bile acid analysis. Clin Chim Acta 1983, 127, 1-17.), gas chromatography (Fischer S, et al. Hepatic levels of bile acids in end stage chronic cholestatic liver disease. Clin Chim Acta 1996, 251, 173-186.), gas liquid chromatography (Van Berge Hengouwen GP et al., Quantitative anaylsis of bile acids in serum and bile, using gas liquid chromatography. Clin Chim Acta 1974, 54, 249-261; Batta AK, et al. Characterization of serum and urinary bile acids in patients with primary biliary cirrhosis by gas-liquid chromatography-mass spectrometry: effect of ursodeoxycholic acid treatment. J Lipid Res 1989, 30, 1953- 1962), luminometric method (Styrellius I, Thore A, Bjorkhem I. Luminometric method. In: Methods of enzymatic analysis. (Ed. III). Bergmeyer, Hans Ulrich [Hrsg]. 8: 274-281, 1985.), UV method for bile assay (Staver E, et al. Fluorimetric method for serum. In: Methods of enzymatic analysis. (Ed.III). Bergmeyer, Hans Ulrich; [Hrsg]. 8, 288-290, 1985; Staver E, et al. UV method for bile, gastric juice and duodenai aspirates. In: Methods of enzymatic analysis, (e.d.III). Bergmeyer, Hans Ulrich [Hrsg]. 8: 285-287, 1985), enzymatic colorimetric method (Collins BJ, et al. Measurement of total bile acids in gastric juice. J Clin Pathol 1984, 37, 313-316) and enzymatic fluorimetric method can be used (Murphy GM, et al. A fluorometric and enzymatic method for the estimation of serum total bile acids. J Clin Path 1970, 23, 594-598; Hanson NQ, Freier E F. Enzymic measurement of total bile acid adapted to the Cobas Fara Centrifugal analyzer. Clin Chem. 1985, 35, 1538-1539).

Importance of Short Chain Fatty Acids (SCFA) to Human Health and Role of Microbiota

[071] Short chain fatty acids (SCFAs) are a principal product of bacterial fermentation in the colon. SCFAs, particularly acetate, propionate and butyrate, are thought to have many potential benefits to the mammalian host. SCFAs are organic acids with fewer than 6 carbons and include acetate, propionate, butyrate, valerate, isovalerate, and 2-methyl butyrate. While longer chain fatty acids are derived primarily from dietary sources, SCFAs are derived from the breakdown of non-digestible plant fiber. Butyrate is a primary energy source for colonocytes, whereas propionate is thought to be metabolized mostly by the liver via portal vein circulation from the colon. Acetate is derived from the microbiota is thought to be more generally available to tissues.

[072] In addition to acting as metabolic substrates, SCFAs have multiple benefits, including that SCFAs produced by the microbiota are essential for immune homeostasis and particularly for immune modulation by regulatory T cells. Direct ingestion of acetate, propionate or butyrate, or a mixture of all three by mice, stimulates the proliferation and maturation of regulatory T cells (Tregs) that reside in the colon. Mice given SCFAs in drinking water have significantly higher levels of colonic CD4+ FoxP3+ T cells (Tregs) than germ free and SPFA controls, and these Treg cells are functionally more

potent as measured by the expression of IL-10 mRNA and protein, and by their ability to inhibit CD8+ effector T cells in vitro (Smith PM et al. 2013 Science The microbial metabolites, short-chain fatty acid regulate colonic Treg cell homeostasis 341: 569-73). This effect of SCFAs is mediated via signaling through GPR43 (FFAR2), a G protein coupled receptor expressed on a variety of cells but with high frequency on colonic Treg cells. GPR43 signaling is upstream of modification of histone deacetylase activity (particularly HDAC9 and HDCA3), which is known to alter gene expression via reconfiguration of chromatin. Furthermore, the effects of experimental colitis induced by adoptive T cell transfer are reduced by SCFAs including propionate alone and a mixture of acetate, propionate or butyrate in a GPR43 dependent fashion.

[073] Beyond the direct effects of SCFA administered orally to animals, microbes can produce SCFA in situ in the colon and improve outcomes in several disease models. Daily administration of 10^9 cfu of Butyricicoccus pullicaecorum, a butyrate forming organism first isolated from chickens, for 1 week ameliorates TNBS-induced colitis in a rat model (Eeckhaut V et al., 2013 Gut Progress towards butyrate-producing pharmabiotics: Butyricicoccus pullicaecorum capsule and efficacy in TNBS models in comparison with therapeutics doi:10.1136/gutjnl-2013-305293). In humans, topical administration of butyrate or sodium butyrate via a rectal enema may be beneficial to ulcerative colitis patients (Scheppach W et al.1992 Gastroenterol Effect of butyrate enemas on the colonic mucosa in distal ulcerative colitis 103: 51–56; Vernia P et al. 2003 Eur. J. Clin. Investig Topical butyrate improves efficacy of 5-ASA in refractory distal ulcerative colitis: results of a multicentre trial. 33: 244–48). Butyrate has effects at multiple levels including signaling via GPR109A, which is expressed on the apical surface of intestinal epithelial cells (IECs). GPR109A lowers NFKB-mediated gene expression, including reduced expression of the inflammatory cytokines TNF-alpha, IL-6 and IL-1beta.

[074] Oral administration of SCFAs in mice also has direct effects on metabolism. SCFAs are a significant energy source and thus fermentation by the microbiota can contribute up 5-10% of the basal energy requirements of a human. SCFAs upregulate production of glucagon-like peptide 1 (GLP-1), peptide (P)YY and insulin. GLP-1 and PYY are noted to play a role in enhancing satiety and reducing food intake. Furthermore, fecal transplantation from lean human donors to obese recipients with metabolic syndrome results in a significant increase in insulin sensitivity after 6 weeks. This change is most correlated with the transfer of Eubacterium hallii, a gram-positive, butyrate-fermenting microbe (Vrieze, A., et al., 2012 Gastroenterol Transfer of intestinal microbiota from lean donors increases insulin sensitivity 143: 913-6).

[075] A common factor underlying both diabetes and obesity is the phenomenon of low-level inflammation termed metabolic endotoxemia (see below). Metabolic endotoxemia refers to increased permeability of the gut ("leaky gut syndrome") coupled with increased translocation of lipopolysaccharide (LPS), mediating an inflammatory response that triggers insulin resistance,

changes in lipid metabolism, and liver inflammation responsible for non-alcoholic fatty liver disease (NAFLD). Low level bacteremia may also lead to the translocation of viable gram-negative organisms into distal tissues, such as adipocytes, and further drive inflammation. SCFAs provide a benefit here as well, both by providing an energy source to enhance colonic epithelial cell integrity and by stimulating the expression of tight junction proteins to reduce translocation of gram-negative LPS, bacterial cells and their fragments (Wang HB et al, 2012 Dig Dis Sci Butyrate enhances intestinal epithelial barrier function via up-regulation of tight junction protein Claudin-1 transcription 57: 3126-35).

[076] For all of these reasons, it would be useful to have microbial communities with an enhanced ability to produce SCFAs for the treatment of diseases such as diabetes, obesity, inflammation, ulcerative colitis and NAFLD.

[077] Acetate, propionate and butyrate are formed as end-products in anaerobic fermentation. SCFA producing bacteria in the gut gain energy by substrate-level phosphorylation during oxidative breakdown of carbon precursors. However, the resulting reducing equivalents, captured in the form of NADH, must be removed to maintain redox balance, and hence the energetic driving force to produce large amounts of reduced end-products such as butyrate and propionate, in order to regenerates NAD+. Acetate, propionate and butyrate are not the only end products of fermentation: microbes in the gut also produce lactate, formate, hydrogen and carbon dioxide depending on the conditions. As discussed below, lactate and acetate can also drive the formation of butyrate and propionate through cross-feeding by one microorganism to another.

[078] The rate of SCFA production in the colon is highly dependent on many factors including the availability of polysaccharide carbon sources (such as, but not limited to, fructans, starches, cellulose, galactomannans, xylans, arabinoxylans, pectins, inulin, fructooligosaccharides, and the like), the presence of alternative electron sinks such as sulfate and nitrate, the redox potential, hydrogen (H_2) partial pressure and pH. As described above, cross-feeding among organisms can also play a role, for instance when a lactate forming organism provides lactate as a substrate for a butyrate or propionate producer, or when a saccharolytic organism breaks down a complex carbohydrate to provide a mono- or disaccharide for fermentation. Acetate, which can be as high as 30 mM in the gut, is also a key building block of butyrate through the action of the enzyme butyryl-CoA:acetate CoA transferase, the final step in the production of butyrate. Importantly, this enzyme can also function as a propionyl-CoA: acetate CoA transferase, resulting in the production of propionate.

[079] Since diet is a principal determinant of the variety of carbon sources and other nutrients available in the colon, it is clear that a functional ecology for SCFA production will comprise multiple organisms capable of adapting to diet-driven changes in in the gut environment. Thus, there exists a need for a bacterial composition that can ferment sufficient quantities of SCFA products in spite of

the varying environmental conditions imposed by a changing diet. Such bacterial compositions will comprise organisms capable of fermenting a variety of carbon sources into SCFA.

Role of Microbiota in Metabolic Endotoxemia/Bacteremia

[080] Chronic, low-grade inflammation is characteristic of obesity and is recognized to play an underlying pathogenic role in the metabolic complications and negative health outcomes of the disease. Notably, obesity is associated with elevated plasma levels of bacterial lipopolysaccharide (LPS). Energy intake, in particular a high fat diet (HFD), increases gut permeability and increases plasma LPS levels 2- to 3-fold. LPS in the circulatory system reflects passage of bacterial fragments across the gut into systemic circulation (termed "metabolic endotoxemia"), either through increases in diffusion due to intestinal paracellular permeability or through absorption by enterocytes during chylomicron secretion. Subcutaneous infusion of LPS into wild type mice maintained on a normal chow diet for 4 weeks leads to increased whole body, liver and adipose tissue weights, adipose and liver inflammation as well as fasted hyperglycemia and insulinemia, effects that are comparable to those induced by HFD (Cani et al., 2007 Diabetes. Metabolic endotoxemia initiates obesity and insulin resistance doi:10.2337/db06-1491). In addition to bacterial fragments, the translocation of live bacteria to host tissues may also be a feature of obesity (termed "metabolic bacteremia") (Shen et al., 2013 Mol Aspects Med. The gut microbiota, obesity and insulin resistance doi: 10.1016/j.mam.2012.11.001).

[081] Host–microbiota interactions at the gut mucosal interface are involved in intestinal barrier functionality and bacterial surveillance/detection. Dysbiosis can promote bacterial translocation and obesity-associated inflammation. In one instance, metabolic endotoxemia of HFD-induced obesity in mice is associated with reductions in Bifidobacterium, and both may be ameliorated through treatment with inulin (oligofructose) (Cani et al. Diabetologia Selective increases of bifidobacteria in gut microflora improve high-fat-diet-induced diabetes in mice through a mechanism associated with endotoxaemia doi: 10.1007/s00125-007-0791-0). The beneficial effects of inulin and Bifidobacterium are associated with enhanced production of intestinotrophic proglucagon-derived peptide 2 (GLP-2), a peptide produced by L cells of the intestine that promotes intestinal growth (Cani et al. Gut. Changes in gut microbiota control inflammation in obese mice through a mechanism involving GLP-2-driven improvement of gut permeability. doi:10.1136/gut.2008.165886). Alternative pathways involving host-microbiota interactions and intestinal barrier integrity and metabolic endotoxemia/bacteremia include but are not limited to those involving intestinotrophic proglucagon-derived peptide (GLP)-2, endocannabinoid (eCB) signaling, and pattern recognition receptors including nucleotide-binding oligomerization domain (NOD)-like receptors (NLR) such as NOD1/NLRC1 and NOD2/NLRC2 as well as Toll like receptors (TLR) such as TLR-2, TLR-4, TLR-5 and TLR adapter protein myeloid differentiation primary-response protein 88 (MyD88) (see review Shen et al., 2013 Mol Aspects Med. The gut microbiota, obesity and insulin resistance doi: 10.1016/j.mam.2012.11.001).

Role of Microbiota in Energy Harvesting and Storage

[082] The gut microbiota is involved in host energy harvesting. Germ free (GF) mice consume more energy but are significantly leaner than wild type counterparts. Conventionalization of GF mice given a low-fat, polysaccharide-rich diet with the microbiota of conventionally-raised mice leads to 60% more adiposity and insulin resistance despite reduced food intake (Backhed et al., 2004 PNAS The gut microbiota as an environmental factor that regulates fat storage doi: 10.1073/pnas.0407076101). GF mice conventionalized with microbiota from obese mice show significantly greater increase in total body fat than GF mice conventionalized with microbiota from lean mice. Obese (ob/ob) mice have significantly less energy remaining in their feces relative to their lean littermates as measured by bomb calorimetry (Turnbaugh et al. 2006 Nature. An obesity-associated gut microbiome with increased capacity for energy harvest doi:10.1038/nature05414). In humans, "overnutrition" (defined as energy consumption as a percentage of weight-maintaining energy needs) is associated with proportionally more Firmicutes and fewer Bacteroidetes and energy loss (stool calories as a percentage of ingested calories) in lean subjects is negatively associated with the proportional change in Firmicutes and positively associated with the proportional change in Bacteroidetes, suggesting impact of the gut microbiota on host energy harvest (Jumpertz et al., 2011 Am J Clin Nutr. Energy-balance studies reveal associations between gut microbes, caloric load, and nutrient absorption in humans. doi: 10.3945/ajcn.110.010132).

[083] In addition to affecting host energy harvesting, gut microbiota is also implicated in energy storage. The increase in body fat observed upon conventionalization of GF mice is associated with a decrease in Fasting-induced adipose factor (Fiaf) expression in the ileum and a 122% increase in Lipoprotein Lipase (LPL) activity in epididymal adipose tissue (Backhed et al., 2004 PNAS The gut microbiota as an environmental factor that regulates fat storage doi/10.1073/pnas.0407076101). Fiaf (also known as angiopoietin-like 4) is a protein secreted by adipose tissues, liver and intestine that inhibits the activity of LPL, a key enzyme in the hydrolysis of lipoprotein-associated triglycerides and the release of fatty acids for transport into cells. In adipocytes, fatty acids released by LPL are re-esterified into triglyceride and stored as fat (Shen et al., 2013 Mol Aspects Med. The gut microbiota, obesity and insulin resistance doi: 10.1016/j.mam.2012.11.001).

Other Functional Pathways

[084] The pathways and mechanisms discussed above on the functional pathways and mechanisms by which the microbiota shape host health and disease is not meant to be exhaustive. Alternative functional pathways and mechanisms exist, including but not limited to pathways involving AMP-activated protein kinase (AMPK), TLR-5, and SREBP-1c and ChREBP.

Emergence of Antibiotic Resistance in Bacteria

[085] Antibiotic resistance is an emerging public health issue (Carlet J, Collignon P, Goldmann D, Goossens H, Gyssens IC, Harbarth S, Jarlier V, Levy SB, N'Doye B, Pittet D, et al. 2011. Society's failure to protect a precious resource: antibiotics. Lancet 378: 369–371.). Numerous genera

of bacteria harbor species that are developing resistance to antibiotics. These include but are not limited to Vancomycin Resistant Enterococcus (VRE) and Carbapenem resistant Klebsiella (CRKp). Klebsiella pneumoniae and Escherichia coli strains are becoming resistant to carbapenems and require the use of old antibiotics characterized by high toxicity, such as colistin (Cantón R, Akóva M, Carmeli Y, Giske CG, Glupczynski Y, Gniadkowski M, Livermore DM, Miriagou V, Naas T, Rossolini GM, et al. 2012. Rapid evolution and spread of carbapenemases among Enterobacteriaceae in Europe. Clin Microbiol Infect 18: 413–431.). Further multiply drug resistant strains of multiple species, including Pseudomonas aeruginosa, Enterobacter spp, and Acinetobacter spp are observed clinically including isolates that are highly resistant to ceftazidime, carbapenems, and quinolones (European Centre for Disease Prevention and Control: EARSS net database. http://ecdc.europa.eu.). The Centers for Disease Control and Prevention in 2013 released a Threat Report (http://www.cdc.gov/drugresistance/threat-report-2013/) citing numerous bacterial infection threats that included Clostridium difficile, Carbapenem-resistant Enterobacteriaceae (CRE), Multidrug-resistant Acinetobacter, Drug-resistant Campylobacter, Extended spectrum β-lactamase producing Enterobacteriaceae (ESBLs), Vancomycin-resistant Enterococcus (VRE), Multidrug-resistant Pseudomonas aeruginosa, Drug-resistant Non-typhoidal Salmonella, Drug-resistant Salmonella Typhi, Drug-resistant Shigella, Methicillin-resistant Staphylococcus aureus (MRSA), Drug-resistant Streptococcus pneumoniae, Vancomycin-resistant Staphylococcus aureus (VRSA), Erythromycin-resistant Group A Streptococcus, and Clindamycin-resistant Group B Streptococcus. The increasing failure of antibiotics due the rise of resistant microbes demands new therapeutics to treat bacterial infections. Administration of a microbiome therapeutic bacterial composition offers potential for such therapies. Applicants have discovered that patients suffering from recurrent *C. difficile* associated diarrhea (CDAD) often harbor antibiotic resistant Gram-negative bacteria, in particular Enterobacteriaceae and that treatment with a bacterial composition effectively treats CDAD and reduces the antibiotic resistant Gram-negative bacteria. The gastrointestinal tract is implicated as a reservoir for many of these organisms including VRE, MRSA, Pseudomonas aeruginosa, Acinetobacter and the yeast Candida (Donskey, Clinical Infectious Diseases 2004 39:214,The Role of the Intestinal Tract as a Reservoir and Source for Transmission of Nosocomial Pathogens), and thus as a source of nosocomial infections. Antibiotic treatment and other decontamination procedures are among the tools in use to reduce colonization of these organisms in susceptible patients including those who are immunosuppressed. Bacterial-based therapeutics would provide a new tool for decolonization, with a key benefit of not promoting antibiotic resistance as antibiotic therapies do.

COMPOSITIONS OF THE INVENTION

Network Ecologies

[086] As described above, the Network Ecology and Functional Network Ecology refer to a consortium of OTUs or Functional modalities respectively that co-occur in a group of subjects. The network is defined mathematically by a graph delineating how specific nodes (*i.e.*, OTUs or

functional modalities) and edges (connections between specific OTUs or functional modalities) relate to one another to define the structural ecology of a consortium of OTUs or functions. Any given Network Ecology or Functional Network Ecology will possess inherent phylogenetic diversity and functional properties.

[087] A Network Class or Core Network refers to a group of Network Ecologies or Functional Network ecologies that are computationally determined to comprise ecologies with similar phylogenetic and/or functional characteristics. A Network Class or Core Network therefore contains important biological features, defined either phylogenetically or functionally, of a group (*i.e.*, a cluster) of related network ecologies.

[088] Keystone OTUs or Functions are one or more OTUs or Functions that are common to many network Ecologies or Functional Netwok Ecologies and are members of Networks Ecologies or Functional Network Ecologies that occur in many subjects (*i.e.*, are pervasive). Due to the ubiquitous nature of Keystone OTUs and Functions, they are central to the function of network ecologies in healthy subjects and are often missing or at reduced levels in subjects with disease. Keystone OTUs and Functions may exist in low, moderate, or high abundance in subjects.

[089] Bacteria that are members of the keystone OTUs, core network or network ecology are provided herein.

Bacterial Compositions

[090] Provided are bacteria and combinations of bacteria that comprise network ecologies and functional network ecologies of the human gut microbiota. The bacteria and combinations of bacteria that comprise network ecologies have a capacity to meaningfully provide functions of a healthy microbiota when administered to mammalian hosts. Without being limited to a specific mechanism, it is believed that the members of network ecologies can inhibit the growth, proliferation, germination and/or colonization of one or a plurality of pathogenic bacteria in the dysbiotic microbiotal niche, and may also augment the growth, proliferation, germination and/or colonization of desired bacteria so that a healthy, diverse and protective microbiota colonizes and populates the intestinal lumen to establish or reestablish ecological control over pathogens or potential pathogens (*e.g.*, some bacteria are pathogenic bacteria only when present in a dysbiotic environment). The term pathogens refers to a bacterium or a group of bacteria or any other organism or entity that is capable of causing or affecting a disease, disorder or condition of a host containing the bacterium, organism or entity, including but not limited to metabolic diseases such as prediabetes, type 1 diabetes, and type 2 diabetes.

[091] As used herein, a "type" or more than one "types" of bacteria may be differentiated at the genus level, the species, level, the sub-species level, the strain level or by any other taxonomic method, as described herein and otherwise known in the art.

[092] Bacterial compositions can comprise two types of bacteria (termed "binary combinations" or "binary pairs"), and typically a large number of bacteria types. For instance, a bacterial composition can comprise at least 2, at least 3, at least 4, at least 5, at least 6, at least 7, at least 8, at least 9, at least 10, at least 11, at least 12, at least 13, at least 14, at least 15, at least 16, at least 17, at least 18, at least 19, at least 20, or at least 21, 22, 23, 24, 25, 26, 27, 28, 29 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, or at least 40, at least 50 or greater than 50 types of bacteria, as defined by species or operational taxonomic unit (OTU), or otherwise as provided herein. In some embodiments, the bacterial composition includes at least 60, 70, 80, 90, 100, 150, 200, 250, 300, 350, 400, 450, 500, 550, 600, or greater numbers of bacteria types.

[093] In another embodiment, the number of types of bacteria present in a bacterial composition is at or below a known value. For example, in such embodiments the network ecology comprises 1000, 900, 800, 700, 600, 500, 400, 300, 200, 100, 50 or fewer types of bacteria, such as 49, 48, 47, 46, 45, 44, 43, 42, 41, 40, 39, 38, 37, 36, 35, 34, 33, 32, 31, 30, 29, 28, 27, 26, 25, 24, 23, 22, 21, 20, 19, 18, 17, 16, 15, 14, 13, 12, 11, or 10 or fewer, or 9 or fewer types of bacteria, 8 or fewer types of bacteria, 7 or fewer types of bacteria, 6 or fewer types of bacteria, 5 or fewer types of bacteria, 4 or fewer types of bacteria, or 3 or fewer types of bacteria.

Bacterial Compositions Described by Species

[094] Bacterial compositions that comprise network ecologies may be prepared comprising at least two types of isolated bacteria, chosen from the species in Table 1.

[095] In one embodiment, the bacterial composition that comprises at least one and preferably more than one of the following: *Enterococcus faecalis* (previously known as *Streptococcus faecalis*), *Clostridium innocuum*, *Clostridium ramosum*, *Bacteroides ovatus*, *Bacteroides vulgatus*, *Bacteroides thetaoiotaomicron*, *Escherichia coli* (1109 and 1108-1), *Clostridum bifermentans*, and *Blautia producta* (previously known as *Peptostreptococcus productus*). In an alternative embodiment, at least one of the preceding species is not substantially present in the bacterial composition.

[096] In one embodiment, the bacterial composition comprises at least one and preferably more than one of the following: *Enterococcus faecalis* (previously known as *Streptococcus faecalis*), *Clostridium innocuum*, *Clostridium ramosum*, *Bacteroides ovatus*, *Bacteroides vulgatus*, *Bacteroides thetaoiotaomicron*, *Escherichia coli* (1109 and 1108-1), *Clostridum bifermentans*, and *Blautia producta* (previously known as *Peptostreptococcus productus*). In an alternative embodiment, at least one of the preceding species is not substantially present in the bacterial composition.

[097] In another embodiment, the bacterial composition comprises at least one and preferably more than one of the following: *Acidaminococcus intestinalis*, *Bacteroides ovatus*, two strains of *Bifidobacterium adolescentis*, two strains of *Bifidobacterium longum*, *Blautia producta*, *Clostridium cocleatum*, *Collinsella aerofaciens*, two strains of *Dorea longicatena*, *Escherichia coli*, *Eubacterium desmolans*, *Eubacterium eligens*, *Eubacterium limosum*, four strains of *Eubacterium rectale*,

Eubacterium ventriosumi, Faecalibacterium prausnitzii, Lachnospira pectinoshiza, Lactobacillus casei, Lactobacillus casei/paracasei, Paracateroides distasonis, Raoultella sp., one strain of *Roseburia* (chosen from *Roseburia faecalis* or *Roseburia faecis*), *Roseburia intestinalis,* two strains of *Ruminococcus torques, two* strains of *Ruminococcus obeum,* and *Streptococcus mitis*. In an alternative embodiment, at least one of the preceding species is not substantially present in the bacterial composition.

[098] In yet another embodiment, the bacterial composition comprises at least one and preferably more than one of the following: *Barnesiella intestinihominis; Lactobacillus reuteri;* a species characterized as one of *Enterococcus hirae, Enterococus faecium*, or *Enterococcus durans;* a species characterized as one of *Anaerostipes caccae* or *Clostridium indolis;* a species characterized as one of *Staphylococcus warneri* or *Staphylococcus pasteuri*; and *Adlercreutzia equolifaciens.* In an alternative embodiment, at least one of the preceding species is not substantially present in the bacterial composition.

[099] In other embodiments, the bacterial composition comprises at least one and preferably more than one of the following: *Clostridium absonum, Clostridium argentinense, Clostridium baratii, Clostridium bartlettii, Clostridium bifermentans, Clostridium botulinum, Clostridium butyricum, Clostridium cadaveris, Clostridium camis, Clostridium celatum, Clostridium chauvoei, Clostridium clostridioforme, Clostridium cochlearium, Clostridium difficile, Clostridium fallax, Clostridium felsineum, Clostridium ghonii, Clostridium glycolicum, Clostridium haemolyticum, Clostridium hastiforme, Clostridium histolyticum, Clostridium indolis, Clostridium innocuum, Clostridium irregulare, Clostridium limosum, Clostridium malenominatum, Clostridium novyi, Clostridium oroticum, Clostridium paraputrificum, Clostridium perfringens, Clostridium piliforme, Clostridium putrefaciens, Clostridium putrificum, Clostridium ramosum, Clostridium sardiniense, Clostridium sartagoforme, Clostridium scindens, Clostridium septicum, Clostridium sordellii, Clostridium sphenoides, Clostridium spiroforme, Clostridium sporogenes, Clostridium subterminale, Clostridium symbiosum, Clostridium tertium, Clostridium tetani, Clostridium welchii,* and *Clostridium villosum*. In an alternative embodiment, at least one of the preceding species is not substantially present in the bacterial composition.

[0100] In one embodiment, the bacterial composition that comprises a network ecology comprises at least one and preferably more than one of the following: *Clostridium innocuum, Clostridum bifermentans, Clostridium butyricum, Bacteroides fragilis, Bacteroides thetaiotaomicron, Bacteroides uniformis*, three strains of *Escherichia coli*, and *Lactobacillus sp.* In an alternative embodiment, at least one of the preceding species is not substantially present in the bacterial composition.

[0101] In one embodiment, the bacterial composition that comprises a network ecology comprises at least one and preferably more than one of the following: *Clostridium bifermentans, Clostridium innocuum, Clostridium butyricum*, three strains of *Escherichia coli*, three strains of *Bacteroides,* and

Blautia producta. In an alternative embodiment, at least one of the preceding species is not substantially present in the bacterial composition.

[0102] In one embodiment, the bacterial composition that comprises a network ecology comprises at least one and preferably more than one of the following: *Bacteroides sp.*, *Escherichia coli*, and non pathogenic *Clostridia*, including *Clostridium innocuum*, *Clostridium bifermentans* and *Clostridium ramosum*. In an alternative embodiment, at least one of the preceding species is not substantially present in the bacterial composition.

[0103] In one embodiment, the bacterial composition that comprises a network ecology comprises at least one and preferably more than one of the following: *Bacteroides* species, *Escherichia coli* and non-pathogenic *Clostridia*, such as *Clostridium butyricum, Clostridium bifermentans* and *Clostridium innocuum*. In an alternative embodiment, at least one of the preceding species is not substantially present in the bacterial composition.

[0104] In one embodiment, the bacterial composition that comprises a network ecology comprises at least one and preferably more than one of the following: *Bacteroides caccae, Bacteroides capillosus, Bacteroides coagulans, Bacteroides distasonis, Bacteroides eggerthii, Bacteroides forsythus, Bacteroides fragilis, Bacteroides fragilis-ryhm, Bacteroides gracilis, Bacteroides levii, Bacteroides macacae, Bacteroides merdae, Bacteroides ovatus, Bacteroides pneumosintes, Bacteroides putredinis, Bacteroides pyogenes, Bacteroides splanchnicus, Bacteroides stercoris, Bacteroides tectum, Bacteroides thetaiotaomicron, Bacteroides uniformis, Bacteroides ureolyticus,* and *Bacteroides vulgatus*. In an alternative embodiment, at least one of the preceding species is not substantially present in the bacterial composition.

[0105] In one embodiment, the bacterial composition that comprises a network ecology comprises at least one and preferably more than one of the following: *Bacteroides, Eubacteria, Fusobacteria, Propionibacteria,* Lactobacilli, *anaerobic cocci, Ruminococcus, Escherichia coli, Gemmiger, Desulfomonas,* and *Peptostreptococcus*. In an alternative embodiment, at least one of the preceding species is not substantially present in the bacterial composition.

[0106] In one embodiment, the bacterial composition that comprises a network ecology comprises at least one and preferably more than one of the following: *Bacteroides fragilis ss. Vulgatus, Eubacterium aerofaciens, Bacteroides fragilis ss. Thetaiotaomicron, Blautia producta* (previously known as *Peptostreptococcus productus II*), *Bacteroides fragilis ss. Distasonis, Fusobacterium prausnitzii, Coprococcus eutactus, Eubacterium aerofaciens III, Blautia producta* (previously known as *Peptostreptococcus productus I*), *Ruminococcus bronii, Bifidobacterium adolescentis, Gemmiger formicilis, Bifidobacterium longum, Eubacterium siraeum, Ruminococcus torques, Eubacterium rectale III-H, Eubacterium rectale IV, Eubacterium eligens, Bacteroides eggerthii, Clostridium leptum, Bacteroides fragilis ss. A, Eubacterium biforme, Bifidobacterium infantis, Eubacterium rectale III-F, Coprococcus comes, Bacteroides capillosus, Ruminococcus albus, Eubacterium*

formicigenerans, Eubacterium hallii, Eubacterium ventriosum I, Fusobacterium russii, Ruminococcus obeum, Eubacterium rectale II, Clostridium ramosum I, Lactobacillus leichmanii, Ruminococcus cailidus, Butyrivibrio crossotus, Acidaminococcus fermentans, Eubacterium ventriosum, Bacteroides fragilis ss. fragilis, Bacteroides AR, Coprococcus catus, Eubacterium hadrum, Eubacterium cylindroides, Eubacterium ruminantium, Eubacterium CH-1, Staphylococcus epidermidis, Peptostreptococcus BL, Eubacterium limosum, Bacteroides praeacutus, Bacteroides L, Fusobacterium mortiferum I, Fusobacterium naviforme, Clostridium innocuum, Clostridium ramosum, Propionibacterium acnes, Ruminococcus flavefaciens, Ruminococcus AT, Peptococcus AU-1, Eubacterium AG, -AK, -AL, -AL-1, -AN; Bacteroides fragilis ss. ovatus, -ss. d, -ss. f; Bacteroides L-1, L-5; Fusobacterium nucleatum, Fusobacterium mortiferum, Escherichia coli, Streptococcus morbiliorum, Peptococcus magnus, Peptococcus G, AU-2; Streptococcus intermedius, Ruminococcus lactaris, Ruminococcus CO Gemmiger X, Coprococcus BH, -CC; Eubacterium tenue, Eubacterium ramulus, Eubacterium AE, -AG-H, -AG-M, -AJ, -BN-1; Bacteroides clostridiiformis ss. clostridliformis, Bacteroides coagulans, Bacteroides orails, Bacteroides ruminicola ss. brevis, -ss. ruminicola, Bacteroides splanchnicus, Desuifomonas pigra, Bacteroides L-4, -N-i; Fusobacterium H, Lactobacillus G, and *Succinivibrio A*. In an alternative embodiment, at least one of the preceding species is not substantially present in the bacterial composition.

Bacterial Compositions Described by Operational Taxonomic Unit (OTUs)

[0107] Bacterial compositions may be prepared comprising at least two types of isolated bacteria, chosen from the SEQ ID Numbers (OTUs) in Table 1.

[0108] OTUs can be defined either by full 16S sequencing of the rRNA gene (Table 1), by sequencing of a specific hypervariable region of this gene (*i.e.* V1, V2, V3, V4, V5, V6, V7, V8, or V9), or by sequencing of any combination of hypervariable regions from this gene (*e.g.* V1-3 or V3-5). The bacterial 16S rDNA is approximately 1500 nucleotides in length and is used in reconstructing the evolutionary relationships and sequence similarity of one bacterial isolate to another using phylogenetic approaches. 16S sequences are used for phylogenetic reconstruction as they are in general highly conserved, but contain specific hypervariable regions that harbor sufficient nucleotide diversity to differentiate genera and species of most microbes.

[0109] Using well known techniques, in order to determine the full 16S sequence or the sequence of any hypervariable region of the 16S sequence, genomic DNA is extracted from a bacterial sample, the 16S rDNA (full region or specific hypervariable regions) amplified using polymerase chain reaction (PCR), the PCR products cleaned, and nucleotide sequences delineated to determine the genetic composition of 16S gene or subdomain of the gene. If full 16S sequencing is performed, the sequencing method used may be, but is not limited to, Sanger sequencing. If one or more hypervariable regions are used, such as the V4 region, the sequencing can be, but is not limited to

being, performed using the Sanger method or using a next-generation sequencing method, such as an Illumina (sequencing by synthesis) method using barcoded primers allowing for multiplex reactions.

[0110] OTUs can be defined by a combination of nucleotide markers or genes, in particular highly conserved genes (*e.g.*, "house-keeping" genes), or a combination thereof, full-genome sequence, or partial genome sequence generated using amplified genetic products, or whole genome sequence (WGS). Using well defined methods familiar to one with ordinary skill in the art, DNA extracted from a bacterial sample will have specific genomic regions amplified using PCR and sequenced to determine the nucleotide sequence of the amplified products. In the whole genome shotgun (WGS) method, extracted DNA will be directly sequenced without amplification. Sequence data can be generated using any sequencing technology including, but not limited to Sanger, Illumina, 454 Life Sciences, Ion Torrent, ABI, Pacific Biosciences, and/or Oxford Nanopore.

[0111] In one embodiment, the OTUs can be characterized by one or more of the variable regions of the 16S sequence (V1-V9). These regions in bacteria are defined by nucleotides 69-99, 137-242, 433-497, 576-682, 822-879, 986-1043, 1117-1173, 1243-1294 and 1435-1465 respectively using numbering based on the *E. coli* system of nomenclature. (*See, e.g.*, Brosius *et al.*, Complete nucleotide sequence of a 16S ribosomal RNA gene from Escherichia coli, PNAS 75(10):4801-4805 (1978)). In some embodiments, at least one of the V1, V2, V3, V4, V5, V6, V7, V8, and V9 regions are used to characterize an OTU. In one embodiment, the V1, V2, and V3 regions are used to characterize an OTU. In another embodiment, the V3, V4, and V5 regions are used to characterize an OTU. In another embodiment, the V4 region is used to characterize an OTU.

Bacterial Compositions Exclusive of Certain Bacterial Species Or Strains

[0112] In one embodiment, the bacterial composition does not comprise at least one of *Enterococcus faecalis* (previously known as *Streptococcus faecalis*), *Clostridium innocuum*, *Clostridium ramosum*, *Bacteroides ovatus*, *Bacteroides vulgatus*, *Bacteroides thetaoiotaomicron*, *Escherichia coli* (1109 and 1108-1), *Clostridum bifermentans*, and *Blautia producta* (previously known as *Peptostreptococcus productus*).

[0113] In another embodiment, the bacterial composition does not comprise at least one of *Acidaminococcus intestinalis*, *Bacteroides ovatus*, two species of *Bifidobacterium adolescentis*, two species of *Bifidobacterium longum*, *Collinsella aerofaciens*, two species of *Dorea longicatena*, *Escherichia coli*, *Eubacterium eligens*, *Eubacterium limosum*, four species of *Eubacterium rectale*, *Eubacterium ventriosumi*, *Faecalibacterium prausnitzii*, *Lactobacillus casei*, *Lactobacillus paracasei*, *Paracateroides distasonis*, *Raoultella sp.*, one species of *Roseburia* (chosen from *Roseburia faecalis* or *Roseburia faecis*), *Roseburia intestinalis*, two species of *Ruminococcus torques*, and *Streptococcus mitis*.

[0114] In yet another embodiment, the bacterial composition does not comprise at least one of *Barnesiella intestinihominis; Lactobacillus reuteri;* a species characterized as one of *Enterococcus*

hirae, *Enterococus faecium*, or *Enterococcus durans;* a species characterized as one of *Anaerostipes caccae* or *Clostridium indolis;* a species characterized as one of *Staphylococcus warneri* or *Staphylococcus pasteuri;* and *Adlercreutzia equolifaciens.*

[0115] In other embodiments, the bacterial composition does not comprise at least one of *Clostridium absonum, Clostridium argentinense, Clostridium baratii, Clostridium bifermentans, Clostridium botulinum, Clostridium butyricum, Clostridium cadaveris, Clostridium camis, Clostridium celatum, Clostridium chauvoei, Clostridium clostridioforme, Clostridium cochlearium, Clostridium difficile, Clostridium fallax, Clostridium felsineum, Clostridium ghonii, Clostridium glycolicum, Clostridium haemolyticum, Clostridium hastiforme, Clostridium histolyticum, Clostridium indolis, Clostridium innocuum, Clostridium irregulare, Clostridium limosum, Clostridium malenominatum, Clostridium novyi, Clostridium oroticum, Clostridium paraputrificum, Clostridium perfringens, Clostridium piliforme, Clostridium putrefaciens, Clostridium putrificum, Clostridium ramosum, Clostridium sardiniense, Clostridium sartagoforme, Clostridium scindens, Clostridium septicum, Clostridium sordellii, Clostridium sphenoides, Clostridium spiroforme, Clostridium sporogenes, Clostridium subterminale, Clostridium symbiosum, Clostridium tertium, Clostridium tetani, Clostridium welchii,* and *Clostridium villosum.*

[0116] In another embodiment, the bacterial composition does not comprise at least one of *Clostridium innocuum, Clostridum bifermentans, Clostridium butyricum, Bacteroides fragilis, Bacteroides thetaiotaomicron, Bacteroides uniformis*, three strains of *Escherichia coli*, and *Lactobacillus sp.*

[0117] In another embodiment, the bacterial composition does not comprise at least one of *Clostridium bifermentans, Clostridium innocuum, Clostridium butyricum*, three strains of *Escherichia coli*, three strains of *Bacteroides,* and *Blautia producta* (previously known as *Peptostreptococcus productus).*

[0118] In another embodiment, the bacterial composition does not comprise at least one of *Bacteroides sp.*, *Escherichia coli*, and non pathogenic *Clostridia*, including *Clostridium innocuum, Clostridium bifermentans* and *Clostridium ramosum.*

[0119] In another embodiment, the bacterial composition does not comprise at least one of more than one *Bacteroides* species, *Escherichia coli* and non-pathogenic *Clostridia*, such as *Clostridium butyricum, Clostridium bifermentans* and *Clostridium innocuum.*

[0120] In another embodiment, the bacterial composition does not comprise at least one of *Bacteroides caccae, Bacteroides capillosus, Bacteroides coagulans, Bacteroides distasonis, Bacteroides eggerthii, Bacteroides forsythus, Bacteroides fragilis, Bacteroides fragilis-ryhm, Bacteroides gracilis, Bacteroides levii, Bacteroides macacae, Bacteroides merdae, Bacteroides ovatus, Bacteroides pneumosintes, Bacteroides putredinis, Bacteroides pyogenes, Bacteroides*

splanchnicus, Bacteroides stercoris, Bacteroides tectum, Bacteroides thetaiotaomicron, Bacteroides uniformis, Bacteroides ureolyticus, and *Bacteroides vulgatus.*

[0121] In another embodiment, the bacterial composition does not comprise at least one of *Bacteroides, Eubacteria, Fusobacteria, Propionibacteria, Lactobacilli, anaerobic cocci, Ruminococcus, Escherichia coli, Gemmiger, Desulfomonas,* and *Peptostreptococcus.*

[0122] In another embodiment, the bacterial composition does not comprise at least one of *Bacteroides fragilis ss. Vulgatus, Eubacterium aerofaciens, Bacteroides fragilis ss. Thetaiotaomicron, Blautia producta* (previously known as *Peptostreptococcus productus II*), *Bacteroides fragilis ss. Distasonis, Fusobacterium prausnitzii, Coprococcus eutactus, Eubacterium aerofaciens III, Blautia producta* (previously known as *Peptostreptococcus productus I*), *Ruminococcus bromii, Bifidobacterium adolescentis, Gemmiger formicilis, Bifidobacterium longum, Eubacterium siraeum, Ruminococcus torques, Eubacterium rectale III-H, Eubacterium rectale IV, Eubacterium eligens, Bacteroides eggerthii, Clostridium leptum, Bacteroides fragilis ss. A, Eubacterium biforme, Bifidobacterium infantis, Eubacterium rectale III-F, Coprococcus comes, Bacteroides capillosus, Ruminococcus albus, Eubacterium formicigenerans, Eubacterium hallii, Eubacterium ventriosum I, Fusobacterium russii, Ruminococcus obeum, Eubacterium rectale II, Clostridium ramosum I, Lactobacillus leichmanii, Ruminococcus cailidus, Butyrivibrio crossotus, Acidaminococcus fermentans, Eubacterium ventriosum, Bacteroides fragilis ss. fragilis, Bacteroides AR, Coprococcus catus, Eubacterium hadrum, Eubacterium cylindroides, Eubacterium ruminantium, Eubacterium CH-1, Staphylococcus epidermidis, Peptostreptococcus BL, Eubacterium limosum, Bacteroides praeacutus, Bacteroides L, Fusobacterium mortiferum I, Fusobacterium naviforme, Clostridium innocuum, Clostridium ramosum, Propionibacterium acnes, Ruminococcus flavefaciens, Ruminococcus AT, Peptococcus AU-1, Eubacterium AG, -AK, -AL, -AL-1, -AN; Bacteroides fragilis ss. ovatus, -ss. d, -ss. f; Bacteroides L-1, L-5; Fusobacterium nucleatum, Fusobacterium mortiferum, Escherichia coli, Streptococcus morbiliorum, Peptococcus magnus, Peptococcus G, AU-2; Streptococcus intermedius, Ruminococcus lactaris, Ruminococcus CO Gemmiger X, Coprococcus BH, -CC; Eubacterium tenue, Eubacterium ramulus, Eubacterium AE, -AG-H, -AG-M, -AJ, -BN-1; Bacteroides clostridiiformis ss. clostridliformis, Bacteroides coagulans, Bacteroides orails, Bacteroides ruminicola ss. brevis, -ss. ruminicola, Bacteroides splanchnicus, Desuifomonas pigra, Bacteroides L-4, -N-i; Fusobacterium H, Lactobacillus G,* and *Succinivibrio A.*

Inhibition of Bacterial Pathogens

[0123] In some embodiments, the bacterial composition provides a protective or therapeutic effect against infection by one or more GI pathogens of interest. Table 1 provides a list of OTUs that are either pathogens, pathobionts, or opportunistic pathogens.

[0124] In some embodiments, the pathogenic bacterium is selected from the group consisting of Yersinia, Vibrio, Treponema, Streptococcus, Staphylococcus, Shigella, Salmonella, Rickettsia,

Orientia, Pseudomonas, Neisseria, Mycoplasma, Mycobacterium, Listeria, Leptospira, Legionella, Klebsiella, Helicobacter, Haemophilus, Francisella, Escherichia, Ehrlichia, Enterococcus, Coxiella, Corynebacterium, Clostridium, Chlamydia, Chlamydophila, Campylobacter, Burkholderia, Brucella, Borrelia, Bordetella, Bifidobacterium , Bacillus, multi-drug resistant bacteria, extended spectrum beta-lactam resistant Enterococci (ESBL), Carbapenem-resistent Enterobacteriaceae (CRE), and vancomycin-resistant Enterococci (VRE).

[0125] In some embodiments, these pathogens include, but are not limited to, Aeromonas hydrophila, Campylobacter fetus, Plesiomonas shigelloides, Bacillus cereus, Campylobacter jejuni, Clostridium botulinum, Clostridium difficile, Clostridium perfringens, enteroaggregative Escherichia coli, enterohemorrhagic Escherichia coli, enteroinvasive Escherichia coli, enterotoxigenic Escherichia coli (such as, but not limited to, LT and/or ST), Escherichia coli 0157:H7, Helicobacter pylori, Klebsiellia pneumonia, Lysteria monocytogenes, Plesiomonas shigelloides, Salmonella spp., Salmonella typhi, Salmonella paratyphi, Shigella spp., Staphylococcus spp., Staphylococcus aureus, vancomycin-resistant enterococcus spp., Vibrio spp., Vibrio cholerae, Vibrio parahaemolyticus, Vibrio vulnificus, and Yersinia enterocolitica.

[0126] In one embodiment, the pathogen of interest is at least one pathogen chosen from Clostridium difficile, Salmonella spp., pathogenic Escherichia coli, vancomycin-resistant Enterococcus spp., and extended spectrum beta-lactam resistant Enterococci (ESBL).

Purified Spore Populations

[0127] In some embodiments, the bacterial compositions comprise purified spore populations or a combination of a purified spore population with a non-spore population. Purified spore populations contain combinations of commensal bacteria of the human gut microbiota with the capacity to meaningfully provide functions of a healthy microbiota when administered to a mammalian subject. Without being limited to a specific mechanism, it is thought that such compositions inhibit the growth of a pathogen such as *C. difficile*, *Salmonella* spp., enteropathogenic *E. coli,* and vancomycin-resistant *Enterococcus* spp., so that a healthy, diverse and protective microbiota can be maintained or, in the case of pathogenic bacterial infections such as *C. difficile* infection, repopulate the intestinal lumen to reestablish ecological control over potential pathogens. In some embodiments, yeast spores and other fungal spores are also purified and selected for therapeutic use.

[0128] Disclosed herein are therapeutic and prophylactic compositions containing non-pathogenic, germination-competent bacterial spores, spore forming organisms and non-spore forming organisms, for the prevention, control, and treatment of gastrointestinal diseases, disorders and conditions and for general nutritional health. These compositions are advantageous in being suitable for safe administration to humans and other mammalian subjects and are efficacious in numerous gastrointestinal diseases, disorders and conditions and in general nutritional health. While spore-based compositions are known, these are generally prepared according to various techniques such as

lyophilization or spray-drying of liquid bacterial cultures, resulting in poor efficacy, instability, substantial variability and lack of adequate safety.

[0129] It has now been found that populations of bacterial spores can be obtained from biological materials obtained from mammalian subjects, including humans. These populations are formulated into compositions as provided herein, and administered to mammalian subjects using the methods as provided herein.

[0130] Provided herein are therapeutic bacterial compositions containing a purified population of bacterial spores, spore forming organisms and non-spore forming organisms.

[0131] As used herein, the terms "purify", "purified" and "purifying" refer to the state of a population (*e.g.*, a plurality of known or unknown amount and/or concentration) of desired bacterial spores or bacteria, that have undergone one or more processes of purification, *e.g.*, a selection or an enrichment of the desired bacterial spore, or alternatively a removal or reduction of residual habitat products as described herein. In some embodiments, a purified population has no detectable undesired activity or, alternatively, the level or amount of the undesired activity is at or below an acceptable level or amount. In other embodiments, a purified population has an amount and/or concentration of desired bacterial spores or bacteria at or above an acceptable amount and/or concentration. In other embodiments, the purified population of bacterial spores or bacteria is enriched as compared to the starting material (*e.g.*, a fecal material liquid culture) from which the population is obtained. This enrichment may be by 10%, 20%, 30%, 40%, 50%, 60%, 70%, 80%, 90%, 95%, 96%, 97%, 98%, 99%, 99.9%, 99.99%, 99.999%, 99.9999%, or greater than 99.9999% as compared to the starting material.

[0132] In certain embodiments, the purified populations of bacterial spores have reduced or undetectable levels of one or more pathogenic activities, such as toxicity, an infection of the mammalian recipient subject, an immunomodulatory activity, an autoimmune response, a metabolic response, or an inflammatory response or a neurological response. Such a reduction in a pathogenic activity may be by 10%, 20%, 30%, 40%, 50%, 60%, 70%, 80%, 90%, 95%, 96%, 97%, 98%, 99%, 99.9%, 99.99%, 99.999%, 99.9999%, or greater than 99.9999% as compared to the starting material. In other embodiments, the purified populations of bacterial spores have reduced sensory components as compared to fecal material, such as reduced odor, taste, appearance, and umami.

[0133] Provided are purified populations of bacterial spores or bacteria that are substantially free of residual habitat products. In certain embodiments, this means that the bacterial spore or bacterial composition no longer contains a substantial amount of the biological matter associated with the microbial community while living on or in the human or animal subject, and the purified population of spores may be 100% free, 99% free, 98% free, 97% free, 96% free, or 95% free of any contamination of the biological matter associated with the microbial community. Substantially free of residual habitat products may also mean that the bacterial spore composition contains no detectable

cells from a human or animal, and that only microbial cells are detectable, in particular, only desired microbial cells are detectable. In another embodiment, it means that fewer than $1x10^{-2}$%, $1x10^{-3}$%, $1x10^{-4}$%, $1x10^{-5}$%, $1x10^{-6}$%, $1x10^{-7}$%, $1x10^{-8}$% of the cells in the bacterial composition are human or animal, as compared to microbial cells. In another embodiment, the residual habitat product present in the purified population is reduced at least a certain level from the fecal material obtained from the mammalian donor subject, *e.g.*, reduced by at least about 10%, 20%, 30%, 40%, 50%, 60%, 70%, 80%, 90%, 95%, 96%, 97%, 98%, 99%, 99.9%, 99.99%, 99.999%, 99.9999%, or greater than 99.9999%.

[0134] In one embodiment, substantially free of residual habitat products or substantially free of a detectable level of a pathogenic material means that the bacterial composition contains no detectable viral (including bacterial viruses (*i.e.*, phage)), fungal, or mycoplasmal or toxoplasmal contaminants, or a eukaryotic parasite such as a helminth. Alternatively, the purified spore populations are substantially free of an acellular material, *e.g.*, DNA, viral coat material, or non-viable bacterial material.

[0135] As described herein, purified spore populations can be demonstrated by genetic analysis (*e.g.*, PCR, DNA sequencing), serology and antigen analysis, and methods using instrumentation such as flow cytometry with reagents that distinguish desired bacterial spores from non-desired, contaminating materials.

[0136] Exemplary biological materials include fecal materials such as feces or materials isolated from the various segments of the small and large intestines. Fecal materials are obtained from a mammalian donor subject, or can be obtained from more than one donor subject, *e.g.*, 2, 3, 4, 5, 6, 7, 8, 9, 10, 15, 20, 25, 30, 35, 40, 45, 50, 75, 100, 200, 300, 400, 500, 750, 1000 or from greater than 1000 donors, where such materials are then pooled prior to purification of the desired bacterial spores.

[0137] In alternative embodiments, the desired bacterial spores or bacteria are purified from a single fecal material sample obtained from a single donor, and after such purification are combined with purified spore populations or bacteria from other purifications, either from the same donor at a different time, or from one or more different donors, or both.

[0138] Preferred bacterial genera include Acetonema, Alkaliphilus, Alicyclobacillus, Amphibacillus, Ammonifex, Anaerobacter, Anaerofustis, Anaerostipes, Anaerotruncus, Anoxybacillus, Bacillus, Blautia, Brevibacillus, Bryantella, Caldicellulosiruptor, Caloramator, Candidatus, Carboxydibrachium, Carboxydothermus, Clostridium, Cohnella, Coprococcus, Dendrosporobacter Desulfitobacterium, Desulfosporosinus, Desulfotomaculum, Dorea, Eubacterium, Faecalibacterium, Filifactor, Geobacillus, Halobacteroides, Heliobacillus, Heliobacterium, Heliophilum, Heliorestis, Lachnoanaerobaculum, Lysinibacillus, Moorella, Oceanobacillus, Orenia (S.), Oxalophagus, Oxobacter, Paenibacillus, Pelospora, Pelotomaculum, Propionispora, Roseburia, Ruminococcus, Sarcina, Sporobacterium, Sporohalobacter, Sporolactobacillus, Sporomusa,

Sporosarcina, Sporotomaculum, Subdoligranulum, Symbiobacterium, Syntrophobotulus, Syntrophospora, Terribacillus, Thermoanaerobacter, and Thermosinus.

[0139] In some embodiments, spore-forming bacteria are identified by the presence of nucleic acid sequences that modulate sporulation. In particular, signature sporulation genes are highly conserved across members of distantly related genera including Clostridium and Bacillus. Traditional approaches of forward genetics have identified many, if not all, genes that are essential for sporulation (spo). The developmental program of sporulation is governed in part by the successive action of four compartment-specific sigma factors (appearing in the order σF, σE, σG and σK), whose activities are confined to the forespore (σF and σG) or the mother cell (σE and σK).

[0140] Provided are spore populations containing more than one type of bacterium. As used herein, a "type" or more than one "types" of bacteria may be differentiated at the genus level, the species, level, the sub-species level, the strain level or by any other taxonomic method, as described herein and otherwise known in the art.

[0141] In some embodiments, all or essentially all of the bacterial spores or bacterial species present in a purified population are originally isolated obtained from a fecal material treated as described herein or otherwise known in the art. In alternative embodiments, one or more than one bacterial spores, bacteria, or types of bacterial spores are generated in culture and combined to form a purified bacterial composition, including a purified spore population. In other alternative embodiments, one or more of these culture-generated populations are combined with a fecal material-derived populations to generate a hybrid population. Bacterial compositions may contain at least two types of these preferred bacteria, including strains of the same species. For instance, a bacterial composition may comprise at least 2, at least 3, at least 4, at least 5, at least 6, at least 7, at least 8, at least 9, at least 10, at least 11, at least 12, at least 13, at least 14, at least 15, at least 16, at least 17, at least 18, at least 19, or at least 20 or more than 20 types of bacteria, as defined by species or operational taxonomic unit (OTU) encompassing such species.

[0142] Thus, provided herein are methods for production of a bacterial composition containing a population of bacterial spores suitable and/or non-sporulating bacteria for therapeutic administration to a mammalian subject in need thereof. And the composition is produced by generally following the steps of: (a) providing a fecal material obtained from a mammalian donor subject; and (b) subjecting the fecal material to at least one purification treatment or step under conditions such that a population of bacterial spores is produced from the fecal material. The composition is formulated such that a single oral dose contains at least about $1x10^4$ colony forming units of the bacterial spores, and a single oral dose will typically contain about $1x10^4$, $1x10^5$, $1x10^6$, $1x10^7$, $1x10^8$, $1x10^9$, $1x10^{10}$, $1x10^{11}$, $1x10^{12}$, $1x10^{13}$, $1x10^{14}$, $1x10^{15}$, or greater than $1x10^{15}$ CFUs of the bacterial spores. The presence and/or concentration of a given type of bacteria or bacterial spore may be known or unknown in a given purified spore population. If known, for example the concentration of bacteria or spores of a

given strain, or the aggregate of all strains, is *e.g.*, $1x10^4$, $1x10^5$, $1x10^6$, $1x10^7$, $1x10^8$, $1x10^9$, $1x10^{10}$, $1x10^{11}$, $1x10^{12}$, $1x10^{13}$, $1x10^{14}$, $1x10^{15}$, or greater than $1x10^{15}$ viable bacteria or bacterial spores per gram of composition or per administered dose.

[0143] In some formulations, the composition contains at least about 10%, 20%, 30%, 40%, 50%, 60%, 70%, 80%, 90% or greater than 90% spores on a mass basis. In some formulations, the administered dose does not exceed 200, 300, 400, 500, 600, 700, 800, 900 milligrams or 1, 1.1, 1.2, 1.3, 1.4, 1.5, 1.6, 1.7, 1.8, or 1.9 grams in mass.

[0144] The bacterial compositions are generally formulated for oral or gastric administration, typically to a mammalian subject. In particular embodiments, the composition is formulated for oral administration as a solid, semi-solid, gel, or liquid form, such as in the form of a pill, tablet, capsule, or lozenge. In some embodiments, such formulations contain or are coated by an enteric coating to protect the bacteria through the stomach and small intestine, although spores are generally resistant to the stomach and small intestines.

[0145] The bacterial compositions may be formulated to be effective in a given mammalian subject in a single administration or over multiple administrations. For example, a single administration is substantially effective to reduce *Cl. difficile* and/or *Cl. difficile* toxin content in a mammalian subject to whom the composition is administered. Substantially effective means that *Cl. difficile* and/or *Cl. difficile* toxin content in the subject is reduced by at least 10%, 20%, 30%, 40%, 50%, 60%, 70%, 80%, 90%, 95%, 98%, 99% or greater than 99% following administration of the composition.

Kits For Diagnosis of a State Of Dysbiosis in a Subject

[0146] In some embodiments, the invention includes kits for carrying out methods of the invention described herein and in the claims. In some embodiments, the invention includes a kit for diagnosis of a state of dysbiosis in a mammalian subject in need thereof. In one embodiment, the kit includes a plurality of detection means suitable for use in detecting (1) a first bacterial entity comprising a keystone bacterial entity and (2) a second bacterial entity, wherein the first and second bacterial entities comprise a Network Ecology, as described herein. The kit can include instructions for use of the kit.

[0147] In other embodiments, the kit provides detection means, reagents, and instructions for detecting a first bacterial entity and a second bacterial entity that comprise a Network Ecology by: obtaining a fecal sample from a mammalian subject comprising a plurality of bacterial entities, contacting the fecal sample with a first detection moiety (and in some cases, a second detection moiety) capable of detecting the first bacterial entity and the second bacterial entity present in the network, detecting the absence of the first and/or second bacterial entities in the fecal sample, and thereby detecting a dysbiosis in the mammailian subject. In some embodiments, the kit provides reagents and steps for administering to the mammailian subject a composition comprising an effect amount of the first and/or second bacterial species.

[0148] In some embodiments, the kit includes detection means and instructions for obtaining a fecal sample from the mammalian subject comprising a plurality of bacterial entities; contacting the fecal sample with a first detection moiety capable of detecting a first bacterial entity present in an network; detecting the absence of the first bacterial entity in the fecal sample, thereby detecting a dysbiosis in the mammalian subject; and administering to the mammalian subject a composition comprising an effective amount of the first bacterial entity.

[0149] In other embodiments, the kit includes reagents and instructions for a method for treating, preventing, or reducing the severity of a disorder selected from the group consisting of Clostridium difficile Associated Diarrhea (CDAD), Type 2 Diabetes, Obesity, Irritable Bowel Disease (IBD), colonization with a pathogen or pathobiont, and infection with a drug-resistant pathogen or pathobiont, comprising: administering to a mammalian subject in need thereof an effective amount of a therapeutic bacterial composition, said therapeutic bacterial composition comprising a plurality of isolated bacteria or a purified bacterial preparation, the plurality of isolated bacteria or the purified bacterial preparation capable of forming a network ecology selected from the group consisting of those in claims 1-61 below and described throughout the specification.

[0150] In another embodiment, the kit includes reagents and instructions for a method for producing short chain fatty acids (SCFA) within a mammalian subject, comprising: administering to said mammalian subject in need thereof an effective amount of a therapeutic bacterial composition, said therapeutic bacterial composition comprising a plurality of isolated bacteria or a purified bacterial preparation, the plurality of isolated bacteria of the purified bacterial preparation capable of forming one or a plurality of bacterial functional pathways, the one or plurality of bacterial functional pathways capable of forming a functional network ecology selected from the group consisting of those in claims 69-71 and described throughout in the specification.

[0151] In another embodiment, the kit includes reagents and instructions for a method for catalyzing secondary metabolism of bile acids within a mammalian subject, comprising: administering to said mammalian subject in need thereof an effective amount of a therapeutic bacterial composition, said therapeutic bacterial composition comprising a plurality of isolated bacteria or a purified bacterial preparation, the plurality of isolated bacteria of the purified bacterial preparation capable of forming one or a plurality of bacterial functional pathways, the one or plurality of bacterial functional pathways capable of forming a functional network ecology selected from the group consisting of claims 72-74 and throughout the specification.

Systems for Predicting a Dysbiosis in a Subject

[0152] The invention provides systems for predicting a dysbiosis in a subject, the system comprising: a storage memory for storing a dataset associated with a sample obtained from the subject, wherein the dataset comprises content data for at least one network of bacterial entities

described herein, and a processor communicatively coupled to the storage memory for determining a score with an interpretation function wherein the score is predictive of dysbiosis in the subject.

[0153] In some embodiments, the invention provides systems for detecting a dysbiosis in a subject comprising: a storage memory for storing a dataset associated with a sample obtained from the subject, wherein the dataset comprises content data for at least one network of bacterial entities described herein, and a processor communicatively coupled to the storage memory for determining a score with an interpretation function, wherein the score is predictive of dysbiosis in the subject.

[0154] An example of a computer system and its components that can be used to perform methods of the invention are described below in Figure 21.

Computer Overview

[0155] Figure 21 is a high-level block diagram illustrating an example of a computer 2100 for use as a server or a user device, in accordance with one embodiment. Illustrated are at least one processor 2102 coupled to a chipset 2104. The chipset 2104 includes a memory controller hub 2120 and an input/output (I/O) controller hub 2122. A memory 2106 and a graphics adapter 2112 are coupled to the memory controller hub 2120, and a display device 2118 is coupled to the graphics adapter 2112. A storage device 2108, keyboard 2110, pointing device 2114, and network adapter 2116 are coupled to the I/O controller hub 2122. Other embodiments of the computer 2100 have different architectures. For example, the memory 2106 is directly coupled to the processor 2102 in some embodiments.

[0156] The storage device 2108 is a non-transitory computer-readable storage medium such as a hard drive, compact disk read-only memory (CD-ROM), DVD, or a solid-state memory device. The memory 2106 holds instructions and data used by the processor 2102. The pointing device 2114 is used in combination with the keyboard 2110 to input data into the computer system 200. The graphics adapter 2112 displays images and other information on the display device 2118. In some embodiments, the display device 2118 includes a touch screen capability for receiving user input and selections. The network adapter 2116 couples the computer system 2100 to the network. Some embodiments of the computer 2100 have different and/or other components than those shown in Figure 21. For example, the server can be formed of multiple blade servers and lack a display device, keyboard, and other components.

[0157] The computer 2100 is adapted to execute computer program modules for providing functionality described herein. As used herein, the term "module" refers to computer program instructions and other logic used to provide the specified functionality. Thus, a module can be implemented in hardware, firmware, and/or software. In one embodiment, program modules formed of executable computer program instructions are stored on the storage device 2108, loaded into the memory 2106, and executed by the processor 2102.

METHODS OF THE INVENTION

Method of Determining Network Ecologies

[0158] Methods are provided for a computational approach based in part on network theory to construct the ecology of a group of microorganisms based on the presence or absence of specific OTUs (*i.e.,* microbial genera, species or strains) in a given set of sampled subjects. *See* Figure 16. *See e.g.*, Cormen TH, Leiserson CE, Rivest RL, and Stein C. 2009. Introduction to Algorithms. Third edition. The MIT Press. Garey MR, and Johnson DS. 1979. Computers and Intractability: A Guide to the Theory of NP-Completeness. First Edition. W. H. Freeman. The approach includes the following: (i) identifying the microbial network ecologies that are present in both healthy and diseased subjects, (ii) identifying the keystone OTUs and/or functions (Figure 17), and phylogenetic clades that characterize a given ecology, and (iii) providing specific metrics with which to prioritize the various network ecologies with respect to their capacity to be useful in restoring the microbiome from a state of dysbiosis to a state of health. In general the method first defines all low and high order networks within given sets of subjects, and then utilizes a comparative approach to define biologically significant networks.

[0159] This method comprises computing a co-occurrence matrix of OTUs (*i.e.,* presence or absence) for each subject across a defined subject population (populations are defined by a specific phenotype such as but not limited to "subjects who are healthy", or "subjects with disease"). The method comprises computing all nodes (OTUs, or species, or strains) and edges (co-occurrence between OTUs, or species, or strains) that define the Network Ecology in a given subject's sample. Each co-occurrence is scored using a discrete binary variable denoting presence or absence. While the algorithm allows co-occurrences to be weighted based on the relative abundance of OTUs in the samples, in general, this is undesirable since low abundance OTUs may be important ecologically. Furthermore, a discretized measure of presence or absence of nodes eliminates bias and errors in the computed network ecologies that will arise from bias in methods used to generate relative abundance measures. A discreet method measuring presence or absence enables the detection of low frequency OTUs and the elucidation of networks that are often missed by methods based on relative abundance measures. Following derivation of all low and high order networks in a given subject, one can define all the network ecologies in a given phenotype (*i.e.*, collections of data sets from subjects with a unifying characteristic, for example, all data sets from healthy subjects) by defining the node and edge combinations that are maximally observed across all subjects. Without being bound by theory, it is understood that such network ecologies are present in a mammalian subject. The algorithm iterates the construction of network ecologies to rank all ecologies (*i.e.* nodes and edges) within each sample based on co-occurrence, [maximum co-occurrence; maximum co-occurrence less 1; maximum co-occurrence less 2; *etc.*] until the networks with minimum co-occurrence are defined (*i.e.*, a minimum edge score is achieved). This method can be computationally intensive for data sets containing a large number of subjects. For data sets containing a large number of subjects the algorithm uses a strategy

whereby first seed network ecologies are constructed using the method defined above in a subset of subjects and then combinations of these seed networks are used to search for higher order networks across the entire data set.

[0160] Biological significance can be assigned to the observed network ecologies and members of a given Network Ecology based on multiple computed metrics including, but not limited to: (i) the frequency that a given OTU or Network Ecology is observed; (ii) the number of OTUs in the network; the frequency of occurrence of the network across subjects (*i.e.*, pervasiveness); (iii) the phylogenetic breadth of the network, (iv) specific functional properties, and (v) whether the network occurs preferentially in individuals that are healthy versus those harboring disease *(i.e.*, the various phenotypes). All network ecologies or OTUs that occur in one phenotype (*e.g.*, health) are compared to those that occur in other phenotypes (*e.g.*, one or more specific disease states) to core Network ecologies or OTUs that are found in one, two, or any multiple of phenotypes. Network ecologies are considered to be related if at least 70%, 80%, or 90% of their OTUs are in common. All network ecologies or OTUs are assigned a score for their biological significance based on but not limited to: (i) the intersections of phenotypes in which they occur or do not occur (e.g. present in health but not disease), and (ii) the various metrics above defined. The final output of all of these steps defines a set of Network Ecologies that are of high biological significance and a set of Keystone OTUs and/or metabolic functions that are integral components of these derived ecologies.

[0161] From these Network Ecologies, the method includes defining "Network Classes" that represent network groups or clusters with specific, related compositional characteristics with respect to OTU content, phylogenetic diversity, and metabolic functional capacity (Figure 18). Network Classes can be first defined by setting an inclusion threshold for networks to include in the analysis that is based on biological characteristics of the networks such as but not limited to the size (number of OTUs) and pervasiveness (*i.e.*, how frequently a given network is observed in a population of individuals). Selected network ecologies are then clustered using two vectors: one vector is phylogenetic relatedness of individual OTUs as defined by a computed phylogenetic tree, and the second vector is network relatedness based on the OTUs content in the individual networks. In another embodiment, clustering vectors are related based on metabolic functional pathways harbored by individual OTUs, and network relatedness is based on the functional pathways present in each individual network. Network Classes are defined by specific nodes in the dendrogram representing the computed network relatedness, and each class is characterized by a specific combination of OTUs. In one embodiment, these nodes are defined as branches of the hierarchical clustering tree based on the topological overlap measure; this measure is a highly robust measure of network interconnectedness. *See* Langfelder P, Zhang B, Horvath S. 2008. Defining clusters from a hierarchical cluster tree: the Dynamic Tree Cut package for R. Bioinformatics 24: 719–720.

[0162] From these Networks Classes, a target microbial composition's usefulness, *e.g.*, as a therapeutic, is selected using desired phylogenetic and functional properties for subsequent testing in in vitro and in vivo models. Exemplary Network Classes are delineated in Table 12, and Table 13 defines taxonomic families that are characteristic of Network Classes.

[0163] As described herein, provided are compositions (Table 8) containing keystone OTUs for states of health, including one or more of the OTUs provided below in Table 9.

[0164] As described herein, provided are compositions containing keystone OTUs, keystone metabolic functions and, optionally, non-keystone OTUs, including one or more of the OTUs provided below in Table 10.

[0165] In some therapeutic compositions, keystone OTUs are provided from members of a genera or family selected from Table 9.

[0166] Exemplary network ecologies are provided in Table 8, Table 11, Table 12, Table 14a 14b, and 14c, and Table 17.

[0167] Exemlary functional network ecologies are provided in Table 18 and Table 21.

[0168] Thus, provided herein are methods for production of a composition containing a population of bacteria as either vegetative cells or spores or both, suitable for therapeutic administration to a mammalian subject in need thereof. The composition is produced by generally following the steps of: (a) defining a target composition by selecting a Network Ecology, Functional Network Ecology, a Network Class, or a set of Keystone OTUs or Keystone Metabolic Functions that comprise the Network Ecology or Functional Network Ecology of interest (a) providing bacterial OTUs obtained from one or more bacterial cultures, biological or environmental sources, or a mammalian donor subject; and (b) combining the bacterial OTUs in a ratio and an amount sufficient to form a Network Ecology or Functional Network Ecology. The composition is formulated such that a single oral dose contains at least about $1x10^4$ colony forming units of the bacteria, and a single oral dose will typically contain about $1x10^4$, $1x10^5$, $1x10^6$, $1x10^7$, $1x10^8$, $1x10^9$, $1x10^{10}$, $1x10^{11}$, $1x10^{12}$, $1x10^{13}$, $1x10^{14}$, $1x10^{15}$, or greater than $1x10^{15}$ CFUs of the bacteria. The concentration of bacterial of a given species or strain, or the aggregate of all species or strains, is *e.g.*, $1x10^4$, $1x10^5$, $1x10^6$, $1x10^7$, $1x10^8$, $1x10^9$, $1x10^{10}$, $1x10^{11}$, $1x10^{12}$, $1x10^{13}$, $1x10^{14}$, $1x10^{15}$, or greater than $1x10^{15}$ viable bacteria per gram of composition or per administered dose.

[0169] The bacterial compositions are generally formulated for oral or gastric administration, typically to a mammalian subject. In particular embodiments, the composition is formulated for oral administration as a solid, semi-solid, gel, or liquid form, such as in the form of a pill, tablet, capsule, or lozenge. In some embodiments, such formulations contain or are coated by an enteric coating to protect the bacteria through the stomach and small intestine, although compositions containing spores are generally resistant to the environment of the stomach and small intestine. Alternatively, the bacterial composition may be formulated for naso-gastric or rectal administration.

[0170] The bacterial compositions may be formulated to be effective in a given mammalian subject in a single administration or over multiple administrations. For example, a single administration is substantially effective to reduce Clostridium difficile (*i.e.*, C. difficile) and/or C. difficile toxin content and/or toxin activity, in a mammalian subject to whom the composition is administered. Substantially effective means that Cl. difficile and/or C. difficile toxin content in the subject is reduced by at least 10%, 20%, 30%, 40%, 50%, 60%, 70%, 80%, 90%, 95%, 98%, 99% or greater than 99% following administration of the composition.

Methods for Determining 16S Sequences

[0171] OTUs can be defined either by full 16S sequencing of the rRNA gene, by sequencing of a specific hypervariable region of this gene (*i.e.* V1, V2, V3, V4, V5, V6, V7, V8, or V9), or by sequencing of any combination of hypervariable regions from this gene (*e.g.* V1-3 or V3-5). The bacterial 16S rDNA is approximately 1500 nucleotides in length and is used in reconstructing the evolutionary relationships and sequence similarity of one bacterial isolate to another using phylogenetic approaches. 16S sequences are used for phylogenetic reconstruction as they are in general highly conserved, but contain specific hypervariable regions that harbor sufficient nucleotide diversity to differentiate genera and species of most microbes.

[0172] Using well known techniques, in order to determine the full 16S sequence or the sequence of any hypervariable region of the 16S sequence, genomic DNA is extracted from a bacterial sample, the 16S rDNA (full region or specific hypervariable regions) amplified using polymerase chain reaction (PCR), the PCR products cleaned, and nucleotide sequences delineated to determine the genetic composition of 16S gene or subdomain of the gene. If full 16S sequencing is performed, the sequencing method used may be, but is not limited to, Sanger sequencing. If one or more hypervariable regions are used, such as the V4 region, the sequencing can be, but is not limited to being, performed using the Sanger method or using a next-generation sequencing method, such as an Illumina (sequencing by synthesis) method using barcoded primers allowing for multiplex reactions.

[0173] OTUs can be defined by a combination of nucleotide markers or genes, in particular highly conserved genes (*e.g.*, "house-keeping" genes), or a combination thereof, full-genome sequence, or partial genome sequence generated using amplified genetic products, or whole genome sequence (WGS). Using well defined methods DNA extracted from a bacterial sample will have specific genomic regions amplified using PCR and sequenced to determine the nucleotide sequence of the amplified products. In the whole genome shotgun (WGS) method, extracted DNA will be directly sequenced without amplification. Sequence data can be generated using any sequencing technology including, but not limited to Sanger, Illumina, 454 Life Sciences, Ion Torrent, ABI, Pacific Biosciences, and/or Oxford Nanopore.

Methods for Preparing a Bacterial Composition for Administration to a Subject

[0174] Methods for producing bacterial compositions can include three main processing steps, combined with one or more mixing steps. The steps include organism banking, organism production, and preservation.

[0175] For banking, the strains included in the bacterial composition may be (1) isolated directly from a specimen or taken from a banked stock, (2) optionally cultured on a nutrient agar or broth that supports growth to generate viable biomass, and (3) the biomass optionally preserved in multiple aliquots in long-term storage.

[0176] In embodiments that use a culturing step, the agar or broth can contain nutrients that provide essential elements and specific factors that enable growth. An example would be a medium composed of 20 g/L glucose, 10 g/L yeast extract, 10 g/L soy peptone, 2 g/L citric acid, 1.5 g/L sodium phosphate monobasic, 100 mg/L ferric ammonium citrate, 80 mg/L magnesium sulfate, 10 mg/L hemin chloride, 2 mg/L calcium chloride, 1 mg/L menadione. A variety of microbiological media and variations are well known in the art (*e.g.* R.M. Atlas, *Handbook of Microbiological Media* (2010) CRC Press). Medium can be added to the culture at the start, may be added during the culture, or may be intermittently/continuously flowed through the culture. The strains in the bacterial composition may be cultivated alone, as a subset of the bacterial composition, or as an entire collection comprising the bacterial composition. As an example, a first strain may be cultivated together with a second strain in a mixed continuous culture, at a dilution rate lower than the maximum growth rate of either cell to prevent the culture from washing out of the cultivation.

[0177] The inoculated culture is incubated under favorable conditions for a time sufficient to build biomass. For bacterial compositions for human use, this is often at 37°C temperature, pH, and other parameter with values similar to the normal human niche. The environment can be actively controlled, passively controlled (*e.g.*, via buffers), or allowed to drift. For example, for anaerobic bacterial compositions (*e.g.*, gut microbiota), an anoxic/reducing environment can be employed. This can be accomplished by addition of reducing agents such as cysteine to the broth, and/or stripping it of oxygen. As an example, a culture of a bacterial composition can be grown at 37°C, pH 7, in the medium above, pre-reduced with 1 g/L cysteine·HCl.

[0178] When the culture has generated sufficient biomass, it can be preserved for banking. The organisms can be placed into a chemical milieu that protects from freezing (adding 'cryoprotectants'), drying ('lyoprotectants'), and/or osmotic shock ('osmoprotectants'), dispensing into multiple (optionally identical) containers to create a uniform bank, and then treating the culture for preservation. Containers are generally impermeable and have closures that assure isolation from the environment. Cryopreservation treatment is accomplished by freezing a liquid at ultra-low temperatures (*e.g.*, at or below -80°C). Dried preservation removes water from the culture by evaporation (in the case of spray drying or 'cool drying') or by sublimation (*e.g.*, for freeze drying, spray freeze drying). Removal of water improves long-term bacterial composition storage stability at

temperatures elevated above cryogenic. If the bacterial composition comprises spore forming species and results in the production of spores, the final composition can be purified by additional means, such as density gradient centrifugation preserved using the techniques described above. Bacterial composition banking can be done by culturing and preserving the strains individually, or by mixing the strains together to create a combined bank. As an example of cryopreservation, a bacterial composition culture can be harvested by centrifugation to pellet the cells from the culture medium, the supernate decanted and replaced with fresh culture broth containing 15% glycerol. The culture can then be aliquoted into 1 mL cryotubes, sealed, and placed at -80°C for long-term viability retention. This procedure achieves acceptable viability upon recovery from frozen storage.

[0179] Organism production can be conducted using similar culture steps to banking, including medium composition and culture conditions. It can be conducted at larger scales of operation, especially for clinical development or commercial production. At larger scales, there can be several subcultivations of the bacterial composition prior to the final cultivation. At the end of cultivation, the culture is harvested to enable further formulation into a dosage form for administration. This can involve concentration, removal of undesirable medium components, and/or introduction into a chemical milieu that preserves the bacterial composition and renders it acceptable for administration via the chosen route. For example, a bacterial composition can be cultivated to a concentration of 10^{10} CFU/mL, then concentrated 20-fold by tangential flow microfiltration; the spent medium can be exchanged by diafiltering with a preservative medium consisting of 2% gelatin, 100 mM trehalose, and 10 mM sodium phosphate buffer. The suspension can then be freeze-dried to a powder and titrated.

[0180] After drying, the powder can be blended to an appropriate potency, and mixed with other cultures and/or a filler such as microcrystalline cellulose for consistency and ease of handling, and the bacterial composition formulated as provided herein.

Methods of Treating a Subject

[0181] In some embodiments, the compositions disclosed herein are administered to a patient or a user (sometimes collectively referred to as a "subject"). As used herein "administer" and "administration" encompasses embodiments in which one person directs another to consume a bacterial composition in a certain manner and/or for a certain purpose, and also situations in which a user uses a bacteria composition in a certain manner and/or for a certain purpose independently of or in variance to any instructions received from a second person. Non-limiting examples of embodiments in which one person directs another to consume a bacterial composition in a certain manner and/or for a certain purpose include when a physician prescribes a course of conduct and/or treatment to a patient, when a parent commands a minor user (such as a child) to consume a bacterial composition, when a trainer advises a user (such as an athlete) to follow a particular course of conduct and/or treatment, and when a manufacturer, distributer, or marketer recommends conditions of use to

an end user, for example through advertisements or labeling on packaging or on other materials provided in association with the sale or marketing of a product.

[0182] The bacterial compositions offer a protective and/or therapeutic effect against diseases, disorders or conditions associated with dysbiosis of the gut microbiota, including but not limited to metabolic disorders such as pre-diabetes, type 1 diabetes, type 2 diabetes, obesity and non-alcoholic fatty liver disease (NAFLD), gastrointestinal disorders such as inflammatory bowel disease (IBD, such as ulcerative colitis and Crohns' disease), pouchitis and irritable bowel syndrome (IBS), and infectious diseases as described herein.

[0183] In some embodiments, the bacterial compositions offer a protective and/or therapeutic effect against diseases, disorders or conditions associated with dysbiosis of the gut microbiota, including but not limited to, metabolic diseases (e.g., Type 1 diabetes, Type 2 diabetes, Gestational diabetes, Diabetes complications, Prediabetes, NAFLD/NASH, Obesity, Weight Loss), GI diseases (Inflammatory bowel disease (IBD), Irritable bowel syndrome (IBS), Ulcerative Colitis, Crohn's Disease). Infectious diseases (Clostridium difficile Associated Diarrhea (CDAD), Carbapenem-resistant Enterobacteriaceae (CRE), Multidrug-resistant Acinetobacter, Drug-resistant Campylobacter, Extended spectrum β-lactamase producing Enterobacteriaceae (ESBLs), Vancomycin-resistant Enterococcus (VRE), Multidrug-resistant Pseudomonas aeruginosa, Drug-resistant Non-typhoidal Salmonella, Drug-resistant Salmonella Typhi, Drug-resistant Shigella, Methicillin-resistant Staphylococcus aureus (MRSA), Drug-resistant Streptococcus pneumonia, Vancomycin-resistant Staphylococcus aureus (VRSA), Erythromycin-resistant Group A Streptococcus, Clindamycin-resistant Group B Streptococcus, Pathogenic fungus, or Candida infection).

[0184] The present bacterial compositions can be administered to animals, including humans, laboratory animals (*e.g.*, primates, rats, mice), livestock (*e.g.*, cows, sheep, goats, pigs, turkeys, chickens), and household pets (*e.g.*, dogs, cats, rodents).

[0185] In the present method, the bacterial composition can be administered enterically, in other words, by a route of access to the gastrointestinal tract. This includes oral administration, rectal administration (including enema, suppository, or colonoscopy), by an oral or nasal tube (nasogastric, nasojejunal, oral gastric, or oral jejunal), as detailed more fully herein.

Pretreatment Protocols

[0186] Prior to administration of the bacterial composition, the patient can optionally have a pretreatment protocol to prepare the gastrointestinal tract to receive the bacterial composition.

[0187] As one way of preparing the patient for administration of the microbial ecosystem, at least one antibiotic can be administered to alter the bacteria in the patient. As another way of preparing the patient for administration of the microbial ecosystem, a standard colon-cleansing preparation can be administered to the patient to substantially empty the contents of the colon, such as used to prepare a patient for a colonscopy. By "substantially emptying the contents of the colon," this application

means removing at least 75%, at least 80%, at least 90%, at least 95%, or about 100% of the contents of the ordinary volume of colon contents. Antibiotic treatment can precede the colon-cleansing protocol.

[0188] If a patient has received an antibiotic for treatment of an infection, or if a patient has received an antibiotic as part of a specific pretreatment protocol, in one embodiment, the antibiotic can be stopped in sufficient time to allow the antibiotic to be substantially reduced in concentration in the gut before the bacterial composition is administered. In one embodiment, the antibiotic can be discontinued 1, 2, or 3 days before the administration of the bacterial composition. In another embodiment, the antibiotic can be discontinued 3, 4, 5, 6, or 7 antibiotic half-lives before administration of the bacterial composition. In another embodiment, the antibiotic can be chosen so the constituents in the bacterial composition have an MIC50 that is higher than the concentration of the antibiotic in the gut.

[0189] MIC50 of a bacterial composition or the elements in the composition can be determined by methods well known in the art. Reller et al., Antimicrobial Susceptibility Testing: A Review of General Principles and Contemporary Practices, Clinical Infectious Diseases 49(11):1749-1755 (2009). In such an embodiment, the additional time between antibiotic administration and administration of the bacterial composition is not necessary. If the pretreatment protocol is part of treatment of an acute infection, the antibiotic can be chosen so that the infection is sensitive to the antibiotic, but the constituents in the bacterial composition are not sensitive to the antibiotic.

Administration of Bacterial Compositions

[0190] The bacterial compositions of the invention are suitable for administration to mammals and non-mammalian animals in need thereof. In certain embodiments, the mammalian subject is a human subject who has one or more symptoms of a dysbiosis.

[0191] When the mammalian subject is suffering from a disease, disorder or condition characterized by an aberrant microbiota, the bacterial compositions described herein are suitable for treatment thereof. In some embodiments, the mammalian subject has not received antibiotics in advance of treatment with the bacterial compositions. For example, the mammalian subject has not been administered at least two doses of vancomycin, metronidazole and/or or similar antibiotic compound within one week prior to administration of the therapeutic composition. In other embodiments, the mammalian subject has not previously received an antibiotic compound in the one month prior to administration of the therapeutic composition. In other embodiments, the mammalian subject has received one or more treatments with one or more different antibiotic compounds and such treatment(s) resulted in no improvement or a worsening of symptoms.

[0192] In some embodiments, the gastrointestinal disease, disorder or condition is diarrhea caused by C. difficile including recurrent C. difficile infection, ulcerative colitis, colitis, Crohn's disease, or irritable bowel disease. Beneficially, the therapeutic composition is administered only once prior to

improvement of the disease, disorder or condition. In some embodiments the therapeutic composition is administered at intervals greater than two days, such as once every three, four, five or six days, or every week or less frequently than every week. Or the preparation may be administered intermittently according to a set schedule, *e.g.*, once a day, once weekly, or once monthly, or when the subject relapses from the primary illness. In another embodiment, the preparation may be administered on a long-term basis to subjects who are at risk for infection with or who may be carriers of these pathogens, including subjects who will have an invasive medical procedure (such as surgery), who will be hospitalized, who live in a long-term care or rehabilitation facility, who are exposed to pathogens by virtue of their profession (livestock and animal processing workers), or who could be carriers of pathogens (including hospital workers such as physicians, nurses, and other health care professionals).

[0193] In embodiments, the bacterial composition is administered enterically. This preferentially includes oral administration, or by an oral or nasal tube (including nasogastric, nasojejunal, oral gastric, or oral jejunal). In other embodiments, administration includes rectal administration (including enema, suppository, or colonoscopy). The bacterial composition may be administered to at least one region of the gastrointestinal tract, including the mouth, esophagus, stomach, small intestine, large intestine, and rectum. In some embodiments it is administered to all regions of the gastrointestinal tract. The bacterial compositions may be administered orally in the form of medicaments such as powders, capsules, tablets, gels or liquids. The bacterial compositions may also be administered in gel or liquid form by the oral route or through a nasogastric tube, or by the rectal route in a gel or liquid form, by enema or instillation through a colonoscope or by a suppository.

[0194] If the composition is administered colonoscopically and, optionally, if the bacterial composition is administered by other rectal routes (such as an enema or suppository) or even if the subject has an oral administration, the subject may have a colon cleansing preparation. The colon-cleansing preparation can facilitate proper use of the colonoscope or other administration devices, but even when it does not serve a mechanical purpose it can also maximize the proportion of the bacterial composition relative to the other organisms previously residing in the gastrointestinal tract of the subject. Any ordinarily acceptable colon cleansing preparation may be used such as those typically provided when a subject undergoes a colonoscopy.

[0195]

Dosages and Schedule for Administration

[0196] In some embodiments, the bacteria and bacterial compositions are provided in a dosage form. In certain embodiments, the dosage form is designed for administration of at least one OTU or combination thereof disclosed herein, wherein the total amount of bacterial composition administered is selected from 0.1ng to 10g, 10ng to 1g, 100ng to 0.1g, 0.1mg to 500mg, 1mg to 100mg, or from 10-15mg. In other embodiments, the bacterial composition is consumed at a rate of from 0.1ng to 10g a

day, 10ng to 1g a day, 100ng to 0.1g a day, 0.1mg to 500mg a day, 1mg to 100mg a day, or from 10-15mg a day, or more.

[0197] In certain embodiments, the treatment period is at least 1 day, at least 2 days, at least 3 days, at least 4 days, at least 5 days, at least 6 days, at least 1 week, at least 2 weeks, at least 3 weeks, at least 4 weeks, at least 1 month, at least 2 months, at least 3 months, at least 4 months, at least 5 months, at least 6 months, or at least 1 year. In some embodiments the treatment period is from 1 day to 1 week, from 1 week to 4 weeks, from 1 month, to 3 months, from 3 months to 6 months, from 6 months to 1 year, or for over a year.

[0198] In one embodiment, 10^5 and 10^{12} microorganisms total can be administered to the patient in a given dosage form. In another embodiment, an effective amount can be provided in from 1 to 500 ml or from 1 to 500 grams of the bacterial composition having from 10^7 to 10^{11} bacteria per ml or per gram, or a capsule, tablet or suppository having from 1 mg to 1000 mg lyophilized powder having from 10^7 to 10^{11} bacteria. Those receiving acute treatment can receive higher doses than those who are receiving chronic administration.

[0199] Any of the preparations described herein can be administered once on a single occasion or on multiple occasions, such as once a day for several days or more than once a day on the day of administration (including twice daily, three times daily, or up to five times daily). In another embodiment, the preparation can be administered intermittently according to a set schedule, *e.g.*, once weekly, once monthly, or when the patient relapses from the primary illness. In one embodiment, the preparation can be administered on a long-term basis to individuals who are at risk for infection with or who may be carriers of these pathogens.

Patient Selection

[0200] Particular bacterial compositions can be selected for individual patients or for patients with particular profiles. For example, 16S sequencing can be performed for a given patient to identify the bacteria present in his or her microbiota. The sequencing can either profile the patient's entire microbiome using 16S sequencing (to the family, genera, or species level), a portion of the patient's microbiome using 16S sequencing, or it can be used to detect the presence or absence of specific candidate bacteria that are biomarkers for health or a particular disease state. Based on the biomarker data, a particular composition can be selected for administration to a patient to supplement or complement a patient's microbiota in order to restore health or treat or prevent disease. In another embodiment, patients can be screened to determine the composition of their microbiota to determine the likelihood of successful treatment.

Combination Therapy

[0201] The bacterial compositions can be administered with other agents in a combination therapy mode, including anti-microbial agents and prebiotics. Administration can be sequential, over a period of hours or days, or simultaneous.

[0202] In one embodiment, the bacterial compositions are included in combination therapy with one or more anti-microbial agents, which include anti-bacterial agents, anti-fungal agents, anti-viral agents and anti-parasitic agents.

[0203] Anti-bacterial agents can include cephalosporin antibiotics (cephalexin, cefuroxime, cefadroxil, cefazolin, cephalothin, cefaclor, cefamandole, cefoxitin, cefprozil, and ceftobiprole); fluoroquinolone antibiotics (cipro, Levaquin, floxin, tequin, avelox, and norflox); tetracycline antibiotics (tetracycline, minocycline, oxytetracycline, and doxycycline); penicillin antibiotics (amoxicillin, ampicillin, penicillin V, dicloxacillin, carbenicillin, vancomycin, and methicillin); and carbapenem antibiotics (ertapenem, doripenem, imipenem/cilastatin, and meropenem).

[0204] Anti-viral agents can include Abacavir, Acyclovir, Adefovir, Amprenavir, Atazanavir, Cidofovir, Darunavir, Delavirdine, Didanosine, Docosanol, Efavirenz, Elvitegravir, Emtricitabine, Enfuvirtide, Etravirine, Famciclovir, Foscarnet, Fomivirsen, Ganciclovir, Indinavir, Idoxuridine, Lamivudine, Lopinavir Maraviroc, MK-2048, Nelfinavir, Nevirapine, Penciclovir, Raltegravir, Rilpivirine, Ritonavir, Saquinavir, Stavudine, Tenofovir Trifluridine, Valaciclovir, Valganciclovir, Vidarabine, Ibacitabine, Amantadine, Oseltamivir, Rimantidine, Tipranavir, Zalcitabine, Zanamivir and Zidovudine.

[0205] Examples of antifungal compounds include, but are not limited to polyene antifungals such as natamycin, rimocidin, filipin, nystatin, amphotericin B, candicin, and hamycin; imidazole antifungals such as miconazole, ketoconazole, clotrimazole, econazole, omoconazole, bifonazole, butoconazole, fenticonazole, isoconazole, oxiconazole, sertaconazole, sulconazole, and tioconazole; triazole antifungals such as fluconazole, itraconazole, isavuconazole, ravuconazole, posaconazole, voriconazole, terconazole, and albaconazole; thiazole antifungals such as abafungin; allylamine antifungals such as terbinafine, naftifine, and butenafine; and echinocandin antifungals such as anidulafungin, caspofungin, and micafungin. Other compounds that have antifungal properties include, but are not limited to polygodial, benzoic acid, ciclopirox, tolnaftate, undecylenic acid, flucytosine or 5-fluorocytosine, griseofulvin, and haloprogin.

[0206] In one embodiment, the bacterial compositions are included in combination therapy with one or more corticosteroids, mesalazine, mesalamine, sulfasalazine, sulfasalazine derivatives, immunosuppressive drugs, cyclosporin A, mercaptopurine, azathiopurine, prednisone, methotrexate, antihistamines, glucocorticoids, epinephrine, theophylline, cromolyn sodium, anti-leukotrienes, anti-cholinergic drugs for rhinitis, anti-cholinergic decongestants, mast-cell stabilizers, monoclonal anti-IgE antibodies, vaccines, and combinations thereof.

[0207] A prebiotic is a selectively fermented ingredient that allows specific changes, both in the composition and/or activity in the gastrointestinal microbiota that confers benefits upon host well-being and health. Prebiotics can include complex carbohydrates, amino acids, peptides, or other essential nutritional components for the survival of the bacterial composition. Prebiotics include, but

are not limited to, amino acids, biotin, fructooligosaccharide, galactooligosaccharides, inulin, lactulose, mannan oligosaccharides, oligofructose-enriched inulin, oligofructose, oligodextrose, tagatose, trans-galactooligosaccharide, and xylooligosaccharides.

Methods for Testing Bacterial Compositions for Populating Effect

In Vivo Assay for Determining Whether a Bacterial Composition Populates a Subject's Gastrointestinal Tract

[0208] In order to determine that the bacterial composition populates the gastrointestinal tract of a subject, an animal model, such as a mouse model, can be used. The model can begin by evaluating the microbiota of the mice. Qualitative assessments can be accomplished using 16S profiling of the microbial community in the feces of normal mice. It can also be accomplished by full genome sequencing, whole genome shotgun sequencing (WGS), or traditional microbiological techniques. Quantitative assessments can be conducted using quantitative PCR (qPCR), described below, or by using traditional microbiological techniques and counting colony formation.

[0209] Optionally, the mice can receive an antibiotic treatment to mimic the condition of dysbiosis. Antibiotic treatment can decrease the taxonomic richness, diversity, and evenness of the community, including a reduction of abundance of a significant number of bacterial taxa. Dethlefsen *et al.*, The pervasive effects of an antibiotic on the human gut microbiota, as revealed by deep 16S rRNA sequencing, PLoS Biology 6(11):3280 (2008). At least one antibiotic can be used, and antibiotics are well known. Antibiotics can include aminoglycoside antibiotic (amikacin, arbekacin,gentamicin, kanamycin, neomycin, netilmicin, paromomycin, rhodostreptomycin, streptomycin, tobramycin, and apramycin), amoxicillin, ampicillin, Augmentin (an amoxicillin/clavulanate potassium combination), cephalosporin (cefaclor, defadroxil, cefazolin, cefixime, fefoxitin, cefprozil, ceftazimdime, cefuroxime, cephalexin), clavulanate potassium, clindamycin, colistin, gentamycin, kanamycin, metronidazole, or vancomycin. As an individual, nonlimiting specific example, the mice can be provided with drinking water containing a mixture of the antibiotics kanamycin, colistin, gentamycin, metronidazole and vancomycin at 40 mg/kg, 4.2 mg/kg, 3.5 mg/kg, 21.5 mg/kg, and 4.5 mg/kg (mg per average mouse body weight), respectively, for 7 days. Alternatively, mice can be administered ciprofloxacin at a dose of 15-20 mg/kg (mg per average mouse body weight), for 7 days. If the mice are provided with an antibiotic, a wash out period of from one day to three days may be provided with no antibiotic treatment and no bacterial composition treatment.

[0210] Subsequently, the bacterial composition is administered to the mice by oral gavage. The bacterial composition may be administered in a volume of 0.2 ml containing 10^4 CFUs of each type of bacteria in the bacterial composition. Dose-response may be assessed by using a range of doses, including, but not limited to 10^2, 10^3, 10^4, 10^5, 10^6, 10^7, 10^8, 10^9, and/or 10^{10}.

[0211] The mice can be evaluated using 16S sequencing, full genome sequencing, whole genome shotgun sequencing (WGS), or traditional microbiological techniques to determine whether the

bacterial composition has populated the gastrointestinal tract of the mice. For example only, one day, three days, one week, two weeks, and one month after administration of the bacterial composition to the mice, 16S profiling is conducted to determine whether the test bacterial composition has populated the gastrointestinal tract of the mice. Quantitative assessments, including qPCR and traditional microbiological techniques such as colony counting, can additionally or alternatively be performed, at the same time intervals.

[0212] Furthermore, the number of sequence counts that correspond exactly to those in the bacterial composition over time can be assessed to determine specifically which components of the bacterial composition reside in the gastrointestinal tract over a particular period of time. In one embodiment, the strains of the bacterial composition persist for a desired period of time. In another embodiment, the components of the bacterial composition persist for a desired period of time, while also increasing the ability of other microbes (such as those present in the environment, food, etc.) to populate the gastrointestinal tract, further increasing overall diversity, as discussed below.

Ability of Bacterial compositions to Populate Different Regions of the Gastrointestinal Tract

[0213] The present bacterial compositions can also be assessed for their ability to populate different regions of the gastrointestinal tract. In one embodiment, a bacterial composition can be chosen for its ability to populate one or more than one region of the gastrointestinal tract, including, but not limited to the stomach, the small intestine (duodenum, jejunum, and ileum), the large intestine (the cecum, the colon (the ascending, transverse, descending, and sigmoid colon), and the rectum).

[0214] An *in vivo* study can be conducted to determine which regions of the gastrointestinal tract a given bacterial composition will populate. A mouse model similar to the one described above can be conducted, except instead of assessing the feces produced by the mice, particular regions of the gastrointestinal tract can be removed and studied individually. For example, at least one particular region of the gastrointestinal tract can be removed and a qualitative or quantitative determination can be performed on the contents of that region of the gastrointestinal tract. In another embodiment, the contents can optionally be removed and the qualitative or quantitative determination may be conducted on the tissue removed from the mouse.

qPCR

[0215] As one quantitative method for determining whether a bacterial composition populates the gastrointestinal tract, quantitative PCR (qPCR) can be performed. Standard techniques can be followed to generate a standard curve for the bacterial composition of interest, either for all of the components of the bacterial composition collectively, individually, or in subsets (if applicable). Genomic DNA can be extracted from samples using commercially-available kits, such as the Mo Bio Powersoil®-htp 96 Well Soil DNA Isolation Kit (Mo Bio Laboratories, Carlsbad, CA), the Mo Bio

Powersoil® DNA Isolation Kit (Mo Bio Laboratories, Carlsbad, CA), or the QIAamp DNA Stool Mini Kit (QIAGEN, Valencia, CA) according to the manufacturer's instructions.

[0216] In some embodiments, qPCR can be conducted using HotMasterMix (5PRIME, Gaithersburg, MD) and primers specific for the bacterial composition of interest, and may be conducted on a MicroAmp® Fast Optical 96-well Reaction Plate with Barcode (0.1mL) (Life Technologies, Grand Island, NY) and performed on a BioRad C1000™ Thermal Cycler equipped with a CFX96™ Real-Time System (BioRad, Hercules, CA), with fluorescent readings of the FAM and ROX channels. The Cq value for each well on the FAM channel is determined by the CFX Manager™ software version 2.1. The $\log_{10}$(cfu/ml) of each experimental sample is calculated by inputting a given sample's Cq value into linear regression model generated from the standard curve comparing the Cq values of the standard curve wells to the known $\log_{10}$(cfu/ml) of those samples. The skilled artisan may employ alternative qPCR modes.

Methods for Characterization of Bacterial Compositions

[0217] In certain embodiments, provided are methods for testing certain characteristics of bacterial compositions. For example, the sensitivity of bacterial compositions to certain environmental variables is determined, *e.g.*, in order to select for particular desirable characteristics in a given composition, formulation and/or use. For example, the constituents in the bacterial composition can be tested for pH resistance, bile acid resistance, and/or antibiotic sensitivity, either individually on a constituent-by-constituent basis or collectively as a bacterial composition comprised of multiple bacterial constituents (collectively referred to in this section as bacterial composition).

pH Sensitivity Testing

[0218] If a bacterial composition will be administered other than to the colon or rectum (*i.e.*, for example, an oral route), optionally testing for pH resistance enhances the selection of bacterial compositions that will survive at the highest yield possible through the varying pH environments of the distinct regions of the GI tract. Understanding how the bacterial compositions react to the pH of the GI tract also assists in formulation, so that the number of bacteria in a dosage form can be increased if beneficial and/or so that the composition may be administered in an enteric-coated capsule or tablet or with a buffering or protective composition. As the pH of the stomach can drop to a pH of 1 to 2 after a high-protein meal for a short time before physiological mechanisms adjust it to a pH of 3 to 4 and often resides at a resting pH of 4 to 5, and as the pH of the small intestine can range from a pH of 6 to 7.4, bacterial compositions can be prepared that survive these varying pH ranges (specifically wherein at least 1%, 5%, 10%, 15%, 20%, 25%, 30%, 40%, 50%, 60%, 70%, 80%, 90%, or as much as 100% of the bacteria can survive gut transit times through various pH ranges). This can be tested by exposing the bacterial composition to varying pH ranges for the expected gut transit times through those pH ranges. Therefore, as a nonlimiting example only, 18-hour cultures of bacterial compositions can be grown in standard media, such as gut microbiota medium ("GMM", see

Goodman et al., Extensive personal human gut microbiota culture collections characterized and manipulated in gnotobiotic mice, PNAS 108(15):6252-6257 (2011)) or another animal-products-free medium, with the addition of pH adjusting agents for a pH of 1 to 2 for 30 minutes, a pH of 3 to 4 for 1 hour, a pH of 4 to 5 for 1 to 2 hours, and a pH of 6 to 7.4 for 2.5 to 3 hours. An alternative method for testing stability to acid is described in U.S. Patent No. 4,839,281. Survival of bacteria may be determined by culturing the bacteria and counting colonies on appropriate selective or non-selective media.

Bile Acid Sensitivity Testing

[0219] Additionally, in some embodiments, testing for bile-acid resistance enhances the selection of bacterial compositions that will survive exposures to bile acid during transit through the GI tract. Bile acids are secreted into the small intestine and can, like pH, affect the survival of bacterial compositions. This can be tested by exposing the bacterial compositions to bile acids for the expected gut exposure time to bile acids. For example, bile acid solutions can be prepared at desired concentrations using 0.05 mM Tris at pH 9 as the solvent. After the bile acid is dissolved, the pH of the solution may be adjusted to 7.2 with 10% HCl. Bacterial compositions can be cultured in 2.2 ml of a bile acid composition mimicking the concentration and type of bile acids in the patient, 1.0 ml of 10% sterile-filtered feces media and 0.1 ml of an 18-hour culture of the given strain of bacteria. Incubations may be conducted for from 2.5 to 3 hours or longer. An alternative method for testing stability to bile acid is described in U.S. Patent No. 4,839,281. Survival of bacteria can be determined by culturing the bacteria and counting colonies on appropriate selective or non-selective media.

Antibiotic Sensitivity Testing

[0220] As a further optional sensitivity test, bacterial compositions can be tested for sensitivity to antibiotics. In one embodiment, bacterial compositions can be chosen so that the bacterial constituents are sensitive to antibiotics such that if necessary they can be eliminated or substantially reduced from the patient's gastrointestinal tract by at least one antibiotic targeting the bacterial composition.

Adherence to Gastrointestinal Cells

[0221] The bacterial compositions may optionally be tested for the ability to adhere to gastrointestinal cells. A method for testing adherence to gastrointestinal cells is described in U.S. Patent No. 4,839,281.

Methods for Purifying Spores

Solvent Treatments

[0222] To purify the bacterial spores, the fecal material is subjected to one or more solvent treatments. A solvent treatment is a miscible solvent treatment (either partially miscible or fully miscible) or an immiscible solvent treatment. Miscibility is the ability of two liquids to mix with each to form a homogeneous solution. Water and ethanol, for example, are fully miscible such that a

mixture containing water and ethanol in any ratio will show only one phase. Miscibility is provided as a wt/wt%, or weight of one solvent in 100 g of final solution. If two solvents are fully miscible in all proportions, their miscibility is 100%. Provided as fully miscible solutions with water are alcohols, *e.g.*, methanol, ethanol, isopropanol, butanol, etc. The alcohols can be provided already combined with water; *e.g.*, a solution containing10%, 20%, 25%, 30%, 35%, 40%, 45%, 50%, 55%, 60%, 65%, 70%, 75%, 89%, 85%, 90%, 95% or greater than 95% Other solvents are only partially miscible, meaning that only some portion will dissolve in water. Diethyl ether, for example, is partially miscible with water. Up to 7 grams of diethyl ether will dissolve in 93 g of water to give a 7% (wt/wt%) solution. If more diethyl ether is added, a two phase solution will result with a distinct diethyl ether layer above the water. Other miscible materials include ethers, dimethoxyethane, or tetrahydrofuran In contrast, an oil such as an alkane and water are immiscible and form two phases. Further, immiscible treatments are optionally combined with a detergent, either an ionic detergent or a non-ionic detergent. Exemplary detergents include Triton X-100, Tween 20, Tween 80, Nonidet P40, a pluronic, or a polyol.

Chromatography treatments

[0223] To purify spore populations, the fecal materials are subjected to one or more chromatographic treatments, either sequentially or in parallel. In a chromatographic treatment, a solution containing the fecal material is contacted with a solid medium containing a hydrophobic interaction chromatographic (HIC) medium or an affinity chromatographic medium. In an alternative embodiment, a solid medium capable of absorbing a residual habitat product present in the fecal material is contacted with a solid medium that adsorbs a residual habitat product. In certain embodiments, the HIC medium contains sepharose or a derivatized sepharose such as butyl sepharose, octyl sepharose, phenyl sepharose, or butyl-s sepharose. In other embodiments, the affinity chromatographic medium contains material derivatized with mucin type I, II, III, IV, V, or VI, or oligosaccharides derived from or similar to those of mucins type I, II, III, IV, V, or VI. Alternatively, the affinity chromatographic medium contains material derivatized with antibodies that recognize spore-forming bacteria.

Mechanical Treatments

[0224] Provided herein is the physical disruption of the fecal material, particularly by one or more mechanical treatment such as blending, mixing, shaking, vortexing, impact pulverization, and sonication. As provided herein, the mechanical disrupting treatment substantially disrupts a non-spore material present in the fecal material and does not substantially disrupt a spore present in the fecal material. Mechanical treatments optionally include filtration treatments, where the desired spore populations are retained on a filter while the undesirable (non-spore) fecal components to pass through, and the spore fraction is then recovered from the filter medium. Alternatively, undesirable particulates and eukaryotic cells may be retained on a filter while bacterial cells including spores pass through. In some embodiments the spore fraction retained on the filter medium is subjected to a

diafiltration step, wherein the retained spores are contacted with a wash liquid, typically a sterile saline-containing solution or other diluent, in order to further reduce or remove the undesirable fecal components.

Thermal Treatments

[0225] Provided herein is the thermal disruption of the fecal material. Generally, the fecal material is mixed in a saline-containing solution such as phosphate-buffered saline (PBS) and subjected to a heated environment, such as a warm room, incubator, water-bath, or the like, such that efficient heat transfer occurs between the heated environment and the fecal material. Preferably the fecal material solution is mixed during the incubation to enhance thermal conductivity and disrupt particulate aggregates. Thermal treatments can be modulated by the temperature of the environment and/or the duration of the thermal treatment. For example, the fecal material or a liquid comprising the fecal material is subjected to a heated environment, *e.g.*, a hot water bath of at least about 20, 25, 30, 35, 40, 45, 50, 55, 60, 65, 70, 75, 80, 85, 90, 95, 100 or greater than 100 degrees Celsius, for at least about 1, 5, 10, 15, 20, 30, 45 seconds, or 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 15, 20, 25, 30, 40, or 50 minutes, or 1, 2, 3, 4, 5, 6, 7, 8, 9, 10 or more than 10 hours. In certain embodiments the thermal treatment occurs at two different temperatures, such as 30 seconds in a 100 degree Celsius environment followed by 10 minutes in a 50 degree Celsius environment. In preferred embodiments the temperature and duration of the thermal treatment are sufficient to kill or remove pathogenic materials while not substantially damaging or reducing the germination-competency of the spores.

Irradiation Treatments

[0226] Provided are methods of treating the fecal material or separated contents of the fecal material with ionizing radiation, typically gamma irradiation, ultraviolet irradiation or electron beam irradiation provided at an energy level sufficient to kill pathogenic materials while not substantially damaging the desired spore populations. For example, ultraviolet radiation at 254nm provided at an energy level below about 22,000 microwatt seconds per cm^2 will not generally destroy desired spores.

Centrifugation and Density Separation Treatments

[0227] Provided are methods of separating desired spore populations from the other components of the fecal material by centrifugation. A solution containing the fecal material is subjected to one or more centrifugation treatments, *e.g.*, at about 1000 x g, 2000 x g, 3000 x g, 4000 x g, 5000 x g, 6000 x g, 7000 x g, 8000 x g or greater than 8000 x g. Differential centrifugation separates desired spores from undesired non-spore material; at low forces the spores are retained in solution, while at higher forces the spores are pelleted while smaller impurities (*e.g.*, virus particles, phage) are retained in solution. For example, a first low force centrifugation pellets fibrous materials; a second, higher force centrifugation pellets undesired eukaryotic cells, and a third, still higher force centrifugation pellets the desired spores while small contaminants remain in suspension. In some embodiments density or mobility gradients or cushions (*e.g.*, step cushions), such as Percoll, Ficoll, Nycodenz, Histodenz or

sucrose gradients, are used to separate desired spore populations from other materials in the fecal material.

[0228] Also provided herein are methods of producing spore populations that combine two or more of the treatments described herein in order to synergistically purify the desired spores while killing or removing undesired materials and/or activities from the spore population. It is generally desirable to retain the spore populations under non-germinating and non-growth promoting conditions and media, in order to minimize the growth of pathogenic bacteria present in the spore populations and to minimize the germination of spores into vegetative bacterial cells.

PHARMACEUTICAL COMPOSITIONS AND FORMULATIONS OF THE INVENTION

Formulations

[0229] Provided are formulations for administration to humans and other subjects in need thereof. Generally the bacterial compositions are combined with additional active and/or inactive materials in order to produce a final product, which may be in single dosage unit or in a multi-dose format.

[0230] In some embodiments, the composition comprises at least one carbohydrate. A "carbohydrate" refers to a sugar or polymer of sugars. The terms "saccharide," "polysaccharide," "carbohydrate," and "oligosaccharide" may be used interchangeably. Most carbohydrates are aldehydes or ketones with many hydroxyl groups, usually one on each carbon atom of the molecule. Carbohydrates generally have the molecular formula $C_nH_{2n}O_n$. A carbohydrate can be a monosaccharide, a disaccharide, trisaccharide, oligosaccharide, or polysaccharide. The most basic carbohydrate is a monosaccharide, such as glucose, sucrose, galactose, mannose, ribose, arabinose, xylose, and fructose. Disaccharides are two joined monosaccharides. Exemplary disaccharides include sucrose, maltose, cellobiose, and lactose. Typically, an oligosaccharide includes between three and six monosaccharide units (*e.g.*, raffinose, stachyose), and polysaccharides include six or more monosaccharide units. Exemplary polysaccharides include starch, glycogen, and cellulose. Carbohydrates can contain modified saccharide units, such as 2'-deoxyribose wherein a hydroxyl group is removed, 2'-fluororibose wherein a hydroxyl group is replace with a fluorine, or N-acetylglucosamine, a nitrogen-containing form of glucose (*e.g.*, 2'-fluororibose, deoxyribose, and hexose). Carbohydrates can exist in many different forms, for example, conformers, cyclic forms, acyclic forms, stereoisomers, tautomers, anomers, and isomers.

[0231] In some embodiments, the composition comprises at least one lipid. As used herein, a "lipid" includes fats, oils, triglycerides, cholesterol, phospholipids, fatty acids in any form including free fatty acids. Fats, oils and fatty acids can be saturated, unsaturated (cis or trans) or partially unsaturated (cis or trans). In some embodiments, the lipid comprises at least one fatty acid selected from lauric acid (12:0), myristic acid (14:0), palmitic acid (16:0), palmitoleic acid (16:1), margaric acid (17:0), heptadecenoic acid (17:1), stearic acid (18:0), oleic acid (18:1), linoleic acid (18:2),

linolenic acid (18:3), octadecatetraenoic acid (18:4), arachidic acid (20:0), eicosenoic acid (20:1), eicosadienoic acid (20:2), eicosatetraenoic acid (20:4), eicosapentaenoic acid (20:5) (EPA), docosanoic acid (22:0), docosenoic acid (22:1), docosapentaenoic acid (22:5), docosahexaenoic acid (22:6) (DHA), and tetracosanoic acid (24:0). In other embodiments, the composition comprises at least one modified lipid, for example, a lipid that has been modified by cooking.

[0232] In some embodiments, the composition comprises at least one supplemental mineral or mineral source. Examples of minerals include, without limitation: chloride, sodium, calcium, iron, chromium, copper, iodine, zinc, magnesium, manganese, molybdenum, phosphorus, potassium, and selenium. Suitable forms of any of the foregoing minerals include soluble mineral salts, slightly soluble mineral salts, insoluble mineral salts, chelated minerals, mineral complexes, non-reactive minerals such as carbonyl minerals, and reduced minerals, and combinations thereof.

[0233] In certain embodiments, the composition comprises at least one supplemental vitamin. The at least one vitamin can be fat-soluble or water soluble vitamins. Suitable vitamins include but are not limited to vitamin C, vitamin A, vitamin E, vitamin B12, vitamin K, riboflavin, niacin, vitamin D, vitamin B6, folic acid, pyridoxine, thiamine, pantothenic acid, and biotin. Suitable forms of any of the foregoing are salts of the vitamin, derivatives of the vitamin, compounds having the same or similar activity of the vitamin, and metabolites of the vitamin.

[0234] In other embodiments, the composition comprises an excipient. Non-limiting examples of suitable excipients include a buffering agent, a preservative, a stabilizer, a binder, a compaction agent, a lubricant, a dispersion enhancer, a disintegration agent, a flavoring agent, a sweetener, and a coloring agent.

[0235] In another embodiment, the excipient is a buffering agent. Non-limiting examples of suitable buffering agents include sodium citrate, magnesium carbonate, magnesium bicarbonate, calcium carbonate, and calcium bicarbonate.

[0236] In some embodiments, the excipient comprises a preservative. Non-limiting examples of suitable preservatives include antioxidants, such as alpha-tocopherol and ascorbate, and antimicrobials, such as parabens, chlorobutanol, and phenol.

[0237] In other embodiments, the composition comprises a binder as an excipient. Non-limiting examples of suitable binders include starches, pregelatinized starches, gelatin, polyvinylpyrolidone, cellulose, methylcellulose, sodium carboxymethylcellulose, ethylcellulose, polyacrylamides, polyvinyloxoazolidone, polyvinylalcohols, C_{12}-C_{18} fatty acid alcohol, polyethylene glycol, polyols, saccharides, oligosaccharides, and combinations thereof.

[0238] In another embodiment, the composition comprises a lubricant as an excipient. Non-limiting examples of suitable lubricants include magnesium stearate, calcium stearate, zinc stearate, hydrogenated vegetable oils, sterotex, polyoxyethylene monostearate, talc, polyethyleneglycol, sodium benzoate, sodium lauryl sulfate, magnesium lauryl sulfate, and light mineral oil.

[0239] In other embodiments, the composition comprises a dispersion enhancer as an excipient. Non-limiting examples of suitable dispersants include starch, alginic acid, polyvinylpyrrolidones, guar gum, kaolin, bentonite, purified wood cellulose, sodium starch glycolate, isoamorphous silicate, and microcrystalline cellulose as high HLB emulsifier surfactants.

[0240] In some embodiments, the composition comprises a disintegrant as an excipient. In other embodiments, the disintegrant is a non-effervescent disintegrant. Non-limiting examples of suitable non-effervescent disintegrants include starches such as corn starch, potato starch, pregelatinized and modified starches thereof, sweeteners, clays, such as bentonite, micro-crystalline cellulose, alginates, sodium starch glycolate, gums such as agar, guar, locust bean, karaya, pecitin, and tragacanth. In another embodiment, the disintegrant is an effervescent disintegrant. Non-limiting examples of suitable effervescent disintegrants include sodium bicarbonate in combination with citric acid, and sodium bicarbonate in combination with tartaric acid.

[0241] In another embodiment, the excipient comprises a flavoring agent. Flavoring agents can be chosen from synthetic flavor oils and flavoring aromatics; natural oils; extracts from plants, leaves, flowers, and fruits; and combinations thereof. In some embodiments the flavoring agent is selected from cinnamon oils; oil of wintergreen; peppermint oils; clover oil; hay oil; anise oil; eucalyptus; vanilla; citrus oil such as lemon oil, orange oil, grape and grapefruit oil; and fruit essences including apple, peach, pear, strawberry, raspberry, cherry, plum, pineapple, and apricot.

[0242] In other embodiments, the excipient comprises a sweetener. Non-limiting examples of suitable sweeteners include glucose (corn syrup), dextrose, invert sugar, fructose, and mixtures thereof (when not used as a carrier); saccharin and its various salts such as the sodium salt; dipeptide sweeteners such as aspartame; dihydrochalcone compounds, glycyrrhizin; Stevia Rebaudiana (Stevioside); chloro derivatives of sucrose such as sucralose; and sugar alcohols such as sorbitol, mannitol, sylitol, and the like. Also contemplated are hydrogenated starch hydrolysates and the synthetic sweetener 3,6-dihydro-6-methyl-1,2,3-oxathiazin-4-one-2,2-dioxide, particularly the potassium salt (acesulfame-K), and sodium and calcium salts thereof.

[0243] In yet other embodiments, the composition comprises a coloring agent. Non-limiting examples of suitable color agents include food, drug and cosmetic colors (FD&C), drug and cosmetic colors (D&C), and external drug and cosmetic colors (Ext. D&C). The coloring agents can be used as dyes or their corresponding lakes.

[0244] The weight fraction of the excipient or combination of excipients in the formulation is usually about 99% or less, such as about 95% or less, about 90% or less, about 85% or less, about 80% or less, about 75% or less, about 70% or less, about 65% or less, about 60% or less, about 55% or less, 50% or less, about 45% or less, about 40% or less, about 35% or less, about 30% or less, about 25% or less, about 20% or less, about 15% or less, about 10% or less, about 5% or less, about 2% or less, or about 1% or less of the total weight of the composition.

[0245] The bacterial compositions disclosed herein can be formulated into a variety of forms and administered by a number of different means. The compositions can be administered orally, rectally, or parenterally, in formulations containing conventionally acceptable carriers, adjuvants, and vehicles as desired. The term "parenteral" as used herein includes subcutaneous, intravenous, intramuscular, or intrasternal injection and infusion techniques. In an exemplary embodiment, the bacterial composition is administered orally.

[0246] Solid dosage forms for oral administration include capsules, tablets, caplets, pills, troches, lozenges, powders, and granules. A capsule typically comprises a core material comprising a bacterial composition and a shell wall that encapsulates the core material. In some embodiments, the core material comprises at least one of a solid, a liquid, and an emulsion. In other embodiments, the shell wall material comprises at least one of a soft gelatin, a hard gelatin, and a polymer. Suitable polymers include, but are not limited to: cellulosic polymers such as hydroxypropyl cellulose, hydroxyethyl cellulose, hydroxypropyl methyl cellulose (HPMC), methyl cellulose, ethyl cellulose, cellulose acetate, cellulose acetate phthalate, cellulose acetate trimellitate, hydroxypropylmethyl cellulose phthalate, hydroxypropylmethyl cellulose succinate and carboxymethylcellulose sodium; acrylic acid polymers and copolymers, such as those formed from acrylic acid, methacrylic acid, methyl acrylate, ammonio methylacrylate, ethyl acrylate, methyl methacrylate and/or ethyl methacrylate (*e.g.*, those copolymers sold under the trade name "Eudragit"); vinyl polymers and copolymers such as polyvinyl pyrrolidone, polyvinyl acetate, polyvinylacetate phthalate, vinylacetate crotonic acid copolymer, and ethylene-vinyl acetate copolymers; and shellac (purified lac). In yet other embodiments, at least one polymer functions as taste-masking agents.

[0247] Tablets, pills, and the like can be compressed, multiply compressed, multiply layered, and/or coated. The coating can be single or multiple. In one embodiment, the coating material comprises at least one of a saccharide, a polysaccharide, and glycoproteins extracted from at least one of a plant, a fungus, and a microbe. Non-limiting examples include corn starch, wheat starch, potato starch, tapioca starch, cellulose, hemicellulose, dextrans, maltodextrin, cyclodextrins, inulins, pectin, mannans, gum arabic, locust bean gum, mesquite gum, guar gum, gum karaya, gum ghatti, tragacanth gum, funori, carrageenans, agar, alginates, chitosans, or gellan gum. In some embodiments the coating material comprises a protein. In another embodiment, the coating material comprises at least one of a fat and an oil. In other embodiments, the at least one of a fat and an oil is high temperature melting. In yet another embodiment, the at least one of a fat and an oil is hydrogenated or partially hydrogenated. In one embodiment, the at least one of a fat and an oil is derived from a plant. In other embodiments, the at least one of a fat and an oil comprises at least one of glycerides, free fatty acids, and fatty acid esters. In some embodiments, the coating material comprises at least one edible wax. The edible wax can be derived from animals, insects, or plants. Non-limiting examples include

beeswax, lanolin, bayberry wax, carnauba wax, and rice bran wax. Tablets and pills can additionally be prepared with enteric coatings.

[0248] Alternatively, powders or granules embodying the bacterial compositions disclosed herein can be incorporated into a food product. In some embodiments, the food product is a drink for oral administration. Non-limiting examples of a suitable drink include fruit juice, a fruit drink, an artificially flavored drink, an artificially sweetened drink, a carbonated beverage, a sports drink, a liquid diary product, a shake, an alcoholic beverage, a caffeinated beverage, infant formula and so forth. Other suitable means for oral administration include aqueous and nonaqueous solutions, emulsions, suspensions and solutions and/or suspensions reconstituted from non-effervescent granules, containing at least one of suitable solvents, preservatives, emulsifying agents, suspending agents, diluents, sweeteners, coloring agents, and flavoring agents.

[0249] In some embodiments, the food product can be a solid foodstuff. Suitable examples of a solid foodstuff include without limitation a food bar, a snack bar, a cookie, a brownie, a muffin, a cracker, an ice cream bar, a frozen yogurt bar, and the like.

[0250] In other embodiments, the compositions disclosed herein are incorporated into a therapeutic food. In some embodiments, the therapeutic food is a ready-to-use food that optionally contains some or all essential macronutrients and micronutrients. In another embodiment, the compositions disclosed herein are incorporated into a supplementary food that is designed to be blended into an existing meal. In one embodiment, the supplemental food contains some or all essential macronutrients and micronutrients. In another embodiment, the bacterial compositions disclosed herein are blended with or added to an existing food to fortify the food's protein nutrition. Examples include food staples (grain, salt, sugar, cooking oil, margarine), beverages (coffee, tea, soda, beer, liquor, sports drinks), snacks, sweets and other foods.

[0251] In one embodiment, the formulations are filled into gelatin capsules for oral administration. An example of an appropriate capsule is a 250 mg gelatin capsule containing from 10 (up to 100 mg) of lyophilized powder (10^8 to 10^{11} bacteria), 160 mg microcrystalline cellulose, 77.5 mg gelatin, and 2.5 mg magnesium stearate. In an alternative embodiment, from 10^5 to 10^{12} bacteria may be used, 10^5 to 10^7, 10^6 to 10^7, or 10^8 to 10^{10}, with attendant adjustments of the excipients if necessary. In an alternative embodiment, an enteric-coated capsule or tablet or with a buffering or protective composition can be used.

EXAMPLES

[0252] Below are examples of specific embodiments for carrying out the present invention. The examples are offered for illustrative purposes only, and are not intended to limit the scope of the present invention in any way. Efforts have been made to ensure accuracy with respect to numbers used (*e.g.*, amounts, temperatures, etc.), but some experimental error and deviation should, of course, be allowed for.

[0253] The practice of the present invention will employ, unless otherwise indicated, conventional methods of protein chemistry, biochemistry, recombinant DNA techniques and pharmacology, within the skill of the art. Such techniques are explained fully in the literature. See, *e.g.*, T.E. Creighton, *Proteins: Structures and Molecular Properties* (W.H. Freeman and Company, 1993); A.L. Lehninger, *Biochemistry* (Worth Publishers, Inc., current addition); Sambrook, et al., *Molecular Cloning: A Laboratory Manual* (2nd Edition, 1989); *Methods In Enzymology* (S. Colowick and N. Kaplan eds., Academic Press, Inc.); *Remington's Pharmaceutical Sciences*, 18th Edition (Easton, Pennsylvania: Mack Publishing Company, 1990); Carey and Sundberg *Advanced Organic Chemistry 3rd Ed.* (Plenum Press) Vols A and B(1992).

Example 1: Sequence-based Genomic Characterization of Operational Taxonomic Units (OTU) and Functional Genes

Method for Determining 16S rDNA Gene Sequence

[0254] As described above, OTUs are defined either by full 16S sequencing of the rRNA gene, by sequencing of a specific hypervariable region of this gene (*i.e.* V1, V2, V3, V4, V5, V6, V7, V8, or V9), or by sequencing of any combination of hypervariable regions from this gene (*e.g.* V1-3 or V3-5). The bacterial 16S rRNA gene is approximately 1500 nucleotides in length and is used in reconstructing the evolutionary relationships and sequence similarity of one bacterial isolate to another using phylogenetic approaches. 16S sequences are used for phylogenetic reconstruction as they are in general highly conserved, but contain specific hypervariable regions that harbor sufficient nucleotide diversity to differentiate genera and species of most microbes. rRNA gene sequencing methods are applicable to both the analysis of non-enriched samples, but also for identification of microbes after enrichment steps that either enrich the microbes of interest from the microbial composition and/or the nucleic acids that harbor the appropriate rDNA gene sequences as described below. For example, enrichment treatments prior to 16S rDNA gene characterization will increase the sensitivity of 16S as well as other molecular-based characterization nucleic acid purified from the microbes.

[0255] Using well known techniques, in order to determine the full 16S sequence or the sequence of any hypervariable region of the 16S rRNA sequence, genomic DNA is extracted from a bacterial sample, the 16S rDNA (full region or specific hypervariable regions) amplified using polymerase chain reaction (PCR), the PCR products cleaned, and nucleotide sequences delineated to determine the genetic composition of 16S gene or subdomain of the gene. If full 16S sequencing is performed, the sequencing method used may be, but is not limited to, Sanger sequencing. If one or more hypervariable regions are used, such as the V4 region, the sequencing may be, but is not limited to being, performed using the Sanger method or using a next-generation sequencing method, such as an Illumina (sequencing by synthesis) method using barcoded primers allowing for multiplex reactions.

Method for Determining 18S rDNA and ITS Gene Sequence

[0256] Methods to assign and identify fungal OTUs by genetic means can be accomplished by analyzing 18S sequences and the internal transcribed spacer (ITS). The rRNA of fungi that forms the core of the ribosome is transcribed as a signal gene and consists of the 8S, 5.8S and 28S regions with ITS4 and 5 between the 8S and 5.8S and 5.8S and 28S regions, respectively. These two intercistronic segments between the 18S and 5.8S and 5.8S and 28S regions are removed by splicing and contain significant variation between species for barcoding purposes as previously described (Schoch et al Nuclear ribosomal internal transcribed spacer (ITS) region as a universal DNA barcode marker for Fungi. PNAS 109:6241-6246. 2012). 18S rDNA is traditionally used for phylogenetic reconstruction however the ITS can serve this function as it is generally highly conserved but contains hypervariable regions that harbor sufficient nucleotide diversity to differentiate genera and species of most fungus.

[0257] Using well known techniques, in order to determine the full 18S and ITS sequences or a smaller hypervariable section of these sequences, genomic DNA is extracted from a microbial sample, the rDNA amplified using polymerase chain reaction (PCR), the PCR products cleaned, and nucleotide sequences delineated to determine the genetic composition rDNA gene or subdomain of the gene. The sequencing method used may be, but is not limited to, Sanger sequencing or using a next-generation sequencing method, such as an Illumina (sequencing by synthesis) method using barcoded primers allowing for multiplex reactions.

Method for Determining Other Marker Gene Sequences

[0258] In addition to the 16S and 18S rRNA gene, one may define an OTU by sequencing a selected set of genes that are known to be marker genes for a given species or taxonomic group of OTUs. These genes may alternatively be assayed using a PCR-based screening strategy. As example, various strains of pathogenic Escherichia coli can be distinguished using DNAs from the genes that encode heat-labile (LTI, LTIIa, and LTIIb) and heat-stable (STI and STII) toxins, verotoxin types 1, 2, and 2e (VT1, VT2, and VT2e, respectively), cytotoxic necrotizing factors (CNF1 and CNF2), attaching and effacing mechanisms (eaeA), enteroaggregative mechanisms (Eagg), and enteroinvasive mechanisms (Einv). The optimal genes to utilize for taxonomic assignment of OTUs by use of marker genes will be familiar to one with ordinary skill of the art of sequence based taxonomic identification.

Genomic DNA Extraction

[0259] Genomic DNA is extracted from pure microbial cultures using a hot alkaline lysis method. 1 µl of microbial culture is added to 9 µl of Lysis Buffer (25mM NaOH, 0.2 mM EDTA) and the mixture is incubated at 95°C for 30 minutes. Subsequently, the samples are cooled to 4°C and neutralized by the addition of 10 µl of Neutralization Buffer (40 mM Tris-HCl) and then diluted 10-fold in Elution Buffer (10 mM Tris-HCl). Alternatively, genomic DNA is extracted from pure microbial cultures using commercially available kits such as the Mo Bio Ultraclean® Microbial DNA Isolation Kit (Mo Bio Laboratories, Carlsbad, CA) or by standard methods known to those skilled in

the art. For fungal samples, DNA extraction can be performed by methods described previously (US20120135127) for producing lysates from fungal fruiting bodies by mechanical grinding methods.

Amplification of 16S Sequences for Downstream Sanger Sequencing

[0260] To amplify bacterial 16S rDNA (e.g, in Figure 1), 2 µl of extracted gDNA is added to a 20 µl final volume PCR reaction. For full-length 16 sequencing the PCR reaction also contains 1x HotMasterMix (5PRIME, Gaithersburg, MD), 250 nM of 27f (AGRGTTTGATCMTGGCTCAG, IDT, Coralville, IA), and 250 nM of 1492r (TACGGYTACCTTGTTAYGACTT, IDT, Coralville, IA), with PCR Water (Mo Bio Laboratories, Carlsbad, CA) for the balance of the volume.

[0261] Figure 1 shows the hypervariable regions mapped onto a 16s sequence and the sequence regions corresponding to these sequences on a sequence map. A schematic is shown of a 16S rRNA gene and the figure denotes the coordinates of hypervariable regions 1-9 (V1-V9), according to an embodiment of the invention. Coordinates of V1-V9 are 69-99, 137-242, 433-497, 576-682, 822-879, 986-1043, 1117-1173, 1243-1294, and 1435-1465 respectively, based on numbering using E. coli system of nomenclature defined by Brosius et al., Complete nucleotide sequence of a 16S ribosomal RNA gene (16S rRNA) from Escherichia coli, PNAS 75(10):4801-4805 (1978).

[0262] Alternatively, other universal bacterial primers or thermostable polymerases known to those skilled in the art are used. For example, primers are available to those skilled in the art for the sequencing of the the "V1-V9 regions" of the 16S rRNA (*e.g.*, Figure 1). These regions refer to the first through ninth hypervariable regions of the 16S rRNA gene that are used for genetic typing of bacterial samples. These regions in bacteria are defined by nucleotides 69-99, 137-242, 433-497, 576-682, 822-879, 986-1043, 1117-1173, 1243-1294 and 1435-1465 respectively using numbering based on the E. coli system of nomenclature. *See* Brosius et al., Complete nucleotide sequence of a 16S ribosomal RNA gene from Escherichia coli, PNAS 75(10):4801-4805 (1978). In some embodiments, at least one of the V1, V2, V3, V4, V5, V6, V7, V8, and V9 regions are used to characterize an OTU. In one embodiment, the V1, V2, and V3 regions are used to characterize an OTU. In another embodiment, the V3, V4, and V5 regions are used to characterize an OTU. In another embodiment, the V4 region is used to characterize an OTU. A person of ordinary skill in the art can identify the specific hypervariable regions of a candidate 16S rRNA (*e.g.*, Figure 1) by comparing the candidate sequence in question to the reference sequence (as in Figure 2) and identifying the hypervariable regions based on similarity to the reference hypervariable regions. Figure 2 highlights in bold the nucleotide sequences for each hypervariable region in the exemplary reference E. coli 16S sequence described by Brosius et al.

[0263] The PCR is performed on commercially available thermocyclers such as a BioRad MyCycler™ Thermal Cycler (BioRad, Hercules, CA). The reactions are run at 94°C for 2 minutes followed by 30 cycles of 94°C for 30 seconds, 51°C for 30 seconds, and 68°C for 1 minute 30 seconds, followed by a 7 minute extension at 72°C and an indefinite hold at 4°C. Following PCR, gel

electrophoresis of a portion of the reaction products is used to confirm successful amplification of a ~1.5 kb product.

[0264] To remove nucleotides and oligonucleotides from the PCR products, 2 µl of HT ExoSap-IT (Affymetrix, Santa Clara, CA) is added to 5 µl of PCR product followed by a 15 minute incubation at 37°C and then a 15 minute inactivation at 80°C.

Amplification of 16S Sequences for Downstream Characterization By Massively Parallel Sequencing Technologies

[0265] Amplification performed for downstream sequencing by short read technologies such as Illumina require amplification using primers known to those skilled in the art that additionally include a sequence-based barcoded tag. As example, to amplify the 16s hypervariable region V4 region of bacterial 16S rDNA, 2 µl of extracted gDNA is added to a 20 µl final volume PCR reaction. The PCR reaction also contains 1x HotMasterMix (5PRIME, Gaithersburg, MD), 200 nM of V4_515f_adapt (AATGATACGGCGACCACCGAGATCTACACTATGGTAATTGTGTGCCAGCMGCCGCGGTAA, IDT, Coralville, IA), and 200 nM of barcoded 806rbc (CAAGCAGAAGACGGCATACGAGAT_12bpGolayBarcode_AGTCAGTCAGCCGGACTACHVGGGTWTCTAAT, IDT, Coralville, IA), with PCR Water (Mo Bio Laboratories, Carlsbad, CA) for the balance of the volume. These primers incorporate barcoded adapters for Illumina sequencing by synthesis. Optionally, identical replicate, triplicate, or quadruplicate reactions may be performed. Alternatively other universal bacterial primers or thermostable polymerases known to those skilled in the art are used to obtain different amplification and sequencing error rates as well as results on alternative sequencing technologies.

[0266] The PCR amplification is performed on commercially available thermocyclers such as a BioRad MyCycler™ Thermal Cycler (BioRad, Hercules, CA). The reactions are run at 94°C for 3 minutes followed by 25 cycles of 94°C for 45 seconds, 50°C for 1 minute, and 72°C for 1 minute 30 seconds, followed by a 10 minute extension at 72°C and a indefinite hold at 4°C. Following PCR, gel electrophoresis of a portion of the reaction products is used to confirm successful amplification of a ~1.5 kb product. PCR cleanup is performed as described above.

Sanger Sequencing of Target Amplicons from Pure Homogeneous Samples

[0267] To detect nucleic acids for each sample, two sequencing reactions are performed to generate a forward and reverse sequencing read. For full-length 16s sequencing primers 27f and 1492r are used. 40 ng of ExoSap-IT-cleaned PCR products are mixed with 25 pmol of sequencing primer and Mo Bio Molecular Biology Grade Water (Mo Bio Laboratories, Carlsbad, CA) to 15 µl total volume. This reaction is submitted to a commercial sequencing organization such as Genewiz (South Plainfield, NJ) for Sanger sequencing.

Amplification of 18S and ITS regions for Downstream Sequencing

[0268] To amplify the 18S or ITS regions, 2 μL fungal DNA were amplified in a final volume of 30 μL with 15 μL AmpliTaq Gold 360 Mastermix, PCR primers, and water. The forward and reverse primers for PCR of the ITS region are 5'-TCCTCCGCTTATTGATATGC-3' and 5'-GGAAGTAAAAGTCGTAACAAGG-3' and are added at 0.2uM concentration each. The forward and reverse primers for the 18s region are 5'-GTAGTCATATGCTTGTCTC-3' and 5'-CTTCCGTCAATTCCTTTAAG-3' and are added at 0.4uM concentration each. PCR is performed with the following protocol: 95C for 10 min, 35 cycles of 95C for 15 seconds, 52C for 30 seconds, 72C for 1.5s; and finally 72C for 7 minutes followed by storage at 4C. All forward primers contained the M13F-20 sequencing primer, and reverse primers included the M13R-27 sequencing primer. PCR products (3 μL) were enzymatically cleaned before cycle sequencing with 1 μL ExoSap-IT and 1 μL Tris EDTA and incubated at 37 °C for 20 min followed by 80 °C for 15 min. Cycle sequencing reactions contained 5 μL cleaned PCR product, 2 μL BigDye Terminator v3.1 Ready Reaction Mix, 1 μL 5× Sequencing Buffer, 1.6 pmol of appropriate sequencing primers designed by one skilled in the art, and water in a final volume of 10 μL. The standard cycle sequencing protocol is 27 cycles of 10 s at 96 °C, 5 s at 50 °C, 4 min at 60 °C, and hold at 4 °C. Sequencing cleaning is performed with the BigDye XTerminator Purification Kit as recommended by the manufacturer for 10-μL volumes. The genetic sequence of the resulting 18S and ITS sequences is performed using methods familiar to one with ordinary skill in the art using either Sanger sequencing technology or next-generation sequencing technologies such as but not limited to Illumina.

Preparation of Extracted Nucleic Acids for Metagenomic Characterization by Massively Parallel Sequencing Technologies

[0269] Extracted nucleic acids (DNA or RNA) are purified and prepared by downstream sequencing using standard methods familiar to one with ordinary skill in the art and as described by the sequencing technology's manufactures instructions for library preparation. In short, RNA or DNA are purified using standard purification kits such as but not limited to Qiagen's RNeasy Kit or Promega's Genomic DNA purification kit. For RNA, the RNA is converted to cDNA prior to sequence library construction. Following purification of nucleic acids, RNA is converted to cDNA using reverse transcription technology such as but not limited to Nugen Ovation RNA-Seq System or Illumina Truseq as per the manufacturer's instructions. Extracted DNA or transcribed cDNA are sheared using physical (*e.g.*, Hydroshear), acoustic (*e.g.*, Covaris), or molecular (*e.g.*, Nextera) technologies and then size selected as per the sequencing technologies manufacturer's recommendations. Following size selection, nucleic acids are prepared for sequencing as per the manufacturer's instructions for sample indexing and sequencing adapter ligation using methods familiar to one with ordinary skill in the art of genomic sequencing.

Massively Parallel Sequencing of Target Amplicons from Heterogeneous Samples

DNA Quantification & Library Construction

[0270] The cleaned PCR amplification products are quantified using the Quant-iT™ PicoGreen® dsDNA Assay Kit (Life Technologies, Grand Island, NY) according to the manufacturer's instructions. Following quantification, the barcoded cleaned PCR products are combined such that each distinct PCR product is at an equimolar ratio to create a prepared Illumina library.

Nucleic Acid Detection

[0271] The prepared library is sequenced on Illumina HiSeq or MiSeq sequencers (Illumina, San Diego, CA) with cluster generation, template hybridization, isothermal amplification, linearization, blocking and denaturation and hybridization of the sequencing primers performed according to the manufacturer's instructions. 16SV4SeqFw (TATGGTAATTGTGTGCCAGCMGCCGCGGTAA), 16SV4SeqRev (AGTCAGTCAGCCGGACTACHVGGGTWTCTAAT), and 16SV4Index (ATTAGAWACCCBDGTAGTCCGGCTGACTGACT) (IDT, Coralville, IA) are used for sequencing. Other sequencing technologies can be used such as but not limited to 454, Pacific Biosciences, Helicos, Ion Torrent, and Nanopore using protocols that are standard to someone skilled in the art of genomic sequencing.

Example 2. Sequence Read Annotation

Primary Read Annotation

[0272] Nucleic acid sequences are analyzed and annotated to define taxonomic assignments using sequence similarity and phylogenetic placement methods or a combination of the two strategies. A similar approach can be used to annotate protein names, protein function, transcription factor names, and any other classification schema for nucleic acid sequences. Sequence similarity based methods include those familiar to individuals skilled in the art including, but not limited to BLAST, BLASTx, tBLASTn, tBLASTx, RDP-classifier, DNAclust, and various implementations of these algorithms such as Qiime or Mothur. These methods rely on mapping a sequence read to a reference database and selecting the match with the best score and e-value. Common databases include, but are not limited to the Human Microbiome Project, NCBI non-redundant database, Greengenes, RDP, and Silva for taxonomic assignments. For functional assignments reads are mapped to various functional databases such as but not limited to COG, KEGG, BioCyc, and MetaCyc. Further functional annotations can be derived from 16S taxonomic annotations using programs such as PICRUST (M. Langille, et al 2013. Nature Biotechnology 31, 814-821). Phylogenetic methods can be used in combination with sequence similarity methods to improve the calling accuracy of an annotation or taxonomic assignment. Here tree topologies and nodal structure are used to refine the resolution of the analysis. In this approach we analyze nucleic acid sequences using one of numerous sequence similarity approaches and leverage phylogenetic methods that are well known to those skilled in the art, including but not limited to maximum likelihood phylogenetic reconstruction (see *e.g.* Liu K, Linder CR, and Warnow T. 2011. RAxML and FastTree: Comparing Two Methods for Large-Scale Maximum Likelihood Phylogeny Estimation. PLoS ONE 6: e27731. McGuire G, Denham MC, and

Balding DJ. 2001. Models of sequence evolution for DNA sequences containing gaps. Mol. Biol. Evol 18: 481–490. Wróbel B. 2008. Statistical measures of uncertainty for branches in phylogenetic trees inferred from molecular sequences by using model-based methods. J. Appl. Genet. 49: 49–67.) Sequence reads (*e.g.* 16S, 18S, or ITS) are placed into a reference phylogeny comprised of appropriate reference sequences. Annotations are made based on the placement of the read in the phylogenetic tree. The certainty or significance of the OTU annotation is defined based on the OTU's sequence similarity to a reference nucleic acid sequence and the proximity of the OTU sequence relative to one or more reference sequences in the phylogeny. As an example, the specificity of a taxonomic assignment is defined with confidence at the the level of Family, Genus, Species, or Strain with the confidence determined based on the position of bootstrap supported branches in the reference phylogenetic tree relative to the placement of the OTU sequence being interrogated. Nucleic acid sequences can be assigned functional annotations using the methods described above.

Clade Assignments

[0273] The ability of 16S-V4 OTU identification to assign an OTU as a specific species depends in part on the resolving power of the 16S-V4 region of the 16S gene for a particular species or group of species. Both the density of available reference 16S sequences for different regions of the tree as well as the inherent variability in the 16S gene between different species will determine the definitiveness of a taxonomic annotation. Given the topological nature of a phylogenetic tree and the fact that tree represents hierarchical relationships of OTUs to one another based on their sequence similarity and an underlying evolutionary model, taxonomic annotations of a read can be rolled up to a higher level using a clade-based assignment procedure. Using this approach, clades are defined based on the topology of a phylogenetic tree that is constructed from full-length 16S sequences using maximum likelihood or other phylogenetic models familiar to individuals with ordinary skill in the art of phylogenetics. Clades are constructed to ensure that all OTUs in a given clade are: (i) within a specified number of bootstrap supported nodes from one another (generally, 1-5 bootstraps), and (ii) share a defined percent similarity (for 16S molecular data typically set to 95%-97% sequence similarity). OTUs that are within the same clade can be distinguished as genetically and phylogenetically distinct from OTUs in a different clade based on 16S-V4 sequence data. OTUs falling within the same clade are evolutionarily closely related and may or may not be distinguishable from one another using 16S-V4 sequence data. The power of clade based analysis is that members of the same clade, due to their evolutionary relatedness, are likely to play similar functional roles in a microbial ecology such as that found in the human gut. Compositions substituting one species with another from the same clade are likely to have conserved ecological function and therefore are useful in the present invention. Notably in addition to 16S-V4 sequences, clade-based analysis can be used to analyze 18S, ITS, and other genetic sequences.

[0274] Notably, 16S sequences of isolates of a given OTU are phylogenetically placed within their respective clades, sometimes in conflict with the microbiological-based assignment of species and

genus that may have preceded 16S-based assignment. Discrepancies between taxonomic assignment based on microbiological characteristics versus genetic sequencing are known to exist from the literature.

[0275] For a given network ecology or functional network ecology one can define a set of OTUs from the network's representative clades. As example, if a network was comprised of clade_100 and clade_102 it can be said to be comprised of at least one OTU from the group consisting of Corynebacterium coyleae, Corynebacterium mucifaciens, and Corynebacterium ureicelerivorans, and at least one OTU from the group consisting of Corynebacterium appendicis, Corynebacterium genitalium, Corynebacterium glaucum, Corynebacterium imitans, Corynebacterium riegelii, Corynebacterium sp. L_2012475, Corynebacterium sp. NML 93_0481, Corynebacterium sundsvallense, and Corynebacterium tuscaniae (see Table 1). Conversely as example, if a network was said to consist of Corynebacterium coyleae and/or Corynebacterium mucifaciens and/or Corynebacterium ureicelerivorans, and also consisted of Corynebacterium appendicis and/or Corynebacterium genitalium and/or Corynebacterium glaucum and/or Corynebacterium imitans and/or Corynebacterium riegelii and/or Corynebacterium sp. L_2012475 and/or Corynebacterium sp. NML 93_0481 and/or Corynebacterium sundsvallense and/or Corynebacterium tuscaniae it can be said to be comprised of clade_100 and clade_102.

[0276] The applicants made clade assignments to all OTUs reported in the application using the above described method and these assignments are reported in Table 1. In some embodiments, the network analysis permits substitutions of clade_172 by clade_172i. In another embodiment, the network analysis permits substitutions of clade_198 by clade_198i. In another embodiment, the network analysis permits substitutions of clade_260 by clade_260c, clade_260g or clade_260h. In another embodiment, the network analysis permits substitutions of clade_262 by clade_262i. In another embodiment, the network analysis permits substitutions of clade_309 by clade_309c, clade_309e, clade_309g, clade_309h or clade_309i. In another embodiment, the network analysis permits substitutions of clade_313 by clade_313f. In another embodiment, the network analysis permits substitutions of clade_325 by clade_325f. In another embodiment, the network analysis permits substitutions of clade_335 by clade_335i. In another embodiment, the network analysis permits substitutions of clade_351 by clade_351e. In another embodiment, the network analysis permits substitutions of clade_354 by clade_354e. In another embodiment, the network analysis permits substitutions of clade_360 by clade_360c, clade_360g, clade_360h, or clade_360i. In another embodiment, the network analysis permits substitutions of clade_378 by clade_378e. In another embodiment, the network analysis permits substitutions of clade_38 by clade_38e or clade_38i. In another embodiment, the network analysis permits substitutions of clade_408 by clade_408b, clade_408d, clade_408f, clade_408g or clade_408h. In another embodiment, the network analysis permits substitutions of clade_420 by clade_420f. In another embodiment, the network analysis permits substitutions of clade_444 by clade_444i. In another embodiment, the

network analysis permits substitutions of clade_478 by clade_478i. In another embodiment, the network analysis permits substitutions of clade_479 by clade_479c, by clade_479g or by clade_479h. In another embodiment, the network analysis permits substitutions of clade_481 by clade_481a, clade_481b, clade_481e, clade_481g, clade_481h or by clade_481i. In another embodiment, the network analysis permits the network analysis permits substitutions of clade_497 by clade_497e or by clade_497f. In another embodiment, the network analysis permits the network analysis permits substitutions of clade_512 by clade_512i. In another embodiment, the network analysis permits the network analysis permits substitutions of clade_516 by clade_516c, by clade_516g or by clade_516h. In another embodiment, the network analysis permits the network analysis permits substitutions of clade_522 by clade_522i. In another embodiment, the network analysis permits the network analysis permits substitutions of clade_553 by clade_553i. In another embodiment, the network analysis permits the network analysis permits substitutions of clade_566 by clade_566f. In another embodiment, the network analysis permits the network analysis permits substitutions of clade_572 by clade_572i. In another embodiment, the network analysis permits the network analysis permits substitutions of clade_65 by clade_65e. In another embodiment, the network analysis permits the network analysis permits substitutions of clade_92 by clade_92e or by clade_92i. In another embodiment, the network analysis permits the network analysis permits substitutions of clade_96 by clade_96g or by clade_96h. In another embodiment, the network analysis permits the network analysis permits substitutions of clade_98 by clade_98i. These permitted clade substitutions are described in Table 22.

Metagenomic Read Annotation

[0277] Metagenomic or whole genome shotgun sequence data is annotated as described above, with the additional step that sequences are either clustered or assembled prior to annotation. Following sequence characterization as described above, sequence reads are demultiplexed using the indexing (*i.e.* barcodes). Following demultiplexing sequence reads are either: (i) clustered using a rapid clustering algorithm such as but not limited to UCLUST (http://drive5.com/usearch/manual/uclust_algo.html) or hash methods such VICUNA (Xiao Yang, Patrick Charlebois, Sante Gnerre, Matthew G Coole, Niall J. Lennon, Joshua Z. Levin, James Qu, Elizabeth M. Ryan, Michael C. Zody, and Matthew R. Henn. 2012. De novo assembly of highly diverse viral populations. BMC Genomics 13:475). Following clustering a representative read for each cluster is identified based and analyzed as described above in "Primary Read Annotation". The result of the primary annotation is then applied to all reads in a given cluster. (ii) A second strategy for metagenomic sequence analysis is genome assembly followed by annotation of genomic assemblies using a platform such as but not limited to MetAMOS (TJ. Treangen et al. 2013 Genome Biology 14:R2), HUMAaN (Abubucker S, Segata N, Goll J, Schubert AM, Izard J, Cantarel BL, Rodriguez-Mueller B, Zucker J, Thiagarajan M, Henrissat B, et al. 2012. Metabolic Reconstruction

for Metagenomic Data and Its Application to the Human Microbiome ed. J.A. Eisen. PLoS Computational Biology 8: e1002358) and other methods familiar to one with ordinary skill in the art.

Example 3. OTU Identification Using Microbial Culturing Techniques

[0278] The identity of the bacterial species which grow up from a complex fraction can be determined in multiple ways. First, individual colonies are picked into liquid media in a 96 well format, grown up and saved as 15% glycerol stocks at -80°C. Aliquots of the cultures are placed into cell lysis buffer and colony PCR methods can be used to amplify and sequence the 16S rDNA gene (Example 1). Alternatively, colonies are streaked to purity in several passages on solid media. Well separated colonies are streaked onto the fresh plates of the same kind and incubated for 48-72 hours at 37°C. The process is repeated multiple times in order to ensure purity. Pure cultures are analyzed by phenotypic- or sequence-based methods, including 16S rDNA amplification and sequencing as described in Example 1. Sequence characterization of pure isolates or mixed communities *e.g.* plate scrapes and spore fractions can also include whole genome shotgun sequencing. The latter is valuable to determine the presence of genes associated with sporulation, antibiotic resistance, pathogenicity, and virulence. Colonies are also scraped from plates en masse and sequenced using a massively parallel sequencing method as described in Example 1, such that individual 16S signatures can be identified in a complex mixture. Optionally, the sample can be sequenced prior to germination (if appropriate DNA isolation procedures are used to lsye and release the DNA from spores) in order to compare the diversity of germinable species with the total number of species in a spore sample. As an alternative or complementary approach to 16S analysis, MALDI-TOF-mass spec is used for species identification (Barreau M, Pagnier I, La Scola B. 2013. Improving the identification of anaerobes in the clinical microbiology laboratory through MALDI-TOF mass spectrometry. Anaerobe 22: 123–125).

Example 4. Microbiological Strain Identification Approaches

[0279] Pure bacterial isolates are identified using microbiological methods as described in Wadsworth-KTL Anaerobic Microbiology Manual (Jousimies-Somer H, Summanen PH, Citron D, Baron E, Wexler HM, Finegold SM. 2002. Wadsworth-KTL Anaerobic Bacteriology Manual), and The Manual of Clinical Microbiology (ASM Press, 10th Edition). These methods rely on phenotypes of strains and include Gram-staining to confirm Gram positive or negative staining behavior of the cell envelope, observance of colony morphologies on solid media, motility, cell morphology observed microscopically at 60x or 100x magnification including the presence of bacterial endospores and flagella. Biochemical tests that discriminate between genera and species are performed using appropriate selective and differential agars and/or commercially available kits for identification of Gram negative and Gram positive bacteria and yeast, for example, RapID tests (Remel) or API tests (bioMerieux). Similar identification tests can also be performed using instrumentation such as the Vitek 2 system (bioMerieux). Phenotypic tests that discriminate between genera and species and strains (for example the ability to use various carbon and nitrogen sources) can also be performed

using growth and metabolic activity detection methods, for example the Biolog Microbial identification microplates. The profile of short chain fatty acid production during fermentation of particular carbon sources can also be used as a way to discriminate between species (Wadsworth-KTL Anaerobic Microbiology Manual, Jousimies-Somer, et al 2002). MALDI-TOF-mass spectrometry can also be used for species identification (as reviewed in Anaerobe 22:123).

Example 5. Computational Prediction of Network Ecologies

[0280] Source data comprising a genomic-based characterization of a microbiome of individual samples were used as input computationally delineate network ecologies that would have biological properties that are characteristic of a state of health and could catalzye a shift from a state of microbial dysbiosis to a state of health. Applicants obtained 16S and metagenomic sequence datasets from public data repositories (see *e.g.* The Human Microbiome Project Consortium. 2012. Structure, function and diversity of the healthy human microbiome. Nature 486: 207–214. Data accessible at URL: hmpdacc.org) and MetaHit Project (Arumugam M, Raes J, Pelletier E, Paslier DL, Yamada T, Mende DR, Fernandes GR, Tap J, Bruls T, Batto J-M, et al. 2011. Enterotypes of the human gut microbiome. Nature 473: 174–180. Data accessible at URL: metahit.eu) for relevant microbiome studies in multiple disease indications including CDAD, Type 2 Diabetes, Ulcerative Colitis, and Irritable Bowel Disease, or generated data sets from samples directly using the methods described in Examples 1 & 2 and further described in the literature (see *e.g.* Aagaard K, Riehle K, Ma J, Segata N, Mistretta T-A, Coarfa C, Raza S, Rosenbaum S, Van den Veyver I, Milosavljevic A, et al. 2012. A Metagenomic Approach to Characterization of the Vaginal Microbiome Signature in Pregnancy ed. A.J. Ratner. PLoS ONE 7: e36466. Jumpstart Consortium Human Microbiome Project Data Generation Working Group. 2012. Evaluation of 16S rDNA-Based Community Profiling for Human Microbiome Research ed. J. Ravel. PLoS ONE 7: e39315. The Human Microbiome Project Consortium. 2012. Structure, function and diversity of the healthy human microbiome. Nature 486: 207–214.). Nucleic acid sequences were analyzed and taxonomic and phylogenetic assignments of specific OTUs were made using sequence similarity and phylogenetic methods that are well known to those skilled in the art, including but not limited to maximum likelihood phylogenetic reconstruction (see *e.g.* Liu K, Linder CR, and Warnow T. 2011. RAxML and FastTree: Comparing Two Methods for Large-Scale Maximum Likelihood Phylogeny Estimation. PLoS ONE 6: e27731. McGuire G, Denham MC, and Balding DJ. 2001. Models of sequence evolution for DNA sequences containing gaps. Mol. Biol. Evol 18: 481–490. Wróbel B. 2008. Statistical measures of uncertainty for branches in phylogenetic trees inferred from molecular sequences by using model-based methods. J. Appl. Genet. 49: 49–67.) From these taxonomic assignments OTUs and clades in the dataset were defined using the method described in Examples 1 and 2. The certainty of the OTU call was defined based on the OTU's sequence similarity to a reference nucleic acid sequence and the proximity of the OTU sequence relative to one or more reference sequences in the phylogeny. The specificity of an OTU's taxonomic and phlylogenetic assignment determines whether the match is assigned at the level of

Family, Genus, Species, or Strain, and the confidence of this assignment is determined based on the position of bootstrap supported branches in the reference phylogenetic tree relative to the placement of the OTU sequence being interrogated. In addition, microbial OTU assignments may be obtained from assignments made in peer-reviewed publications.

[0281] Applicants designated individual subject samples to biologically relevant sample phenotypes such as but not limited to "healthy state," "recurrent Clostridium difficile infection," "Crohn's disease," "Insulin Resistance," "Obesity," "Type 2 diabetes," "Ulcerative Colitis". In one embodiment samples are assigned to "health" and "disease" phenotypes. In another embodiment, samples are assigned higher resolution phenotype such as but not limited to: "health:human", "health:mouse", "health:human microbiome project", "health:microbiota donor", "health:microbiota recipient", "disease:microbiota recipient", or "disease:no treatment", "disease:human", or "disease:mouse". In another embodiment, samples where assigned to higher resolution phenotypes, such as but not limited to those defined in Figure 19 that characterize phenotypes specific to samples from fecal donors and patients who received a fecal microbial transplant from these donors. Figure 19 shows phenotypes assigned to samples for the computational derivation of Network Ecologies that typify microbiome states of health (Hpost, Hdon, & Hgen) and states of disease (DdonF & DpreF).

[0282] In another embodiment, other phenotypes that define a category of disease or health that represents the underlying state of the population under study can be used. Applicants then computationally determined the microbial network ecologies for each phenotype using the OTU and clade assignments that comprise the microbial profile for each sample and the algorithms described above in the Section entitled "Method of Determining Network Ecologies."

[0283] Tables 8, 11, and 14a below provide exemplary network ecologies that define states of health as compared to states of dysbiosis or disease for multiple disease indications. The disease indications for which the network ecologies represent a health state are denoted in Table 8, and Keystone and Non-Keystone OTUs (see Example 6) are delineated in Tables 9-10. Importantly, Network Ecologies that represent a state of health in one disease indication can represent states of health in additional disease states. Additionally, Keystone OTUs found in a network associated with health for different disease indications can overlap. Applicants found that a large number of network ecologies overlapped particularly between those associated with health in the cases of CDAD and Type 2 Diabetes despite the analysis of substantially different genomic data sets for the two diseases.

Example 6. Identification of Network Classes, Keystone OTUs, Clades, and Functional Modalities

Identification of Keystone OTUs, Clades and Functions

[0284] The human body is an ecosystem in which the microbiota and the microbiome play a significant role in the basic healthy function of human systems (*e.g.* metabolic, immunological, and neurological). The microbiota and resulting microbiome comprise an ecology of microorganisms that

co-exist within single subjects interacting with one another and their host (*i.e.*, the mammalian subject) to form a dynamic unit with inherent biodiversity and functional characteristics. Within these networks of interacting microbes (*i.e.* ecologies), particular members can contribute more significantly than others; as such these members are also found in many different ecologies, and the loss of these microbes from the ecology can have a significant impact on the functional capabilities of the specific ecology. Robert Paine coined the concept "Keystone Species" in 1969 (see Paine RT. 1969. A note on trophic complexity and community stability. The American Naturalist 103: 91–93) to describe the existence of such lynchpin species that are integral to a given ecosystem regardless of their abundance in the ecological community. Paine originally describe the role of the starfish Pisaster ochraceus in marine systems and since the concept has been experimentally validated in numerous ecosystems.

[0285] Keystone OTUs (as shown in Table 9), Phylogenetic Clades (a.k.a. Clades), and/or Functions (for example, but not limited to, KEGG Orthology Pathways) are computationally-derived by analysis of network ecologies elucidated from a defined set of samples that share a specific phenotype. Keystone OTUs, Clades and/or Functions are defined as all Nodes within a defined set of networks that meet two or more of the following criteria. Using Criterion 1, the node is frequently observed in networks, and the networks in which the node is observed are found in a large number of individual subjects; the frequency of occurrence of these Nodes in networks and the pervasiveness of the networks in individuals indicates these Nodes perform an important biological function in many individuals. Using Criterion 2, the node is frequently observed in networks, and the Node is observed contains a large number of edges connecting it to other nodes in the network. These Nodes are thus "super-connectors", meaning that they form a nucleus of a majority of networks (See Figure 17) and as such have high biological significance with respect to their functional contributions to a given ecology.

[0286] Figure 17 is a schematic representation of how Keystone OTUs (nodes 2 and 4, shaded circles) are central members of many network ecologies that contain non-Keystone OTUs (nodes 1, 3, and 5-9). Distinct network ecologies include [node 2--node 7], [node--3--node 2--node--4], [node 2--node 4--node 5--node 6--node 7], [node 1--node 2--node 8--node 9], and [node --node 3].

[0287] Using Criterion 3, the Node is found in networks containing a large number of Nodes (*i.e.*, they are large networks), and the networks in which the Node is found occur in a large number of subjects; these networks are potentially of high interest as it is unlikely that large networks occurring in many individuals would occur by chance alone strongly suggesting biological relevance. Optionally, the required thresholds for the frequency at which a Node is observed in network ecologies, the frequency at which a given network is observed across subject samples, and the size of a given network to be considered a Keystone Node are defined by the 50th, 70th, 80th, or 90th percentiles of the distribution of these variables. Optionally, the required thresholds are defined by

the value for a given variable that is significantly different from the mean or median value for a given variable using standard parametric or non-parametric measures of statistical significance. In another embodiment a Keystone Node is defined as one that occurs in a sample phenotype of interest such as but not limited to "health" and simultaneously does not occur in a sample phenotype that is not of interest such as but not limited to "disease." Optionally, a Keystone Node is defined as one that is shown to be significantly different from what is observed using permuted test datasets to measure significance. In another embodiment of Criterion 2 Keystone OTUs, Clades, or Functions can be defined using a hierarchical clustering method that clusters Networks based on their OTU, Clade, or functional pathways. Statistically significant branch points in the hierarchy are defined based on the topological overlap measure; this measure is a highly robust measure of network interconnectedness (Langfelder P, Zhang B, Horvath S. 2008. Defining clusters from a hierarchical cluster tree: the Dynamic Tree Cut package for R. Bioinformatics 24: 719–720.). Once these branch points are defined the Keystones are delineated as OTUs, clades or functional pathways that are found consistently across all networks in all or a subset of the network clusters.

[0288] Applicants defined the Keystone OTUs and Clades characteristic of health states for the computationally determined networks reported in Table 8 for the various disease indications analyszed using the three criterion defined above. Keystone Clades were defined from the Keystone OTUs using clade definitions as outlined in Example 1. Keystone OTUs are reported in Table 9. Importantly, we identified the absence of Keystone OTUs in multiple particular disease states, indicating that bacterial compositions comprised of specific sets of Keystone OTUs are likely to have utility in multiple disease indications.

Demonstration that Keystone OTUs inhibit *C. difficile* Growth in a Competitive In Vitro Simulation Assay

[0289] To screen the ability of binary combinations comprising at least one Keystone OTU (binary pairs) to inhibit the growth of Clostridium difficile in vitro, vials of -80 °C glycerol stock banks of each OTU were thawed and diluted to 1e8 CFU/mL. Each strain was then diluted 10x (to a final concentration of 1e7 CFU/mL of each strain) into 200 uL of PBS + 15% glycerol in the wells of a 96-well plate. Plates were then frozen at -80 °C. When needed for the assay, plates were removed from -80 °C and thawed at room temperature under anaerobic conditions prior to use.

[0290] An overnight culture of Clostridium difficile was grown under anaerobic conditions in SweetB-FosIn or other suitable media for the growth of C. difficile. SweetB-FosIn is a complex media composed of brain heart infusion, yeast extract, cysteine, cellobiose, maltose, soluble starch, and fructooligosaccharides/inulin, and hemin, and is buffered with morpholino-propane sulphonic acid (MOPS). After 24 hr of growth the culture was diluted 100,000 fold into SweetB-FosIn. The diluted C. difficile mixture was then aliquoted to wells of a 96-well plate (180 uL to each well). 20 uL of a unique binary pair of Keystone OTUs was then added to each well at a final concentration of 1e6

CFU/mL of each species. Alternatively the assay can be tested with binary pairs at different initial concentrations (1e9 CFU/mL, 1e8 CFU/mL, 1e7 CFU/mL, 1e5 CFU/mL, 1e4 CFU/mL, 1e3 CFU/mL, 1e2 CFU/mL). Control wells only inoculated with C. difficile were included for a comparison to the growth of C. difficile without inhibition. Additional wells were used for controls that either inhibit or do not inhibit the growth of C. difficile. Plates were wrapped with parafilm and incubated for 24 hr at 37 °C under anaerobic conditions. After 24 hr the wells containing C. difficile alone were serially diluted and plated to determine titer on selective media such as CCFA (Anaerobe Systems) or CDSA (Becton Dickinson). The 96-well plate was then frozen at -80°C before quantifying C. difficile by qPCR.

[0291] C. difficile in each well was quantified by qPCR. A standard curve was generated from a well on each assay plate containing only pathogenic C. difficile grown in SweetB + FosIn media as provided herein and compare to the microbiological titer determined above. Genomic DNA was extracted from the standard curve samples along with the other wells. Genomic DNA was extracted from 5 µl of each sample using a dilution, freeze/thaw, and heat lysis protocol. 5 µL of thawed samples were added to 45 µL of UltraPure water (Life Technologies, Carlsbad, CA) and mixed by pipetting. The plates with diluted samples were frozen at -20°C until use for qPCR which includes a heated lysis step prior to amplification. Alternatively the genomic DNA could be isolated using the Mo Bio Powersoil®-htp 96 Well Soil DNA Isolation Kit (Mo Bio Laboratories, Carlsbad, CA), Mo Bio Powersoil® DNA Isolation Kit (Mo Bio Laboratories, Carlsbad, CA), or the QIAamp DNA Stool Mini Kit (QIAGEN, Valencia, CA) according to the manufacturer's instructions.

[0292] The qPCR reaction mixture contained 1x SsoAdvanced Universal Probes Supermix, 900 nM of Wr-tcdB-F primer (AGCAGTTGAATATAGTGGTTTAGTTAGAGTTG, IDT, Coralville, IA), 900 nM of Wr-tcdB-R primer (CATGCTTTTTTAGTTTCTGGATTGAA, IDT, Coralville, IA), 250 nM of Wr-tcdB-P probe (6FAM-CATCCAGTCTCAATTGTATATGTTTCTCCA-MGB, Life Technologies, Grand Island, NY), and Molecular Biology Grade Water (Mo Bio Laboratories, Carlsbad, CA) to 18 µl (Primers adapted from: Wroblewski, D. et al., Rapid Molecular Characterization of Clostridium difficile and Assessment of Populations of C. difficile in Stool Specimens, Journal of Clinical Microbiology 47:2142–2148 (2009)). This reaction mixture was aliquoted to wells of a Hard-shell Low-Profile Thin Wall 96-well Skirted PCR Plate (BioRad, Hercules, CA). To this reaction mixture, 2 µl of diluted, frozen, and thawed samples were added and the plate sealed with a Microseal 'B' Adhesive Seal (BioRad, Hercules, CA). The qPCR was performed on a BioRad C1000™ Thermal Cycler equipped with a CFX96™ Real-Time System (BioRad, Hercules, CA). The thermocycling conditions were 95°C for 15 minutes followed by 45 cycles of 95°C for 5 seconds, 60°C for 30 seconds, and fluorescent readings of the FAM channel. Alternatively, the qPCR could be performed with other standard methods known to those skilled in the art.

[0293] The Cq value for each well on the FAM channel was determined by the CFX Manager™ 3.0 software. The log10(cfu/mL) of C. difficile each experimental sample was calculated by inputting a given sample's Cq value into a linear regression model generated from the standard curve comparing the Cq values of the standard curve wells to the known log10(cfu/mL) of those samples. The log inhibition was calculated for each sample by subtracting the log10(cfu/mL) of C. difficile in the sample from the log10(cfu/mL) of C. difficile in the sample on each assay plate used for the generation of the standard curve that has no additional bacteria added. The mean log inhibition was calculated for all replicates for each composition.

[0294] A histogram of the range and standard deviation of each composition was plotted. Ranges or standard deviations of the log inhibitions that were distinct from the overall distribution were examined as possible outliers. If the removal of a single log inhibition datum from one of the binary pairs that were identified in the histograms would bring the range or standard deviation in line with those from the majority of the samples, that datum was removed as an outlier, and the mean log inhibition was recalculated.

[0295] The pooled variance of all samples evaluated in the assay was estimated as the average of the sample variances weighted by the sample's degrees of freedom. The pooled standard error was then calculated as the square root of the pooled variance divided by the square root of the number of samples. Confidence intervals for the null hypothesis were determined by multiplying the pooled standard error to the z score corresponding to a given percentage threshold. Mean log inhibitions outside the confidence interval were considered to be inhibitory if positive or stimulatory if negative with the percent confidence corresponding to the interval used. Samples with mean log inhibition greater than the 99% confidence interval (C.I) of the null hypothesis are reported as ++++, those with a 95% < C.I. <99% as +++, those with a 90% < C.I. <95% as ++, those with a 80% < C.I. <90% as + while samples with mean log inhibition less than than the 99% confidence interval (C.I) of the null hypothesis are reported as ----, those with a 95% < C.I. <99% as ---, those with a 90% < C.I. <95% as --, those with a 80% < C.I. <90% as -. Many binary pairs comprising Keystone OTUs inhibit C. difficile as delineated in Table 20.

Assignment of a Network Classes Based On Phylogenetic Diversity and Functional Modalities

[0296] "Network Classes" can be delineated by clustering computationally determined network ecologies into groupings based on the OTUs observed in a given network. In one example, OTUs are treated individualistically with each OTU representing a unique entity within the network. In other examples, the OTUs are clustered according to their phylogenetic relationships defined by a phylogenetic tree, e.g., into clades. In yet another embodiment, functional modules such as but not limited to KEGG Orthology Pathways can be used to cluster the networks, OTUs and Clades according to the biological or biochemical functions they comprise. . A set of ecological networks

from which a Network Class is defined, is selected using one or a combination of the following criteria: (i) networks that are derived from a biological phenotype, (ii) the frequency at which a given network is observed across samples, or (iii) the size of the network. In one embodiment, the required thresholds for the frequency at which a given network is observed across subject samples, and the size of a given network to be considered for further analysis are defined by the 50^{th}, 70^{th}, 80^{th}, or 90^{th} percentiles of the distribution of these variables. In another embodiment, the required thresholds are defined by the value for a given variable that is significantly different from the mean or median value for a given variable using standard parametric or non-parametric measures of statistical significance. In yet another embodiment, ecological networks derived from Network Classes are selected that contain 5 or fewer, 10 or fewer, 15 or fewer, 20 or fewer, 25 or fewer, or 50 or fewer OTUs, Clades, or Functional modalities.

[0297] Network Class ecologies are defined using a heatmap analytical strategy whereby the OTU content of a given network is mapped relative to the networks in which it exists (See, *e.g.*, Figure 18). Figure 18 is a Derivation of Network Ecology Classes, according to an embodiment of the invention. Subsets of networks are selected for use in defining Network Classes based on key biological criteria. Hierarchical Network clusters are defined by the presence (white) and absence (blue (or dark color)) of OTUs and/or Functional Metabolic Pathways and Classes are defined as branches of the hierarchical clustering tree based on the topological overlap measure.

[0298] Both OTUs comprising the network ecologies and the network ecologies themselves are ordered using a dendrogram that represents the relatedness of each OTU to every other OTU, or each Network Ecology to every other Network Ecology. The dendrogram for OTUs can be constructed using various clustering algorithms including but not limited to phylogenetic maximum likelihood, hierarchical clustering, or k-means clustering. In one embodiment, each row in the heatmap represents a single OTU, each column represents a Network Ecology and the color in the heatmap at a given row/column intersection represents whether the given OTU is present or absent in the given network. In another embodiment, the color in the heatmap represents the summed number of occurrences of the OTU in a set of related networks, represented as a cluster in the dendrogram of network ecologies. In another embodiment, the row and column intersections represent a summary variable calculated from the collapse of multiple rows and/or columns at selected nodes in the dendrograms. Network Classes are defined finding significant branch points in the hierarchical dendrogram. In one embodiment these branch points are defined as branches of the hierarchical clustering tree based on the topological overlap measure; this measure is a highly robust measure of network interconnectedness (Langfelder P, Zhang B, Horvath S. 2008. Defining clusters from a hierarchical cluster tree: the Dynamic Tree Cut package for R. Bioinformatics 24: 719–720.). Network Classes are defined based on OTU presence/absence or presence/absence and frequency patterns in network clusters; these patterns can be defined using specific OTUs, taxonomic groupings, or phylogenetic clades defined by the phylogenetically derived dendrogram (*i.e.* phylogenetic tree).

Network Classes can be defined with the intent of maximizing the phylogenetic diversity of the class, and/or representing specific regions of functional relevance on the phylogenetic tree.
We defined a set of Network Classes for the Network Ecologies reported in Table 8 that were computationally inferred from health and disease datasets tied to CDAD studies using the method described above. We defined six Network Classes for these network ecologies (Figure 18 and Tables 12-13).

Example 7. Biologically-Informed Optimization of Network Ecologies Based on Biological Properties

[0299] Network Ecologies can be optimized to have specific biological properties including but not limited to being of specific size (as example a specific number or OTUs); having a frequency of being observed in a population of healthy individuals (*i.e.* pervasiveness); having a certain percentage of spore forming OTUs as constituents; having a certain percentage of Keystone OTUs, clades or functions; having a defined phylogenetic breadth (as example defined by the total evolutionary distance spanned on a tree by the constituent members, or by the total number of genera or other taxonomic unit); or comprising specific functional capabilities such as but not limited to the ability metabolize secondary bile acids, or produce short chain fatty acids (SCFAs), or the biological intersection in which network ecology falls in a comparative phenotype map (see Figure 19). The constituents of a network ecology can be optimized using both computational means as well as experimental means.

[0300] In one embodiment, we developed a biopriority score for networks that was computationally derived. This algorithm took the form of [F1 * W1] + [F2 * W2] + [F3 * W3] + [F4 * W4] where F is a biological criteria of interest and W is a weighting for that factor based on its importance to the derivation of the target network ecology. As example, if having a network with phylogenetic breadth was important one would weight this factor greater than the other factors. We developed a biopriority score that took into consideration the biological intersection of the network (Figure 19), phylogenetic breadth, the pervasiveness or prevalence of the network in populations of healthy individuals, and the percentage of OTUs in the network that were Keystone OTUs. Network Ecologies reported in Table 8 were ranked based on this scoring and networks with a high score were preferentially screened and in vivo mouse model of C. difficile infection (Table 16).

[0301] In another embodiment we used a phylogenetic method paired with empirical testing to optimize the network ecologies for efficacy for the treatment of CDAD. Based on computational insights from our network analysis (Table 8), applicants defined Keystone Clades that represent specific phylogenetic clusters of OTUs. Applicants constructed various bacterial compositions using the methods described in Example 9 below, whereby applicants varied the phylogenetic breadth of the network ecologies based on the inclusion or exclusion of OTUs from specific clades. To test the effect of these variations on efficacy, 11 networks that feature clade

substitutions, additions, or subtractions were tested at the same target dose of 1e7 CFU per OTU per animal in the mouse model of C. difficile infection experiment SP-376 (see Example 13 and Table 16). Figure 3 provides an overview of the various clade substitutions or removals

[0302] The removal of clades 494 & 537 and the addition of clade 444 from network N1962, which was highly efficacious in protecting from symptoms of C. difficile infection with no mortality, yields network N1991, which was still largely protective of weight loss, but had increased mean maximum clinical scores relative to N1962.

[0303] N1990 adds clades 444 & 478 to N1962, and resulted in decreased mean minimum relative weight and increased mean maximum clinical scores relative to N1962 while remaining efficacious relative to the experiment's vehicle control.

[0304] Removal of clades 252 & 253 and the addition of clades 444 & 478 from N1962 produces N1975, which has increased mortality, decreased mean minimum relative weight and increased mean maximum clinical scores relative to N1962, which is only slightly less efficacious than the vehicle control.

[0305] The optimization of network ecologies to design microbiome therapeutics (as example a composition comprised of bacterial OTUs) with particular biological properties and features is executed using the strategy of having a core Backbone Network Ecology onto which R-Groups are added or subtracted to design toward particular characteristics. The Backbone forms a foundational composition of organisms or functions that are core to efficacy and need be present to observe efficacy. On this backbone one can make various compositional modifications using R-groups. R-Groups can be defined in multiple terms including but not limited to: individual OTUs, individual or multiple OTUs derived from a specific phylogenetic clade, and functional modalities comprised of multiple functional pathways and/or specific metabolic pathways. In other embodiments, R-groups could be considered prebiotics and other co-factors that are design into, or administered with a network ecology to promote specific biological properties.

Example 8. Network Analysis Across Multiple Data Sets and Selection of Target Network Ecologies with Capacity to Sporulate

[0306] One can select Network Ecologies and/or Network Class Ecologies as lead targets by defining networks with a specific biological function or activity such as sporulation. Networks Ecologies or Network Class Ecologies are first selected as described above and in Example 5 and 6. In one example, all Network Ecologies or Network Class Ecologies that contain at least one OTU that is capable of forming spores are targeted. In another example, all Network Ecologies or Network Class Ecologies that contain at least one OTU that is capable of forming spores, and that are comprised of at least 50%, 75%, or 100% Keystone OTUs are targeted. Keystone OTUs are selected as described above and in Example 6. OTUs are defined as spore formers using either phenotypic assays (see *e.g.* Stackebrandt and Hippe. Taxonomy and Systematics. In Clostridia. Biotechnology

and Medical Applications.) or genetic assays (see *e.g.* Abecasis AB, Serrano M, Alves R, Quintais L, Pereira-Leal JB, and Henriques AO. 2013. A genomic signature and the identification of new sporulation genes. J. Bacteriol.; Paredes-Sabja D, Setlow P, and Sarker MR. 2011. Germination of spores of Bacillales and Clostridiales species: mechanisms and proteins involved. Trends Microbiol. 19: 85–94). Exemplary network ecologies that are comprised of spore formers are illustrated in Table11.

Example 9. Construction of Defined Ecobiotic Compositions

[0307] Source of Microbial Cultures. Pure cultures of organisms are isolated from the stool, oral cavity or other niche of the body of clinically qualified donors (as in Example 10) that contains microorganisms of interest using microbiological methods including those described below, and as are known to those skilled in the art. Alternatively, pure cultures are sourced from repositories such as the ATCC (www.atcc.org) or the DSMZ (https://www.dsmz.de/) which preserve and distribute cultures of bacteria, yeasts, phages, cell lines and other biological materials.

[0308] Enrichment and Purification of Bacteria. To purify individual bacterial strains, dilution plates were selected in which the density enables distinct separation of single colonies. Colonies were picked with a sterile implement (either a sterile loop or toothpick) and re-streaked to BBA or other solid media. Plates were incubated at 37°C for 3-7 days. One or more well-isolated single colonies of the major morphology type were re-streaked. This process was repeated at least three times until a single, stable colony morphology is observed. The isolated microbe was then cultured anaerobically in liquid media for 24 hours or longer to obtain a pure culture of 106-1010 cfu/ml. Liquid growth medium might include Brain Heart Infusion-based medium (Atlas, Handbook of Microbiological Media, 4th ed, ASM Press, 2010) supplemented with yeast extract, hemin, cysteine, and carbohydrates (for example, maltose, cellobiose, soluble starch) or other media described previously. The culture was centrifuged at 10,000 x g for 5 min to pellet the bacteria, the spent culture media was removed, and the bacteria were resuspended in sterile PBS. Sterile 75% glycerol was added to a final concentration of 20%. An aliquot of glycerol stock was titered by serial dilution and plating. The remainder of the stock was frozen on dry ice for 10-15 min and then placed at -80°C for long term storage.

Cell Bank Preparation

[0309] Cell banks (RCBs) of bacterial strains were prepared as follows. Bacterial strains were struck from -80°C frozen glycerol stocks to Brucella blood agar with Hemin or Vitamin K (Atlas, Handbook of Microbiological Media, 4th ed, ASM Press, 2010), M2GSC (Atlas, Handbook of Microbiological Media, 4th ed, ASM Press, 2010) or other solid growth media and incubated for 24 to 48 h at 37°C in an anaerobic chamber with a gas mixture of H2:CO2:N2 of 10:10:80. Single colonies were then picked and used to inoculate 250 ml to 1 L of Wilkins-Chalgren broth, Brain-Heart Infusion broth, M2GSC broth or other growth media, and grown to mid to late exponential phase or into the

stationary phase of growth. Alternatively, the single colonies may be used to inoculate a pilot culture of 10 ml, which were then used to inoculate a large volume culture. The growth media and the growth phase at harvest were selected to enhance cell titer, sporulation (if desired) and phenotypes that might be associated desired in vitro or in vivo. Optionally, cultures were grown static or shaking, depending which yielded maximal cell titer. The cultures were then concentrated 10 fold or more by centrifugation at 5000 rpm for 20 min, and resuspended in sterile phosphate buffered saline (PBS) plus 15% glycerol. 1 ml aliquots were transferred into 1.8 ml cryovials which were then frozen on dry ice and stored at -80°C. The identity of a given cell bank was confirmed by PCR amplification of the 16S rDNA gene, followed by Sanger direct cycle sequencing. See Examples 1, 2. Each bank was confirmed to yield colonies of a single morphology upon streaking to Brucella blood agar or M2GSC agar. When more than one morphology was observed, colonies were confirmed to be the expected species by PCR and sequencing analysis of the 16S rDNA gene. Variant colony morphologies can be observed within pure cultures, and in a variety of bacteria the mechanisms of varying colony morphologies have been well described (van der Woude, Clinical Microbiology Reviews, 17:518, 2004), including in Clostridium species (Wadsworth-KTL Anaerobic Bacteriology Manual, 6th Ed, Jousimie-Somer, et al 2002). For obligate anaerobes, RCBs were confirmed to lack aerobic colony forming units at a limit of detection of 10 cfu/ml.

Titer Determination

[0310] The number of viable cells per ml was determined on the freshly harvested, washed and concentrated culture by plating serial dilutions of the RCB to Brucella blood agar or other solid media, and varied from 106 to 1010 cfu/ml. The impact of freezing on viability was determined by titering the banks after one or two freeze-thaw cycles on dry ice or at -80°C, followed by thawing in an anaerobic chamber at room temperature. Some strains displayed a 1-3 log drop in viable cfu/ml after the 1st and/or 2nd freeze thaw, while the viability of others were unaffected.

Preparation of Bacterial Compositions

[0311] Individual strains were typically thawed on ice and combined in an anaerobic chamber to create mixtures, followed by a second freeze at -80°C to preserve the mixed samples. When making combinations of strains for in vitro or in vivo assays, the cfu in the final mixture was estimated based on the second freeze-thaw titer of the individual strains. For experiments in rodents, strains may be combined at equal counts in order to deliver between 1e4 and 1e10 per strain. Additionally, some bacteria may not grow to sufficient titer to yield cell banks that allowed the production of compositions where all bacteria were present at 1e10.

Selection of Media for Growth

[0312] Provided are appropriate media to support growth, including preferred carbon sources. For example, some organisms prefer complex sugars such as cellobiose over simple sugars. Examples of media used in the isolation of sporulating organisms include EYA, BHI, BHIS, and GAM (see below

for complete names and references). Multiple dilutions are plated out to ensure that some plates will have well isolated colonies on them for analysis, or alternatively plates with dense colonies may scraped and suspended in PBS to generate a mixed diverse community.

[0313] Plates are incubated anaerobically or aerobically at 37°C for 48-72 or more hours, targeting anaerobic or aerobic spore formers, respectively.

[0314] Solid plate media include:

- Gifu Anaerobic Medium (GAM, Nissui) without dextrose supplemented with fructooligosaccharides/inulin (0.4%), mannitol (0.4%), inulin (0.4%), or fructose (0.4%), or a combination thereof.
- Sweet GAM [Gifu Anaerobic Medium (GAM, Nissui)] modified, supplemented with glucose, cellobiose, maltose, L-arabinose, fructose, fructooligosaccharides/inulin, mannitol and sodium lactate)
- Brucella Blood Agar (BBA, Atlas, Handbook of Microbiological Media, 4th ed, ASM Press, 2010)
- PEA sheep blood (Anaerobe Systems; 5% Sheep Blood Agar with Phenylethyl Alcohol)
- Egg Yolk Agar (EYA) (Atlas, Handbook of Microbiological Media, 4th ed, ASM Press, 2010)
- Sulfite polymyxin milk agar (Mevissen-Verhage et al., J. Clin. Microbiol. 25:285-289 (1987))
- Mucin agar (Derrien et al., IJSEM 54: 1469-1476 (2004))
- Polygalacturonate agar (Jensen & Canale-Parola, Appl. Environ. Microbiol. 52:880-997 (1986))
- M2GSC (Atlas, Handbook of Microbiological Media, 4th ed, ASM Press, 2010)
- M2 agar (Atlas, Handbook of Microbiological Media, 4th ed, ASM Press, 2010) supplemented with starch (1%), mannitol (0.4%), lactate (1.5g/L) or lactose (0.4%)
- Sweet B - Brain Heart Infusion agar (Atlas, Handbook of Microbiological Media, 4th ed, ASM Press, 2010) supplemented with yeast extract (0.5%), hemin, cysteine (0.1%), maltose (0.1%), cellobiose (0.1%), soluble starch (sigma, 1%), MOPS (50mM, pH 7).
- PY-salicin (peptone-yeast extract agar supplemented with salicin) (Atlas, Handbook of Microbiological Media, 4th ed, ASM Press, 2010).
- Modified Brain Heart Infusion (M-BHI) [[sweet and sour]] contains the following per L: 37.5g Brain Heart Infusion powder (Remel), 5g yeast extract, 2.2g meat extract, 1.2g liver extract, 1g cystein HCl, 0.3g sodium thioglycolate, 10mg hemin, 2g soluble starch, 2g FOS/Inulin, 1g cellobiose, 1g L-arabinose, 1g mannitol, 1 Na-lactate, 1mL Tween 80, 0.6g MgSO4x7H2O, 0.6g CaCl2, 6g (NH4)2SO4, 3g KH2PO4, 0.5g K2HPO4, 33mM Acetic acid, 9mM propionic acid, 1mM Isobutyric acid, 1mM isovaleric acid, 15g agar, and after autoclaving add 50mL of 8% NaHCO3 solution and 50mL 1M MOPS-KOH (pH 7).

- Noack-Blaut Eubacterium agar (See Noack et al. J. Nutr. (1998) 128:1385-1391)
- BHIS az1/ge2 - BHIS az/ge agar (Reeves et. al. Infect. Immun. 80:3786-3794 (2012)) [Brain Heart Infusion agar (Atlas, Handbook of Microbiological Media, 4th ed, ASM Press, 2010) supplemented with yeast extract 0.5%, cysteine 0.1%, 0.1% cellobiose, 0.1% inulin, 0.1% maltose, aztreonam 1 mg/L, gentamycin 2 mg/L]
- BHIS CInM az1/ge2- BHIS CInM [Brain Heart Infusion agar (Atlas, Handbook of Microbiological Media, 4th ed, ASM Press, 2010) supplemented with yeast extract 0.5%, cysteine 0.1%, 0.1% cellobiose, 0.1% inulin, 0.1% maltose, aztreonam 1 mg/L, gentamycin 2 mg/L].

Method of Preparing the Bacterial Composition for Administration to a Patient

[0315] Two strains for the bacterial composition are independently cultured and mixed together before administration. Both strains are independently be grown at 37°C, pH 7, in a GMM or other animal-products-free medium, pre-reduced with 1 g/L cysteineŸHCl. After each strain reaches a sufficient biomass, it is preserved for banking by adding 15% glycerol and then frozen at -80°C in 1 ml cryotubes.

[0316] Each strain is then be cultivated to a concentration of 1010 CFU/mL, then concentrated 20-fold by tangential flow microfiltration; the spent medium is exchanged by diafiltering with a preservative medium consisting of 2% gelatin, 100 mM trehalose, and 10 mM sodium phosphate buffer, or other suitable preservative medium. The suspension is freeze-dried to a powder and titrated.

[0317] After drying, the powder is blended with microcrystalline cellulose and magnesium stearate and formulated into a 250 mg gelatin capsule containing 10 mg of lyophilized powder (108 to 1011 bacteria), 160 mg microcrystalline cellulose, 77.5 mg gelatin, and 2.5 mg magnesium stearate.

Example 10. Construction and Administration of an Ethanol-treated spore Preparation

[0318] Provision of fecal material. Fresh fecal samples were obtained from healthy human donors who have been screened for general good health and for the absence of infectious diseases, and meet inclusion and exclusion criteria, inclusion criteria include being in good general health, without significant medical history, physical examination findings, or clinical laboratory abnormalities, regular bowel movements with stool appearance typically Type 2, 3, 4, 5 or 6 on the Bristol Stool Scale, and having a BMI $\geq$ 18 kg/m2 and $\leq$ 25 kg/m2. Exclusion criteria generally included significant chronic or acute medical conditions including renal, hepatic, pulmonary, gastrointestinal, cardiovascular, genitourinary, endocrine, immunologic, metabolic, neurologic or hematological disease, a family history of, inflammatory bowel disease including Crohn's disease and ulcerative colitis, Irritable bowel syndrome, colon, stomach or other gastrointestinal malignancies, or gastrointestinal polyposis syndromes, or recent use of yogurt or commercial probiotic materials in

which an organism(s) is a primary component. Non-related donors were screened for general health history for absence of chronic medical conditions (including inflammatory bowel disease; irritable bowel syndrome; Celiac disease; or any history of gastrointestinal malignancy or polyposis), absence of risk factors for transmissible infections, antibiotic non-use in the previous 6 months, and negative results in laboratory assays for blood-borne pathogens (HIV, HTLV, HCV, HBV, CMV, HAV and Treponema pallidum) and fecal bacterial pathogens (Salmonella, Shigella, Yersinia, Campylobacter, E. coli 0157), ova and parasites, and other infectious agents (Giardia, Cryptosporidium, Cyclospora, Isospora) prior to stool donation. Samples were collected directly using a commode specimen collection system, which contains a plastic support placed on the toilet seat and a collection container that rests on the support. Feces were deposited into the container, and the lid was then placed on the container and sealed tightly. The sample was then delivered on ice within 1-4 hours for processing. Samples were mixed with a sterile disposable tool, and 2-4 g aliquots were weighed and placed into tubes and flash frozen in a dry ice/ethanol bath. Aliquots are frozen at -80 degrees Celsius until use.

[0319] Optionally, the fecal material was suspended in a solution, and/or fibrous and/or particulate materials were removed using either filtration or centrifugation. A frozen aliquot containing a known weight of feces was removed from storage at -80°C and allowed to thaw at room temperature. Sterile 1x PBS was added to create a 10% w/v suspension, and vigorous vortexing was performed to suspend the fecal material until the material appeared homogeneous. The material was then left to sit for 10 minutes at room temperature to sediment fibrous and particulate matter. The suspension above the sediment was then carefully removed into a new tube and contains a purified spore population. Optionally, the suspension was then centrifuged at a low speed, *e.g.*, 1000 x g, for 5 minutes to pellet particulate matter including fibers. The pellet was discarded and the supernatant, which contained vegetative organisms and spores, was removed into a new tube. The supernatant was then centrifuged at 6000 x g for 10 minutes to pellet the vegetative organisms and spores. The pellet was then resuspended in 1x PBS with vigorous vortexing until the material appears homogenous.

Generation of a Spore Preparation From Alcohol Treatment of Fecal Material

[0320] A 10% w/v suspension of human fecal material in PBS was filtered, centrifuged at low speed, and the supernate containing spores was mixed with absolute ethanol in a 1:1 ratio and vortexed to mix. The suspension was incubated at room temperature for 1 hour. After incubation the suspension was centrifuged at high speed to concentrate spores into a pellet containing a purified spore-containing preparation. The supernate was discarded and the pellet resuspended in an equal mass of glycerol, and the purified spore preparation was placed into capsules and stored at -80 degrees Celsius.

Characterization of Spores Content in Purified Spore Populations

[0321] In one embodiment, counts of viable spores are determined by performing 10 fold serial dilutions in PBS and plating to Brucella Blood Agar Petri plates or applicable solid media. Plates are

incubated at 37 degrees Celsius for 2 days. Colonies are counted from a dilution plate with 50-400 colonies and used to back-calculate the number of viable spores in the population. The ability to germinate into vegetative bacteria is also demonstrated. Visual counts are determined by phase contrast microscopy. A spore preparation is either diluted in PBS or concentrated by centrifugation, and a 5 microliter aliquot is placed into a Petroff Hauser counting chamber for visualization at 400x magnification. Spores are counted within ten 0.05 mm x 0.05 mm grids and an average spore count per grid is determined and used to calculate a spore count per ml of preparation. Lipopolysaccharide (LPS) reduction in purified spore populations is measured using a Limulus amebocyte lysate (LAL) assay such as the commercially available ToxinSensor™ Chromogenic LAL Endotoxin Assay Kit (GenScript, Piscataway, NJ) or other standard methods known to those skilled in the art.

[0322] In a second embodiment, counts of spores are determined using a spore germination assay. Germinating a spore fraction increases the number of viable spores that will grow on various media types. To germinate a population of spores, the sample is moved to the anaerobic chamber, resuspended in prereduced PBS, mixed and incubated for 1 hour at 37°C to allow for germination. Germinants can include amino-acids (*e.g.*, alanine, glycine), sugars (*e.g.*, fructose), nucleosides (*e.g.*, inosine), bile salts (*e.g.*, cholate and taurocholate), metal cations (*e.g.*, Mg2+, Ca2+), fatty acids, and long-chain alkyl amines (*e.g.*, dodecylamine, Germination of bacterial spores with alkyl primary amines" J. Bacteriology, 1961.). Mixtures of these or more complex natural mixtures, such as rumen fluid or Oxgall, can be used to induce germination. Oxgall is dehydrated bovine bile composed of fatty acids, bile acids, inorganic salts, sulfates, bile pigments, cholesterol, mucin, lecithin, glycuronic acids, porphyrins, and urea. The germination can also be performed in a growth medium like prereduced BHIS/oxgall germination medium, in which BHIS (Brain heart infusion powder (37 g/L), yeast extract (5 g/L), L-cysteine HCl (1 g/L)) provides peptides, amino acids, inorganic ions and sugars in the complex BHI and yeast extract mixtures and Oxgall provides additional bile acid germinants.

[0323] In addition, pressure may be used to germinate spores. The selection of germinants can vary with the microbe being sought. Different species require different germinants and different isolates of the same species can require different germinants for optimal germination. Finally, it is important to dilute the mixture prior to plating because some germinants are inhibitory to growth of the vegetative-state microorganisms. For instance, it has been shown that alkyl amines must be neutralized with anionic lipophiles in order to promote optimal growth. Bile acids can also inhibit growth of some organisms despite promoting their germination, and must be diluted away prior to plating for viable cells.

[0324] For example, BHIS/oxgall solution is used as a germinant and contains 0.5X BHIS medium with 0.25% oxgall (dehydrated bovine bile) where 1x BHIS medium contains the following per L of solution: 6g Brain Heart Infusion from solids, 7g peptic digest of animal tissue, 14.5g of pancreatic

digest of casein, 5g of yeast extract, 5g sodium chloride, 2g glucose, 2.5g disodium phosphate, and 1g cysteine. Additionally, Ca-DPA is a germinant and contains 40mM CaCl2, and 40mM dipicolinic acid (DPA). Rumen fluid (Bar Diamond, Inc.) is also a germinant. Simulated gastric fluid (Ricca Chemical) is a germinant and is 0.2% (w/v) Sodium Chloride in 0.7% (v/v) Hydrochloric Acid. Mucin medium is a germinant and prepared by adding the following items to 1L of distilled sterile water: 0.4 g KH2PO4, 0.53 g Na2HPO4, 0.3 g NH4Cl, 0.3 g NaCl, 0.1 g MgCl2 x 6H2O, 0.11 g CaCl2, 1 ml alkaline trace element solution, 1 ml acid trace element solution, 1 ml vitamin solution, 0.5 mg resazurin, 4 g NaHCO3, 0.25 g Na2S x 9 H2O. The trace element and vitamin solutions prepared as described previously (Stams et al., 1993). All compounds were autoclaved, except the vitamins, which were filter-sterilized. The basal medium was supplemented with 0.7% (v/v) clarified, sterile rumen fluid and 0.25% (v/v) commercial hog gastric mucin (Type III; Sigma), purified by ethanol precipitation as described previously (Miller & Hoskins, 1981). This medium is referred herein as mucin medium.

[0325] Fetal Bovine Serum (Gibco) can be used as a germinant and contains 5% FBS heat inactivated, in Phosphate Buffered Saline (PBS, Fisher Scientific) containing 0.137M Sodium Chloride, 0.0027M Potassium Chloride, 0.0119M Phosphate Buffer. Thioglycollate is a germinant as described previously (Kamiya et al Journal of Medical Microbiology 1989) and contains 0.25M (pH10) sodium thioglycollate. Dodecylamine solution containing 1mM dodecylamine in PBS is a germinant. A sugar solution can be used as a germinant and contains 0.2% fructose, 0.2% glucose, and 0.2% mannitol. Amino acid solution can also be used as a germinant and contains 5mM alanine, 1mM arginine, 1mM histidine, 1mM lysine, 1mM proline, 1mM asparagine, 1mM aspartic acid, 1mM phenylalanine. A germinant mixture referred to herein as Germix 3 can be a germinant and contains 5mM alanine, 1mM arginine, 1mM histidine, 1mM lysine, 1mM proline, 1mM asparagine, 1mM aspartic acid, 1mM phenylalanine, 0.2%taurocholate, 0.2% fructose, 0.2% mannitol, 0.2% glucose, 1mM inosine, 2.5mM Ca-DPA, and 5mM KCl. BHIS medium + DPA is a germinant mixture and contains BHIS medium and 2mM Ca-DPA. Escherichia coli spent medium supernatant referred to herein as EcSN is a germinant and is prepared by growing E. coli MG1655 in SweetB/Fos inulin medium anaerobically for 48 hr, spinning down cells at 20,000rcf for 20 minutes, collecting the supernatant and heating to 60C for 40 min. Finally, the solution is filter sterilized and used as a germinant solution.

Determination of Bacterial Pathogens In Purified Spore Populations

[0326] Bacterial pathogens present in a purified spore population are determined by qPCR using specific oligonucleotide primers as follows.

Standard Curve Preparation

[0327] The standard curve is generated from wells containing the pathogen of interest at a known concentration or simultaneously quantified by selective spot plating. Serial dilutions of duplicate

cultures are performed in sterile phosphate-buffered saline. Genomic DNA is then extracted from the standard curve samples along with the other samples.

Genomic DNA Extraction

[0328] Genomic DNA may be extracted from 100 µl of fecal samples, fecal-derived samples, or purified spore preparations using the Mo Bio Powersoil®-htp 96 Well Soil DNA Isolation Kit (Mo Bio Laboratories, Carlsbad, CA) according to the manufacturer's instructions with two exceptions: the beadbeating is performed for 2 x 4:40 minutes using a BioSpec Mini-Beadbeater-96 (BioSpec Products, Bartlesville, OK) and the DNA is eluted in 50 µl of Solution C6. Alternatively the genomic DNA could be isolated using the Mo Bio Powersoil® DNA Isolation Kit (Mo Bio Laboratories, Carlsbad, CA), the Sigma-Aldrich Extract-N-Amp™Plant PCR Kit, the QIAamp DNA Stool Mini Kit (QIAGEN, Valencia, CA) according to the manufacturer's instructions.

qPCR Composition and Conditions

[0329] The qPCR reaction to detect C. difficile contains 1x HotMasterMix (5PRIME, Gaithersburg, MD), 900 nM of Wr-tcdB-F (AGCAGTTGAATATAGTGGTTTAGTTAGAGTTG, IDT, Coralville, IA), 900 nM of Wr-tcdB-R (CATGCTTTTTTAGTTTCTGGATTGAA, IDT, Coralville, IA), 250 nM of We-tcdB-P (6FAM-CATCCAGTCTCAATTGTATATGTTTCTCCA-MGB, Life Technologies, Grand Island, NY), and PCR Water (Mo Bio Laboratories, Carlsbad, CA) to 18 µl (Primers adaped from: Wroblewski, D. et al. Rapid Molecular Characterization of Clostridium difficile and Assessment of Populations of C. difficile in Stool Specimens. Journal of Clinical Microbiology 47:2142–2148 (2009)). This reaction mixture is aliquoted to wells of a MicroAmp® Fast Optical 96-well Reaction Plate with Barcode (0.1mL) (Life Technologies, Grand Island, NY). To this reaction mixture, 2 µl of extracted genomic DNA is added. The qPCR is performed on a BioRad C1000™ Thermal Cycler equipped with a CFX96™ Real-Time System (BioRad, Hercules, CA). The thermocycling conditions are 95°C for 2 minutes followed by 45 cycles of 95°C for 3 seconds, 60°C for 30 seconds, and fluorescent readings of the FAM and ROX channels. Other bacterial pathogens can be detected by using primers and a probe specific for the pathogen of interest.

Data Analysis

[0330] The Cq value for each well on the FAM channel is determined by the CFX Manager™ Software Version 2.1. The log10(cfu/ml) of each experimental sample is calculated by inputting a given sample's Cq value into linear regression model generated from the standard curve comparing the Cq values of the standard curve wells to the known log10(cfu/ml) of those samples. Viral pathogens present in a purified spore population are determined by qPCR as described herein and otherwise known in the art.

Example 11. Characterization of Microbiome in Ethanol-treated spore population and Patients Post-Treatment

Microbial Population Engraftment, Augmentation, and Reduction of Pathogen Carriage in Patients Treated with Spore Compositions.

[0331] Complementary genomic and microbiological methods were used to characterize the composition of the microbiota from Patient 1, 2, 3, 4, and 5, 6, 7, 8, 9, and 10 at pretreatment (pretreatment) and up to 4 weeks post-treatment.

[0332] Table 3 shows bacterial OTUs associated with engraftment and ecological augmentation and establishment of a more diverse microbial ecology in patients treated with an ethanol-treated spore preparation. OTUs that comprise an augmented ecology are below the limit of detection in the patient prior to treatment and/or exist at extremely low frequencies such that they do not comprise a significant fraction of the total microbial carriage and are not detectable by genomic and/or microbiological assay methods in the bacterial composition. OTUs that are members of the engrafting and augmented ecologies were identified by characterizing the OTUs that increase in their relative abundance post treatment and that respectively are: (i) present in the ethanol-treated spore preparation and not detectable in the patient pretreatment (engrafting OTUs), or (ii) absent in the ethanol-treated spore preparation, but increase in their relative abundance in the patient through time post treatment with the preparation due to the formation of favorable growth conditions by the treatment (augmenting OTUs). Notably, the latter OTUs can grow from low frequency reservoirs in the patient, or be introduced from exogenous sources such as diet. OTUs that comprise a "core" augmented or engrafted ecology can be defined by the percentage of total patients in which they are observed to engraft and/or augment; the greater this percentage the more likely they are to be part of a core ecology responsible for catalyzing a shift away from a dysbiotic ecology. The dominant OTUs in an ecology can be identified using several methods including but not limited to defining the OTUs that have the greatest relative abundance in either the augmented or engrafted ecologies and defining a total relative abundance threshold. As example, the dominant OTUs in the augmented ecology of Patient-1 were identified by defining the OTUs with the greatest relative abundance, which together comprise 60% of the microbial carriage in this patient's augmented ecology by day 25 post-treatment..

[0333] Patient treatment with the ethanol-treated spore preparation leads to the population of a microbial ecology that has greater diversity than prior to treatment (See Figure 5 & 6). Genomic-based microbiome characterization confirmed engraftment of a range of OTUs that were not detectable in the patient pretreatment (Table 3). These OTUs comprised both bacterial species that were capable and not capable of forming spores, and OTUs that represent multiple phylogenetic clades. Organisms not detectable in Patient 1 pre-treatment either engraft directly from the ethanol-treated spore fraction or are augmented by the creation of a gut environment favoring a healthy,

diverse microbiota. Microbiological analysis shows that Bacteroides fragilis group species were increased by 4 and 6 logs in patients 1 and 2 (Figure 7).

[0334] Figure 5 shows the microbial diversity measured in the ethanol-treated spore treatment sample and patient pre- and post-treatment samples. Total microbial diversity is defined using the Chao1 Alpha-Diversity Index and is measured at different genomic sampling depths to confirm adequate sequence coverage to assay the microbiome in the target samples. The patient pretreatment (purple) harbored a microbiome that was significantly reduced in total diversity as compared to the ethanol-treated spore product (red) and patient post treatment at days 5 (blue), 14 (orange), and 25 (green).

[0335] Figure 6 shows patient microbial ecology is shifted by treatment with an ethanol-treated spore treatment from a dysbiotic state to a state of health. Principal Coordinates Analysis based on the total diversity and structure of the microbiome (Bray-Curtis Beta-Diversity) of the patient pre- and post-treatment delineates that the engraftment of OTUs from the spore treatment and the augmentation of the patient microbial ecology leads to a microbial ecology that is distinct from both the pretreatment microbiome and the ecology of the ethanol-treated spore treatment (Table 3).

[0336] Figure 7 shows the augmentation of Bacteroides species in patients. Comparing the number of Bacteroides fragilis groups species in feces (cfu/g) pre-treatment and in week 4 post treatment reveals an increase of 4 logs or greater. The ability of 16S-V4 OTU identification to assign an OTU as a specific species depends in part on the resolution of the 16S-V4 region of the 16S gene for a particular species or group of species. Both the density of available reference 16S sequences for different regions of the tree as well as the inherent variability in the 16S gene between different species will determine the definitiveness of a taxonomic annotation to a given sequence read. Given the topological nature of a phylogenetic tree and that the tree represents hierarchical relationships of OTUs to one another based on their sequence similarity and an underlying evolutionary model, taxonomic annotations of a read can be rolled up to a higher level using a clade-based assignment procedure (Table 1). Using this approach, clades are defined based on the topology of a phylogenetic tree that is constructed from full-length 16S sequences using maximum likelihood or other phylogenetic models familiar to individuals with ordinary skill in the art of phylogenetics. Clades are constructed to ensure that all OTUs in a given clade are: (i) within a specified number of bootstrap supported nodes from one another (generally, 1-5 bootstraps), and (ii) within a 5% genetic similarity. OTUs that are within the same clade can be distinguished as genetically and phylogenetically distinct from OTUs in a different clade based on 16S-V4 sequence data. OTUs falling within the same clade are evolutionarily closely related and may or may not be distinguishable from one another using 16S-V4 sequence data. The power of clade based analysis is that members of the same clade, due to their evolutionary relatedness, play similar functional roles in a microbial ecology such as that found in the

human gut. Compositions substituting one species with another from the same clade are likely to have conserved ecological function and therefore are useful in the present invention.

[0337] Stool samples were aliquoted and resuspended 10x vol/wt in either 100% ethanol (for genomic characterization) or PBS containing 15% glycerol (for isolation of microbes) and then stored at -80°C until needed for use. For genomic 16S sequence analysis colonies picked from plate isolates had their full-length 16S sequence characterized as described in Examples 2 and 3, and primary stool samples were prepared targeting the 16S-V4 region using the method for heterogeneous samples described herein.

[0338] Notably, 16S sequences of isolates of a given OTU are phylogenetically placed within their respective clades despite that the actual taxonomic assignment of species and genus may suggest they are taxonomically distinct from other members of the clades in which they fall. Discrepancies between taxonomic names given to an OTU is based on microbiological characteristics versus genetic sequencing are known to exist from the literature. The OTUs footnoted in this table are known to be discrepant between the different methods for assigning a taxonomic name.

[0339] Engraftment of OTUs from the ethanol-treated spore preparation treatment into the patient as well as the resulting augmentation of the resident microbiome led to a significant decrease in and elimination of the carriage of pathogenic species other than C. difficile in the patient. 16S-V4 sequencing of primary stool samples demonstrated that at pretreatment, 20% of reads were from the genus Klebsiella and an additional 19% were assigned to the genus Fusobacterium. These striking data are evidence of a profoundly dysbiotic microbiota associated with recurrent C. difficile infection and chronic antibiotic use. In healthy individuals, Klebsiella is a resident of the human microbiome in only about 2% of subjects based on an analysis of HMP database (www.hmpdacc.org), and the mean relative abundance of Klebsiella is only about 0.09% in the stool of these people. Its surprising presence at 20% relative abundance in Patient 1 before treatment is an indicator of a proinflammatory gut environment enabling a "pathobiont" to overgrow and outcompete the commensal organisms normally found in the gut. Similarly, the dramatic overgrowth of Fusobacterium indicates a profoundly dysbiotic gut microbiota. One species of Fusobacterium, F. nucleatum (an OTU phylogenetically indistinguishable from Fusobacterium sp. 3_1_33 based on 16S-V4), has been termed "an emerging gut pathogen" based on its association with IBD, Crohn's disease, and colorectal cancer in humans and its demonstrated causative role in the development of colorectal cancer in animal models [Allen-Vercoe, Gut Microbes (2011) 2:294-8]. Importantly, neither Klebsiella nor Fusobacterium was detected in the 16S-V4 reads by Day 25 (Table 4).

[0340] To further characterize the colonization of the gut by Klebsiella and other Enterobacteriaceae and to speciate these organisms, pretreatment and Day 25 fecal samples stored at -80C as PBS-glycerol suspensions were plated on a variety of selective media including MacConkey lactose media (selective for gram negative enterobacteria) and Simmons Citrate Inositol media

(selective for Klebsiella spp) [Van Cregten et al, J. Clin. Microbiol. (1984) 20: 936-41]. Enterobacteria identified in the patient samples included K. pneumoniae, Klebsiella sp. Co_9935 and E. coli. Strikingly, each Klebsiella species was reduced by 2-4 logs whereas E. coli, a normal commensal organism present in a healthy microbiota, was reduced by less than 1 log (Table 14 below). This decrease in Klebsiella spp. carriage is consistent across multiple patients. Four separate patients were evaluated for the presence of Klebsiella spp. pre treatment and 4 weeks post treatment. Klebsiella spp. were detected by growth on selective Simmons Citrate Inositol media as previously described. Serial dilution and plating, followed by determining cfu/mL titers of morphologically distinct species and 16S full length sequence identification of representatives of those distinct morphological classes, allowed calculation of titers of specific species.

[0341] The genus Bacteroides is an important member of the gastrointestinal microbiota; 100% of stool samples from the Human Microbiome Project contain at least one species of Bacteroides with total relative abundance in these samples ranging from 0.96% to 93.92% with a median relative abundance of 52.67% (www.hmpdacc.org reference data set HMSMCP). Bacteroides in the gut has been associated with amino acid fermentation and degradation of complex polysaccharides. Its presence in the gut is enhanced by diets rich in animal-derived products as found in the typical western diet [David, L. A. et al, Nature (2013) doi:10.1038/nature12820]. Strikingly, prior to treatment, fewer than 0.008% of the 16S-V4 reads from Patient 1 mapped to the genus Bacteroides strongly suggesting that Bacteroides species were absent or that viable Bacteroides were reduced to an extremely minor component of the patient's gut microbiome. Post treatment, ≥42% of the 16S-V4 reads could be assigned to the genus Bacteroides within 5 days of treatment and by Day 25 post treatment 59.48% of the patients gut microbiome was comprised of Bacteroides. These results were confirmed microbiologically by the absence of detectable Bacteroides in the pretreatment sample plated on two different Bacteroides selective media: Bacteroides Bile Esculin (BBE) agar which is selective for Bacteroides fragilis group species [Livingston, S.J.et al J. Clin. Microbiol (1978). 7: 448-453] and Polyamine Free Arabinose (PFA) agar [Noack et al. J. Nutr. (1998) 128: 1385-1391; modified by replacing glucose with arabinose]. The highly selective BBE agar had a limit of detection of <2x103 cfu/g, while the limit of detection for Bacteroides on PFA agar was approximately 2x107 cfu/g due to the growth of multiple non-Bacteroides species in the pretreatment sample on that medium. Colony counts of Bacteroides species on Day 25 were up to 2x1010 cfu/g, consistent with the 16S-V4 sequencing, demonstrating a profound reconstitution of the gut microbiota in Patient 1 (Table 5 below).

[0342] The significant abundance of Bacteroides in Patient 1 on Day 25 (and as early as Day 5 as shown by 16S-V4 sequencing) is remarkable. Viable Bacteroides fragilis group species were not present in the ethanol-treated spore population based on microbiological plating (limit of detection of 10 cfu/ml). Thus, administration of the ethanol-treated spore population to Patient 1 resulted in microbial population of the patient's GI tract, not only due to the engraftment of bacterial species such

as but not limited to spore forming species, but also the restoration of high levels of non-spore forming species commonly found in healthy individuals through the creation of a niche that allowed for the repopulation of Bacteroides species. These organisms were most likely either present at extremely low abundance in the GI tract of Patient 1, or present in a reservoir in the GI tract from which they could rebound to high titer. Those species may also be reinoculated via oral uptake from food following treatment. We term this healthy repopulation of the gut with OTUs that are not present in the bacterial composition such as but not limited to a spore population or ethanol-treated spore population, "Augmentation." Augmentation is an important phenomenon in that it shows the ability to use an ethanol-treated spore ecology or other bacterial composition to restore a healthy microbiota by seeding a diverse array or commensal organisms beyond the actual component organisms in the bacterial composition such as but not limited to an ethanol-treated spore population itself; specifically the spore composition treatment itself and the engraftment of OTUs from the spore composition create a niche that enables the outgrowth of OTUs required to shift a dysbiotic microbiome to a microbial ecology that is associated with health. The diversity of Bacteroides species and their approximate relative abundance in the gut of Patient 1 is shown in Table 16, comprising at least 8 different species.

[0343] Figure 8 shows species engrafting versus species augmenting in patients microbiomes after treatment with a bacterial composition such as but not limited to an ethanol-treated spore population. Relative abundance of species that engrafted or augmented as described were determined based on the number of 16S sequence reads. Each plot is from a different patient treated with the bacterial composition such as but not limited to an ethanol-treated spore population for recurrent C. difficile.

[0344] The impact of the bacterial composition such as but not limited to an ethanol-treated spore population treatment on carriage of imipenem resistant Enterobacteriaceae was assessed by plating pretreatment and Day 28 clinical samples from Patients 2, 4 and 5 on MacConkey lactose plus 1 ug/mL of imipenem. Resistant organisms were scored by morphology, enumerated and DNA was submitted for full length 16S rDNA sequencing as described above. Isolates were identified as Morganella morganii, Providencia rettgeri and Proteus penneri. Each of these are gut commensal organisms; overgrowth can lead to bacteremia and/or urinary tract infections requiring aggressive antibiotic treatment and, in some cases, hospitalization [Kim, B-N, et al Scan J. Inf Dis (2003) 35: 98-103; Lee, I-K and Liu, J-W J. Microbiol Immunol Infect (2006) 39: 328-334; O'Hara et al, Clin Microbiol Rev (2000) 13: 534]. The titer of organisms at pretreatment and Day 28 by patient is shown in Table 17. Importantly, administration of the bacterial composition such as but not limited to an ethanol-treated spore preparation resulted in greater than 100-fold reduction in 4 of 5 cases of Enterobacteriaceae carriage with multiple imipenem resistant organisms (See Table 17 which shows titers (in cfu/g) of imipenem-resistant M. morganii, P. rettgeri and P. penneri from Patients 2, 4 & 5).

[0345] In addition to speciation and enumeration, multiple isolates of each organism from Patient 4 were grown overnight in 96-well trays containing a 2-fold dilution series of imipenem in order to quantitatively determine the minimum inhibitory concentration (MIC) of antibiotic. Growth of organisms was detected by light scattering at 600 nm on a SpectraMax M5e plate reader. In the clinical setting, these species are considered resistant to imipenem if they have an MIC of 1 ug/mL or greater. M. morganii isolates from pretreatment samples from Patient 4 had MICs of 2-4 ug/mL and P. penneri isolates had MICs of 4-8 ug/mL. Thus, the bacterial composition, such as but not limited to, an ethanol-treated spores administered to Patient 4 caused the clearance of 2 imipenem resistant organisms (Table 4). While this example specifically uses a spore preparation, the methods herein describe how one skilled in the art would use a more general bacterial composition to achieve the same effects. The specific example should not be viewed as a limitation of the scope of this disclosure.

Identifying the Core Ecology From the Bacterial Combination

[0346] Ten different bacterial compositions were made by the ethanol-treated spore preparation methods from 6 different donors (as described above). The spore preparations were used to treat 10 patients, each suffering from recurrent C. difficile infection. Donors were identified using the inclusion/exclusion criteria described above under provision of fecal material. None of the patients experienced a relapse of C. difficile in the 4 weeks of follow up after treatment, whereas the literature would predict that 70-80% of subjects would experience a relapse following cessation of antibiotic [Van Nood, et al, NEJM (2013)]. Thus, the ethanol-treated spore preparations derived from multiple different donors and donations showed remarkable clinical efficacy. These ethanol-treated spore preparations are a subset of the bacterial compositions described herein and the results should not be viewed as a limitation on the scope of the broader set of bacterial compositions.

[0347] To define the Core Ecology underlying the remarkable clinical efficacy of the bacterial compositions *e.g.* ethanol-treated spore preparations, the following analysis was carried out. The OTU composition of the spore preparation was determined by 16S-V4 rDNA sequencing and computational assignment of OTUs per Example 2. A requirement to detect at least ten sequence reads in the ethanol-treated spore preparation was set as a conservative threshold to define only OTUs that were highly unlikely to arise from errors during amplification or sequencing. Methods routinely employed by those familiar to the art of genomic-based microbiome characterization use a read relative abundance threshold of 0.005% (see *e.g.* Bokulich, A. et al. 2013. Quality-filtering vastly improves diversity estimates from Illumina amplicon sequencing. Nature Methods 10: 57-59), which would equate to ≥2 reads given the sequencing depth obtained for the samples analyzed in this example, as cut-off which is substantially lower than the ≥10 reads used in this analysis. All taxonomic and clade assignments were made for each OTU as described in Example 2. The resulting list of OTUs, clade assignments, and frequency of detection in the spore preparations are shown in

Table 18. Table 18 shows OTUs detected by a minimum of ten 16S-V4 sequence reads in at least one ethanol-treated spore preparatio. OTUs that engraft in a treated patients and the percentage of patients in which they engraft are denoted, as are the clades, spore forming status, and Keystone OTU status. Starred OTUs occur in ≥80% of the ethanol preps and engraft in ≥50% of the treated patients.

[0348] Next, it was reasoned that for an OTU to be considered a member of the Core Ecology of the bacterial composition, that OTU must be shown to engraft in a patient. Engraftment is important for two reasons. First, engraftment is a sine qua non of the mechanism to reshape the microbiome and eliminate C. difficile colonization. OTUs that engraft with higher frequency are highly likely to be a component of the Core Ecology of the spore preparation or broadly speaking a set bacterial composition. Second, OTUs detected by sequencing a bacterial composition (as in Table 6 may include non-viable cells or other contaminant DNA molecules not associated with the composition. The requirement that an OTU must be shown to engraft in the patient eliminates OTUs that represent non-viable cells or contaminating sequences. Table 6 also identifies all OTUs detected in the bacterial composition that also were shown to engraft in at least one patient post-treatment. OTUs that are present in a large percentage of the bacterial composition *e.g.* ethanol spore preparations analyzed and that engraft in a large number of patients represent a subset of the Core Ecology that are highly likely to catalyze the shift from a dysbiotic disease ecology to a healthy microbiome.

[0349] A third lens was applied to further refine insights into the Core Ecology of the bacterial composition (*e.g.* spore preparation). Computational-based, network analysis has enabled the description of microbial ecologies that are present in the microbiota of a broad population of healthy individuals (see Example 5). These network ecologies are comprised of multiple OTUs, some of which are defined as Keystone OTUs. Keystone OTUs are computationally defined as described in Example 6. Keystone OTUs form a foundation to the microbially ecologies in that they are found and as such are central to the function of network ecologies in healthy subjects. Keystone OTUs associated with microbial ecologies associated with healthy subjects are often are missing or exist at reduced levels in subjects with disease. Keystone OTUs may exist in low, moderate, or high abundance in subjects. Table 6 further notes which of the OTUs in the bacterial composition *e.g.* spore preparation are Keystone OTUs exclusively associated with individuals that are healthy and do not harbor disease. The presence of computationally derived Keystone OTUs in the Core Ecology of the doses validates the predictive capacity of computationally derived network ecologies.

[0350] There are several important findings from this data. A relatively small number of species, 16 in total, are detected in all of the spore preparations from 6 donors and 10 donations. This is surprising because the HMP database (www.hmpdacc.org) describes the enormous variability of commensal species across healthy individuals. The presence of a small number of consistent OTUs lends support to the concept of a Core Ecology and Backbone Networks. The engraftment data further supports this conclusion. A regression analysis shows a significant correlation between

frequency of detection in a spore preparation and frequency of engraftment in a donor: $R = 0.43$ ($p < 0.001$). While this may seem obvious, there is no a priori requirement that an OTU detected frequently in the bacterial composition *e.g.* spore preparation will or should engraft. For instance, Lutispora thermophila, a spore former found in all ten spore preparations, did not engraft in any of the patients. Bilophila wadsworthia, a gram negative anaerobe, is present in 9 of 10 donations, yet it does not engraft in any patient, indicating that it is likely a non-viable contaminant in the ethanol-treated spore preparation. Finally, it is worth noting the high preponderance of previously defined Keystone OTUs among the most frequent OTUs in the spore preparations.

[0351] These three factors--prevalence in the bacterial composition such as but not limited to a spore preparation, frequency of engraftment, and designation as a Keystone OTUs--enabled the creation of a "Core Ecology Score" (CES) to rank individual OTUs. CES was defined as follows:

- 40% weighting for presence of OTU in spore preparation
    - multiplier of 1 for presence in 1-3 spore preparations
    - multiplier of 2.5 for presence in 4-8 spore preparations
    - multiplier of 5 for presences in ≥ 9 spore preparations
- 40% weighting for engraftment in a patient
    - multiplier of 1 for engraftment in 1-4 patients
    - multiplier of 2.5 for engraftment in 5-6 patients
    - multiplier of 5 for engraftment in ≥ 7 patients
- 20% weighting to Keystone OTUs
    - multiplier of 1 for a Keystone OTU
    - multiplier of 0 for a non-Keystone OTU

[0352] Using this guide, the CES has a maximum possible score of 5 and a minimum possible score of 0.8. As an example, an OTU found in 8 of the 10 bacterial composition such as but not limited to a spore preparations that engrafted in 3 patients and was a Keystone OTU would be assigned the follow CES:

[0353] $CES = (0.4 \times 2.5) + (0.4 \times 1) + (0.2 \times 1) = 1.6$

[0354] Table 7 ranks the top 20 OTUs by CES with the further requirement that an OTU must be shown to engraft to be a considered an element of a core ecology.

Defining Efficacious Subsets of the Core Ecology

[0355] The number of organisms in the human gastrointestinal tract, as well as the diversity between healthy individuals, is indicative of the functional redundancy of a healthy gut microbiome ecology (see The Human Microbiome Consortia. 2012. Structure, function and diversity of the healthy human microbiome. Nature 486: 207-214). This redundancy makes it highly likely that subsets of the Core Ecology describe therapeutically beneficial components of the bacterial composition such as but not limited to an ethanol-treated spore preparation and that such subsets may

themselves be useful compositions for populating the GI tract and for the treatment of C. difficile infection given the ecologies functional characteristics. Using the CES, individual OTUs can be prioritized for evaluation as an efficacious subset of the Core Ecology.

[0356] Another aspect of functional redundancy is that evolutionarily related organisms (*i.e.* those close to one another on the phylogenetic tree, *e.g.* those grouped into a single clade) will also be effective substitutes in the Core Ecology or a subset thereof for treating C. difficile.

[0357] To one skilled in the art, the selection of appropriate OTU subsets for testing in vitro (see Example 20 below) or in vivo (see Examples 13 or 14) is straightforward. Subsets may be selected by picking any 2, 3, 4, 5, 6, 7, 8, 9, 10, or more than 10 OTUs from Table 6, with a particular emphasis on those with higher CES, such as the OTUs described Table 7. In addition, using the clade relationships defined in Example 2 above and Table 1, related OTUs can be selected as substitutes for OTUs with acceptable CES values. These organisms can be cultured anaerobically in vitro using the appropriate media (selected from those described in Example 5 above), and then combined in a desired ratio. A typical experiment in the mouse C. difficile model utilizes at least 10^4 and preferably at least 10^5, 10^6, 10^7, 10^8, 10^9 or more than 10^9 colony forming units of a each microbe in the composition. Variations in the culture yields may sometimes mean that organisms are combined in unequal ratios, *e.g.* 1:10, 1:100, 1:1,000, 1:10,000, 1:100,000, or greater than 1:100,000. What is important in these compositions is that each strain be provided in a minimum amount so that the strain's contribution to the efficacy of the Core Ecology subset can be measured. Using the principles and instructions described here, it is straightforward for one of skill in the art to make clade-based substitutions to test the efficacy of subsets of the Core Ecology. Table 18 describes the clades for each OTU detected in a spore preparation, and Table 1 describes the OTUs that can be used for substitutions based on clade relationships. Examples of network ecologies empirically screened in vivo are presented in Example 13 below.

Example 12. Presence of Network Ecologies and Keystone OTUs in Clinically prepped Ethanol-treated spore Preparation and CDAD Patients Post Treatment

[0358] Network ecologies computationally determined as described in Example 5 and reported in Table 8 as being networks or subsets of networks characteristic of health states in the context of CDAD or other disease indications (Table 14a-b) are observed in the ethanol-treated spore preparation (a.k.a. the bacterial composition) and the microbiome of patients post treatment (see Example 11) indicating that they play an important role in treatment of CDAD and other indications. For each computationally determined network ecology (Table 8), we determined whether the full network or a subset of the network was observed in the microbiome of (i) each of the 10 ethanol-treated spore preparations used to treat patients with recurrent Clostridium difficile associated diarrhea; (ii) the engrafted ecology of each of the 10 patients (see Example 11); (iii) the augmented ecology of each of the 10 patients (see Example 11); or (iv) of each of the 10 patient's microbiome pretreatment. If the

computationally determined networks are indeed representative of a state of health and not a disease state, one would expect that these networks would be responsible for catalyzing a shift from a disease state to a health state. This can happen either by the network ecology changing the gut environment to favor the growth of OTUs that are required to establish a health state (*i.e.* promoting augmentation) or by the engraftment of OTUs in the bacterial composition or both. Applicants observed that numerous computationally determined networks and/or subsets of these networks were in fact observed both in the bacterial composition used to treat the patients and the microbiota that expanded post-treatment (Table 14b). These same networks or sub-sets of networks were significantly under-represented in the patients pre-treatment. To demonstrate this, we computed the percentage of network OTUs that are found in (i) the treatment bacterial composition, (ii) the post-treatment augmented ecology, (iii) the post-treatment engrafted ecology, and (iv) the pretreatment ecology (*i.e.* patient microbiome prior to administration of the bacterial composition). Applicants observed across all doses of bacterial composition and patient samples that on average 46% ± 19% , 28% ± 14%, 11% ± 8%, and 7% ± 4% of the computed networks OTUs were present in the various microbiome ecologies, respectively (reported here as average ± standard deviation). There was a significant difference ($p<0.0001$, ANOVA) between all of these percentages indicating that prior to treatment, the OTUs found in CDAD patients are significantly under-represented in the networks, and that the network OTUs are significantly over-represented in the bacterial compositions and post-treatment patient samples, affirming the predictive utility of the computational network analysis. These results in combination with those reported in Table 14b demonstrate that, prior to treatment, the patients harbored a significantly lower number of OTUs that comprised network ecologies. In contrast, the ecology of the bacterial composition, as well as the augmenting ecologies whose appearance was catalyzed by the spore population, were significantly overrepresented in patients whose CDAD resolved due to treatment.

[0359] We observed both large and small computationally determined network ecologies characteristic of states of health in the ethanol-treated spore population and the patients post treatment (Table 14a). These observed networks ranged in size from 2-15 OTUs and were comprised of OTUs that represented from 29% to 100% of the OTUs in the computationally determined network ecology. Notably, on average the network ecologies found in the ethanol-treated spore population or the patient ecologies post treatment comprised 72% ± 15% (average ± SD) of the computationally determined network ecology again strongly indicating an important role of the computed network ecologies in catalyzing a shift in a dysbiotic disease ecology to a state of health in these patients with recurrent CDAD. Further, Keystone OTUs in the computationally determined network ecologies were frequently observed in the ethanol-treated spore preparations and in the patients' post-treatment gut ecologies. Clades representing Keystone OTUs where typically more common in the bacterial composition and post-treatment patient ecologies than in the pre-treatment dysbiotic patient ecology (Table 15).

[0360] The computed network ecologies and their respective subsets that are observed in the ethanol-treated spore preparation and the various patient ecologies post-treatment represent both complete and foundational networks (*e.g.*, Backbone Network Ecology). Microbial therapeutics can be comprised of these network ecologies in their entirety, or they can be modified by the addition or subtraction of other OTUs or functional modalities as described in Example 7 and Example 22 to design particular phylogenetic and/or functional characteristics, including metabolic functions such as SCFA production or bile acid metabolism, into the microbial therapeutic.

Example 13. In vivo validation of Network Ecology Bacterial Compositions Efficacy in Clostridium Difficile Infection Prevention Mouse Model

[0361] To test the therapeutic potential of the bacterial composition such as but not limited to a spore population, a prophylactic mouse model of C. difficile infection was used (model based on Chen X, Katchar K, Goldsmith JD, Nanthakumar N, Cheknis A, Gerding DN, Kelly CP. 2008. A mouse model of Clostridium difficile-associated disease. Gastroenterology 135: 1984–1992.). Two cages of five mice each were tested for each arm of the experiment. All mice received an antibiotic cocktail consisting of 10% glucose, kanamycin (0.5 mg/ml), gentamicin (0.044 mg/ml), colistin (1062.5 U/ml), metronidazole (0.269 mg/ml), ciprofloxacin (0.156 mg/ml), ampicillin (0.1 mg/ml) and Vancomycin (0.056 mg/ml) in their drinking water on days -14 through -5 and a dose of 10 mg/kg Clindamycin by oral gavage on day -3. On day -1, test articles are spun for 5 minutes at 12,100 rcf, their supernatants' removed, and the remaining pellets are resuspended in sterile PBS, prereduced if bacterial composition is not in spore form, and delivered via oral gavage. On day 0 they were challenged by administration of approximately 4.5 log10 cfu of C. difficile (ATCC 43255) or sterile PBS (for the Naive arm) via oral gavage. Optionally a positive control group received vancomycin from day -1 through day 3 in addition to the antibiotic protocol and C. difficile challenge specified above. Feces were collected from the cages for analysis of bacterial carriage. Mortality, weight and clinical scoring of C. difficile symptoms based upon a 0-4 scale by combining scores for Appearance (0-2 pts based on normal, hunched, piloerection, or lethargic), and Clinical Signs (0-2 points based on normal, wet tail, cold-to-the-touch, or isolation from other animals) are assessed every day from day -2 through day6. Mean minimum weight relative to day -1 and mean maximum clinical score where a death is assigned a clinical score of 4 as well as average cumulative mortality are calculated. Reduced mortality, increased mean minimum weight relative to day -1, and reduced mean maximum clinical score with death assigned to a score of 4 relative to the vehicle control are used to assess the success of the test article.

[0362] Table 16 reports results for 15 experiments of the prophylactic mouse model of C. difficile infection. In the 15 experiments, 157 of the arms tested network ecologies, with 86 distinct networks ecologies tested (Table 17). Of those 157 arms, 136 of the arms and 73 of the networks performed better than the respective experiment's vehicle control arm by at least one of the following metrics:

cumulative mortality, mean minimum relative weight, and mean maximum clinical score. Examples of efficacious networks include but are not limited to networks N1979 as tested in SP-361 which had 0% cumulative mortality, 0.97 mean minimum relative weight, and 0 mean maximum clinical score or N2007 which had 10% cumulative mortality, 0.91 mean minimum relative weight, and 0.9 mean maximum clinical score with both networks compared to the vehicle control in SP-361 which had 30% cumulative mortality, 0.88 mean minimum relative weight, and 2.4 mean maximum clinical score. In SP-376, N1962 had no cumulative mortality, mean maximum clinical scores of 0 at both target doses tested with mean minimum relative weights of 0.98 and 0.95 for target doses of 1e8 and 1e7 CFU/OTU/mouse respectively. These results confirm that bacterial compositions comprising bacteria identified from computationally determined networks or subsets of these determined networks have utility and efficacy in the mouse model.

Example 14. In Vivo Validation of Network Ecology Bacterial Composition Efficacy in Prophylactic and Relapse Prevention Hamster Model

[0363] Previous studies with hamsters using toxigenic and nontoxigenic strains of C. difficile demonstrated the utility of the hamster model in examining relapse post antibiotic treatment and the effects of prophylaxis treatments with cecal flora in C. difficile infection (Wilson et al. 1981, Wilson et al. 1983, Borriello et al. 1985) and more broadly in gastrointestinal infectious disease. To demonstrate prophylactic use of ethanol-treated spores and ethanol treated, gradient-purified spores to ameliorate C. difficile infection, the following hamster model was used. In the prophylactic model, Clindamycin (10mg/kg s.c.) was given on day -5, the test article or control was administered on day -3, and C. difficile challenge occurred on day 0. In the positive control arm, vancomycin was then administered on day 1-5 (and vehicle control was delivered on day -3). Feces were collected on day -5, -4, -1, 1, 3, 5, 7, 9 and fecal samples were assessed for pathogen carriage and reduction by microbiological methods. 16S sequencing approaches or other methods could also be utilized by one skilled in the art. Mortality was assessed multiple times per day through 21 days post C. difficile challenge. The percentage survival curves showed that ethanol-treated spores and ethanol treated, gradient-purified spores better protected the hamsters compared to the Vancomycin control, and vehicle control.

[0364] Figure 9 shows a prophylaxis model with the ethanol-treated spore preparation and the ethanol treated, gradient-purified spore preparation. In the relapse prevention model, hamsters were challenged with toxigenic C. difficile strains on day 0, and treated with clindamycin by oral gavage on day 1, and vancomycin was dosed on days 2-6. Test or control treatment was then administered on day 7, 8, and 9. The groups of hamsters for each arm consisted of 8 hamsters per group. Fecal material was collected on day -1, 1, 3, 5, 7, 10 and 13 and hamster mortality was assessed throughout. Survival curves were used to assess the efficacy of the test articles, *e.g.*, ethanol treated or ethanol treated, gradient purified spores versus the control treatment in preventing hamster death. The survival

curves demonstrated maximum efficacy for the ethanol treated, gradient-purified spores followed by the ethanol-treated spores. Both treatments improved survival percentage over vancomycin treatment.

[0365] Also in the relapse prevention model, the efficacy of a bacterial community of pure cultures, N1962, was tested. The survival curves demonstrate protection against relapse by N1962 relative to the vancomycin control treatment.

[0366] Figure 10 shows a relapse prevention model with ethanol-treated spores and ethanol treated, gradient purified spores. In particular, it shows an in vivo hamster Clostridium difficile relapse prevention model to validate efficacy of ethanol-treated spores and ethanol treated, gradient purified spores.

[0367] Figure 11 shows a relapse prevention model with a bacterial community. In particular, it shows an in vivo hamster Clostridium difficile relapse prevention model to validate efficacy of network ecology bacterial composition.

Example 15. Derivation of Functional Profile of Individual Microbial OTUs or Consortia of OTUs Representing Specific Network Ecologies

[0368] To generate a functional profile of an OTU, or consortium of OTUs one can leverage multiple -omic data types. These include, but are not limited to functional prediction based on 16S rRNA sequence, functional annotation of metagenomic or full-genome sequences, transcriptomics, and metabolomics. A consortium of OTUs of interest can be defined using numerous criteria including but not limited to: (i) a computationally derived network of OTUs based on the analysis of samples that represent states of health and disease such as those delineated in Example 5 and reported in Table 8, (ii) a consortia of OTUs that are identified in an individual sample or group of samples using either a 16S-based, metagenomic-based, or microbiological-based methods such as delineated in Examples 3, 4 and 16, and (iii) a list of OTUs derived from the assessment of literature.

[0369] For 16S rRNA sequences, phylogenetic investigation of communities by reconstruction of unobserved states, also known as PICRUSt (Langille MGI, Zaneveld J, Caporaso JG, McDonald D, Knights D, Reyes JA, Clemente JC, Burkepile DE, Vega Thurber RL, Knight R, et al. 2013. Predictive functional profiling of microbial communities using 16S rRNA marker gene sequences. Nat Biotechnol.), enables the prediction of a functional metabolic pathway of an OTU or a consortium of OTUs based on the KEGG database of reference functional pathways and functional ontologies (Kyoto Encyclopedia of Genes and Genomes; www.genome.jp/kegg/). PICRUSt matches the taxonomic annotation of a single 16S sequence read with a reference functional annotation of a genome sequence for a given OTU or set of OTUs. From these reference genome annotations, a functional annotation is assigned to each OTU. PICRUSt is composed of two high-level workflows: gene content inference and metagenome inference. The gene content inference produces gene content predictions for a set of reference OTUs as well as copy number predictions. The metagenome inference then uses these inputs and an OTU table that defines the OTUs in a sample and their relative

abundances to then infer the functional metabolic profile of the OTUs in the OTU table. In an alternative, but related method, one can lookup for all of the OTUs in a consortia the OTU taxonomic identifications in a functional reference database such as IMG (http://img.jgi.doe.gov) and then derive a functional annotation of the network by concatenating the database's metabolic pathway maps (*e.g.* KEGG Pathway Orthology in case of IMG) for each of the OTUs in the consortia (see below for specific example).

[0370] To generate functional annotation from metagenomic or whole genome shotgun sequence data, reads are first clustered and then representative reads are annotated. Sequence annotation is then performed as described in Example 1, with the additional step that sequences are either clustered or assembled prior to annotation. Following sequence characterization as described above using a technology such as but not limited to Illumina, sequence reads are demultiplexed using the indexing barcodes. Following demultiplexing sequence reads are clustered using a rapid clustering algorithm such as but not limited to UCLUST (http://drive5.com/usearch/manual/uclust_algo.html) or hash-based methods such VICUNA (Xiao Yang, Patrick Charlebois, Sante Gnerre, Matthew G Coole, Niall J. Lennon, Joshua Z. Levin, James Qu, Elizabeth M. Ryan, Michael C. Zody, and Matthew R. Henn. 2012. De novo assembly of highly diverse viral populations. BMC Genomics 13:475). Following clustering a representative read for each cluster is identified and analyzed as described above in Example 2 "Primary Read Annotation". The result of the primary annotation is then applied to all reads in a given cluster. In another embodiment, metagenomic sequences are first assembled into contigs and then these assembled contigs are annotated using methods familiar to one with ordinary skill in the art of genome assembly and annotation. Platforms such as but not limited to MetAMOS (TJ. Treangen et al. 2013 Geneome Biology 14:R2), and HUMAaN (Abubucker S, Segata N, Goll J, Schubert AM, Izard J, Cantarel BL, Rodriguez-Mueller B, Zucker J, Thiagarajan M, Henrissat B, et al. 2012. Metabolic Reconstruction for Metagenomic Data and Its Application to the Human Microbiome ed. J.A. Eisen. PLoS Computational Biology 8: e1002358) are suitable for analysis of metagenomic data sets using the methods described above. Tools such as MetAMOS are also suitable for the generation of a functional annotation of complete genome sequence assembled from the sample or obtained from a reference genome database such as but not limited to NCBI's genome database (http://www.ncbi.nlm.nih.gov/genome). In all cases, functional pathways are derived from the sequence read annotations based on the mapping of the sequence annotations to a functional database, such as but not limited to KEGG (http://www.genome.jp/kegg), Biocyc (http://biocyc.org), IMG (http://img.jgi.doe.gov), MetaCyc (http://www.metacyc.org), or Reactome (http://www.reactome.org). Various tools are available for this task that are familiar to one with ordinary skill in the art including, but not limited to, The HMP Unified Metabolic Analysis Network (HUMAnN) (Abubucker S, Segata N, Goll J, Schubert AM, Izard J, Cantarel BL, Rodriguez-Mueller B, Zucker J, Thiagarajan M, Henrissat B, et al. 2012. Metabolic Reconstruction for Metagenomic Data and Its Application to the Human Microbiome ed. J.A. Eisen. PLoS Computational Biology 8:

e1002358). The HUMAnN software recovers the presence, absence, and abundance of microbial gene families and pathways from metagenomic data. Cleaned short DNA reads are aligned to the KEGG Orthology (or any other characterized sequence database with functional annotation assigned to genetic sequences) using accelerated translated BLAST. Gene family abundances are calculated as weighted sums of the alignments from each read, normalized by gene length and alignment quality. Pathway reconstruction is performed using a maximum parsimony approach followed by taxonomic limitation (to remove false positive pathway identifications) and gap filling (to account for rare genes in abundant pathways). The resulting output is a set of matrices of pathway coverages (presence/absence) and abundances, as analyzed here for the seven primary body sites of the Human Microbiome Project.

[0371] Transcriptomic or RNA-Seq data are also a means to generate a functional profile of a sample (Wang Z, Gerstein M, Snyder M. 2009. RNA-Seq: a revolutionary tool for transcriptomics. Nat Rev Genet 10: 57–63). Briefly, long RNAs are first converted into a library of cDNA fragments through either RNA fragmentation or DNA fragmentation. Sequencing adaptors appropriate to the sequencing technology being used for downstream sequencing are subsequently added to each cDNA fragment and a short sequence is obtained from each cDNA using high-throughput sequencing technology. The resulting sequence reads are aligned with the reference genome or transcriptome and annotated and mapped to functional pathways as described above. Reads are categorized as three types: exonic reads, junction reads and poly(A) end-reads. These three types of reads in combination with the gene annotation are used to generate a base-resolution expression profile for each gene.

[0372] In yet another method to generate a metabolic profile of a microbial ecology, characterization of metabolites produced by the ecology are analyzed in tissues or fluids. Samples can include, without limitation, blood, urine, serum, feces, ileal fluid, gastric fluid, pulmonary aspirates, tissue culture fluid, or bacterial culture supernatants. Both targeted and untargeted methods can be utilized for metabolomics analysis (Patti GJ, Yanes O, Siuzdak G. 2012. Innovation: Metabolomics: the apogee of the omics trilogy. Nat Rev Mol Cell Biol 13: 263–269.). Metabolomic methods utilize LC/MS-based technologies to generate a metabolite profile of sample. In the triple quadrupole (QqQ)-based targeted metabolomic workflow, standard compounds for the metabolites of interest are first used to set up selected reaction monitoring methods. Here, optimal instrument voltages are determined and response curves are generated using reference standards for absolute quantification. After the targeted methods have been established on the basis of standard metabolites, metabolites are extracted from the sample using methods familiar to one with ordinary skill in the art. Extraction methods can include liquid:liquid extraction using organic solvents or two-phase aqueous methods, solid phase extraction using hydrophobic or ion exchange resins, filtrations to remove solid contaminants, centrifugation or other means of clarification, and counter-current techniques. The data output provides quantification only of those metabolites for which standards are available. In the untargeted metabolomic workflow, extracted metabolites are first iseparated by liquid

chromatography followed by mass spectrometry (LC/MS). After data acquisition, the results are processed by using bioinformatic software such as XCMS to perform nonlinear retention time alignment and identify peaks that are changing between the groups of related samples. The m/z values for the peaks of interest are searched in a metabolite databases to obtain putative identifications. Putative identifications are then confirmed by comparing tandem mass spectrometry (MS/MS) data and retention time data to that of standard compounds. The untargeted workflow is global in scope and outputs data related to comprehensive cellular metabolism.

[0373] Applicants generated a functional profile for all of the computationally determined network ecologies delineated in Table 8 and Table 14a that were derived using the methods outlined in Example 5. Table 18 and Table 21 provide written description of the corresponding functional network ecologies respectively. For each network, applicants generated a functional metabolic profile by concatenating the KEGG Orthology Pathways for each OTU available in the IMG functional database (http://img.jgi.doe.gov). The taxonomic annotations of each OTU in the network were mapped to the taxon_display_names in the IMG database. For each taxon_display_name the taxon_iod with the best 16S sequence match to the 16S sequence of the OTU in the computed network ecology was selected (best match based on expectation value and an alignment score). The functional annotation for each OTU in the network was then derived from IMG's KEGG Orthology Pathway (*i.e.* ko_id) for the given taxon_iod. KEGG Orthology Pathways (KO) for all the OTUs in the network were concatenated and then the list was made unique to generate a non-redundant functional profile of the network. In another embodiment, the ko_id list is not made unique and the functional profile of the network is defined based on the relative abundances of the ko_ids not just their presence or absence. It is with the level of ordinary skill using the aforementioned disclosure to construct functional network ecologies that substitute the exemplified OTUs with equivalent OTUs that harbor the orthologous KEGG Orthology Pathways. Such substitiutions are contemplated to be within the scope of the present invention, either literally or as an equivalent to the claimed invention as determined by determined by a court of competent jurisdiction.

[0374] Each functional network ecology was scored for its ability to metabolize bile acids and to produce short chain fatty acids (SCFAs). As described above, both bile acid metabolism and the production of SCFAs by bacterial ecologies plays an important role in human health. Specifically, applicants subsetted the KEGG Orthology Pathways computed for each network ecology to those described to be involved in secondary bile acid biosynthesis, butyrate (a.k.a. butanoate) metabolism, propionate (a.k.a. propanoate) metabolism, or pyruvate metabolism (leads to production of acetate).

We identified and ranked network ecologies for their capacity to metabolize bile acid and produce SCFAs by defining a bile acid and SCFA functional score (F-Score) that defines a network ecologies' capacity to perform these two important metabolic roles. The F-score is defined by the total number of KEGG Orthology Pathways in a given network that mapped to secondary bile acid biosynthesis, a butyrate metabolism, a propionate metabolism, or a pyruvate metabolism (Table 18). A functional

translation of the KEGG Orthology Pathways (*i.e.*, KO numbers) and their respective metabolic ontology classification is provided in Table 19 as reference. Significantly, as shown in Table 18, there are only two computed network ecologies that did not harbor at least one pathway related to secondary bile acid biosynthesis, butyrate metabolism, propionate metabolism, or a pyruvate metabolism, suggesting both likely importance of these pathways to the metabolism of a large number of gastrointestinal ecologies, and the importance of these pathways to catalyzing a shift from a disease to a health state in the example cases of CDAD and Type 2 Diabetes.

Example 16. Use of Biolog assay to Generate a Nutrient Utilization Functional Profile of an OTU or Consortium of OTU

[0375] Metabolic capabilities of individual organisms or a consortia of organisms can be determined using Biolog technology in which metabolic activity is detected by measurement of NADH production using a redox sensitive dye. Carbon source or other metabolic capabilities of a single species can be determined, as described below. Carbon source utilization of an ecology or network can also be assessed using the same methods.

[0376] A screen was performed to test the ability of Clostridium difficile and potential competitor species to utilize a panel of 190 different carbon sources. The screen was carried out using PM1 and PM2 MicroPlates (Biolog #12111, #12112), IF-0a base media (Biolog #72268) and Biolog Redox Dye Mix D (Biolog #74224). For each strain, a 1 uL aliquot from -80° C glycerol stock was streaked out for single colonies to solid Brucella Blood Agar plates (BBA) (Anaerobe Systems #AS-111) and incubated anaerobically at 37° C for 24 hr. A single colony was then re-streaked to a BBA plate and incubated anaerobically at 37° C for 24 hr. The MicroPlates were pre-reduced by incubating for at least 24 hr in a hydrogen free anaerobic environment before use. All liquid media and supplements used were pre-reduced by placing them in an anaerobic chamber with loose lids for at least 24 hr before use. Alternatively, combinations of bacteria can also be tested.

[0377] The base media for inoculation was prepared by adding 0.029 mL of 1M potassium ferricyanide to 0.240 mL of Dye Mix D followed by addition of 19.7 mL of IF-0a, 4 mL sterile water and 0.024 mL 0.5 mM menadione. For some species, the concentrations of potassium ferricyanide and menadione were adjusted to achieve the optimal redox balance or to test multiple redox conditions. Potassium ferricyanide was tested at a final concentration of 0.38, 0.12, 0.038 and 0.06 mM. Menadione was tested at a final concentration of 0.5, 0.16 and 0.05 μM. In total, this yields 9 redox conditions for testing. Reduction of the tetrazolium dye that forms the basis for the endpoint measurement was sensitive to the redox state of each bacterial culture, and thus to the ratio of menadione to potassium ferricyanide. It was therefore important to test various ratios for each bacterial isolate and was also important in some cases to test a species at multiple menadione / potassium ferricyanide ratios in order to detect all conditions in which a possible nutrient utilization

was detectable. Some species were tested beyond the 20 hr time point to detect all conditions resulting in a positive result. In these cases plates were read at 20, 44 or 96 hr.

[0378] Using a sterile, 1 μL microbiological loop, a loopful of biomass was scraped from the BBA plate and resuspended in the base media by vortexing. The OD was adjusted to 0.1 at 600 nm using a SpectraMax M5 plate reader. The bacterial suspension was then aliquoted into each well of the PM1 and PM2 plates (100 μL per well). The plates were incubated at 37°C for 20 hr in a rectangular anaerobic jar (Mitsubishi) with 3 anaerobic, hydrogen-free gas packs (Mitsubishi AnaeroPack). After 20 hr, OD at 550 nm was read using a SpectraMax M5 plate reader. Wells were scored as a weak hit if the value was 1.5x above the negative control well, and a strong hit if the value was 2x above the negative control well. The results are shown in the Table in Figure 4.

[0379] The following list of nutrient sources were tested: L-Arabinose, N-Acetyl-D-Glucosamine, D-Saccharic Acid, SuccinicAcid, D-Galactose, L-AsparticAcid, L-Proline, D-Alanine, D-Trehalose, D-Mannose, Dulcitol, D-Serine, D-Sorbitol, Glycerol, L-Fucose, D-Glucuronic Acid, D-Gluconic Acid, D, L-alpha-Glycerol-Phosphate, D-Xylose, L-Lactic Acid, Formic Acid, D-Mannitol, L-Glutamic Acid, D-Glucose-6-Phosphate, D-Galactonic Acid-gamma-Lactone, D,L-Malic Acid, D-Ribose, Tween 20, L-Rhamnose, D-Fructose, Acetic Acid, alpha-D-Glucose, Maltose, D-Mellibiose, Thymidine, L-Asparagine, D-Aspartic Acid, D-Glucosaminic Acid, 1,2-Propanediol, Tween 40, alpha-Keto-Glutaric Acid, alpha-Keto-ButyricAcid, alpha-Methyl-D-Galactoside, alpha-D-Lactose, Lactulose, Sucrose, Uridine, L-Glutamine, M-Tartaric Acid, D-Glucose-1-Phosphate, D-Fructose-6-Phosphate, Tween 80, alpha-Hydroxy-Glutaric-gamma-lactone, alpha-Hydroxy Butyric Acid, beta-Methyl-D-Glucoside, Adonitol, Maltotriose, 2-Deoxy Adenosine, Adenosine, Glycyl-L-Aspartic Acid, Citric Acid ,M-Inositol ,D-Threonine, Fumaric Acid, Bromo Succinic Acid, Propionic Acid, Mucic Acid, Glycolic Acid, Glyoxylic Acid, D-Cellobiose, Inosine, Glycyl-L-Glutamic Acid, Tricarballylic Acid,L-Serine, L-Threonine, L-Alanine, L-Alanyl-Glycine, Acetoacetic Acid, N-Acetyl-beta-D-Mannosamine, Mono Methyl Succinate, Methyl Pyruvate, D-Malic Acid, L-Malic Acid,Glycyl-L-Proline, p-Hydroxy Phenyl Acetic Acid, m-Hydroxy Phenyl Acetic Acid, Tyramine, D-Psicose, L-Lyxose, Glucuronamide, Pyruvic Acid, L-Galactonic Acid-gamma-Lactone,D-Galacturonic Acid,Pheylethyl-amine,2-aminoethanol, Chondroitin Sulfate C, alpha-Cyclodextrin, beta-Cyclodextrin, gamma-Cyclodextrin, Dextrin, Gelatin, Glycogen, Inulin, Laminarin, Mannan, Pectin, N-Acetyl-D-Galactosamine, N-Acetyl-Neuramic Acid, beta-D-Allose, Amygdalin, D-Arabinose, D-Arabitol, L-Arabitol, Arbutin, 2-Deoxy-D-Ribose, I-Erythritol, D-Fucose, 3-0-beta-D-Galacto-pyranosyl-D-Arabinose, Gentibiose, L-Glucose, Lactitol, D-Melezitose, Maltitol, alpha-Methyl-D-Glucoside, beta-Methyl-D-Galactoside, 3-Methyl Glucose, beta-Methyl-D-GlucoronicAcid, alpha-Methyl-D-Mannoside, beta-Metyl-D-Xyloside, Palatinose, D-Raffinose, Salicin, Sedoheptulosan, L-Sorbose, Stachyose, D-Tagatose, Turanose, Xylitol, N-Acetyl-D-Glucosaminitol, gamma-Amino Butyric Acid, delta-Amino Valeric Acid, Butyric Acid, Capric Acid, Caproic Acid, Citraconic Acid, Citramalic Acid, D-Glucosamine, 2-Hydroxy Benzoic Acid, 4-

Hydroxy Benzoic Acid, beta-Hydroxy Butyric Acid, gamma-Hydroxy Butyric Acid, alpha-Keto Valeric Acid, Itaconic Acid, 5-Keto-D-Gluconic Acid, D-Lactic Acid Methyl Ester, Malonic Acid, Melibionic Acid, Oxalic Acid, Oxalomalic Acid, Quinic Acid, D-Ribino-1,4-Lacton, Sebacic Acid, Sorbic Acid, Succinamic Acid, D-Tartaric Acid, L-Tartaric Acid, Acetamide, L-Alaninamide, N-Acetyl-L-Glutamic Acid, L-Arginine, Glycine, L-Histidine, L-Homserine, Hydroxy-L-Proline, L-Isoleucine, L-Leucine, L-Lysine, L-Methionine, L-Ornithine, L-Phenylalanine, L-Pyroglutamic Acid, L-Valine, D,L-Carnithine, Sec-Butylamine, D,L-Octopamine, Putrescine, Dihydroxy Acetone, 2,3-Butanediol, 2,3-Butanone, 3-Hydroxy 2-Butanone.

[0380] Additionally, one of skill in the art could design nutrient utilization assays for a broader set of nutrients using the methods described above including complex polysaccharides or prebiotics.

[0381] A similar screen can be performed to test the utilization of vitamins, amino acids, or cofactors. In these instances, Biolog MicroPlates for screening of vitamins, amino acids or cofactors that are of interest would be used in place of the PM1 and PM2 plates, for example PM5. Table 2 contains a list of representative vitamins, minerals, and cofactors. For each strain tested, a universal carbon source such as glucose will be used as a positive control to demonstrate reduction of the tetrazolium dye under the specific conditions of the assay.

Example 17. In vitro Screening of microbes for 7-alphadehydroxylase activity

[0382] Cultures of individual microbes are grown overnight and frozen for later use as described according to Example 9. The sodium salts of CA, CDCA, GCA, GCDCA, TCA, and TCDCA (Sigma) are obtained and prepared as aqueous stock solutions. For initial screening to define organisms capable of 7-alphadehydroxylation reactions, growth media are prepared containing 0.4 mM of each bile salt. Cultures are inoculated from a 1:100 dilution of the frozen stock into the media and grown in an anaerobic chamber for 24-48 hours, or until the culture is turbid. Two mL of culture is acidified by the addition of 1 mL of 2N HCl and 100 ug of 23-nordeoxycholic acid (Steraloids) as an internal reference standard. The acidified mixture is extracted twice with 6 mL of diethyl ether. The organic extracts are combined and then evaporated and derivatized to methyl esters with diazomethane. Gas chromatography is performed on a 7 ft (ca. 2 m) 3% OV-1 column at 260°C and a 3% OV-17 column at 250°C after trimethylsilylation of the methylated bile acids with Tri-Sil (Pierce, Rockford, Ill.). The retention times of the silylated bile acids are compared with those of reference products representing CA, CDCA, DCA and LCA.

[0383] For strains showing 7-alphadehydroxylase activity, a kinetic assessment is performed by harvesting a growing culture of each organisms of interest, washing and resuspending in fresh media at a concentration of between 108 to 1010 cfu/mL. The sodium salts of CA, CDCA, GCA, GCDCA, TCA, and TCDCA are then added at 0.5 to 5 mM and the resulting culture is sampled at 1, 2, 4 and 8 hours. The sample is analyzed as described above to find organisms with maximal activity. Highly

active strains are selected for further incorporation into microbial compositions that exhibit maximal 7-alphadehydroxylase activity.

Example 18. In vitro Screening of Microbes for Bile Salt Hydrolase Activity

[0384] Cultures of individual microbes are grown overnight and frozen for later use as described according to Example 9. The sodium salts of GCA, GCDCA, TCA, and TCDCA (Sigma) are obtained and prepared as aqueous stock solutions. Overnight, actively growing cultures are combined with 0.5 to 5 mM of conjugated bile acid and allowed to incubate for 24-48 hours. To analyze cultures, 0.5 mL of culture is first centrifuged at 3,000 x g for 10 min to remove the bacteria, and is then acidified with 5 uL of 6 N HCl. This acidified supernatant is combined with an equal volume of methanol containing 4 mM of 23-nordeoxycholic as an internal standard. The samples are vortexed for at least 2 min and clarified by centrifugation at 1000 x g for 15 min. Samples are filtered through a 0.2 um filter prior to HPLC analysis according to the method described by Jones et al 2003 J Med Sci 23: 277-80. Briefly, the isocratic method is performed on a reversed-phase C-18 column (LiChrosorb RP-18, 5m, 250 x 4.6 mm from HiChrom, Novato, CA, USA). Acetate buffer is prepared daily with 0.5 M sodium acetate, adjusted to pH 4.3 with o-phosphoric acid, and filtered through a 0.22m filter. The flow is 1.0 mL/min and the detection is performed at 205 nm. The injection loop is set to 20 uL.

[0385] For strains showing bile salt hydrolase activity, a kinetic assessment is performed by harvesting a growing culture of each organisms of interest, washing and resuspending in fresh media at a concentration of between 108 to 1010 cfu/mL. The sodium salts of GCA, GCDCA, TCA, and TCDCA are then added at 0.5 to 5 mM and the resulting culture is sampled at 1, 2, 4 and 8 hours. The sample is analyzed by HPLC as described above to find organisms with maximal activity. Highly active strains are selected for further incorporation into microbial compositions that exhibit maximal bile salt hydrolase activity.

Example 19. In vitro Screening of Microbial Communities for 7-alpha-dehydroxylase activity

[0386] Measurement of the conversion of 7-alpha-hydroxyl bile salts (primary bile salts) to 7-dehydroxy-bile salts (secondary bile salts) by single bacterial strains or bacterial communities is determined in an in vitro assay, and can be used to screen a library of organisms, whole communities or subsets of communities using limiting dilutions to identify simpler compositions. Communities to be studies include cecal or fecal communities from animals with altered gastrointestinal microbiota due to antibiotics, diet, genetics, enterohepatic metabolism, or other experimental perturbations that cause GI alterations, or from human fecal samples from healthy individuals or those with altered gastrointestinal microbiomes due to antibiotics, diet, enterohepatic metabolism dysfunction, metabolic dysfunction, or gastrointestinal infection. Dilutions or subsets of these communities (such as could be generated by selective culturing for of the whole community to enrich for aerobes, anaerobes, Gram

positives, Gram negatives, spore formers or using other microbiological selections known to one skilled in the art) can be utilized to identify a group of organisms required for a particular multi-step conversion.

[0387] To assay 7-alpha-dehydroxylation activity in vitro, an enzymatic assay is established to quantify the amount of 7-alphahydroxy bile acid in a sample. Recombinant 7-alpha-hydroxysteroid dehydrogenase (7-alpha-HSDH) from E. coli (MyBiosource.com) is an enzyme that oxidizes the 7-hydroxy group to a ketone and simultaneously reduces NAD+ to NADH + H+. The production of NADH is monitored at 340 nm using the extinction co-efficient of 6.2 x 103 M-1 cm-1.

[0388] A community of microbes is prepared according to Example 9 or, alternatively a preparation of cecal or fecal bacteria from mice or from human feces or a dilution thereof, or an enriched community thereof, can be tested after being washed 5 times to remove bile acids from the matrix. To the initial sample, a mixture of one or more primary bile acids including but not limited to CA, CDCA or any of their taurine or glycine conjugates is added to a final total concentration of 0.5-5 mM. An initial 100 uL aliquot is removed and heated at 55°C for 15 min to quench further enzymatic activity. The bacterial composition is then incubated under anaerobic conditions at 37°C, and aliquots are removed sequentially after 30 min, 1 hour, 2 hours, 4 and 8 hours and heated as per above. An assay mix is prepared by combining 0.9 mL glycine-NaOH buffer pH 9.5, 50 uL of 53 mM NAD+ (Sigma), and 20 uL of freshly prepared 7-alpha-HSDH (4 mg/mL in distilled water). 80 uL of assay mix is combined with 20 uL of each aliquot in a 96-well microtiter plate and incubated at 37°C on a SpectraMax m5 plate reader, monitoring A340. The incubation is allowed to proceed until the A340 value achieves its maximum. Total 7-alpha-hydroxyl bile acid is determined using the extinction coefficient for NADH. Changes due to dehydroxylation by the bacterial composition are calculated by subtracting the final value at any timepoint from the initial value.

[0389] Microbial communities of interest can be further fractionated using methods described in Example 9.

Example 20. In vitro evaluation of mixed microbial cultures for bile acid metabolism

[0390] Candidates strains identified in Examples 17, 18 and 19 above are tested using the methods defined for bile salt hydrolase activity and 7-alphadehydroxylase activity are combined in communities to evaluate synergies among strains and define ecologies for further testing in animal models. Synergies include: i) the potential for more rapid conversion from conjugated primary bile salts to unconjugated, dehydryoxylated bile acids; ii) the potential for a broader range of products than determined by the additive combination of activities; iii) equivalent activity at a lower concentration (cfu) of the individual strains. Combinations exhibiting such synergies are particularly favored for subsequent in vivo testing. Another important function of a community is to remove endproducts of a microbial conversion so as to avoid inhibition of growth through product accumulation. For bile acid conversion, communities can optionally include organisms capable of degrading taurine, using it both

as a carbon and nitrogen source and using the sulfonic acid group as an electron acceptor in fermentation.

Example 21. Combinations of Bacterial Compositions For SCFA Production Under Variable Conditions

[0391] Combinations of synergistic bacterial compositions may be selected such that the composition is capable of producing SCFA under a wide range of in vitro conditions when the entire mixture is tested together. That is, a combination of bacterial compositions comprises multiple pairs of organisms that, together with a complex carbon source, are capable of synthesizing SCFA. Combinations may be constructed that are capable of producing a given set of SCFAs, for example butyrate and proprionate, but not acetate, or that produce butyrate, proprionate and acetate, but that the acetate is then used by another organism as a carbon source. A number of specific combinations of final SCFAs may be generated by communities designed by one skilled in the art. Construction of bacterial combinations follows the protocol described in Example 9.

Example 22. De novo Design of Network Ecologies with Specific Functional Properties

[0392] The role of the microbiome in mediating and influencing human metabolic function is well established. Microbes produce secondary bile acids (as example, Louis P, Flint HJ. 2009. Diversity, metabolism and microbial ecology of butyrate-producing bacteria from the human large intestine. FEMS Microbiol Lett 294: 1–8.), short chain fatty acids (for example, Smith PM et al. 2013 Science. The microbial metabolites, short-chain fatty acid regulate colonic Treg cell homeostasis 341: 569-73) as well as numerous other functional metabolites that influence immunity and metabolic health of the human host.

[0393] To identify consortia of microbes suitable for the use as therapeutics, to influence host metabolic functions, and to treat microbial dysbiosis one can computationally derive in silico network ecologies that possess specific metabolic functions such as, but not limited to, a single or multiple metabolic nodes in the functional pathways involved in secondary bile acid biosynthesis (Figure 12), butyrate metabolism (Figure 13), propionate metabolism (Figure 14), or pyruvate metabolism (Figure 15). As additional examples, network ecologies can be in silico designed to target host genes involved in important host:microbe innate and adaptive immune responses through targets such as the Toll-like receptors (TLRs) and nucleotide-binding oligomerization domains (NOD) (Saleh M, Trinchieri G. 2011. Innate immune mechanisms of colitis and colitis-associated colorectal cancer. Nat Rev Immunol 11: 9–20. and Knight P, Campbell BJ, Rhodes JM. 2008. Host-bacteria interaction in inflammatory bowel disease. Br Med Bull 88: 95–113.). In addition, the functional pathways to target for in silico network ecology design can be empirically defined by comparing the microbiomes of samples derived from different phenotypes such as but not limited to a state of disease and a state of health. For example, one can compare the microbiome and corresponding metabolic functional profile of individuals with and without insulin resistance. Vrieze et al. have shown that treatment

with vancomycin can reduce the diversity of the microbiome and result in a small, but statistically significant change in peripheral insulin sensitivity. Similar changes are not observed following amoxicillin treatment (Vrieze, A et al., 2013, J Hepatol. Impact of oral vancomycin on gut microbiota, bile acid metabolism, and insulin sensitivity dx.doi.org/10.1016/j.jhep.2013.11.034). Decreased insulin sensitivity was associated with a decrease in the presence of secondary bile acids DCA, LCA and iso-LCA and an increase in primary bile acids CA and CDCA increased. In another example, Applicants can compare the microbiome and metabolomic profile of healthy individuals to those with CDAD disease. In yet another example, Applicants can compare the microbiome and metabolomic profile of healthy individuals to those that harbor IBD, IBS, Ulcerative Colitis, Crohn's Disease, Type-2-Diabetes, or Type-1-Diabetes.

[0394] For both CDAD and insulin resistance, Applicants can define the functional metabolic profile of the respective disease and health microbiomes using the 16S and metagenomic genomic methods outlined in Example 15. In another embodiment, Applicants can use the transcriptomic and metabolomic methods outlined in Example 15. In another embodiment we use functional metabolic information garnered from the literature and derived from functional screens such as but not limited to Biolog MicroPlates (see Example 16). From these profiles, Applicants can generate a metabolic function matrix for both the disease state and the health state. This matrix is comprised of columns of OTUs and rows of KEGG Orthology Pathways delineated as described in Example 15. A metabolic function matrix can be generated for both the disease state and the health state. From these disease and health matrices, Applicants can compute a delta-function matrix (*i.e.* difference matrix) that defines the OTUs, the relative abundance of the metabolic pathways they harbor, and the difference in the relative abundance between the disease and health state. In another embodiment, the relative abundances are discretized to be a binary, ternary, or quaternary factor. This delta-function matrix defines the differences in the microbiome distinguishing the disease state from the health state.

[0395] One can then design a network ecology with the desired functional characteristics described by the delta-function matrix. In one embodiment, one can use a greedy algorithm to optimize for the most parsimonious solution to the delta-function matrix. One can design towards (*i.e.* select) the minimal number of OTUs to capture the full breadth of KEGG Orthology Pathways that are represented in the health state. In short, the greedy algorithm repetitively samples the OTUs spanning the greatest number of health associated KEGGs until the desired breath of KEGGs is obtained to define a functional network ecology comprised of specific OTUs. In another embodiment, one can optimize the greedy algorithm to weigh OTUs that are from specific phylogenetic clades. In another embodiment, one can start with the computationally derived network ecologies derived using the methods defined in Example 5 to both seed and constrain the greedy algorithm to return functional network ecologies that embody the co-occurrence relationships that exist between OTUs. Microbial therapeutic compositions comprised of the OTUs of the computed network ecologies are constructed using the methods defined in Example 9. In one embodiment, constraints around network ecologies

are defined by networks found in specific individuals. In another embodiment, strains of each OTU that are used for construction preferentially are selected from strains isolated from the same individual since these strains are evolutionary co-evolved and have an increased likelihood of functional synergy.

[0396] In another embodiment, Applicants computationally defined in silico a network ecology with the explicit capacity to produce butyrate. In this embodiment, Applicants defined the health state in terms of the metabolic pathways and associated gene products required for the metabolism of non-digestable carbohydrates via fermentation by colonic bacteria and by the gene products leading from mono- and di-saccharides and simple substrates such as acetate and lactate to butyrate (Figures 12-15). We then used the IMG functional database (http://img.jgi.doe.gov) of OTU KEGG Orthology Pathways (*i.e.* ko_id) to generate a metabolic function matrix comprised of columns of OTUs and rows of KEGG Orthology Pathways delineated as described in Example 15. This matrix was restricted to OTUs known to reside in the gastrointestinal tract. From this metabolic function matrix we used the greedy algorithm described above to design network ecologies capable of butyrate production.

Example 23. Identification of Organisms Harboring butyryl-CoA: acetate CoA Transferase Genes

[0397] A panel of putative butyrate forming bacteria can be screened for the presence of butyryl-CoA: acetate CoA transferase genes to define candidates for SCFA production. Bacteria are scraped from isolated colonies on agar plates or from liquid culture (media selected from Example 9) and subjected to DNA isolation in 96-well plates. 1 µl of microbial culture or an amount of a bacterial colony approximately 1 µL in volume is added to 9 µl of Lysis Buffer (25mM NaOH, 0.2 mM EDTA) in each well of a 96 well, thin walled PCR plate, sealed with an adhesive seal, and the mixture is incubated at 95°C for 30 minutes. Subsequently, the samples are cooled to 4°C and neutralized by the addition of 10 µl of Neutralization Buffer (40 mM Tris-HCl) and then diluted 10-fold in Elution Buffer (10 mM Tris-HCl), at which point the genomic DNA is suitable for use in downstream amplifications such as PCR amplification. Alternatively, genomic DNA is extracted from pure microbial cultures using commercially available kits such as the Mo Bio Ultraclean® Microbial DNA Isolation Kit (Mo Bio Laboratories, Carlsbad, CA) or by standard methods known to those skilled in the art.

[0398] Degenerate primers are designed to selectively amplify the gene for butyryl-CoA:acetate CoA transferase based on published genomic sequences. Examples of primers are BCoATforward: 5' GCIGAICATTTCACITGGAAYWSITGGCAYATG; and BCoATreverse: 5' CCTGCCTTTGCAATRTCIACRAANGC, where I = inosine; N = any base; W = A or T; Y = T or C; S = C or G. Amplification is as follows: 1 cycle of 95°C for 3 min; 40 cycles of 95°C, 53°C, and 72°C for 30 s each with data acquisition at 72°C; 1 cycle each of 95°C and 55°C for 1 min; and a

stepwise increase of the temperature from 55 to 95°C (at 10 s/0.5°C) to obtain melting curve data and evaluate product complexity. The target amplicon is about 530 nt in length.

Example 24. Identification of Organisms Harboring butyrate-kinase Genes

[0399] Butyrate may be produced by substrate level phosphorylation of butyrylCoA by butyrate-kinase and subsequent phosphorylation of ADP to generate ATP and butyrate. DNA isolation and PCR amplification was performed as in Example 23 with the exception that the following primers were used: BUKfor: 5' GTATAGATTACTIR- YIATHAAYCCNGG; and BUKrev: 5' CAAGCTCRTCIACIACIACNGGRTCNAC, where I = inosine; N = any base; R = A or G.

Example 25. Identification of Organisms with butyryl-CoA: acetate CoA transferase Enzymatic Activity

[0400] Bacterial strains are grown overnight in an anaerobic chamber at 37°C in pre-reduced media selected from those described in Example 9. 10 mL of the bacterial culture is harvested by centrifugation at 10,000 rpm for 10 min, cooled to 4°C on ice, and disrupted by sonication as described (Duncan, S. et al., 2002 Appl Environ Microbiol Acetate utilization and butyryl coenzyme A (CoA):acetate-CoA transferase in butyrate producing bacteria from the human large intestine 68: 5186-90). ButyrylCoA: acetate CoA transferase activities are determined by the method of Barker, scaled for application to a microtiter plate (Barker HA, et al., 1955 Methods Enzymol 1: 599-600).

Example 26. Identification of organisms with butyrate-kinase, propionate-kinase and acetate-kinase enzymatic activity

[0401] Bacterial strains are grown overnight in an anaerobic chamber at 37°C in pre-reduced media selected from those described in Example 9. 10 mL of the bacterial culture is harvested by centrifugation at 10,000 rpm for 10 min, cooled to 4°C on ice, and disrupted by sonication as described (Duncan, S. et al., 2002 Appl Environ Microbiol Acetate utilization and butyryl coenzyme A (CoA):acetate-CoA transferase in butyrate producing bacteria from the human large intestine 68: 5186-90). Butyrate-, propionate-, and acetate-kinase activities were determined by colorimetric the method of Rose (Rose IA, 1955 Methods Enzymol Acetate kinase of bacteria 1: 591-5).

Example 27. Characterization of propionate or butyrate production from a variety of carbon sources

[0402] Strains identified as having either genes for butyrate or propionate fermentation or having the corresponding enzymatic activities are assayed in vitro using a variety of simple carbon sources for the production of propionate and butyrate. Bacteria are grown overnight in complex media selected from Example 9 in an anaerobic chamber at 37°C. When cultures are visibly turbid, the bacteria are pelleted at 10,000 x g for 10 min, the spent media is removed, and they are resuspended in pre-reduced minimal media containing essential vitamins and cofactors (pyridoxamine, p-aminobenzoic acid, biotin, nicotinic acid, folic acid, nicotinamide, choline, pantothenate, riboflavin or vitamin), divalent mineral salts (including the chloride salts of Mg2+, Ca2+ and Mn2+), and organic

nitrogenous nutrients (especially glycine, glutamate or asparagine) but lacking carbohydrate as a carbon source. Alternatively, strains may be resuspended in a dilution of the original rich media, for instance a 1:10 or 1:100 dilution, such that essential factors are available but a required carbon source is limiting.

[0403] Various carbon sources are added to individual cell suspensions. These include acetate and D and L isomers of lactate, simple sugars including glucose, galactose, mannose, arabinose, xylose or any other naturally sugar, amino sugars such as N-acetyl glucosamine, galactosamine, sialic acid or glucosamine, sugar alcohols such as glycerol, erythritol, threitol, mannitol, inositol or sorbitol. In addition, the cell suspensions are individually incubated with complex carbon sources including di-, tri-, oligo- and polysaccharide carbon sources including fructans, starches, cellulose, galactomannans, xylans, arabinoxylans, pectins, inulin, and fructooligosaccharides. Tested carbon sources also include glycopeptides and glycoproteins, such as mucin. The cell suspension is incubated overnight in a sealed 96-well plate in order prevent the escape of volatile products.

[0404] At the end of the incubation period, the production of propionate, butyrate and other SCFAs is determined according to the following protocol:

[0405] Reagents

- Internal Standard: 2-ethylbutyric acid, 2-EBA (100 mM)
- SCFA Mixed Standard: formic acid 10 mM, acetic acid 30 mM, propionic acid 20 mM, isobutyric acid 5 mM, n-butyric acid 20 mM, n-valeric acid 5 mM, isovaleric acid 5 mM, sodium lactate 10 mM, sodium succinate 10 mM, phenylacetic acid 5 mM
- MTBSTFA Derivatizing Reagent (N-Methyl-N-(tert-butyldimethylsilyl)- trifluoroacetamide), purchased from Regis Technologies
- Concentrated HCl
- Deionized Water
- Diethyl ether (unstabilized)
- Hexane

[0406] Linearity Standards Preparation: Linearity Standard 1 is prepared using straight SCFA Standard. Linearity Standard 2 is prepared using 100 uL of SCFA Standard and 900 uL of water. Linearity Standard 3 is prepared using 100 uL of Linearity Standard 2 and 900 uL of water.

[0407] SCFA Extraction: Extractions of samples (Media and Culture Supernatant), water blanks, and linearity standards were prepared in 4-mL vials using 250 uL of sample, blank, or standard, 250 uL of concentrated HCl, and 50 uL of Internal Standard (2-EBA). Once combined, the sample, standards, and blanks were vortexed and allowed to stand for about 5-10 minutes. Diethyl ether (2000 uL) was added to each of the samples, standards and blanks, and each was liquid-liquid extracted for approximately 2 minutes. The aqueous and organic phases of the extracted samples, standards and blanks were allowed to separate. Once the layers separated, 1000 uL of the ether layer was

transferred to 2-mL micro-centrifuge tubes and centrifuged at 14k for 2 minutes to remove any remaining water.

Sample/Standard/Blank*	250 uL
HCl	250 uL
Internal Standard (2-EBA)	50 uL
Ether	2000 uL

[0408] *substitute deionized water for blank preparations

[0409] Derivatization: Derivatization of all samples, blanks and standards was conducted in HPLC vials using 175 uL of the upper ether layer of samples or standards and 25 uL of MTBSTFA derivatizing reagent. The reaction mixture was vortexed and allowed to sit at RT for 24 hours. After 24 hours, the ether was removed using a gentle stream of nitrogen, and the residual material was dissolved in 50 uL of hexane. (Note: solvent was removed until no further change in volume was apparent, ~ 5 – 10 min). The derivatized solutions were transferred to small-volume inserts for GC-MS analysis.

[0410] An aliquot of the resulting derivatized material is injected into a gas chromatograph (Hewlett Packard 6890) coupled to a mass spectrometer detector (Agilent Technologies 5973). Analyses are completed using DB-5MS (60 m, 0.25 mm i.d., 0.25 mm film coating; P. J. Cobert, St. Louis, MO) and electronic impact (70 eV) for ionization. A linear temperature gradient is used. The initial temperature of 80°C is held for 1 min, then increased to 280°C (15°C/min) and maintained at 280°C for 5 min. The source temperature and emission current are 200°C and 300 mA, respectively. The injector and transfer line temperatures are 250°C. Quantitation is completed in selected ion monitoring acquisition mode by comparison to labeled internal standards [formate was also compared to acetate-13C1,d2]. The m/z ratios of monitored ions for formic acid, acetic acid, propionic acid, butyric acid, acetate, proprionate and butyrate are as follows: 103 (formic acid), 117 (acetic acid), 131 (propionic acid), 145 (butyric acid), 121 ([2H2]- and [1-13C]acetate), 136 ([2H5]propionate), and 149 ([13C4]butyrate).

[0411] At the completion of the experiment, a database is generated for each tested organism defining what carbon sources yield which SCFAs. In each case where a microbe is capable of making propionate or butyrate from acetate, lactate, a simple sugar including a disaccharide, an amino sugar or sugar alcohol it is scored as positive for SCFA production. Also noted is whether organisms are capable of utilizing complex carbon sources such as polysaccharides to produce SCFA and which SCFAs are produced.

Example 28. Identification of Organisms Capable of Metabolizing Complex Carbon Sources Including Polysaccharides and Steroids

[0412] Individual strains are screened for their ability to metabolize complex carbon sources including polysaccharides and steroids (such as bile salts) according to Example 16 to determine bacterial strain nutrient utilization. For a more complete characterization, specialized plates are constructed utilizing polysaccharide carbon sources including fructans, starches, cellulose, galactomannans, xylans, arabinoxylans, pectins, inulin, and fructooligosaccharides as well as carbon sources including glycopeptides and glycoproteins (such as mucin). These can be made to order by Biolog.

[0413] At the end of the experiment, a catalogue of is generated for each tested organism defining what carbon sources it can utilize.

Example 29. Construction of Cross Feeding Compositions

[0414] Data from Examples 27 and 28 are analyzed to determine combinations where one organism can make SCFAs from at least one simple carbon source but not from at least one complex carbon source (a polysaccharide or a glycoprotein), and another organism cannot make SCFAs from a simple carbon source but can utilize at least one complex carbon source as a metabolic substrate.

[0415] In these cases, a bacterial mixture is made combining a washed overnight culture of the SCFA producer and a washed overnight culture of the SCFA non-producer in a minimal media as described in Example 27 with the addition of the at least one complex carbon source. The bacterial mixture is incubated anaerobically overnight at 37°C in minimal media or a 1:10 or 1:100 dilution of rich media, and the next day is worked up according to Example 27 in order to detect whether SCFA has been produced. Control cultures include each microbe cultured individually, and the bacterial mixture cultured overnight without the complex carbon source.

[0416] Bacterial mixtures in which control cultures do not yield SCFA but the complete mixture does define synergistic bacterial compositions. Synergistic bacterial compositions may be tested for further effects in a variety of in vitro or in vivo models, with and without the complex carbon source, which may be considered a component of one embodiment of the synergistic bacterial composition.

Example 30. In vivo Validation of Bacterial Composition Efficacy In For Amelioration of Leaky Gut

[0417] A murine model for "leaky gut syndrome" is constructed by intraperitoneal injection of pregnant C57BL/6N mice (Charles River, Wilmington, MA) with 20 mg/kg poly(I:C) in 200 uL of saline on embryonic day 12.5. Control pregnant mice are injected with 200 uL of saline only (Hsiao EY et al., 2013 Cell Microbiota modulate behavioral and physiological abnormalities associated with neurodevelopmental disorders 155: 1451-63).

[0418] Pups are randomly selected for treatment with a single bacterial composition or a combination of bacterial compositions at the time of weaning (Day 20-22) and received oral gavage

every other day for 6 days. In addition, groups of animals receive mouse chow supplemented with the complex carbohydrate relevant to the bacterial composition(s) that is (are) dosed. Control groups (saline injections) receive comparable combinations of bacterial compositions, with and without the complex carbohydrate.

[0419] Animals are tested at adolescence (3 weeks post-weaning) and adulthood (8 weeks post weaning) for leaky gut. Mice are fasted for 4 hr before gavage with 0.6 g/kg 4 kDa FITC-dextran (Sigma Aldrich). Four hours later, serum samples are read for fluorescence intensity at 521 nm using an xFluor4 spectrometer (Tecan). Increased fluorescence is taken as evidence of leaky gut, while decreased fluorescence is evidence for amelioration of leaky gut induced by poly(I:C) treatment. Preferred bacterial compositions decrease leak gut in mice.

Example 31. In vivo Validation of Bacterial Composition Efficacy in Germ Free Mice Conventionalized with Human Obese Microbiota

[0420] Ridaura et al. (2013) showed that germ-free (GF) mice conventionalized with microbiota from female twins discordant for obesity showed taxonomic and phenotypic features of the human donor's microbiota. Mice receiving obese twin microbiota (Ob mice) showed significantly greater body mass and adiposity than recipients of lean twin microbiota (Ln mice). Furthermore, they observed that cohousing Ob mice and Ln mice prevented development of the obese phenotype in the Ob mice and showed that the rescue correlated with invasion of members of the microbiota from the Ln mice into the Ob mice.

[0421] Ob and Ln mice prepared as described by Ridaura et al. (2013) can be used to test the therapeutic potential of a bacterial composition for obesity. Ob and Ln mice are generated by introducing via oral gavage fecal samples from twins discordant for obesity into 8-9 week old adult male germ-free C57BL/6J mice. One gnotobiotic isolator is used per microbiota sample and each recipient mouse is individually caged within the isolator. The obese twin must have BMI > 30 kg/m2 and the pair must have a sustained multi-year BMI difference of at least 5.5 kg/m2. Recipient mice are fed a low fat (4% by weight) high in plant polysaccharide (LF-HPP), autoclaved mouse chow (B&K Universal, East Yorkshire, U.K. diet 7378000).

[0422] To prepare the fecal samples for gavage into the GF mice, fecal samples provided by donors are frozen immediately after production, stored at -80°C. Samples are homogenized by mortar and pestle while submerged in liquid nitrogen and a 500 mg aliquot of the pulverized material is diluted in 5 mL of reduced PBS (PBS supplemented with 0.1% Resazurin (w/v), 0.05% L-cysteine-HCl) in an anaerobic Coy chamber (atmosphere, 75% N2, 20% CO2, 5% H2) and then vortexed for 5 min at room temperature. The suspension is settled by gravity for 5 min, and then the clarified supernatant transferred to an anaerobic crimped tube that is transported to a gnotobiotic mouse facility. Prior to transfer of the tube into the gnotobiotic isolator, the outer surface of the tube is sterilized by exposure

for 20 min to chlorine dioxide in the transfer sleeve attached to the isolator. 200 µL aliquot of the suspension is provided into the stomachs of each recipient animal by gavage.

[0423] At day 15 post-colonization, the bacterial composition containing at least 108 CFU/ml per strain is administered daily by oral gavage for 4 weeks to half of the Ob mice and half of the Ln mice. The remaining Ob mice and Ln mice are administered PBS by the same regimen. Optionally, mice can receive 0-3 days of antibiotic pre-treatment prior to administration of the bacterial composition. Alternative dosing schedules and routes of administration (*e.g.* rectal) may be employed, including multiple doses of test article, and 103 to 1010 CFU/ml per strain of a bacterial composition may be delivered. The bacterial composition may optionally be administered together or co-formulated with prebiotic(s).

[0424] Feces are collected from the cages for analysis of bacterial carriage. Total body weight, fat mass and lean body mass are measured at baseline before colonization, at days 8 and 15 post-colonization, and days 22, 29, 35, and 42 post-colonization (7, 14, 21, and 28 days after administration of the bacterial composition) using quantitative magnetic resonance analysis of body composition (EchoMRI-3in1 instrument). At time of sacrifice, epididymal fat pads are also collected and weighed. Optionally, luminal contents of the stomach, small intestine, cecum, and colon contents as well as the liver, spleen, and mesenteric lymph nodes can be collected for subsequent analysis. Alternative or additional time points may also be collected.

[0425] By the end of the treatment period with the bacterial composition, the Ob mice receiving the bacterial composition is expected to show significant differences in body composition (change in % fat mass; fat pad weight/total body weight) as compared to the Ob group receiving PBS and the Ln groups.

[0426] Optionally, at the end of the treatment period, the body composition is determined for all mice. Bacterial compositions that produce significant changes in body composition in the Ob mice (decrease in % fat mass; decrease in fat pad weight; or decrease in total body weight) as compared to control Ob mice receiving PBS are identified as therapeutic candidates.

Example 32. In vivo Validation of Bacterial Composition Efficacy In Germ Free Mice Conventionalized With Bacterial Composition and Lean/Obese Microbiota Controls

[0427] To test the potential of a bacterial composition's ability to treat obesity, 8-9 week old GF C57BL/6J mice can be conventionalized by introducing by oral gavage a) the bacterial composition, b) fecal samples from an obese female twin discordant for obesity (obese control), or c) fecal samples from the paired lean female twin (lean control). One gnotobiotic isolator is used per microbiota sample and each recipient mouse is individually caged within the isolator. The obese twin donors must have BMI > 30 kg/m2 and the donating pair must have a sustained multi-year BMI difference of at least 5.5 kg/m2. Recipient mice are fed a low fat (4% by weight) high in plant polysaccharide (LF-HPP), autoclaved mouse chow (B&K Universal, East Yorkshire, U.K. diet 7378000).

[0428] To prepare the fecal samples for gavage into the GF mice, fecal samples provided by donors are frozen immediately after production, stored at -80°C. Samples are homogenized by mortar and pestle while submerged in liquid nitrogen and a 500 mg aliquot of the pulverized material is diluted in 5 mL of reduced PBS (PBS supplemented with 0.1% Resazurin (w/v), 0.05% L-cysteine-HCl) in an anaerobic Coy chamber (atmosphere, 75% N2, 20% CO2, 5% H2) and then vortexed for 5 min at room temperature. The suspension is settled by gravity for 5 min, and then the clarified supernatant transferred to an anaerobic crimped tube that is transported to a gnotobiotic mouse facility.

[0429] To prepare the bacterial composition for gavage into the GF mice, see Example 9. Prior to transfer of tubes into the gnotobiotic isolator, the outer surface of the tube is sterilized by exposure for 20 min to chlorine dioxide in the transfer sleeve attached to the isolator. 200 µL aliquots of the fecal suspensions are provided into the stomachs of the recipient animals by gavage.

[0430] Feces are collected from the cages for analysis of bacterial carriage. Total body weight, fat mass and lean body mass are measured at baseline before colonization, at days 8, 15, 22, 29, and 35. At time of sacrifice, epididymal fat pads are also collected and weighed. Optionally, luminal contents of the stomach, small intestine, cecum, and colon contents as well as the liver, spleen, and mesenteric lymph nodes can be collected for subsequent analysis. Alternative or additional timepoints may also be collected.

[0431] By the end of the treatment period with the bacterial composition, the mice receiving the bacterial composition is expected to show body composition (change in % fat mass; fat pad weight/total body weight) and microbial composition that is similar to the lean control and that is statistically different from the obese control.

Example 33. In vivo Validation of Bacterial Composition Efficacy In Dietary Induced Obesity Mouse Model

[0432] Male C57BL/6 mice fed a high fat diet can be used to test bacterial compositions' ability to treat obesity in a diet-induced obesity (DIO mouse) prevention model. To do so, eight groups of mice (n=8) are used, with all combinations of +/- antibiotic pretreatment, bacterial composition vs. vehicle, and high fat vs. standard diet.

[0433] 4 week old male C57BL/6 mice are group housed (2-5 mice per cage) in filter top cages with autoclaved bedding, and free access to autoclaved irradiated food (LabDiet 5053, LabDiet, St. Louis, MO 63144) and autoclaved water. For groups receiving antibiotic pretreatment, drinking water is replaced by an antibiotic cocktail consisting of 10% glucose, kanamycin (0.5 mg/mL), gentamicin (0.044 mg/mL), colistin (1062.5 U/mL), metronidazole (0.269 mg/mL), ciprofloxacin (0.156 mg/mL), ampicillin (0.1 mg/mL) and vancomycin (0.056 mg/mL) (all constituents from Sigma-Aldrich, St. Louis MO) for 1 week, after which autoclaved water is returned to all cages. The mice are dosed daily with a volume of 0.2 ml containing at least 1 x 108 cfu/ml per strain daily or an equal volume of sterile PBS. Optionally, the dose may range from 5 x 106 to 5 x 1010 cfu/ml per strain and or dosing

may occur three times a week. After one week of dosing, a group (n=10) of mice dosed with vehicle and one with the bacterial composition are switched to a high fat diet (Research Diet D12492) and dosing is continued for all groups. Treatment is continued for 15 weeks following the diet shift. Alternative dosing schedules and routes of administration (*e.g.* rectal) may be employed, including multiple doses of test article, and 103 to 1010 CFU/ml per strain of a bacterial composition may be delivered. The bacterial composition may be optionally be administered together or co-formulated with prebiotic(s).

[0434] Body weight will be measured three times per week throughout the study. Blood will be drawn by submandibular bleed every three weeks, from which serum cholesterol and triglycerides will be measured. Fasting blood glucose will be measured in weeks 12 and 15 following the diet shift. At sacrifice, total body, gastrocnemius, liver, epididymal fat pad, and cecum weights are measured, and the contents of the cecum as well as one lobe of the liver are stored at -80°C. By the end of the experiment, successful treatments will have statistically significant differences in total body weight, epididymal fat pad mass, or cholesterol.

Example 34. In vivo Validation of Bacterial Composition Efficacy In Nonobese Diabetic Mouse Model of Type-1-Diabetes

[0435] To demonstrate the efficacy of the microbial composition for improving the incidence of type 1 diabetes, a type 1 diabetes mouse model described previously is utilized (*e.g.* see Markle et al 2013. Sex differences in the gut microbiome drive hormone dependent regulation of autoimmunity. Science 339: 1084). Briefly, nonobese diabetic (NOD)/Jsd (NOD) Specific Pathogen Free (SPF) female mice are housed in sterilized static caging. The animals receive a standard mouse diet (LabDiet #5015, PMI Nutrition International) and autoclaved water. All staff uses autoclaved gowns, caps, masks, shoe covers, and sterile gloves. Animal handling and cage changes are done under HEPA filtered air. The pathogen status is determined by weekly exposure of CD-1 sentinel mice to soiled bedding from the cages in the room. Quarterly serological testing of sentinels confirmed the NOD mice are negative for: Mouse Hepatitis Virus, Minute Virus of Mice, Mouse Parvovirus, Murine Norovirus, Sendai Virus, Theiler's Murine Encephalomyelitis, Retrovirus and for endo- and ectoparasites. In addition, live animals are subjected to additional, annual comprehensive testing, including necropsy, histopathology, bacteriology and parasitology testing.

[0436] To test the microbial composition for prophylactic ability to reduce, delay or prevent disease appearance, weanling NOD females (aged 22-26 days) are gavaged with 250uL the microbial bacterial composition using a 24G round tip gavage needle. Recipients are rested for 24 hours, and this procedure is repeated once. Optionally, mice can receive 0-3 days of antibiotic pre-treatment prior to administration with the bacterial composition. Alternative dosing schedules and routes of administration (*e.g.* rectal) may be employed, including multiple doses of test article, and 103 to 1010

CFU/ml per strain of a bacterial composition may be delivered. The bacterial composition may be optionally be administered together or co-formulated with prebiotic(s).

[0437] As a negative control, a group of female weanling NOD mice are gavaged with cecal contents from a female NOD mouse, and as a positive control a third group of female NOD mice are given cecal contents from a male NOD diluted 50x (v/v) and delivered in 250ul. Spontaneous development of T1D assessment is assessed biweekly by measuring glucose levels in blood and urine. Animals are checked daily and are classified as diabetic when blood glucose exceeds 16mmol/L or urine glucose exceeds 250mg/dL. Additionally, serum insulin autoantibody (IAA) is measured by a micro-IAA assay (mIAA). Briefly, 125-I labeled human insulin (Perkin Elmer) is incubated with NOD serum with and without cold (unlabeled) human insulin and the immune complex is isolated by binding to protein A and G Sepharose. The assay is performed on a 96-well filtration plate to retain Sepharose beads and radioactivity is counted on a Topcount 96-well plate beta counter or similar instrument. An index is calculated by taking the difference of cpm between wells without and with cold insulin. A positive is defined by any conventional cut-off measure including a value greater than the 99th percentile of control values, or a value 3 standard deviations beyond the mean of the control values. Furthermore Insulitis is assessed. Briefly, pancreata are dissected and immediately immersed in OCT media (Tissue-Tek, Torrance, CA), frozen in -20°C 2-methylbutane, and stored at –70°C. Preparation of frozen sections is performed with a Leica CM 3050 Cryostat (Leica Canada). To maximize analysis of independent islet infiltrates, three 5-μm sections are cut at least 400 μm apart. Pancreatic sections are stained with Mayer's hematoxylin and eosin Y (H+E, Sigma) to visualize leukocyte infiltration. Assessment of insulitis severity in pancreatic sections is performed by one skilled in the art. Briefly, islets are graded according to the following criteria: 0, no visible infiltrates; 1, peri-insulitis as indicated by peri-vascular and peri-islet infiltrates; 2, <25% of the islet interior 9 occluded by leukocytes displaying invasive infiltrates; 3, >25% but <50% of the islet interior invaded by leukocytes; or 4, invasive insulitis involving 50%-100% of the islet field.

[0438] To evaluate the microbial composition for treatment of disease, the procedure above is repeated whereby NOD nonobese diabetic (NOD)/Jsd (NOD) Specific Pathogen Free (SPF) female mice are housed and evaluated for development of diabetes by the criteria described above. Once a mouse develops diabetes it is gavaged with the microbial composition, and blood glucose, urine glucose, and insulin serum levels are evaluated by ELISA weekly to determine disease progression. 7 weeks later animals are sacrificed and insulitis is evaluated by methods described above. Optionally, mice can receive 0-3 days of antibiotic pre-treatment prior to administration with the bacterial composition. Alternative dosing schedules and routes of administration (*e.g.* rectal) may be employed, including multiple doses of test article, and 103 to 1010 CFU/ml per strain of a bacterial composition may be delivered.

Example 35. In vivo Validation of Bacterial Composition Efficacy In Nile Rat Model of Type-2-Diabetes

[0439] To test the efficacy of a microbial composition for delaying, treating or preventing the symptoms of type 2 diabetes, a Nile grass rat (Arvicanthis niloticus) model described previously is utilized (*e.g.* see Noda, K., et al. (2010). An animal model of spontaneous metabolic syndrome: Nile grass rat. The FASEB Journal 24, 2443–2453. or Chaabo, F., et al. (2010). Nutritional correlates and dynamics of diabetes in the Nile rat (Arvicanthis niloticus): a novel model for diet-induced type 2 diabetes and the metabolic syndrome. Nutrition & Metabolism 7, 29.). Nile rats, which spontaneously develop symptoms of type 2 diabetes and metabolic syndrome, are individually housed and have free access to autoclaved water and autoclaved standard laboratory chow (Lab Diet 5021; PMI Nutrition, St. Louis, MO, USA). At 5 weeks of age, thrice-weekly dosing of the Nile rats with about 5 x 108 cfu/ml per strain of the microbial composition or an equal volume of sterile PBS by oral gavage while under light sedation with 50%/50% O2/CO2 is initiated. Optionally, the dose may range from 5 x 106 to 5 x 1010 cfu/ml per strain and/or dosing may occur once weekly. Dosing will continue for 20 weeks post initiation, optionally lasting 15, 30, 40, or 50 weeks. The model could be modified to address prediabetes by shortening the duration to about 3 to 10 weeks post initiation of dosing.

[0440] Body weight will be measured three times per week throughout the study. Blood glucose, cholesterol, triglycerides, and hemoglobin A1C will be measured after obtaining blood by tail bleed while under light sedation with 50%/50% O2/CO2 every three weeks following initiation of dosing. At sacrifice, total body, liver, kidney, epididymal fat pad, and cecum weights are measured. Terminal plasma samples are used for measurement of insulin, blood glucose, cholesterol, triglycerides, and hemoglobin A1C. Following perfusion with PBS under deep anesthesia, the liver and kidneys are excised and fixed in 4% paraformaldehyde. Subsequently, 15 µm sections are stained with Oil-Red-O and counterstained with Mayer's hematoxylin to facilitate the identification of stores of hydrophobic lipids. The contents of the cecum are flash frozen in liquid nitrogen and stored at -80°C.

[0441] Animals treated with successful compositions will have statistically significant differences in terminal body weight, blood glucose, hemoglobin A1C, liver or kidney accumulation of lipid, and/or insulin from control animals.

Example 36. In vivo Validation Of Bacterial Composition For Prophylactic Use And Treatment In A Mouse Model Of Vancomycin Resistant Enterococcus (VRE) colonization

[0442] The emergence and spread of highly antibiotic-resistant bacteria represent a major clinical challenge (Snitkin et al Science Translational Medicine, 2012). In recent years, the numbers of infections caused by organisms such as methicillin- resistant Staphylococcus aureus, carbapenem-resistant Enterobacteriaceae, vancomycin-resistant Enterococcus (VRE), and Clostridium difficile have increased markedly, and many of these strains are acquiring resistance to the few remaining active antibiotics. Most infections produced by highly antibiotic-resistant bacteria are acquired during hospitalizations, and preventing patient- to-patient transmission of these pathogens is one of the major

challenges confronting hospitals and clinics. Most highly antibiotic-resistant bacterial strains belong to genera that colonize mucosal surfaces, usually at low densities. The highly complex microbiota that normally colonizes mucosal surfaces inhibits expansion of and domination by bacteria such as Enterobacteriaceae and Enterococcaceae. Destruction of the normal flora by antibiotic administration, however, leads to disinhibition antibiotic-resistant members of these bacterial families, enabling to their expansion to very high densities (Ubeda et al Journal of Clinical Investigation 2010). High-density colonization by these organisms can be calamitous for the susceptible patient, resulting in bacteremia and sepsis (Taur et al, Clinical Infectious Disease, 2012).

[0443] To test prophylactic use and treatment of a bacterial composition, a VRE infection mouse model is used as previously described (Ubeda et al, Infectious Immunity 2013, Ubeda et al, Journal of Clinical Investigation, 2010). Briefly, experiments are done with 7-week-old C57BL/6J female mice purchased from Jackson Laboratory, housed with irradiated food, and provided with acidified water. Mice are individually housed to avoid exchange of microbiota between mice due to coprophagia. For experimental infections with VRE, mice are treated with ampicillin (0.5 g/liter) in their drinking water, which is changed every 3 days.

[0444] In the treatment model, on day 1, mice are infected by means of oral gavage with 108 CFU of the vancomycin-resistant Enterococcus faecium strain purchased from ATCC (ATCC 700221). One day after infection (day 1), antibiotic treatment is stopped and VRE levels are determined at different time points by plating serial dilutions of fecal pellets on Enterococcosel agar plates (Difco) with vancomycin (8 ug/ml; Sigma). VRE colonies are identified by appearance and confirmed by Gram staining or other methods previously described (*e.g.* see Examples 1,2,3, and 4). In addition, as previously described (Ubeda et al, Journal of Clinical Investigation 2010), PCR of the vanA gene, which confers resistance to vancomycin, confirms the presence of VRE in infected mice. The bacterial composition test article such as but not limited to an ethanol treated, gradient purified spore preparation (as described herein), fecal suspension, or a Network Ecology is delivered in PBS on days 1-3 while the negative control contains only PBS and is also delivered on days 1-3 by oral gavage. Fresh fecal stool pellets are obtained daily for the duration of the experiment from days -7 to day 10. The samples are immediately frozen and stored at -80°C. DNA is extracted using standard techniques and analyzed with 16S or comparable methods (*e.g.* see Examples 1 and 2).

[0445] In the colonization model, ampicillin is administered as described above for day -7 to day 1, treatment with the bacterial composition or vehicle control is administered on day 0-2 and the VRE resistant bacteria at 108 CFU are administered on day 14. Fecal samples are taken throughout the experiment daily from -7 to day 21 and submitted for 16S sequencing as previously described (*e.g.* see Examples 1 and 2).

[0446] In both models, titers of VRE in feces are used to evaluate the success of the bacterial composition versus the negative control. A preferred bacterial composition either prevents or reduces

colonization by VRE compared to the negative control, or it accelerates the decrease in colonization after cessation of antibiotics. Furthermore, each bacterial composition is assessed for the ability of the bacterial composition test article to induce a healthy microbiome, as measured by engraftment, augmentation and increase in microbiota diversity.

Example 37. In vivo Validation of A Bacterial Composition For Prophylactic Use And Treatment of a Mouse Model of Carbapenem Resistant Klebsiella (CRKp) Colonization

[0447] The emergence of Klebsiella pneumoniae strains with decreased susceptibility to carbapenems is a significant threat to hospitalized patients. Resistance to carbapenems in these organisms is most frequently mediated by K. pneumoniae carbapenemase (KPC), a class A beta-lactamase that also confers resistance to broad-spectrum cephalosporins and commercially available beta-lactam/beta-lactamase inhibitor combinations (Queenan et al, Clinical Microbiology Review, 2007). KPC-producing K. pneumoniae (KPC-Kp) strains often harbor resistance determinants against several other classes of antimicrobials, including aminoglycosides and fluoroquinolones, resulting in truly multidrug-resistant (MDR) organisms (Hirsch et al, Journal of Antimicrobial Chemotherapy, 2009). Considering the limited antimicrobial options, infections caused by KPC-Kp pose a tremendous therapeutic challenge and are associated with poor clinical outcomes.

[0448] A treatment protocol in a mouse model previously described in mice sensitive to KCP-Kp (*e.g.* Perez et al, Antimicrobial Agents Chemotherapy, 2011) is used to evaluate the bacterial composition (test article) for treating carbapenem resistant Klebsiella and reducing carriage in the GI tract. Female CF1 mice (Harlan Sprague-Dawley, Indianapolis, IN) are used and are individually housed and weighed between 25 and 30 g. The bacterial composition includes without limitation an ethanol treated, gradient purified spore preparation (as described herein), fecal suspension, or a Network Ecology.

[0449] The thoroughly characterized strain of K. pneumoniae, VA-367 (8, 9, 25) is used. This clinical isolate is genetically related to the KPC-Kp strain circulating in the Eastern United States. Characterization of the resistance mechanisms in K. pneumoniae VA-367 with PCR and DNA sequence analysis revealed the presence of blaKPC-3, blaTEM-1, blaSHV-11, and blaSHV-12 as well as qnrB19 and aac(6')-Ib. Additionally, PCR and DNA sequencing revealed disruptions in the coding sequences of the following outer membrane protein genes: ompK35, ompK36, and ompK37. Antibiotic susceptibility testing (AST) was performed with the agar dilution method and interpreted according to current recommendations from the Clinical and Laboratory Standards Institute (CLSI). A modified Hodge test were performed, according to a method described previously (*e.g.* see Anderson et al, Journal of Clinical Microbiology, 2007) with ertapenem, meropenem, and imipenem. Tigecycline and polymyxin E were evaluated by Etest susceptibility assays (AB bioMerieux, Solna, Sweden). Results for tigecycline were interpreted as suggested by the U.S. Food and Drug

Administration (FDA) and according to CLSI recommendations (criteria for Pseudomonas) for polymyxin E.

[0450] In a prophylactic design, mice (10 per group) are assigned to receive either a bacterial composition (test article; *e.g.* see Example 9 or 10), or control group receiving only the vehicle. After 3 days of subcutaneous clindamycin treatment (Day -6,-5, -4) to sensitize them to KPC-Kp, mice are administered the test article or vehicle daily from day -10 to day 0, On day 0, 103 CFU of KPC-Kp VA-367 diluted in 0.5 ml phosphate-buffered saline (PBS) is administered by oral gavage. Fecal samples are collected 1, 4, 6, and 11 days after the administration of KPC-Kp to measure the concentration of carbapenem-resistant K. pneumoniae. Fecal samples (100 mg diluted in 800 ml of PBS) are plated onto MacConkey agar with 0.5 ug/ml of imipenem, and the number of CFU per gram of stool is determined. Efficacy of test articles is apparent as a reduction in KPC-Kp burden.

[0451] Alternatively other methods may be used to measure the levels of carbapenem-resistant K. pneumoniae *e.g.* PCR, antigen testing, as one who is skilled in the art could perform.

[0452] In a treatment design, mice are treated with subcutaneous clindamycin to reduce the normal intestinal flora 1 day before receiving 104 CFU of KPC-Kp VA-367 by oral gavage. For 7 days after oral gavage with KPC-Kp, mice receive oral gavage of normal saline (control group), or the bacterial composition. Fecal samples are collected at baseline and at 3, 6, 8, 11, 16, and 21 days after KPC-Kp VA-367 was given by gavage. The level of CRKp in feces is determined by plating serial dilutions of fecal suspensions to MacConkey agar with 0.5 ug/ml of imipenem, and the number of CFU per gram of stool is determined. Alternatively other methods may be used to measure the levels of carbapenem-resistant K. pneumoniae *e.g.* PCR, antigen testing, as one who's skilled in the art could perform. Efficacy of test articles is apparent as a reduction in KPC-Kp burden.

Example 38. In vivo validation of Bacterial Composition For Efficacy in For the Prophylactic Use or Treatment of Pathogenic Fungus in Mice Models

[0453] The bacterial compositions of the invention can be utilized for prophylaxis or treatment of pathogenic fungus in a mouse colonized with one of several Candida species. Adult male CD-1 (ICR) mice are intragastrically inoculated with C. albicans, C. tropicalis or C. parapsilosis as previously described (Mellado et al., Diagnostic Microbiology and Infectious Disease 2000). Tetracycline-HCl at 1g/L and 5% glucose are included in the drinking water starting on Day -2, 2 days before Candida dosing on Day 0, and throughout the experiment, to enhance colonization. 5 x 107 Candida are dosed in 0.1 mL on Day 0. By Day 4 all mice are colonized as detected by fecal cfu assay described below. Test articles are used in both prophylactic and treatment regimens. Prophylactic dosing with a bacterial composition including without limitation an ethanol treated, gradient purified spore preparation (as described herein), fecal suspension, or a Network Ecology occurs on Day -1 with a dose between 104 and 1010 bacteria, while treatment dosing occurs on Days 1, 2 and 3 with a similar dose. Negative control groups in both regimes are dosed with PBS administered in a similar manner.

All test article dosing is by oral gavage. Treated and untreated mice are kept separate in independently ventilated cages for all of the experiments. Sterilized food, bedding and bottles are used throughout the experiment. Sterilized tap water with or without supplements are also used to avoid contamination. Starting at day -1 postinfection (p.i.), mice are weighed daily and stool samples are collected from each animal and scored for consistency (0, normal feces; 1, mixed stool samples containing both solid and pasty feces; 2, pasty feces; 3, semiliquid feces; 4, liquid feces).

[0454] Feces are cultured for yeasts. Dilutions of fecal samples are titrated on Sabouraud Dextrose Chloramphenicol agar (Neogen cat #(7306) agar plates which are selective for fungi. After 24 – 48 h of incubation at 37°C, quantification of the cultures is achieved by counting the plates visually or by scanning the plates on a Colony Image Analysis Scanner (Spiral Biotech) and processed by the computer software CASBA 4 (Spiral Biotech). The results are noted as colony forming units (CFU) per gram of feces. Effect of bacterial composition on Candida colonization and quality of feces of infected mice is thus analyzed by comparing to placebo, and representative colonies are submitted for 16S/18S/ITS microbial identification before and after infection as previously described (*e.g.* See Example 1 and 2).

[0455] Using this model, the ability of test articles to prevent fungal dissemination and death is also tested. Starting on Day 4 in the above regimen, animals colonized with fungi are treated with immunosuppressive agents to induce deep neutropenia [defined as >500 polymorphonuclear cell per ml. Total white cells counts are performed using a hemacytometer Neubauer improved (Brand, Werthheim/Main, Germany)]. The immunosuppressive agents (150 mg/kg of cyclophosphamide (Sigma) and 65 mg/kg of 6-methyl-prednisolone (Sigma) are both administered intraperitoneally (i.p.) every 72–96 h until deep neutropenia is obtained and continue for 10 days. Test articles are delivered either on Day 4, 5 and 6, in parallel with the start of immunosuppression or for 3 consecutive days after deep neurtopenia is confirmed. Control animals are treated with PBS in each mode of treatment (Day 4-6, or 3 days post neutropenia. Mortality, dissemination and histology are monitored. When animals are severely ill, they are humanely euthanized with pentobarbital (Nembutal) or similar acceptable methods. Dissemination is quantified in kidneys, liver and spleen is quantified by suspending tissue separately in 2 mL of cooled PBS, and homogenizing using a lab-blender (Stomacher 80, Madrid, Spain). Aliquots of the homogenates are cultured for yeasts and bacterial flora. Results are expressed as CFU per gram of tissues. Candida dissemination is defined as positive cultures of at least two cultured organs. Positive culture is defined as plates yielding a value of > 1.5 log10 CFU/g of tissues. Histologic studies are also performed on five cut sections of liver, kidneys and spleen to detect yeasts.

Example 39. In vivo Validation of Bacterial Composition for Efficacy for Prophylaxis or Treatment in a Mouse Model of Methicillin Resistant Staphylococcus Aureus (MRSA)

[0456] Methicillin resistant Staphylococcus aureus (MRSA) is a Gram positive pathogen that is a major cause of nosocomial infections including sepsis, pneumonia and surgical site infections. Both nasal and gastrointestinal carriage of MRSA are implicated as sources of organisms associated with nosocomial infections. Rectal carriage of MRSA is common in patients in intensive care units and patients with both rectal and nasal colonization had significantly higher rates of MRSA infection than did patients with nasal colonization alone (Squier et al Staphylococcus aureus rectal carriage and its association with infections in patients in a surgical intensive care unit and a liver transplant unit. Infect Control Hosp Epidemiol 2002; 23:495–501.)

[0457] MRSA is also associated with gastrointestinal disease, including antibiotic associated diarrhea (Boyce and Havill, Nosocomial antibiotic-associated diarrhea associated with enterotoxin-producing strains of methicillin-resistant Staphylococcus aureus. Am J Gastroenterol. 2005 Aug;100(8):1828-34; Lo and Bourchardt, Antibiotic-associated diarrhea due to methicillin-resistant Staphylococcus aureus, Diagnostic Microbiology & Infectious Disease 63:388-389, 2009).

[0458] A mouse model of MRSA colonization is used to test the efficacy of bacterial compositions in treating MRSA colonization of the gut. CF1 mice are treated with streptomycin (1mg/ml), delivered in drinking water, for 5 days, after which they are orally inoculated with 1e7 cfu MRSA daily from Day 0 to Day 5 via their drinking water (Gries et al, Growth in Cecal Mucus Facilitates Colonization of the Mouse Intestinal Tract by Methicillin-Resistant Staphylococcus aureus, JID 2005;192:1621–7). Drinking water is prepared fresh each day. Colonization by MRSA is monitored by determining cfu/ml in feces each day starting on the day prior to the first day of MRSA inoculation. Feces are homogenized in sterile PBS and serial dilutions are plated to Mannitol salt agar and incubated aerobically for 48 h at 37°C. Presumptive MRSA colonies are confirmed by 16S rDNA PCR and sequencing as in (Examples 1 and 2). Bacterial compositions, control PBS or vancomycin are delivered by oral gavage starting on Day 6 for 3 days. Efficacy is observed as a reduction in MRSA cfu/g in feces, and/or faster time to a reduction of MRSA cfu/g, in the animals treated with bacterial compositions but not in control animals. Efficacy is compared to that of the positive control vancomycin, which clears the colonization.

[0459] The efficacy of bacterial compositions in preventing MRSA colonization is tested in a mouse model of prophylaxis in which CF1 mice are treated with streptomycin, delivered in drinking water, for 5 days. After 2 days without streptomycin, the mice are treated with bacterial compositions or control PBS by oral gavage for 3 days, and then inoculated with 1e7 cfu MRSA by oral gavage. Colonization by MRSA is monitored by determining cfu/ml in feces each day starting on the day prior to the first day of MRSA inoculation. Feces are homogenized in sterile PBS and serial dilutions are plated to Mannitol salt agar and incubated aerobically for 48 h at 37°C. Presumptive MRSA colonies

are confirmed by 16S rDNA PCR and sequencing as in Examples 1 and 2 for 16S sequencing. Efficacy is observed as a reduction in MRSA cfu/g in feces, and/or faster reduction of MRSA cfu/g, in the animals treated with bacterial compositions compared to control animals.

Example 40. Clinical Validation of Bacterial Composition for Efficacy in Obesity

[0460] To demonstrate a bacterial composition's ability to treat obesity, a group of 400 obese human subjects can be prospectively recruited. Inclusion criteria include BMI 30-45 kg/m^2. Exclusion criteria include Type 1 or Type 2 diabetes, treatment with any kind of anti-diabetic, anti-hyperglycemic or anti-obesity medication or surgical procedure (*e.g.* bariatric surgery), significant co-morbidities, participation in a formal weight loss program, either systolic blood pressure > 160 mm Hg or diastolic blood pressure >100 mmHg, subjects whose body weight is not stable, as judged by the Investigator (*e.g.* >5% change within 3 months prior to screening).

[0461] During a double blind treatment period of 12 weeks, the experimental treatment group (n=200) receives a daily oral dose of about 1x109 CFUs of viable bacteria either in the form of vegetative organisms or spores or both, whereas the control group (n=200) is administered a placebo at an identical frequency. The composition can be formulated in a delayed release enteric coated capsule or co-administered with bicarbonate buffer to aid passage of viable organisms through the stomach. The bacterial composition may be optionally be administered together or co-formulated with prebiotic(s).

[0462] Patients can be optionally treated with a broad spectrum antibiotic 0-10 days prior to first administration of the bacterial composition. Alternative dosing schedules and routes of administration (*e.g.* rectal) may be employed, including multiple daily doses of test article, and a range of 103 to 1010 CFU of a given composition may be delivered.

[0463] At baseline and 6, 12, and 24 weeks after the beginning of the treatment period, change in body weight, waist and hip circumference, and waist/hip ratio will be measured. By the end of the 24 week treatment challenge period, the experimental group is expected to show significant differences from the control group in weight loss and/or waist and hip circumference, optionally 5% or greater weight loss.

[0464] Optionally, in the event an effect is detected at the end of the 24 week treatment period, the durability of the effect may be tested. All subjects will be taken off the experimental treatment and change in weight measured after 2 weeks, 4 weeks, 8 weeks, 16 weeks, and 52 weeks.

Example 41. Clinical Validation of Bacterial Composition for Efficacy in Weight Loss

[0465] To demonstrate a bacterial composition's ability to cause weight loss, a group of 400 human subjects with BMI > 25 kg/m^2 is prospectively recruited. Inclusion criteria include BMI > 25 kg/m^2. Exclusion criteria include Type 1 or Type 2 diabetes, treatment with any kind of anti-diabetic, anti-hyperglycemic or anti-obesity medication or surgical procedure (*e.g.* bariatric surgery), significant co-morbidities, participation in a formal weight loss program, either systolic blood

pressure > 160 mm Hg or diastolic blood pressure >100 mmHg, subjects who do not show stable body weight as judged by PI (*e.g.* >5% change within 3 months prior to screening).

[0466] During a double blind treatment period of 24 weeks, the experimental treatment group (n=200) receives a daily oral dose of about 1x109 CFUs of viable bacteria either in the form of vegetative organisms or spores or both, whereas the control group (n=200) is administered a placebo at an identical frequency. The composition can be formulated in a delayed release enteric coated capsule or co-administered with bicarbonate buffer to aid passage of viable organisms through the stomach. The bacterial composition may be optionally be administered together or co-formulated with prebiotic(s).

[0467] Patients may be optionally treated with a broad spectrum antibiotic 0-10 days prior to first administration of the bacterial composition. Alternative dosing schedules and routes of administration (*e.g.* rectal) may be employed, including multiple daily doses of test article, and a range of 103 to 1010 CFU of a given composition may be delivered.

[0468] At baseline and 6, 12, and 24 weeks after the beginning of the treatment period, change in body weight will be measured. By the end of the 24 week treatment challenge period, the experimental group are expected to show significant differences from the control group in weight loss.

[0469] Optionally, in the event an effect is detected at the end of the 24 week treatment period, the durability of the effect may be tested. All subjects will be taken off the experimental treatment and change in weight measured after 2 weeks, 4 weeks, 8 weeks, 16 weeks, and 52 weeks.

Example 42. Clinical Validation of Bacterial Composition for Efficacy In Prediabetes

[0470] To demonstrate a bacterial composition's ability to treat prediabetes by exerting beneficial effects on markers associated with the onset of diabetes, a group of 60 human subjects with metabolic syndrome/prediabetes is prospectively recruited. Inclusion criteria include either (a) fasting plasma glucose between 5.6 and 6.9 mmol/L and 2 hr post-glucose load plasma glucose < 7.8 mmol/L, and/or (b) 2 hr post-glucose load plasma glucose in oral glucose tolerance test (OGTT) between 7.8 and 11.0 mmol/L. Exclusion criteria include established gestational, Type 1 or Type 2 diabetes, treatment with any kind of anti-diabetic, anti-hyperglycemic or anti-obesity medication or surgical procedure, use of systemic long-acting corticosteroids or prolonged use (greater than 10 days) of systemic corticosteroids, or any significant medical condition that would complicate the measurement of the endpoint or put the patient at risk.

[0471] Optionally, the study can be performed specifically in obese patients meeting the above inclusion criteria with the additional inclusion criteria of BMI 30-45 kg/m^2 as well as waist circumference > 88 cm in women and > 102 cm in men. Additional exclusion criteria include: 1) a history of surgical procedures for weight loss; 2) 2 repeat laboratory values at the screening visit of triglycerides > 4.52 mmol; and 3) either systolic blood pressure > 160 mm Hg or diastolic blood pressure >100 mmHg.

[0472] During a double blind treatment period of 12 weeks, the experimental treatment group (n=30) receives a daily oral dose of about 1x109 CFUs of viable bacteria either in the form of vegetative organisms or spores or both, whereas the control group is administered a placebo at an identical frequency (n=30). The composition can be formulated in a delayed release enteric coated capsule or co-administered with bicarbonate buffer to aid passage of viable organisms through the stomach. The bacterial composition may be optionally be administered together or co-formulated with prebiotic(s).

[0473] Patients can be optionally treated with a broad spectrum antibiotic 0-3 days prior to first administration of the bacterial composition. Alternative dosing schedules and routes of administration (*e.g.* rectal) may be employed, including multiple daily doses of test article, and a range of 103 to 1011 CFU of a given composition may be delivered.

[0474] At baseline and 4, 8 and 12 weeks after the beginning of the treatment period, glucose tolerance is tested by OGTT and HbA1c (glycosylated hemoglobin) levels measured. At the same timepoints, insulin secretion will be assessed by plasma insulin levels measured during the oral glucose tolerance tests. Homeostatic model assessment beta (HOMA-beta) will be used to quantify beta cell function and HOMA-IR for insulin sensitivity. In addition, subjects will perform home blood glucose testing once weekly at home.

[0475] By the end of the 12 week treatment period, the experimental group is expected to show significant differences from the control group in glucose tolerance, insulin sensitivity, and/or insulin secretion reflecting improved insulin sensitivity, decreased pre-diabetes symptoms and improvement in metabolic syndrome.

[0476] Optionally, in the event an effect is detected at the end of the 12 week treatment period, the durability of the effect may be tested. All subjects will be taken off their respective treatment and return for oral glucose tolerance tests after 2 weeks, 4 weeks, 8 weeks, 16 weeks, and 52 weeks to measure HbA1c, insulin secretion, HOMA-beta, and HOMA-IR.

[0477] Optionally, the treatment period can be extended to collect an additional endpoint of progression to type 2 diabetes at 6 months and 12 months after the beginning of the treatment period.

Example 43. Clinical validation of bacterial composition for efficacy in type-2-diabetes

[0478] To demonstrate a bacterial composition's ability to treat type 2 diabetes, a group of 60 human subjects with type 2 diabetes is prospectively recruited. Inclusion criteria include diagnosis of type 2 diabetes with inadequate glycemic control on diet and exercise, glycosylated hemoglobin between 7.5% and 10.0% at screening, BMI $\leq$ 45 kg/m2.

[0479] Exclusion criteria include gestational diabetes, type 1 diabetes, treatment with any kind of anti-diabetic medication in the 12 weeks prior to screening, use of anti-obesity medication/surgical procedure, use of systemic long-acting corticosteroids or prolonged use (greater than 10 days) of systemic corticosteroids, or any significant co-morbidities related to the underlying diabetic condition.

[0480] Optionally, the study can be done in non insulin dependent type 2 diabetics who have inadequate glycemic control who are taking oral medications such as metformin, sulfonylureas, DPP-4 inhibitors, GLP-1 agonists, and SGLT2 inhibitors. Optionally, the study can be done in newly diagnosed non insulin dependent type 2 diabetics who are completely treatment naive.

[0481] During a double-blinded treatment period of 18 weeks, the experimental treatment group (n=30) receives a daily oral dose of about 1x109 CFUs of viable bacteria either in the form of vegetative organisms or spores or both, whereas the control group (n=30) is administered a placebo at an identical frequency. The composition can be formulated in a delayed release enteric coated capsule or co-administered with bicarbonate buffer to aid passage of viable organisms through the stomach. The bacterial composition may be optionally be administered together or co-formulated with prebiotic(s).

[0482] Patients may be optionally treated with a broad spectrum antibiotic 0-10 days prior to first administration of the bacterial composition. Alternative dosing schedules and routes of administration (*e.g.* rectal) may be employed, including multiple daily doses of test article, and a range of 103 to 1010 CFUs of a given composition may be delivered.

[0483] At baseline and 6, 12 and 18 weeks after the beginning of the treatment period, HbA1c (glycosylated hemoglobin) levels, fasting plasma glucose, fasting insulin, HOMA-beta, and HOMA-IR, In addition, subjects will perform home blood glucose testing once weekly at home.

[0484] Optionally high sensitivity C-reactive protein, adiponectin, total cholesterol, low-density lipoprotein cholesterol, high-density lipoprotein cholesterol, triglycerides, systolic and diastolic blood pressure can also be measured at the same timepoints.

[0485] By the end of the 18 week treatment period, the experimental group are expected to show significant differences from the control group in change in HbA1c, fasting plasma glucose, insulin sensitivity, and/or insulin secretion from baseline.

[0486] Optionally, in the event an effect is detected at the end of the 18 week treatment period, the durability of the effect may be tested. All subjects will be taken off the experimental treatment and return for measurement of HbA1c, fasting plasma glucose, fasting insulin, HOMA-beta, and HOMA-IR after 2 weeks, 4 weeks, 8 weeks, 16 weeks, and 52 weeks.

Example 44. Clinical Validation of Bacterial Composition for Efficacy in Recent Onset Type-1-Diabetes

[0487] To demonstrate a bacterial composition's ability to slow progression of recent onset type 1 diabetes, a group of 60 human subjects with recent onset type 1 diabetes is prospectively assembled.

[0488] Inclusion criteria include diagnosis of type 1 diabetes within 40 days prior to screening, positive test for at least one diabetes-related autoantibody such as GAD, IA-2, ZnT8, and/or anti-insulin (obtained within 10 days of onset of insulin therapy), peak stimulated C-peptide level ≥ 0.2 pmol/mL following mixed meal tolerance test (MMTT), and evidence of some fraction of residual

(normal) pancreatic function. Exclusion criteria include any form of diabetes other than type 1 (*e.g.* type 2 diabetes), prior or current treatment with corticosteroids, significant co-morbidities.

[0489] During a double-blind treatment period of 18 weeks, the experimental treatment group (n=30) receives a daily oral dose of about 1x109 CFUs of viable bacteria either in the form of vegetative organisms or spores or both, whereas the control group (n=30) is administered a placebo at an identical frequency. The composition can be formulated in a delayed release enteric coated capsule or co-administered with bicarbonate buffer to aid passage of viable organisms through the stomach. The bacterial composition may be optionally be administered together or co-formulated with prebiotic(s).

[0490] Patients can be optionally treated with a broad spectrum antibiotic 0-10 days prior to first administration of the bacterial composition. Alternative dosing schedules and routes of administration (*e.g.* rectal) may be employed, including multiple daily doses of test article, and a range of 103 to 1010 CFUs of a given composition are delivered.

[0491] At baseline and 6, 12 and 18 weeks after the beginning of the treatment period, stimulated C-peptide released in 2 hours during a standard mixed meal tolerance test (MMTT) and HbA1c levels will be measured. In addition, subjects will record total daily dose of insulin in a diary.

[0492] By the end of the 18 week treatment period, the experimental group is expected to show significant differences from the control group in change in stimulated C-peptide, HbA1c, and/or insulin dosage from baseline.

[0493] Optionally, in the event an effect is detected at the end of the 18 week treatment period, the durability of the effect may be tested. All subjects will be taken off the experimental treatment and return for measurement of stimulated C-peptide in response to MMTT and HbA1c levels after 2 weeks, 4 weeks, 8 weeks, 16 weeks, and 52 weeks.

Example 45. Clinical Validation of Bacterial Composition for Efficacy in Reduction of Opportunistic Pathogenic Fungus in Humans

[0494] The dimorphic yeast, Candida albicans, is the leading fungal pathogen in normal hosts and in patients with damaged immune systems. In immunocompromised hosts such as cancer patients, transplant patients, post-operative surgical patients, premature newborns, or HIV-infected people, C. albicans ranks as the leading fungal pathogen. Invasion leading to systemic infection may also develop in neutropenic patients whose T cell function is comprised. (Hostetter MK, Clinical Microbiology Reviews, Jan 1994, pp. 29-42.) In this population, disease ranges from aggressive local infections such as periodontitis, oral ulceration, or esophagitis in HIV-infected patients, to complex and potentially lethal infections of the bloodstream with subsequent dissemination to brain, eye, heart, liver, spleen, kidneys, or bone. Recently, the incidence of systemic candidiasis, which is caused by Candida spp., predominantly Candida albicans, has increased. This increase over the last two decades has caused a rise in the use of antifungal drugs, including azoles, such as fluconazole or ketoconazol,

leading to emergence of resistant organisms and thus increasing the need for alternative therapies (Looi et al., FEMS Microbiol Lett 2005).

[0495] In a prophylactic, randomized, double-blind study, healthy volunteers who have been prescreened as colonized with Candida albicans at >104 cfu/g by fecal culturing are randomized to receive either a placebo or a bacterial composition daily. Study volunteers are asked to avoid taking probiotics in any form in the week prior to dosing. The dosing of bacterial composition may, optionally, be modified to daily, every-other-day, weekly or any other frequency, and doses may range from 105 to 1010 CFU/mL. The subjects provide faecal and vaginal fluid samples pretreatment and on Days 7, 14 and 28 post-treatment that are cultivated on agar plates within 3 hours after delivery to the laboratory. Complementary genomic and microbiological methods are used to characterize the composition of the microbiota from each of the samples. C. albicans is detected by microbiological methods, for example by serial dilution and plating to fungal selective media CHROMagar Candida (BD cat#254093) which selects for fungal organisms, and against bacterial growth, or another fungal selective media, and also by using Taqman PCR based assay using similar methods as described previously (Maaroufi et al., J Clin Microbiol. 2003). A reduction in C. albicans levels in feces indicates efficacy in reducing colonization.

Summary

[0496] Unless otherwise indicated, all numbers expressing quantities of ingredients, reaction conditions, and so forth used in the specification, including claims, are to be understood as being modified in all instances by the term "about." Accordingly, unless otherwise indicated to the contrary, the numerical parameters are approximations and may vary depending upon the desired properties sought to be obtained. At the very least, and not as an attempt to limit the application of the doctrine of equivalents to the scope of the claims, each numerical parameter should be construed in light of the number of significant digits and ordinary rounding approaches.

[0497] Unless otherwise indicated, the term "at least" preceding a series of elements is to be understood to refer to every element in the series.

[0498] While the invention has been particularly shown and described with reference to a preferred embodiment and various alternate embodiments, it will be understood by persons skilled in the relevant art that various changes in form and details can be made therein without departing from the spirit and scope of the invention.

[0499] All references, issued patents and patent applications cited within the body of the instant specification are hereby incorporated by reference in their entirety, for all purposes.

[0500] The foregoing description of the embodiments of the invention has been presented for the purpose of illustration; it is not intended to be exhaustive or to limit the invention to the precise forms disclosed. Persons skilled in the relevant art can appreciate that many modifications and variations are possible in light of the above disclosure.

[0501] Some portions of this description describe the embodiments of the invention in terms of algorithms and symbolic representations of operations on information. These algorithmic descriptions and representations are commonly used by those skilled in the data processing arts to convey the substance of their work effectively to others skilled in the art. These operations, while described functionally, computationally, or logically, are understood to be implemented by computer programs or equivalent electrical circuits, microcode, or the like. Furthermore, it has also proven convenient at times, to refer to these arrangements of operations as modules, without loss of generality. The described operations and their associated modules may be embodied in software, firmware, hardware, or any combinations thereof.

[0502] Any of the steps, operations, or processes described herein may be performed or implemented with one or more hardware or software modules, alone or in combination with other devices. In one embodiment, a software module is implemented with a computer program product comprising a computer-readable medium containing computer program code, which can be executed by a computer processor for performing any or all of the steps, operations, or processes described.

[0503] Embodiments of the invention may also relate to an apparatus for performing the operations herein. This apparatus may be specially constructed for the required purposes, and/or it may comprise a general-purpose computing device selectively activated or reconfigured by a computer program stored in the computer. Such a computer program may be stored in a tangible computer readable storage medium or any type of media suitable for storing electronic instructions, and coupled to a computer system bus. Furthermore, any computing systems referred to in the specification may include a single processor or may be architectures employing multiple processor designs for increased computing capability.

[0504] Embodiments of the invention may also relate to a computer data signal embodied in a carrier wave, where the computer data signal includes any embodiment of a computer program product or other data combination described herein. The computer data signal is a product that is presented in a tangible medium or carrier wave and modulated or otherwise encoded in the carrier wave, which is tangible, and transmitted according to any suitable transmission method.

[0505] Finally, the language used in the specification has been principally selected for readability and instructional purposes, and it may not have been selected to delineate or circumscribe the inventive subject matter. It is therefore intended that the scope of the invention be limited not by this detailed description, but rather by any claims that issue on an application based hereon. Accordingly, the disclosure of the embodiments of the invention is intended to be illustrative, but not limiting, of the scope of the invention, which is set forth in the following claims.

TABLES

Table 1.

List of Operational Taxonomic Units (OTU) with taxonomic assignments made to Genus, Species, and Phylogenetic Clade. Clade membership of bacterial OTUs is based on 16S sequence data. Clades are defined based on the topology of a phylogenetic tree that is constructed from full-length 16S sequences using maximum likelihood methods familiar to individuals with ordinary skill in the art of phylogenetics. Clades are constructed to ensure that all OTUs in a given clade are: (i) within a specified number of bootstrap supported nodes from one another, and (ii) within 5% genetic similarity. OTUs that are within the same clade can be distinguished as genetically and phylogenetically distinct from OTUs in a different clade based on 16S-V4 sequence data, while OTUs falling within the same clade are closely related. OTUs falling within the same clade are evolutionarily closely related and may or may not be distinguishable from one another using 16S-V4 sequence data. Members of the same clade, due to their evolutionary relatedness, play similar functional roles in a microbial ecology such as that found in the human gut. Compositions substituting one species with another from the same clade are likely to have conserved ecological function and therefore are useful in the present invention. All OTUs are denoted as to their putative capacity to form spores and whether they are a Pathogen or Pathobiont (see Definitions for description of "Pathobiont"). NIAID Priority Pathogens are denoted as 'Category-A', 'Category-B', or 'Category-C', and Opportunistic Pathogens are denoted as 'OP'. OTUs that are not pathogenic or for which their ability to exist as a pathogen is unknown are denoted as 'N'. The 'SEQ ID Number' denotes the identifier of the OTU in the Sequence Listing File and 'Public DB Accession' denotes the identifier of the OTU in a public sequence repository.

OTU	SEQ ID Number	Public DB Accession	Phylogenetic Clade	Spore Former	Pathogen Status
Corynebacterium coyleae	692	X96497	clade_100	N	N
Corynebacterium mucifaciens	711	NR_026396	clade_100	N	N
Corynebacterium ureicelerivorans	733	AM397636	clade_100	N	N
Corynebacterium appendicis	684	NR_028951	clade_102	N	N
Corynebacterium genitalium	698	ACLJ01000031	clade_102	N	N
Corynebacterium glaucum	699	NR_028971	clade_102	N	N
Corynebacterium imitans	703	AF537597	clade_102	N	N
Corynebacterium riegelii	719	EU848548	clade_102	N	N
Corynebacterium sp. L_2012475	723	HE575405	clade_102	N	N
Corynebacterium sp. NML 93_0481	724	GU238409	clade_102	N	N
Corynebacterium sundsvallense	728	Y09655	clade_102	N	N
Corynebacterium tuscaniae	730	AY677186	clade_102	N	N
Prevotella maculosa	1504	AGEK01000035	clade_104	N	N
Prevotella oris	1513	ADDV01000091	clade_104	N	N
Prevotella salivae	1517	AB108826	clade_104	N	N
Prevotella sp. ICM55	1521	HQ616399	clade_104	N	N
Prevotella sp. oral clone AA020	1528	AY005057	clade_104	N	N

Prevotella sp. oral clone GI032	1538	AY349396	clade_104	N	N
Prevotella sp. oral taxon G70	1558	GU432179	clade_104	N	N
Prevotella corporis	1491	L16465	clade_105	N	N
Bacteroides sp. 4_1_36	312	ACTC01000133	clade_110	N	N
Bacteroides sp. AR20	315	AF139524	clade_110	N	N
Bacteroides sp. D20	319	ACPT01000052	clade_110	N	N
Bacteroides sp. F_4	322	AB470322	clade_110	N	N
Bacteroides uniformis	329	AB050110	clade_110	N	N
Prevotella nanceiensis	1510	JN867228	clade_127	N	N
Prevotella sp. oral taxon 299	1548	ACWZ01000026	clade_127	N	N
Prevotella bergensis	1485	ACKS01000100	clade_128	N	N
Prevotella buccalis	1489	JN867261	clade_129	N	N
Prevotella timonensis	1564	ADEF01000012	clade_129	N	N
Prevotella oralis	1512	AEPE01000021	clade_130	N	N
Prevotella sp. SEQ072	1525	JN867238	clade_130	N	N
Leuconostoc carnosum	1177	NR_040811	clade_135	N	N
Leuconostoc gasicomitatum	1179	FN822744	clade_135	N	N
Leuconostoc inhae	1180	NR_025204	clade_135	N	N
Leuconostoc kimchii	1181	NR_075014	clade_135	N	N
Edwardsiella tarda	777	CP002154	clade_139	N	N
Photorhabdus asymbiotica	1466	Z76752	clade_139	N	N
Psychrobacter arcticus	1607	CP000082	clade_141	N	N
Psychrobacter cibarius	1608	HQ698586	clade_141	N	N
Psychrobacter cryohalolentis	1609	CP000323	clade_141	N	N
Psychrobacter faecalis	1610	HQ698566	clade_141	N	N
Psychrobacter nivimaris	1611	HQ698587	clade_141	N	N
Psychrobacter pulmonis	1612	HQ698582	clade_141	N	N
Pseudomonas aeruginosa	1592	AABQ07000001	clade_154	N	N
Pseudomonas sp. 2_1_26	1600	ACWU01000257	clade_154	N	N
Corynebacterium confusum	691	Y15886	clade_158	N	N
Corynebacterium propinquum	712	NR_037038	clade_158	N	N
Corynebacterium pseudodiphtheriticum	713	X84258	clade_158	N	N
Bartonella bacilliformis	338	NC_008783	clade_159	N	N
Bartonella grahamii	339	CP001562	clade_159	N	N
Bartonella henselae	340	NC_005956	clade_159	N	N
Bartonella quintana	341	BX897700	clade_159	N	N
Bartonella tamiae	342	EF672728	clade_159	N	N
Bartonella washoensis	343	FJ719017	clade_159	N	N
Brucella abortus	430	ACBJ01000075	clade_159	N	Category-B
Brucella canis	431	NR_044652	clade_159	N	Category-B
Brucella ceti	432	ACJD01000006	clade_159	N	Category-B
Brucella melitensis	433	AE009462	clade_159	N	Category-B
Brucella microti	434	NR_042549	clade_159	N	Category-B

Brucella ovis	435	NC_009504	clade_159	N	Category-B
Brucella sp. 83_13	436	ACBQ01000040	clade_159	N	Category-B
Brucella sp. BO1	437	EU053207	clade_159	N	Category-B
Brucella suis	438	ACBK01000034	clade_159	N	Category-B
Ochrobactrum anthropi	1360	NC_009667	clade_159	N	N
Ochrobactrum intermedium	1361	ACQA01000001	clade_159	N	N
Ochrobactrum pseudintermedium	1362	DQ365921	clade_159	N	N
Prevotella genomosp. C2	1496	AY278625	clade_164	N	N
Prevotella multisaccharivorax	1509	AFJE01000016	clade_164	N	N
Prevotella sp. oral clone IDR_CEC_0055	1543	AY550997	clade_164	N	N
Prevotella sp. oral taxon 292	1547	GQ422735	clade_164	N	N
Prevotella sp. oral taxon 300	1549	GU409549	clade_164	N	N
Prevotella marshii	1505	AEEI01000070	clade_166	N	N
Prevotella sp. oral clone IK053	1544	AY349401	clade_166	N	N
Prevotella sp. oral taxon 781	1554	GQ422744	clade_166	N	N
Prevotella stercorea	1562	AB244774	clade_166	N	N
Prevotella brevis	1487	NR_041954	clade_167	N	N
Prevotella ruminicola	1516	CP002006	clade_167	N	N
Prevotella sp. sp24	1560	AB003384	clade_167	N	N
Prevotella sp. sp34	1561	AB003385	clade_167	N	N
Prevotella albensis	1483	NR_025300	clade_168	N	N
Prevotella copri	1490	ACBX02000014	clade_168	N	N
Prevotella oulorum	1514	L16472	clade_168	N	N
Prevotella sp. BI_42	1518	AJ581354	clade_168	N	N
Prevotella sp. oral clone P4PB_83 P2	1546	AY207050	clade_168	N	N
Prevotella sp. oral taxon G60	1557	GU432133	clade_168	N	N
Prevotella amnii	1484	AB547670	clade_169	N	N
Bacteroides caccae	268	EU136686	clade_170	N	N
Bacteroides finegoldii	277	AB222699	clade_170	N	N
Bacteroides intestinalis	283	ABJL02000006	clade_171	N	N
Bacteroides sp. XB44A	326	AM230649	clade_171	N	N
Bifidobacteriaceae genomosp. C1	345	AY278612	clade_172	N	N
Bifidobacterium adolescentis	346	AAXD02000018	clade_172	N	N
Bifidobacterium angulatum	347	ABYS02000004	clade_172	N	N
Bifidobacterium animalis	348	CP001606	clade_172	N	N
Bifidobacterium breve	350	CP002743	clade_172	N	N
Bifidobacterium catenulatum	351	ABXY01000019	clade_172	N	N
Bifidobacterium dentium	352	CP001750	clade_172	N	OP
Bifidobacterium gallicum	353	ABXB03000004	clade_172	N	N
Bifidobacterium infantis	354	AY151398	clade_172	N	N
Bifidobacterium kashiwanohense	355	AB491757	clade_172	N	N
Bifidobacterium longum	356	ABQQ01000041	clade_172	N	N
Bifidobacterium pseudocatenulatum	357	ABXX02000002	clade_172	N	N
Bifidobacterium pseudolongum	358	NR_043442	clade_172	N	N

Bifidobacterium scardovii	359	AJ307005	clade_172	N	N
Bifidobacterium sp. HM2	360	AB425276	clade_172	N	N
Bifidobacterium sp. HMLN12	361	JF519685	clade_172	N	N
Bifidobacterium sp. M45	362	HM626176	clade_172	N	N
Bifidobacterium sp. MSX5B	363	HQ616382	clade_172	N	N
Bifidobacterium sp. TM_7	364	AB218972	clade_172	N	N
Bifidobacterium thermophilum	365	DQ340557	clade_172	N	N
Leuconostoc citreum	1178	AM157444	clade_175	N	N
Leuconostoc lactis	1182	NR_040823	clade_175	N	N
Eubacterium saburreum	858	AB525414	clade_178	Y	N
Eubacterium sp. oral clone IR009	866	AY349376	clade_178	Y	N
Lachnospiraceae bacterium ICM62	1061	HQ616401	clade_178	Y	N
Lachnospiraceae bacterium MSX33	1062	HQ616384	clade_178	Y	N
Lachnospiraceae bacterium oral taxon 107	1063	ADDS01000069	clade_178	Y	N
Alicyclobacillus acidocaldarius	122	NR_074721	clade_179	Y	N
Alicyclobacillus acidoterrestris	123	NR_040844	clade_179	N	N
Alicyclobacillus cycloheptanicus	125	NR_024754	clade_179	N	N
Acinetobacter baumannii	27	ACYQ01000014	clade_181	N	N
Acinetobacter calcoaceticus	28	AM157426	clade_181	N	N
Acinetobacter genomosp. C1	29	AY278636	clade_181	N	N
Acinetobacter haemolyticus	30	ADMT01000017	clade_181	N	N
Acinetobacter johnsonii	31	ACPL01000162	clade_181	N	N
Acinetobacter junii	32	ACPM01000135	clade_181	N	N
Acinetobacter lwoffii	33	ACPN01000204	clade_181	N	N
Acinetobacter parvus	34	AIEB01000124	clade_181	N	N
Acinetobacter schindleri	36	NR_025412	clade_181	N	N
Acinetobacter sp. 56A1	37	GQ178049	clade_181	N	N
Acinetobacter sp. CIP 101934	38	JQ638573	clade_181	N	N
Acinetobacter sp. CIP 102143	39	JQ638578	clade_181	N	N
Acinetobacter sp. M16_22	41	HM366447	clade_181	N	N
Acinetobacter sp. RUH2624	42	ACQF01000094	clade_181	N	N
Acinetobacter sp. SH024	43	ADCH01000068	clade_181	N	N
Lactobacillus jensenii	1092	ACQD01000066	clade_182	N	N
Alcaligenes faecalis	119	AB680368	clade_183	N	N
Alcaligenes sp. CO14	120	DQ643040	clade_183	N	N
Alcaligenes sp. S3	121	HQ262549	clade_183	N	N
Oligella ureolytica	1366	NR_041998	clade_183	N	N
Oligella urethralis	1367	NR_041753	clade_183	N	N
Eikenella corrodens	784	ACEA01000028	clade_185	N	N
Kingella denitrificans	1019	AEWV01000047	clade_185	N	N
Kingella genomosp. P1 oral cone MB2_C20	1020	DQ003616	clade_185	N	N
Kingella kingae	1021	AFHS01000073	clade_185	N	N
Kingella oralis	1022	ACJW02000005	clade_185	N	N
Kingella sp. oral clone ID059	1023	AY349381	clade_185	N	N
Neisseria elongata	1330	ADBF01000003	clade_185	N	N
Neisseria genomosp. P2 oral clone MB5_P15	1332	DQ003630	clade_185	N	N
Neisseria sp. oral clone JC012	1345	AY349388	clade_185	N	N
Neisseria sp. SMC_A9199	1342	FJ763637	clade_185	N	N

Simonsiella muelleri	1731	ADCY01000105	clade_185	N	N
Corynebacterium glucuronolyticum	700	ABYP01000081	clade_193	N	N
Corynebacterium pyruviciproducens	716	FJ185225	clade_193	N	N
Rothia aeria	1649	DQ673320	clade_194	N	N
Rothia dentocariosa	1650	ADDW01000024	clade_194	N	N
Rothia sp. oral taxon 188	1653	GU470892	clade_194	N	N
Corynebacterium accolens	681	ACGD01000048	clade_195	N	N
Corynebacterium macginleyi	707	AB359393	clade_195	N	N
Corynebacterium pseudogenitalium	714	ABYQ01000237	clade_195	N	N
Corynebacterium tuberculostearicum	729	ACVP01000009	clade_195	N	N
Lactobacillus casei	1074	CP000423	clade_198	N	N
Lactobacillus paracasei	1106	ABQV01000067	clade_198	N	N
Lactobacillus zeae	1143	NR_037122	clade_198	N	N
Prevotella dentalis	1492	AB547678	clade_205	N	N
Prevotella sp. oral clone ASCG10	1529	AY923148	clade_206	N	N
Prevotella sp. oral clone HF050	1541	AY349399	clade_206	N	N
Prevotella sp. oral clone ID019	1542	AY349400	clade_206	N	N
Prevotella sp. oral clone IK062	1545	AY349402	clade_206	N	N
Prevotella genomosp. P9 oral clone MB7_G16	1499	DQ003633	clade_207	N	N
Prevotella sp. oral clone AU069	1531	AY005062	clade_207	N	N
Prevotella sp. oral clone CY006	1532	AY005063	clade_207	N	N
Prevotella sp. oral clone FL019	1534	AY349392	clade_207	N	N
Actinomyces genomosp. C1	56	AY278610	clade_212	N	N
Actinomyces genomosp. C2	57	AY278611	clade_212	N	N
Actinomyces genomosp. P1 oral clone MB6_C03	58	DQ003632	clade_212	N	N
Actinomyces georgiae	59	GU561319	clade_212	N	N
Actinomyces israelii	60	AF479270	clade_212	N	N
Actinomyces massiliensis	61	AB545934	clade_212	N	N
Actinomyces meyeri	62	GU561321	clade_212	N	N
Actinomyces odontolyticus	66	ACYT01000123	clade_212	N	N
Actinomyces orihominis	68	AJ575186	clade_212	N	N
Actinomyces sp. CCUG 37290	71	AJ234058	clade_212	N	N
Actinomyces sp. ICM34	75	HQ616391	clade_212	N	N
Actinomyces sp. ICM41	76	HQ616392	clade_212	N	N
Actinomyces sp. ICM47	77	HQ616395	clade_212	N	N
Actinomyces sp. ICM54	78	HQ616398	clade_212	N	N
Actinomyces sp. oral clone IP081	87	AY349366	clade_212	N	N
Actinomyces sp. oral taxon 178	91	AEUH01000060	clade_212	N	N
Actinomyces sp. oral taxon 180	92	AEPP01000041	clade_212	N	N
Actinomyces sp. TeJ5	80	GU561315	clade_212	N	N
Haematobacter sp. BC14248	968	GU396991	clade_213	N	N
Paracoccus denitrificans	1424	CP000490	clade_213	N	N
Paracoccus marcusii	1425	NR_044922	clade_213	N	N
Grimontia hollisae	967	ADAQ01000013	clade_216	N	N
Shewanella putrefaciens	1723	CP002457	clade_216	N	N
Afipia genomosp. 4	111	EU117385	clade_217	N	N
Rhodopseudomonas palustris	1626	CP000301	clade_217	N	N
Methylobacterium extorquens	1223	NC_010172	clade_218	N	N

Methylobacterium podarium	1224	AY468363	clade_218	N	N
Methylobacterium radiotolerans	1225	GU294320	clade_218	N	N
Methylobacterium sp. 1sub	1226	AY468371	clade_218	N	N
Methylobacterium sp. MM4	1227	AY468370	clade_218	N	N
Clostridium baratii	555	NR_029229	clade_223	Y	N
Clostridium colicanis	576	FJ957863	clade_223	Y	N
Clostridium paraputrificum	611	AB536771	clade_223	Y	N
Clostridium sardiniense	621	NR_041006	clade_223	Y	N
Eubacterium budayi	837	NR_024682	clade_223	Y	N
Eubacterium moniliforme	851	HF558373	clade_223	Y	N
Eubacterium multiforme	852	NR_024683	clade_223	Y	N
Eubacterium nitritogenes	853	NR_024684	clade_223	Y	N
Achromobacter denitrificans	18	NR_042021	clade_224	N	N
Achromobacter piechaudii	19	ADMS01000149	clade_224	N	N
Achromobacter xylosoxidans	20	ACRC01000072	clade_224	N	N
Bordetella bronchiseptica	384	NR_025949	clade_224	N	OP
Bordetella holmesii	385	AB683187	clade_224	N	OP
Bordetella parapertussis	386	NR_025950	clade_224	N	OP
Bordetella pertussis	387	BX640418	clade_224	N	OP
Microbacterium chocolatum	1230	NR_037045	clade_225	N	N
Microbacterium flavescens	1231	EU714363	clade_225	N	N
Microbacterium lacticum	1233	EU714351	clade_225	N	N
Microbacterium oleivorans	1234	EU714381	clade_225	N	N
Microbacterium oxydans	1235	EU714348	clade_225	N	N
Microbacterium paraoxydans	1236	AJ491806	clade_225	N	N
Microbacterium phyllosphaerae	1237	EU714359	clade_225	N	N
Microbacterium schleiferi	1238	NR_044936	clade_225	N	N
Microbacterium sp. 768	1239	EU714378	clade_225	N	N
Microbacterium sp. oral strain C24KA	1240	AF287752	clade_225	N	N
Microbacterium testaceum	1241	EU714365	clade_225	N	N
Corynebacterium atypicum	686	NR_025540	clade_229	N	N
Corynebacterium mastitidis	708	AB359395	clade_229	N	N
Corynebacterium sp. NML 97_0186	725	GU238411	clade_229	N	N
Mycobacterium elephantis	1275	AF385898	clade_237	N	OP
Mycobacterium paraterrae	1288	EU919229	clade_237	N	OP
Mycobacterium phlei	1289	GU142920	clade_237	N	OP
Mycobacterium sp. 1776	1293	EU703152	clade_237	N	N
Mycobacterium sp. 1781	1294	EU703147	clade_237	N	N
Mycobacterium sp. AQ1GA4	1297	HM210417	clade_237	N	N
Mycobacterium sp. GN_10546	1299	FJ497243	clade_237	N	N
Mycobacterium sp. GN_10827	1300	FJ497247	clade_237	N	N
Mycobacterium sp. GN_11124	1301	FJ652846	clade_237	N	N
Mycobacterium sp. GN_9188	1302	FJ497240	clade_237	N	N
Mycobacterium sp. GR_2007_210	1303	FJ555538	clade_237	N	N
Anoxybacillus contaminans	172	NR_029006	clade_238	N	N
Anoxybacillus flavithermus	173	NR_074667	clade_238	Y	N
Bacillus aeolius	195	NR_025557	clade_238	N	N
Bacillus aerophilus	196	NR_042339	clade_238	Y	N

Bacillus aestuarii	197	GQ980243	clade_238	Y	N
Bacillus amyloliquefaciens	199	NR_075005	clade_238	Y	N
Bacillus anthracis	200	AAEN01000020	clade_238	Y	Category-A
Bacillus atrophaeus	201	NR_075016	clade_238	Y	OP
Bacillus badius	202	NR_036893	clade_238	Y	OP
Bacillus cereus	203	ABDJ01000015	clade_238	Y	OP
Bacillus circulans	204	AB271747	clade_238	Y	OP
Bacillus firmus	207	NR_025842	clade_238	Y	OP
Bacillus flexus	208	NR_024691	clade_238	Y	OP
Bacillus fordii	209	NR_025786	clade_238	Y	OP
Bacillus halmapalus	211	NR_026144	clade_238	Y	OP
Bacillus herbersteinensis	213	NR_042286	clade_238	Y	OP
Bacillus idriensis	215	NR_043268	clade_238	Y	OP
Bacillus lentus	216	NR_040792	clade_238	Y	OP
Bacillus licheniformis	217	NC_006270	clade_238	Y	OP
Bacillus megaterium	218	GU252124	clade_238	Y	OP
Bacillus nealsonii	219	NR_044546	clade_238	Y	OP
Bacillus niabensis	220	NR_043334	clade_238	Y	OP
Bacillus niacini	221	NR_024695	clade_238	Y	OP
Bacillus pocheonensis	222	NR_041377	clade_238	Y	OP
Bacillus pumilus	223	NR_074977	clade_238	Y	OP
Bacillus safensis	224	JQ624766	clade_238	Y	OP
Bacillus simplex	225	NR_042136	clade_238	Y	OP
Bacillus sonorensis	226	NR_025130	clade_238	Y	OP
Bacillus sp. 10403023 MM10403188	227	CAET01000089	clade_238	Y	OP
Bacillus sp. 2_A_57_CT2	230	ACWD01000095	clade_238	Y	OP
Bacillus sp. 2008724126	228	GU252108	clade_238	Y	OP
Bacillus sp. 2008724139	229	GU252111	clade_238	Y	OP
Bacillus sp. 7_16AIA	231	FN397518	clade_238	Y	OP
Bacillus sp. AP8	233	JX101689	clade_238	Y	OP
Bacillus sp. B27(2008)	234	EU362173	clade_238	Y	OP
Bacillus sp. BT1B_CT2	235	ACWC01000034	clade_238	Y	OP
Bacillus sp. GB1.1	236	FJ897765	clade_238	Y	OP
Bacillus sp. GB9	237	FJ897766	clade_238	Y	OP
Bacillus sp. HU19.1	238	FJ897769	clade_238	Y	OP
Bacillus sp. HU29	239	FJ897771	clade_238	Y	OP
Bacillus sp. HU33.1	240	FJ897772	clade_238	Y	OP
Bacillus sp. JC6	241	JF824800	clade_238	Y	OP
Bacillus sp. oral taxon F79	248	HM099654	clade_238	Y	OP
Bacillus sp. SRC_DSF1	243	GU797283	clade_238	Y	OP
Bacillus sp. SRC_DSF10	242	GU797292	clade_238	Y	OP
Bacillus sp. SRC_DSF2	244	GU797284	clade_238	Y	OP
Bacillus sp. SRC_DSF6	245	GU797288	clade_238	Y	OP
Bacillus sp. tc09	249	HQ844242	clade_238	Y	OP
Bacillus sp. zh168	250	FJ851424	clade_238	Y	OP
Bacillus sphaericus	251	DQ286318	clade_238	Y	OP
Bacillus sporothermodurans	252	NR_026010	clade_238	Y	OP

Bacillus subtilis	253	EU627588	clade_238	Y	OP
Bacillus thermoamylovorans	254	NR_029151	clade_238	Y	OP
Bacillus thuringiensis	255	NC_008600	clade_238	Y	OP
Bacillus weihenstephanensis	256	NR_074926	clade_238	Y	OP
Brevibacterium frigoritolerans	422	NR_042639	clade_238	N	N
Geobacillus kaustophilus	933	NR_074989	clade_238	Y	N
Geobacillus sp. E263	934	DQ647387	clade_238	N	N
Geobacillus sp. WCH70	935	CP001638	clade_238	N	N
Geobacillus stearothermophilus	936	NR_040794	clade_238	Y	N
Geobacillus thermocatenulatus	937	NR_043020	clade_238	N	N
Geobacillus thermodenitrificans	938	NR_074976	clade_238	Y	N
Geobacillus thermoglucosidasius	939	NR_043022	clade_238	Y	N
Geobacillus thermoleovorans	940	NR_074931	clade_238	N	N
Lysinibacillus fusiformis	1192	FN397522	clade_238	N	N
Lysinibacillus sphaericus	1193	NR_074883	clade_238	Y	N
Planomicrobium koreense	1468	NR_025011	clade_238	N	N
Sporosarcina newyorkensis	1754	AFPZ01000142	clade_238	N	N
Sporosarcina sp. 2681	1755	GU994081	clade_238	N	N
Ureibacillus composti	1968	NR_043746	clade_238	N	N
Ureibacillus suwonensis	1969	NR_043232	clade_238	N	N
Ureibacillus terrenus	1970	NR_025394	clade_238	N	N
Ureibacillus thermophilus	1971	NR_043747	clade_238	N	N
Ureibacillus thermosphaericus	1972	NR_040961	clade_238	N	N
Prevotella micans	1507	AGWK01000061	clade_239	N	N
Prevotella sp. oral clone DA058	1533	AY005065	clade_239	N	N
Prevotella sp. SEQ053	1523	JN867222	clade_239	N	N
Treponema socranskii	1937	NR_024868	clade_240	N	OP
Treponema sp. 6:H:D15A_4	1938	AY005083	clade_240	N	N
Treponema sp. oral taxon 265	1953	GU408850	clade_240	N	N
Treponema sp. oral taxon G85	1958	GU432215	clade_240	N	N
Porphyromonas endodontalis	1472	ACNN01000021	clade_241	N	N
Porphyromonas sp. oral clone BB134	1478	AY005068	clade_241	N	N
Porphyromonas sp. oral clone F016	1479	AY005069	clade_241	N	N
Porphyromonas sp. oral clone P2PB_52 P1	1480	AY207054	clade_241	N	N
Porphyromonas sp. oral clone P4GB_100 P2	1481	AY207057	clade_241	N	N
Acidovorax sp. 98_63833	26	AY258065	clade_245	N	N
Comamonadaceae bacterium NML000135	663	JN585335	clade_245	N	N
Comamonadaceae bacterium NML790751	664	JN585331	clade_245	N	N
Comamonadaceae bacterium NML910035	665	JN585332	clade_245	N	N
Comamonadaceae bacterium NML910036	666	JN585333	clade_245	N	N
Comamonas sp. NSP5	668	AB076850	clade_245	N	N
Delftia acidovorans	748	CP000884	clade_245	N	N
Xenophilus aerolatus	2018	JN585329	clade_245	N	N
Clostridiales sp. SS3/4	543	AY305316	clade_246	Y	N
Oribacterium sp. oral taxon 078	1380	ACIQ02000009	clade_246	N	N
Oribacterium sp. oral taxon 102	1381	GQ422713	clade_246	N	N
Weissella cibaria	2007	NR_036924	clade_247	N	N
Weissella confusa	2008	NR_040816	clade_247	N	N

Weissella hellenica	2009	AB680902	clade_247	N	N
Weissella kandleri	2010	NR_044659	clade_247	N	N
Weissella koreensis	2011	NR_075058	clade_247	N	N
Weissella paramesenteroides	2012	ACKU01000017	clade_247	N	N
Weissella sp. KLDS 7.0701	2013	EU600924	clade_247	N	N
Mobiluncus curtisii	1251	AEPZ01000013	clade_249	N	N
Clostridium beijerinckii	557	NR_074434	clade_252	Y	N
Clostridium botulinum	560	NC_010723	clade_252	Y	Category-A
Clostridium butyricum	561	ABDT01000017	clade_252	Y	N
Clostridium chauvoei	568	EU106372	clade_252	Y	N
Clostridium favososporum	582	X76749	clade_252	Y	N
Clostridium histolyticum	592	HF558362	clade_252	Y	N
Clostridium isatidis	597	NR_026347	clade_252	Y	N
Clostridium limosum	602	FR870444	clade_252	Y	N
Clostridium sartagoforme	622	NR_026490	clade_252	Y	N
Clostridium septicum	624	NR_026020	clade_252	Y	N
Clostridium sp. 7_2_43FAA	626	ACDK01000101	clade_252	Y	N
Clostridium sporogenes	645	ABKW02000003	clade_252	Y	N
Clostridium tertium	653	Y18174	clade_252	Y	N
Clostridium carnis	564	NR_044716	clade_253	Y	N
Clostridium celatum	565	X77844	clade_253	Y	N
Clostridium disporicum	579	NR_026491	clade_253	Y	N
Clostridium gasigenes	585	NR_024945	clade_253	Y	N
Clostridium quinii	616	NR_026149	clade_253	Y	N
Enhydrobacter aerosaccus	785	ACYI01000081	clade_256	N	N
Moraxella osloensis	1262	JN175341	clade_256	N	N
Moraxella sp. GM2	1264	JF837191	clade_256	N	N
Brevibacterium casei	420	JF951998	clade_257	N	N
Brevibacterium epidermidis	421	NR_029262	clade_257	N	N
Brevibacterium sanguinis	426	NR_028016	clade_257	N	N
Brevibacterium sp. H15	427	AB177640	clade_257	N	N
Clostridium hylemonae	593	AB023973	clade_260	Y	N
Clostridium scindens	623	AF262238	clade_260	Y	N
Lachnospiraceae bacterium 5_1_57FAA	1054	ACTR01000020	clade_260	Y	N
Acinetobacter radioresistens	35	ACVR01000010	clade_261	N	N
Clostridium glycyrrhizinilyticum	588	AB233029	clade_262	Y	N
Clostridium nexile	607	X73443	clade_262	Y	N
Coprococcus comes	674	ABVR01000038	clade_262	Y	N
Lachnospiraceae bacterium 1_1_57FAA	1048	ACTM01000065	clade_262	Y	N
Lachnospiraceae bacterium 1_4_56FAA	1049	ACTN01000028	clade_262	Y	N
Lachnospiraceae bacterium 8_1_57FAA	1057	ACWQ01000079	clade_262	Y	N
Ruminococcus lactaris	1663	ABOU02000049	clade_262	Y	N
Ruminococcus torques	1670	AAVP02000002	clade_262	Y	N
Lactobacillus alimentarius	1068	NR_044701	clade_263	N	N
Lactobacillus farciminis	1082	NR_044707	clade_263	N	N
Lactobacillus kimchii	1097	NR_025045	clade_263	N	N
Lactobacillus nodensis	1101	NR_041629	clade_263	N	N

Lactobacillus tucceti	1138	NR_042194	clade_263	N	N
Pseudomonas mendocina	1595	AAUL01000021	clade_265	N	N
Pseudomonas pseudoalcaligenes	1598	NR_037000	clade_265	N	N
Pseudomonas sp. NP522b	1602	EU723211	clade_265	N	N
Pseudomonas stutzeri	1603	AM905854	clade_265	N	N
Paenibacillus barcinonensis	1390	NR_042272	clade_270	N	N
Paenibacillus barengoltzii	1391	NR_042756	clade_270	N	N
Paenibacillus chibensis	1392	NR_040885	clade_270	N	N
Paenibacillus cookii	1393	NR_025372	clade_270	N	N
Paenibacillus durus	1394	NR_037017	clade_270	N	N
Paenibacillus glucanolyticus	1395	D78470	clade_270	N	N
Paenibacillus lactis	1396	NR_025739	clade_270	N	N
Paenibacillus lautus	1397	NR_040882	clade_270	Y	N
Paenibacillus pabuli	1398	NR_040853	clade_270	N	N
Paenibacillus polymyxa	1399	NR_037006	clade_270	Y	N
Paenibacillus popilliae	1400	NR_040888	clade_270	N	N
Paenibacillus sp. CIP 101062	1401	HM212646	clade_270	N	N
Paenibacillus sp. HGF5	1402	AEXS01000095	clade_270	Y	N
Paenibacillus sp. HGF7	1403	AFDH01000147	clade_270	Y	N
Paenibacillus sp. JC66	1404	JF824808	clade_270	N	N
Paenibacillus sp. R_27413	1405	HE586333	clade_270	N	N
Paenibacillus sp. R_27422	1406	HE586338	clade_270	N	N
Paenibacillus timonensis	1408	NR_042844	clade_270	N	N
Rothia mucilaginosa	1651	ACVO01000020	clade_271	N	N
Rothia nasimurium	1652	NR_025310	clade_271	N	N
Prevotella sp. oral taxon 302	1550	ACZK01000043	clade_280	N	N
Prevotella sp. oral taxon F68	1556	HM099652	clade_280	N	N
Prevotella tannerae	1563	ACIJ02000018	clade_280	N	N
Prevotellaceae bacterium P4P_62 P1	1566	AY207061	clade_280	N	N
Porphyromonas asaccharolytica	1471	AENO01000048	clade_281	N	N
Porphyromonas gingivalis	1473	AE015924	clade_281	N	N
Porphyromonas macacae	1475	NR_025908	clade_281	N	N
Porphyromonas sp. UQD 301	1477	EU012301	clade_281	N	N
Porphyromonas uenonis	1482	ACLR01000152	clade_281	N	N
Leptotrichia buccalis	1165	CP001685	clade_282	N	N
Leptotrichia hofstadii	1168	ACVB02000032	clade_282	N	N
Leptotrichia sp. oral clone HE012	1173	AY349386	clade_282	N	N
Leptotrichia sp. oral taxon 223	1176	GU408547	clade_282	N	N
Bacteroides fluxus	278	AFBN01000029	clade_285	N	N
Bacteroides helcogenes	281	CP002352	clade_285	N	N
Parabacteroides johnsonii	1419	ABYH01000014	clade_286	N	N
Parabacteroides merdae	1420	EU136685	clade_286	N	N
Treponema denticola	1926	ADEC01000002	clade_288	N	OP
Treponema genomosp. P5 oral clone MB3_P23	1929	DQ003624	clade_288	N	N
Treponema putidum	1935	AJ543428	clade_288	N	OP
Treponema sp. oral clone P2PB_53 P3	1942	AY207055	clade_288	N	N
Treponema sp. oral taxon 247	1949	GU408748	clade_288	N	N
Treponema sp. oral taxon 250	1950	GU408776	clade_288	N	N

Treponema sp. oral taxon 251	1951	GU408781	clade_288	N	N
Anaerococcus hydrogenalis	144	ABXA01000039	clade_289	N	N
Anaerococcus sp. 8404299	148	HM587318	clade_289	N	N
Anaerococcus sp. gpac215	156	AM176540	clade_289	N	N
Anaerococcus vaginalis	158	ACXU01000016	clade_289	N	N
Propionibacterium acidipropionici	1569	NC_019395	clade_290	N	N
Propionibacterium avidum	1571	AJ003055	clade_290	N	N
Propionibacterium granulosum	1573	FJ785716	clade_290	N	N
Propionibacterium jensenii	1574	NR_042269	clade_290	N	N
Propionibacterium propionicum	1575	NR_025277	clade_290	N	N
Propionibacterium sp. H456	1577	AB177643	clade_290	N	N
Propionibacterium thoenii	1581	NR_042270	clade_290	N	N
Bifidobacterium bifidum	349	ABQP01000027	clade_293	N	N
Leuconostoc mesenteroides	1183	ACKV01000113	clade_295	N	N
Leuconostoc pseudomesenteroides	1184	NR_040814	clade_295	N	N
Eubacterium sp. oral clone JI012	868	AY349379	clade_298	Y	N
Johnsonella ignava	1016	X87152	clade_298	N	N
Propionibacterium acnes	1570	ADJM01000010	clade_299	N	N
Propionibacterium sp. 434_HC2	1576	AFIL01000035	clade_299	N	N
Propionibacterium sp. LG	1578	AY354921	clade_299	N	N
Propionibacterium sp. S555a	1579	AB264622	clade_299	N	N
Alicyclobacillus contaminans	124	NR_041475	clade_301	Y	N
Alicyclobacillus herbarius	126	NR_024753	clade_301	Y	N
Alicyclobacillus pomorum	127	NR_024801	clade_301	Y	N
Alicyclobacillus sp. CCUG 53762	128	HE613268	clade_301	N	N
Actinomyces cardiffensis	53	GU470888	clade_303	N	N
Actinomyces funkei	55	HQ906497	clade_303	N	N
Actinomyces sp. HKU31	74	HQ335393	clade_303	N	N
Actinomyces sp. oral taxon C55	94	HM099646	clade_303	N	N
Kerstersia gyiorum	1018	NR_025669	clade_307	N	N
Pigmentiphaga daeguensis	1467	JN585327	clade_307	N	N
Aeromonas allosaccharophila	104	S39232	clade_308	N	N
Aeromonas enteropelogenes	105	X71121	clade_308	N	N
Aeromonas hydrophila	106	NC_008570	clade_308	N	N
Aeromonas jandaei	107	X60413	clade_308	N	N
Aeromonas salmonicida	108	NC_009348	clade_308	N	N
Aeromonas trota	109	X60415	clade_308	N	N
Aeromonas veronii	110	NR_044845	clade_308	N	N
Blautia coccoides	373	AB571656	clade_309	Y	N
Blautia glucerasea	374	AB588023	clade_309	Y	N
Blautia glucerasei	375	AB439724	clade_309	Y	N
Blautia hansenii	376	ABYU02000037	clade_309	Y	N
Blautia luti	378	AB691576	clade_309	Y	N
Blautia producta	379	AB600998	clade_309	Y	N
Blautia schinkii	380	NR_026312	clade_309	Y	N
Blautia sp. M25	381	HM626178	clade_309	Y	N
Blautia stercoris	382	HM626177	clade_309	Y	N
Blautia wexlerae	383	EF036467	clade_309	Y	N

Bryantella formatexigens	439	ACCL02000018	clade_309	Y	N
Clostridium coccoides	573	EF025906	clade_309	Y	N
Eubacterium cellulosolvens	839	AY178842	clade_309	Y	N
Lachnospiraceae bacterium 6_1_63FAA	1056	ACTV01000014	clade_309	Y	N
Marvinbryantia formatexigens	1196	AJ505973	clade_309	N	N
Ruminococcus hansenii	1662	M59114	clade_309	Y	N
Ruminococcus obeum	1664	AY169419	clade_309	Y	N
Ruminococcus sp. 5_1_39BFAA	1666	ACII01000172	clade_309	Y	N
Ruminococcus sp. K_1	1669	AB222208	clade_309	Y	N
Syntrophococcus sucromutans	1911	NR_036869	clade_309	Y	N
Rhodobacter sp. oral taxon C30	1620	HM099648	clade_310	N	N
Rhodobacter sphaeroides	1621	CP000144	clade_310	N	N
Lactobacillus antri	1071	ACLL01000037	clade_313	N	N
Lactobacillus coleohominis	1076	ACOH01000030	clade_313	N	N
Lactobacillus fermentum	1083	CP002033	clade_313	N	N
Lactobacillus gastricus	1085	AICN01000060	clade_313	N	N
Lactobacillus mucosae	1099	FR693800	clade_313	N	N
Lactobacillus oris	1103	AEKL01000077	clade_313	N	N
Lactobacillus pontis	1111	HM218420	clade_313	N	N
Lactobacillus reuteri	1112	ACGW02000012	clade_313	N	N
Lactobacillus sp. KLDS 1.0707	1127	EU600911	clade_313	N	N
Lactobacillus sp. KLDS 1.0709	1128	EU600913	clade_313	N	N
Lactobacillus sp. KLDS 1.0711	1129	EU600915	clade_313	N	N
Lactobacillus sp. KLDS 1.0713	1131	EU600917	clade_313	N	N
Lactobacillus sp. KLDS 1.0716	1132	EU600921	clade_313	N	N
Lactobacillus sp. KLDS 1.0718	1133	EU600922	clade_313	N	N
Lactobacillus sp. oral taxon 052	1137	GQ422710	clade_313	N	N
Lactobacillus vaginalis	1140	ACGV01000168	clade_313	N	N
Brevibacterium aurantiacum	419	NR_044854	clade_314	N	N
Brevibacterium linens	423	AJ315491	clade_314	N	N
Lactobacillus pentosus	1108	JN813103	clade_315	N	N
Lactobacillus plantarum	1110	ACGZ02000033	clade_315	N	N
Lactobacillus sp. KLDS 1.0702	1123	EU600906	clade_315	N	N
Lactobacillus sp. KLDS 1.0703	1124	EU600907	clade_315	N	N
Lactobacillus sp. KLDS 1.0704	1125	EU600908	clade_315	N	N
Lactobacillus sp. KLDS 1.0705	1126	EU600909	clade_315	N	N
Agrobacterium radiobacter	115	CP000628	clade_316	N	N
Agrobacterium tumefaciens	116	AJ389893	clade_316	N	N
Corynebacterium argentoratense	685	EF463055	clade_317	N	N
Corynebacterium diphtheriae	693	NC_002935	clade_317	N	OP
Corynebacterium pseudotuberculosis	715	NR_037070	clade_317	N	N
Corynebacterium renale	717	NR_037069	clade_317	N	N
Corynebacterium ulcerans	731	NR_074467	clade_317	N	N
Aurantimonas coralicida	191	AY065627	clade_318	N	N
Aureimonas altamirensis	192	FN658986	clade_318	N	N
Lactobacillus acidipiscis	1066	NR_024718	clade_320	N	N
Lactobacillus salivarius	1117	AEBA01000145	clade_320	N	N
Lactobacillus sp. KLDS 1.0719	1134	EU600923	clade_320	N	N

Lactobacillus buchneri	1073	ACGH01000101	clade_321	N	N
Lactobacillus genomosp. C1	1086	AY278619	clade_321	N	N
Lactobacillus genomosp. C2	1087	AY278620	clade_321	N	N
Lactobacillus hilgardii	1089	ACGP01000200	clade_321	N	N
Lactobacillus kefiri	1096	NR_042230	clade_321	N	N
Lactobacillus parabuchneri	1105	NR_041294	clade_321	N	N
Lactobacillus parakefiri	1107	NR_029039	clade_321	N	N
Lactobacillus curvatus	1079	NR_042437	clade_322	N	N
Lactobacillus sakei	1116	DQ989236	clade_322	N	N
Aneurinibacillus aneurinilyticus	167	AB101592	clade_323	N	N
Aneurinibacillus danicus	168	NR_028657	clade_323	N	N
Aneurinibacillus migulanus	169	NR_036799	clade_323	N	N
Aneurinibacillus terranovensis	170	NR_042271	clade_323	N	N
Staphylococcus aureus	1757	CP002643	clade_325	N	Category-B
Staphylococcus auricularis	1758	JQ624774	clade_325	N	N
Staphylococcus capitis	1759	ACFR01000029	clade_325	N	N
Staphylococcus caprae	1760	ACRH01000033	clade_325	N	N
Staphylococcus carnosus	1761	NR_075003	clade_325	N	N
Staphylococcus cohnii	1762	JN175375	clade_325	N	N
Staphylococcus condimenti	1763	NR_029345	clade_325	N	N
Staphylococcus epidermidis	1764	ACHE01000056	clade_325	N	N
Staphylococcus equorum	1765	NR_027520	clade_325	N	N
Staphylococcus haemolyticus	1767	NC_007168	clade_325	N	N
Staphylococcus hominis	1768	AM157418	clade_325	N	N
Staphylococcus lugdunensis	1769	AEQA01000024	clade_325	N	N
Staphylococcus pasteuri	1770	FJ189773	clade_325	N	N
Staphylococcus pseudintermedius	1771	CP002439	clade_325	N	N
Staphylococcus saccharolyticus	1772	NR_029158	clade_325	N	N
Staphylococcus saprophyticus	1773	NC_007350	clade_325	N	N
Staphylococcus sp. clone bottae7	1777	AF467424	clade_325	N	N
Staphylococcus sp. H292	1775	AB177642	clade_325	N	N
Staphylococcus sp. H780	1776	AB177644	clade_325	N	N
Staphylococcus succinus	1778	NR_028667	clade_325	N	N
Staphylococcus warneri	1780	ACPZ01000009	clade_325	N	N
Staphylococcus xylosus	1781	AY395016	clade_325	N	N
Cardiobacterium hominis	490	ACKY01000036	clade_326	N	N
Cardiobacterium valvarum	491	NR_028847	clade_326	N	N
Pseudomonas fluorescens	1593	AY622220	clade_326	N	N
Pseudomonas gessardii	1594	FJ943496	clade_326	N	N
Pseudomonas monteilii	1596	NR_024910	clade_326	N	N
Pseudomonas poae	1597	GU188951	clade_326	N	N
Pseudomonas putida	1599	AF094741	clade_326	N	N
Pseudomonas sp. G1229	1601	DQ910482	clade_326	N	N
Pseudomonas tolaasii	1604	AF320988	clade_326	N	N
Pseudomonas viridiflava	1605	NR_042764	clade_326	N	N
Bacillus alcalophilus	198	X76436	clade_327	Y	N
Bacillus clausii	205	FN397477	clade_327	Y	OP

Bacillus gelatini	210	NR_025595	clade_327	Y	OP
Bacillus halodurans	212	AY144582	clade_327	Y	OP
Bacillus sp. oral taxon F26	246	HM099642	clade_327	Y	OP
Listeria grayi	1185	ACCR02000003	clade_328	N	OP
Listeria innocua	1186	JF967625	clade_328	N	N
Listeria ivanovii	1187	X56151	clade_328	N	N
Listeria monocytogenes	1188	CP002003	clade_328	N	Category-B
Listeria welshimeri	1189	AM263198	clade_328	N	OP
Capnocytophaga sp. oral clone ASCH05	484	AY923149	clade_333	N	N
Capnocytophaga sputigena	489	ABZV01000054	clade_333	N	N
Leptotrichia genomosp. C1	1166	AY278621	clade_334	N	N
Leptotrichia shahii	1169	AY029806	clade_334	N	N
Leptotrichia sp. neutropenicPatient	1170	AF189244	clade_334	N	N
Leptotrichia sp. oral clone GT018	1171	AY349384	clade_334	N	N
Leptotrichia sp. oral clone GT020	1172	AY349385	clade_334	N	N
Bacteroides sp. 20_3	296	ACRQ01000064	clade_335	N	N
Bacteroides sp. 3_1_19	307	ADCJ01000062	clade_335	N	N
Bacteroides sp. 3_2_5	311	ACIB01000079	clade_335	N	N
Parabacteroides distasonis	1416	CP000140	clade_335	N	N
Parabacteroides goldsteinii	1417	AY974070	clade_335	N	N
Parabacteroides gordonii	1418	AB470344	clade_335	N	N
Parabacteroides sp. D13	1421	ACPW01000017	clade_335	N	N
Capnocytophaga genomosp. C1	477	AY278613	clade_336	N	N
Capnocytophaga ochracea	480	AEOH01000054	clade_336	N	N
Capnocytophaga sp. GEJ8	481	GU561335	clade_336	N	N
Capnocytophaga sp. oral strain A47ROY	486	AY005077	clade_336	N	N
Capnocytophaga sp. S1b	482	U42009	clade_336	N	N
Paraprevotella clara	1426	AFFY01000068	clade_336	N	N
Bacteroides heparinolyticus	282	JN867284	clade_338	N	N
Prevotella heparinolytica	1500	GQ422742	clade_338	N	N
Treponema genomosp. P4 oral clone MB2_G19	1928	DQ003618	clade_339	N	N
Treponema genomosp. P6 oral clone MB4_G11	1930	DQ003625	clade_339	N	N
Treponema sp. oral taxon 254	1952	GU408803	clade_339	N	N
Treponema sp. oral taxon 508	1956	GU413616	clade_339	N	N
Treponema sp. oral taxon 518	1957	GU413640	clade_339	N	N
Chlamydia muridarum	502	AE002160	clade_341	N	OP
Chlamydia trachomatis	504	U68443	clade_341	N	OP
Chlamydia psittaci	503	NR_036864	clade_342	N	Category-B
Chlamydophila pneumoniae	509	NC_002179	clade_342	N	OP
Chlamydophila psittaci	510	D85712	clade_342	N	OP
Anaerococcus octavius	146	NR_026360	clade_343	N	N
Anaerococcus sp. 8405254	149	HM587319	clade_343	N	N
Anaerococcus sp. 9401487	150	HM587322	clade_343	N	N
Anaerococcus sp. 9403502	151	HM587325	clade_343	N	N
Gardnerella vaginalis	923	CP001849	clade_344	N	N
Campylobacter lari	466	CP000932	clade_346	N	OP

Anaerobiospirillum succiniciproducens	142	NR_026075	clade_347	N	N
Anaerobiospirillum thomasii	143	AJ420985	clade_347	N	N
Ruminobacter amylophilus	1654	NR_026450	clade_347	N	N
Succinatimonas hippei	1897	AEVO01000027	clade_347	N	N
Actinomyces europaeus	54	NR_026363	clade_348	N	N
Actinomyces sp. oral clone GU009	82	AY349361	clade_348	N	N
Moraxella catarrhalis	1260	CP002005	clade_349	N	N
Moraxella lincolnii	1261	FR822735	clade_349	N	N
Moraxella sp. 16285	1263	JF682466	clade_349	N	N
Psychrobacter sp. 13983	1613	HM212668	clade_349	N	N
Actinobaculum massiliae	49	AF487679	clade_350	N	N
Actinobaculum schaalii	50	AY957507	clade_350	N	N
Actinobaculum sp. BM#101342	51	AY282578	clade_350	N	N
Actinobaculum sp. P2P_19 P1	52	AY207066	clade_350	N	N
Actinomyces sp. oral clone IO076	84	AY349363	clade_350	N	N
Actinomyces sp. oral taxon 848	93	ACUY01000072	clade_350	N	N
Clostridium innocuum	595	M23732	clade_351	Y	N
Clostridium sp. HGF2	628	AENW01000022	clade_351	Y	N
Actinomyces neuii	65	X71862	clade_352	N	N
Mobiluncus mulieris	1252	ACKW01000035	clade_352	N	N
Clostridium perfringens	612	ABDW01000023	clade_353	Y	Category-B
Sarcina ventriculi	1687	NR_026146	clade_353	Y	N
Clostridium bartlettii	556	ABEZ02000012	clade_354	Y	N
Clostridium bifermentans	558	X73437	clade_354	Y	N
Clostridium ghonii	586	AB542933	clade_354	Y	N
Clostridium glycolicum	587	FJ384385	clade_354	Y	N
Clostridium mayombei	605	FR733682	clade_354	Y	N
Clostridium sordellii	625	AB448946	clade_354	Y	N
Clostridium sp. MT4 E	635	FJ159523	clade_354	Y	N
Eubacterium tenue	872	M59118	clade_354	Y	N
Clostridium argentinense	553	NR_029232	clade_355	Y	N
Clostridium sp. JC122	630	CAEV01000127	clade_355	Y	N
Clostridium sp. NMBHI_1	636	JN093130	clade_355	Y	N
Clostridium subterminale	650	NR_041795	clade_355	Y	N
Clostridium sulfidigenes	651	NR_044161	clade_355	Y	N
Blastomonas natatoria	372	NR_040824	clade_356	N	N
Novosphingobium aromaticivorans	1357	AAAV03000008	clade_356	N	N
Sphingomonas sp. oral clone FI012	1745	AY349411	clade_356	N	N
Sphingopyxis alaskensis	1749	CP000356	clade_356	N	N
Oxalobacter formigenes	1389	ACDQ01000020	clade_357	N	N
Veillonella atypica	1974	AEDS01000059	clade_358	N	N
Veillonella dispar	1975	ACIK02000021	clade_358	N	N
Veillonella genomosp. P1 oral clone MB5_P17	1976	DQ003631	clade_358	N	N
Veillonella parvula	1978	ADFU01000009	clade_358	N	N
Veillonella sp. 3_1_44	1979	ADCV01000019	clade_358	N	N
Veillonella sp. 6_1_27	1980	ADCW01000016	clade_358	N	N
Veillonella sp. ACP1	1981	HQ616359	clade_358	N	N

Veillonella sp. AS16	1982	HQ616365	clade_358	N	N
Veillonella sp. BS32b	1983	HQ616368	clade_358	N	N
Veillonella sp. ICM51a	1984	HQ616396	clade_358	N	N
Veillonella sp. MSA12	1985	HQ616381	clade_358	N	N
Veillonella sp. NVG 100cf	1986	EF108443	clade_358	N	N
Veillonella sp. OK11	1987	JN695650	clade_358	N	N
Veillonella sp. oral clone ASCG01	1990	AY923144	clade_358	N	N
Veillonella sp. oral clone ASCG02	1991	AY953257	clade_358	N	N
Veillonella sp. oral clone OH1A	1992	AY947495	clade_358	N	N
Veillonella sp. oral taxon 158	1993	AENU01000007	clade_358	N	N
Dorea formicigenerans	773	AAXA02000006	clade_360	Y	N
Dorea longicatena	774	AJ132842	clade_360	Y	N
Lachnospiraceae bacterium 2_1_46FAA	1050	ADLB01000035	clade_360	Y	N
Lachnospiraceae bacterium 2_1_58FAA	1051	ACTO01000052	clade_360	Y	N
Lachnospiraceae bacterium 4_1_37FAA	1053	ADCR01000030	clade_360	Y	N
Lachnospiraceae bacterium 9_1_43BFAA	1058	ACTX01000023	clade_360	Y	N
Ruminococcus gnavus	1661	X94967	clade_360	Y	N
Ruminococcus sp. ID8	1668	AY960564	clade_360	Y	N
Kocuria marina	1040	GQ260086	clade_365	N	N
Kocuria rhizophila	1042	AY030315	clade_365	N	N
Kocuria rosea	1043	X87756	clade_365	N	N
Kocuria varians	1044	AF542074	clade_365	N	N
Blautia hydrogenotrophica	377	ACBZ01000217	clade_368	Y	N
Clostridiaceae bacterium END_2	531	EF451053	clade_368	N	N
Lactonifactor longoviformis	1147	DQ100449	clade_368	Y	N
Robinsoniella peoriensis	1633	AF445258	clade_368	Y	N
Micrococcus antarcticus	1242	NR_025285	clade_371	N	N
Micrococcus luteus	1243	NR_075062	clade_371	N	N
Micrococcus lylae	1244	NR_026200	clade_371	N	N
Micrococcus sp. 185	1245	EU714334	clade_371	N	N
Lactobacillus brevis	1072	EU194349	clade_372	N	N
Lactobacillus parabrevis	1104	NR_042456	clade_372	N	N
Pediococcus acidilactici	1436	ACXB01000026	clade_372	N	N
Pediococcus pentosaceus	1437	NR_075052	clade_372	N	N
Lactobacillus dextrinicus	1081	NR_036861	clade_373	N	N
Lactobacillus perolens	1109	NR_029360	clade_373	N	N
Lactobacillus rhamnosus	1113	ABWJ01000068	clade_373	N	N
Lactobacillus saniviri	1118	AB602569	clade_373	N	N
Lactobacillus sp. BT6	1121	HQ616370	clade_373	N	N
Mycobacterium mageritense	1282	FR798914	clade_374	N	OP
Mycobacterium neoaurum	1286	AF268445	clade_374	N	OP
Mycobacterium smegmatis	1291	CP000480	clade_374	N	OP
Mycobacterium sp. HE5	1304	AJ012738	clade_374	N	N
Dysgonomonas gadei	775	ADLV01000001	clade_377	N	N
Dysgonomonas mossii	776	ADLW01000023	clade_377	N	N
Porphyromonas levii	1474	NR_025907	clade_377	N	N
Porphyromonas somerae	1476	AB547667	clade_377	N	N
Bacteroides barnesiae	267	NR_041446	clade_378	N	N

Bacteroides coprocola	272	ABIY02000050	clade_378	N	N
Bacteroides coprophilus	273	ACBW01000012	clade_378	N	N
Bacteroides dorei	274	ABWZ01000093	clade_378	N	N
Bacteroides massiliensis	284	AB200226	clade_378	N	N
Bacteroides plebeius	289	AB200218	clade_378	N	N
Bacteroides sp. 3_1_33FAA	309	ACPS01000085	clade_378	N	N
Bacteroides sp. 3_1_40A	310	ACRT01000136	clade_378	N	N
Bacteroides sp. 4_3_47FAA	313	ACDR02000029	clade_378	N	N
Bacteroides sp. 9_1_42FAA	314	ACAA01000096	clade_378	N	N
Bacteroides sp. NB_8	323	AB117565	clade_378	N	N
Bacteroides vulgatus	331	CP000139	clade_378	N	N
Bacteroides ovatus	287	ACWH01000036	clade_38	N	N
Bacteroides sp. 1_1_30	294	ADCL01000128	clade_38	N	N
Bacteroides sp. 2_1_22	297	ACPQ01000117	clade_38	N	N
Bacteroides sp. 2_2_4	299	ABZZ01000168	clade_38	N	N
Bacteroides sp. 3_1_23	308	ACRS01000081	clade_38	N	N
Bacteroides sp. D1	318	ACAB02000030	clade_38	N	N
Bacteroides sp. D2	321	ACGA01000077	clade_38	N	N
Bacteroides sp. D22	320	ADCK01000151	clade_38	N	N
Bacteroides xylanisolvens	332	ADKP01000087	clade_38	N	N
Treponema lecithinolyticum	1931	NR_026247	clade_380	N	OP
Treponema parvum	1933	AF302937	clade_380	N	OP
Treponema sp. oral clone JU025	1940	AY349417	clade_380	N	N
Treponema sp. oral taxon 270	1954	GQ422733	clade_380	N	N
Parascardovia denticolens	1428	ADEB01000020	clade_381	N	N
Scardovia inopinata	1688	AB029087	clade_381	N	N
Scardovia wiggsiae	1689	AY278626	clade_381	N	N
Clostridiales bacterium 9400853	533	HM587320	clade_384	N	N
Eubacterium infirmum	849	U13039	clade_384	Y	N
Eubacterium sp. WAL 14571	864	FJ687606	clade_384	Y	N
Mogibacterium diversum	1254	NR_027191	clade_384	N	N
Mogibacterium neglectum	1255	NR_027203	clade_384	N	N
Mogibacterium pumilum	1256	NR_028608	clade_384	N	N
Mogibacterium timidum	1257	Z36296	clade_384	N	N
Erysipelotrichaceae bacterium 5_2_54FAA	823	ACZW01000054	clade_385	Y	N
Eubacterium biforme	835	ABYT01000002	clade_385	Y	N
Eubacterium cylindroides	842	FP929041	clade_385	Y	N
Eubacterium dolichum	844	L34682	clade_385	Y	N
Eubacterium sp. 3_1_31	861	ACTL01000045	clade_385	Y	N
Eubacterium tortuosum	873	NR_044648	clade_385	Y	N
Borrelia burgdorferi	389	ABGI01000001	clade_386	N	OP
Borrelia garinii	392	ABJV01000001	clade_386	N	OP
Borrelia sp. NE49	397	AJ224142	clade_386	N	OP
Caldimonas manganoxidans	457	NR_040787	clade_387	N	N
Comamonadaceae bacterium oral taxon F47	667	HM099651	clade_387	N	N
Lautropia mirabilis	1149	AEQP01000026	clade_387	N	N
Lautropia sp. oral clone AP009	1150	AY005030	clade_387	N	N
Bulleidia extructa	441	ADFR01000011	clade_388	Y	N

Solobacterium moorei	1739	AECQ01000039	clade_388	Y	N
Peptoniphilus asaccharolyticus	1441	D14145	clade_389	N	N
Peptoniphilus duerdenii	1442	EU526290	clade_389	N	N
Peptoniphilus harei	1443	NR_026358	clade_389	N	N
Peptoniphilus indolicus	1444	AY153431	clade_389	N	N
Peptoniphilus lacrimalis	1446	ADDO01000050	clade_389	N	N
Peptoniphilus sp. gpac077	1450	AM176527	clade_389	N	N
Peptoniphilus sp. JC140	1447	JF824803	clade_389	N	N
Peptoniphilus sp. oral taxon 386	1452	ADCS01000031	clade_389	N	N
Peptoniphilus sp. oral taxon 836	1453	AEAA01000090	clade_389	N	N
Peptostreptococcaceae bacterium ph1	1454	JN837495	clade_389	N	N
Dialister pneumosintes	765	HM596297	clade_390	N	N
Dialister sp. oral taxon 502	767	GQ422739	clade_390	N	N
Cupriavidus metallidurans	741	GU230889	clade_391	N	N
Herbaspirillum seropedicae	1001	CP002039	clade_391	N	N
Herbaspirillum sp. JC206	1002	JN657219	clade_391	N	N
Janthinobacterium sp. SY12	1015	EF455530	clade_391	N	N
Massilia sp. CCUG 43427A	1197	FR773700	clade_391	N	N
Ralstonia pickettii	1615	NC_010682	clade_391	N	N
Ralstonia sp. 5_7_47FAA	1616	ACUF01000076	clade_391	N	N
Francisella novicida	889	ABSS01000002	clade_392	N	N
Francisella philomiragia	890	AY928394	clade_392	N	N
Francisella tularensis	891	ABAZ01000082	clade_392	N	Category-A
Ignatzschineria indica	1009	HQ823562	clade_392	N	N
Ignatzschineria sp. NML 95_0260	1010	HQ823559	clade_392	N	N
Coprococcus catus	673	EU266552	clade_393	Y	N
Lachnospiraceae bacterium oral taxon F15	1064	HM099641	clade_393	Y	N
Streptococcus mutans	1814	AP010655	clade_394	N	N
Clostridium cochlearium	574	NR_044717	clade_395	Y	N
Clostridium malenominatum	604	FR749893	clade_395	Y	N
Clostridium tetani	654	NC_004557	clade_395	Y	N
Acetivibrio ethanolgignens	6	FR749897	clade_396	Y	N
Anaerosporobacter mobilis	161	NR_042953	clade_396	Y	N
Bacteroides pectinophilus	288	ABVQ01000036	clade_396	Y	N
Clostridium aminovalericum	551	NR_029245	clade_396	Y	N
Clostridium phytofermentans	613	NR_074652	clade_396	Y	N
Eubacterium hallii	848	L34621	clade_396	Y	N
Eubacterium xylanophilum	875	L34628	clade_396	Y	N
Lactobacillus gasseri	1084	ACOZ01000018	clade_398	N	N
Lactobacillus hominis	1090	FR681902	clade_398	N	N
Lactobacillus iners	1091	AEKJ01000002	clade_398	N	N
Lactobacillus johnsonii	1093	AE017198	clade_398	N	N
Lactobacillus senioris	1119	AB602570	clade_398	N	N
Lactobacillus sp. oral clone HT002	1135	AY349382	clade_398	N	N
Weissella beninensis	2006	EU439435	clade_398	N	N
Sphingomonas echinoides	1744	NR_024700	clade_399	N	N
Sphingomonas sp. oral taxon A09	1747	HM099639	clade_399	N	N

Sphingomonas sp. oral taxon F71	1748	HM099645	clade_399	N	N
Zymomonas mobilis	2032	NR_074274	clade_399	N	N
Arcanobacterium haemolyticum	174	NR_025347	clade_400	N	N
Arcanobacterium pyogenes	175	GU585578	clade_400	N	N
Trueperella pyogenes	1962	NR_044858	clade_400	N	N
Lactococcus garvieae	1144	AF061005	clade_401	N	N
Lactococcus lactis	1145	CP002365	clade_401	N	N
Brevibacterium mcbrellneri	424	ADNU01000076	clade_402	N	N
Brevibacterium paucivorans	425	EU086796	clade_402	N	N
Brevibacterium sp. JC43	428	JF824806	clade_402	N	N
Selenomonas artemidis	1692	HM596274	clade_403	N	N
Selenomonas sp. FOBRC9	1704	HQ616378	clade_403	N	N
Selenomonas sp. oral taxon 137	1715	AENV01000007	clade_403	N	N
Desmospora activa	751	AM940019	clade_404	N	N
Desmospora sp. 8437	752	AFHT01000143	clade_404	N	N
Paenibacillus sp. oral taxon F45	1407	HM099647	clade_404	N	N
Corynebacterium ammoniagenes	682	ADNS01000011	clade_405	N	N
Corynebacterium aurimucosum	687	ACLH01000041	clade_405	N	N
Corynebacterium bovis	688	AF537590	clade_405	N	N
Corynebacterium canis	689	GQ871934	clade_405	N	N
Corynebacterium casei	690	NR_025101	clade_405	N	N
Corynebacterium durum	694	Z97069	clade_405	N	N
Corynebacterium efficiens	695	ACLI01000121	clade_405	N	N
Corynebacterium falsenii	696	Y13024	clade_405	N	N
Corynebacterium flavescens	697	NR_037040	clade_405	N	N
Corynebacterium glutamicum	701	BA000036	clade_405	N	N
Corynebacterium jeikeium	704	ACYW01000001	clade_405	N	OP
Corynebacterium kroppenstedtii	705	NR_026380	clade_405	N	N
Corynebacterium lipophiloflavum	706	ACHJ01000075	clade_405	N	N
Corynebacterium matruchotii	709	ACSH02000003	clade_405	N	N
Corynebacterium minutissimum	710	X82064	clade_405	N	N
Corynebacterium resistens	718	ADGN01000058	clade_405	N	N
Corynebacterium simulans	720	AF537604	clade_405	N	N
Corynebacterium singulare	721	NR_026394	clade_405	N	N
Corynebacterium sp. 1 ex sheep	722	Y13427	clade_405	N	N
Corynebacterium sp. NML 99_0018	726	GU238413	clade_405	N	N
Corynebacterium striatum	727	ACGE01000001	clade_405	N	OP
Corynebacterium urealyticum	732	X81913	clade_405	N	OP
Corynebacterium variabile	734	NR_025314	clade_405	N	N
Ruminococcus callidus	1658	NR_029160	clade_406	Y	N
Ruminococcus champanellensis	1659	FP929052	clade_406	Y	N
Ruminococcus sp. 18P13	1665	AJ515913	clade_406	Y	N
Ruminococcus sp. 9SE51	1667	FM954974	clade_406	Y	N
Aerococcus sanguinicola	98	AY837833	clade_407	N	N
Aerococcus urinae	99	CP002512	clade_407	N	N
Aerococcus urinaeequi	100	NR_043443	clade_407	N	N
Aerococcus viridans	101	ADNT01000041	clade_407	N	N
Anaerostipes caccae	162	ABAX03000023	clade_408	Y	N

Anaerostipes sp. 3_2_56FAA	163	ACWB01000002	clade_408	Y	N
Clostridiales bacterium 1_7_47FAA	541	ABQR01000074	clade_408	Y	N
Clostridiales sp. SM4_1	542	FP929060	clade_408	Y	N
Clostridiales sp. SSC_2	544	FP929061	clade_408	Y	N
Clostridium aerotolerans	546	X76163	clade_408	Y	N
Clostridium aldenense	547	NR_043680	clade_408	Y	N
Clostridium algidixylanolyticum	550	NR_028726	clade_408	Y	N
Clostridium amygdalinum	552	AY353957	clade_408	Y	N
Clostridium asparagiforme	554	ACCJ01000522	clade_408	Y	N
Clostridium bolteae	559	ABCC02000039	clade_408	Y	N
Clostridium celerecrescens	566	JQ246092	clade_408	Y	N
Clostridium citroniae	569	ADLJ01000059	clade_408	Y	N
Clostridium clostridiiformes	571	M59089	clade_408	Y	N
Clostridium clostridioforme	572	NR_044715	clade_408	Y	N
Clostridium hathewayi	590	AY552788	clade_408	Y	N
Clostridium indolis	594	AF028351	clade_408	Y	N
Clostridium lavalense	600	EF564277	clade_408	Y	N
Clostridium saccharolyticum	620	CP002109	clade_408	Y	N
Clostridium sp. M62_1	633	ACFX02000046	clade_408	Y	N
Clostridium sp. SS2_1	638	ABGC03000041	clade_408	Y	N
Clostridium sphenoides	643	X73449	clade_408	Y	N
Clostridium symbiosum	652	ADLQ01000114	clade_408	Y	N
Clostridium xylanolyticum	658	NR_037068	clade_408	Y	N
Eubacterium hadrum	847	FR749933	clade_408	Y	N
Fusobacterium naviforme	898	HQ223106	clade_408	N	N
Lachnospiraceae bacterium 3_1_57FAA	1052	ACTP01000124	clade_408	Y	N
Lachnospiraceae bacterium 5_1_63FAA	1055	ACTS01000081	clade_408	Y	N
Lachnospiraceae bacterium A4	1059	DQ789118	clade_408	Y	N
Lachnospiraceae bacterium DJF VP30	1060	EU728771	clade_408	Y	N
Lachnospiraceae genomosp. C1	1065	AY278618	clade_408	Y	N
Moryella indoligenes	1268	AF527773	clade_408	N	N
Clostridium difficile	578	NC_013315	clade_409	Y	OP
Selenomonas genomosp. P5	1697	AY341820	clade_410	N	N
Selenomonas sp. oral clone IQ048	1710	AY349408	clade_410	N	N
Selenomonas sputigena	1717	ACKP02000033	clade_410	N	N
Hyphomicrobium sulfonivorans	1007	AY468372	clade_411	N	N
Methylocella silvestris	1228	NR_074237	clade_411	N	N
Legionella pneumophila	1153	NC_002942	clade_412	N	OP
Lactobacillus coryniformis	1077	NR_044705	clade_413	N	N
Arthrobacter agilis	178	NR_026198	clade_414	N	N
Arthrobacter arilaitensis	179	NR_074608	clade_414	N	N
Arthrobacter bergerei	180	NR_025612	clade_414	N	N
Arthrobacter globiformis	181	NR_026187	clade_414	N	N
Arthrobacter nicotianae	182	NR_026190	clade_414	N	N
Mycobacterium abscessus	1269	AGQU01000002	clade_418	N	OP
Mycobacterium chelonae	1273	AB548610	clade_418	N	OP
Bacteroides salanitronis	291	CP002530	clade_419	N	N
Paraprevotella xylaniphila	1427	AFBR01000011	clade_419	N	N

Barnesiella intestinihominis	336	AB370251	clade_420	N	N
Barnesiella viscericola	337	NR_041508	clade_420	N	N
Parabacteroides sp. NS31_3	1422	JN029805	clade_420	N	N
Porphyromonadaceae bacterium NML 060648	1470	EF184292	clade_420	N	N
Tannerella forsythia	1913	CP003191	clade_420	N	N
Tannerella sp. 6_1_58FAA_CT1	1914	ACWX01000068	clade_420	N	N
Mycoplasma amphoriforme	1311	AY531656	clade_421	N	N
Mycoplasma genitalium	1317	L43967	clade_421	N	N
Mycoplasma pneumoniae	1322	NC_000912	clade_421	N	N
Mycoplasma penetrans	1321	NC_004432	clade_422	N	N
Ureaplasma parvum	1966	AE002127	clade_422	N	N
Ureaplasma urealyticum	1967	AAYN01000002	clade_422	N	N
Treponema genomosp. P1	1927	AY341822	clade_425	N	N
Treponema sp. oral taxon 228	1943	GU408580	clade_425	N	N
Treponema sp. oral taxon 230	1944	GU408603	clade_425	N	N
Treponema sp. oral taxon 231	1945	GU408631	clade_425	N	N
Treponema sp. oral taxon 232	1946	GU408646	clade_425	N	N
Treponema sp. oral taxon 235	1947	GU408673	clade_425	N	N
Treponema sp. ovine footrot	1959	AJ010951	clade_425	N	N
Treponema vincentii	1960	ACYH01000036	clade_425	N	OP
Eubacterium sp. AS15b	862	HQ616364	clade_428	Y	N
Eubacterium sp. OBRC9	863	HQ616354	clade_428	Y	N
Eubacterium sp. oral clone OH3A	871	AY947497	clade_428	Y	N
Eubacterium yurii	876	AEES01000073	clade_428	Y	N
Clostridium acetobutylicum	545	NR_074511	clade_430	Y	N
Clostridium algidicarnis	549	NR_041746	clade_430	Y	N
Clostridium cadaveris	562	AB542932	clade_430	Y	N
Clostridium carboxidivorans	563	FR733710	clade_430	Y	N
Clostridium estertheticum	580	NR_042153	clade_430	Y	N
Clostridium fallax	581	NR_044714	clade_430	Y	N
Clostridium felsineum	583	AF270502	clade_430	Y	N
Clostridium frigidicarnis	584	NR_024919	clade_430	Y	N
Clostridium kluyveri	598	NR_074165	clade_430	Y	N
Clostridium magnum	603	X77835	clade_430	Y	N
Clostridium putrefaciens	615	NR_024995	clade_430	Y	N
Clostridium sp. HPB_46	629	AY862516	clade_430	Y	N
Clostridium tyrobutyricum	656	NR_044718	clade_430	Y	N
Burkholderiales bacterium 1_1_47	452	ADCQ01000066	clade_432	N	OP
Parasutterella excrementihominis	1429	AFBP01000029	clade_432	N	N
Parasutterella secunda	1430	AB491209	clade_432	N	N
Sutterella morbirenis	1898	AJ832129	clade_432	N	N
Sutterella parvirubra	1899	AB300989	clade_432	Y	N
Sutterella sanguinus	1900	AJ748647	clade_432	N	N
Sutterella sp. YIT 12072	1901	AB491210	clade_432	N	N
Sutterella stercoricanis	1902	NR_025600	clade_432	N	N
Sutterella wadsworthensis	1903	ADMF01000048	clade_432	N	N
Propionibacterium freudenreichii	1572	NR_036972	clade_433	N	N
Propionibacterium sp. oral taxon 192	1580	GQ422728	clade_433	N	N

Tessaracoccus sp. oral taxon F04	1917	HM099640	clade_433	N	N
Peptoniphilus ivorii	1445	Y07840	clade_434	N	N
Peptoniphilus sp. gpac007	1448	AM176517	clade_434	N	N
Peptoniphilus sp. gpac018A	1449	AM176519	clade_434	N	N
Peptoniphilus sp. gpac148	1451	AM176535	clade_434	N	N
Flexispira rappini	887	AY126479	clade_436	N	N
Helicobacter bilis	993	ACDN01000023	clade_436	N	N
Helicobacter cinaedi	995	ABQT01000054	clade_436	N	N
Helicobacter sp. None	998	U44756	clade_436	N	N
Brevundimonas subvibrioides	429	CP002102	clade_438	N	N
Hyphomonas neptunium	1008	NR_074092	clade_438	N	N
Phenylobacterium zucineum	1465	AY628697	clade_438	N	N
Acetanaerobacterium elongatum	4	NR_042930	clade_439	Y	N
Clostridium cellulosi	567	NR_044624	clade_439	Y	N
Ethanoligenens harbinense	832	AY675965	clade_439	Y	N
Streptococcus downei	1793	AEKN01000002	clade_441	N	N
Streptococcus sp. SHV515	1848	Y07601	clade_441	N	N
Acinetobacter sp. CIP 53.82	40	JQ638584	clade_443	N	N
Halomonas elongata	990	NR_074782	clade_443	N	N
Halomonas johnsoniae	991	FR775979	clade_443	N	N
Butyrivibrio fibrisolvens	456	U41172	clade_444	N	N
Eubacterium rectale	856	FP929042	clade_444	Y	N
Eubacterium sp. oral clone GI038	865	AY349374	clade_444	Y	N
Lachnobacterium bovis	1045	GU324407	clade_444	Y	N
Roseburia cecicola	1634	GU233441	clade_444	Y	N
Roseburia faecalis	1635	AY804149	clade_444	Y	N
Roseburia faecis	1636	AY305310	clade_444	Y	N
Roseburia hominis	1637	AJ270482	clade_444	Y	N
Roseburia intestinalis	1638	FP929050	clade_444	Y	N
Roseburia inulinivorans	1639	AJ270473	clade_444	Y	N
Roseburia sp. 11SE37	1640	FM954975	clade_444	N	N
Roseburia sp. 11SE38	1641	FM954976	clade_444	N	N
Shuttleworthia satelles	1728	ACIP02000004	clade_444	N	N
Shuttleworthia sp. MSX8B	1729	HQ616383	clade_444	N	N
Shuttleworthia sp. oral taxon G69	1730	GU432167	clade_444	N	N
Bdellovibrio sp. MPA	344	AY294215	clade_445	N	N
Desulfobulbus sp. oral clone CH031	755	AY005036	clade_445	N	N
Desulfovibrio desulfuricans	757	DQ092636	clade_445	N	N
Desulfovibrio fairfieldensis	758	U42221	clade_445	N	N
Desulfovibrio piger	759	AF192152	clade_445	N	N
Desulfovibrio sp. 3_1_syn3	760	ADDR01000239	clade_445	N	N
Geobacter bemidjiensis	941	CP001124	clade_445	N	N
Brachybacterium alimentarium	401	NR_026269	clade_446	N	N
Brachybacterium conglomeratum	402	AB537169	clade_446	N	N
Brachybacterium tyrofermentans	403	NR_026272	clade_446	N	N
Dermabacter hominis	749	FJ263375	clade_446	N	N
Aneurinibacillus thermoaerophilus	171	NR_029303	clade_448	N	N
Brevibacillus agri	409	NR_040983	clade_448	N	N

Brevibacillus brevis	410	NR_041524	clade_448	Y	N
Brevibacillus centrosporus	411	NR_043414	clade_448	N	N
Brevibacillus choshinensis	412	NR_040980	clade_448	N	N
Brevibacillus invocatus	413	NR_041836	clade_448	N	N
Brevibacillus laterosporus	414	NR_037005	clade_448	Y	N
Brevibacillus parabrevis	415	NR_040981	clade_448	N	N
Brevibacillus reuszeri	416	NR_040982	clade_448	N	N
Brevibacillus sp. phR	417	JN837488	clade_448	N	N
Brevibacillus thermoruber	418	NR_026514	clade_448	N	N
Lactobacillus murinus	1100	NR_042231	clade_449	N	N
Lactobacillus oeni	1102	NR_043095	clade_449	N	N
Lactobacillus ruminis	1115	ACGS02000043	clade_449	N	N
Lactobacillus vini	1141	NR_042196	clade_449	N	N
Gemella haemolysans	924	ACDZ02000012	clade_450	N	N
Gemella morbillorum	925	NR_025904	clade_450	N	N
Gemella morbillorum	926	ACRX01000010	clade_450	N	N
Gemella sanguinis	927	ACRY01000057	clade_450	N	N
Gemella sp. oral clone ASCE02	929	AY923133	clade_450	N	N
Gemella sp. oral clone ASCF04	930	AY923139	clade_450	N	N
Gemella sp. oral clone ASCF12	931	AY923143	clade_450	N	N
Gemella sp. WAL 1945J	928	EU427463	clade_450	N	N
Bacillus coagulans	206	DQ297928	clade_451	Y	OP
Sporolactobacillus inulinus	1752	NR_040962	clade_451	Y	N
Sporolactobacillus nakayamae	1753	NR_042247	clade_451	N	N
Gluconacetobacter entanii	945	NR_028909	clade_452	N	N
Gluconacetobacter europaeus	946	NR_026513	clade_452	N	N
Gluconacetobacter hansenii	947	NR_026133	clade_452	N	N
Gluconacetobacter oboediens	949	NR_041295	clade_452	N	N
Gluconacetobacter xylinus	950	NR_074338	clade_452	N	N
Auritibacter ignavus	193	FN554542	clade_453	N	N
Dermacoccus sp. Ellin185	750	AEJQ01000090	clade_453	N	N
Janibacter limosus	1013	NR_026362	clade_453	N	N
Janibacter melonis	1014	EF063716	clade_453	N	N
Kocuria palustris	1041	EU333884	clade_453	Y	N
Acetobacter aceti	7	NR_026121	clade_454	N	N
Acetobacter fabarum	8	NR_042678	clade_454	N	N
Acetobacter lovaniensis	9	NR_040832	clade_454	N	N
Acetobacter malorum	10	NR_025513	clade_454	N	N
Acetobacter orientalis	11	NR_028625	clade_454	N	N
Acetobacter pasteurianus	12	NR_026107	clade_454	N	N
Acetobacter pomorum	13	NR_042112	clade_454	N	N
Acetobacter syzygii	14	NR_040868	clade_454	N	N
Acetobacter tropicalis	15	NR_036881	clade_454	N	N
Gluconacetobacter azotocaptans	943	NR_028767	clade_454	N	N
Gluconacetobacter diazotrophicus	944	NR_074292	clade_454	N	N
Gluconacetobacter johannae	948	NR_024959	clade_454	N	N
Nocardia brasiliensis	1351	AIHV01000038	clade_455	N	N
Nocardia cyriacigeorgica	1352	HQ009486	clade_455	N	N

Nocardia farcinica	1353	NC_006361	clade_455	Y	N
Nocardia puris	1354	NR_028994	clade_455	N	N
Nocardia sp. 01_Je_025	1355	GU574059	clade_455	N	N
Rhodococcus equi	1623	ADNW01000058	clade_455	N	N
Bacillus sp. oral taxon F28	247	HM099650	clade_456	Y	OP
Oceanobacillus caeni	1358	NR_041533	clade_456	N	N
Oceanobacillus sp. Ndiop	1359	CAER01000083	clade_456	N	N
Ornithinibacillus bavariensis	1384	NR_044923	clade_456	N	N
Ornithinibacillus sp. 7_10AIA	1385	FN397526	clade_456	N	N
Virgibacillus proomii	2005	NR_025308	clade_456	N	N
Corynebacterium amycolatum	683	ABZU01000033	clade_457	N	OP
Corynebacterium hansenii	702	AM946639	clade_457	N	N
Corynebacterium xerosis	735	FN179330	clade_457	N	OP
Staphylococcaceae bacterium NML 92_0017	1756	AY841362	clade_458	N	N
Staphylococcus fleurettii	1766	NR_041326	clade_458	N	N
Staphylococcus sciuri	1774	NR_025520	clade_458	N	N
Staphylococcus vitulinus	1779	NR_024670	clade_458	N	N
Stenotrophomonas maltophilia	1782	AAVZ01000005	clade_459	N	N
Stenotrophomonas sp. FG_6	1783	EF017810	clade_459	N	N
Mycobacterium africanum	1270	AF480605	clade_46	N	OP
Mycobacterium alsiensis	1271	AJ938169	clade_46	N	OP
Mycobacterium avium	1272	CP000479	clade_46	N	OP
Mycobacterium colombiense	1274	AM062764	clade_46	N	OP
Mycobacterium gordonae	1276	GU142930	clade_46	N	OP
Mycobacterium intracellulare	1277	GQ153276	clade_46	N	OP
Mycobacterium kansasii	1278	AF480601	clade_46	N	OP
Mycobacterium lacus	1279	NR_025175	clade_46	N	OP
Mycobacterium leprae	1280	FM211192	clade_46	N	OP
Mycobacterium lepromatosis	1281	EU203590	clade_46	N	OP
Mycobacterium mantenii	1283	FJ042897	clade_46	N	OP
Mycobacterium marinum	1284	NC_010612	clade_46	N	OP
Mycobacterium microti	1285	NR_025234	clade_46	N	OP
Mycobacterium parascrofulaceum	1287	ADNV01000350	clade_46	N	OP
Mycobacterium seoulense	1290	DQ536403	clade_46	N	OP
Mycobacterium sp. 1761	1292	EU703150	clade_46	N	N
Mycobacterium sp. 1791	1295	EU703148	clade_46	N	N
Mycobacterium sp. 1797	1296	EU703149	clade_46	N	N
Mycobacterium sp. B10_07.09.0206	1298	HQ174245	clade_46	N	N
Mycobacterium sp. NLA001000736	1305	HM627011	clade_46	N	N
Mycobacterium sp. W	1306	DQ437715	clade_46	N	N
Mycobacterium tuberculosis	1307	CP001658	clade_46	N	Category-C
Mycobacterium ulcerans	1308	AB548725	clade_46	N	OP
Mycobacterium vulneris	1309	EU834055	clade_46	N	OP
Xanthomonas campestris	2016	EF101975	clade_461	N	N
Xanthomonas sp. kmd_489	2017	EU723184	clade_461	N	N
Dietzia natronolimnaea	769	GQ870426	clade_462	N	N
Dietzia sp. BBDP51	770	DQ337512	clade_462	N	N

Dietzia sp. CA149	771	GQ870422	clade_462	N	N
Dietzia timorensis	772	GQ870424	clade_462	N	N
Gordonia bronchialis	951	NR_027594	clade_463	N	N
Gordonia polyisoprenivorans	952	DQ385609	clade_463	N	N
Gordonia sp. KTR9	953	DQ068383	clade_463	N	N
Gordonia sputi	954	FJ536304	clade_463	N	N
Gordonia terrae	955	GQ848239	clade_463	N	N
Leptotrichia goodfellowii	1167	ADAD01000110	clade_465	N	N
Leptotrichia sp. oral clone IK040	1174	AY349387	clade_465	N	N
Leptotrichia sp. oral clone P2PB_51 P1	1175	AY207053	clade_465	N	N
Bacteroidales genomosp. P7 oral clone MB3_P19	264	DQ003623	clade_466	N	N
Butyricimonas virosa	454	AB443949	clade_466	N	N
Odoribacter laneus	1363	AB490805	clade_466	N	N
Odoribacter splanchnicus	1364	CP002544	clade_466	N	N
Capnocytophaga gingivalis	478	ACLQ01000011	clade_467	N	N
Capnocytophaga granulosa	479	X97248	clade_467	N	N
Capnocytophaga sp. oral clone AH015	483	AY005074	clade_467	N	N
Capnocytophaga sp. oral strain S3	487	AY005073	clade_467	N	N
Capnocytophaga sp. oral taxon 338	488	AEXX01000050	clade_467	N	N
Capnocytophaga canimorsus	476	CP002113	clade_468	N	N
Capnocytophaga sp. oral clone ID062	485	AY349368	clade_468	N	N
Catenibacterium mitsuokai	495	AB030224	clade_469	Y	N
Clostridium sp. TM_40	640	AB249652	clade_469	Y	N
Coprobacillus cateniformis	670	AB030218	clade_469	Y	N
Coprobacillus sp. 29_1	671	ADKX01000057	clade_469	Y	N
Lactobacillus catenaformis	1075	M23729	clade_469	N	N
Lactobacillus vitulinus	1142	NR_041305	clade_469	N	N
Cetobacterium somerae	501	AJ438155	clade_470	N	N
Clostridium rectum	618	NR_029271	clade_470	Y	N
Fusobacterium gonidiaformans	896	ACET01000043	clade_470	N	N
Fusobacterium mortiferum	897	ACDB02000034	clade_470	N	N
Fusobacterium necrogenes	899	X55408	clade_470	N	N
Fusobacterium necrophorum	900	AM905356	clade_470	N	N
Fusobacterium sp. 12_1B	905	AGWJ01000070	clade_470	N	N
Fusobacterium sp. 3_1_5R	911	ACDD01000078	clade_470	N	N
Fusobacterium sp. D12	918	ACDG02000036	clade_470	N	N
Fusobacterium ulcerans	921	ACDH01000090	clade_470	N	N
Fusobacterium varium	922	ACIE01000009	clade_470	N	N
Mycoplasma arthritidis	1312	NC_011025	clade_473	N	N
Mycoplasma faucium	1314	NR_024983	clade_473	N	N
Mycoplasma hominis	1318	AF443616	clade_473	N	N
Mycoplasma orale	1319	AY796060	clade_473	N	N
Mycoplasma salivarium	1324	M24661	clade_473	N	N
Mitsuokella jalaludinii	1247	NR_028840	clade_474	N	N
Mitsuokella multacida	1248	ABWK02000005	clade_474	N	N
Mitsuokella sp. oral taxon 521	1249	GU413658	clade_474	N	N
Mitsuokella sp. oral taxon G68	1250	GU432166	clade_474	N	N
Selenomonas genomosp. C1	1695	AY278627	clade_474	N	N

Selenomonas genomosp. P8 oral clone MB5_P06	1700	DQ003628	clade_474	N	N
Selenomonas ruminantium	1703	NR_075026	clade_474	N	N
Veillonellaceae bacterium oral taxon 131	1994	GU402916	clade_474	N	N
Alloscardovia omnicolens	139	NR_042583	clade_475	N	N
Alloscardovia sp. OB7196	140	AB425070	clade_475	N	N
Bifidobacterium urinalis	366	AJ278695	clade_475	N	N
Eubacterium nodatum	854	U13041	clade_476	Y	N
Eubacterium saphenum	859	NR_026031	clade_476	Y	N
Eubacterium sp. oral clone JH012	867	AY349373	clade_476	Y	N
Eubacterium sp. oral clone JS001	870	AY349378	clade_476	Y	N
Faecalibacterium prausnitzii	880	ACOP02000011	clade_478	Y	N
Gemmiger formicilis	932	GU562446	clade_478	Y	N
Subdoligranulum variabile	1896	AJ518869	clade_478	Y	N
Clostridiaceae bacterium JC13	532	JF824807	clade_479	Y	N
Clostridium sp. MLG055	634	AF304435	clade_479	Y	N
Erysipelotrichaceae bacterium 3_1_53	822	ACTJ01000113	clade_479	Y	N
Prevotella loescheii	1503	JN867231	clade_48	N	N
Prevotella sp. oral clone ASCG12	1530	DQ272511	clade_48	N	N
Prevotella sp. oral clone GU027	1540	AY349398	clade_48	N	N
Prevotella sp. oral taxon 472	1553	ACZS01000106	clade_48	N	N
Selenomonas dianae	1693	GQ422719	clade_480	N	N
Selenomonas flueggei	1694	AF287803	clade_480	N	N
Selenomonas genomosp. C2	1696	AY278628	clade_480	N	N
Selenomonas genomosp. P6 oral clone MB3_C41	1698	DQ003636	clade_480	N	N
Selenomonas genomosp. P7 oral clone MB5_C08	1699	DQ003627	clade_480	N	N
Selenomonas infelix	1701	AF287802	clade_480	N	N
Selenomonas noxia	1702	GU470909	clade_480	N	N
Selenomonas sp. oral clone FT050	1705	AY349403	clade_480	N	N
Selenomonas sp. oral clone G1064	1706	AY349404	clade_480	N	N
Selenomonas sp. oral clone GT010	1707	AY349405	clade_480	N	N
Selenomonas sp. oral clone HU051	1708	AY349406	clade_480	N	N
Selenomonas sp. oral clone IK004	1709	AY349407	clade_480	N	N
Selenomonas sp. oral clone JI021	1711	AY349409	clade_480	N	N
Selenomonas sp. oral clone JS031	1712	AY349410	clade_480	N	N
Selenomonas sp. oral clone OH4A	1713	AY947498	clade_480	N	N
Selenomonas sp. oral clone P2PA_80 P4	1714	AY207052	clade_480	N	N
Selenomonas sp. oral taxon 149	1716	AEEJ01000007	clade_480	N	N
Veillonellaceae bacterium oral taxon 155	1995	GU470897	clade_480	N	N
Clostridium cocleatum	575	NR_026495	clade_481	Y	N
Clostridium ramosum	617	M23731	clade_481	Y	N
Clostridium saccharogumia	619	DQ100445	clade_481	Y	N
Clostridium spiroforme	644	X73441	clade_481	Y	N
Coprobacillus sp. D7	672	ACDT01000199	clade_481	Y	N
Clostridiales bacterium SY8519	535	AB477431	clade_482	Y	N
Clostridium sp. SY8519	639	AP012212	clade_482	Y	N
Eubacterium ramulus	855	AJ011522	clade_482	Y	N
Agrococcus jenensis	117	NR_026275	clade_484	N	N
Microbacterium gubbeenense	1232	NR_025098	clade_484	N	N

Pseudoclavibacter sp. Timone	1590	FJ375951	clade_484	N	N
Tropheryma whipplei	1961	BX251412	clade_484	N	N
Zimmermannella bifida	2031	AB012592	clade_484	N	N
Erysipelothrix inopinata	819	NR_025594	clade_485	Y	N
Erysipelothrix rhusiopathiae	820	ACLK01000021	clade_485	Y	N
Erysipelothrix tonsillarum	821	NR_040871	clade_485	Y	N
Holdemania filiformis	1004	Y11466	clade_485	Y	N
Mollicutes bacterium pACH93	1258	AY297808	clade_485	Y	N
Coxiella burnetii	736	CP000890	clade_486	Y	Category-B
Legionella hackeliae	1151	M36028	clade_486	N	OP
Legionella longbeachae	1152	M36029	clade_486	N	OP
Legionella sp. D3923	1154	JN380999	clade_486	N	OP
Legionella sp. D4088	1155	JN381012	clade_486	N	OP
Legionella sp. H63	1156	JF831047	clade_486	N	OP
Legionella sp. NML 93L054	1157	GU062706	clade_486	N	OP
Legionella steelei	1158	HQ398202	clade_486	N	OP
Tatlockia micdadei	1915	M36032	clade_486	N	N
Clostridium hiranonis	591	AB023970	clade_487	Y	N
Clostridium irregulare	596	NR_029249	clade_487	Y	N
Helicobacter pullorum	996	ABQU01000097	clade_489	N	N
Acetobacteraceae bacterium AT_5844	16	AGEZ01000040	clade_490	N	N
Roseomonas cervicalis	1643	ADVL01000363	clade_490	N	N
Roseomonas mucosa	1644	NR_028857	clade_490	N	N
Roseomonas sp. NML94_0193	1645	AF533357	clade_490	N	N
Roseomonas sp. NML97_0121	1646	AF533359	clade_490	N	N
Roseomonas sp. NML98_0009	1647	AF533358	clade_490	N	N
Roseomonas sp. NML98_0157	1648	AF533360	clade_490	N	N
Rickettsia akari	1627	CP000847	clade_492	N	OP
Rickettsia conorii	1628	AE008647	clade_492	N	OP
Rickettsia prowazekii	1629	M21789	clade_492	N	Category-B
Rickettsia rickettsii	1630	NC_010263	clade_492	N	OP
Rickettsia slovaca	1631	L36224	clade_492	N	OP
Rickettsia typhi	1632	AE017197	clade_492	N	OP
Anaeroglobus geminatus	160	AGCJ01000054	clade_493	N	N
Megasphaera genomosp. C1	1201	AY278622	clade_493	N	N
Megasphaera micronuciformis	1203	AECS01000020	clade_493	N	N
Clostridium orbiscindens	609	Y18187	clade_494	Y	N
Clostridium sp. NML 04A032	637	EU815224	clade_494	Y	N
Flavonifractor plautii	886	AY724678	clade_494	Y	N
Pseudoflavonifractor capillosus	1591	AY136666	clade_494	Y	N
Ruminococcaceae bacterium D16	1655	ADDX01000083	clade_494	Y	N
Acetivibrio cellulolyticus	5	NR_025917	clade_495	Y	N
Clostridiales genomosp. BVAB3	540	CP001850	clade_495	N	N
Clostridium aldrichii	548	NR_026099	clade_495	Y	N
Clostridium clariflavum	570	NR_041235	clade_495	Y	N
Clostridium stercorarium	647	NR_025100	clade_495	Y	N

Clostridium straminisolvens	649	NR_024829	clade_495	Y	N
Clostridium thermocellum	655	NR_074629	clade_495	Y	N
Tsukamurella paurometabola	1963	X80628	clade_496	N	N
Tsukamurella tyrosinosolvens	1964	AB478958	clade_496	N	N
Abiotrophia para_adiacens	2	AB022027	clade_497	N	N
Carnobacterium divergens	492	NR_044706	clade_497	N	N
Carnobacterium maltaromaticum	493	NC_019425	clade_497	N	N
Enterococcus avium	800	AF133535	clade_497	N	N
Enterococcus caccae	801	AY943820	clade_497	N	N
Enterococcus casseliflavus	802	AEWT01000047	clade_497	N	N
Enterococcus durans	803	AJ276354	clade_497	N	N
Enterococcus faecalis	804	AE016830	clade_497	N	N
Enterococcus faecium	805	AM157434	clade_497	N	N
Enterococcus gallinarum	806	AB269767	clade_497	N	N
Enterococcus gilvus	807	AY033814	clade_497	N	N
Enterococcus hawaiiensis	808	AY321377	clade_497	N	N
Enterococcus hirae	809	AF061011	clade_497	N	N
Enterococcus italicus	810	AEPV01000109	clade_497	N	N
Enterococcus mundtii	811	NR_024906	clade_497	N	N
Enterococcus raffinosus	812	FN600541	clade_497	N	N
Enterococcus sp. BV2CASA2	813	JN809766	clade_497	N	N
Enterococcus sp. CCRI 16620	814	GU457263	clade_497	N	N
Enterococcus sp. F95	815	FJ463817	clade_497	N	N
Enterococcus sp. RfL6	816	AJ133478	clade_497	N	N
Enterococcus thailandicus	817	AY321376	clade_497	N	N
Fusobacterium canifelinum	893	AY162222	clade_497	N	N
Fusobacterium genomosp. C1	894	AY278616	clade_497	N	N
Fusobacterium genomosp. C2	895	AY278617	clade_497	N	N
Fusobacterium nucleatum	901	ADVK01000034	clade_497	Y	N
Fusobacterium periodonticum	902	ACJY01000002	clade_497	N	N
Fusobacterium sp. 1_1_41FAA	906	ADGG01000053	clade_497	N	N
Fusobacterium sp. 11_3_2	904	ACUO01000052	clade_497	N	N
Fusobacterium sp. 2_1_31	907	ACDC02000018	clade_497	N	N
Fusobacterium sp. 3_1_27	908	ADGF01000045	clade_497	N	N
Fusobacterium sp. 3_1_33	909	ACQE01000178	clade_497	N	N
Fusobacterium sp. 3_1_36A2	910	ACPU01000044	clade_497	N	N
Fusobacterium sp. AC18	912	HQ616357	clade_497	N	N
Fusobacterium sp. ACB2	913	HQ616358	clade_497	N	N
Fusobacterium sp. AS2	914	HQ616361	clade_497	N	N
Fusobacterium sp. CM1	915	HQ616371	clade_497	N	N
Fusobacterium sp. CM21	916	HQ616375	clade_497	N	N
Fusobacterium sp. CM22	917	HQ616376	clade_497	N	N
Fusobacterium sp. oral clone ASCF06	919	AY923141	clade_497	N	N
Fusobacterium sp. oral clone ASCF11	920	AY953256	clade_497	N	N
Granulicatella adiacens	959	ACKZ01000002	clade_497	N	N
Granulicatella elegans	960	AB252689	clade_497	N	N
Granulicatella paradiacens	961	AY879298	clade_497	N	N
Granulicatella sp. oral clone ASC02	963	AY923126	clade_497	N	N

Granulicatella sp. oral clone ASCA05	964	DQ341469	clade_497	N	N
Granulicatella sp. oral clone ASCB09	965	AY953251	clade_497	N	N
Granulicatella sp. oral clone ASCG05	966	AY923146	clade_497	N	N
Tetragenococcus halophilus	1918	NR_075020	clade_497	N	N
Tetragenococcus koreensis	1919	NR_043113	clade_497	N	N
Vagococcus fluvialis	1973	NR_026489	clade_497	N	N
Chryseobacterium anthropi	514	AM982793	clade_498	N	N
Chryseobacterium gleum	515	ACKQ02000003	clade_498	N	N
Chryseobacterium hominis	516	NR_042517	clade_498	N	N
Treponema refringens	1936	AF426101	clade_499	N	OP
Treponema sp. oral clone JU031	1941	AY349416	clade_499	N	N
Treponema sp. oral taxon 239	1948	GU408738	clade_499	N	N
Treponema sp. oral taxon 271	1955	GU408871	clade_499	N	N
Alistipes finegoldii	129	NR_043064	clade_500	N	N
Alistipes onderdonkii	131	NR_043318	clade_500	N	N
Alistipes putredinis	132	ABFK02000017	clade_500	N	N
Alistipes shahii	133	FP929032	clade_500	N	N
Alistipes sp. HGB5	134	AENZ01000082	clade_500	N	N
Alistipes sp. JC50	135	JF824804	clade_500	N	N
Alistipes sp. RMA 9912	136	GQ140629	clade_500	N	N
Mycoplasma agalactiae	1310	AF010477	clade_501	N	N
Mycoplasma bovoculi	1313	NR_025987	clade_501	N	N
Mycoplasma fermentans	1315	CP002458	clade_501	N	N
Mycoplasma flocculare	1316	X62699	clade_501	N	N
Mycoplasma ovipneumoniae	1320	NR_025989	clade_501	N	N
Arcobacter butzleri	176	AEPT01000071	clade_502	N	N
Arcobacter cryaerophilus	177	NR_025905	clade_502	N	N
Campylobacter curvus	461	NC_009715	clade_502	N	OP
Campylobacter rectus	467	ACFU01000050	clade_502	N	OP
Campylobacter showae	468	ACVQ01000030	clade_502	N	OP
Campylobacter sp. FOBRC14	469	HQ616379	clade_502	N	OP
Campylobacter sp. FOBRC15	470	HQ616380	clade_502	N	OP
Campylobacter sp. oral clone BB120	471	AY005038	clade_502	N	OP
Campylobacter sputorum	472	NR_044839	clade_502	N	OP
Bacteroides ureolyticus	330	GQ167666	clade_504	N	N
Campylobacter gracilis	463	ACYG01000026	clade_504	N	OP
Campylobacter hominis	464	NC_009714	clade_504	N	OP
Dialister invisus	762	ACIM02000001	clade_506	N	N
Dialister micraerophilus	763	AFBB01000028	clade_506	N	N
Dialister microaerophilus	764	AENT01000008	clade_506	N	N
Dialister propionicifaciens	766	NR_043231	clade_506	N	N
Dialister succinatiphilus	768	AB370249	clade_506	N	N
Megasphaera elsdenii	1200	AY038996	clade_506	N	N
Megasphaera genomosp. type_1	1202	ADGP01000010	clade_506	N	N
Megasphaera sp. BLPYG_07	1204	HM990964	clade_506	N	N
Megasphaera sp. UPII 199_6	1205	AFIJ01000040	clade_506	N	N
Chromobacterium violaceum	513	NC_005085	clade_507	N	N
Laribacter hongkongensis	1148	CP001154	clade_507	N	N

Methylophilus sp. ECd5	1229	AY436794	clade_507	N	N
Finegoldia magna	883	ACHM02000001	clade_509	N	N
Parvimonas micra	1431	AB729072	clade_509	N	N
Parvimonas sp. oral taxon 110	1432	AFII01000002	clade_509	N	N
Peptostreptococcus micros	1456	AM176538	clade_509	N	N
Peptostreptococcus sp. oral clone FJ023	1460	AY349390	clade_509	N	N
Peptostreptococcus sp. P4P_31 P3	1458	AY207059	clade_509	N	N
Helicobacter pylori	997	CP000012	clade_510	N	OP
Anaplasma marginale	165	ABOR01000019	clade_511	N	N
Anaplasma phagocytophilum	166	NC_007797	clade_511	N	N
Ehrlichia chaffeensis	783	AAIF01000035	clade_511	N	OP
Neorickettsia risticii	1349	CP001431	clade_511	N	N
Neorickettsia sennetsu	1350	NC_007798	clade_511	N	N
Eubacterium barkeri	834	NR_044661	clade_512	Y	N
Eubacterium callanderi	838	NR_026330	clade_512	Y	N
Eubacterium limosum	850	CP002273	clade_512	Y	N
Pseudoramibacter alactolyticus	1606	AB036759	clade_512	N	N
Veillonella montpellierensis	1977	AF473836	clade_513	N	N
Veillonella sp. oral clone ASCA08	1988	AY923118	clade_513	N	N
Veillonella sp. oral clone ASCB03	1989	AY923122	clade_513	N	N
Inquilinus limosus	1012	NR_029046	clade_514	N	N
Sphingomonas sp. oral clone FZ016	1746	AY349412	clade_514	N	N
Anaerococcus lactolyticus	145	ABYO01000217	clade_515	N	N
Anaerococcus prevotii	147	CP001708	clade_515	N	N
Anaerococcus sp. gpac104	152	AM176528	clade_515	N	N
Anaerococcus sp. gpac126	153	AM176530	clade_515	N	N
Anaerococcus sp. gpac155	154	AM176536	clade_515	N	N
Anaerococcus sp. gpac199	155	AM176539	clade_515	N	N
Anaerococcus tetradius	157	ACGC01000107	clade_515	N	N
Bacteroides coagulans	271	AB547639	clade_515	N	N
Clostridiales bacterium 9403326	534	HM587324	clade_515	N	N
Clostridiales bacterium ph2	539	JN837487	clade_515	N	N
Peptostreptococcus sp. 9succ1	1457	X90471	clade_515	N	N
Peptostreptococcus sp. oral clone AP24	1459	AB175072	clade_515	N	N
Tissierella praeacuta	1924	NR_044860	clade_515	N	N
Anaerotruncus colihominis	164	ABGD02000021	clade_516	Y	N
Clostridium methylpentosum	606	ACEC01000059	clade_516	Y	N
Clostridium sp. YIT 12070	642	AB491208	clade_516	Y	N
Hydrogenoanaerobacterium saccharovorans	1005	NR_044425	clade_516	Y	N
Ruminococcus albus	1656	AY445600	clade_516	Y	N
Ruminococcus flavefaciens	1660	NR_025931	clade_516	Y	N
Clostridium haemolyticum	589	NR_024749	clade_517	Y	N
Clostridium novyi	608	NR_074343	clade_517	Y	N
Clostridium sp. LMG 16094	632	X95274	clade_517	Y	N
Helicobacter canadensis	994	ABQS01000108	clade_518	N	N
Eubacterium ventriosum	874	L34421	clade_519	Y	N
Peptostreptococcus anaerobius	1455	AY326462	clade_520	N	N
Peptostreptococcus stomatis	1461	ADGQ01000048	clade_520	N	N

Bilophila wadsworthia	367	ADCP01000166	clade_521	N	N
Desulfovibrio vulgaris	761	NR_074897	clade_521	N	N
Bacteroides galacturonicus	280	DQ497994	clade_522	Y	N
Eubacterium eligens	845	CP001104	clade_522	Y	N
Lachnospira multipara	1046	FR733699	clade_522	Y	N
Lachnospira pectinoschiza	1047	L14675	clade_522	Y	N
Lactobacillus rogosae	1114	GU269544	clade_522	Y	N
Actinomyces nasicola	64	AJ508455	clade_523	N	N
Cellulosimicrobium funkei	500	AY501364	clade_523	N	N
Lactococcus raffinolactis	1146	NR_044359	clade_524	N	N
Bacillus horti	214	NR_036860	clade_527	Y	OP
Bacillus sp. 9_3AIA	232	FN397519	clade_527	Y	OP
Bacteroidales genomosp. P1	258	AY341819	clade_529	N	N
Bacteroidales genomosp. P2 oral clone MB1_G13	259	DQ003613	clade_529	N	N
Bacteroidales genomosp. P3 oral clone MB1_G34	260	DQ003615	clade_529	N	N
Bacteroidales genomosp. P4 oral clone MB2_G17	261	DQ003617	clade_529	N	N
Bacteroidales genomosp. P5 oral clone MB2_P04	262	DQ003619	clade_529	N	N
Bacteroidales genomosp. P6 oral clone MB3_C19	263	DQ003634	clade_529	N	N
Bacteroidales genomosp. P8 oral clone MB4_G15	265	DQ003626	clade_529	N	N
Bacteroidetes bacterium oral taxon D27	333	HM099638	clade_530	N	N
Bacteroidetes bacterium oral taxon F31	334	HM099643	clade_530	N	N
Bacteroidetes bacterium oral taxon F44	335	HM099649	clade_530	N	N
Flavobacterium sp. NF2_1	885	FJ195988	clade_530	N	N
Myroides odoratimimus	1326	NR_042354	clade_530	N	N
Myroides sp. MY15	1327	GU253339	clade_530	N	N
Chlamydiales bacterium NS16	507	JN606076	clade_531	N	N
Chlamydophila pecorum	508	D88317	clade_531	N	OP
Parachlamydia sp. UWE25	1423	BX908798	clade_531	N	N
Fusobacterium russii	903	NR_044687	clade_532	N	N
Streptobacillus moniliformis	1784	NR_027615	clade_532	N	N
Eubacteriaceae bacterium P4P_50 P4	833	AY207060	clade_533	N	N
Eubacterium brachy	836	U13038	clade_533	Y	N
Filifactor alocis	881	CP002390	clade_533	Y	N
Filifactor villosus	882	NR_041928	clade_533	Y	N
Abiotrophia defectiva	1	ACIN02000016	clade_534	N	N
Abiotrophia sp. oral clone P4PA_155 P1	3	AY207063	clade_534	N	N
Catonella genomosp. P1 oral clone MB5_P12	496	DQ003629	clade_534	N	N
Catonella morbi	497	ACIL02000016	clade_534	N	N
Catonella sp. oral clone FL037	498	AY349369	clade_534	N	N
Eremococcus coleocola	818	AENN01000008	clade_534	N	N
Facklamia hominis	879	Y10772	clade_534	N	N
Granulicatella sp. M658_99_3	962	AJ271861	clade_534	N	N
Campylobacter coli	459	AAFL01000004	clade_535	N	OP
Campylobacter concisus	460	CP000792	clade_535	N	OP
Campylobacter fetus	462	ACLG01001177	clade_535	N	OP
Campylobacter jejuni	465	AL139074	clade_535	N	Category-B
Campylobacter upsaliensis	473	AEPU01000040	clade_535	N	OP

Clostridium leptum	601	AJ305238	clade_537	Y	N
Clostridium sp. YIT 12069	641	AB491207	clade_537	Y	N
Clostridium sporosphaeroides	646	NR_044835	clade_537	Y	N
Eubacterium coprostanoligenes	841	HM037995	clade_537	Y	N
Ruminococcus bromii	1657	EU266549	clade_537	Y	N
Eubacterium siraeum	860	ABCA03000054	clade_538	Y	N
Atopobium minutum	183	HM007583	clade_539	N	N
Atopobium parvulum	184	CP001721	clade_539	N	N
Atopobium rimae	185	ACFE01000007	clade_539	N	N
Atopobium sp. BS2	186	HQ616367	clade_539	N	N
Atopobium sp. F0209	187	EU592966	clade_539	N	N
Atopobium sp. ICM42b10	188	HQ616393	clade_539	N	N
Atopobium sp. ICM57	189	HQ616400	clade_539	N	N
Atopobium vaginae	190	AEDQ01000024	clade_539	N	N
Coriobacteriaceae bacterium BV3Ac1	677	JN809768	clade_539	N	N
Actinomyces naeslundii	63	X81062	clade_54	N	N
Actinomyces oricola	67	NR_025559	clade_54	N	N
Actinomyces oris	69	BABV01000070	clade_54	N	N
Actinomyces sp. 7400942	70	EU484334	clade_54	N	N
Actinomyces sp. ChDC B197	72	AF543275	clade_54	N	N
Actinomyces sp. GEJ15	73	GU561313	clade_54	N	N
Actinomyces sp. M2231_94_1	79	AJ234063	clade_54	N	N
Actinomyces sp. oral clone GU067	83	AY349362	clade_54	N	N
Actinomyces sp. oral clone IO077	85	AY349364	clade_54	N	N
Actinomyces sp. oral clone IP073	86	AY349365	clade_54	N	N
Actinomyces sp. oral clone JA063	88	AY349367	clade_54	N	N
Actinomyces sp. oral taxon 170	89	AFBL01000010	clade_54	N	N
Actinomyces sp. oral taxon 171	90	AECW01000034	clade_54	N	N
Actinomyces urogenitalis	95	ACFH01000038	clade_54	N	N
Actinomyces viscosus	96	ACRE01000096	clade_54	N	N
Clostridium viride	657	NR_026204	clade_540	Y	N
Oscillibacter sp. G2	1386	HM626173	clade_540	Y	N
Oscillibacter valericigenes	1387	NR_074793	clade_540	Y	N
Oscillospira guilliermondii	1388	AB040495	clade_540	Y	N
Orientia tsutsugamushi	1383	AP008981	clade_541	N	OP
Megamonas funiformis	1198	AB300988	clade_542	N	N
Megamonas hypermegale	1199	AJ420107	clade_542	N	N
Butyrivibrio crossotus	455	ABWN01000012	clade_543	Y	N
Clostridium sp. L2_50	631	AAYW02000018	clade_543	Y	N
Coprococcus eutactus	675	EF031543	clade_543	Y	N
Coprococcus sp. ART55_1	676	AY350746	clade_543	Y	N
Eubacterium ruminantium	857	NR_024661	clade_543	Y	N
Aeromicrobium marinum	102	NR_025681	clade_544	N	N
Aeromicrobium sp. JC14	103	JF824798	clade_544	N	N
Luteococcus sanguinis	1190	NR_025507	clade_544	N	N
Propionibacteriaceae bacterium NML 02_0265	1568	EF599122	clade_544	N	N
Rhodococcus corynebacterioides	1622	X80615	clade_546	N	N
Rhodococcus erythropolis	1624	ACNO01000030	clade_546	N	N

Rhodococcus fascians	1625	NR_037021	clade_546	N	N
Segniliparus rotundus	1690	CP001958	clade_546	N	N
Segniliparus rugosus	1691	ACZI01000025	clade_546	N	N
Exiguobacterium acetylicum	878	FJ970034	clade_547	N	N
Macrococcus caseolyticus	1194	NR_074941	clade_547	N	N
Streptomyces sp. 1 AIP_2009	1890	FJ176782	clade_548	N	N
Streptomyces sp. SD 524	1892	EU544234	clade_548	N	N
Streptomyces sp. SD 528	1893	EU544233	clade_548	N	N
Streptomyces thermoviolaceus	1895	NR_027616	clade_548	N	N
Borrelia afzelii	388	ABCU01000001	clade_549	N	OP
Borrelia crocidurae	390	DQ057990	clade_549	N	OP
Borrelia duttonii	391	NC_011229	clade_549	N	OP
Borrelia hermsii	393	AY597657	clade_549	N	OP
Borrelia hispanica	394	DQ057988	clade_549	N	OP
Borrelia persica	395	HM161645	clade_549	N	OP
Borrelia recurrentis	396	AF107367	clade_549	N	OP
Borrelia spielmanii	398	ABKB01000002	clade_549	N	OP
Borrelia turicatae	399	NC_008710	clade_549	N	OP
Borrelia valaisiana	400	ABCY01000002	clade_549	N	OP
Providencia alcalifaciens	1586	ABXW01000071	clade_55	N	N
Providencia rettgeri	1587	AM040492	clade_55	N	N
Providencia rustigianii	1588	AM040489	clade_55	N	N
Providencia stuartii	1589	AF008581	clade_55	N	N
Treponema pallidum	1932	CP001752	clade_550	N	OP
Treponema phagedenis	1934	AEFH01000172	clade_550	N	N
Treponema sp. clone DDKL_4	1939	Y08894	clade_550	N	N
Acholeplasma laidlawii	17	NR_074448	clade_551	N	N
Mycoplasma putrefaciens	1323	U26055	clade_551	N	N
Mycoplasmataceae genomosp P1 oral clone	1325	DQ003614	clade_551	N	N
Spiroplasma insolitum	1750	NR_025705	clade_551	N	N
Collinsella aerofaciens	659	AAVN02000007	clade_553	Y	N
Collinsella intestinalis	660	ABXH02000037	clade_553	N	N
Collinsella stercoris	661	ABXJ01000150	clade_553	N	N
Collinsella tanakaei	662	AB490807	clade_553	N	N
Alkaliphilus metalliredigenes	137	AY137848	clade_554	Y	N
Alkaliphilus oremlandii	138	NR_043674	clade_554	Y	N
Caminicella sporogenes	458	NR_025485	clade_554	N	N
Clostridium sticklandii	648	L04167	clade_554	Y	N
Turicibacter sanguinis	1965	AF349724	clade_555	Y	N
Acidaminococcus fermentans	21	CP001859	clade_556	N	N
Acidaminococcus intestini	22	CP003058	clade_556	N	N
Acidaminococcus sp. D21	23	ACGB01000071	clade_556	N	N
Phascolarctobacterium faecium	1462	NR_026111	clade_556	N	N
Phascolarctobacterium sp. YIT 12068	1463	AB490812	clade_556	N	N
Phascolarctobacterium succinatutens	1464	AB490811	clade_556	N	N
Acidithiobacillus ferrivorans	25	NR_074660	clade_557	N	N
Fulvimonas sp. NML 060897	892	EF589680	clade_557	Y	N
Xanthomonadaceae bacterium NML 03_0222	2015	EU313791	clade_557	N	N

Catabacter hongkongensis	494	AB671763	clade_558	N	N
Christensenella minuta	512	AB490809	clade_558	N	N
Clostridiales bacterium oral clone P4PA	536	AY207065	clade_558	N	N
Clostridiales bacterium oral taxon 093	537	GQ422712	clade_558	N	N
Desulfitobacterium frappieri	753	AJ276701	clade_560	Y	N
Desulfitobacterium hafniense	754	NR_074996	clade_560	Y	N
Desulfotomaculum nigrificans	756	NR_044832	clade_560	Y	N
Heliobacterium modesticaldum	1000	NR_074517	clade_560	N	N
Alistipes indistinctus	130	AB490804	clade_561	N	N
Bacteroidales bacterium ph8	257	JN837494	clade_561	N	N
Candidatus Sulcia muelleri	475	CP002163	clade_561	N	N
Cytophaga xylanolytica	742	FR733683	clade_561	N	N
Flavobacteriaceae genomosp. C1	884	AY278614	clade_561	N	N
Gramella forsetii	958	NR_074707	clade_561	N	N
Sphingobacterium faecium	1740	NR_025537	clade_562	N	N
Sphingobacterium mizutaii	1741	JF708889	clade_562	N	N
Sphingobacterium multivorum	1742	NR_040953	clade_562	N	N
Sphingobacterium spiritivorum	1743	ACHA02000013	clade_562	N	N
Jonquetella anthropi	1017	ACOO02000004	clade_563	N	N
Pyramidobacter piscolens	1614	AY207056	clade_563	N	N
Synergistes genomosp. C1	1904	AY278615	clade_563	N	N
Synergistes sp. RMA 14551	1905	DQ412722	clade_563	N	N
Synergistetes bacterium ADV897	1906	GQ258968	clade_563	N	N
Candidatus Arthromitus sp. SFB_mouse_Yit	474	NR_074460	clade_564	N	N
Gracilibacter thermotolerans	957	NR_043559	clade_564	N	N
Lutispora thermophila	1191	NR_041236	clade_564	Y	N
Brachyspira aalborgi	404	FM178386	clade_565	N	N
Brachyspira pilosicoli	405	NR_075069	clade_565	Y	N
Brachyspira sp. HIS3	406	FM178387	clade_565	N	N
Brachyspira sp. HIS4	407	FM178388	clade_565	N	N
Brachyspira sp. HIS5	408	FM178389	clade_565	N	N
Adlercreutzia equolifaciens	97	AB306661	clade_566	N	N
Coriobacteriaceae bacterium JC110	678	CAEM01000062	clade_566	N	N
Coriobacteriaceae bacterium phI	679	JN837493	clade_566	N	N
Cryptobacterium curtum	740	GQ422741	clade_566	N	N
Eggerthella lenta	778	AF292375	clade_566	Y	N
Eggerthella sinensis	779	AY321958	clade_566	N	N
Eggerthella sp. 1_3_56FAA	780	ACWN01000099	clade_566	N	N
Eggerthella sp. HGA1	781	AEXR01000021	clade_566	N	N
Eggerthella sp. YY7918	782	AP012211	clade_566	N	N
Gordonibacter pamelaeae	680	AM886059	clade_566	N	N
Gordonibacter pamelaeae	956	FP929047	clade_566	N	N
Slackia equolifaciens	1732	EU377663	clade_566	N	N
Slackia exigua	1733	ACUX01000029	clade_566	N	N
Slackia faecicanis	1734	NR_042220	clade_566	N	N
Slackia heliotrinireducens	1735	NR_074439	clade_566	N	N
Slackia isoflavoniconvertens	1736	AB566418	clade_566	N	N
Slackia piriformis	1737	AB490806	clade_566	N	N

Slackia sp. NATTS	1738	AB505075	clade_566	N	N
Streptomyces albus	1888	AJ697941	clade_566	Y	N
Chlamydiales bacterium NS11	505	JN606074	clade_567	Y	N
Chlamydiales bacterium NS13	506	JN606075	clade_567	N	N
Victivallaceae bacterium NML 080035	2003	FJ394915	clade_567	N	N
Victivallis vadensis	2004	ABDE02000010	clade_567	N	N
Anaerofustis stercorihominis	159	ABIL02000005	clade_570	Y	N
Butyricicoccus pullicaecorum	453	HH793440	clade_572	Y	N
Eubacterium desmolans	843	NR_044644	clade_572	Y	N
Papillibacter cinnamivorans	1415	NR_025025	clade_572	Y	N
Sporobacter termitidis	1751	NR_044972	clade_572	Y	N
Streptomyces griseus	1889	NR_074787	clade_573	N	N
Streptomyces sp. SD 511	1891	EU544231	clade_573	N	N
Streptomyces sp. SD 534	1894	EU544232	clade_573	N	N
Cloacibacillus evryensis	530	GQ258966	clade_575	N	N
Deferribacteres sp. oral clone JV001	743	AY349370	clade_575	N	N
Deferribacteres sp. oral clone JV006	744	AY349371	clade_575	Y	N
Deferribacteres sp. oral clone JV023	745	AY349372	clade_575	N	N
Synergistetes bacterium LBVCM1157	1907	GQ258969	clade_575	N	N
Synergistetes bacterium oral taxon 362	1909	GU410752	clade_575	N	N
Synergistetes bacterium oral taxon D48	1910	GU430992	clade_575	N	N
Clostridium colinum	577	NR_026151	clade_576	Y	N
Clostridium lactatifermentans	599	NR_025651	clade_576	Y	N
Clostridium piliforme	614	D14639	clade_576	Y	N
Peptococcus sp. oral clone JM048	1439	AY349389	clade_576	N	N
Helicobacter winghamensis	999	ACDO01000013	clade_577	N	N
Wolinella succinogenes	2014	BX571657	clade_577	N	N
Olsenella genomosp. C1	1368	AY278623	clade_578	N	N
Olsenella profusa	1369	FN178466	clade_578	N	N
Olsenella sp. F0004	1370	EU592964	clade_578	N	N
Olsenella sp. oral taxon 809	1371	ACVE01000002	clade_578	N	N
Olsenella uli	1372	CP002106	clade_578	N	N
Nocardiopsis dassonvillei	1356	CP002041	clade_579	N	N
Saccharomonospora viridis	1671	X54286	clade_579	Y	N
Thermobifida fusca	1921	NC_007333	clade_579	Y	N
Peptococcus niger	1438	NR_029221	clade_580	N	N
Peptococcus sp. oral taxon 167	1440	GQ422727	clade_580	N	N
Akkermansia muciniphila	118	CP001071	clade_583	N	N
Opitutus terrae	1373	NR_074978	clade_583	N	N
Clostridiales bacterium oral taxon F32	538	HM099644	clade_584	N	N
Leptospira borgpetersenii	1161	NC_008508	clade_585	N	OP
Leptospira broomii	1162	NR_043200	clade_585	N	OP
Leptospira interrogans	1163	NC_005823	clade_585	N	OP
Leptospira licerasiae	1164	EF612284	clade_585	Y	OP
Methanobrevibacter gottschalkii	1213	NR_044789	clade_587	N	N
Methanobrevibacter millerae	1214	NR_042785	clade_587	N	N
Methanobrevibacter oralis	1216	HE654003	clade_587	N	N
Methanobrevibacter thaueri	1219	NR_044787	clade_587	N	N

Methanobrevibacter smithii	1218	ABYV02000002	clade_588	N	N
Deinococcus radiodurans	746	AE000513	clade_589	N	N
Deinococcus sp. R_43890	747	FR682752	clade_589	N	N
Thermus aquaticus	1923	NR_025900	clade_589	N	N
Actinomyces sp. c109	81	AB167239	clade_590	N	N
Moorella thermoacetica	1259	NR_075001	clade_590	Y	N
Syntrophomonadaceae genomosp. P1	1912	AY341821	clade_590	N	N
Thermoanaerobacter pseudethanolicus	1920	CP000924	clade_590	Y	N
Anaerobaculum hydrogeniformans	141	ACJX02000009	clade_591	N	N
Flexistipes sinusarabici	888	NR_074881	clade_591	Y	N
Microcystis aeruginosa	1246	NC_010296	clade_592	N	N
Prochlorococcus marinus	1567	CP000551	clade_592	N	N
Methanobrevibacter acididurans	1208	NR_028779	clade_593	N	N
Methanobrevibacter arboriphilus	1209	NR_042783	clade_593	N	N
Methanobrevibacter curvatus	1210	NR_044796	clade_593	N	N
Methanobrevibacter cuticularis	1211	NR_044776	clade_593	N	N
Methanobrevibacter filiformis	1212	NR_044801	clade_593	N	N
Methanobrevibacter woesei	1220	NR_044788	clade_593	N	N
Roseiflexus castenholzii	1642	CP000804	clade_594	N	N
Methanobrevibacter olleyae	1215	NR_043024	clade_595	N	N
Methanobrevibacter ruminantium	1217	NR_042784	clade_595	N	N
Methanobrevibacter wolinii	1221	NR_044790	clade_595	N	N
Methanosphaera stadtmanae	1222	AY196684	clade_595	N	N
Chloroflexi genomosp. P1	511	AY331414	clade_596	N	N
Gloeobacter violaceus	942	NR_074282	clade_596	Y	N
Halorubrum lipolyticum	992	AB477978	clade_597	N	N
Methanobacterium formicicum	1207	NR_025028	clade_597	N	N
Acidilobus saccharovorans	24	AY350586	clade_598	N	N
Hyperthermus butylicus	1006	CP000493	clade_598	N	N
Ignicoccus islandicus	1011	X99562	clade_598	N	N
Metallosphaera sedula	1206	D26491	clade_598	N	N
Thermofilum pendens	1922	X14835	clade_598	N	N
Prevotella melaninogenica	1506	CP002122	clade_6	N	N
Prevotella sp. ICM1	1520	HQ616385	clade_6	N	N
Prevotella sp. oral clone FU048	1535	AY349393	clade_6	N	N
Prevotella sp. oral clone GI030	1537	AY349395	clade_6	N	N
Prevotella sp. SEQ116	1526	JN867246	clade_6	N	N
Streptococcus anginosus	1787	AECT01000011	clade_60	N	N
Streptococcus milleri	1812	X81023	clade_60	N	N
Streptococcus sp. 16362	1829	JN590019	clade_60	N	N
Streptococcus sp. 69130	1832	X78825	clade_60	N	N
Streptococcus sp. AC15	1833	HQ616356	clade_60	N	N
Streptococcus sp. CM7	1839	HQ616373	clade_60	N	N
Streptococcus sp. OBRC6	1847	HQ616352	clade_60	N	N
Burkholderia ambifaria	442	AAUZ01000009	clade_61	N	OP
Burkholderia cenocepacia	443	AAHI01000060	clade_61	N	OP
Burkholderia cepacia	444	NR_041719	clade_61	N	OP
Burkholderia mallei	445	CP000547	clade_61	N	Category-

					B
Burkholderia multivorans	446	NC_010086	clade_61	N	OP
Burkholderia oklahomensis	447	DQ108388	clade_61	N	OP
Burkholderia pseudomallei	448	CP001408	clade_61	N	Category-B
Burkholderia rhizoxinica	449	HQ005410	clade_61	N	OP
Burkholderia sp. 383	450	CP000151	clade_61	N	OP
Burkholderia xenovorans	451	U86373	clade_61	N	OP
Prevotella buccae	1488	ACRB01000001	clade_62	N	N
Prevotella genomosp. P8 oral clone MB3_P13	1498	DQ003622	clade_62	N	N
Prevotella sp. oral clone FW035	1536	AY349394	clade_62	N	N
Prevotella bivia	1486	ADFO01000096	clade_63	N	N
Prevotella disiens	1494	AEDO01000026	clade_64	N	N
Bacteroides faecis	276	GQ496624	clade_65	N	N
Bacteroides fragilis	279	AP006841	clade_65	N	N
Bacteroides nordii	285	NR_043017	clade_65	N	N
Bacteroides salyersiae	292	EU136690	clade_65	N	N
Bacteroides sp. 1_1_14	293	ACRP01000155	clade_65	N	N
Bacteroides sp. 1_1_6	295	ACIC01000215	clade_65	N	N
Bacteroides sp. 2_1_56FAA	298	ACWI01000065	clade_65	N	N
Bacteroides sp. AR29	316	AF139525	clade_65	N	N
Bacteroides sp. B2	317	EU722733	clade_65	N	N
Bacteroides thetaiotaomicron	328	NR_074277	clade_65	N	N
Actinobacillus minor	45	ACFT01000025	clade_69	N	N
Haemophilus parasuis	978	GU226366	clade_69	N	N
Vibrio cholerae	1996	AAUR01000095	clade_71	N	Category-B
Vibrio fluvialis	1997	X76335	clade_71	N	Category-B
Vibrio furnissii	1998	CP002377	clade_71	N	Category-B
Vibrio mimicus	1999	ADAF01000001	clade_71	N	Category-B
Vibrio parahaemolyticus	2000	AAWQ01000116	clade_71	N	Category-B
Vibrio sp. RC341	2001	ACZT01000024	clade_71	N	Category-B
Vibrio vulnificus	2002	AE016796	clade_71	N	Category-B
Lactobacillus acidophilus	1067	CP000033	clade_72	N	N
Lactobacillus amylolyticus	1069	ADNY01000006	clade_72	N	N
Lactobacillus amylovorus	1070	CP002338	clade_72	N	N
Lactobacillus crispatus	1078	ACOG01000151	clade_72	N	N
Lactobacillus delbrueckii	1080	CP002341	clade_72	N	N
Lactobacillus helveticus	1088	ACLM01000202	clade_72	N	N
Lactobacillus kalixensis	1094	NR_029083	clade_72	N	N
Lactobacillus kefiranofaciens	1095	NR_042440	clade_72	N	N
Lactobacillus leichmannii	1098	JX986966	clade_72	N	N
Lactobacillus sp. 66c	1120	FR681900	clade_72	N	N

Lactobacillus sp. KLDS 1.0701	1122	EU600905	clade_72	N	N
Lactobacillus sp. KLDS 1.0712	1130	EU600916	clade_72	N	N
Lactobacillus sp. oral clone HT070	1136	AY349383	clade_72	N	N
Lactobacillus ultunensis	1139	ACGU01000081	clade_72	N	N
Prevotella intermedia	1502	AF414829	clade_81	N	N
Prevotella nigrescens	1511	AFPX01000069	clade_81	N	N
Prevotella pallens	1515	AFPY01000135	clade_81	N	N
Prevotella sp. oral taxon 310	1551	GQ422737	clade_81	N	N
Prevotella genomosp. C1	1495	AY278624	clade_82	N	N
Prevotella sp. CM38	1519	HQ610181	clade_82	N	N
Prevotella sp. oral taxon 317	1552	ACQH01000158	clade_82	N	N
Prevotella sp. SG12	1527	GU561343	clade_82	N	N
Prevotella denticola	1493	CP002589	clade_83	N	N
Prevotella genomosp. P7 oral clone MB2_P31	1497	DQ003620	clade_83	N	N
Prevotella histicola	1501	JN867315	clade_83	N	N
Prevotella multiformis	1508	AEWX01000054	clade_83	N	N
Prevotella sp. JCM 6330	1522	AB547699	clade_83	N	N
Prevotella sp. oral clone GI059	1539	AY349397	clade_83	N	N
Prevotella sp. oral taxon 782	1555	GQ422745	clade_83	N	N
Prevotella sp. oral taxon G71	1559	GU432180	clade_83	N	N
Prevotella sp. SEQ065	1524	JN867234	clade_83	N	N
Prevotella veroralis	1565	ACVA01000027	clade_83	N	N
Bacteroides acidifaciens	266	NR_028607	clade_85	N	N
Bacteroides cellulosilyticus	269	ACCH01000108	clade_85	N	N
Bacteroides clarus	270	AFBM01000011	clade_85	N	N
Bacteroides eggerthii	275	ACWG01000065	clade_85	N	N
Bacteroides oleiciplenus	286	AB547644	clade_85	N	N
Bacteroides pyogenes	290	NR_041280	clade_85	N	N
Bacteroides sp. 315_5	300	FJ848547	clade_85	N	N
Bacteroides sp. 31SF15	301	AJ583248	clade_85	N	N
Bacteroides sp. 31SF18	302	AJ583249	clade_85	N	N
Bacteroides sp. 35AE31	303	AJ583244	clade_85	N	N
Bacteroides sp. 35AE37	304	AJ583245	clade_85	N	N
Bacteroides sp. 35BE34	305	AJ583246	clade_85	N	N
Bacteroides sp. 35BE35	306	AJ583247	clade_85	N	N
Bacteroides sp. WH2	324	AY895180	clade_85	N	N
Bacteroides sp. XB12B	325	AM230648	clade_85	N	N
Bacteroides stercoris	327	ABFZ02000022	clade_85	N	N
Actinobacillus pleuropneumoniae	46	NR_074857	clade_88	N	N
Actinobacillus ureae	48	AEVG01000167	clade_88	N	N
Haemophilus aegyptius	969	AFBC01000053	clade_88	N	N
Haemophilus ducreyi	970	AE017143	clade_88	N	OP
Haemophilus haemolyticus	973	JN175335	clade_88	N	N
Haemophilus influenzae	974	AADP01000001	clade_88	N	OP
Haemophilus parahaemolyticus	975	GU561425	clade_88	N	N
Haemophilus parainfluenzae	976	AEWU01000024	clade_88	N	N
Haemophilus paraphrophaemolyticus	977	M75076	clade_88	N	N
Haemophilus somnus	979	NC_008309	clade_88	N	N

Haemophilus sp. 70334	980	HQ680854	clade_88	N	N
Haemophilus sp. HK445	981	FJ685624	clade_88	N	N
Haemophilus sp. oral clone ASCA07	982	AY923117	clade_88	N	N
Haemophilus sp. oral clone ASCG06	983	AY923147	clade_88	N	N
Haemophilus sp. oral clone BJ021	984	AY005034	clade_88	N	N
Haemophilus sp. oral clone BJ095	985	AY005033	clade_88	N	N
Haemophilus sp. oral taxon 851	987	AGRK01000004	clade_88	N	N
Haemophilus sputorum	988	AFNK01000005	clade_88	N	N
Histophilus somni	1003	AF549387	clade_88	N	N
Mannheimia haemolytica	1195	ACZX01000102	clade_88	N	N
Pasteurella bettyae	1433	L06088	clade_88	N	N
Moellerella wisconsensis	1253	JN175344	clade_89	N	N
Morganella morganii	1265	AJ301681	clade_89	N	N
Morganella sp. JB_T16	1266	AJ781005	clade_89	N	N
Proteus mirabilis	1582	ACLE01000013	clade_89	N	N
Proteus penneri	1583	ABVP01000020	clade_89	N	N
Proteus sp. HS7514	1584	DQ512963	clade_89	N	N
Proteus vulgaris	1585	AJ233425	clade_89	N	N
Eubacterium sp. oral clone JN088	869	AY349377	clade_90	Y	N
Oribacterium sinus	1374	ACKX01000142	clade_90	N	N
Oribacterium sp. ACB1	1375	HM120210	clade_90	N	N
Oribacterium sp. ACB7	1376	HM120211	clade_90	N	N
Oribacterium sp. CM12	1377	HQ616374	clade_90	N	N
Oribacterium sp. ICM51	1378	HQ616397	clade_90	N	N
Oribacterium sp. OBRC12	1379	HQ616355	clade_90	N	N
Oribacterium sp. oral taxon 108	1382	AFIH01000001	clade_90	N	N
Actinobacillus actinomycetemcomitans	44	AY362885	clade_92	N	N
Actinobacillus succinogenes	47	CP000746	clade_92	N	N
Aggregatibacter actinomycetemcomitans	112	CP001733	clade_92	N	N
Aggregatibacter aphrophilus	113	CP001607	clade_92	N	N
Aggregatibacter segnis	114	AEPS01000017	clade_92	N	N
Averyella dalhousiensis	194	DQ481464	clade_92	N	N
Bisgaard Taxon	368	AY683487	clade_92	N	N
Bisgaard Taxon	369	AY683489	clade_92	N	N
Bisgaard Taxon	370	AY683491	clade_92	N	N
Bisgaard Taxon	371	AY683492	clade_92	N	N
Buchnera aphidicola	440	NR_074609	clade_92	N	N
Cedecea davisae	499	AF493976	clade_92	N	N
Citrobacter amalonaticus	517	FR870441	clade_92	N	N
Citrobacter braakii	518	NR_028687	clade_92	N	N
Citrobacter farmeri	519	AF025371	clade_92	N	N
Citrobacter freundii	520	NR_028894	clade_92	N	N
Citrobacter gillenii	521	AF025367	clade_92	N	N
Citrobacter koseri	522	NC_009792	clade_92	N	N
Citrobacter murliniae	523	AF025369	clade_92	N	N
Citrobacter rodentium	524	NR_074903	clade_92	N	N
Citrobacter sedlakii	525	AF025364	clade_92	N	N
Citrobacter sp. 30_2	526	ACDJ01000053	clade_92	N	N

Citrobacter sp. KMSI_3	527	GQ468398	clade_92	N	N
Citrobacter werkmanii	528	AF025373	clade_92	N	N
Citrobacter youngae	529	ABWL02000011	clade_92	N	N
Cronobacter malonaticus	737	GU122174	clade_92	N	N
Cronobacter sakazakii	738	NC_009778	clade_92	N	N
Cronobacter turicensis	739	FN543093	clade_92	N	N
Enterobacter aerogenes	786	AJ251468	clade_92	N	N
Enterobacter asburiae	787	NR_024640	clade_92	N	N
Enterobacter cancerogenus	788	Z96078	clade_92	N	N
Enterobacter cloacae	789	FP929040	clade_92	N	N
Enterobacter cowanii	790	NR_025566	clade_92	N	N
Enterobacter hormaechei	791	AFHR01000079	clade_92	N	N
Enterobacter sp. 247BMC	792	HQ122932	clade_92	N	N
Enterobacter sp. 638	793	NR_074777	clade_92	N	N
Enterobacter sp. JC163	794	JN657217	clade_92	N	N
Enterobacter sp. SCSS	795	HM007811	clade_92	N	N
Enterobacter sp. TSE38	796	HM156134	clade_92	N	N
Enterobacteriaceae bacterium 9_2_54FAA	797	ADCU01000033	clade_92	N	N
Enterobacteriaceae bacterium CF01Ent_1	798	AJ489826	clade_92	N	N
Enterobacteriaceae bacterium Smarlab 3302238	799	AY538694	clade_92	N	N
Escherichia albertii	824	ABKX01000012	clade_92	N	N
Escherichia coli	825	NC_008563	clade_92	N	Category-B
Escherichia fergusonii	826	CU928158	clade_92	N	N
Escherichia hermannii	827	HQ407266	clade_92	N	N
Escherichia sp. 1_1_43	828	ACID01000033	clade_92	N	N
Escherichia sp. 4_1_40B	829	ACDM02000056	clade_92	N	N
Escherichia sp. B4	830	EU722735	clade_92	N	N
Escherichia vulneris	831	NR_041927	clade_92	N	N
Ewingella americana	877	JN175329	clade_92	N	N
Haemophilus genomosp. P2 oral clone MB3_C24	971	DQ003621	clade_92	N	N
Haemophilus genomosp. P3 oral clone MB3_C38	972	DQ003635	clade_92	N	N
Haemophilus sp. oral clone JM053	986	AY349380	clade_92	N	N
Hafnia alvei	989	DQ412565	clade_92	N	N
Klebsiella oxytoca	1024	AY292871	clade_92	N	OP
Klebsiella pneumoniae	1025	CP000647	clade_92	N	OP
Klebsiella sp. AS10	1026	HQ616362	clade_92	N	N
Klebsiella sp. Co9935	1027	DQ068764	clade_92	N	N
Klebsiella sp. enrichment culture clone SRC_DSD25	1036	HM195210	clade_92	N	N
Klebsiella sp. OBRC7	1028	HQ616353	clade_92	N	N
Klebsiella sp. SP_BA	1029	FJ999767	clade_92	N	N
Klebsiella sp. SRC_DSD1	1033	GU797254	clade_92	N	N
Klebsiella sp. SRC_DSD11	1030	GU797263	clade_92	N	N
Klebsiella sp. SRC_DSD12	1031	GU797264	clade_92	N	N
Klebsiella sp. SRC_DSD15	1032	GU797267	clade_92	N	N
Klebsiella sp. SRC_DSD2	1034	GU797253	clade_92	N	N
Klebsiella sp. SRC_DSD6	1035	GU797258	clade_92	N	N
Klebsiella variicola	1037	CP001891	clade_92	N	N

Kluyvera ascorbata	1038	NR_028677	clade_92	N	N
Kluyvera cryocrescens	1039	NR_028803	clade_92	N	N
Leminorella grimontii	1159	AJ233421	clade_92	N	N
Leminorella richardii	1160	HF558368	clade_92	N	N
Pantoea agglomerans	1409	AY335552	clade_92	N	N
Pantoea ananatis	1410	CP001875	clade_92	N	N
Pantoea brenneri	1411	EU216735	clade_92	N	N
Pantoea citrea	1412	EF688008	clade_92	N	N
Pantoea conspicua	1413	EU216737	clade_92	N	N
Pantoea septica	1414	EU216734	clade_92	N	N
Pasteurella dagmatis	1434	ACZR01000003	clade_92	N	N
Pasteurella multocida	1435	NC_002663	clade_92	N	N
Plesiomonas shigelloides	1469	X60418	clade_92	N	N
Raoultella ornithinolytica	1617	AB364958	clade_92	N	N
Raoultella planticola	1618	AF129443	clade_92	N	N
Raoultella terrigena	1619	NR_037085	clade_92	N	N
Salmonella bongori	1683	NR_041699	clade_92	N	Category-B
Salmonella enterica	1672	NC_011149	clade_92	N	Category-B
Salmonella enterica	1673	NC_011205	clade_92	N	Category-B
Salmonella enterica	1674	DQ344532	clade_92	N	Category-B
Salmonella enterica	1675	ABEH02000004	clade_92	N	Category-B
Salmonella enterica	1676	ABAK02000001	clade_92	N	Category-B
Salmonella enterica	1677	NC_011080	clade_92	N	Category-B
Salmonella enterica	1678	EU118094	clade_92	N	Category-B
Salmonella enterica	1679	NC_011094	clade_92	N	Category-B
Salmonella enterica	1680	AE014613	clade_92	N	Category-B
Salmonella enterica	1682	ABFH02000001	clade_92	N	Category-B
Salmonella enterica	1684	ABEM01000001	clade_92	N	Category-B
Salmonella enterica	1685	ABAM02000001	clade_92	N	Category-B
Salmonella typhimurium	1681	DQ344533	clade_92	N	Category-B
Salmonella typhimurium	1686	AF170176	clade_92	N	Category-B
Serratia fonticola	1718	NR_025339	clade_92	N	N
Serratia liquefaciens	1719	NR_042062	clade_92	N	N
Serratia marcescens	1720	GU826157	clade_92	N	N

Serratia odorifera	1721	ADBY01000001	clade_92	N	N
Serratia proteamaculans	1722	AAUN01000015	clade_92	N	N
Shigella boydii	1724	AAKA01000007	clade_92	N	Category-B
Shigella dysenteriae	1725	NC_007606	clade_92	N	Category-B
Shigella flexneri	1726	AE005674	clade_92	N	Category-B
Shigella sonnei	1727	NC_007384	clade_92	N	Category-B
Tatumella ptyseos	1916	NR_025342	clade_92	N	N
Trabulsiella guamensis	1925	AY373830	clade_92	N	N
Yersinia aldovae	2019	AJ871363	clade_92	N	OP
Yersinia aleksiciae	2020	AJ627597	clade_92	N	OP
Yersinia bercovieri	2021	AF366377	clade_92	N	OP
Yersinia enterocolitica	2022	FR729477	clade_92	N	Category-B
Yersinia frederiksenii	2023	AF366379	clade_92	N	OP
Yersinia intermedia	2024	AF366380	clade_92	N	OP
Yersinia kristensenii	2025	ACCA01000078	clade_92	N	OP
Yersinia mollaretii	2026	NR_027546	clade_92	N	OP
Yersinia pestis	2027	AE013632	clade_92	N	Category-A
Yersinia pseudotuberculosis	2028	NC_009708	clade_92	N	OP
Yersinia rohdei	2029	ACCD01000071	clade_92	N	OP
Yokenella regensburgei	2030	AB273739	clade_92	N	N
Conchiformibius kuhniae	669	NR_041821	clade_94	N	N
Morococcus cerebrosus	1267	JN175352	clade_94	N	N
Neisseria bacilliformis	1328	AFAY01000058	clade_94	N	N
Neisseria cinerea	1329	ACDY01000037	clade_94	N	N
Neisseria flavescens	1331	ACQV01000025	clade_94	N	N
Neisseria gonorrhoeae	1333	CP002440	clade_94	N	OP
Neisseria lactamica	1334	ACEQ01000095	clade_94	N	N
Neisseria macacae	1335	AFQE01000146	clade_94	N	N
Neisseria meningitidis	1336	NC_003112	clade_94	N	OP
Neisseria mucosa	1337	ACDX01000110	clade_94	N	N
Neisseria pharyngis	1338	AJ239281	clade_94	N	N
Neisseria polysaccharea	1339	ADBE01000137	clade_94	N	N
Neisseria sicca	1340	ACKO02000016	clade_94	N	N
Neisseria sp. KEM232	1341	GQ203291	clade_94	N	N
Neisseria sp. oral clone AP132	1344	AY005027	clade_94	N	N
Neisseria sp. oral strain B33KA	1346	AY005028	clade_94	N	N
Neisseria sp. oral taxon 014	1347	ADEA01000039	clade_94	N	N
Neisseria sp. TM10_1	1343	DQ279352	clade_94	N	N
Neisseria subflava	1348	ACEO01000067	clade_94	N	N
Clostridium oroticum	610	FR749922	clade_96	Y	N
Clostridium sp. D5	627	ADBG01000142	clade_96	Y	N
Eubacterium contortum	840	FR749946	clade_96	Y	N
Eubacterium fissicatena	846	FR749935	clade_96	Y	N

Okadaella gastrococcus	1365	HQ699465	clade_98	N	N
Streptococcus agalactiae	1785	AAJO01000130	clade_98	N	N
Streptococcus alactolyticus	1786	NR_041781	clade_98	N	N
Streptococcus australis	1788	AEQR01000024	clade_98	N	N
Streptococcus bovis	1789	AEEL01000030	clade_98	N	N
Streptococcus canis	1790	AJ413203	clade_98	N	N
Streptococcus constellatus	1791	AY277942	clade_98	N	N
Streptococcus cristatus	1792	AEVC01000028	clade_98	N	N
Streptococcus dysgalactiae	1794	AP010935	clade_98	N	N
Streptococcus equi	1795	CP001129	clade_98	N	N
Streptococcus equinus	1796	AEVB01000043	clade_98	N	N
Streptococcus gallolyticus	1797	FR824043	clade_98	N	N
Streptococcus genomosp. C1	1798	AY278629	clade_98	N	N
Streptococcus genomosp. C2	1799	AY278630	clade_98	N	N
Streptococcus genomosp. C3	1800	AY278631	clade_98	N	N
Streptococcus genomosp. C4	1801	AY278632	clade_98	N	N
Streptococcus genomosp. C5	1802	AY278633	clade_98	N	N
Streptococcus genomosp. C6	1803	AY278634	clade_98	N	N
Streptococcus genomosp. C7	1804	AY278635	clade_98	N	N
Streptococcus genomosp. C8	1805	AY278609	clade_98	N	N
Streptococcus gordonii	1806	NC_009785	clade_98	N	N
Streptococcus infantarius	1807	ABJK02000017	clade_98	N	N
Streptococcus infantis	1808	AFNN01000024	clade_98	N	N
Streptococcus intermedius	1809	NR_028736	clade_98	N	N
Streptococcus lutetiensis	1810	NR_037096	clade_98	N	N
Streptococcus massiliensis	1811	AY769997	clade_98	N	N
Streptococcus mitis	1813	AM157420	clade_98	N	N
Streptococcus oligofermentans	1815	AY099095	clade_98	N	N
Streptococcus oralis	1816	ADMV01000001	clade_98	N	N
Streptococcus parasanguinis	1817	AEKM01000012	clade_98	N	N
Streptococcus pasteurianus	1818	AP012054	clade_98	N	N
Streptococcus peroris	1819	AEVF01000016	clade_98	N	N
Streptococcus pneumoniae	1820	AE008537	clade_98	N	N
Streptococcus porcinus	1821	EF121439	clade_98	N	N
Streptococcus pseudopneumoniae	1822	FJ827123	clade_98	N	N
Streptococcus pseudoporcinus	1823	AENS01000003	clade_98	N	N
Streptococcus pyogenes	1824	AE006496	clade_98	N	OP
Streptococcus ratti	1825	X58304	clade_98	N	N
Streptococcus salivarius	1826	AGBV01000001	clade_98	N	N
Streptococcus sanguinis	1827	NR_074974	clade_98	N	N
Streptococcus sinensis	1828	AF432857	clade_98	N	N
Streptococcus sp. 2_1_36FAA	1831	ACOI01000028	clade_98	N	N
Streptococcus sp. 2285_97	1830	AJ131965	clade_98	N	N
Streptococcus sp. ACS2	1834	HQ616360	clade_98	N	N
Streptococcus sp. AS20	1835	HQ616366	clade_98	N	N
Streptococcus sp. BS35a	1836	HQ616369	clade_98	N	N
Streptococcus sp. C150	1837	ACRI01000045	clade_98	N	N
Streptococcus sp. CM6	1838	HQ616372	clade_98	N	N

Streptococcus sp. ICM10	1840	HQ616389	clade_98	N	N
Streptococcus sp. ICM12	1841	HQ616390	clade_98	N	N
Streptococcus sp. ICM2	1842	HQ616386	clade_98	N	N
Streptococcus sp. ICM4	1844	HQ616387	clade_98	N	N
Streptococcus sp. ICM45	1843	HQ616394	clade_98	N	N
Streptococcus sp. M143	1845	ACRK01000025	clade_98	N	N
Streptococcus sp. M334	1846	ACRL01000052	clade_98	N	N
Streptococcus sp. oral clone ASB02	1849	AY923121	clade_98	N	N
Streptococcus sp. oral clone ASCA03	1850	DQ272504	clade_98	N	N
Streptococcus sp. oral clone ASCA04	1851	AY923116	clade_98	N	N
Streptococcus sp. oral clone ASCA09	1852	AY923119	clade_98	N	N
Streptococcus sp. oral clone ASCB04	1853	AY923123	clade_98	N	N
Streptococcus sp. oral clone ASCB06	1854	AY923124	clade_98	N	N
Streptococcus sp. oral clone ASCC04	1855	AY923127	clade_98	N	N
Streptococcus sp. oral clone ASCC05	1856	AY923128	clade_98	N	N
Streptococcus sp. oral clone ASCC12	1857	DQ272507	clade_98	N	N
Streptococcus sp. oral clone ASCD01	1858	AY923129	clade_98	N	N
Streptococcus sp. oral clone ASCD09	1859	AY923130	clade_98	N	N
Streptococcus sp. oral clone ASCD10	1860	DQ272509	clade_98	N	N
Streptococcus sp. oral clone ASCE03	1861	AY923134	clade_98	N	N
Streptococcus sp. oral clone ASCE04	1862	AY953253	clade_98	N	N
Streptococcus sp. oral clone ASCE05	1863	DQ272510	clade_98	N	N
Streptococcus sp. oral clone ASCE06	1864	AY923135	clade_98	N	N
Streptococcus sp. oral clone ASCE09	1865	AY923136	clade_98	N	N
Streptococcus sp. oral clone ASCE10	1866	AY923137	clade_98	N	N
Streptococcus sp. oral clone ASCE12	1867	AY923138	clade_98	N	N
Streptococcus sp. oral clone ASCF05	1868	AY923140	clade_98	N	N
Streptococcus sp. oral clone ASCF07	1869	AY953255	clade_98	N	N
Streptococcus sp. oral clone ASCF09	1870	AY923142	clade_98	N	N
Streptococcus sp. oral clone ASCG04	1871	AY923145	clade_98	N	N
Streptococcus sp. oral clone BW009	1872	AY005042	clade_98	N	N
Streptococcus sp. oral clone CH016	1873	AY005044	clade_98	N	N
Streptococcus sp. oral clone GK051	1874	AY349413	clade_98	N	N
Streptococcus sp. oral clone GM006	1875	AY349414	clade_98	N	N
Streptococcus sp. oral clone P2PA_41 P2	1876	AY207051	clade_98	N	N
Streptococcus sp. oral clone P4PA_30 P4	1877	AY207064	clade_98	N	N
Streptococcus sp. oral taxon 071	1878	AEEP01000019	clade_98	N	N
Streptococcus sp. oral taxon G59	1879	GU432132	clade_98	N	N
Streptococcus sp. oral taxon G62	1880	GU432146	clade_98	N	N
Streptococcus sp. oral taxon G63	1881	GU432150	clade_98	N	N
Streptococcus suis	1882	FM252032	clade_98	N	N
Streptococcus thermophilus	1883	CP000419	clade_98	N	N
Streptococcus uberis	1884	HQ391900	clade_98	N	N
Streptococcus urinalis	1885	DQ303194	clade_98	N	N
Streptococcus vestibularis	1886	AEKO01000008	clade_98	N	N
Streptococcus viridans	1887	AF076036	clade_98	N	N
Synergistetes bacterium oral clone 03 5 D05	1908	GU227192	clade_98	N	N

Table 2.

Representative vitamins, minerals, and cofactors

L-glutamine
nickel chloride
$BaCl_2$
hemin
potassium tellurite
Fibrinogen
Bacto Vitamin-Free Casamino Acids
cocarboxylase
bovine albumin fraction V
$FeCl_2 \cdot H_2O$
L-cystine·2HCl
Bacto Casamino Acids
Agar
$CuSO_4$
pyridoxine
$SnCl_2 \cdot 2H_2O$
sodium selenite
$CaCl_2$
NaCl
albumin fraction V
vitamin B_{12}
folic acid
$ZnCl_2$
$FeSO_4$
oleic acid
$Co(NO_3)_2 \cdot 6H_2O$
L-cystine
$Na_2B_4O_7 \cdot 10H_2O$
$CaSO_4 \cdot 2H_2O$
$AlCl_3$
$SeCl_4$
$Na_2MoO_4 \cdot 2H_2O$
thiamine pyrophosphate
Pyridoxine·HCl
$MnCl_2 \cdot 4H_2O$
aluminum sulphate
Na_2HPO_4
H_3BO_3
L-cysteine·HCl·H_2O
adenine sulfate

long-chain fatty acids
KNO_3
sodium metabisulfite
sodium molybdate
$CoCl_2 \cdot 6H_2O$
Na_2MoO_4
Castenholz Salts
$NaNO_3$
HCl
L-cysteine
copper sulfate
L-cysteine·HCl
thiamine·HCl
biotin
sodium chloride
thallium acetate
$NiCl_2 \cdot 6H_2O$
$NaVO_3 \cdot H_2O$
nicotinamide adenine dinucleotide
nicotinic acid
$Na_2MoO_4 \cdot H_2O$
$CuCl_2 \cdot 2H_2O$
$FeCl_2 \cdot 4H_2O$
$(NH_4)_2MoO_4$
$MnSO_4$
guanine·HCl
H_2SO_4
$CoCl_2$
cholesterol
LiCl
pyridoxine·2HCl
Disodium ethylenediamine tetraacetic acid
Vitamin K1
KBr
alkalinized oleic acid
$ZnSO_4 \cdot 7H_2O$
trypsin inhibitor
KI
ethanol
cobalt nitrate
Ethylenediamine tetraacetic acid
$CuSO_4 \cdot 5H_2O$
calcium-D-pathothenate

$Fe(NO_3)_3$
$CaCl_2 \cdot 2H_2O$
Sodium pyruvate
NaOH
p-aminobenzoic acid
a-ketoglutarate
boric acid
casein
Pyridoxine hydrochloride
Dried bovine hemoglobin
$ZnSO_4$
Nicotinamide
$FeCl_3$
$Fe(NO_3)_3 \cdot 6H_2O$
calcium pantothenate
cyanocobalamin
nitrilotriacetic acid
Adenine
sodium tartrate
magnesium sulfate
zinc sulfate
$NaHCO_3$
Glucose
$MgSO_4 \cdot 7H_2O$
$Na_2S \cdot 9H_2O$
riboflavin
ferric pyrophosphate
Essential growth factors V and X
Peptone
$FeSO_4 \cdot 7H_2O$
catalase
$MnSO_4 \cdot 7H_2O$
$CuCl_2$
$Na_2SeO_3 \cdot 5H_2O$
thiamine
$NiCl_2$
sodium tungstate
iron sulfate
calcium chloride
$(NH_4)_6Mo_7O_{24} \cdot 4H_2O$
ACES buffer/KOH
Thioctic acid
succinate
formate

lactate
butyrate
acetate
Vitamin K
Mercaptoethane-sulfonic acid
Lipoic acid
ammonia
heme
S-Adenosylmethionine

Table 3.

Bacterial OTUs associated with engraftment and ecological augmentation and establishment of a more diverse microbial ecology in patients treated with an ethanol-treated spore preparation. OTUs that comprise an augmented ecology are not present in the patient prior to treatment and/or exist at extremely low frequencies such that they do not comprise a significant fraction of the total microbial carriage and are not detectable by genomic and/or microbiological assay methods. OTUs that are members of the engrafting and augmented ecologies were identified by characterizing the OTUs that increase in their relative abundance post treatment and that respectively are: (i) present in the ethanol-treated spore preparation and absent in the patient pretreatment, or (ii) absent in the ethanol-treated spore preparation, but increase in their relative abundance through time post treatment with the preparation due to the formation of favorable growth conditions by the treatment. Notably, the latter OTUs can grow from low frequency reservoirs in the patient, or be introduced from exogenous sources such as diet. OTUs that comprise a "core" augmented or engrafted ecology can be defined by the percentage of total patients in which they are observed to engraft and/or augment; the greater this percentage the more likely they are to be part of a core ecology responsible for catalyzing a shift away from a dysbiotic ecology. The dominant OTUs in an ecology can be identified using several methods including but not limited to defining the OTUs that have the greatest relative abundance in either the augmented or engrafted ecologies and defining a total relative abundance threshold. As example, the dominant OTUs in the augmented ecology of Patient-1 were identified by defining the OTUs with the greatest relative abundance, which together comprise 60% of the microbial carriage in this patient's augmented ecology.

OTU	Phylogenetic Clade	Spore Forming OTU	Dominant OTU in Augmented Ecology
Bacteroides sp. 2_1_22	clade38	N	Y
Streptococcus anginosus	clade60	N	
Prevotella intermedia	clade81	N	
Prevotella nigrescens	clade81	N	
Oribacterium sp. ACB7	clade90	N	
Prevotella salivae	clade104	N	
Bacteroides intestinalis	clade171	N	Y
Bifidobacterium dentium	clade172	N	
Alcaligenes faecalis	clade183	N	

[illegible]	[illegible]	[illegible]	[illegible]
Rothia dentocariosa	clade194	N	
Peptoniphilus lacrimalis	clade291	N	
Anaerococcus sp. gpac155	clade294	N	
Sutterella stercoricanis	clade302	N	Y
Bacteroides sp. 3_1_19	clade335	N	Y
Parabacteroides goldsteinii	clade335	N	
Bacteroides dorei	clade378	N	Y
Bacteroides massiliensis	clade378	N	
Lactobacillus iners	clade398	N	
Granulicatella adiacens	clade460	N	
Eggerthella sp. 1_3_56FAA	clade477	N	
Gordonibacter pamelaeae	clade477	N	
Finegoldia magna	clade509	N	
Actinomyces nasicola	clade523	N	
Streptobacillus moniliformis	clade532	N	
Oscillospira guilliermondii	clade540	N	
Orientia tsutsugamushi	clade541	N	
Christensenella minuta	clade558	N	
Clostridium oroticum	clade96	Y	
Clostridium sp. D5	clade96	Y	
Clostridium glycyrrhizinilyticum	clade147	Y	
Coprococcus comes	clade147	Y	
Ruminococcus lactaris	clade147	Y	
Ruminococcus torques	clade147	Y	Y
Clostridiales sp. SS3/4	clade246	Y	
Clostridium hylemonae	clade260	Y	

[illegible]	[illegible]	[illegible]	[illegible]
Clostridium aerotolerans	clade269	Y	
Clostridium asparagiforme	clade300	Y	Y
Clostridium sp. M62/1	clade300	Y	
Clostridium symbiosum	clade300	Y	
Lachnospiraceae genomosp. C1	clade300	Y	
Blautia sp. M25	clade304	Y	Y
Blautia stercoris	clade304	Y	
Ruminococcus hansenii	clade304	Y	
Ruminococcus obeum	clade304	Y	
Ruminococcus sp. 5_1_39BFAA	clade304	Y	
Bryantella formatexigens	clade309	Y	
Eubacterium cellulosolvens	clade309	Y	
Clostridium sp. HGF2	clade351	Y	
Clostridium bartlettii	clade354	Y	
Clostridium bifermentans	clade354	Y	
Clostridium glycolicum	clade354	Y	
Eubacterium tenue	clade354	Y	
Dorea formicigenerans	clade360	Y	
Dorea longicatena	clade360	Y	
Lachnospiraceae bacterium 2_1_46FAA	clade360	Y	
Lachnospiraceae bacterium 9_1_43BFAA	clade360	Y	Y
Ruminococcus gnavus	clade360	Y	
Clostridium hathewayi	clade362	Y	
Blautia hydrogenotrophica	clade368	Y	
Clostridiaceae bacterium END-2	clade368	Y	
Roseburia faecis	clade369	Y	

[illegible]	[illegible]	[illegible]	[illegible]
Roseburia hominis	clade370	Y	
Roseburia intestinalis	clade370	Y	
Eubacterium sp. WAL 14571	clade384	Y	
Erysipelotrichaceae bacterium 5_2_54FAA	clade385	Y	
Eubacterium biforme	clade385	Y	
Eubacterium dolichum	clade385	Y	
Coprococcus catus	clade393	Y	
Acetivibrio ethanolgignens	clade396	Y	
Anaerosporobacter mobilis	clade396	Y	
Bacteroides pectinophilus	clade396	Y	
Eubacterium hallii	clade396	Y	
Eubacterium xylanophilum	clade396	Y	
Anaerostipes caccae	clade408	Y	
Clostridiales bacterium 1_7_47FAA	clade408	Y	
Clostridium aldenense	clade408	Y	
Clostridium citroniae	clade408	Y	
Eubacterium hadrum	clade408	Y	Y
Acetanaerobacterium elongatum	clade439	Y	
Faecalibacterium prausnitzii	clade478	Y	
Gemmiger formicilis	clade478	Y	Y
Eubacterium ramulus	clade482	Y	
Lachnospiraceae bacterium 3_1_57FAA_CT1	clade483	Y	
Lachnospiraceae bacterium A4	clade483	Y	Y
Lachnospiraceae bacterium DJF VP30	clade483	Y	
Holdemania filiformis	clade485	Y	
Clostridium orbiscindens	clade494	Y	

OTU	Phylogenetic Clade	Spore Forming OTU	Treatment OTU or Augmented Taxon
Pseudoflavonifractor capillosus	clade494	Y	
Ruminococcaceae bacterium D16	clade494	Y	
Acetivibrio cellulolyticus	clade495	Y	
Eubacterium limosum	clade512	Y	
Anaerotruncus colihominis	clade516	Y	
Clostridium methylpentosum	clade516	Y	
Clostridium sp. YIT 12070	clade516	Y	
Hydrogenoanaerobacterium saccharovorans	clade516	Y	
Eubacterium ventriosum	clade519	Y	
Eubacterium eligens	clade522	Y	
Lachnospira pectinoschiza	clade522	Y	
Lactobacillus rogosae	clade522	Y	Y
Clostridium leptum	clade537	Y	
Eubacterium coprostanoligenes	clade537	Y	
Ruminococcus bromii	clade537	Y	
Clostridium viride	clade540	Y	
Butyrivibrio crossotus	clade543	Y	
Coprococcus eutactus	clade543	Y	
Eubacterium ruminantium	clade543	Y	
Eubacterium rectale	clade568	Y	Y
Roseburia inulinivorans	clade568	Y	
Butyricicoccus pullicaecorum	clade572	Y	
Eubacterium desmolans	clade572	Y	
Papillibacter cinnamivorans	clade572	Y	
Sporobacter termitidis	clade572	Y	
Clostridium lactatifermentans	clade576	Y	

Table 4.

Reduction in pathogen carriage post treatment with bacterial composition treatment of Patient 1.

	Pretreatment	Day 5	Day 14	Day 25
Klebsiella (% of total reads)	20.27%	1.32%	7.62%	0.00%
Fusobacterium (% total of reads)	19.14%	3.01%	0.01%	0.00%

Table 5.

Augmentation of Bacteroides as a function of bacterial composition treatment of Patient 1.

Media	Bacteroides species	Pretreatment titer (cfu/g)	Day 25 titer (cfu/g)
BBE	*B. fragilis* group	$<2x10^4$	$3x10^8$
PFA	All Bacteroides	$<2x10^7$	$2x10^{10}$

Table 6.

OTUs detected by a minimum of ten 16S-V4 sequence reads in at least a one ethanol-treated spore preparation. OTUs that engraft in a treated patients and the percentage of patients in which they engraft are denoted, as are the clades, spore forming status, and Keystone OTU status. Starred OTUs occur in ≥80% of the ethanol preps and engraft in ≥50% of the treated patients.

OTU	Clade	% of Spore Preps with OTU	% of Patients OTU Engrafts	Spore Former	Keystone OTU
Prevotella_maculosa	clade_104	10%	0%	N	N
Prevotella_copri	clade_168	20%	0%	N	N
Bacteroides_caccae	clade_170	30%	0%	N	Y
Bifidobacterium_sp_TM_7*	**clade_172**	**90%**	**60%**	**N**	**N**
Bifidobacterium_gallicum	clade_172	70%	20%	N	N
Bifidobacterium_dentium	clade_172	50%	0%	N	N
Lactobacillus_casei	clade_198	20%	10%	N	N
Actinomyces_odontolyticus	clade_212	20%	30%	N	N
Clostridium_colicanis	clade_223	10%	10%	Y	N
Clostridiales_sp_SS3_4*	**clade_246**	**100%**	**70%**	**Y**	**N**
Clostridium_sporogenes	clade_252	40%	40%	Y	N
Clostridium_butyricum	clade_252	20%	20%	Y	N
Clostridium_disporicum	clade_253	40%	30%	Y	N
Clostridium_hylemonae*	**clade_260**	**100%**	**50%**	**Y**	**N**
Clostridium_scindens	clade_260	10%	60%	Y	N
Coprococcus_comes*	**clade_262**	**90%**	**80%**	**Y**	**Y**
Lachnospiraceae_bacterium_1_4_56FAA*	**clade_262**	**90%**	**80%**	**Y**	**Y**
Ruminococcus_torques	clade_262	30%	70%	Y	Y
Parabacteroides_merdae	clade_286	30%	20%	N	Y
Bifidobacterium_bifidum	clade_293	10%	0%	N	N

OTU	Clade	% of Spore Preps with OTU	% of Patients OTU Engrafts	Spore Former	Keystone OTU
Johnsonella_ignava	clade_298	10%	10%	N	N
Blautia_glucerasea*	**clade_309**	**100%**	**80%**	**Y**	**N**
Blautia_sp_M25*	**clade_309**	**100%**	**70%**	**Y**	**Y**
Lachnospiraceae_bacterium_6_1_63FAA*	**clade_309**	**100%**	**60%**	**Y**	**N**
Eubacterium_cellulosolvens	clade_309	10%	30%	Y	Y
Lactobacillus_fermentum	clade_313	10%	0%	N	N
Sarcina_ventriculi	clade_353	10%	10%	Y	N
Clostridium_bartlettii*	**clade_354**	**90%**	**70%**	**Y**	**N**
Clostridium_bifermentans	clade_354	70%	70%	Y	N
Clostridium_mayombei	clade_354	50%	50%	Y	N
Dorea_longicatena*	**clade_360**	**100%**	**60%**	**Y**	**Y**
Lachnospiraceae_bacterium_9_1_43BFAA	clade_360	100%	30%	Y	N
Lachnospiraceae_bacterium_2_1_58FAA*	**clade_360**	**80%**	**80%**	**Y**	**N**
Lachnospiraceae_bacterium_2_1_46FAA	clade_360	50%	50%	Y	N
Lactobacillus_perolens	clade_373	10%	0%	N	N
Bacteroides_dorei	clade_378	60%	50%	N	Y
Eubacterium_biforme	clade_385	10%	0%	Y	N
Peptoniphilus_sp_gpac077	clade_389	10%	20%	N	N
Coprococcus_catus*	**clade_393**	**100%**	**70%**	**Y**	**Y**
Eubacterium_hallii*	**clade_396**	**90%**	**60%**	**Y**	**Y**
Anaerosporobacter_mobilis	clade_396	40%	60%	Y	N
Bacteroides_pectinophilus	clade_396	10%	60%	Y	N
Lactobacillus_hominis	clade_398	10%	0%	N	N
Lactococcus_lactis	clade_401	40%	40%	N	N
Ruminococcus_champanellensis*	**clade_406**	**80%**	**50%**	**Y**	**N**

OTU	Clade	% of Spore Preps with OTU	% of Patients OTU Engrafts	Spore Former	Keystone OTU
Ruminococcus_callidus	clade_406	10%	10%	Y	N
Clostridium_clostridioforme*	**clade_408**	**100%**	**60%**	**Y**	**Y**
Eubacterium_hadrum*	**clade_408**	**100%**	**90%**	**Y**	**Y**
Clostridium_symbiosum	clade_408	30%	50%	Y	Y
Anaerostipes_caccae	clade_408	10%	50%	Y	N
Parasutterella_excrementihominis	clade_432	10%	0%	N	N
Sutterella_stercoricanis	clade_432	10%	0%	N	N
Eubacterium_rectale*	**clade_444**	**100%**	**80%**	**Y**	**Y**
Lachnobacterium_bovis*	**clade_444**	**100%**	**80%**	**Y**	**N**
Desulfovibrio_desulfuricans	clade_445	10%	0%	N	Y
Eubacterium_sp_oral_clone_JS001*	**clade_476**	**80%**	**70%**	**Y**	**N**
Faecalibacterium_prausnitzii*	**clade_478**	**100%**	**60%**	**Y**	**Y**
Subdoligranulum_variabile*	**clade_478**	**100%**	**80%**	**Y**	**Y**
Coprobacillus_sp_D7*	**clade_481**	**90%**	**60%**	**Y**	**N**
Clostridium_cocleatum	clade_481	60%	20%	Y	N
Clostridium_spiroforme	clade_481	40%	50%	Y	N
Eubacterium_ramulus*	**clade_482**	**80%**	**60%**	**Y**	**N**
Flavonifractor_plautii	clade_494	70%	60%	Y	Y
Pseudoflavonifractor_capillosus	clade_494	60%	60%	Y	Y
Ruminococcaceae_bacterium_D16	clade_494	30%	50%	Y	Y
Acetivibrio_cellulolyticus*	**clade_495**	**70%**	**80%**	**Y**	**N**
Clostridium_stercorarium	clade_495	40%	50%	Y	N
Enterococcus_durans	clade_497	10%	10%	N	N
Enterococcus_faecium	clade_497	10%	10%	N	N
Dialister_invisus	clade_506	50%	10%	N	N

OTU	Clade	% of Spore Preps with OTU	% of Patients OTU Engrafts	Spore Former	Keystone OTU
Eubacterium_limosum	clade_512	20%	0%	Y	N
Ruminococcus_flavefaciens	clade_516	60%	60%	Y	N
Eubacterium_ventriosum	clade_519	30%	60%	Y	Y
Bilophila_wadsworthia	clade_521	90%	0%	N	Y
Lachnospira_pectinoschiza	clade_522	40%	60%	Y	N
Eubacterium_eligens	clade_522	30%	50%	Y	Y
Catonella_morbi	clade_534	20%	0%	N	N
Clostridium_sporosphaeroides*	**clade_537**	**100%**	**80%**	**Y**	**N**
Ruminococcus_bromii	clade_537	60%	30%	Y	Y
Clostridium_leptum	clade_537	40%	70%	Y	Y
Clostridium_sp_YIT_12069	clade_537	40%	60%	Y	N
Clostridium_viride	clade_540	10%	10%	Y	N
Megamonas_funiformis	clade_542	50%	0%	N	N
Eubacterium_ruminantium*	**clade_543**	**80%**	**90%**	**Y**	**N**
Coprococcus_eutactus	clade_543	20%	20%	Y	N
Collinsella_aerofaciens	clade_553	50%	10%	Y	Y
Alkaliphilus_metalliredigenes	clade_554	40%	10%	Y	N
Turicibacter_sanguinis	clade_555	80%	40%	Y	N
Phascolarctobacterium_faecium	clade_556	20%	0%	N	N
Clostridiales_bacterium_oral_clone_P4PA*	**clade_558**	**80%**	**50%**	**N**	**N**
Lutispora_thermophila	clade_564	100%	0%	Y	N
Coriobacteriaceae_bacterium_JC110	clade_566	70%	0%	N	N
Eggerthella_sp_1_3_56FAA	clade_566	70%	30%	N	N
Adlercreutzia_equolifaciens	clade_566	40%	0%	N	N
Gordonibacter_pamelaeae	clade_566	30%	0%	N	Y

OTU	Clade	% of Spore Preps with OTU	% of Patients OTU Engrafts	Spore Former	Keystone OTU
Slackia_isoflavoniconvertens	clade_566	10%	0%	N	N
Eubacterium_desmolans*	**clade_572**	**90%**	**70%**	**Y**	**N**
Papillibacter_cinnamivorans*	**clade_572**	**90%**	**80%**	**Y**	**N**
Clostridium_colinum	clade_576	30%	30%	Y	N
Akkermansia_muciniphila	clade_583	60%	10%	N	Y
Clostridiales_bacterium_oral_taxon_F32	clade_584	60%	30%	N	N
Prochlorococcus_marinus	clade_592	30%	0%	N	N
Methanobrevibacter_wolinii	clade_595	30%	0%	N	N
Bacteroides_fragilis	clade_65	20%	30%	N	Y
Lactobacillus_delbrueckii	clade_72	10%	0%	N	N
Escherichia_coli	clade_92	50%	0%	N	Y
Clostridium_sp_D5	clade_96	80%	60%	Y	N
Streptococcus_thermophilus	clade_98	90%	20%	N	Y
Streptococcus_sp_CM6	clade_98	20%	10%	N	N
Streptococcus_sp_oral_clone_ASCE05	clade_98	10%	0%	N	N

Table 7.

Top 20 OTUs ranked by CES

OTU	Clade	CES	Spore Former	Keystone OTU
Eubacterium_hadrum	clade_408	4.2	Y	Y
Eubacterium_rectale	clade_444	4.2	Y	Y
Subdoligranulum_variabile	clade_478	4.2	Y	Y
Blautia_sp_M25	clade_309	4.2	Y	Y
Coprococcus_catus	clade_393	4.2	Y	Y
Lachnospiraceae_bacterium_1_4_56FAA	clade_262	4.2	Y	Y
Coprococcus_comes	clade_262	4.2	Y	Y
Blautia_glucerasea	clade_309	4.0	Y	N
Lachnobacterium_bovis	clade_444	4.0	Y	N
Clostridium_sporosphaeroides	clade_537	4.0	Y	N
Clostridiales_sp_SS3_4	clade_246	4.0	Y	N
Papillibacter_cinnamivorans	clade_572	4.0	Y	N
Clostridium_bartlettii	clade_354	4.0	Y	N
Eubacterium_desmolans	clade_572	4.0	Y	N
Clostridium_clostridioforme	clade_408	3.2	Y	Y
Dorea_longicatena	clade_360	3.2	Y	Y
Faecalibacterium_prausnitzii	clade_478	3.2	Y	Y
Eubacterium_hallii	clade_396	3.2	Y	Y
Clostridium_leptum	clade_537	3.2	Y	Y
Lachnospiraceae_bacterium_6_1_63FAA	clade_309	3.0	Y	N

Table 8.

Computationally derived Network Ecologies and associated disease indications for which bacterial composition represents a state of health. Network Ecologies are ordered based on their size defined by the number of OTUs in the network.

Network Ecology ID	Disease Indication for which Network Ecology is Health State	Num. of Clades in Network Ecology	Num. of OTUs in Network Ecology	Per cent of OTUs that are Spore Forming	Per cent of Keystone OTUs in Network Ecology	Exemplary Network clades	Exemplary Network OTUs	Exemplary Keystone OTUs
N249	CDAD	29	37	27	16.2	clade_141, clade_195, clade_256, (clade_262 or clade_262i), (clade_325 or clade_325f), clade_333, clade_344, (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_368, (clade_378 or clade_378e), (clade_38 or clade_38e or clade_38i), clade_393, (clade_444 or clade_444i), clade_476, (clade_481 or clade_481a or clade_481b or clade_481e or clade_481g or clade_481h or clade_481i), (clade_497 or clade_497e or	Akkermansia muciniphila, Alistipes indistinctus, Bacteroides coprocola, Bacteroides sp. 3_1_40A, Bacteroides sp. D2, Bacteroides xylanisolvens, Bilophila wadsworthia, Blautia hydrogenotrophica, Campylobacter upsaliensis, Capnocytophaga sp. oral clone ASCH05, Chlamydiales bacterium NS13, Chromobacterium violaceum, Clostridium cocleatum, Coprobacillus sp. D7, Coprococcus catus, Corynebacterium pseudogenitalium, Enhydrobacter aerosaccus, Enterococcus raffinosus, Eubacterium eligens, Eubacterium nodatum, Eubacterium rectale, Gardnerella vaginalis, Lachnobacterium bovis, Lachnospiraceae bacterium 1_1_57FAA,	Akkermansia muciniphila, Bacteroides xylanisolvens, Bilophila wadsworthia, Coprococcus catus, Eubacterium eligens, Eubacterium rectale

						clade_497f), clade_507, clade_515, clade_521, (clade_522 or clade_522i), clade_535, clade_556, clade_561, clade_567, clade_575, clade_583, clade_94, (clade_98 or clade_98i)	Neisseria meningitidis, Peptoniphilus sp. gpac077, Phascolarctobacterium sp. YIT 12068, Psychrobacter pulmonis, Ruminococcus sp. ID8, Staphylococcus warneri, Streptococcus dysgalactiae, Streptococcus peroris, Streptococcus pyogenes, Streptococcus sp. oral clone ASCF07, Streptococcus suis, Synergistetes bacterium oral taxon D48, Tissierella praeacuta	

N250	CDAD	30	37	24.3	16.2	clade_195, clade_256, (clade_262 or clade_262i), (clade_325 or clade_325f), clade_344, (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_368, (clade_378 or clade_378e), (clade_38 or clade_38e or clade_38i), (clade_38 or clade_38e or clade_38i)1, clade_393, (clade_420 or clade_420f), (clade_444 or clade_444i), clade_453, clade_467, clade_476, (clade_481 or clade_481a or clade_481b or clade_481e or clade_481g or clade_481h or clade_481i), (clade_497 or clade_497e or clade_497f), clade_507, clade_521, (clade_522 or clade_522i), clade_535, (clade_553 or clade_553i), clade_556, clade_558, clade_561, clade_583,	Akkermansia muciniphila, Alistipes indistinctus, Auritibacter ignavus, Bacteroides coprocola, Bacteroides sp. 3_1_40A, Bacteroides sp. D2, Bacteroides xylanisolvens, Barnesiella viscericola, Bilophila wadsworthia, Blautia hydrogenotrophica, Campylobacter upsaliensis, Capnocytophaga sp. oral taxon 338, Chromobacterium violaceum, Clostridiales bacterium oral clone P4PA, Clostridium cocleatum, Collinsella tanakaei, Coprobacillus sp. D7, Coprococcus catus, Corynebacterium pseudogenitalium, Enhydrobacter aerosaccus, Enterococcus sp. CCRI 16620, Eubacterium eligens, Eubacterium nodatum, Eubacterium rectale, Gardnerella vaginalis, Lachnospiraceae bacterium 1_1_57FAA, Neisseria meningitidis, Peptoniphilus sp. gpac077, Phascolarctobacterium sp. YIT 12068, Ruminococcus sp. ID8, Scardovia inopinata, Staphylococcus warneri, Streptococcus dysgalactiae, Streptococcus peroris, Streptococcus pyogenes, Streptococcus sp. oral clone ASCF07,	Akkermansia muciniphila, Bacteroides xylanisolvens, Bilophila wadsworthia, Coprococcus catus, Eubacterium eligens, Eubacterium rectale

						clade_94, (clade_98 or clade_98i)	Streptococcus suis	

N251	CDAD	29	34	20.6	14.7	clade_141, clade_181, clade_195, clade_256, (clade_262 or clade_262i), clade_293, clade_333, clade_344, (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_368, (clade_378 or clade_378e), (clade_38 or clade_38e or clade_38i), clade_393, (clade_420 or clade_420f), (clade_444 or clade_444i), clade_476, clade_507, clade_515, clade_521, (clade_522 or clade_522i), clade_535, clade_551, (clade_553 or clade_553i), clade_556, clade_558, clade_583, clade_597, (clade_98 or clade_98i)	Acinetobacter johnsonii, Akkermansia muciniphila, Bacteroides coprocola, Bacteroides sp. 3_1_40A, Bacteroides sp. D2, Bifidobacterium bifidum, Bilophila wadsworthia, Blautia hydrogenotrophica, Campylobacter upsaliensis, Capnocytophaga sp. oral clone ASCH05, Chromobacterium violaceum, Clostridiales bacterium oral clone P4PA, Collinsella tanakaei, Coprococcus catus, Corynebacterium pseudogenitalium, Enhydrobacter aerosaccus, Eubacterium eligens, Eubacterium nodatum, Eubacterium rectale, Gardnerella vaginalis, Halorubrum lipolyticum, Lachnospiraceae bacterium 1_1_57FAA, Mycoplasmataceae genomosp P1 oral clone, Peptoniphilus sp. gpac077, Phascolarctobacterium sp. YIT 12068, Psychrobacter pulmonis, Ruminococcus sp. ID8, Streptococcus dysgalactiae, Streptococcus peroris, Streptococcus pyogenes, Streptococcus sp. oral clone ASCF07, Streptococcus suis, Tannerella sp. 6_1_58FAA_CT1, Tissierella praeacuta	Akkermansia muciniphila, Bilophila wadsworthia, Coprococcus catus, Eubacterium eligens, Eubacterium rectale

N252	CDAD	25	32	28.1	18.8	clade_181, clade_195, clade_256, (clade_262 or clade_262i), (clade_325 or clade_325f), clade_344, (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_368, (clade_378 or clade_378e), (clade_38 or clade_38e or clade_38i), clade_393, (clade_444 or clade_444i), clade_476, (clade_481 or clade_481a or clade_481b or clade_481e or clade_481g or clade_481h or clade_481i), clade_507, clade_515, clade_521, (clade_522 or clade_522i), clade_535, clade_556, clade_561, clade_583, clade_94, (clade_98 or clade_98i)	Acinetobacter johnsonii, Akkermansia muciniphila, Alistipes indistinctus, Bacteroides coprocola, Bacteroides sp. 3_1_40A, Bacteroides sp. D2, Bacteroides xylanisolvens, Bilophila wadsworthia, Blautia hydrogenotrophica, Campylobacter upsaliensis, Chromobacterium violaceum, Clostridium cocleatum, Coprobacillus sp. D7, Coprococcus catus, Corynebacterium pseudogenitalium, Enhydrobacter aerosaccus, Eubacterium eligens, Eubacterium nodatum, Eubacterium rectale, Gardnerella vaginalis, Lachnospiraceae bacterium 1_1_57FAA, Neisseria meningitidis, Peptoniphilus sp. gpac077, Phascolarctobacterium sp. YIT 12068, Ruminococcus sp. ID8, Staphylococcus warneri, Streptococcus dysgalactiae, Streptococcus peroris, Streptococcus pyogenes, Streptococcus sp. oral clone ASCF07, Streptococcus suis, Tissierella praeacuta	Akkermansia muciniphila, Bacteroides xylanisolvens, Bilophila wadsworthia, Coprococcus catus, Eubacterium eligens, Eubacterium rectale

N253	CDAD	24	31	29	19.4	clade_195, clade_256, (clade_262 or clade_262i), (clade_325 or clade_325f), clade_344, (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_368, (clade_378 or clade_378e), (clade_38 or clade_38e or clade_38i), clade_393, (clade_444 or clade_444i), clade_476, (clade_481 or clade_481a or clade_481b or clade_481e or clade_481g or clade_481h or clade_481i), clade_507, clade_515, clade_521, (clade_522 or clade_522i), clade_535, clade_556, clade_561, clade_583, clade_94, (clade_98 or clade_98i)	Akkermansia muciniphila, Alistipes indistinctus, Bacteroides coprocola, Bacteroides sp. 3_1_40A, Bacteroides sp. D2, Bacteroides xylanisolvens, Bilophila wadsworthia, Blautia hydrogenotrophica, Campylobacter upsaliensis, Chromobacterium violaceum, Clostridium cocleatum, Coprobacillus sp. D7, Coprococcus catus, Corynebacterium pseudogenitalium, Enhydrobacter aerosaccus, Eubacterium eligens, Eubacterium nodatum, Eubacterium rectale, Gardnerella vaginalis, Lachnospiraceae bacterium 1_1_57FAA, Neisseria meningitidis, Peptoniphilus sp. gpac077, Phascolarctobacterium sp. YIT 12068, Ruminococcus sp. ID8, Staphylococcus warneri, Streptococcus dysgalactiae, Streptococcus peroris, Streptococcus pyogenes, Streptococcus sp. oral clone ASCF07, Streptococcus suis, Tissierella praeacuta	Akkermansia muciniphila, Bacteroides xylanisolvens, Bilophila wadsworthia, Coprococcus catus, Eubacterium eligens, Eubacterium rectale

N254	CDAD	24	30	23.3	20	clade_141, clade_181, clade_195, (clade_262 or clade_262i), clade_293, clade_344, (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_368, (clade_378 or clade_378e), (clade_38 or clade_38c or clade_38i), clade_393, (clade_420 or clade_420f), (clade_444 or clade_444i), clade_476, clade_507, clade_521, (clade_522 or clade_522i), clade_535, clade_556, clade_567, clade_575, clade_583, (clade_98 or clade_98i)	Acinetobacter johnsonii, Akkermansia muciniphila, Bacteroides coprocola, Bacteroides sp. 3_1_40A, Bacteroides sp. D2, Bacteroides xylanisolvens, Barnesiella viscericola, Bifidobacterium bifidum, Bilophila wadsworthia, Blautia hydrogenotrophica, Campylobacter upsaliensis, Chlamydiales bacterium NS13, Chromobacterium violaceum, Coprococcus catus, Corynebacterium pseudogenitalium, Eubacterium eligens, Eubacterium nodatum, Eubacterium rectale, Gardnerella vaginalis, Lachnospiraceae bacterium 1_1_57FAA, Peptoniphilus sp. gpac077, Phascolarctobacterium sp. YIT 12068, Psychrobacter pulmonis, Ruminococcus sp. ID8, Streptococcus dysgalactiae, Streptococcus peroris, Streptococcus pyogenes, Streptococcus sp. oral clone ASCF07, Streptococcus suis, Synergistetes bacterium oral taxon D48	Akkermansia muciniphila, Bacteroides xylanisolvens, Bilophila wadsworthia, Coprococcus catus, Eubacterium eligens, Eubacterium rectale

N255	CDAD	23	29	34.5	17.2	clade_141, clade_181, clade_195, (clade_262 or clade_262i), clade_293, clade_344, (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_368, (clade_378 or clade_378e), (clade_38 or clade_38e or clade_38i), clade_393, (clade_444 or clade_444i), clade_476, (clade_481 or clade_481a or clade_481b or clade_481e or clade_481g or clade_481h or clade_481i), clade_507, (clade_516 or clade_516c or clade_516g or clade_516h), clade_521, (clade_522 or clade_522i), clade_535, clade_556, clade_583, (clade_98 or clade_98i)	Acinetobacter johnsonii, Akkermansia muciniphila, Bacteroides coprocola, Bacteroides sp. 3_1_40A, Bacteroides sp. D2, Bifidobacterium bifidum, Bilophila wadsworthia, Blautia hydrogenotrophica, Campylobacter upsaliensis, Chromobacterium violaceum, Coprobacillus sp. D7, Coprococcus catus, Corynebacterium pseudogenitalium, Eubacterium eligens, Eubacterium nodatum, Eubacterium rectale, Gardnerella vaginalis, Lachnobacterium bovis, Lachnospiraceae bacterium 1_1_57FAA, Peptoniphilus sp. gpac077, Phascolarctobacterium sp. YIT 12068, Psychrobacter pulmonis, Ruminococcus albus, Ruminococcus sp. ID8, Streptococcus dysgalactiae, Streptococcus peroris, Streptococcus pyogenes, Streptococcus sp. oral clone ASCF07, Streptococcus suis	Akkermansia muciniphila, Bilophila wadsworthia, Coprococcus catus, Eubacterium eligens, Eubacterium rectale

N256	CDAD	19	26	76.9	92.3	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_38 or clade_38e or clade_38i), clade_393, clade_396, (clade_444 or clade_444i), clade_445, clade_466, (clade_478 or clade_478i), clade_485, clade_494, clade_500, (clade_516 or clade_516c or clade_516g or clade_516h), clade_519, clade_521, (clade_522 or clade_522i), clade_537, clade_538	Alistipes putredinis, Alistipes shahii, Bacteroides pectinophilus, Bacteroides xylanisolvens, Bilophila wadsworthia, Coprococcus catus, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Eubacterium siraeum, Eubacterium ventriosum, Faecalibacterium prausnitzii, Holdemania filiformis, Odoribacter splanchnicus, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus albus, Ruminococcus bromii, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Bacteroides xylanisolvens, Bilophila wadsworthia, Coprococcus catus, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Eubacterium siraeum, Eubacterium ventriosum, Faecalibacterium prausnitzii, Holdemania filiformis, Odoribacter splanchnicus, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus bromii, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile

N257	CDAD	21	26	26.9	19.2	clade_141, clade_181, clade_195, (clade_262 or clade_262i), clade_293, clade_344, (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_368, (clade_378 or clade_378e), (clade_38 or clade_38e or clade_38i), clade_393, (clade_444 or clade_444i), clade_476, clade_507, clade_521, (clade_522 or clade_522i), clade_535, clade_556, clade_583, (clade_98 or clade_98i)	Acinetobacter johnsonii, Akkermansia muciniphila, Bacteroides coprocola, Bacteroides sp. 3_1_40A, Bacteroides sp. D2, Bifidobacterium bifidum, Bilophila wadsworthia, Blautia hydrogenotrophica, Campylobacter upsaliensis, Chromobacterium violaceum, Coprococcus catus, Corynebacterium pseudogenitalium, Eubacterium eligens, Eubacterium nodatum, Eubacterium rectale, Gardnerella vaginalis, Lachnospiraceae bacterium 1_1_57FAA, Peptoniphilus sp. gpac077, Phascolarctobacterium sp. YIT 12068, Psychrobacter pulmonis, Ruminococcus sp. ID8, Streptococcus dysgalactiae, Streptococcus peroris, Streptococcus pyogenes, Streptococcus sp. oral clone ASCF07, Streptococcus suis	Akkermansia muciniphila, Bilophila wadsworthia, Coprococcus catus, Eubacterium eligens, Eubacterium rectale

N258	CDAD	18	24	75	91.7	(clade_262 or clade_262i), clade_286, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_393, clade_396, (clade_444 or clade_444i), clade_445, clade_466, clade_474, (clade_478 or clade_478i), clade_494, clade_500, clade_519, (clade_522 or clade_522i), clade_537, clade_538, (clade_553 or clade_553i)	Alistipes putredinis, Alistipes shahii, Collinsella aerofaciens, Coprococcus catus, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Eubacterium siraeum, Eubacterium ventriosum, Faecalibacterium prausnitzii, Mitsuokella multacida, Odoribacter splanchnicus, Parabacteroides merdae, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus bromii, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Coprococcus catus, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Eubacterium siraeum, Eubacterium ventriosum, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Parabacteroides merdae, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus bromii, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile

N259	CDAD	17	24	75	91.7	(clade_262 or clade_262i), clade_286, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_378 or clade_378e), clade_396, (clade_444 or clade_444i), clade_466, (clade_478 or clade_478i), clade_485, clade_494, clade_500, (clade_516 or clade_516c or clade_516g or clade_516h), clade_519, (clade_522 or clade_522i), clade_537, clade_556	Acidaminococcus fermentans, Alistipes putredinis, Alistipes shahii, Anaerotruncus colihominis, Bacteroides dorei, Clostridium leptum, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Holdemania filiformis, Odoribacter splanchnicus, Parabacteroides merdae, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus lactaris, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Bacteroides dorei, Clostridium leptum, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Holdemania filiformis, Odoribacter splanchnicus, Parabacteroides merdae, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus lactaris, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile

N260	CDAD	15	22	72.7	95.5	(clade_172 or clade_172i), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_393, clade_396, (clade_444 or clade_444i), clade_445, clade_466, (clade_478 or clade_478i), clade_485, clade_494, clade_500, clade_519, clade_537	Alistipes putredinis, Alistipes shahii, Bifidobacterium catenulatum, Bifidobacterium longum, Clostridium leptum, Coprococcus catus, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Holdemania filiformis, Odoribacter splanchnicus, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Bifidobacterium longum, Clostridium leptum, Coprococcus catus, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Holdemania filiformis, Odoribacter splanchnicus, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile
N261	CDAD	14	21	81	90.5	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_393, clade_396, (clade_444 or clade_444i), clade_449, clade_466, (clade_478 or clade_478i), clade_485,	Alistipes putredinis, Alistipes shahii, Collinsella aerofaciens, Coprococcus catus, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Holdemania filiformis, Lactobacillus ruminis, Odoribacter splanchnicus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus lactaris, Ruminococcus obeum, Ruminococcus torques,	Alistipes putredinis, Alistipes shahii, Coprococcus catus, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Holdemania filiformis, Odoribacter splanchnicus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus lactaris, Ruminococcus obeum, Ruminococcus torques,

						clade_500, clade_519, (clade_522 or clade_522i), (clade_553 or clade_553i)	Subdoligranulum variabile	Subdoligranulum variabile
N262	CDAD	13	21	71.4	95.2	(clade_172 or clade_172i), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), clade_466, (clade_478 or clade_478i), clade_485, clade_494, clade_500, (clade_522 or clade_522i), (clade_98 or clade_98i)	Alistipes putredinis, Alistipes shahii, Bifidobacterium dentium, Bifidobacterium longum, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Odoribacter splanchnicus, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus lactaris, Ruminococcus obeum, Ruminococcus torques, Streptococcus parasanguinis, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Bifidobacterium longum, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Odoribacter splanchnicus, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus lactaris, Ruminococcus obeum, Ruminococcus torques, Streptococcus parasanguinis, Subdoligranulum variabile

N263	CDAD,T2D	13	21	76.2	90.5	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_38 or clade_38e or clade_38i), (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i), clade_485, clade_494, clade_500, (clade_516 or clade_516c or clade_516g or clade_516h), (clade_522 or clade_522i), clade_537	Alistipes putredinis, Alistipes shahii, Anaerotruncus colihominis, Bacteroides xylanisolvens, Clostridium leptum, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Marvinbryantia formatexigens, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus lactaris, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Bacteroides xylanisolvens, Clostridium leptum, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus lactaris, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile
N264	CDAD,T2D	14	21	76.2	95.2	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_393, clade_396, (clade_444 or clade_444i), clade_445, clade_466,	Alistipes putredinis, Alistipes shahii, Clostridium leptum, Coprococcus catus, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Marvinbryantia formatexigens, Odoribacter splanchnicus,	Alistipes putredinis, Alistipes shahii, Clostridium leptum, Coprococcus catus, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Odoribacter splanchnicus, Pseudoflavonifractor capillosus, Roseburia

						(clade_478 or clade_478i), clade_485, clade_494, clade_500, (clade_522 or clade_522i), clade_537	Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile
N265	CDAD,T2D	15	21	71.4	90.5	(clade_262 or clade_262i), clade_286, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_393, clade_396, (clade_444 or clade_444i), clade_445, clade_466, clade_474, (clade_478 or clade_478i), clade_494, clade_500, (clade_522 or clade_522i), (clade_553 or clade_553i)	Alistipes putredinis, Alistipes shahii, Collinsella aerofaciens, Coprococcus catus, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Mitsuokella multacida, Odoribacter splanchnicus, Parabacteroides merdae, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Coprococcus catus, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Parabacteroides merdae, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile

N266	CDAD,T2D	13	21	76.2	90.5	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_38 or clade_38e or clade_38i), (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i), clade_485, clade_494, clade_500, (clade_516 or clade_516c or clade_516g or clade_516h), (clade_522 or clade_522i), clade_537	Alistipes putredinis, Alistipes shahii, Anaerotruncus colihominis, Bacteroides xylanisolvens, Clostridium leptum, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Marvinbryantia formatexigens, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus lactaris, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Bacteroides xylanisolvens, Clostridium leptum, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus lactaris, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile
N267	CDAD,T2D	14	21	81	95.2	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_393, clade_396, (clade_444 or clade_444i), clade_445, clade_466,	Alistipes putredinis, Alistipes shahii, Bacteroides pectinophilus, Coprococcus catus, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Odoribacter splanchnicus, Pseudoflavonifractor capillosus, Roseburia	Alistipes putredinis, Alistipes shahii, Coprococcus catus, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Odoribacter splanchnicus, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia

						(clade_478 or clade_478i), clade_485, clade_494, clade_500, (clade_522 or clade_522i), clade_537	intestinalis, Roseburia inulinivorans, Ruminococcus bromii, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	inulinivorans, Ruminococcus bromii, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile
N268	CDAD,T2D	14	21	76.2	95.2	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_393, clade_396, (clade_444 or clade_444i), clade_445, clade_466, (clade_478 or clade_478i), clade_485, clade_494, clade_500, (clade_522 or clade_522i), clade_537	Alistipes putredinis, Alistipes shahii, Clostridium leptum, Coprococcus catus, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Marvinbryantia formatexigens, Odoribacter splanchnicus, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Clostridium leptum, Coprococcus catus, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Odoribacter splanchnicus, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile

N269	CDAD,T2D	15	21	71.4	90.5	(clade_262 or clade_262i), clade_286, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_393, clade_396, (clade_444 or clade_444i), clade_445, clade_466, clade_474, (clade_478 or clade_478i), clade_494, clade_500, (clade_522 or clade_522i), (clade_553 or clade_553i)	Alistipes putredinis, Alistipes shahii, Collinsella aerofaciens, Coprococcus catus, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Mitsuokella multacida, Odoribacter splanchnicus, Parabacteroides merdae, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Coprococcus catus, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Parabacteroides merdae, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile
N270	CDAD,T2D	14	21	81	95.2	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_393, clade_396, (clade_444 or clade_444i), clade_445, clade_466, (clade_478 or clade_478i),	Alistipes putredinis, Alistipes shahii, Bacteroides pectinophilus, Coprococcus catus, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Odoribacter splanchnicus, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans,	Alistipes putredinis, Alistipes shahii, Coprococcus catus, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Odoribacter splanchnicus, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus bromii,

						clade_485, clade_494, clade_500, (clade_522 or clade_522i), clade_537	Ruminococcus bromii, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile
N271	CDAD	11	20	70	90	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), clade_466, (clade_478 or clade_478i), clade_485, clade_494, clade_500, (clade_98 or clade_98i)	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Odoribacter splanchnicus, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus lactaris, Ruminococcus obeum, Ruminococcus torques, Streptococcus parasanguinis, Streptococcus salivarius, Streptococcus vestibularis, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Odoribacter splanchnicus, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus lactaris, Ruminococcus obeum, Ruminococcus torques, Streptococcus parasanguinis, Subdoligranulum variabile

N272	CDAD	14	20	70	95	(clade_262 or clade_262i), clade_286, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_378 or clade_378e), clade_393, clade_396, (clade_444 or clade_444i), clade_445, clade_466, (clade_478 or clade_478i), clade_494, clade_500, clade_538	Alistipes putredinis, Alistipes shahii, Bacteroides coprophilus, Coprococcus catus, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Eubacterium siraeum, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Parabacteroides merdae, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Coprococcus catus, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Eubacterium siraeum, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Parabacteroides merdae, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile
N273	CDAD,T2D	13	20	65	95	(clade_262 or clade_262i), clade_286, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_38 or clade_38e or clade_38i), (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i), clade_500,	Alistipes putredinis, Alistipes shahii, Bacteroides ovatus, Bacteroides xylanisolvens, Clostridium leptum, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Methanobrevibacter smithii, Parabacteroides merdae, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum,	Alistipes putredinis, Alistipes shahii, Bacteroides ovatus, Bacteroides xylanisolvens, Clostridium leptum, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Parabacteroides merdae, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques,

						clade_519, (clade_522 or clade_522i), clade_537, clade_588	Ruminococcus torques, Subdoligranulum variabile	Subdoligranulum variabile
N274	CDAD,T2D	13	20	65	95	(clade_262 or clade_262i), clade_286, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_38 or clade_38e or clade_38i), (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i), clade_500, clade_519, (clade_522 or clade_522i), clade_537, clade_588	Alistipes putredinis, Alistipes shahii, Bacteroides ovatus, Bacteroides xylanisolvens, Clostridium leptum, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Methanobrevibacter smithii, Parabacteroides merdae, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Bacteroides ovatus, Bacteroides xylanisolvens, Clostridium leptum, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Parabacteroides merdae, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile

N275	CDAD	13	19	73.7	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_357, (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), clade_445, clade_466, (clade_478 or clade_478i), clade_485, clade_494, clade_500, clade_519	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Holdemania filiformis, Odoribacter splanchnicus, Oxalobacter formigenes, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Holdemania filiformis, Odoribacter splanchnicus, Oxalobacter formigenes, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile
N276	CDAD	13	19	78.9	94.7	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), clade_445, clade_466, (clade_478 or clade_478i), clade_485, clade_494, clade_500, (clade_516 or	Alistipes putredinis, Alistipes shahii, Clostridium leptum, Clostridium methylpentosum, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Odoribacter splanchnicus, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus lactaris, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Clostridium leptum, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Odoribacter splanchnicus, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus lactaris, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile

						clade_516c or clade_516g or clade_516h), clade_537		
N277	CDAD,T2D	13	19	73.7	94.7	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_378 or clade_378e), clade_393, clade_396, (clade_444 or clade_444i), clade_445, clade_466, (clade_478 or clade_478i), clade_494, clade_500, clade_538	Alistipes putredinis, Alistipes shahii, Bacteroides coprophilus, Coprococcus catus, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Eubacterium siraeum, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Coprococcus catus, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Eubacterium siraeum, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile

N278	CDAD,T2D	13	19	73.7	94.7	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_378 or clade_378e), clade_393, clade_396, (clade_444 or clade_444i), clade_445, clade_466, (clade_478 or clade_478i), clade_494, clade_500, clade_538	Alistipes putredinis, Alistipes shahii, Bacteroides coprophilus, Coprococcus catus, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Eubacterium siraeum, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Coprococcus catus, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Eubacterium siraeum, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile
N279	CDAD	12	18	77.8	94.4	(clade_172 or clade_172i), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_38 or clade_38e or clade_38i)8, clade_396, (clade_444 or clade_444i), clade_466, (clade_478 or clade_478i),	Alistipes putredinis, Alistipes shahii, Bifidobacterium longum, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Odoribacter splanchnicus, Pseudoflavonifractor capillosus, Roseburia inulinivorans, Ruminococcus lactaris, Ruminococcus obeum, Ruminococcus torques, Solobacterium moorei, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Bifidobacterium longum, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Odoribacter splanchnicus, Pseudoflavonifractor capillosus, Roseburia inulinivorans, Ruminococcus lactaris, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile

						clade_485, clade_494, clade_500		
N280	CDAD	11	18	77.8	94.4	(clade_262 or clade_262i), clade_271, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i), clade_485, clade_494, clade_500	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Rothia mucilaginosa, Ruminococcus lactaris, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus lactaris, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile

N281	CDAD	11	18	72.2	94.4	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), clade_445, clade_466, (clade_478 or clade_478i), clade_500, clade_538, (clade_553 or clade_553i)	Alistipes putredinis, Alistipes shahii, Collinsella aerofaciens, Coprococcus comes, Desulfovibrio desulfuricans, Desulfovibrio piger, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Eubacterium siraeum, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Desulfovibrio desulfuricans, Desulfovibrio piger, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Eubacterium siraeum, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile
N282	CDAD	11	18	77.8	94.4	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, clade_401, (clade_444 or clade_444i), clade_466, (clade_478 or clade_478i), clade_485, clade_494, clade_500	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Lactococcus lactis, Odoribacter splanchnicus, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus lactaris, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Odoribacter splanchnicus, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus lactaris, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile

N283	CDAD	11	18	83.3	94.4	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i), clade_485, clade_494, clade_500, (clade_522 or clade_522i)	Alistipes putredinis, Alistipes shahii, Blautia hansenii, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus lactaris, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus lactaris, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile
N284	CDAD,T2D	12	18	83.3	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_393, clade_396, (clade_444 or clade_444i), clade_466, (clade_478 or clade_478i), clade_500, clade_519, clade_538, clade_543	Alistipes putredinis, Alistipes shahii, Butyrivibrio crossotus, Coprococcus catus, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Eubacterium siraeum, Eubacterium ventriosum, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Butyrivibrio crossotus, Coprococcus catus, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Eubacterium siraeum, Eubacterium ventriosum, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile

N285	CDAD,T2D	12	18	83.3	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_393, clade_396, (clade_444 or clade_444i), clade_466, (clade_478 or clade_478i), clade_500, clade_519, clade_538, clade_543	Alistipes putredinis, Alistipes shahii, Butyrivibrio crossotus, Coprococcus catus, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Eubacterium siraeum, Eubacterium ventriosum, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Butyrivibrio crossotus, Coprococcus catus, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Eubacterium siraeum, Eubacterium ventriosum, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile
N286	CDAD	13	18	72.2	94.4	clade_129, (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_38 or clade_38e or clade_38i), clade_396, (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i), clade_485, clade_494, clade_500,	Alistipes putredinis, Alistipes shahii, Bacteroides xylanisolvens, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Holdemania filiformis, Prevotella buccalis, Pseudoflavonifractor capillosus, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Bacteroides xylanisolvens, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile

						clade_519		
N287	CDAD	11	17	76.5	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), clade_445, clade_466, (clade_478 or clade_478i), clade_485, clade_494, clade_500	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Odoribacter splanchnicus, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Odoribacter splanchnicus, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile

N288	CDAD	11	17	76.5	94.1	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), clade_466, (clade_478 or clade_478i), clade_485, clade_494, clade_500, (clade_98 or clade_98i)	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Odoribacter splanchnicus, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Streptococcus mitis, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Odoribacter splanchnicus, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile
N289	CDAD	11	17	76.5	100	(clade_262 or clade_262i), clade_286, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), clade_466, (clade_478 or clade_478i), clade_485, clade_494, clade_500	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Odoribacter splanchnicus, Parabacteroides johnsonii, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Odoribacter splanchnicus, Parabacteroides johnsonii, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile

N290	CDAD,T2D	11	17	88.2	94.1	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_393, clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_494, clade_500, (clade_522 or clade_522i), clade_543	Alistipes putredinis, Alistipes shahii, Coprococcus catus, Coprococcus comes, Coprococcus eutactus, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Coprococcus catus, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile
N291	CDAD	11	17	76.5	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), clade_466, (clade_478 or clade_478i), clade_485, clade_494, clade_500, clade_567	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Odoribacter splanchnicus, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile, Victivallis vadensis	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Odoribacter splanchnicus, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile, Victivallis vadensis

N292	CDAD	12	17	82.4	88.2	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i), clade_485, clade_494, clade_500, (clade_516 or clade_516c or clade_516g or clade_516h)	Alistipes putredinis, Alistipes shahii, Anaerotruncus colihominis, Clostridium symbiosum, Desulfovibrio desulfuricans, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus lactaris, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Desulfovibrio desulfuricans, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus lactaris, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile
N293	CDAD,T2D	12	17	70.6	94.1	clade_129, (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_38 or clade_38e or clade_38i), clade_396,	Alistipes putredinis, Alistipes shahii, Bacteroides xylanisolvens, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Prevotella buccalis, Pseudoflavonifractor capillosus, Roseburia inulinivorans,	Alistipes putredinis, Alistipes shahii, Bacteroides xylanisolvens, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Roseburia inulinivorans, Ruminococcus obeum,

						(clade_444 or clade_444i), clade_445, (clade_478 or clade_478i), clade_485, clade_494, clade_500	Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Ruminococcus torques, Subdoligranulum variabile
N294	CDAD,T2D	12	17	70.6	94.1	clade_129, (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_38 or clade_38e or clade_38i), clade_396, (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i), clade_485, clade_494, clade_500	Alistipes putredinis, Alistipes shahii, Bacteroides xylanisolvens, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Prevotella buccalis, Pseudoflavonifractor capillosus, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Bacteroides xylanisolvens, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile

N295	CDAD,T2D	10	17	70.6	94.1	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), clade_445, clade_466, (clade_478 or clade_478i), clade_500, (clade_553 or clade_553i)	Alistipes putredinis, Alistipes shahii, Collinsella aerofaciens, Coprococcus comes, Desulfovibrio desulfuricans, Desulfovibrio piger, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Desulfovibrio desulfuricans, Desulfovibrio piger, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile
N296	CDAD,T2D	11	17	70.6	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_357, (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), clade_445, clade_466, (clade_478 or clade_478i), clade_494, clade_500	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Oxalobacter formigenes, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Oxalobacter formigenes, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile

N297	CDAD,T2D	11	17	88.2	94.1	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_393, clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_494, clade_500, (clade_522 or clade_522i), clade_543	Alistipes putredinis, Alistipes shahii, Coprococcus catus, Coprococcus comes, Coprococcus eutactus, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Coprococcus catus, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile
N298	CDAD,T2D	10	17	70.6	94.1	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), clade_445, clade_466, (clade_478 or clade_478i), clade_500, (clade_553 or clade_553i)	Alistipes putredinis, Alistipes shahii, Collinsella aerofaciens, Coprococcus comes, Desulfovibrio desulfuricans, Desulfovibrio piger, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Desulfovibrio desulfuricans, Desulfovibrio piger, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile

N299	CDAD,T2D	11	17	70.6	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_357, (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), clade_445, clade_466, (clade_478 or clade_478i), clade_494, clade_500	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Oxalobacter formigenes, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Oxalobacter formigenes, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile
N300	CDAD	11	16	81.3	93.8	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i), clade_485, clade_494, clade_500, (clade_566 or clade_566f)	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Eggerthella lenta, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Roseburia inulinivorans, Ruminococcus lactaris, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Roseburia inulinivorans, Ruminococcus lactaris, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile

N301	CDAD	10	16	75	93.8	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, clade_432, (clade_444 or clade_444i), clade_466, (clade_478 or clade_478i), clade_485, clade_500	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Odoribacter splanchnicus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus lactaris, Ruminococcus obeum, Ruminococcus torques, Sutterella wadsworthensis	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Odoribacter splanchnicus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus lactaris, Ruminococcus obeum, Ruminococcus torques
N302	CDAD	10	16	81.3	93.8	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_393, clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500, clade_519, clade_588	Alistipes putredinis, Alistipes shahii, Coprococcus catus, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Methanobrevibacter smithii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Coprococcus catus, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile

N303	CDAD	11	16	68.8	93.8	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_378 or clade_378e), clade_396, (clade_444 or clade_444i), clade_445, clade_466, (clade_478 or clade_478i), clade_485, clade_500	Alistipes putredinis, Alistipes shahii, Bacteroides plebeius, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Odoribacter splanchnicus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Odoribacter splanchnicus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques
N304	CDAD,T2D	11	16	81.3	100	clade_171, (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_485, clade_494, clade_500, (clade_522 or clade_522i)	Alistipes putredinis, Alistipes shahii, Bacteroides intestinalis, Coprococcus comes, Dorea formicigenerans, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Bacteroides intestinalis, Coprococcus comes, Dorea formicigenerans, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile

N305	CDAD,T2D	10	16	81.3	93.8	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_38 or clade_38e or clade_38i), clade_396, (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i), (clade_522 or clade_522i), clade_543	Bacteroides ovatus, Bacteroides xylanisolvens, Coprococcus comes, Coprococcus eutactus, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Bacteroides ovatus, Bacteroides xylanisolvens, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile
N306	CDAD	12	16	100	31.3	clade_252, (clade_260 or clade_260c or clade_260g or clade_260h), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_351 or clade_351e), (clade_38 or clade_38e or clade_38i)4, (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_444 or	Blautia producta, Clostridium hylemonae, Clostridium innocuum, Clostridium orbiscindens, Clostridium symbiosum, Clostridium tertium, Collinsella aerofaciens, Coprobacillus sp. D7, Coprococcus comes, Eubacterium rectale, Eubacterium sp. WAL 14571, Faecalibacterium prausnitzii, Lachnospiraceae bacterium 5_1_57FAA, Roseburia faecalis, Ruminococcus obeum, Ruminococcus torques	Coprococcus comes, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques

						clade_444i), (clade_478 or clade_478i), (clade_481 or clade_481a or clade_481b or clade_481e or clade_481g or clade_481h or clade_481i), clade_494, (clade_553 or clade_553i)		
N307	CDAD	13	16	75	68.8	clade_170, (clade_260 or clade_260c or clade_260g or clade_260h), (clade_262 or clade_262i), clade_286, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_444 or clade_444i), clade_485,	Alistipes shahii, Bacteroides caccae, Bacteroides stercoris, Blautia producta, Clostridium hathewayi, Clostridium symbiosum, Collinsella aerofaciens, Coprococcus comes, Dorea formicigenerans, Eubacterium rectale, Holdemania filiformis, Lachnospiraceae bacterium 5_1_57FAA, Parabacteroides merdae, Ruminococcus bromii, Ruminococcus obeum, Ruminococcus torques	Alistipes shahii, Bacteroides caccae, Bacteroides stercoris, Coprococcus comes, Dorea formicigenerans, Eubacterium rectale, Holdemania filiformis, Parabacteroides merdae, Ruminococcus bromii, Ruminococcus obeum, Ruminococcus torques

						clade_500, clade_537, (clade_553 or clade_553i), clade_85		
N308	CDAD,T2D	10	16	81.3	93.8	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_38 or clade_38e or clade_38i), clade_396, (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i), (clade_522 or clade_522i), clade_543	Bacteroides ovatus, Bacteroides xylanisolvens, Coprococcus comes, Coprococcus eutactus, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Bacteroides ovatus, Bacteroides xylanisolvens, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile

N309	CDAD,T2D	11	16	81.3	100	clade_171, (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_485, clade_494, clade_500, (clade_522 or clade_522i)	Alistipes putredinis, Alistipes shahii, Bacteroides intestinalis, Coprococcus comes, Dorea formicigenerans, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Bacteroides intestinalis, Coprococcus comes, Dorea formicigenerans, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile
N310	CDAD,T2D	10	16	75	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), clade_466, (clade_478 or clade_478i), clade_494, clade_500, clade_567	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile, Victivallis vadensis	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile, Victivallis vadensis

N311	CDAD,T2D	10	16	75	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), clade_466, (clade_478 or clade_478i), clade_494, clade_500, clade_567	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile, Victivallis vadensis	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile, Victivallis vadensis
N312	CDAD,T2D	10	15	80	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), clade_466, clade_469, (clade_478 or clade_478i), clade_500, (clade_522 or clade_522i)	Alistipes putredinis, Alistipes shahii, Catenibacterium mitsuokai, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Catenibacterium mitsuokai, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques

N313	CDAD,T2D	11	15	80	86.7	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_494, clade_500, (clade_522 or clade_522i), (clade_553 or clade_553i), clade_62	Alistipes putredinis, Alistipes shahii, Collinsella aerofaciens, Dorea formicigenerans, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Prevotella buccae, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile
N314	CDAD	10	15	73.3	93.3	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_335 or clade_335i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), clade_466, (clade_478 or clade_478i), clade_485, clade_500	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Odoribacter splanchnicus, Parabacteroides distasonis, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Odoribacter splanchnicus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques

N315	CDAD	9	15	80	93.3	(clade_172 or clade_172i), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_494, clade_500	Alistipes putredinis, Alistipes shahii, Bifidobacterium pseudocatenulatum, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile
N316	CDAD	10	15	80	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i), clade_485, clade_494, clade_500	Alistipes putredinis, Alistipes shahii, Clostridium nexile, Desulfovibrio desulfuricans, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Clostridium nexile, Desulfovibrio desulfuricans, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile

N317	CDAD,T2D	11	15	80	93.3	clade_168, (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_38 or clade_38e or clade_38i), (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i), clade_494, clade_519, (clade_522 or clade_522i)	Bacteroides xylanisolvens, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Eubacterium eligens, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Prevotella copri, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Bacteroides xylanisolvens, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Eubacterium eligens, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile
N318	CDAD,T2D	11	15	66.7	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_357, (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_38 or clade_38e or clade_38i), (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i), clade_500, clade_519,	Alistipes putredinis, Alistipes shahii, Bacteroides xylanisolvens, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Oxalobacter formigenes, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Bacteroides xylanisolvens, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Oxalobacter formigenes, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile

						(clade_522 or clade_522i)		
N319	CDAD,T2D	11	15	80	86.7	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_494, clade_500, (clade_522 or clade_522i), (clade_553 or clade_553i), clade_62	Alistipes putredinis, Alistipes shahii, Collinsella aerofaciens, Dorea formicigenerans, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Prevotella buccae, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile

N320	CDAD,T2D	11	15	80	93.3	clade_168, (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_38 or clade_38e or clade_38i), (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i), clade_494, clade_519, (clade_522 or clade_522i)	Bacteroides xylanisolvens, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Eubacterium eligens, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Prevotella copri, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Bacteroides xylanisolvens, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Eubacterium eligens, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile
N321	CDAD,T2D	10	15	80	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), clade_466, clade_469, (clade_478 or clade_478i), clade_500, (clade_522 or clade_522i)	Alistipes putredinis, Alistipes shahii, Catenibacterium mitsuokai, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Catenibacterium mitsuokai, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques

N322	CDAD,T2D	10	15	66.7	93.3	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_378 or clade_378e), clade_396, (clade_444 or clade_444i), clade_445, clade_466, (clade_478 or clade_478i), clade_500	Alistipes putredinis, Alistipes shahii, Bacteroides plebeius, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques
N323	CDAD,T2D	9	15	80	93.3	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_393, clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500, clade_588	Alistipes putredinis, Alistipes shahii, Coprococcus catus, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Methanobrevibacter smithii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Coprococcus catus, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile

N324	CDAD,T2D	11	15	66.7	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_357, (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_38 or clade_38e or clade_38i), (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i), clade_500, clade_519, (clade_522 or clade_522i)	Alistipes putredinis, Alistipes shahii, Bacteroides xylanisolvens, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Oxalobacter formigenes, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Bacteroides xylanisolvens, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Oxalobacter formigenes, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile
N325	CDAD	11	15	73.3	86.7	(clade_262 or clade_262i), clade_281, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_38 or clade_38e or clade_38i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_494, clade_500,	Alistipes putredinis, Alistipes shahii, Anaerotruncus colihominis, Bacteroides xylanisolvens, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Porphyromonas asaccharolytica, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Bacteroides xylanisolvens, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile

						(clade_516 or clade_516c or clade_516g or clade_516h)		
N326	CDAD	12	15	66.7	93.3	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_38 or clade_38e or clade_38i), (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i), clade_494, clade_500, clade_504, clade_519, (clade_522 or clade_522i)	Alistipes putredinis, Alistipes shahii, Bacteroides xylanisolvens, Campylobacter hominis, Desulfovibrio desulfuricans, Dorea formicigenerans, Eubacterium eligens, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Bacteroides xylanisolvens, Desulfovibrio desulfuricans, Dorea formicigenerans, Eubacterium eligens, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile

N327	CDAD,T2D	10	15	66.7	93.3	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_378 or clade_378e), clade_396, (clade_444 or clade_444i), clade_445, clade_466, (clade_478 or clade_478i), clade_500	Alistipes putredinis, Alistipes shahii, Bacteroides plebeius, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques
N328	CDAD,T2D	9	15	80	93.3	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_393, clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500, clade_588	Alistipes putredinis, Alistipes shahii, Coprococcus catus, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Methanobrevibacter smithii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Coprococcus catus, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile

N329	CDAD,T2D	10	14	71.4	85.7	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_358, (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500, (clade_553 or clade_553i), (clade_98 or clade_98i)	Alistipes putredinis, Alistipes shahii, Collinsella aerofaciens, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Streptococcus parasanguinis, Subdoligranulum variabile, Veillonella dispar	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Streptococcus parasanguinis, Subdoligranulum variabile
N330	CDAD	9	14	78.6	92.9	clade_168, (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_393, clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500	Alistipes putredinis, Alistipes shahii, Coprococcus catus, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Prevotella copri, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Coprococcus catus, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques

N331	CDAD	8	14	85.7	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500, clade_538	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Eubacterium siraeum, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Eubacterium siraeum, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile
N332	CDAD	10	14	78.6	92.9	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_485, clade_494, clade_500, (clade_98 or clade_98i)	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Streptococcus thermophilus, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile

N333	CDAD	11	14	78.6	92.9	(clade_260 or clade_260c or clade_260g or clade_260h), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i), clade_485, clade_494, clade_500	Alistipes putredinis, Alistipes shahii, Clostridium scindens, Desulfovibrio desulfuricans, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Desulfovibrio desulfuricans, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile
N334	CDAD	11	14	78.6	92.9	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_444 or clade_444i), clade_445, (clade_478 or	Alistipes putredinis, Alistipes shahii, Clostridium hathewayi, Desulfovibrio desulfuricans, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Desulfovibrio desulfuricans, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile

						clade_478i), clade_485, clade_494, clade_500		
N335	CDAD,T2D	10	14	71.4	85.7	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_358, (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500, (clade_553 or clade_553i), (clade_98 or clade_98i)	Alistipes putredinis, Alistipes shahii, Collinsella aerofaciens, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Streptococcus parasanguinis, Subdoligranulum variabile, Veillonella dispar	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Streptococcus parasanguinis, Subdoligranulum variabile

N336	CDAD,T2D	9	14	71.4	92.9	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_335 or clade_335i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), clade_466, (clade_478 or clade_478i), clade_500	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Parabacteroides distasonis, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques
N337	CDAD,T2D	9	14	71.4	92.9	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_335 or clade_335i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), clade_466, (clade_478 or clade_478i), clade_500	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Parabacteroides distasonis, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques

N338	CDAD	9	13	76.9	92.3	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500, (clade_522 or clade_522i), (clade_98 or clade_98i)	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Streptococcus australis, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile
N339	CDAD	9	13	76.9	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_494, clade_500, (clade_566 or clade_566f)	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Gordonibacter pamelaeae, Pseudoflavonifractor capillosus, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Gordonibacter pamelaeae, Pseudoflavonifractor capillosus, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile

N340	CDAD	9	13	84.6	92.3	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_354 or clade_354e), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_494, clade_500	Alistipes putredinis, Alistipes shahii, Clostridium bartlettii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile
N341	CDAD	9	13	84.6	92.3	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_494, clade_500, (clade_516 or clade_516c or clade_516g or clade_516h)	Alistipes putredinis, Alistipes shahii, Anaerotruncus colihominis, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile

N342	CDAD,T2D	9	13	69.2	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i), clade_500, clade_583	Akkermansia muciniphila, Alistipes putredinis, Alistipes shahii, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques	Akkermansia muciniphila, Alistipes putredinis, Alistipes shahii, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques
N343	CDAD	9	13	69.2	100	(clade_262 or clade_262i), clade_286, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), clade_466, (clade_478 or clade_478i), clade_500	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Parabacteroides merdae, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Parabacteroides merdae, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques

N344	CDAD	9	13	69.2	92.3	(clade_172 or clade_172i), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), clade_466, (clade_478 or clade_478i), clade_500	Alistipes putredinis, Alistipes shahii, Bifidobacterium adolescentis, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques
N345	CDAD	10	13	84.6	92.3	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_444 or clade_444i), (clade_478 or clade_478i), clade_485, clade_494, clade_500	Alistipes putredinis, Alistipes shahii, Clostridium asparagiforme, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile

N346	CDAD	9	13	84.6	92.3	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_485, clade_500, (clade_516 or clade_516c or clade_516g or clade_516h)	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus albus, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile
N347	CDAD	9	13	69.2	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i), clade_500, clade_85	Alistipes putredinis, Alistipes shahii, Bacteroides cellulosilyticus, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Bacteroides cellulosilyticus, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile

N348	CDAD	8	13	76.9	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500, (clade_65 or clade_65e)	Alistipes putredinis, Alistipes shahii, Bacteroides thetaiotaomicron, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Bacteroides thetaiotaomicron, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques
N349	CDAD,T2D	9	13	69.2	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i), clade_500, clade_583	Akkermansia muciniphila, Alistipes putredinis, Alistipes shahii, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques	Akkermansia muciniphila, Alistipes putredinis, Alistipes shahii, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques

N350	CDAD,T2D	11	13	61.5	92.3	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_368, (clade_38 or clade_38e or clade_38i), clade_396, clade_445, clade_466, (clade_478 or clade_478i), clade_494, clade_500	Alistipes putredinis, Alistipes shahii, Bacteroides ovatus, Blautia hydrogenotrophica, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Eubacterium hallii, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Bacteroides ovatus, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Eubacterium hallii, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N351	CDAD,T2D	11	13	61.5	92.3	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_368, (clade_38 or clade_38e or clade_38i), clade_396, clade_445, clade_466, (clade_478 or clade_478i), clade_494, clade_500	Alistipes putredinis, Alistipes shahii, Bacteroides ovatus, Blautia hydrogenotrophica, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Eubacterium hallii, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Bacteroides ovatus, Coprococcus comes, Desulfovibrio desulfuricans, Dorea formicigenerans, Eubacterium hallii, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques

N352	CDAD	8	12	75	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_358, (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile, Veillonella parvula	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile, Veillonella parvula
N353	CDAD	9	12	75	91.7	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_494, clade_500, clade_506	Alistipes putredinis, Alistipes shahii, Dialister invisus, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile

N354	CDAD	8	12	75	91.7	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500, clade_88	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Haemophilus parainfluenzae, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile
N355	CDAD,T2D	8	12	83.3	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500, clade_519	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile

N356	CDAD	8	12	83.3	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500, clade_537	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus bromii, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus bromii, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile
N357	CDAD	9	12	75	100	clade_170, (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_485, clade_500	Alistipes putredinis, Alistipes shahii, Bacteroides finegoldii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Bacteroides finegoldii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques

N358	CDAD	8	12	75	100	clade_110, (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500	Alistipes putredinis, Alistipes shahii, Bacteroides uniformis, Coprococcus comes, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Bacteroides uniformis, Coprococcus comes, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques
N359	CDAD	8	12	75	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500, clade_85	Alistipes putredinis, Alistipes shahii, Bacteroides eggerthii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Bacteroides eggerthii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile

N360	CDAD,T2D	10	12	58.3	100	clade_110, (clade_262 or clade_262i), clade_286, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_38 or clade_38e or clade_38i), (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i), clade_494, clade_519	Bacteroides ovatus, Bacteroides uniformis, Bacteroides xylanisolvens, Desulfovibrio desulfuricans, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Parabacteroides johnsonii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Bacteroides ovatus, Bacteroides uniformis, Bacteroides xylanisolvens, Desulfovibrio desulfuricans, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Parabacteroides johnsonii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile
N361	CDAD,T2D	8	12	83.3	91.7	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500, (clade_516 or clade_516c or clade_516g or clade_516h)	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus albus, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile

N362	CDAD,T2D	8	12	83.3	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500, clade_519	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile
N363	CDAD,T2D	10	12	66.7	91.7	(clade_262 or clade_262i), clade_271, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i), clade_485, clade_494, clade_500	Alistipes putredinis, Alistipes shahii, Desulfovibrio desulfuricans, Dorea formicigenerans, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Rothia mucilaginosa, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Desulfovibrio desulfuricans, Dorea formicigenerans, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile

N364	CDAD,T2D	10	12	58.3	100	clade_110, (clade_262 or clade_262i), clade_286, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_38 or clade_38e or clade_38i), (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i), clade_494, clade_519	Bacteroides ovatus, Bacteroides uniformis, Bacteroides xylanisolvens, Desulfovibrio desulfuricans, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Parabacteroides johnsonii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Bacteroides ovatus, Bacteroides uniformis, Bacteroides xylanisolvens, Desulfovibrio desulfuricans, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Parabacteroides johnsonii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile
N365	CDAD,T2D	10	12	66.7	91.7	(clade_262 or clade_262i), clade_271, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i), clade_485, clade_494, clade_500	Alistipes putredinis, Alistipes shahii, Desulfovibrio desulfuricans, Dorea formicigenerans, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Rothia mucilaginosa, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Desulfovibrio desulfuricans, Dorea formicigenerans, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile

N366	CDAD,T2D	8	12	83.3	91.7	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500, (clade_516 or clade_516c or clade_516g or clade_516h)	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus albus, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile
N367	CDAD	8	11	72.7	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_358, (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile, Veillonella atypica	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile, Veillonella atypica

N368	CDAD	8	11	72.7	90.9	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500, (clade_98 or clade_98i)	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Streptococcus salivarius	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques
N369	CDAD	8	11	81.8	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500, (clade_522 or clade_522i)	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques

N370	CDAD	8	11	72.7	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), clade_466, (clade_478 or clade_478i), clade_500	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques
N371	CDAD	7	11	81.8	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques
N372	CDAD	8	11	81.8	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Roseburia inulinivorans, Ruminococcus obeum,	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Roseburia inulinivorans, Ruminococcus obeum,

						clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_494, clade_500	Ruminococcus torques, Subdoligranulum variabile	Ruminococcus torques, Subdoligranulum variabile
N373	CDAD	8	11	81.8	90.9	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_485, clade_500	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Roseburia inulinivorans, Ruminococcus gnavus, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques
N374	CDAD	8	11	72.7	100	(clade_172 or clade_172i), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or	Alistipes putredinis, Alistipes shahii, Bifidobacterium longum, Coprococcus comes, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Bifidobacterium longum, Coprococcus comes, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques

						clade_478i), clade_500		
N375	CDAD	8	11	81.8	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500, clade_537	Alistipes putredinis, Alistipes shahii, Clostridium leptum, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Clostridium leptum, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile
N376	CDAD	8	11	72.7	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i),	Alistipes putredinis, Alistipes shahii, Bacteroides stercoris, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Bacteroides stercoris, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques

						clade_500, clade_85		
N377	CDAD	8	11	72.7	100	clade_170, (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500	Alistipes putredinis, Alistipes shahii, Bacteroides caccae, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Bacteroides caccae, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques
N378	CDAD	9	11	72.7	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_378 or clade_378e), clade_396, (clade_444 or clade_444i), (clade_478 or	Alistipes putredinis, Alistipes shahii, Bacteroides dorei, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Bacteroides dorei, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques

						clade_478i), clade_485, clade_500		
N379	CDAD	8	11	72.7	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_38 or clade_38e or clade_38i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500	Alistipes putredinis, Alistipes shahii, Bacteroides xylanisolvens, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Bacteroides xylanisolvens, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques
N380	CDAD	9	11	81.8	81.8	(clade_172 or clade_172i), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_38 or	Bacteroides ovatus, Bifidobacterium adolescentis, Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Roseburia faecalis, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques	Bacteroides ovatus, Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques

						clade_38e or clade_38i), (clade_444 or clade_444i), (clade_478 or clade_478i), clade_519, (clade_522 or clade_522i)		
N381	CDAD,T2D	9	11	90.9	81.8	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_38 or clade_38e or clade_38i), (clade_444 or clade_444i), (clade_478 or clade_478i), clade_494, (clade_516 or clade_516c or clade_516g or clade_516h), (clade_522 or clade_522i), clade_537	Anaerotruncus colihominis, Bacteroides xylanisolvens, Clostridium leptum, Clostridium methylpentosum, Eubacterium eligens, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques	Bacteroides xylanisolvens, Clostridium leptum, Eubacterium eligens, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques

N382	CDAD	10	11	100	18.2	clade_252, (clade_260 or clade_260c or clade_260g or clade_260h), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_351 or clade_351e), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), clade_494, clade_537, (clade_553 or clade_553i)	Blautia producta, Clostridium hylemonae, Clostridium innocuum, Clostridium orbiscindens, Clostridium symbiosum, Clostridium tertium, Collinsella aerofaciens, Coprococcus comes, Lachnospiraceae bacterium 5_1_57FAA, Ruminococcus bromii, Ruminococcus gnavus	Coprococcus comes, Ruminococcus bromii
N383	CDAD,T2D	9	11	90.9	81.8	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_38 or clade_38e or clade_38i), (clade_444 or clade_444i), (clade_478 or clade_478i), clade_494, (clade_516 or clade_516c or clade_516g or clade_516h),	Anaerotruncus colihominis, Bacteroides xylanisolvens, Clostridium leptum, Clostridium methylpentosum, Eubacterium eligens, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques	Bacteroides xylanisolvens, Clostridium leptum, Eubacterium eligens, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques

						(clade_522 or clade_522i), clade_537		
N384	CDAD,T2D	10	11	63.6	90.9	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_38 or clade_38e or clade_38i), clade_419, (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i), clade_485, clade_494, clade_500	Alistipes shahii, Bacteroides ovatus, Bacteroides salanitronis, Desulfovibrio desulfuricans, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques	Alistipes shahii, Bacteroides ovatus, Desulfovibrio desulfuricans, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques
N385	CDAD,T2D	10	11	63.6	90.9	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_38 or clade_38e or clade_38i), clade_419, (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i), clade_485,	Alistipes shahii, Bacteroides ovatus, Bacteroides salanitronis, Desulfovibrio desulfuricans, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques	Alistipes shahii, Bacteroides ovatus, Desulfovibrio desulfuricans, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques

						clade_494, clade_500		
N386	CDAD	8	10	70	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500, (clade_98 or clade_98i)	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Streptococcus parasanguinis	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Streptococcus parasanguinis
N387	CDAD	8	10	80	90	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500,	Alistipes putredinis, Alistipes shahii, Collinsella aerofaciens, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques

						(clade_553 or clade_553i)		
N388	CDAD	7	10	80	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus lactaris, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus lactaris, Ruminococcus obeum, Ruminococcus torques
N389	CDAD	8	10	80	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_393, clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i),	Alistipes putredinis, Alistipes shahii, Coprococcus catus, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Coprococcus catus, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques

						clade_500		
N390	CDAD	8	10	70	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500, clade_521	Alistipes putredinis, Alistipes shahii, Bilophila wadsworthia, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Bilophila wadsworthia, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques
N391	CDAD	8	10	70	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i),	Alistipes putredinis, Alistipes shahii, Desulfovibrio desulfuricans, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Desulfovibrio desulfuricans, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques

						clade_500		
N392	CDAD	7	10	80	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques
N393	CDAD	7	10	80	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques

N394	CDAD	7	10	80	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile
N395	CDAD	8	10	80	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_485, clade_500	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques

N396	CDAD	8	10	70	90	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500, (clade_65 or clade_65e)	Alistipes putredinis, Alistipes shahii, Bacteroides fragilis, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques
N397	CDAD	8	10	70	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_38 or clade_38e or clade_38i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500	Alistipes putredinis, Alistipes shahii, Bacteroides ovatus, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Bacteroides ovatus, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques

N398	CDAD,T2D	8	10	70	100	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_38 or clade_38e or clade_38i), (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i), clade_519, clade_567	Bacteroides xylanisolvens, Desulfovibrio desulfuricans, Dorea formicigenerans, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus obeum, Subdoligranulum variabile, Victivallis vadensis	Bacteroides xylanisolvens, Desulfovibrio desulfuricans, Dorea formicigenerans, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus obeum, Subdoligranulum variabile, Victivallis vadensis
N399	CDAD,T2D	10	10	70	90	clade_110, (clade_172 or clade_172i), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_494, clade_500	Alistipes shahii, Bacteroides uniformis, Bifidobacterium catenulatum, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Alistipes shahii, Bacteroides uniformis, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques

N400	CDAD	10	10	100	50	clade_253, (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_351 or clade_351e), (clade_354 or clade_354e), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_444 or clade_444i), (clade_478 or clade_478i), (clade_481 or clade_481a or clade_481b or clade_481e or clade_481g or clade_481h or clade_481i)	Clostridium celatum, Clostridium glycolicum, Clostridium innocuum, Clostridium ramosum, Clostridium symbiosum, Coprococcus comes, Dorea formicigenerans, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum	Coprococcus comes, Dorea formicigenerans, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum
N401	CDAD	8	10	60	70	(clade_262 or clade_262i), (clade_335 or clade_335i), (clade_38 or clade_38e or clade_38i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_444 or clade_444i),	Bacteroides ovatus, Bacteroides sp. 1_1_30, Bacteroides sp. 20_3, Bilophila wadsworthia, Clostridium leptum, Eubacterium desmolans, Lachnospiraceae bacterium 3_1_57FAA, Roseburia inulinivorans, Ruminococcus lactaris, Ruminococcus torques	Bacteroides ovatus, Bilophila wadsworthia, Clostridium leptum, Roseburia inulinivorans, Ruminococcus lactaris, Ruminococcus torques

						clade_521, clade_537, (clade_572 or clade_572i)		
N402	CDAD	8	10	70	100	(clade_262 or clade_262i), clade_286, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), clade_466, (clade_478 or clade_478i), clade_500	Alistipes shahii, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Parabacteroides merdae, Ruminococcus obeum, Ruminococcus torques	Alistipes shahii, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Parabacteroides merdae, Ruminococcus obeum, Ruminococcus torques
N403	CDAD	7	10	80	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500, (clade_65 or clade_65e)	Alistipes shahii, Bacteroides thetaiotaomicron, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques	Alistipes shahii, Bacteroides thetaiotaomicron, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques

N404	CDAD,T2D	8	10	70	100	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_38 or clade_38e or clade_38i), (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i), clade_519, clade_567	Bacteroides xylanisolvens, Desulfovibrio desulfuricans, Dorea formicigenerans, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus obeum, Subdoligranulum variabile, Victivallis vadensis	Bacteroides xylanisolvens, Desulfovibrio desulfuricans, Dorea formicigenerans, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus obeum, Subdoligranulum variabile, Victivallis vadensis
N405	CDAD,T2D	7	10	70	80	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_378 or clade_378e), (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i)	Bacteroides coprocola, Bacteroides vulgatus, Desulfovibrio desulfuricans, Dorea formicigenerans, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Desulfovibrio desulfuricans, Dorea formicigenerans, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile

N406	CDAD,T2D	10	10	70	90	clade_110, (clade_172 or clade_172i), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_494, clade_500	Alistipes shahii, Bacteroides uniformis, Bifidobacterium catenulatum, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Alistipes shahii, Bacteroides uniformis, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N407	CDAD,T2D	9	10	80	90	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i), clade_485, clade_494, clade_500, (clade_516 or clade_516c or clade_516g or clade_516h)	Alistipes shahii, Clostridium methylpentosum, Desulfovibrio desulfuricans, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Ruminococcus lactaris, Ruminococcus obeum, Ruminococcus torques	Alistipes shahii, Desulfovibrio desulfuricans, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Ruminococcus lactaris, Ruminococcus obeum, Ruminococcus torques

N408	CDAD,T2D	9	10	60	90	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_466, (clade_478 or clade_478i), clade_494, clade_500, (clade_522 or clade_522i), clade_556	Acidaminococcus fermentans, Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium eligens, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium eligens, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N409	CDAD,T2D	9	10	80	90	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i), clade_485, clade_494, clade_500, (clade_516 or clade_516c or clade_516g or clade_516h)	Alistipes shahii, Clostridium methylpentosum, Desulfovibrio desulfuricans, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Ruminococcus lactaris, Ruminococcus obeum, Ruminococcus torques	Alistipes shahii, Desulfovibrio desulfuricans, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Ruminococcus lactaris, Ruminococcus obeum, Ruminococcus torques

N410	CDAD,T2D	9	10	60	90	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_466, (clade_478 or clade_478i), clade_494, clade_500, (clade_522 or clade_522i), clade_556	Acidaminococcus fermentans, Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium eligens, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium eligens, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N411	CDAD,T2D	7	10	70	80	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_378 or clade_378e), (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i)	Bacteroides coprocola, Bacteroides vulgatus, Desulfovibrio desulfuricans, Dorea formicigenerans, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Desulfovibrio desulfuricans, Dorea formicigenerans, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile

N412	CDAD	6	9	88.9	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), clade_466, (clade_478 or clade_478i)	Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques	Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques
N413	CDAD,T2D	7	9	77.8	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques
N414	CDAD	7	9	88.9	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i),	Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Ruminococcus obeum, Ruminococcus torques	Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Ruminococcus obeum, Ruminococcus torques

						(clade_444 or clade_444i), clade_466, (clade_478 or clade_478i), (clade_522 or clade_522i)		
N415	CDAD	7	9	77.8	100	clade_170, (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), (clade_478 or clade_478i), (clade_65 or clade_65e)	Bacteroides caccae, Bacteroides thetaiotaomicron, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Bacteroides caccae, Bacteroides thetaiotaomicron, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N416	CDAD,T2D	8	9	66.7	77.8	(clade_262 or clade_262i), clade_281, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_396, (clade_444 or clade_444i), clade_494, clade_500, (clade_516 or clade_516c or clade_516g or clade_516h)	Alistipes putredinis, Alistipes shahii, Anaerotruncus colihominis, Eubacterium hallii, Eubacterium rectale, Porphyromonas asaccharolytica, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Eubacterium hallii, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques

N417	CDAD,T2D	7	9	77.8	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques
N418	CDAD,T2D	8	9	66.7	77.8	(clade_262 or clade_262i), clade_281, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_396, (clade_444 or clade_444i), clade_494, clade_500, (clade_516 or clade_516c or clade_516g or clade_516h)	Alistipes putredinis, Alistipes shahii, Anaerotruncus colihominis, Eubacterium hallii, Eubacterium rectale, Porphyromonas asaccharolytica, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Eubacterium hallii, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N419	CDAD,T2D	6	9	44.4	77.8	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), clade_494, clade_500, (clade_98 or	Alistipes putredinis, Alistipes shahii, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques, Streptococcus parasanguinis, Streptococcus salivarius, Streptococcus vestibularis	Alistipes putredinis, Alistipes shahii, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques, Streptococcus parasanguinis

						clade_98i)		
N420	CDAD,T2D	8	9	66.7	88.9	(clade_172 or clade_172i), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_445, (clade_478 or clade_478i), clade_485, clade_494	Bifidobacterium catenulatum, Bifidobacterium longum, Desulfovibrio desulfuricans, Dorea formicigenerans, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Bifidobacterium longum, Desulfovibrio desulfuricans, Dorea formicigenerans, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N421	CDAD,T2D	8	9	66.7	88.9	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, clade_419, (clade_444 or clade_444i), clade_466, (clade_478 or clade_478i), clade_500	Alistipes putredinis, Bacteroides salanitronis, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Odoribacter splanchnicus, Roseburia inulinivorans, Subdoligranulum variabile	Alistipes putredinis, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Odoribacter splanchnicus, Roseburia inulinivorans, Subdoligranulum variabile

N422	CDAD,T2D	7	9	66.7	100	(clade_262 or clade_262i), clade_286, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), clade_494, clade_500	Alistipes putredinis, Alistipes shahii, Dorea longicatena, Eubacterium rectale, Parabacteroides johnsonii, Pseudoflavonifractor capillosus, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Dorea longicatena, Eubacterium rectale, Parabacteroides johnsonii, Pseudoflavonifractor capillosus, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques
N423	CDAD,T2D	7	9	77.8	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500, clade_538	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium rectale, Eubacterium siraeum, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium rectale, Eubacterium siraeum, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile
N424	CDAD,T2D	6	9	44.4	77.8	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), clade_494, clade_500, (clade_98 or	Alistipes putredinis, Alistipes shahii, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques, Streptococcus parasanguinis, Streptococcus salivarius, Streptococcus vestibularis	Alistipes putredinis, Alistipes shahii, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques, Streptococcus parasanguinis

						clade_98i)		
N425	CDAD,T2D	8	9	66.7	88.9	(clade_172 or clade_172i), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_445, (clade_478 or clade_478i), clade_485, clade_494	Bifidobacterium catenulatum, Bifidobacterium longum, Desulfovibrio desulfuricans, Dorea formicigenerans, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Bifidobacterium longum, Desulfovibrio desulfuricans, Dorea formicigenerans, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N426	CDAD,T2D	7	9	66.7	100	(clade_262 or clade_262i), clade_286, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), clade_494, clade_500	Alistipes putredinis, Alistipes shahii, Dorea longicatena, Eubacterium rectale, Parabacteroides johnsonii, Pseudoflavonifractor capillosus, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Dorea longicatena, Eubacterium rectale, Parabacteroides johnsonii, Pseudoflavonifractor capillosus, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques

N427	CDAD,T2D	7	9	77.8	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500, clade_538	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium rectale, Eubacterium siraeum, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium rectale, Eubacterium siraeum, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile
N428	CDAD,T2D	8	9	66.7	88.9	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, clade_419, (clade_444 or clade_444i), clade_466, (clade_478 or clade_478i), clade_500	Alistipes putredinis, Bacteroides salanitronis, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Odoribacter splanchnicus, Roseburia inulinivorans, Subdoligranulum variabile	Alistipes putredinis, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Odoribacter splanchnicus, Roseburia inulinivorans, Subdoligranulum variabile
N429	CDAD,T2D	7	8	75	87.5	(clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_38 or clade_38e or clade_38i), (clade_444 or clade_444i), (clade_478 or clade_478i), clade_504, clade_519, (clade_522 or clade_522i)	Bacteroides xylanisolvens, Campylobacter hominis, Dorea formicigenerans, Eubacterium eligens, Eubacterium ventriosum, Faecalibacterium prausnitzii, Roseburia inulinivorans, Subdoligranulum variabile	Bacteroides xylanisolvens, Dorea formicigenerans, Eubacterium eligens, Eubacterium ventriosum, Faecalibacterium prausnitzii, Roseburia inulinivorans, Subdoligranulum variabile

N430	CDAD	7	8	100	87.5	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), (clade_478 or clade_478i), clade_519, (clade_522 or clade_522i)	Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Roseburia faecalis, Ruminococcus obeum, Ruminococcus torques	Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N431	CDAD	7	8	87.5	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_38 or clade_38e or clade_38i), (clade_444 or clade_444i), (clade_478 or clade_478i), clade_519	Bacteroides ovatus, Dorea longicatena, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques	Bacteroides ovatus, Dorea longicatena, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques
N432	CDAD,T2D	6	8	87.5	87.5	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or	Clostridium leptum, Coprococcus comes, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques, Streptococcus sanguinis	Clostridium leptum, Coprococcus comes, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques

						clade_444i), (clade_478 or clade_478i), clade_537, (clade_98 or clade_98i)		
N433	CDAD	6	8	87.5	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), (clade_478 or clade_478i), (clade_65 or clade_65e)	Bacteroides thetaiotaomicron, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Bacteroides thetaiotaomicron, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N434	CDAD	7	8	87.5	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_38 or clade_38e or clade_38i), (clade_444 or clade_444i), (clade_478 or clade_478i), (clade_522 or clade_522i)	Bacteroides ovatus, Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques	Bacteroides ovatus, Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques

N435	CDAD	6	8	87.5	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), clade_466, (clade_478 or clade_478i)	Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Ruminococcus obeum, Ruminococcus torques	Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Ruminococcus obeum, Ruminococcus torques
N436	CDAD	5	8	100	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i)	Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques	Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques
N437	CDAD	5	8	100	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), (clade_478 or	Coprococcus comes, Dorea formicigenerans, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Coprococcus comes, Dorea formicigenerans, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile

						clade_478i)		
N438	CDAD,T2D	7	8	50	87.5	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), clade_445, clade_494, clade_500, clade_504	Alistipes putredinis, Alistipes shahii, Campylobacter hominis, Desulfovibrio desulfuricans, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Desulfovibrio desulfuricans, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N439	CDAD,T2D	8	8	75	87.5	(clade_262 or clade_262i), clade_293, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), (clade_478 or clade_478i), clade_494, clade_500	Alistipes shahii, Bifidobacterium bifidum, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Alistipes shahii, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques

N440	CDAD,T2D	8	8	87.5	87.5	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i), clade_494, clade_537	Clostridium leptum, Clostridium symbiosum, Desulfovibrio desulfuricans, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Clostridium leptum, Desulfovibrio desulfuricans, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N441	CDAD	7	8	100	25	clade_252, clade_253, (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_351 or clade_351e), (clade_354 or clade_354e), (clade_360 or clade_360c or clade_360g or clade_360h clade_360i)	Blautia producta, Clostridium butyricum, Clostridium celatum, Clostridium glycolicum, Clostridium innocuum, Dorea formicigenerans, Eubacterium tenue, Ruminococcus torques	Dorea formicigenerans, Ruminococcus torques
N442	CDAD,T2D	6	8	87.5	87.5	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i),	Clostridium leptum, Coprococcus comes, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques, Streptococcus sanguinis	Clostridium leptum, Coprococcus comes, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques

						(clade_478 or clade_478i), clade_537, (clade_98 or clade_98i)		
N443	CDAD,T2D	7	8	75	87.5	(clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_38 or clade_38e or clade_38i), (clade_444 or clade_444i), (clade_478 or clade_478i), clade_504, clade_519, (clade_522 or clade_522i)	Bacteroides xylanisolvens, Campylobacter hominis, Dorea formicigenerans, Eubacterium eligens, Eubacterium ventriosum, Faecalibacterium prausnitzii, Roseburia inulinivorans, Subdoligranulum variabile	Bacteroides xylanisolvens, Dorea formicigenerans, Eubacterium eligens, Eubacterium ventriosum, Faecalibacterium prausnitzii, Roseburia inulinivorans, Subdoligranulum variabile
N444	CDAD,T2D	7	8	50	87.5	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), clade_445, clade_494, clade_500, clade_504	Alistipes putredinis, Alistipes shahii, Campylobacter hominis, Desulfovibrio desulfuricans, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Desulfovibrio desulfuricans, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N445	CDAD,T2D	8	8	75	87.5	(clade_262 or clade_262i), clade_293, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or	Alistipes shahii, Bifidobacterium bifidum, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Alistipes shahii, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques

						clade_360h or clade_360i), (clade_444 or clade_444i), (clade_478 or clade_478i), clade_494, clade_500		
N446	CDAD,T2D	7	8	50	87.5	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_378 or clade_378e), clade_396, (clade_444 or clade_444i), clade_466, clade_500	Alistipes putredinis, Alistipes shahii, Bacteroides coprocola, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Odoribacter splanchnicus, Roseburia inulinivorans	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Odoribacter splanchnicus, Roseburia inulinivorans
N447	CDAD,T2D	7	8	87.5	87.5	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), (clade_478 or clade_478i), clade_494, clade_506	Dialister invisus, Dorea formicigenerans, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Dorea formicigenerans, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile

N448	CDAD,T2D	7	8	75	100	(clade_262 or clade_262i), clade_286, (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), clade_466, (clade_478 or clade_478i)	Coprococcus comes, Dorea formicigenerans, Eubacterium hallii, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Parabacteroides johnsonii, Roseburia inulinivorans, Subdoligranulum variabile	Coprococcus comes, Dorea formicigenerans, Eubacterium hallii, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Parabacteroides johnsonii, Roseburia inulinivorans, Subdoligranulum variabile
N449	CDAD,T2D	8	8	87.5	87.5	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i), clade_494, clade_537	Clostridium leptum, Clostridium symbiosum, Desulfovibrio desulfuricans, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Clostridium leptum, Desulfovibrio desulfuricans, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N450	CDAD,T2D	7	8	75	87.5	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_478 or clade_478i),	Alistipes putredinis, Alistipes shahii, Anaerotruncus colihominis, Dorea formicigenerans, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques

						clade_494, clade_500, (clade_516 or clade_516c or clade_516g or clade_516h)		
N451	CDAD,T2D	6	8	75	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_478 or clade_478i), clade_500	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea formicigenerans, Eubacterium hallii, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea formicigenerans, Eubacterium hallii, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N452	CDAD,T2D	7	8	50	87.5	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_378 or clade_378e), clade_396, (clade_444 or clade_444i), clade_466, clade_500	Alistipes putredinis, Alistipes shahii, Bacteroides coprocola, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Odoribacter splanchnicus, Roseburia inulinivorans	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Odoribacter splanchnicus, Roseburia inulinivorans

N453	CDAD,T2D	7	8	87.5	87.5	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), (clade_478 or clade_478i), clade_494, clade_506	Dialister invisus, Dorea formicigenerans, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Dorea formicigenerans, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile
N454	CDAD,T2D	7	8	75	87.5	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_478 or clade_478i), clade_494, clade_500, (clade_516 or clade_516c or clade_516g or clade_516h)	Alistipes putredinis, Alistipes shahii, Anaerotruncus colihominis, Dorea formicigenerans, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N455	CDAD,T2D	6	8	75	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea formicigenerans, Eubacterium hallii, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea formicigenerans, Eubacterium hallii, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques

						clade_360g or clade_360h or clade_360i), clade_396, (clade_478 or clade_478i), clade_500		
N456	CDAD,T2D	7	8	75	100	(clade_262 or clade_262i), clade_286, (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), clade_466, (clade_478 or clade_478i)	Coprococcus comes, Dorea formicigenerans, Eubacterium hallii, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Parabacteroides johnsonii, Roseburia inulinivorans, Subdoligranulum variabile	Coprococcus comes, Dorea formicigenerans, Eubacterium hallii, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Parabacteroides johnsonii, Roseburia inulinivorans, Subdoligranulum variabile
N457	CDAD	6	7	100	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), (clade_478 or clade_478i), (clade_522 or clade_522i)	Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques	Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques

N458	CDAD	7	7	85.7	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_38 or clade_38e or clade_38i), (clade_444 or clade_444i), (clade_478 or clade_478i), (clade_522 or clade_522i)	Bacteroides ovatus, Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Bacteroides ovatus, Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N459	CDAD	6	7	85.7	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_38 or clade_38e or clade_38i), (clade_444 or clade_444i), (clade_478 or clade_478i)	Bacteroides ovatus, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques	Bacteroides ovatus, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques

N460	CDAD	6	7	85.7	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), clade_466, (clade_478 or clade_478i)	Coprococcus comes, Dorea formicigenerans, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Ruminococcus obeum, Ruminococcus torques	Coprococcus comes, Dorea formicigenerans, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Ruminococcus obeum, Ruminococcus torques
N461	CDAD	5	7	100	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), (clade_478 or clade_478i)	Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N462	CDAD,T2D	5	7	71.4	85.7	(clade_262 or clade_262i), clade_281, (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_38 or clade_38e or clade_38i), (clade_478 or clade_478i)	Bacteroides xylanisolvens, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Faecalibacterium prausnitzii, Porphyromonas asaccharolytica, Subdoligranulum variabile	Bacteroides xylanisolvens, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Faecalibacterium prausnitzii, Subdoligranulum variabile

N463	CDAD	6	7	85.7	85.7	clade_170, clade_246, (clade_262 or clade_262i), (clade_444 or clade_444i), (clade_478 or clade_478i), clade_576	Bacteroides finegoldii, Clostridiales sp. SS3/4, Clostridium lactatifermentans, Faecalibacterium prausnitzii, Gemmiger formicilis, Roseburia inulinivorans, Ruminococcus torques	Bacteroides finegoldii, Clostridium lactatifermentans, Faecalibacterium prausnitzii, Gemmiger formicilis, Roseburia inulinivorans, Ruminococcus torques
N464	CDAD	7	7	100	28.6	clade_252, clade_253, (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_351 or clade_351e), (clade_354 or clade_354e), (clade_360 or clade_360c or clade_360g or clade_360h clade_360i)	Blautia producta, Clostridium butyricum, Clostridium celatum, Clostridium glycolicum, Clostridium innocuum, Dorea formicigenerans, Ruminococcus torques	Dorea formicigenerans, Ruminococcus torques
N465	CDAD,T2D	6	7	71.4	85.7	clade_168, (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500	Alistipes shahii, Eubacterium rectale, Faecalibacterium prausnitzii, Prevotella copri, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques	Alistipes shahii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques
N466	CDAD,T2D	6	7	71.4	85.7	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i),	Alistipes putredinis, Alistipes shahii, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques, Solobacterium moorei	Alistipes putredinis, Alistipes shahii, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques

						(clade_38 or clade_38e or clade_38i)8, (clade_444 or clade_444i), clade_494, clade_500		
N467	CDAD,T2D	5	7	71.4	85.7	(clade_262 or clade_262i), clade_281, (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_38 or clade_38e or clade_38i), (clade_478 or clade_478i)	Bacteroides xylanisolvens, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Faecalibacterium prausnitzii, Porphyromonas asaccharolytica, Subdoligranulum variabile	Bacteroides xylanisolvens, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Faecalibacterium prausnitzii, Subdoligranulum variabile
N468	CDAD,T2D	6	7	42.9	85.7	(clade_262 or clade_262i), clade_293, (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, clade_466, clade_500	Alistipes putredinis, Alistipes shahii, Bifidobacterium bifidum, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Odoribacter splanchnicus	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Odoribacter splanchnicus
N469	CDAD,T2D	6	7	42.9	85.7	(clade_172 or clade_172i), (clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, clade_466, clade_500	Alistipes putredinis, Alistipes shahii, Bifidobacterium catenulatum, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Odoribacter splanchnicus	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Odoribacter splanchnicus

N470	CDAD,T2D	6	7	71.4	85.7	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_466, (clade_478 or clade_478i), clade_485, (clade_98 or clade_98i)	Dorea formicigenerans, Faecalibacterium prausnitzii, Holdemania filiformis, Odoribacter splanchnicus, Ruminococcus lactaris, Streptococcus vestibularis, Subdoligranulum variabile	Dorea formicigenerans, Faecalibacterium prausnitzii, Holdemania filiformis, Odoribacter splanchnicus, Ruminococcus lactaris, Subdoligranulum variabile
N471	CDAD,T2D	6	7	57.1	85.7	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), clade_494, clade_500, (clade_98 or clade_98i)	Alistipes putredinis, Alistipes shahii, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques, Streptococcus mitis	Alistipes putredinis, Alistipes shahii, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N472	CDAD,T2D	6	7	71.4	85.7	clade_168, (clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), clade_500	Alistipes putredinis, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Prevotella copri, Roseburia inulinivorans	Alistipes putredinis, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Roseburia inulinivorans
N473	CDAD,T2D	7	7	57.1	85.7	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, clade_432, (clade_444 or clade_444i),	Alistipes putredinis, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Odoribacter splanchnicus, Roseburia inulinivorans, Sutterella wadsworthensis	Alistipes putredinis, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Odoribacter splanchnicus, Roseburia inulinivorans

						clade_466, clade_500		
N474	CDAD,T2D	7	7	71.4	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), (clade_478 or clade_478i), clade_494, clade_500, (clade_566 or clade_566f)	Alistipes shahii, Eubacterium rectale, Faecalibacterium prausnitzii, Gordonibacter pamelaeae, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Alistipes shahii, Eubacterium rectale, Faecalibacterium prausnitzii, Gordonibacter pamelaeae, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N475	CDAD,T2D	6	7	85.7	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_85	Bacteroides cellulosilyticus, Coprococcus comes, Dorea formicigenerans, Eubacterium hallii, Faecalibacterium prausnitzii, Roseburia inulinivorans, Subdoligranulum variabile	Bacteroides cellulosilyticus, Coprococcus comes, Dorea formicigenerans, Eubacterium hallii, Faecalibacterium prausnitzii, Roseburia inulinivorans, Subdoligranulum variabile
N476	CDAD,T2D	6	7	42.9	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), clade_445, clade_500, clade_85	Alistipes putredinis, Alistipes shahii, Bacteroides cellulosilyticus, Desulfovibrio desulfuricans, Eubacterium rectale, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Bacteroides cellulosilyticus, Desulfovibrio desulfuricans, Eubacterium rectale, Ruminococcus obeum, Ruminococcus torques

N477	CDAD,T2D	6	7	57.1	85.7	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), clade_494, clade_500, (clade_98 or clade_98i)	Alistipes putredinis, Alistipes shahii, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques, Streptococcus thermophilus	Alistipes putredinis, Alistipes shahii, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N478	CDAD,T2D	6	7	57.1	100	clade_170, (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_478 or clade_478i), clade_500	Alistipes putredinis, Alistipes shahii, Bacteroides caccae, Dorea formicigenerans, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Bacteroides caccae, Dorea formicigenerans, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N479	CDAD,T2D	6	7	57.1	100	clade_110, (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_478 or clade_478i), clade_500	Alistipes putredinis, Alistipes shahii, Bacteroides uniformis, Dorea formicigenerans, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Bacteroides uniformis, Dorea formicigenerans, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques

N480	CDAD,T2D	6	7	71.4	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_478 or clade_478i), clade_500, clade_537	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Faecalibacterium prausnitzii, Ruminococcus bromii, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Faecalibacterium prausnitzii, Ruminococcus bromii, Ruminococcus obeum, Ruminococcus torques
N481	CDAD,T2D	6	7	71.4	85.7	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_478 or clade_478i), clade_500, (clade_553 or clade_553i)	Alistipes putredinis, Alistipes shahii, Collinsella aerofaciens, Dorea formicigenerans, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N482	CDAD,T2D	6	7	71.4	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_478 or clade_478i),	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium eligens, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium eligens, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques

						clade_500, (clade_522 or clade_522i)		
N483	CDAD,T2D	6	7	57.1	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_466, (clade_478 or clade_478i), clade_500	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Ruminococcus obeum, Ruminococcus torques
N484	CDAD,T2D	6	7	71.4	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_478 or clade_478i), clade_500	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques

N485	CDAD,T2D	6	7	71.4	85.7	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_38 or clade_38e or clade_38i)8, (clade_444 or clade_444i), clade_494, clade_500	Alistipes putredinis, Alistipes shahii, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques, Solobacterium moorei	Alistipes putredinis, Alistipes shahii, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N486	CDAD,T2D	6	7	42.9	85.7	(clade_262 or clade_262i), clade_293, (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, clade_466, clade_500	Alistipes putredinis, Alistipes shahii, Bifidobacterium bifidum, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Odoribacter splanchnicus	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Odoribacter splanchnicus
N487	CDAD,T2D	6	7	42.9	85.7	(clade_172 or clade_172i), (clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, clade_466, clade_500	Alistipes putredinis, Alistipes shahii, Bifidobacterium catenulatum, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Odoribacter splanchnicus	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Odoribacter splanchnicus
N488	CDAD	6	7	85.7	85.7	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_396, (clade_444 or clade_444i), (clade_478 or	Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques, Streptococcus infantis	Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques

						clade_478i), (clade_98 or clade_98i)		
N489	CDAD,T2D	6	7	57.1	85.7	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), clade_494, clade_500, (clade_98 or clade_98i)	Alistipes putredinis, Alistipes shahii, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques, Streptococcus mitis	Alistipes putredinis, Alistipes shahii, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N490	CDAD	6	7	85.7	85.7	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), (clade_98 or clade_98i)	Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques, Streptococcus australis	Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques
N491	CDAD,T2D	7	7	57.1	85.7	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, clade_432, (clade_444 or clade_444i), clade_466, clade_500	Alistipes putredinis, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Odoribacter splanchnicus, Roseburia inulinivorans, Sutterella wadsworthensis	Alistipes putredinis, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Odoribacter splanchnicus, Roseburia inulinivorans

N492	CDAD,T2D	6	7	71.4	85.7	clade_168, (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500	Alistipes shahii, Eubacterium rectale, Faecalibacterium prausnitzii, Prevotella copri, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques	Alistipes shahii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques
N493	CDAD	7	7	100	85.7	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_354 or clade_354e), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_494	Clostridium bartlettii, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N494	CDAD,T2D	7	7	71.4	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), (clade_478 or clade_478i), clade_494, clade_500, (clade_566 or clade_566f)	Alistipes shahii, Eubacterium rectale, Faecalibacterium prausnitzii, Gordonibacter pamelaeae, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Alistipes shahii, Eubacterium rectale, Faecalibacterium prausnitzii, Gordonibacter pamelaeae, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques

N495	CDAD,T2D	6	7	42.9	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), clade_445, clade_500, clade_85	Alistipes putredinis, Alistipes shahii, Bacteroides cellulosilyticus, Desulfovibrio desulfuricans, Eubacterium rectale, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Bacteroides cellulosilyticus, Desulfovibrio desulfuricans, Eubacterium rectale, Ruminococcus obeum, Ruminococcus torques
N496	CDAD,T2D	6	7	57.1	85.7	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), clade_494, clade_500, (clade_98 or clade_98i)	Alistipes putredinis, Alistipes shahii, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques, Streptococcus thermophilus	Alistipes putredinis, Alistipes shahii, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N497	CDAD	6	7	42.9	100	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_378 or clade_378e), (clade_38 or clade_38e or clade_38i), (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i)	Bacteroides dorei, Bacteroides ovatus, Bacteroides xylanisolvens, Desulfovibrio desulfuricans, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum	Bacteroides dorei, Bacteroides ovatus, Bacteroides xylanisolvens, Desulfovibrio desulfuricans, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum

N498	CDAD,T2D	6	7	57.1	100	clade_170, (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_478 or clade_478i), clade_500	Alistipes putredinis, Alistipes shahii, Bacteroides caccae, Dorea formicigenerans, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Bacteroides caccae, Dorea formicigenerans, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N499	CDAD,T2D	6	7	57.1	100	clade_110, (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_478 or clade_478i), clade_500	Alistipes putredinis, Alistipes shahii, Bacteroides uniformis, Dorea formicigenerans, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Bacteroides uniformis, Dorea formicigenerans, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N500	CDAD,T2D	6	7	71.4	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_478 or clade_478i), clade_500,	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Faecalibacterium prausnitzii, Ruminococcus bromii, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Faecalibacterium prausnitzii, Ruminococcus bromii, Ruminococcus obeum, Ruminococcus torques

						clade_537		
N501	CDAD,T2D	6	7	71.4	85.7	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_478 or clade_478i), clade_500, (clade_553 or clade_553i)	Alistipes putredinis, Alistipes shahii, Collinsella aerofaciens, Dorea formicigenerans, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N502	CDAD,T2D	6	7	71.4	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_478 or clade_478i), clade_500, (clade_522 or clade_522i)	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium eligens, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium eligens, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques

N503	CDAD,T2D	6	7	57.1	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_466, (clade_478 or clade_478i), clade_500	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Ruminococcus obeum, Ruminococcus torques
N504	CDAD,T2D	6	7	71.4	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_478 or clade_478i), clade_500	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Eubacterium hallii, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N505	CDAD,T2D	6	7	71.4	85.7	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_466, (clade_478 or clade_478i), clade_485, (clade_98 or clade_98i)	Dorea formicigenerans, Faecalibacterium prausnitzii, Holdemania filiformis, Odoribacter splanchnicus, Ruminococcus lactaris, Streptococcus vestibularis, Subdoligranulum variabile	Dorea formicigenerans, Faecalibacterium prausnitzii, Holdemania filiformis, Odoribacter splanchnicus, Ruminococcus lactaris, Subdoligranulum variabile

N506	CDAD,T2D	6	7	71.4	85.7	clade_168, (clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), clade_500	Alistipes putredinis, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Prevotella copri, Roseburia inulinivorans	Alistipes putredinis, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Roseburia inulinivorans
N507	CDAD,T2D	6	7	85.7	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_85	Bacteroides cellulosilyticus, Coprococcus comes, Dorea formicigenerans, Eubacterium hallii, Faecalibacterium prausnitzii, Roseburia inulinivorans, Subdoligranulum variabile	Bacteroides cellulosilyticus, Coprococcus comes, Dorea formicigenerans, Eubacterium hallii, Faecalibacterium prausnitzii, Roseburia inulinivorans, Subdoligranulum variabile
N508	CDAD	5	6	100	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), (clade_478 or clade_478i)	Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques	Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques

N509	CDAD	6	6	100	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), (clade_478 or clade_478i), clade_519	Dorea longicatena, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Dorea longicatena, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N510	CDAD	6	6	100	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), (clade_478 or clade_478i), (clade_522 or clade_522i)	Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N511	CDAD	4	6	100	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), (clade_478 or clade_478i)	Coprococcus comes, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques	Coprococcus comes, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques

N512	CDAD	4	6	100	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i)	Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium rectale, Ruminococcus obeum, Ruminococcus torques	Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium rectale, Ruminococcus obeum, Ruminococcus torques
N513	CDAD	5	6	100	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), (clade_478 or clade_478i)	Coprococcus comes, Dorea formicigenerans, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Coprococcus comes, Dorea formicigenerans, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N514	CDAD	6	6	50	50	(clade_378 or clade_378e), clade_393, (clade_420 or clade_420f), (clade_444 or clade_444i), (clade_522 or clade_522i), clade_558	Bacteroides sp. 3_1_40A, Clostridiales bacterium oral clone P4PA, Coprococcus catus, Eubacterium eligens, Eubacterium rectale, Tannerella sp. 6_1_58FAA_CT1	Coprococcus catus, Eubacterium eligens, Eubacterium rectale
N515	CDAD	6	6	50	66.7	(clade_378 or clade_378e), clade_393, (clade_444 or clade_444i), clade_521, (clade_522 or clade_522i),	Bacteroides sp. 3_1_40A, Bilophila wadsworthia, Citrobacter sp. 30_2, Coprococcus catus, Eubacterium eligens, Eubacterium rectale	Bilophila wadsworthia, Coprococcus catus, Eubacterium eligens, Eubacterium rectale

						(clade_92 or clade_92e or clade_92i)		
N516	CDAD	6	6	50	83.3	(clade_378 or clade_378e), clade_393, (clade_444 or clade_444i), clade_445, clade_521, (clade_522 or clade_522i)	Bacteroides sp. 3_1_40A, Bilophila wadsworthia, Coprococcus catus, Desulfovibrio desulfuricans, Eubacterium eligens, Eubacterium rectale	Bilophila wadsworthia, Coprococcus catus, Desulfovibrio desulfuricans, Eubacterium eligens, Eubacterium rectale
N517	CDAD	6	6	83.3	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500	Alistipes shahii, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Alistipes shahii, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N518	CDAD,T2D	6	6	100	83.3	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_354 or clade_354e), clade_396, (clade_444 or clade_444i), clade_494	Clostridium bartlettii, Eubacterium hallii, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Eubacterium hallii, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques

N519	CDAD,T2D	6	6	83.3	83.3	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_401, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_494	Eubacterium rectale, Faecalibacterium prausnitzii, Lactococcus lactis, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N520	CDAD,T2D	6	6	83.3	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_478 or clade_478i), clade_494, clade_537, (clade_566 or clade_566f)	Clostridium leptum, Faecalibacterium prausnitzii, Gordonibacter pamelaeae, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Clostridium leptum, Faecalibacterium prausnitzii, Gordonibacter pamelaeae, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N521	CDAD,T2D	6	6	83.3	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_393, (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i)	Coprococcus catus, Desulfovibrio desulfuricans, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques	Coprococcus catus, Desulfovibrio desulfuricans, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques
N522	T2D	6	6	66.7	50	(clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), clade_466, clade_494,	Clostridium symbiosum, Clostridium thermocellum, Eubacterium siraeum, Heliobacterium modesticaldum, Odoribacter splanchnicus,	Eubacterium siraeum, Odoribacter splanchnicus, Pseudoflavonifractor capillosus

						clade_495, clade_538, clade_560	Pseudoflavonifractor capillosus	
N523	CDAD,T2D	5	6	83.3	83.3	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_432, (clade_444 or clade_444i), (clade_478 or clade_478i)	Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques, Sutterella wadsworthensis	Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques
N524	CDAD,T2D	5	6	83.3	83.3	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_38 or clade_38e or clade_38i)8, clade_466, (clade_478 or clade_478i)	Dorea formicigenerans, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Ruminococcus lactaris, Solobacterium moorei, Subdoligranulum variabile	Dorea formicigenerans, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Ruminococcus lactaris, Subdoligranulum variabile
N525	CDAD,T2D	5	6	83.3	66.7	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), clade_445, clade_494	Anaerostipes caccae, Clostridium bolteae, Desulfovibrio desulfuricans, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Desulfovibrio desulfuricans, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques

N526	CDAD,T2D	5	6	83.3	83.3	(clade_262 or clade_262i), clade_271, (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i)	Coprococcus comes, Dorea longicatena, Eubacterium hallii, Roseburia intestinalis, Roseburia inulinivorans, Rothia mucilaginosa	Coprococcus comes, Dorea longicatena, Eubacterium hallii, Roseburia intestinalis, Roseburia inulinivorans
N527	CDAD,T2D	5	6	50	83.3	(clade_172 or clade_172i), (clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, clade_500	Alistipes putredinis, Alistipes shahii, Bifidobacterium pseudocatenulatum, Coprococcus comes, Dorea longicatena, Eubacterium hallii	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea longicatena, Eubacterium hallii
N528	CDAD,T2D	6	6	66.7	83.3	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), clade_445, clade_494, clade_500	Alistipes shahii, Clostridium symbiosum, Desulfovibrio desulfuricans, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Alistipes shahii, Desulfovibrio desulfuricans, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N529	CDAD,T2D	6	6	83.3	83.3	(clade_172 or clade_172i), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or	Bifidobacterium pseudocatenulatum, Dorea formicigenerans, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Dorea formicigenerans, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques

						clade_360c or clade_360g or clade_360h or clade_360i), (clade_478 or clade_478i), clade_494		
N530	CDAD,T2D	5	6	50	83.3	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), clade_500, (clade_98 or clade_98i)	Alistipes putredinis, Alistipes shahii, Eubacterium rectale, Ruminococcus obeum, Ruminococcus torques, Streptococcus australis	Alistipes putredinis, Alistipes shahii, Eubacterium rectale, Ruminococcus obeum, Ruminococcus torques
N531	CDAD,T2D	6	6	83.3	83.3	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_401, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_494	Eubacterium rectale, Faecalibacterium prausnitzii, Lactococcus lactis, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N532	CDAD,T2D	6	6	100	83.3	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_354 or clade_354e), clade_396, (clade_444 or	Clostridium bartlettii, Eubacterium hallii, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Eubacterium hallii, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques

						clade_444i), clade_494		
N533	CDAD,T2D	5	6	83.3	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), clade_445, clade_494	Clostridium nexile, Desulfovibrio desulfuricans, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Clostridium nexile, Desulfovibrio desulfuricans, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N534	CDAD,T2D	6	6	66.7	83.3	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500, (clade_65 or clade_65e)	Alistipes shahii, Bacteroides fragilis, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Alistipes shahii, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N535	CDAD,T2D	5	6	83.3	100	clade_358, (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i)	Dorea formicigenerans, Eubacterium hallii, Faecalibacterium prausnitzii, Roseburia inulinivorans, Subdoligranulum variabile, Veillonella atypica	Dorea formicigenerans, Eubacterium hallii, Faecalibacterium prausnitzii, Roseburia inulinivorans, Subdoligranulum variabile, Veillonella atypica

N536	CDAD,T2D	5	6	50	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_358, (clade_444 or clade_444i), clade_500	Alistipes putredinis, Alistipes shahii, Eubacterium rectale, Ruminococcus obeum, Ruminococcus torques, Veillonella atypica	Alistipes putredinis, Alistipes shahii, Eubacterium rectale, Ruminococcus obeum, Ruminococcus torques, Veillonella atypica
N537	CDAD,T2D	6	6	83.3	83.3	(clade_260 or clade_260c or clade_260g or clade_260h), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), clade_445, clade_494	Clostridium scindens, Desulfovibrio desulfuricans, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Desulfovibrio desulfuricans, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N538	CDAD,T2D	6	6	66.7	83.3	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), clade_445, clade_494, clade_500	Alistipes shahii, Clostridium hathewayi, Desulfovibrio desulfuricans, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Alistipes shahii, Desulfovibrio desulfuricans, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques

N539	CDAD,T2D	5	6	66.7	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_358, (clade_444 or clade_444i), clade_500	Alistipes shahii, Eubacterium rectale, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques, Veillonella parvula	Alistipes shahii, Eubacterium rectale, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques, Veillonella parvula
N540	CDAD,T2D	6	6	83.3	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_478 or clade_478i), clade_494, clade_537, (clade_566 or clade_566f)	Clostridium leptum, Faecalibacterium prausnitzii, Gordonibacter pamelaeae, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Clostridium leptum, Faecalibacterium prausnitzii, Gordonibacter pamelaeae, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N541	CDAD,T2D	6	6	100	83.3	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_478 or clade_478i), clade_494	Clostridium asparagiforme, Dorea formicigenerans, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Dorea formicigenerans, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques

N542	CDAD,T2D	5	6	50	83.3	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), clade_500, clade_88	Alistipes putredinis, Alistipes shahii, Eubacterium rectale, Haemophilus parainfluenzae, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Eubacterium rectale, Ruminococcus obeum, Ruminococcus torques
N543	CDAD,T2D	6	6	100	83.3	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_354 or clade_354e), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_478 or clade_478i), clade_494	Clostridium bartlettii, Dorea formicigenerans, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Dorea formicigenerans, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N544	CDAD,T2D	6	6	83.3	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_393, (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i)	Coprococcus catus, Desulfovibrio desulfuricans, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques	Coprococcus catus, Desulfovibrio desulfuricans, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus obeum, Ruminococcus torques
N545	CDAD,T2D	5	6	100	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or	Coprococcus comes, Dorea longicatena, Eubacterium hallii, Eubacterium siraeum, Roseburia intestinalis, Roseburia inulinivorans	Coprococcus comes, Dorea longicatena, Eubacterium hallii, Eubacterium siraeum, Roseburia intestinalis, Roseburia

						clade_360i), clade_396, (clade_444 or clade_444i), clade_538		inulinivorans
N546	CDAD,T2D	5	6	83.3	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500	Alistipes shahii, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus lactaris, Ruminococcus obeum, Ruminococcus torques	Alistipes shahii, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus lactaris, Ruminococcus obeum, Ruminococcus torques
N547	CDAD,T2D	5	6	100	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), (clade_478 or clade_478i)	Dorea formicigenerans, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Dorea formicigenerans, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile
N548	CDAD	6	6	66.7	83.3	(clade_262 or clade_262i), clade_299, (clade_38 or clade_38e or clade_38i), (clade_444 or clade_444i), (clade_478 or clade_478i), clade_494	Bacteroides xylanisolvens, Eubacterium rectale, Faecalibacterium prausnitzii, Propionibacterium acnes, Pseudoflavonifractor capillosus, Ruminococcus torques	Bacteroides xylanisolvens, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus torques

N549	CDAD,T2D	5	6	83.3	83.3	(clade_262 or clade_262i), clade_271, (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i)	Coprococcus comes, Dorea longicatena, Eubacterium hallii, Roseburia intestinalis, Roseburia inulinivorans, Rothia mucilaginosa	Coprococcus comes, Dorea longicatena, Eubacterium hallii, Roseburia intestinalis, Roseburia inulinivorans
N550	CDAD,T2D	5	6	50	83.3	(clade_172 or clade_172i), (clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, clade_500	Alistipes putredinis, Alistipes shahii, Bifidobacterium pseudocatenulatum, Coprococcus comes, Dorea longicatena, Eubacterium hallii	Alistipes putredinis, Alistipes shahii, Coprococcus comes, Dorea longicatena, Eubacterium hallii
N551	CDAD,T2D	6	6	83.3	83.3	(clade_172 or clade_172i), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_478 or clade_478i), clade_494	Bifidobacterium pseudocatenulatum, Dorea formicigenerans, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Dorea formicigenerans, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N552	CDAD,T2D	5	6	50	83.3	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i),	Alistipes putredinis, Alistipes shahii, Eubacterium rectale, Ruminococcus obeum, Ruminococcus torques, Streptococcus australis	Alistipes putredinis, Alistipes shahii, Eubacterium rectale, Ruminococcus obeum, Ruminococcus torques

						clade_500, (clade_98 or clade_98i)		
N553	CDAD,T2D	5	6	83.3	83.3	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_432, (clade_444 or clade_444i), (clade_478 or clade_478i)	Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques, Sutterella wadsworthensis	Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques
N554	CDAD,T2D	5	6	83.3	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), clade_445, clade_494	Clostridium nexile, Desulfovibrio desulfuricans, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Clostridium nexile, Desulfovibrio desulfuricans, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N555	CDAD,T2D	6	6	66.7	83.3	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500, (clade_65 or clade_65e)	Alistipes shahii, Bacteroides fragilis, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Alistipes shahii, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques

N556	CDAD,T2D	5	6	50	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_358, (clade_444 or clade_444i), clade_500	Alistipes putredinis, Alistipes shahii, Eubacterium rectale, Ruminococcus obeum, Ruminococcus torques, Veillonella atypica	Alistipes putredinis, Alistipes shahii, Eubacterium rectale, Ruminococcus obeum, Ruminococcus torques, Veillonella atypica
N557	CDAD,T2D	6	6	83.3	83.3	(clade_260 or clade_260c or clade_260g or clade_260h), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), clade_445, clade_494	Clostridium scindens, Desulfovibrio desulfuricans, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Desulfovibrio desulfuricans, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N558	CDAD,T2D	5	6	66.7	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_358, (clade_444 or clade_444i), clade_500	Alistipes shahii, Eubacterium rectale, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques, Veillonella parvula	Alistipes shahii, Eubacterium rectale, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques, Veillonella parvula

N559	CDAD,T2D	6	6	100	83.3	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_478 or clade_478i), clade_494	Clostridium asparagiforme, Dorea formicigenerans, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Dorea formicigenerans, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N560	CDAD,T2D	5	6	50	83.3	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), clade_500, clade_88	Alistipes putredinis, Alistipes shahii, Eubacterium rectale, Haemophilus parainfluenzae, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Eubacterium rectale, Ruminococcus obeum, Ruminococcus torques
N561	CDAD,T2D	6	6	100	83.3	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_354 or clade_354e), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_478 or	Clostridium bartlettii, Dorea formicigenerans, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Dorea formicigenerans, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques

						clade_478i), clade_494		
N562	CDAD,T2D	5	6	100	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), clade_538	Coprococcus comes, Dorea longicatena, Eubacterium hallii, Eubacterium siraeum, Roseburia intestinalis, Roseburia inulinivorans	Coprococcus comes, Dorea longicatena, Eubacterium hallii, Eubacterium siraeum, Roseburia intestinalis, Roseburia inulinivorans
N563	CDAD,T2D	5	6	83.3	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500	Alistipes shahii, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus lactaris, Ruminococcus obeum, Ruminococcus torques	Alistipes shahii, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus lactaris, Ruminococcus obeum, Ruminococcus torques
N564	CDAD,T2D	5	6	100	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i),	Dorea formicigenerans, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile	Dorea formicigenerans, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques, Subdoligranulum variabile

						(clade_478 or clade_478i)		
N565	CDAD,T2D	5	6	83.3	83.3	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_38 or clade_38e or clade_38i)8, clade_466, (clade_478 or clade_478i)	Dorea formicigenerans, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Ruminococcus lactaris, Solobacterium moorei, Subdoligranulum variabile	Dorea formicigenerans, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Ruminococcus lactaris, Subdoligranulum variabile
N566	CDAD,T2D	5	6	83.3	66.7	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), clade_445, clade_494	Anaerostipes caccae, Clostridium bolteae, Desulfovibrio desulfuricans, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Desulfovibrio desulfuricans, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N567	CDAD,T2D	6	6	66.7	83.3	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_408 or clade_408b or clade_408d or	Alistipes shahii, Clostridium symbiosum, Desulfovibrio desulfuricans, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Alistipes shahii, Desulfovibrio desulfuricans, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques

						clade_408f or clade_408g or clade_408h), clade_445, clade_494, clade_500		
N568	CDAD,T2D	5	6	83.3	100	clade_358, (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i)	Dorea formicigenerans, Eubacterium hallii, Faecalibacterium prausnitzii, Roseburia inulinivorans, Subdoligranulum variabile, Veillonella atypica	Dorea formicigenerans, Eubacterium hallii, Faecalibacterium prausnitzii, Roseburia inulinivorans, Subdoligranulum variabile, Veillonella atypica
N569	CDAD,T2D	6	6	66.7	83.3	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), clade_445, clade_494, clade_500	Alistipes shahii, Clostridium hathewayi, Desulfovibrio desulfuricans, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Alistipes shahii, Desulfovibrio desulfuricans, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N570	CDAD,T2D	5	5	80	80	(clade_172 or clade_172i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i),	Bifidobacterium adolescentis, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum	Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum

						(clade_444 or clade_444i), (clade_478 or clade_478i)		
N571	CDAD	5	5	100	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), (clade_478 or clade_478i)	Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N572	CDAD,T2D	5	5	40	100	clade_286, (clade_38 or clade_38e or clade_38i), (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i)	Bacteroides xylanisolvens, Desulfovibrio desulfuricans, Eubacterium rectale, Faecalibacterium prausnitzii, Parabacteroides merdae	Bacteroides xylanisolvens, Desulfovibrio desulfuricans, Eubacterium rectale, Faecalibacterium prausnitzii, Parabacteroides merdae
N573	CDAD	5	5	60	80	(clade_378 or clade_378e), clade_393, (clade_444 or clade_444i), clade_521, (clade_522 or clade_522i)	Bacteroides sp. 3_1_40A, Bilophila wadsworthia, Coprococcus catus, Eubacterium eligens, Eubacterium rectale	Bilophila wadsworthia, Coprococcus catus, Eubacterium eligens, Eubacterium rectale

N574	CDAD,T2D	5	5	80	80	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_396, (clade_478 or clade_478i), clade_537, (clade_98 or clade_98i)	Clostridium leptum, Eubacterium hallii, Faecalibacterium prausnitzii, Ruminococcus obeum, Streptococcus thermophilus	Clostridium leptum, Eubacterium hallii, Faecalibacterium prausnitzii, Ruminococcus obeum
N575	CDAD,T2D	5	5	60	100	clade_170, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i)	Bacteroides caccae, Desulfovibrio desulfuricans, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum	Bacteroides caccae, Desulfovibrio desulfuricans, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum
N576	CDAD,T2D	5	5	40	100	(clade_262 or clade_262i), (clade_38 or clade_38e or clade_38i), clade_445, (clade_478 or clade_478i), clade_85	Bacteroides eggerthii, Bacteroides ovatus, Desulfovibrio desulfuricans, Faecalibacterium prausnitzii, Ruminococcus torques	Bacteroides eggerthii, Bacteroides ovatus, Desulfovibrio desulfuricans, Faecalibacterium prausnitzii, Ruminococcus torques
N577	CDAD,T2D	4	5	80	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_537, clade_567	Clostridium leptum, Coprococcus comes, Dorea longicatena, Ruminococcus torques, Victivallis vadensis	Clostridium leptum, Coprococcus comes, Dorea longicatena, Ruminococcus torques, Victivallis vadensis
N578	CDAD,T2D	5	5	60	80	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i),	Desulfovibrio desulfuricans, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques, Sutterella wadsworthensis	Desulfovibrio desulfuricans, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques

						clade_432, clade_445, (clade_478 or clade_478i)		
N579	CDAD,T2D	5	5	80	80	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_396, (clade_444 or clade_444i), (clade_98 or clade_98i)	Eubacterium hallii, Eubacterium rectale, Ruminococcus obeum, Ruminococcus torques, Streptococcus infantis	Eubacterium hallii, Eubacterium rectale, Ruminococcus obeum, Ruminococcus torques
N580	CDAD,T2D	5	5	80	80	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_396, (clade_444 or clade_444i), (clade_98 or clade_98i)	Eubacterium hallii, Eubacterium rectale, Ruminococcus obeum, Ruminococcus torques, Streptococcus australis	Eubacterium hallii, Eubacterium rectale, Ruminococcus obeum, Ruminococcus torques
N581	CDAD,T2D	5	5	100	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_478 or clade_478i), clade_494, clade_538	Eubacterium siraeum, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Eubacterium siraeum, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques

N582	CDAD	5	5	100	80	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_444 or clade_444i), (clade_478 or clade_478i)	Clostridium symbiosum, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N583	CDAD	5	5	100	0	clade_252, clade_253, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_351 or clade_351e), (clade_354 or clade_354e)	Blautia producta, Clostridium butyricum, Clostridium celatum, Clostridium glycolicum, Clostridium innocuum	
N584	CDAD	5	5	100	20	(clade_260 or clade_260c or clade_260g or clade_260h), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_553 or clade_553i)	Blautia producta, Clostridium symbiosum, Collinsella aerofaciens, Coprococcus comes, Lachnospiraceae bacterium 5_1_57FAA	Coprococcus comes

N585	T2D	3	5	80	80	(clade_444 or clade_444i), (clade_478 or clade_478i), clade_88	Eubacterium rectale, Faecalibacterium prausnitzii, Haemophilus parainfluenzae, Roseburia intestinalis, Roseburia inulinivorans	Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans
N586	CDAD,T2D	3	5	100	80	clade_368, (clade_444 or clade_444i), (clade_478 or clade_478i)	Blautia hydrogenotrophica, Eubacterium rectale, Roseburia intestinalis, Roseburia inulinivorans, Subdoligranulum variabile	Eubacterium rectale, Roseburia intestinalis, Roseburia inulinivorans, Subdoligranulum variabile
N587	CDAD,T2D	5	5	60	80	(clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_466, (clade_478 or clade_478i), clade_500, (clade_516 or clade_516c or clade_516g or clade_516h)	Alistipes putredinis, Clostridium methylpentosum, Dorea formicigenerans, Odoribacter splanchnicus, Subdoligranulum variabile	Alistipes putredinis, Dorea formicigenerans, Odoribacter splanchnicus, Subdoligranulum variabile
N588	CDAD,T2D	5	5	80	60	clade_396, (clade_516 or clade_516c or clade_516g or clade_516h), clade_519, clade_521, clade_538	Bacteroides pectinophilus, Bilophila wadsworthia, Eubacterium siraeum, Eubacterium ventriosum, Ruminococcus albus	Bilophila wadsworthia, Eubacterium siraeum, Eubacterium ventriosum
N589	CDAD,T2D	5	5	80	80	(clade_262 or clade_262i), clade_293, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_478 or	Bifidobacterium bifidum, Dorea formicigenerans, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Dorea formicigenerans, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques

						clade_478i)		
N590	CDAD,T2D	4	5	80	80	(clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_401, (clade_478 or clade_478i), clade_485	Dorea formicigenerans, Faecalibacterium prausnitzii, Holdemania filiformis, Lactococcus lactis, Subdoligranulum variabile	Dorea formicigenerans, Faecalibacterium prausnitzii, Holdemania filiformis, Subdoligranulum variabile
N591	CDAD,T2D	5	5	80	80	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_401, (clade_444 or clade_444i), clade_494	Eubacterium rectale, Lactococcus lactis, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N592	CDAD,T2D	4	5	80	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_537, clade_567	Clostridium leptum, Coprococcus comes, Dorea longicatena, Ruminococcus torques, Victivallis vadensis	Clostridium leptum, Coprococcus comes, Dorea longicatena, Ruminococcus torques, Victivallis vadensis
N593	CDAD,T2D	5	5	80	80	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_396, (clade_444 or	Eubacterium hallii, Eubacterium rectale, Ruminococcus obeum, Ruminococcus torques, Streptococcus infantis	Eubacterium hallii, Eubacterium rectale, Ruminococcus obeum, Ruminococcus torques

						clade_444i), (clade_98 or clade_98i)		
N594	CDAD,T2D	4	5	80	80	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_445, clade_494	Blautia hansenii, Desulfovibrio desulfuricans, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Desulfovibrio desulfuricans, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N595	CDAD,T2D	4	5	60	80	(clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_466, (clade_478 or clade_478i), (clade_98 or clade_98i)	Dorea formicigenerans, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Streptococcus mitis, Subdoligranulum variabile	Dorea formicigenerans, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Subdoligranulum variabile
N596	CDAD,T2D	5	5	60	80	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_432, clade_445, (clade_478 or clade_478i)	Desulfovibrio desulfuricans, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques, Sutterella wadsworthensis	Desulfovibrio desulfuricans, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N597	CDAD,T2D	4	5	80	80	(clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_478 or clade_478i), (clade_522 or clade_522i), (clade_98 or clade_98i)	Dorea formicigenerans, Eubacterium eligens, Faecalibacterium prausnitzii, Streptococcus australis, Subdoligranulum variabile	Dorea formicigenerans, Eubacterium eligens, Faecalibacterium prausnitzii, Subdoligranulum variabile

N598	CDAD,T2D	5	5	80	80	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_396, (clade_444 or clade_444i), (clade_98 or clade_98i)	Eubacterium hallii, Eubacterium rectale, Ruminococcus obeum, Ruminococcus torques, Streptococcus australis	Eubacterium hallii, Eubacterium rectale, Ruminococcus obeum, Ruminococcus torques
N599	CDAD,T2D	5	5	80	80	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_445, clade_494, (clade_566 or clade_566f)	Desulfovibrio desulfuricans, Eggerthella lenta, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Desulfovibrio desulfuricans, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N600	CDAD,T2D	5	5	80	80	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_396, (clade_478 or clade_478i), clade_537, (clade_98 or clade_98i)	Clostridium leptum, Eubacterium hallii, Faecalibacterium prausnitzii, Ruminococcus obeum, Streptococcus thermophilus	Clostridium leptum, Eubacterium hallii, Faecalibacterium prausnitzii, Ruminococcus obeum
N601	CDAD,T2D	5	5	40	100	(clade_262 or clade_262i), (clade_38 or clade_38e or clade_38i), clade_445, (clade_478 or clade_478i), clade_85	Bacteroides eggerthii, Bacteroides ovatus, Desulfovibrio desulfuricans, Faecalibacterium prausnitzii, Ruminococcus torques	Bacteroides eggerthii, Bacteroides ovatus, Desulfovibrio desulfuricans, Faecalibacterium prausnitzii, Ruminococcus torques

N602	CDAD,T2D	5	5	80	100	clade_358, (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i)	Dorea formicigenerans, Eubacterium hallii, Roseburia inulinivorans, Subdoligranulum variabile, Veillonella parvula	Dorea formicigenerans, Eubacterium hallii, Roseburia inulinivorans, Subdoligranulum variabile, Veillonella parvula
N603	CDAD,T2D	5	5	80	80	(clade_172 or clade_172i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), (clade_478 or clade_478i)	Bifidobacterium adolescentis, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum	Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum
N604	CDAD,T2D	5	5	80	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_478 or clade_478i), clade_85	Bacteroides stercoris, Dorea formicigenerans, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Bacteroides stercoris, Dorea formicigenerans, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques

N605	CDAD,T2D	5	5	60	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_478 or clade_478i), clade_500, clade_85	Alistipes shahii, Bacteroides eggerthii, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Alistipes shahii, Bacteroides eggerthii, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N606	CDAD,T2D	5	5	100	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_478 or clade_478i), clade_494, clade_538	Eubacterium siraeum, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Eubacterium siraeum, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N607	CDAD,T2D	5	5	60	100	clade_170, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i)	Bacteroides caccae, Desulfovibrio desulfuricans, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum	Bacteroides caccae, Desulfovibrio desulfuricans, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum
N608	CDAD,T2D	5	5	40	100	clade_286, (clade_38 or clade_38e or clade_38i), (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i)	Bacteroides xylanisolvens, Desulfovibrio desulfuricans, Eubacterium rectale, Faecalibacterium prausnitzii, Parabacteroides merdae	Bacteroides xylanisolvens, Desulfovibrio desulfuricans, Eubacterium rectale, Faecalibacterium prausnitzii, Parabacteroides merdae

N609	CDAD,T2D	5	5	60	100	(clade_262 or clade_262i), clade_286, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), clade_500	Alistipes shahii, Eubacterium rectale, Parabacteroides merdae, Ruminococcus obeum, Ruminococcus torques	Alistipes shahii, Eubacterium rectale, Parabacteroides merdae, Ruminococcus obeum, Ruminococcus torques
N610	CDAD,T2D	5	5	60	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), clade_500, (clade_98 or clade_98i)	Alistipes shahii, Eubacterium rectale, Ruminococcus obeum, Ruminococcus torques, Streptococcus parasanguinis	Alistipes shahii, Eubacterium rectale, Ruminococcus obeum, Ruminococcus torques, Streptococcus parasanguinis
N611	CDAD,T2D	5	5	80	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_378 or clade_378e), (clade_478 or clade_478i)	Bacteroides dorei, Dorea formicigenerans, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Bacteroides dorei, Dorea formicigenerans, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N612	CDAD,T2D	5	5	60	80	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i),	Alistipes shahii, Eubacterium rectale, Ruminococcus obeum, Ruminococcus torques, Streptococcus salivarius	Alistipes shahii, Eubacterium rectale, Ruminococcus obeum, Ruminococcus torques

						(clade_444 or clade_444i), clade_500, (clade_98 or clade_98i)		
N613	CDAD,T2D	5	5	80	80	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_378 or clade_378e), (clade_478 or clade_478i)	Bacteroides vulgatus, Dorea formicigenerans, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Dorea formicigenerans, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N614	CDAD,T2D	5	5	80	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_478 or clade_478i), clade_500, clade_537	Alistipes shahii, Clostridium leptum, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Alistipes shahii, Clostridium leptum, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N615	CDAD,T2D	5	5	80	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_38 or	Bacteroides xylanisolvens, Dorea formicigenerans, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Bacteroides xylanisolvens, Dorea formicigenerans, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques

						clade_38e or clade_38i), (clade_478 or clade_478i)		
N616	CDAD,T2D	4	5	100	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_478 or clade_478i)	Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Faecalibacterium prausnitzii	Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Faecalibacterium prausnitzii
N617	CDAD,T2D	4	5	60	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_500	Alistipes putredinis, Alistipes shahii, Dorea longicatena, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Dorea longicatena, Ruminococcus obeum, Ruminococcus torques
N618	CDAD	5	5	60	80	clade_281, (clade_444 or clade_444i), clade_445, clade_519, clade_537	Clostridium leptum, Desulfovibrio desulfuricans, Eubacterium ventriosum, Porphyromonas asaccharolytica, Roseburia inulinivorans	Clostridium leptum, Desulfovibrio desulfuricans, Eubacterium ventriosum, Roseburia inulinivorans
N619	CDAD,T2D	3	5	100	80	clade_368, (clade_444 or clade_444i), (clade_478 or clade_478i)	Blautia hydrogenotrophica, Eubacterium rectale, Roseburia intestinalis, Roseburia inulinivorans, Subdoligranulum variabile	Eubacterium rectale, Roseburia intestinalis, Roseburia inulinivorans, Subdoligranulum variabile

N620	CDAD,T2D	5	5	80	80	(clade_262 or clade_262i), clade_293, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_478 or clade_478i)	Bifidobacterium bifidum, Dorea formicigenerans, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Dorea formicigenerans, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N621	CDAD	5	5	100	80	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_396, (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_444 or clade_444i), (clade_478 or clade_478i)	Anaerostipes caccae, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum	Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum
N622	CDAD,T2D	5	5	80	80	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_401, (clade_444 or clade_444i), clade_494	Eubacterium rectale, Lactococcus lactis, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques

N623	CDAD	5	5	60	80	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_358, (clade_38 or clade_38e or clade_38i), (clade_444 or clade_444i), (clade_478 or clade_478i)	Bacteroides xylanisolvens, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Veillonella dispar	Bacteroides xylanisolvens, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum
N624	CDAD	5	5	100	80	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_478 or clade_478i), clade_494	Clostridium hathewayi, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N625	CDAD	5	5	60	80	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_38 or clade_38e or clade_38i), (clade_444 or clade_444i), (clade_478 or clade_478i), (clade_98 or clade_98i)	Bacteroides xylanisolvens, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Streptococcus salivarius	Bacteroides xylanisolvens, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum

N626	CDAD	5	5	100	80	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_478 or clade_478i), clade_494, (clade_566 or clade_566f)	Eggerthella lenta, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N627	CDAD,T2D	5	5	80	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_478 or clade_478i), clade_85	Bacteroides stercoris, Dorea formicigenerans, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Bacteroides stercoris, Dorea formicigenerans, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N628	CDAD,T2D	5	5	60	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_478 or clade_478i), clade_500, clade_85	Alistipes shahii, Bacteroides eggerthii, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Alistipes shahii, Bacteroides eggerthii, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques

N629	CDAD	5	5	100	80	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_478 or clade_478i), clade_494	Clostridium asparagiforme, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N630	CDAD,T2D	5	5	60	100	(clade_262 or clade_262i), clade_286, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), clade_500	Alistipes shahii, Eubacterium rectale, Parabacteroides merdae, Ruminococcus obeum, Ruminococcus torques	Alistipes shahii, Eubacterium rectale, Parabacteroides merdae, Ruminococcus obeum, Ruminococcus torques
N631	CDAD,T2D	5	5	60	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), clade_500, (clade_98 or clade_98i)	Alistipes shahii, Eubacterium rectale, Ruminococcus obeum, Ruminococcus torques, Streptococcus parasanguinis	Alistipes shahii, Eubacterium rectale, Ruminococcus obeum, Ruminococcus torques, Streptococcus parasanguinis

N632	CDAD,T2D	5	5	80	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_378 or clade_378e), (clade_478 or clade_478i)	Bacteroides dorei, Dorea formicigenerans, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Bacteroides dorei, Dorea formicigenerans, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N633	CDAD,T2D	5	5	60	80	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), clade_500, (clade_98 or clade_98i)	Alistipes shahii, Eubacterium rectale, Ruminococcus obeum, Ruminococcus torques, Streptococcus salivarius	Alistipes shahii, Eubacterium rectale, Ruminococcus obeum, Ruminococcus torques
N634	CDAD,T2D	5	5	80	80	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_378 or clade_378e), (clade_478 or clade_478i)	Bacteroides vulgatus, Dorea formicigenerans, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Dorea formicigenerans, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques

N635	CDAD,T2D	5	5	80	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_478 or clade_478i), clade_500, clade_537	Alistipes shahii, Clostridium leptum, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Alistipes shahii, Clostridium leptum, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N636	CDAD,T2D	5	5	80	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_38 or clade_38e or clade_38i), (clade_478 or clade_478i)	Bacteroides xylanisolvens, Dorea formicigenerans, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Bacteroides xylanisolvens, Dorea formicigenerans, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N637	CDAD,T2D	4	5	100	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_478 or clade_478i)	Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Faecalibacterium prausnitzii	Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium hallii, Faecalibacterium prausnitzii
N638	CDAD,T2D	4	5	60	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or	Alistipes putredinis, Alistipes shahii, Dorea longicatena, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Dorea longicatena, Ruminococcus obeum, Ruminococcus torques

						clade_360g or clade_360h or clade_360i), clade_500		
N639	CDAD,T2D	5	5	60	80	(clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_466, (clade_478 or clade_478i), clade_500, (clade_516 or clade_516c or clade_516g or clade_516h)	Alistipes putredinis, Clostridium methylpentosum, Dorea formicigenerans, Odoribacter splanchnicus, Subdoligranulum variabile	Alistipes putredinis, Dorea formicigenerans, Odoribacter splanchnicus, Subdoligranulum variabile
N640	CDAD,T2D	5	5	80	60	clade_396, (clade_516 or clade_516c or clade_516g or clade_516h), clade_519, clade_521, clade_538	Bacteroides pectinophilus, Bilophila wadsworthia, Eubacterium siraeum, Eubacterium ventriosum, Ruminococcus albus	Bilophila wadsworthia, Eubacterium siraeum, Eubacterium ventriosum
N641	CDAD,T2D	4	5	80	80	(clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_401, (clade_478 or clade_478i), clade_485	Dorea formicigenerans, Faecalibacterium prausnitzii, Holdemania filiformis, Lactococcus lactis, Subdoligranulum variabile	Dorea formicigenerans, Faecalibacterium prausnitzii, Holdemania filiformis, Subdoligranulum variabile
N642	CDAD,T2D	4	5	80	80	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_445, clade_494	Blautia hansenii, Desulfovibrio desulfuricans, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Desulfovibrio desulfuricans, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques

N643	CDAD,T2D	4	5	60	80	(clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_466, (clade_478 or clade_478i), (clade_98 or clade_98i)	Dorea formicigenerans, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Streptococcus mitis, Subdoligranulum variabile	Dorea formicigenerans, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Subdoligranulum variabile
N644	CDAD,T2D	4	5	80	80	(clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_478 or clade_478i), (clade_522 or clade_522i), (clade_98 or clade_98i)	Dorea formicigenerans, Eubacterium eligens, Faecalibacterium prausnitzii, Streptococcus australis, Subdoligranulum variabile	Dorea formicigenerans, Eubacterium eligens, Faecalibacterium prausnitzii, Subdoligranulum variabile
N645	CDAD,T2D	5	5	80	80	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_445, clade_494, (clade_566 or clade_566f)	Desulfovibrio desulfuricans, Eggerthella lenta, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Desulfovibrio desulfuricans, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N646	CDAD,T2D	5	5	80	100	clade_358, (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i)	Dorea formicigenerans, Eubacterium hallii, Roseburia inulinivorans, Subdoligranulum variabile, Veillonella parvula	Dorea formicigenerans, Eubacterium hallii, Roseburia inulinivorans, Subdoligranulum variabile, Veillonella parvula

N647	CDAD	4	4	100	100	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), (clade_478 or clade_478i)	Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum	Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum
N648	CDAD,T2D	4	4	100	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_478 or clade_478i)	Dorea longicatena, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Dorea longicatena, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N649	CDAD,T2D	4	4	50	100	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_378 or clade_378e), (clade_444 or clade_444i), clade_445	Bacteroides dorei, Desulfovibrio desulfuricans, Eubacterium rectale, Ruminococcus obeum	Bacteroides dorei, Desulfovibrio desulfuricans, Eubacterium rectale, Ruminococcus obeum
N650	CDAD	4	4	75	50	clade_368, (clade_378 or clade_378e), (clade_444 or clade_444i), (clade_522 or clade_522i)	Bacteroides sp. 3_1_40A, Blautia hydrogenotrophica, Eubacterium eligens, Eubacterium rectale	Eubacterium eligens, Eubacterium rectale

N651	CDAD,T2D	4	4	75	50	(clade_172 or clade_172i), (clade_444 or clade_444i), (clade_516 or clade_516c or clade_516g or clade_516h), (clade_522 or clade_522i)	Anaerotruncus colihominis, Bifidobacterium catenulatum, Eubacterium eligens, Roseburia inulinivorans	Eubacterium eligens, Roseburia inulinivorans
N652	CDAD	4	4	75	75	(clade_378 or clade_378e), clade_393, (clade_444 or clade_444i), (clade_522 or clade_522i)	Bacteroides sp. 3_1_40A, Coprococcus catus, Eubacterium eligens, Eubacterium rectale	Coprococcus catus, Eubacterium eligens, Eubacterium rectale
N653	CDAD,T2D	4	4	100	75	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_396, (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_444 or clade_444i)	Anaerostipes caccae, Eubacterium hallii, Eubacterium rectale, Ruminococcus obeum	Eubacterium hallii, Eubacterium rectale, Ruminococcus obeum
N654	CDAD,T2D	4	4	100	75	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), (clade_478 or clade_478i), (clade_516 or clade_516c or clade_516g or clade_516h)	Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus albus, Ruminococcus obeum	Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum

N655	CDAD,T2D	3	4	100	100	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), (clade_478 or clade_478i)	Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Subdoligranulum variabile	Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Subdoligranulum variabile
N656	CDAD	4	4	75	75	clade_170, (clade_262 or clade_262i), clade_396, clade_537	Bacteroides caccae, Bacteroides pectinophilus, Clostridium leptum, Ruminococcus lactaris	Bacteroides caccae, Clostridium leptum, Ruminococcus lactaris
N657	CDAD,T2D	3	4	25	100	(clade_378 or clade_378e), (clade_38 or clade_38e or clade_38i), (clade_478 or clade_478i)	Bacteroides dorei, Bacteroides ovatus, Bacteroides xylanisolvens, Faecalibacterium prausnitzii	Bacteroides dorei, Bacteroides ovatus, Bacteroides xylanisolvens, Faecalibacterium prausnitzii
N658	CDAD,T2D	4	4	50	100	(clade_262 or clade_262i), clade_445, (clade_478 or clade_478i), clade_85	Bacteroides stercoris, Desulfovibrio desulfuricans, Faecalibacterium prausnitzii, Ruminococcus torques	Bacteroides stercoris, Desulfovibrio desulfuricans, Faecalibacterium prausnitzii, Ruminococcus torques
N659	CDAD,T2D	3	4	25	100	clade_171, (clade_478 or clade_478i), clade_500	Alistipes putredinis, Alistipes shahii, Bacteroides intestinalis, Faecalibacterium prausnitzii	Alistipes putredinis, Alistipes shahii, Bacteroides intestinalis, Faecalibacterium prausnitzii
N660	CDAD	3	4	25	75	(clade_172 or clade_172i), clade_466, clade_485	Bifidobacterium longum, Bifidobacterium pseudocatenulatum, Holdemania filiformis, Odoribacter splanchnicus	Bifidobacterium longum, Holdemania filiformis, Odoribacter splanchnicus
N661	CDAD,T2D,UC	4	4	0	100	clade_110, clade_170, clade_567, clade_85	Bacteroides finegoldii, Bacteroides stercoris, Bacteroides uniformis, Victivallis vadensis	Bacteroides finegoldii, Bacteroides stercoris, Bacteroides uniformis, Victivallis vadensis
N662	CDAD,T2D	3	4	50	75	clade_110, (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i),	Bacteroides uniformis, Dorea formicigenerans, Dorea longicatena, Sutterella wadsworthensis	Bacteroides uniformis, Dorea formicigenerans, Dorea longicatena

						clade_432		
N663	CDAD,T2D	4	4	50	75	clade_110, (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), (clade_98 or clade_98i)	Bacteroides uniformis, Dorea longicatena, Roseburia inulinivorans, Streptococcus sanguinis	Bacteroides uniformis, Dorea longicatena, Roseburia inulinivorans
N664	CDAD	4	4	75	75	(clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_378 or clade_378e), (clade_516 or clade_516c or clade_516g or clade_516h), clade_519	Bacteroides dorei, Clostridium methylpentosum, Dorea longicatena, Eubacterium ventriosum	Bacteroides dorei, Dorea longicatena, Eubacterium ventriosum
N665	CDAD,T2D	3	4	50	100	clade_286, (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i)	Dorea formicigenerans, Parabacteroides johnsonii, Parabacteroides merdae, Roseburia intestinalis	Dorea formicigenerans, Parabacteroides johnsonii, Parabacteroides merdae, Roseburia intestinalis
N666	CDAD	4	4	75	75	(clade_444 or clade_444i), clade_476, clade_521, (clade_522 or clade_522i)	Bilophila wadsworthia, Eubacterium eligens, Eubacterium nodatum, Eubacterium rectale	Bilophila wadsworthia, Eubacterium eligens, Eubacterium rectale
N667	CDAD,T2D	3	4	25	100	clade_500, (clade_522 or clade_522i), clade_567	Alistipes putredinis, Alistipes shahii, Eubacterium eligens, Victivallis vadensis	Alistipes putredinis, Alistipes shahii, Eubacterium eligens, Victivallis vadensis
N668	CDAD,T2D	3	4	0	100	clade_286, (clade_378 or clade_378e), clade_500	Alistipes putredinis, Alistipes shahii, Bacteroides dorei, Parabacteroides johnsonii	Alistipes putredinis, Alistipes shahii, Bacteroides dorei, Parabacteroides johnsonii

N669	CDAD	4	4	50	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_466, clade_85	Bacteroides eggerthii, Coprococcus comes, Dorea longicatena, Odoribacter splanchnicus	Bacteroides eggerthii, Coprococcus comes, Dorea longicatena, Odoribacter splanchnicus
N670	CDAD	4	4	50	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_466, clade_85	Bacteroides stercoris, Coprococcus comes, Dorea longicatena, Odoribacter splanchnicus	Bacteroides stercoris, Coprococcus comes, Dorea longicatena, Odoribacter splanchnicus
N671	CDAD	4	4	50	100	clade_170, (clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_466	Bacteroides finegoldii, Coprococcus comes, Dorea longicatena, Odoribacter splanchnicus	Bacteroides finegoldii, Coprococcus comes, Dorea longicatena, Odoribacter splanchnicus
N672	CDAD,T2D	4	4	75	75	(clade_262 or clade_262i), clade_299, (clade_444 or clade_444i), clade_494	Eubacterium rectale, Propionibacterium acnes, Pseudoflavonifractor capillosus, Ruminococcus torques	Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus torques
N673	CDAD,T2D	3	4	100	100	(clade_262 or clade_262i), (clade_444 or clade_444i), (clade_478 or clade_478i)	Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus lactaris, Ruminococcus torques	Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus lactaris, Ruminococcus torques
N674	CDAD,T2D	4	4	75	100	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_445, (clade_478 or clade_478i), clade_519	Desulfovibrio desulfuricans, Eubacterium ventriosum, Faecalibacterium prausnitzii, Ruminococcus obeum	Desulfovibrio desulfuricans, Eubacterium ventriosum, Faecalibacterium prausnitzii, Ruminococcus obeum

N675	CDAD,T2D	4	4	50	100	(clade_262 or clade_262i), (clade_38 or clade_38e or clade_38i), (clade_478 or clade_478i), (clade_65 or clade_65e)	Bacteroides ovatus, Bacteroides thetaiotaomicron, Faecalibacterium prausnitzii, Ruminococcus torques	Bacteroides ovatus, Bacteroides thetaiotaomicron, Faecalibacterium prausnitzii, Ruminococcus torques
N676	CDAD,T2D	4	4	100	75	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_494, (clade_566 or clade_566f)	Eggerthella lenta, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N677	CDAD,T2D	4	4	100	75	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), clade_494	Clostridium hathewayi, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N678	CDAD,T2D	4	4	50	100	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_445, (clade_478 or clade_478i), clade_583	Akkermansia muciniphila, Desulfovibrio desulfuricans, Faecalibacterium prausnitzii, Ruminococcus obeum	Akkermansia muciniphila, Desulfovibrio desulfuricans, Faecalibacterium prausnitzii, Ruminococcus obeum

N679	CDAD,T2D	4	4	100	75	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), clade_494	Clostridium asparagiforme, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N680	CDAD,T2D	4	4	100	75	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_368, (clade_478 or clade_478i)	Blautia hydrogenotrophica, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N681	CDAD,T2D	3	4	100	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_478 or clade_478i)	Coprococcus comes, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Coprococcus comes, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N682	CDAD	4	4	75	100	clade_170, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), (clade_478 or clade_478i)	Bacteroides caccae, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum	Bacteroides caccae, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum

N683	CDAD	4	4	50	100	(clade_262 or clade_262i), (clade_38 or clade_38e or clade_38i), (clade_478 or clade_478i), clade_85	Bacteroides eggerthii, Bacteroides ovatus, Faecalibacterium prausnitzii, Ruminococcus torques	Bacteroides eggerthii, Bacteroides ovatus, Faecalibacterium prausnitzii, Ruminococcus torques
N684	CDAD,T2D,UC	4	4	0	100	clade_110, clade_170, clade_567, clade_85	Bacteroides finegoldii, Bacteroides stercoris, Bacteroides uniformis, Victivallis vadensis	Bacteroides finegoldii, Bacteroides stercoris, Bacteroides uniformis, Victivallis vadensis
N685	Obesity	4	4	25	100	clade_170, clade_286, clade_469, (clade_65 or clade_65e)	Bacteroides caccae, Bacteroides thetaiotaomicron, Catenibacterium mitsuokai, Parabacteroides merdae	Bacteroides caccae, Bacteroides thetaiotaomicron, Catenibacterium mitsuokai, Parabacteroides merdae
N686	Obesity	4	4	25	100	(clade_378 or clade_378e), (clade_38 or clade_38e or clade_38i), clade_445, clade_485	Bacteroides dorei, Bacteroides ovatus, Desulfovibrio piger, Holdemania filiformis	Bacteroides dorei, Bacteroides ovatus, Desulfovibrio piger, Holdemania filiformis
N687	T2D	4	4	100	50	clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_543	Bacteroides pectinophilus, Coprococcus eutactus, Faecalibacterium prausnitzii, Roseburia intestinalis	Faecalibacterium prausnitzii, Roseburia intestinalis
N688	CDAD,T2D	4	4	75	50	(clade_172 or clade_172i), (clade_444 or clade_444i), (clade_516 or clade_516c or clade_516g or clade_516h), (clade_522 or clade_522i)	Anaerotruncus colihominis, Bifidobacterium catenulatum, Eubacterium eligens, Roseburia inulinivorans	Eubacterium eligens, Roseburia inulinivorans
N689	CDAD,T2D	4	4	100	75	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i), (clade_516 or clade_516c or clade_516g or clade_516h)	Clostridium methylpentosum, Coprococcus comes, Eubacterium hallii, Roseburia inulinivorans	Coprococcus comes, Eubacterium hallii, Roseburia inulinivorans

N690	CDAD,T2D	4	4	100	75	(clade_262 or clade_262i), (clade_38 or clade_38e or clade_38i)8, clade_396, (clade_444 or clade_444i)	Coprococcus comes, Eubacterium hallii, Roseburia inulinivorans, Solobacterium moorei	Coprococcus comes, Eubacterium hallii, Roseburia inulinivorans
N691	CDAD,T2D	4	4	75	75	(clade_262 or clade_262i), clade_299, (clade_444 or clade_444i), clade_494	Eubacterium rectale, Propionibacterium acnes, Pseudoflavonifractor capillosus, Ruminococcus torques	Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus torques
N692	CDAD,T2D	4	4	75	75	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, clade_556	Acidaminococcus fermentans, Coprococcus comes, Dorea longicatena, Eubacterium hallii	Coprococcus comes, Dorea longicatena, Eubacterium hallii
N693	CDAD,T2D	4	4	75	75	(clade_262 or clade_262i), clade_396, clade_401, (clade_444 or clade_444i)	Coprococcus comes, Eubacterium hallii, Lactococcus lactis, Roseburia inulinivorans	Coprococcus comes, Eubacterium hallii, Roseburia inulinivorans
N694	CDAD,T2D	4	4	100	75	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_396, (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_444 or clade_444i)	Anaerostipes caccae, Eubacterium hallii, Eubacterium rectale, Ruminococcus obeum	Eubacterium hallii, Eubacterium rectale, Ruminococcus obeum
N695	CDAD,T2D	4	4	50	25	(clade_378 or clade_378e), clade_396, (clade_516 or clade_516c or clade_516g or	Bacteroides vulgatus, Eubacterium hallii, Methanobrevibacter smithii, Ruminococcus albus	Eubacterium hallii

						clade_516h), clade_588		
N696	CDAD,T2D	4	4	75	75	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i), (clade_98 or clade_98i)	Coprococcus comes, Eubacterium hallii, Roseburia inulinivorans, Streptococcus vestibularis	Coprococcus comes, Eubacterium hallii, Roseburia inulinivorans
N697	CDAD,T2D,UC	4	4	0	100	clade_110, clade_170, clade_567, clade_85	Bacteroides finegoldii, Bacteroides stercoris, Bacteroides uniformis, Victivallis vadensis	Bacteroides finegoldii, Bacteroides stercoris, Bacteroides uniformis, Victivallis vadensis
N698	CDAD,T2D	3	4	75	75	(clade_172 or clade_172i), (clade_444 or clade_444i), (clade_478 or clade_478i)	Bifidobacterium catenulatum, Eubacterium rectale, Roseburia intestinalis, Subdoligranulum variabile	Eubacterium rectale, Roseburia intestinalis, Subdoligranulum variabile
N699	CDAD,T2D	3	4	25	100	clade_500, (clade_522 or clade_522i), clade_567	Alistipes putredinis, Alistipes shahii, Eubacterium eligens, Victivallis vadensis	Alistipes putredinis, Alistipes shahii, Eubacterium eligens, Victivallis vadensis
N700	CDAD,T2D	4	4	50	75	clade_110, (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), (clade_98 or clade_98i)	Bacteroides uniformis, Dorea longicatena, Roseburia inulinivorans, Streptococcus sanguinis	Bacteroides uniformis, Dorea longicatena, Roseburia inulinivorans
N701	CDAD,T2D	3	4	75	75	(clade_172 or clade_172i), (clade_444 or clade_444i), (clade_478 or clade_478i)	Bifidobacterium pseudocatenulatum, Eubacterium rectale, Roseburia intestinalis, Subdoligranulum variabile	Eubacterium rectale, Roseburia intestinalis, Subdoligranulum variabile
N702	CDAD,T2D	3	4	0	100	clade_286, (clade_378 or clade_378e), clade_500	Alistipes putredinis, Alistipes shahii, Bacteroides dorei, Parabacteroides johnsonii	Alistipes putredinis, Alistipes shahii, Bacteroides dorei, Parabacteroides johnsonii

N703	CDAD,T2D	4	4	100	75	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_478 or clade_478i), clade_485	Blautia hansenii, Dorea formicigenerans, Faecalibacterium prausnitzii, Holdemania filiformis	Dorea formicigenerans, Faecalibacterium prausnitzii, Holdemania filiformis
N704	CDAD,T2D	3	4	50	100	clade_286, (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i)	Dorea formicigenerans, Parabacteroides johnsonii, Parabacteroides merdae, Roseburia intestinalis	Dorea formicigenerans, Parabacteroides johnsonii, Parabacteroides merdae, Roseburia intestinalis
N705	CDAD,T2D	4	4	75	75	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i), (clade_98 or clade_98i)	Coprococcus comes, Eubacterium hallii, Roseburia inulinivorans, Streptococcus mitis	Coprococcus comes, Eubacterium hallii, Roseburia inulinivorans
N706	CDAD,T2D	3	4	50	75	clade_110, (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_432	Bacteroides uniformis, Dorea formicigenerans, Dorea longicatena, Sutterella wadsworthensis	Bacteroides uniformis, Dorea formicigenerans, Dorea longicatena
N707	CDAD,T2D	4	4	100	75	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_368, (clade_478 or clade_478i)	Blautia hydrogenotrophica, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques

N708	CDAD,T2D	4	4	100	75	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), clade_494	Clostridium hathewayi, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N709	CDAD,T2D	4	4	75	100	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i), (clade_566 or clade_566f)	Coprococcus comes, Eubacterium hallii, Gordonibacter pamelaeae, Roseburia inulinivorans	Coprococcus comes, Eubacterium hallii, Gordonibacter pamelaeae, Roseburia inulinivorans
N710	CDAD,T2D	4	4	50	100	(clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_478 or clade_478i), clade_500, (clade_566 or clade_566f)	Alistipes putredinis, Dorea formicigenerans, Gordonibacter pamelaeae, Subdoligranulum variabile	Alistipes putredinis, Dorea formicigenerans, Gordonibacter pamelaeae, Subdoligranulum variabile
N711	CDAD,T2D	3	4	25	100	clade_171, (clade_478 or clade_478i), clade_500	Alistipes putredinis, Alistipes shahii, Bacteroides intestinalis, Faecalibacterium prausnitzii	Alistipes putredinis, Alistipes shahii, Bacteroides intestinalis, Faecalibacterium prausnitzii
N712	CDAD,T2D	3	4	100	75	(clade_260 or clade_260c or clade_260g or clade_260h), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_478 or clade_478i)	Clostridium scindens, Dorea formicigenerans, Faecalibacterium prausnitzii, Subdoligranulum variabile	Dorea formicigenerans, Faecalibacterium prausnitzii, Subdoligranulum variabile

N713	CDAD,T2D	4	4	100	75	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_494, (clade_566 or clade_566f)	Eggerthella lenta, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N714	CDAD,T2D	3	4	75	75	(clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_478 or clade_478i), (clade_98 or clade_98i)	Dorea formicigenerans, Faecalibacterium prausnitzii, Streptococcus thermophilus, Subdoligranulum variabile	Dorea formicigenerans, Faecalibacterium prausnitzii, Subdoligranulum variabile
N715	CDAD,T2D	4	4	50	100	clade_170, (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_500	Alistipes shahii, Bacteroides finegoldii, Ruminococcus obeum, Ruminococcus torques	Alistipes shahii, Bacteroides finegoldii, Ruminococcus obeum, Ruminococcus torques
N716	CDAD,T2D	4	4	100	75	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), clade_494	Clostridium bolteae, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N717	CDAD,T2D	3	4	75	75	(clade_360 or clade_360c or clade_360g or clade_360h or clade_360i),	Dorea formicigenerans, Faecalibacterium prausnitzii, Haemophilus parainfluenzae,	Dorea formicigenerans, Faecalibacterium prausnitzii, Subdoligranulum variabile

						(clade_478 or clade_478i), clade_88	Subdoligranulum variabile	
N718	CDAD,T2D	4	4	50	100	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_445, (clade_478 or clade_478i), clade_583	Akkermansia muciniphila, Desulfovibrio desulfuricans, Faecalibacterium prausnitzii, Ruminococcus obeum	Akkermansia muciniphila, Desulfovibrio desulfuricans, Faecalibacterium prausnitzii, Ruminococcus obeum
N719	CDAD,T2D	4	4	100	75	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), clade_494	Clostridium asparagiforme, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N720	CDAD,T2D	4	4	50	100	(clade_262 or clade_262i), clade_445, (clade_478 or clade_478i), clade_85	Bacteroides stercoris, Desulfovibrio desulfuricans, Faecalibacterium prausnitzii, Ruminococcus torques	Bacteroides stercoris, Desulfovibrio desulfuricans, Faecalibacterium prausnitzii, Ruminococcus torques
N721	CDAD,T2D	3	4	25	100	(clade_378 or clade_378e), (clade_38 or clade_38e or clade_38i), (clade_478 or clade_478i)	Bacteroides dorei, Bacteroides ovatus, Bacteroides xylanisolvens, Faecalibacterium prausnitzii	Bacteroides dorei, Bacteroides ovatus, Bacteroides xylanisolvens, Faecalibacterium prausnitzii

N722	CDAD,T2D	4	4	100	75	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), (clade_478 or clade_478i), (clade_516 or clade_516c or clade_516g or clade_516h)	Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus albus, Ruminococcus obeum	Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum
N723	CDAD,T2D	4	4	50	100	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_378 or clade_378e), (clade_444 or clade_444i), clade_445	Bacteroides dorei, Desulfovibrio desulfuricans, Eubacterium rectale, Ruminococcus obeum	Bacteroides dorei, Desulfovibrio desulfuricans, Eubacterium rectale, Ruminococcus obeum
N724	CDAD,T2D	3	4	100	100	(clade_262 or clade_262i), (clade_444 or clade_444i), (clade_478 or clade_478i)	Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus lactaris, Ruminococcus torques	Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus lactaris, Ruminococcus torques
N725	CDAD,T2D	4	4	75	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_65 or clade_65e)	Bacteroides thetaiotaomicron, Coprococcus comes, Dorea longicatena, Eubacterium hallii	Bacteroides thetaiotaomicron, Coprococcus comes, Dorea longicatena, Eubacterium hallii
N726	CDAD,T2D	4	4	50	100	(clade_262 or clade_262i), (clade_38 or clade_38e or clade_38i), (clade_478 or clade_478i), (clade_65 or clade_65e)	Bacteroides ovatus, Bacteroides thetaiotaomicron, Faecalibacterium prausnitzii, Ruminococcus torques	Bacteroides ovatus, Bacteroides thetaiotaomicron, Faecalibacterium prausnitzii, Ruminococcus torques

N727	CDAD,T2D	4	4	75	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_478 or clade_478i), (clade_65 or clade_65e)	Bacteroides thetaiotaomicron, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Bacteroides thetaiotaomicron, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N728	CDAD,T2D	4	4	75	75	(clade_172 or clade_172i), (clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396	Bifidobacterium adolescentis, Coprococcus comes, Dorea longicatena, Eubacterium hallii	Coprococcus comes, Dorea longicatena, Eubacterium hallii
N729	CDAD,T2D	4	4	75	75	(clade_172 or clade_172i), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_478 or clade_478i)	Bifidobacterium adolescentis, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N730	CDAD,T2D	4	4	75	100	(clade_262 or clade_262i), clade_286, clade_396, (clade_444 or clade_444i)	Coprococcus comes, Eubacterium hallii, Parabacteroides merdae, Roseburia inulinivorans	Coprococcus comes, Eubacterium hallii, Parabacteroides merdae, Roseburia inulinivorans
N731	CDAD,T2D	4	4	75	100	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_445, (clade_478 or clade_478i), clade_519	Desulfovibrio desulfuricans, Eubacterium ventriosum, Faecalibacterium prausnitzii, Ruminococcus obeum	Desulfovibrio desulfuricans, Eubacterium ventriosum, Faecalibacterium prausnitzii, Ruminococcus obeum

N732	CDAD,T2D	3	4	100	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_478 or clade_478i)	Coprococcus comes, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Coprococcus comes, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N733	CDAD,T2D	4	4	50	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_38 or clade_38e or clade_38i), clade_500	Alistipes shahii, Bacteroides ovatus, Ruminococcus obeum, Ruminococcus torques	Alistipes shahii, Bacteroides ovatus, Ruminococcus obeum, Ruminococcus torques
N734	CDAD,T2D	4	4	50	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_500, clade_521	Alistipes shahii, Bilophila wadsworthia, Ruminococcus obeum, Ruminococcus torques	Alistipes shahii, Bilophila wadsworthia, Ruminococcus obeum, Ruminococcus torques
N735	CDAD,T2D	3	4	100	100	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), (clade_478 or clade_478i)	Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Subdoligranulum variabile	Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Subdoligranulum variabile

N736	CDAD,T2D	4	4	100	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_478 or clade_478i)	Dorea longicatena, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Dorea longicatena, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N737	CDAD,T2D	4	4	100	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_393, (clade_444 or clade_444i)	Coprococcus catus, Eubacterium rectale, Ruminococcus obeum, Ruminococcus torques	Coprococcus catus, Eubacterium rectale, Ruminococcus obeum, Ruminococcus torques
N738	CDAD,T2D	4	4	100	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_478 or clade_478i), clade_485	Faecalibacterium prausnitzii, Holdemania filiformis, Ruminococcus obeum, Ruminococcus torques	Faecalibacterium prausnitzii, Holdemania filiformis, Ruminococcus obeum, Ruminococcus torques
N739	CDAD,T2D	3	4	50	100	(clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_478 or clade_478i), clade_500	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Faecalibacterium prausnitzii	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Faecalibacterium prausnitzii

N740	CDAD,T2D	3	4	100	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i)	Eubacterium rectale, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques	Eubacterium rectale, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques
N741	CDAD,T2D	3	4	50	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_500	Alistipes putredinis, Alistipes shahii, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Ruminococcus obeum, Ruminococcus torques
N742	CDAD,T2D	4	4	100	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_478 or clade_478i)	Dorea formicigenerans, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Dorea formicigenerans, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N743	CDAD,T2D	4	4	50	100	clade_170, (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_500	Alistipes shahii, Bacteroides finegoldii, Ruminococcus obeum, Ruminococcus torques	Alistipes shahii, Bacteroides finegoldii, Ruminococcus obeum, Ruminococcus torques

N744	CDAD	4	4	75	100	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_358, (clade_444 or clade_444i), (clade_478 or clade_478i)	Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Veillonella parvula	Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Veillonella parvula
N745	CDAD,T2D	4	4	75	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_65 or clade_65e)	Bacteroides thetaiotaomicron, Coprococcus comes, Dorea longicatena, Eubacterium hallii	Bacteroides thetaiotaomicron, Coprococcus comes, Dorea longicatena, Eubacterium hallii
N746	CDAD,T2D	4	4	75	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_478 or clade_478i), (clade_65 or clade_65e)	Bacteroides thetaiotaomicron, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Bacteroides thetaiotaomicron, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N747	CDAD,T2D	4	4	75	75	(clade_172 or clade_172i), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_478 or clade_478i)	Bifidobacterium adolescentis, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques

N748	CDAD,T2D	4	4	50	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_38 or clade_38e or clade_38i), clade_500	Alistipes shahii, Bacteroides ovatus, Ruminococcus obeum, Ruminococcus torques	Alistipes shahii, Bacteroides ovatus, Ruminococcus obeum, Ruminococcus torques
N749	CDAD,T2D	4	4	50	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_500, clade_521	Alistipes shahii, Bilophila wadsworthia, Ruminococcus obeum, Ruminococcus torques	Alistipes shahii, Bilophila wadsworthia, Ruminococcus obeum, Ruminococcus torques
N750	CDAD,T2D	4	4	100	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_393, (clade_444 or clade_444i)	Coprococcus catus, Eubacterium rectale, Ruminococcus obeum, Ruminococcus torques	Coprococcus catus, Eubacterium rectale, Ruminococcus obeum, Ruminococcus torques
N751	CDAD,T2D	4	4	100	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_478 or clade_478i), clade_485	Faecalibacterium prausnitzii, Holdemania filiformis, Ruminococcus obeum, Ruminococcus torques	Faecalibacterium prausnitzii, Holdemania filiformis, Ruminococcus obeum, Ruminococcus torques
N752	CDAD,T2D	3	4	50	100	(clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_478 or	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Faecalibacterium prausnitzii	Alistipes putredinis, Alistipes shahii, Dorea formicigenerans, Faecalibacterium prausnitzii

						clade_478i), clade_500		
N753	CDAD,T2D	3	4	100	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i)	Eubacterium rectale, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques	Eubacterium rectale, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques
N754	CDAD,T2D	3	4	50	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_500	Alistipes putredinis, Alistipes shahii, Ruminococcus obeum, Ruminococcus torques	Alistipes putredinis, Alistipes shahii, Ruminococcus obeum, Ruminococcus torques
N755	CDAD,T2D	4	4	100	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_478 or clade_478i)	Dorea formicigenerans, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Dorea formicigenerans, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N756	CDAD,T2D	4	4	100	75	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i), (clade_516 or clade_516c or clade_516g or clade_516h)	Clostridium methylpentosum, Coprococcus comes, Eubacterium hallii, Roseburia inulinivorans	Coprococcus comes, Eubacterium hallii, Roseburia inulinivorans

N757	CDAD,T2D	4	4	100	75	(clade_262 or clade_262i), (clade_38 or clade_38e or clade_38i)8, clade_396, (clade_444 or clade_444i)	Coprococcus comes, Eubacterium hallii, Roseburia inulinivorans, Solobacterium moorei	Coprococcus comes, Eubacterium hallii, Roseburia inulinivorans
N758	CDAD,T2D	4	4	75	75	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, clade_556	Acidaminococcus fermentans, Coprococcus comes, Dorea longicatena, Eubacterium hallii	Coprococcus comes, Dorea longicatena, Eubacterium hallii
N759	CDAD,T2D	4	4	75	75	(clade_262 or clade_262i), clade_396, clade_401, (clade_444 or clade_444i)	Coprococcus comes, Eubacterium hallii, Lactococcus lactis, Roseburia inulinivorans	Coprococcus comes, Eubacterium hallii, Roseburia inulinivorans
N760	CDAD,T2D	4	4	75	75	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i), (clade_98 or clade_98i)	Coprococcus comes, Eubacterium hallii, Roseburia inulinivorans, Streptococcus vestibularis	Coprococcus comes, Eubacterium hallii, Roseburia inulinivorans
N761	CDAD,T2D	3	4	75	75	(clade_172 or clade_172i), (clade_444 or clade_444i), (clade_478 or clade_478i)	Bifidobacterium catenulatum, Eubacterium rectale, Roseburia intestinalis, Subdoligranulum variabile	Eubacterium rectale, Roseburia intestinalis, Subdoligranulum variabile
N762	CDAD,T2D	3	4	75	75	(clade_172 or clade_172i), (clade_444 or clade_444i), (clade_478 or clade_478i)	Bifidobacterium pseudocatenulatum, Eubacterium rectale, Roseburia intestinalis, Subdoligranulum variabile	Eubacterium rectale, Roseburia intestinalis, Subdoligranulum variabile

N763	CDAD,T2D	4	4	100	75	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_478 or clade_478i), clade_485	Blautia hansenii, Dorea formicigenerans, Faecalibacterium prausnitzii, Holdemania filiformis	Dorea formicigenerans, Faecalibacterium prausnitzii, Holdemania filiformis
N764	CDAD,T2D	4	4	75	75	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i), (clade_98 or clade_98i)	Coprococcus comes, Eubacterium hallii, Roseburia inulinivorans, Streptococcus mitis	Coprococcus comes, Eubacterium hallii, Roseburia inulinivorans
N765	CDAD,T2D	4	4	75	100	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i), (clade_566 or clade_566f)	Coprococcus comes, Eubacterium hallii, Gordonibacter pamelaeae, Roseburia inulinivorans	Coprococcus comes, Eubacterium hallii, Gordonibacter pamelaeae, Roseburia inulinivorans
N766	CDAD,T2D	4	4	50	100	(clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_478 or clade_478i), clade_500, (clade_566 or clade_566f)	Alistipes putredinis, Dorea formicigenerans, Gordonibacter pamelaeae, Subdoligranulum variabile	Alistipes putredinis, Dorea formicigenerans, Gordonibacter pamelaeae, Subdoligranulum variabile
N767	CDAD,T2D	3	4	100	75	(clade_260 or clade_260c or clade_260g or clade_260h), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_478 or clade_478i)	Clostridium scindens, Dorea formicigenerans, Faecalibacterium prausnitzii, Subdoligranulum variabile	Dorea formicigenerans, Faecalibacterium prausnitzii, Subdoligranulum variabile

N768	CDAD,T2D	3	4	75	75	(clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_478 or clade_478i), (clade_98 or clade_98i)	Dorea formicigenerans, Faecalibacterium prausnitzii, Streptococcus thermophilus, Subdoligranulum variabile	Dorea formicigenerans, Faecalibacterium prausnitzii, Subdoligranulum variabile
N769	CDAD	4	4	100	75	(clade_260 or clade_260c or clade_260g or clade_260h), (clade_262 or clade_262i), (clade_478 or clade_478i), clade_494	Clostridium scindens, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus torques	Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus torques
N770	CDAD,T2D	4	4	100	75	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), clade_494	Clostridium bolteae, Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N771	CDAD,T2D	3	4	75	75	(clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_478 or clade_478i), clade_88	Dorea formicigenerans, Faecalibacterium prausnitzii, Haemophilus parainfluenzae, Subdoligranulum variabile	Dorea formicigenerans, Faecalibacterium prausnitzii, Subdoligranulum variabile
N772	CDAD,T2D	4	4	75	75	(clade_172 or clade_172i), (clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i),	Bifidobacterium adolescentis, Coprococcus comes, Dorea longicatena, Eubacterium hallii	Coprococcus comes, Dorea longicatena, Eubacterium hallii

						clade_396		
N773	CDAD,T2D	4	4	75	100	(clade_262 or clade_262i), clade_286, clade_396, (clade_444 or clade_444i)	Coprococcus comes, Eubacterium hallii, Parabacteroides merdae, Roseburia inulinivorans	Coprococcus comes, Eubacterium hallii, Parabacteroides merdae, Roseburia inulinivorans
N774	CDAD,T2D	3	3	100	100	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_478 or clade_478i)	Dorea formicigenerans, Faecalibacterium prausnitzii, Ruminococcus obeum	Dorea formicigenerans, Faecalibacterium prausnitzii, Ruminococcus obeum
N775	CDAD,T2D	3	3	66.7	100	(clade_262 or clade_262i), clade_286, clade_396	Coprococcus comes, Eubacterium hallii, Parabacteroides johnsonii	Coprococcus comes, Eubacterium hallii, Parabacteroides johnsonii
N776	CDAD,T2D	3	3	66.7	33.3	(clade_172 or clade_172i), (clade_516 or clade_516c or clade_516g or clade_516h), clade_538	Bifidobacterium catenulatum, Eubacterium siraeum, Ruminococcus albus	Eubacterium siraeum
N777	CDAD,T2D	3	3	66.7	66.7	clade_358, (clade_444 or clade_444i), clade_519	Eubacterium ventriosum, Roseburia inulinivorans, Veillonella dispar	Eubacterium ventriosum, Roseburia inulinivorans
N778	CDAD,T2D	3	3	66.7	66.7	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_358, (clade_444 or clade_444i)	Eubacterium rectale, Ruminococcus obeum, Veillonella dispar	Eubacterium rectale, Ruminococcus obeum

N779	CDAD,T2D	3	3	66.7	66.7	(clade_444 or clade_444i), (clade_478 or clade_478i), (clade_98 or clade_98i)	Faecalibacterium prausnitzii, Roseburia intestinalis, Streptococcus australis	Faecalibacterium prausnitzii, Roseburia intestinalis
N780	CDAD,T2D	3	3	66.7	66.7	(clade_444 or clade_444i), (clade_478 or clade_478i), (clade_98 or clade_98i)	Faecalibacterium prausnitzii, Roseburia intestinalis, Streptococcus infantis	Faecalibacterium prausnitzii, Roseburia intestinalis
N781	CDAD	3	3	66.7	66.7	clade_293, clade_393, (clade_444 or clade_444i)	Bifidobacterium bifidum, Coprococcus catus, Eubacterium rectale	Coprococcus catus, Eubacterium rectale
N782	CDAD,T2D	3	3	66.7	100	clade_171, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_522 or clade_522i)	Bacteroides intestinalis, Eubacterium eligens, Ruminococcus obeum	Bacteroides intestinalis, Eubacterium eligens, Ruminococcus obeum
N783	CDAD,T2D	3	3	66.7	100	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_358, (clade_444 or clade_444i)	Eubacterium rectale, Ruminococcus obeum, Veillonella parvula	Eubacterium rectale, Ruminococcus obeum, Veillonella parvula
N784	CDAD,T2D	3	3	66.7	100	clade_170, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i)	Bacteroides finegoldii, Eubacterium rectale, Ruminococcus obeum	Bacteroides finegoldii, Eubacterium rectale, Ruminococcus obeum
N785	CDAD,T2D	3	3	100	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i),	Coprococcus comes, Dorea longicatena, Eubacterium ventriosum	Coprococcus comes, Dorea longicatena, Eubacterium ventriosum

						clade_519		
N786	CDAD	3	3	100	100	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), (clade_478 or clade_478i)	Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum	Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum
N787	CDAD	3	3	33.3	66.7	clade_110, (clade_378 or clade_378e), clade_537	Bacteroides coprocola, Bacteroides uniformis, Clostridium leptum	Bacteroides uniformis, Clostridium leptum
N788	CDAD	1	3	100	0	(clade_516 or clade_516c or clade_516g or clade_516h)	Anaerotruncus colihominis, Clostridium methylpentosum, Ruminococcus albus	
N789	CDAD	3	3	66.7	100	(clade_262 or clade_262i), clade_357, clade_537	Clostridium leptum, Oxalobacter formigenes, Ruminococcus lactaris	Clostridium leptum, Oxalobacter formigenes, Ruminococcus lactaris
N790	CDAD,T2D	3	3	33.3	66.7	clade_358, (clade_38 or clade_38e or clade_38i), (clade_478 or clade_478i)	Bacteroides xylanisolvens, Faecalibacterium prausnitzii, Veillonella dispar	Bacteroides xylanisolvens, Faecalibacterium prausnitzii
N791	CDAD,T2D	3	3	33.3	66.7	clade_299, (clade_38 or clade_38e or clade_38i), (clade_478 or clade_478i)	Bacteroides xylanisolvens, Faecalibacterium prausnitzii, Propionibacterium acnes	Bacteroides xylanisolvens, Faecalibacterium prausnitzii
N792	CDAD,T2D	3	3	100	66.7	(clade_444 or clade_444i), (clade_478 or clade_478i), (clade_516 or clade_516c or clade_516g or clade_516h)	Clostridium methylpentosum, Eubacterium rectale, Subdoligranulum variabile	Eubacterium rectale, Subdoligranulum variabile
N793	CDAD,T2D	3	3	66.7	33.3	clade_504, (clade_516 or	Anaerotruncus colihominis,	Clostridium leptum

						clade_516c or clade_516g or clade_516h), clade_537	Campylobacter hominis, Clostridium leptum	
N794	CDAD,T2D	3	3	100	33.3	(clade_516 or clade_516c or clade_516g or clade_516h), clade_537, clade_543	Anaerotruncus colihominis, Clostridium leptum, Coprococcus eutactus	Clostridium leptum
N795	CDAD,T2D	2	3	33.3	66.7	clade_500, (clade_516 or clade_516c or clade_516g or clade_516h)	Alistipes putredinis, Alistipes shahii, Clostridium methylpentosum	Alistipes putredinis, Alistipes shahii
N796	CDAD,T2D	2	3	33.3	100	clade_500, clade_537	Alistipes putredinis, Alistipes shahii, Ruminococcus bromii	Alistipes putredinis, Alistipes shahii, Ruminococcus bromii
N797	CDAD,T2D	3	3	33.3	66.7	(clade_38 or clade_38e or clade_38i), (clade_478 or clade_478i), (clade_98 or clade_98i)	Bacteroides xylanisolvens, Faecalibacterium prausnitzii, Streptococcus salivarius	Bacteroides xylanisolvens, Faecalibacterium prausnitzii
N798	CDAD,T2D	3	3	33.3	66.7	(clade_378 or clade_378e), clade_494, clade_588	Bacteroides dorei, Methanobrevibacter smithii, Pseudoflavonifractor capillosus	Bacteroides dorei, Pseudoflavonifractor capillosus
N799	CDAD	2	3	0	66.7	(clade_38 or clade_38e or clade_38i), clade_556	Acidaminococcus fermentans, Bacteroides ovatus, Bacteroides xylanisolvens	Bacteroides ovatus, Bacteroides xylanisolvens
N800	CDAD,T2D	3	3	33.3	66.7	clade_299, clade_445, clade_537	Clostridium leptum, Desulfovibrio desulfuricans, Propionibacterium acnes	Clostridium leptum, Desulfovibrio desulfuricans
N801	CDAD,T2D	3	3	33.3	66.7	clade_281, clade_445, clade_537	Clostridium leptum, Desulfovibrio desulfuricans, Porphyromonas asaccharolytica	Clostridium leptum, Desulfovibrio desulfuricans
N802	CDAD,T2D	3	3	100	66.7	(clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), clade_485,	Anaerostipes caccae, Clostridium leptum, Holdemania filiformis	Clostridium leptum, Holdemania filiformis

						clade_537		
N803	CDAD,T2D	3	3	0	66.7	(clade_38 or clade_38e or clade_38i), clade_432, clade_500	Alistipes shahii, Bacteroides xylanisolvens, Sutterella wadsworthensis	Alistipes shahii, Bacteroides xylanisolvens
N804	CDAD,T2D	3	3	100	66.7	clade_485, clade_494, clade_543	Coprococcus eutactus, Holdemania filiformis, Pseudoflavonifractor capillosus	Holdemania filiformis, Pseudoflavonifractor capillosus
N805	CDAD,T2D	3	3	33.3	66.7	clade_293, (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_445	Bifidobacterium bifidum, Desulfovibrio desulfuricans, Dorea formicigenerans	Desulfovibrio desulfuricans, Dorea formicigenerans
N806	CDAD,T2D	3	3	33.3	66.7	(clade_172 or clade_172i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_445	Bifidobacterium catenulatum, Desulfovibrio desulfuricans, Dorea formicigenerans	Desulfovibrio desulfuricans, Dorea formicigenerans
N807	CDAD,T2D	3	3	100	66.7	(clade_262 or clade_262i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_478 or clade_478i)	Anaerostipes caccae, Coprococcus comes, Subdoligranulum variabile	Coprococcus comes, Subdoligranulum variabile
N808	CDAD,T2D	3	3	66.7	66.7	(clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_445, (clade_516 or clade_516c or clade_516g or clade_516h)	Clostridium methylpentosum, Desulfovibrio desulfuricans, Dorea formicigenerans	Desulfovibrio desulfuricans, Dorea formicigenerans

N809	CDAD,T2D	3	3	66.7	66.7	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_445, (clade_478 or clade_478i)	Blautia hansenii, Desulfovibrio desulfuricans, Faecalibacterium prausnitzii	Desulfovibrio desulfuricans, Faecalibacterium prausnitzii
N810	CDAD,T2D	3	3	33.3	66.7	(clade_172 or clade_172i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_445	Bifidobacterium adolescentis, Desulfovibrio desulfuricans, Dorea formicigenerans	Desulfovibrio desulfuricans, Dorea formicigenerans
N811	CDAD,T2D	3	3	66.7	66.7	(clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_445, (clade_516 or clade_516c or clade_516g or clade_516h)	Desulfovibrio desulfuricans, Dorea formicigenerans, Ruminococcus albus	Desulfovibrio desulfuricans, Dorea formicigenerans
N812	CDAD,T2D	3	3	66.7	100	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_85	Bacteroides eggerthii, Dorea formicigenerans, Ruminococcus obeum	Bacteroides eggerthii, Dorea formicigenerans, Ruminococcus obeum
N813	CDAD,T2D	3	3	66.7	100	clade_286, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h	Dorea formicigenerans, Parabacteroides merdae, Ruminococcus obeum	Dorea formicigenerans, Parabacteroides merdae, Ruminococcus obeum

						clade_360i)		
N814	CDAD,T2D	3	3	66.7	100	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_85	Bacteroides stercoris, Dorea formicigenerans, Ruminococcus obeum	Bacteroides stercoris, Dorea formicigenerans, Ruminococcus obeum
N815	CDAD,T2D	3	3	66.7	33.3	(clade_172 or clade_172i), (clade_522 or clade_522i), (clade_553 or clade_553i)	Bifidobacterium catenulatum, Collinsella aerofaciens, Eubacterium eligens	Eubacterium eligens
N816	CDAD	3	3	33.3	66.7	(clade_38 or clade_38e or clade_38i), (clade_522 or clade_522i), (clade_98 or clade_98i)	Bacteroides ovatus, Eubacterium eligens, Streptococcus vestibularis	Bacteroides ovatus, Eubacterium eligens
N817	CDAD	3	3	66.7	66.7	clade_519, clade_537, (clade_98 or clade_98i)	Clostridium leptum, Eubacterium ventriosum, Streptococcus vestibularis	Clostridium leptum, Eubacterium ventriosum
N818	CDAD,T2D	3	3	33.3	100	clade_357, (clade_38 or clade_38e or clade_38i), clade_396	Bacteroides ovatus, Eubacterium hallii, Oxalobacter formigenes	Bacteroides ovatus, Eubacterium hallii, Oxalobacter formigenes
N819	CDAD,T2D	2	3	0	100	clade_500, clade_85	Alistipes putredinis, Alistipes shahii, Bacteroides eggerthii	Alistipes putredinis, Alistipes shahii, Bacteroides eggerthii
N820	CDAD,T2D	2	3	0	66.7	clade_168, clade_500	Alistipes putredinis, Alistipes shahii, Prevotella copri	Alistipes putredinis, Alistipes shahii
N821	CDAD,T2D	2	3	0	66.7	clade_500, (clade_98 or	Alistipes putredinis, Alistipes shahii,	Alistipes putredinis, Alistipes shahii

						clade_98i)	Streptococcus sanguinis	
N822	CDAD,T2D	2	3	0	66.7	clade_401, clade_500	Alistipes putredinis, Alistipes shahii, Lactococcus lactis	Alistipes putredinis, Alistipes shahii
N823	CDAD,T2D	2	3	0	66.7	clade_299, clade_500	Alistipes putredinis, Alistipes shahii, Propionibacterium acnes	Alistipes putredinis, Alistipes shahii
N824	CDAD,T2D	3	3	0	66.7	(clade_172 or clade_172i), (clade_38 or clade_38e or clade_38i), clade_521	Bacteroides xylanisolvens, Bifidobacterium catenulatum, Bilophila wadsworthia	Bacteroides xylanisolvens, Bilophila wadsworthia
N825	CDAD	3	3	66.7	100	(clade_444 or clade_444i), clade_521, (clade_522 or clade_522i)	Bilophila wadsworthia, Eubacterium eligens, Eubacterium rectale	Bilophila wadsworthia, Eubacterium eligens, Eubacterium rectale
N826	CDAD,T2D	2	3	33.3	66.7	clade_500, clade_543	Alistipes putredinis, Alistipes shahii, Coprococcus eutactus	Alistipes putredinis, Alistipes shahii
N827	CDAD	3	3	66.7	66.7	(clade_378 or clade_378e), (clade_444 or clade_444i), (clade_522 or clade_522i)	Bacteroides sp. 3_1_40A, Eubacterium eligens, Eubacterium rectale	Eubacterium eligens, Eubacterium rectale
N828	CDAD	3	3	66.7	66.7	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_98 or clade_98i)	Coprococcus comes, Dorea longicatena, Streptococcus australis	Coprococcus comes, Dorea longicatena
N829	CDAD,T2D	3	3	66.7	66.7	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_65 or clade_65e)	Bacteroides fragilis, Coprococcus comes, Dorea longicatena	Coprococcus comes, Dorea longicatena
N830	CDAD	3	3	33.3	66.7	(clade_262 or clade_262i), clade_466, (clade_98 or	Coprococcus comes, Odoribacter splanchnicus, Streptococcus	Coprococcus comes, Odoribacter splanchnicus

						clade_98i)	thermophilus	
N831	CDAD,T2D	3	3	33.3	66.7	(clade_172 or clade_172i), clade_396, clade_500	Alistipes shahii, Bifidobacterium pseudocatenulatum, Eubacterium hallii	Alistipes shahii, Eubacterium hallii
N832	CDAD,T2D	3	3	33.3	66.7	clade_293, (clade_38 or clade_38e or clade_38i), (clade_478 or clade_478i)	Bacteroides xylanisolvens, Bifidobacterium bifidum, Subdoligranulum variabile	Bacteroides xylanisolvens, Subdoligranulum variabile
N833	CDAD	3	3	66.7	66.7	(clade_260 or clade_260c or clade_260g or clade_260h), (clade_262 or clade_262i), clade_466	Clostridium scindens, Coprococcus comes, Odoribacter splanchnicus	Coprococcus comes, Odoribacter splanchnicus
N834	CDAD,T2D	2	3	0	100	clade_500, (clade_98 or clade_98i)	Alistipes putredinis, Alistipes shahii, Streptococcus parasanguinis	Alistipes putredinis, Alistipes shahii, Streptococcus parasanguinis
N835	CDAD,T2D	2	3	0	100	clade_500, (clade_566 or clade_566f)	Alistipes putredinis, Alistipes shahii, Gordonibacter pamelaeae	Alistipes putredinis, Alistipes shahii, Gordonibacter pamelaeae
N836	CDAD	3	3	100	66.7	(clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_478 or clade_478i), clade_494	Pseudoflavonifractor capillosus, Ruminococcus gnavus, Subdoligranulum variabile	Pseudoflavonifractor capillosus, Subdoligranulum variabile
N837	CDAD	3	3	66.7	66.7	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_88	Coprococcus comes, Dorea longicatena, Haemophilus parainfluenzae	Coprococcus comes, Dorea longicatena
N838	CDAD,T2D	3	3	33.3	100	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or	Alistipes shahii, Bacteroides cellulosilyticus, Ruminococcus obeum	Alistipes shahii, Bacteroides cellulosilyticus, Ruminococcus obeum

						clade_309i), clade_500, clade_85		
N839	CDAD,T2D	3	3	33.3	66.7	(clade_335 or clade_335i), clade_445, (clade_478 or clade_478i)	Desulfovibrio desulfuricans, Faecalibacterium prausnitzii, Parabacteroides distasonis	Desulfovibrio desulfuricans, Faecalibacterium prausnitzii
N840	CDAD,T2D	3	3	66.7	66.7	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), (clade_98 or clade_98i)	Eubacterium rectale, Ruminococcus obeum, Streptococcus salivarius	Eubacterium rectale, Ruminococcus obeum
N841	CDAD,T2D	3	3	100	100	(clade_262 or clade_262i), (clade_478 or clade_478i), clade_537	Faecalibacterium prausnitzii, Ruminococcus bromii, Ruminococcus torques	Faecalibacterium prausnitzii, Ruminococcus bromii, Ruminococcus torques
N842	CDAD,T2D	2	3	33.3	100	clade_393, clade_500	Alistipes putredinis, Alistipes shahii, Coprococcus catus	Alistipes putredinis, Alistipes shahii, Coprococcus catus
N843	CDAD,T2D	2	3	33.3	100	(clade_262 or clade_262i), clade_500	Alistipes putredinis, Alistipes shahii, Coprococcus comes	Alistipes putredinis, Alistipes shahii, Coprococcus comes
N844	CDAD	3	3	66.7	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_521	Bilophila wadsworthia, Coprococcus comes, Dorea longicatena	Bilophila wadsworthia, Coprococcus comes, Dorea longicatena
N845	CDAD,T2D	3	3	66.7	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_378 or clade_378e)	Bacteroides dorei, Coprococcus comes, Dorea longicatena	Bacteroides dorei, Coprococcus comes, Dorea longicatena

N846	CDAD,T2D	3	3	66.7	100	clade_170, (clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h clade_360i)	Bacteroides caccae, Coprococcus comes, Dorea longicatena	Bacteroides caccae, Coprococcus comes, Dorea longicatena
N847	CDAD,T2D	3	3	100	100	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), (clade_478 or clade_478i)	Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus obeum	Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus obeum
N848	CDAD	3	3	66.7	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_466	Coprococcus comes, Dorea longicatena, Odoribacter splanchnicus	Coprococcus comes, Dorea longicatena, Odoribacter splanchnicus
N849	CDAD	3	3	100	66.7	(clade_444 or clade_444i), (clade_481 or clade_481a or clade_481b or clade_481e or clade_481g or clade_481h or clade_481i), (clade_522 or clade_522i)	Clostridium cocleatum, Eubacterium eligens, Eubacterium rectale	Eubacterium eligens, Eubacterium rectale
N850	CDAD	3	3	100	0	(clade_351 or clade_351e), (clade_354 or clade_354e), (clade_481 or clade_481a or clade_481b or clade_481e or clade_481g or clade_481h or clade_481i)	Clostridium bifermentans, Clostridium innocuum, Clostridium ramosum	

N851	CDAD	3	3	0	66.7	clade_445, clade_521, clade_556	Acidaminococcus fermentans, Bilophila wadsworthia, Desulfovibrio desulfuricans	Bilophila wadsworthia, Desulfovibrio desulfuricans
N852	CDAD,T2D	3	3	66.7	100	(clade_172 or clade_172i), (clade_262 or clade_262i), (clade_478 or clade_478i)	Bifidobacterium longum, Faecalibacterium prausnitzii, Ruminococcus torques	Bifidobacterium longum, Faecalibacterium prausnitzii, Ruminococcus torques
N853	CDAD	3	3	100	100	(clade_262 or clade_262i), (clade_444 or clade_444i), (clade_478 or clade_478i)	Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus torques	Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus torques
N854	CDAD,T2D	3	3	66.7	100	clade_110, (clade_262 or clade_262i), (clade_478 or clade_478i)	Bacteroides uniformis, Faecalibacterium prausnitzii, Ruminococcus torques	Bacteroides uniformis, Faecalibacterium prausnitzii, Ruminococcus torques
N855	CDAD,T2D	3	3	66.7	100	clade_170, (clade_262 or clade_262i), (clade_478 or clade_478i)	Bacteroides finegoldii, Faecalibacterium prausnitzii, Ruminococcus torques	Bacteroides finegoldii, Faecalibacterium prausnitzii, Ruminococcus torques
N856	CDAD,T2D	2	3	100	100	(clade_262 or clade_262i), clade_494	Clostridium nexile, Pseudoflavonifractor capillosus, Ruminococcus torques	Clostridium nexile, Pseudoflavonifractor capillosus, Ruminococcus torques
N857	CDAD,T2D	3	3	100	66.7	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_494	Blautia hansenii, Pseudoflavonifractor capillosus, Ruminococcus torques	Pseudoflavonifractor capillosus, Ruminococcus torques
N858	CDAD,T2D	3	3	100	66.7	(clade_262 or clade_262i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), clade_494	Anaerostipes caccae, Pseudoflavonifractor capillosus, Ruminococcus torques	Pseudoflavonifractor capillosus, Ruminococcus torques

N859	CDAD,T2D	3	3	100	66.7	(clade_260 or clade_260c or clade_260g or clade_260h), (clade_262 or clade_262i), clade_494	Clostridium scindens, Pseudoflavonifractor capillosus, Ruminococcus torques	Pseudoflavonifractor capillosus, Ruminococcus torques
N860	CDAD,T2D	3	3	66.7	66.7	(clade_262 or clade_262i), clade_494, (clade_98 or clade_98i)	Pseudoflavonifractor capillosus, Ruminococcus torques, Streptococcus thermophilus	Pseudoflavonifractor capillosus, Ruminococcus torques
N861	CDAD	3	3	100	66.7	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h)	Clostridium hathewayi, Ruminococcus obeum, Ruminococcus torques	Ruminococcus obeum, Ruminococcus torques
N862	CDAD,T2D	3	3	100	66.7	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_494	Pseudoflavonifractor capillosus, Ruminococcus gnavus, Ruminococcus torques	Pseudoflavonifractor capillosus, Ruminococcus torques
N863	CDAD,T2D	3	3	100	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_478 or clade_478i)	Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N864	CDAD	3	3	100	0	clade_253, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or	Blautia producta, Clostridium celatum, Clostridium innocuum	

						clade_309i), (clade_351 or clade_351e)		
N865	Obesity	2	3	0	0	(clade_335 or clade_335i), (clade_378 or clade_378e)	Bacteroides coprocola, Bacteroides plebeius, Parabacteroides distasonis	
N866	Obesity	3	3	33.3	66.7	clade_170, clade_286, clade_368	Bacteroides caccae, Blautia hydrogenotrophica, Parabacteroides merdae	Bacteroides caccae, Parabacteroides merdae
N867	Obesity	3	3	66.7	66.7	clade_396, clade_543, (clade_65 or clade_65e)	Bacteroides pectinophilus, Bacteroides thetaiotaomicron, Butyrivibrio crossotus	Bacteroides thetaiotaomicron, Butyrivibrio crossotus
N868	Obesity	3	3	66.7	33.3	clade_110, clade_368, (clade_566 or clade_566f)	Bacteroides uniformis, Blautia hydrogenotrophica, Eggerthella lenta	Bacteroides uniformis
N869	Obesity	3	3	33.3	100	(clade_38 or clade_38e or clade_38i), clade_537, (clade_566 or clade_566f)	Bacteroides xylanisolvens, Clostridium leptum, Gordonibacter pamelaeae	Bacteroides xylanisolvens, Clostridium leptum, Gordonibacter pamelaeae
N870	T2D	2	3	100	0	clade_252, clade_495	Clostridium beijerinckii, Clostridium botulinum, Clostridium thermocellum	
N871	CDAD,T2D	2	3	66.7	66.7	(clade_444 or clade_444i), clade_556	Acidaminococcus fermentans, Roseburia intestinalis, Roseburia inulinivorans	Roseburia intestinalis, Roseburia inulinivorans
N872	CDAD,T2D	3	3	66.7	66.7	(clade_444 or clade_444i), (clade_478 or clade_478i), (clade_98 or clade_98i)	Faecalibacterium prausnitzii, Roseburia intestinalis, Streptococcus infantis	Faecalibacterium prausnitzii, Roseburia intestinalis
N873	CDAD,T2D	3	3	66.7	66.7	(clade_444 or clade_444i), (clade_478 or clade_478i), (clade_98 or clade_98i)	Faecalibacterium prausnitzii, Roseburia intestinalis, Streptococcus australis	Faecalibacterium prausnitzii, Roseburia intestinalis

N874	CDAD,T2D	3	3	66.7	66.7	clade_396, (clade_444 or clade_444i), clade_88	Eubacterium hallii, Haemophilus parainfluenzae, Roseburia inulinivorans	Eubacterium hallii, Roseburia inulinivorans
N875	CDAD,T2D	2	3	100	66.7	(clade_444 or clade_444i), (clade_516 or clade_516c or clade_516g or clade_516h)	Anaerotruncus colihominis, Roseburia intestinalis, Roseburia inulinivorans	Roseburia intestinalis, Roseburia inulinivorans
N876	CDAD,T2D	2	3	66.7	100	clade_170, (clade_444 or clade_444i)	Bacteroides caccae, Roseburia intestinalis, Roseburia inulinivorans	Bacteroides caccae, Roseburia intestinalis, Roseburia inulinivorans
N877	CDAD,T2D	2	3	66.7	100	clade_110, (clade_444 or clade_444i)	Bacteroides uniformis, Roseburia intestinalis, Roseburia inulinivorans	Bacteroides uniformis, Roseburia intestinalis, Roseburia inulinivorans
N878	CDAD,T2D	2	3	100	100	(clade_444 or clade_444i), (clade_522 or clade_522i)	Eubacterium eligens, Roseburia intestinalis, Roseburia inulinivorans	Eubacterium eligens, Roseburia intestinalis, Roseburia inulinivorans
N879	CDAD,T2D	3	3	100	100	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), (clade_478 or clade_478i)	Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus obeum	Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus obeum
N880	CDAD,T2D	2	3	100	100	(clade_262 or clade_262i), (clade_444 or clade_444i)	Coprococcus comes, Eubacterium rectale, Roseburia inulinivorans	Coprococcus comes, Eubacterium rectale, Roseburia inulinivorans
N881	CDAD,T2D	2	3	100	100	clade_396, (clade_444 or clade_444i)	Eubacterium hallii, Roseburia intestinalis, Roseburia inulinivorans	Eubacterium hallii, Roseburia intestinalis, Roseburia inulinivorans
N882	CDAD,T2D	3	3	0	66.7	(clade_172 or clade_172i), (clade_38 or clade_38e or clade_38i), clade_521	Bacteroides xylanisolvens, Bifidobacterium catenulatum, Bilophila wadsworthia	Bacteroides xylanisolvens, Bilophila wadsworthia

N883	CDAD,T2D	3	3	33.3	66.7	(clade_172 or clade_172i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_445	Bifidobacterium catenulatum, Desulfovibrio desulfuricans, Dorea formicigenerans	Desulfovibrio desulfuricans, Dorea formicigenerans
N884	CDAD,T2D	2	3	0	66.7	clade_299, clade_500	Alistipes putredinis, Alistipes shahii, Propionibacterium acnes	Alistipes putredinis, Alistipes shahii
N885	CDAD,T2D	3	3	100	66.7	(clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_478 or clade_478i), clade_485	Anaerostipes caccae, Faecalibacterium prausnitzii, Holdemania filiformis	Faecalibacterium prausnitzii, Holdemania filiformis
N886	CDAD,T2D	3	3	33.3	66.7	clade_299, (clade_38 or clade_38e or clade_38i), (clade_478 or clade_478i)	Bacteroides xylanisolvens, Faecalibacterium prausnitzii, Propionibacterium acnes	Bacteroides xylanisolvens, Faecalibacterium prausnitzii
N887	CDAD,T2D	3	3	33.3	66.7	clade_299, clade_445, clade_537	Clostridium leptum, Desulfovibrio desulfuricans, Propionibacterium acnes	Clostridium leptum, Desulfovibrio desulfuricans
N888	CDAD,T2D	2	3	33.3	66.7	clade_500, clade_543	Alistipes putredinis, Alistipes shahii, Coprococcus eutactus	Alistipes putredinis, Alistipes shahii
N889	CDAD,T2D	3	3	100	33.3	(clade_516 or clade_516c or clade_516g or clade_516h), clade_537, clade_543	Anaerotruncus colihominis, Clostridium leptum, Coprococcus eutactus	Clostridium leptum
N890	CDAD,T2D	3	3	100	66.7	clade_485, clade_494, clade_543	Coprococcus eutactus, Holdemania filiformis, Pseudoflavonifractor capillosus	Holdemania filiformis, Pseudoflavonifractor capillosus
N891	CDAD,T2D	3	3	100	33.3	clade_368, (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h),	Blautia hydrogenotrophica, Clostridium bolteae, Holdemania filiformis	Holdemania filiformis

						clade_485		
N892	CDAD,T2D	3	3	100	66.7	(clade_262 or clade_262i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_478 or clade_478i)	Anaerostipes caccae, Coprococcus comes, Subdoligranulum variabile	Coprococcus comes, Subdoligranulum variabile
N893	CDAD,T2D	3	3	33.3	66.7	clade_281, clade_445, clade_537	Clostridium leptum, Desulfovibrio desulfuricans, Porphyromonas asaccharolytica	Clostridium leptum, Desulfovibrio desulfuricans
N894	CDAD,T2D	3	3	66.7	66.7	clade_293, (clade_444 or clade_444i), (clade_478 or clade_478i)	Bifidobacterium bifidum, Eubacterium rectale, Subdoligranulum variabile	Eubacterium rectale, Subdoligranulum variabile
N895	CDAD,T2D	2	3	0	66.7	clade_168, clade_500	Alistipes putredinis, Alistipes shahii, Prevotella copri	Alistipes putredinis, Alistipes shahii
N896	CDAD,T2D	3	3	66.7	33.3	clade_504, (clade_516 or clade_516c or clade_516g or clade_516h), clade_537	Anaerotruncus colihominis, Campylobacter hominis, Clostridium leptum	Clostridium leptum
N897	CDAD,T2D	3	3	100	66.7	(clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), clade_485, clade_537	Anaerostipes caccae, Clostridium leptum, Holdemania filiformis	Clostridium leptum, Holdemania filiformis
N898	CDAD,T2D	3	3	66.7	66.7	(clade_444 or clade_444i), (clade_478 or clade_478i), clade_556	Acidaminococcus fermentans, Eubacterium rectale, Subdoligranulum variabile	Eubacterium rectale, Subdoligranulum variabile
N899	CDAD,T2D	3	3	66.7	33.3	(clade_172 or clade_172i), (clade_516 or	Bifidobacterium catenulatum, Eubacterium siraeum,	Eubacterium siraeum

						clade_516c or clade_516g or clade_516h), clade_538	Ruminococcus albus	
N900	CDAD,T2D	3	3	33.3	66.7	(clade_378 or clade_378e), clade_494, clade_588	Bacteroides dorei, Methanobrevibacter smithii, Pseudoflavonifractor capillosus	Bacteroides dorei, Pseudoflavonifractor capillosus
N901	CDAD,T2D	3	3	33.3	66.7	(clade_262 or clade_262i), clade_401, clade_466	Lactococcus lactis, Odoribacter splanchnicus, Ruminococcus lactaris	Odoribacter splanchnicus, Ruminococcus lactaris
N902	CDAD,T2D	3	3	100	66.7	(clade_262 or clade_262i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), clade_494	Anaerostipes caccae, Pseudoflavonifractor capillosus, Ruminococcus torques	Pseudoflavonifractor capillosus, Ruminococcus torques
N903	CDAD,T2D	3	3	33.3	66.7	clade_293, (clade_38 or clade_38e or clade_38i), (clade_478 or clade_478i)	Bacteroides xylanisolvens, Bifidobacterium bifidum, Subdoligranulum variabile	Bacteroides xylanisolvens, Subdoligranulum variabile
N904	CDAD,T2D	2	3	0	66.7	clade_500, (clade_98 or clade_98i)	Alistipes putredinis, Alistipes shahii, Streptococcus sanguinis	Alistipes putredinis, Alistipes shahii
N905	CDAD,T2D	3	3	33.3	66.7	clade_293, (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_445	Bifidobacterium bifidum, Desulfovibrio desulfuricans, Dorea formicigenerans	Desulfovibrio desulfuricans, Dorea formicigenerans
N906	CDAD,T2D	3	3	66.7	33.3	(clade_172 or clade_172i), (clade_522 or clade_522i), (clade_553 or clade_553i)	Bifidobacterium catenulatum, Collinsella aerofaciens, Eubacterium eligens	Eubacterium eligens
N907	CDAD,T2D	3	3	66.7	66.7	(clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or	Dorea longicatena, Roseburia intestinalis, Streptococcus vestibularis	Dorea longicatena, Roseburia intestinalis

						clade_444i), (clade_98 or clade_98i)		
N908	CDAD,T2D	3	3	33.3	100	clade_357, (clade_38 or clade_38e or clade_38i), clade_396	Bacteroides ovatus, Eubacterium hallii, Oxalobacter formigenes	Bacteroides ovatus, Eubacterium hallii, Oxalobacter formigenes
N909	CDAD,T2D	2	3	33.3	66.7	clade_500, (clade_516 or clade_516c or clade_516g or clade_516h)	Alistipes putredinis, Alistipes shahii, Clostridium methylpentosum	Alistipes putredinis, Alistipes shahii
N910	CDAD,T2D	3	3	33.3	66.7	(clade_172 or clade_172i), clade_396, clade_500	Alistipes shahii, Bifidobacterium pseudocatenulatum, Eubacterium hallii	Alistipes shahii, Eubacterium hallii
N911	CDAD,T2D	3	3	66.7	66.7	(clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_445, (clade_516 or clade_516c or clade_516g or clade_516h)	Clostridium methylpentosum, Desulfovibrio desulfuricans, Dorea formicigenerans	Desulfovibrio desulfuricans, Dorea formicigenerans
N912	CDAD,T2D	3	3	100	66.7	(clade_444 or clade_444i), (clade_478 or clade_478i), (clade_516 or clade_516c or clade_516g or clade_516h)	Clostridium methylpentosum, Eubacterium rectale, Subdoligranulum variabile	Eubacterium rectale, Subdoligranulum variabile
N913	CDAD,T2D	3	3	100	33.3	(clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_516 or clade_516c or	Anaerotruncus colihominis, Clostridium symbiosum, Dorea formicigenerans	Dorea formicigenerans

						clade_516g or clade_516h)		
N914	CDAD,T2D	3	3	66.7	66.7	clade_358, (clade_444 or clade_444i), clade_519	Eubacterium ventriosum, Roseburia inulinivorans, Veillonella dispar	Eubacterium ventriosum, Roseburia inulinivorans
N915	CDAD,T2D	3	3	100	66.7	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_396	Blautia hansenii, Coprococcus comes, Eubacterium hallii	Coprococcus comes, Eubacterium hallii
N916	CDAD,T2D	3	3	66.7	66.7	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_445, (clade_478 or clade_478i)	Blautia hansenii, Desulfovibrio desulfuricans, Faecalibacterium prausnitzii	Desulfovibrio desulfuricans, Faecalibacterium prausnitzii
N917	CDAD,T2D	3	3	33.3	66.7	clade_358, (clade_38 or clade_38e or clade_38i), (clade_478 or clade_478i)	Bacteroides xylanisolvens, Faecalibacterium prausnitzii, Veillonella dispar	Bacteroides xylanisolvens, Faecalibacterium prausnitzii
N918	CDAD,T2D	3	3	100	66.7	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_494	Blautia hansenii, Pseudoflavonifractor capillosus, Ruminococcus torques	Pseudoflavonifractor capillosus, Ruminococcus torques

N919	CDAD,T2D	2	3	33.3	66.7	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_500	Alistipes putredinis, Alistipes shahii, Blautia hansenii	Alistipes putredinis, Alistipes shahii
N920	CDAD,T2D	3	3	66.7	100	(clade_262 or clade_262i), clade_286, clade_396	Coprococcus comes, Eubacterium hallii, Parabacteroides johnsonii	Coprococcus comes, Eubacterium hallii, Parabacteroides johnsonii
N921	CDAD,T2D	3	3	66.7	66.7	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_358, (clade_444 or clade_444i)	Eubacterium rectale, Ruminococcus obeum, Veillonella dispar	Eubacterium rectale, Ruminococcus obeum
N922	CDAD,T2D	2	3	0	33.3	(clade_378 or clade_378e), (clade_38 or clade_38e or clade_38i)	Bacteroides ovatus, Bacteroides plebeius, Bacteroides vulgatus	Bacteroides ovatus
N923	CDAD,T2D	3	3	66.7	66.7	(clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), (clade_98 or clade_98i)	Dorea longicatena, Roseburia intestinalis, Streptococcus mitis	Dorea longicatena, Roseburia intestinalis
N924	CDAD,T2D	3	3	0	66.7	(clade_38 or clade_38e or clade_38i), clade_432, clade_500	Alistipes shahii, Bacteroides xylanisolvens, Sutterella wadsworthensis	Alistipes shahii, Bacteroides xylanisolvens
N925	CDAD,T2D	3	3	66.7	66.7	clade_396, (clade_444 or clade_444i), (clade_98 or clade_98i)	Eubacterium hallii, Roseburia inulinivorans, Streptococcus australis	Eubacterium hallii, Roseburia inulinivorans
N926	CDAD,T2D	2	3	0	66.7	clade_401, clade_500	Alistipes putredinis, Alistipes shahii, Lactococcus lactis	Alistipes putredinis, Alistipes shahii
N927	CDAD,T2D	3	3	66.7	66.7	clade_396, (clade_444 or clade_444i),	Dialister invisus, Eubacterium hallii, Roseburia inulinivorans	Eubacterium hallii, Roseburia inulinivorans

						clade_506		
N928	CDAD,T2D	2	3	0	66.7	clade_500, clade_506	Alistipes putredinis, Alistipes shahii, Dialister invisus	Alistipes putredinis, Alistipes shahii
N929	CDAD,T2D	3	3	100	66.7	(clade_262 or clade_262i), clade_396, (clade_566 or clade_566f)	Coprococcus comes, Eggerthella lenta, Eubacterium hallii	Coprococcus comes, Eubacterium hallii
N930	CDAD,T2D	3	3	100	100	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i)	Clostridium nexile, Eubacterium hallii, Roseburia inulinivorans	Clostridium nexile, Eubacterium hallii, Roseburia inulinivorans
N931	CDAD,T2D	3	3	100	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_478 or clade_478i)	Clostridium nexile, Dorea formicigenerans, Subdoligranulum variabile	Clostridium nexile, Dorea formicigenerans, Subdoligranulum variabile
N932	CDAD,T2D	2	3	100	100	(clade_262 or clade_262i), clade_494	Clostridium nexile, Pseudoflavonifractor capillosus, Ruminococcus torques	Clostridium nexile, Pseudoflavonifractor capillosus, Ruminococcus torques
N933	CDAD,T2D	3	3	66.7	66.7	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_65 or clade_65e)	Bacteroides fragilis, Coprococcus comes, Dorea longicatena	Coprococcus comes, Dorea longicatena
N934	CDAD,T2D	3	3	100	100	(clade_262 or clade_262i), (clade_478 or clade_478i), clade_485	Clostridium nexile, Faecalibacterium prausnitzii, Holdemania filiformis	Clostridium nexile, Faecalibacterium prausnitzii, Holdemania filiformis
N935	CDAD,T2D	3	3	66.7	66.7	clade_396, (clade_444 or clade_444i), (clade_65 or clade_65e)	Bacteroides fragilis, Eubacterium hallii, Roseburia inulinivorans	Eubacterium hallii, Roseburia inulinivorans

N936	CDAD,T2D	3	3	33.3	66.7	(clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_500, (clade_65 or clade_65e)	Alistipes putredinis, Bacteroides fragilis, Dorea formicigenerans	Alistipes putredinis, Dorea formicigenerans
N937	CDAD,T2D	2	3	0	100	clade_500, clade_85	Alistipes putredinis, Alistipes shahii, Bacteroides eggerthii	Alistipes putredinis, Alistipes shahii, Bacteroides eggerthii
N938	CDAD,T2D	3	3	66.7	100	clade_171, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_522 or clade_522i)	Bacteroides intestinalis, Eubacterium eligens, Ruminococcus obeum	Bacteroides intestinalis, Eubacterium eligens, Ruminococcus obeum
N939	CDAD,T2D	3	3	66.7	66.7	(clade_262 or clade_262i), clade_494, (clade_98 or clade_98i)	Pseudoflavonifractor capillosus, Ruminococcus torques, Streptococcus thermophilus	Pseudoflavonifractor capillosus, Ruminococcus torques
N940	CDAD,T2D	3	3	33.3	66.7	(clade_38 or clade_38e or clade_38i), (clade_478 or clade_478i), (clade_98 or clade_98i)	Bacteroides xylanisolvens, Faecalibacterium prausnitzii, Streptococcus salivarius	Bacteroides xylanisolvens, Faecalibacterium prausnitzii
N941	CDAD,T2D	3	3	33.3	66.7	(clade_335 or clade_335i), clade_445, (clade_478 or clade_478i)	Desulfovibrio desulfuricans, Faecalibacterium prausnitzii, Parabacteroides distasonis	Desulfovibrio desulfuricans, Faecalibacterium prausnitzii
N942	CDAD,T2D	3	3	100	66.7	(clade_260 or clade_260c or clade_260g or clade_260h), clade_396, (clade_444 or clade_444i)	Clostridium scindens, Eubacterium hallii, Roseburia inulinivorans	Eubacterium hallii, Roseburia inulinivorans

N943	CDAD,T2D	3	3	66.7	100	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_85	Bacteroides eggerthii, Dorea formicigenerans, Ruminococcus obeum	Bacteroides eggerthii, Dorea formicigenerans, Ruminococcus obeum
N944	CDAD,T2D	3	3	66.7	66.7	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), (clade_98 or clade_98i)	Eubacterium rectale, Ruminococcus obeum, Streptococcus salivarius	Eubacterium rectale, Ruminococcus obeum
N945	CDAD,T2D	2	3	33.3	66.7	(clade_260 or clade_260c or clade_260g or clade_260h), clade_500	Alistipes putredinis, Alistipes shahii, Clostridium scindens	Alistipes putredinis, Alistipes shahii
N946	CDAD,T2D	3	3	100	66.7	(clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_478 or clade_478i), clade_485	Clostridium hathewayi, Faecalibacterium prausnitzii, Holdemania filiformis	Faecalibacterium prausnitzii, Holdemania filiformis
N947	CDAD,T2D	3	3	66.7	66.7	clade_396, (clade_444 or clade_444i), (clade_98 or clade_98i)	Eubacterium hallii, Roseburia inulinivorans, Streptococcus thermophilus	Eubacterium hallii, Roseburia inulinivorans
N948	CDAD,T2D	2	3	0	100	clade_500, (clade_566 or clade_566f)	Alistipes putredinis, Alistipes shahii, Gordonibacter pamelaeae	Alistipes putredinis, Alistipes shahii, Gordonibacter pamelaeae
N949	CDAD,T2D	3	3	33.3	66.7	(clade_172 or clade_172i), (clade_360 or clade_360c or clade_360g or	Bifidobacterium adolescentis, Desulfovibrio desulfuricans, Dorea formicigenerans	Desulfovibrio desulfuricans, Dorea formicigenerans

						clade_360h or clade_360i), clade_445		
N950	CDAD,T2D	3	3	66.7	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_85	Bacteroides stercoris, Coprococcus comes, Dorea longicatena	Bacteroides stercoris, Coprococcus comes, Dorea longicatena
N951	CDAD,T2D	3	3	100	66.7	(clade_260 or clade_260c or clade_260g or clade_260h), (clade_262 or clade_262i), clade_494	Clostridium scindens, Pseudoflavonifractor capillosus, Ruminococcus torques	Pseudoflavonifractor capillosus, Ruminococcus torques
N952	CDAD,T2D	2	3	0	100	clade_500, clade_85	Alistipes putredinis, Alistipes shahii, Bacteroides stercoris	Alistipes putredinis, Alistipes shahii, Bacteroides stercoris
N953	CDAD,T2D	3	3	66.7	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_85	Bacteroides eggerthii, Coprococcus comes, Dorea longicatena	Bacteroides eggerthii, Coprococcus comes, Dorea longicatena
N954	CDAD,T2D	2	3	33.3	66.7	(clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), clade_500	Alistipes putredinis, Alistipes shahii, Clostridium asparagiforme	Alistipes putredinis, Alistipes shahii
N955	CDAD,T2D	3	3	100	66.7	(clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_444 or clade_444i), (clade_478 or clade_478i)	Clostridium asparagiforme, Eubacterium rectale, Subdoligranulum variabile	Eubacterium rectale, Subdoligranulum variabile

N956	CDAD,T2D	3	3	33.3	100	(clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_500, clade_85	Alistipes putredinis, Bacteroides eggerthii, Dorea formicigenerans	Alistipes putredinis, Bacteroides eggerthii, Dorea formicigenerans
N957	CDAD,T2D	2	3	33.3	100	clade_500, clade_537	Alistipes putredinis, Alistipes shahii, Ruminococcus bromii	Alistipes putredinis, Alistipes shahii, Ruminococcus bromii
N958	CDAD,T2D	3	3	66.7	100	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_358, (clade_444 or clade_444i)	Eubacterium rectale, Ruminococcus obeum, Veillonella parvula	Eubacterium rectale, Ruminococcus obeum, Veillonella parvula
N959	CDAD,T2D	3	3	33.3	100	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_500, clade_85	Alistipes shahii, Bacteroides cellulosilyticus, Ruminococcus obeum	Alistipes shahii, Bacteroides cellulosilyticus, Ruminococcus obeum
N960	CDAD,T2D	2	3	33.3	66.7	(clade_354 or clade_354e), clade_500	Alistipes putredinis, Alistipes shahii, Clostridium bartlettii	Alistipes putredinis, Alistipes shahii
N961	CDAD,T2D	3	3	100	66.7	(clade_354 or clade_354e), (clade_444 or clade_444i), (clade_478 or clade_478i)	Clostridium bartlettii, Eubacterium rectale, Subdoligranulum variabile	Eubacterium rectale, Subdoligranulum variabile
N962	CDAD,T2D	3	3	100	100	(clade_262 or clade_262i), (clade_478 or clade_478i), clade_537	Faecalibacterium prausnitzii, Ruminococcus bromii, Ruminococcus torques	Faecalibacterium prausnitzii, Ruminococcus bromii, Ruminococcus torques
N963	CDAD,T2D	3	3	100	66.7	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or	Ruminococcus gnavus, Ruminococcus obeum, Ruminococcus torques	Ruminococcus obeum, Ruminococcus torques

						clade_360c or clade_360g or clade_360h clade_360i)		
N964	CDAD,T2D	3	3	66.7	100	(clade_172 or clade_172i), (clade_262 or clade_262i), (clade_478 or clade_478i)	Bifidobacterium longum, Faecalibacterium prausnitzii, Ruminococcus torques	Bifidobacterium longum, Faecalibacterium prausnitzii, Ruminococcus torques
N965	CDAD,T2D	3	3	100	66.7	(clade_262 or clade_262i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), clade_494	Clostridium bolteae, Pseudoflavonifractor capillosus, Ruminococcus torques	Pseudoflavonifractor capillosus, Ruminococcus torques
N966	CDAD,T2D	2	3	0	100	clade_500, (clade_98 or clade_98i)	Alistipes putredinis, Alistipes shahii, Streptococcus parasanguinis	Alistipes putredinis, Alistipes shahii, Streptococcus parasanguinis
N967	CDAD,T2D	3	3	66.7	100	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_85	Bacteroides stercoris, Dorea formicigenerans, Ruminococcus obeum	Bacteroides stercoris, Dorea formicigenerans, Ruminococcus obeum
N968	CDAD,T2D	3	3	66.7	66.7	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_92 or clade_92e or clade_92i)	Escherichia coli, Ruminococcus obeum, Ruminococcus torques	Ruminococcus obeum, Ruminococcus torques

N969	CDAD,T2D	3	3	66.7	66.7	(clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_445, (clade_516 or clade_516c or clade_516g or clade_516h)	Desulfovibrio desulfuricans, Dorea formicigenerans, Ruminococcus albus	Desulfovibrio desulfuricans, Dorea formicigenerans
N970	CDAD,T2D	3	3	66.7	100	clade_286, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h clade_360i)	Dorea formicigenerans, Parabacteroides merdae, Ruminococcus obeum	Dorea formicigenerans, Parabacteroides merdae, Ruminococcus obeum
N971	CDAD,T2D	3	3	66.7	100	clade_170, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i)	Bacteroides finegoldii, Eubacterium rectale, Ruminococcus obeum	Bacteroides finegoldii, Eubacterium rectale, Ruminococcus obeum
N972	CDAD,T2D	3	3	100	66.7	(clade_444 or clade_444i), (clade_478 or clade_478i), (clade_516 or clade_516c or clade_516g or clade_516h)	Anaerotruncus colihominis, Eubacterium rectale, Subdoligranulum variabile	Eubacterium rectale, Subdoligranulum variabile
N973	CDAD,T2D	3	3	66.7	100	clade_170, (clade_262 or clade_262i), (clade_478 or clade_478i)	Bacteroides finegoldii, Faecalibacterium prausnitzii, Ruminococcus torques	Bacteroides finegoldii, Faecalibacterium prausnitzii, Ruminococcus torques
N974	CDAD,T2D	3	3	0	66.7	(clade_172 or clade_172i), clade_466, clade_500	Alistipes putredinis, Bifidobacterium adolescentis, Odoribacter splanchnicus	Alistipes putredinis, Odoribacter splanchnicus

N975	CDAD,T2D	3	3	66.7	100	clade_170, (clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h clade_360i)	Bacteroides caccae, Coprococcus comes, Dorea longicatena	Bacteroides caccae, Coprococcus comes, Dorea longicatena
N976	CDAD,T2D	3	3	33.3	100	clade_286, (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_466	Dorea formicigenerans, Odoribacter splanchnicus, Parabacteroides merdae	Dorea formicigenerans, Odoribacter splanchnicus, Parabacteroides merdae
N977	CDAD,T2D	3	3	66.7	100	clade_396, (clade_444 or clade_444i), (clade_98 or clade_98i)	Eubacterium hallii, Roseburia inulinivorans, Streptococcus parasanguinis	Eubacterium hallii, Roseburia inulinivorans, Streptococcus parasanguinis
N978	CDAD,T2D	3	3	66.7	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_378 or clade_378e)	Bacteroides dorei, Coprococcus comes, Dorea longicatena	Bacteroides dorei, Coprococcus comes, Dorea longicatena
N979	CDAD,T2D	2	3	0	100	(clade_378 or clade_378e), clade_500	Alistipes putredinis, Alistipes shahii, Bacteroides dorei	Alistipes putredinis, Alistipes shahii, Bacteroides dorei
N980	CDAD,T2D	2	3	33.3	100	(clade_262 or clade_262i), clade_500	Alistipes putredinis, Alistipes shahii, Coprococcus comes	Alistipes putredinis, Alistipes shahii, Coprococcus comes
N981	CDAD,T2D	3	3	66.7	100	clade_110, (clade_262 or clade_262i), (clade_478 or clade_478i)	Bacteroides uniformis, Faecalibacterium prausnitzii, Ruminococcus torques	Bacteroides uniformis, Faecalibacterium prausnitzii, Ruminococcus torques
N982	CDAD,T2D	3	3	66.7	100	(clade_172 or clade_172i), (clade_262 or clade_262i), clade_396	Bifidobacterium longum, Coprococcus comes, Eubacterium hallii	Bifidobacterium longum, Coprococcus comes, Eubacterium hallii
N983	CDAD,T2D	3	3	66.7	66.7	clade_396, (clade_444 or clade_444i), (clade_98 or clade_98i)	Eubacterium hallii, Roseburia inulinivorans, Streptococcus salivarius	Eubacterium hallii, Roseburia inulinivorans

N984	CDAD,T2D	3	3	100	66.7	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_494	Pseudoflavonifractor capillosus, Ruminococcus gnavus, Ruminococcus torques	Pseudoflavonifractor capillosus, Ruminococcus torques
N985	CDAD,T2D	3	3	66.7	100	clade_110, (clade_262 or clade_262i), clade_396	Bacteroides uniformis, Coprococcus comes, Eubacterium hallii	Bacteroides uniformis, Coprococcus comes, Eubacterium hallii
N986	CDAD,T2D	3	3	66.7	100	(clade_172 or clade_172i), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i)	Bifidobacterium longum, Ruminococcus obeum, Ruminococcus torques	Bifidobacterium longum, Ruminococcus obeum, Ruminococcus torques
N987	CDAD,T2D	3	3	100	100	(clade_262 or clade_262i), clade_396, clade_537	Coprococcus comes, Eubacterium hallii, Ruminococcus bromii	Coprococcus comes, Eubacterium hallii, Ruminococcus bromii
N988	CDAD,T2D	3	3	100	100	(clade_444 or clade_444i), (clade_478 or clade_478i), clade_537	Eubacterium rectale, Ruminococcus bromii, Subdoligranulum variabile	Eubacterium rectale, Ruminococcus bromii, Subdoligranulum variabile
N989	CDAD,T2D	3	3	100	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_519	Coprococcus comes, Dorea longicatena, Eubacterium ventriosum	Coprococcus comes, Dorea longicatena, Eubacterium ventriosum
N990	CDAD,T2D	3	3	66.7	66.7	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_378 or clade_378e)	Bacteroides vulgatus, Coprococcus comes, Dorea longicatena	Coprococcus comes, Dorea longicatena

N991	CDAD,T2D	3	3	100	100	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i)	Eubacterium hallii, Roseburia inulinivorans, Ruminococcus lactaris	Eubacterium hallii, Roseburia inulinivorans, Ruminococcus lactaris
N992	CDAD,T2D	2	3	0	66.7	(clade_378 or clade_378e), clade_500	Alistipes putredinis, Alistipes shahii, Bacteroides vulgatus	Alistipes putredinis, Alistipes shahii
N993	CDAD,T2D	3	3	66.7	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_500	Alistipes putredinis, Dorea formicigenerans, Ruminococcus lactaris	Alistipes putredinis, Dorea formicigenerans, Ruminococcus lactaris
N994	CDAD,T2D	2	3	0	100	(clade_38 or clade_38e or clade_38i), clade_500	Alistipes putredinis, Alistipes shahii, Bacteroides xylanisolvens	Alistipes putredinis, Alistipes shahii, Bacteroides xylanisolvens
N995	CDAD,T2D	3	3	66.7	100	(clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_500, clade_537	Alistipes putredinis, Clostridium leptum, Dorea formicigenerans	Alistipes putredinis, Clostridium leptum, Dorea formicigenerans
N996	CDAD,T2D	3	3	100	100	clade_393, clade_396, (clade_444 or clade_444i)	Coprococcus catus, Eubacterium hallii, Roseburia inulinivorans	Coprococcus catus, Eubacterium hallii, Roseburia inulinivorans
N997	CDAD,T2D	2	3	33.3	100	clade_393, clade_500	Alistipes putredinis, Alistipes shahii, Coprococcus catus	Alistipes putredinis, Alistipes shahii, Coprococcus catus
N998	CDAD,T2D	3	3	100	100	(clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_393, (clade_478 or clade_478i)	Coprococcus catus, Dorea formicigenerans, Faecalibacterium prausnitzii	Coprococcus catus, Dorea formicigenerans, Faecalibacterium prausnitzii
N999	CDAD,T2D	3	3	100	100	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or	Dorea formicigenerans, Faecalibacterium prausnitzii, Ruminococcus obeum	Dorea formicigenerans, Faecalibacterium prausnitzii, Ruminococcus obeum

						clade_360g or clade_360h or clade_360i), (clade_478 or clade_478i)		
N1000	CDAD,T2D	3	3	66.7	100	(clade_262 or clade_262i), clade_396, clade_466	Coprococcus comes, Eubacterium hallii, Odoribacter splanchnicus	Coprococcus comes, Eubacterium hallii, Odoribacter splanchnicus
N1001	CDAD,T2D	3	3	100	100	clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i)	Eubacterium hallii, Roseburia inulinivorans, Subdoligranulum variabile	Eubacterium hallii, Roseburia inulinivorans, Subdoligranulum variabile
N1002	CDAD,T2D	2	3	33.3	100	(clade_478 or clade_478i), clade_500	Alistipes putredinis, Alistipes shahii, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Subdoligranulum variabile
N1003	CDAD,T2D	3	3	100	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_494	Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N1004	CDAD,T2D	3	3	66.7	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_445	Desulfovibrio desulfuricans, Ruminococcus obeum, Ruminococcus torques	Desulfovibrio desulfuricans, Ruminococcus obeum, Ruminococcus torques
N1005	CDAD,T2D	3	3	66.7	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_500	Alistipes shahii, Ruminococcus obeum, Ruminococcus torques	Alistipes shahii, Ruminococcus obeum, Ruminococcus torques

N1006	CDAD,T2D	3	3	100	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i)	Eubacterium rectale, Ruminococcus obeum, Ruminococcus torques	Eubacterium rectale, Ruminococcus obeum, Ruminococcus torques
N1007	CDAD,T2D	3	3	100	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_478 or clade_478i)	Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N1008	CDAD	3	3	66.7	100	(clade_262 or clade_262i), (clade_478 or clade_478i), clade_521	Bilophila wadsworthia, Faecalibacterium prausnitzii, Ruminococcus torques	Bilophila wadsworthia, Faecalibacterium prausnitzii, Ruminococcus torques
N1009	CDAD,T2D	3	3	100	100	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i)	Eubacterium hallii, Roseburia inulinivorans, Ruminococcus lactaris	Eubacterium hallii, Roseburia inulinivorans, Ruminococcus lactaris
N1010	CDAD	3	3	100	100	(clade_262 or clade_262i), (clade_478 or clade_478i), clade_537	Clostridium leptum, Faecalibacterium prausnitzii, Ruminococcus torques	Clostridium leptum, Faecalibacterium prausnitzii, Ruminococcus torques
N1011	CDAD,T2D	2	3	66.7	66.7	(clade_444 or clade_444i), clade_556	Acidaminococcus fermentans, Roseburia intestinalis, Roseburia inulinivorans	Roseburia intestinalis, Roseburia inulinivorans
N1012	CDAD,T2D	3	3	66.7	66.7	clade_293, (clade_444 or clade_444i), (clade_478 or clade_478i)	Bifidobacterium bifidum, Eubacterium rectale, Subdoligranulum variabile	Eubacterium rectale, Subdoligranulum variabile
N1013	CDAD,T2D	3	3	66.7	66.7	(clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or	Dorea longicatena, Roseburia intestinalis, Streptococcus vestibularis	Dorea longicatena, Roseburia intestinalis

						clade_444i), (clade_98 or clade_98i)		
N1014	CDAD,T2D	2	3	33.3	66.7	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_500	Alistipes putredinis, Alistipes shahii, Blautia hansenii	Alistipes putredinis, Alistipes shahii
N1015	CDAD,T2D	3	3	66.7	66.7	(clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), (clade_98 or clade_98i)	Dorea longicatena, Roseburia intestinalis, Streptococcus mitis	Dorea longicatena, Roseburia intestinalis
N1016	CDAD,T2D	3	3	66.7	66.7	clade_396, (clade_444 or clade_444i), (clade_98 or clade_98i)	Eubacterium hallii, Roseburia inulinivorans, Streptococcus australis	Eubacterium hallii, Roseburia inulinivorans
N1017	CDAD,T2D	3	3	66.7	66.7	clade_396, (clade_444 or clade_444i), clade_506	Dialister invisus, Eubacterium hallii, Roseburia inulinivorans	Eubacterium hallii, Roseburia inulinivorans
N1018	CDAD,T2D	2	3	0	66.7	clade_500, clade_506	Alistipes putredinis, Alistipes shahii, Dialister invisus	Alistipes putredinis, Alistipes shahii
N1019	CDAD	3	3	66.7	100	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_358, (clade_478 or clade_478i)	Faecalibacterium prausnitzii, Ruminococcus obeum, Veillonella atypica	Faecalibacterium prausnitzii, Ruminococcus obeum, Veillonella atypica
N1020	CDAD,T2D	3	3	100	100	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i)	Clostridium nexile, Eubacterium hallii, Roseburia inulinivorans	Clostridium nexile, Eubacterium hallii, Roseburia inulinivorans
N1021	CDAD,T2D	3	3	66.7	66.7	clade_396, (clade_444 or clade_444i),	Bacteroides fragilis, Eubacterium hallii, Roseburia inulinivorans	Eubacterium hallii, Roseburia inulinivorans

						(clade_65 or clade_65e)		
N1022	CDAD,T2D	3	3	33.3	66.7	(clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_500, (clade_65 or clade_65e)	Alistipes putredinis, Bacteroides fragilis, Dorea formicigenerans	Alistipes putredinis, Dorea formicigenerans
N1023	CDAD	3	3	66.7	66.7	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_98 or clade_98i)	Dorea longicatena, Ruminococcus torques, Streptococcus salivarius	Dorea longicatena, Ruminococcus torques
N1024	CDAD,T2D	3	3	100	66.7	(clade_260 or clade_260c or clade_260g or clade_260h), clade_396, (clade_444 or clade_444i)	Clostridium scindens, Eubacterium hallii, Roseburia inulinivorans	Eubacterium hallii, Roseburia inulinivorans
N1025	CDAD,T2D	2	3	33.3	66.7	(clade_260 or clade_260c or clade_260g or clade_260h), clade_500	Alistipes putredinis, Alistipes shahii, Clostridium scindens	Alistipes putredinis, Alistipes shahii
N1026	CDAD,T2D	3	3	66.7	66.7	clade_396, (clade_444 or clade_444i), (clade_98 or clade_98i)	Eubacterium hallii, Roseburia inulinivorans, Streptococcus thermophilus	Eubacterium hallii, Roseburia inulinivorans
N1027	CDAD,T2D	3	3	66.7	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_85	Bacteroides stercoris, Coprococcus comes, Dorea longicatena	Bacteroides stercoris, Coprococcus comes, Dorea longicatena
N1028	CDAD,T2D	2	3	0	100	clade_500, clade_85	Alistipes putredinis, Alistipes shahii, Bacteroides stercoris	Alistipes putredinis, Alistipes shahii, Bacteroides stercoris

N1029	CDAD,T2D	3	3	66.7	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_85	Bacteroides eggerthii, Coprococcus comes, Dorea longicatena	Bacteroides eggerthii, Coprococcus comes, Dorea longicatena
N1030	CDAD,T2D	2	3	33.3	66.7	(clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), clade_500	Alistipes putredinis, Alistipes shahii, Clostridium asparagiforme	Alistipes putredinis, Alistipes shahii
N1031	CDAD,T2D	3	3	66.7	66.7	clade_396, (clade_444 or clade_444i), clade_88	Eubacterium hallii, Haemophilus parainfluenzae, Roseburia inulinivorans	Eubacterium hallii, Roseburia inulinivorans
N1032	CDAD,T2D	2	3	33.3	66.7	(clade_354 or clade_354e), clade_500	Alistipes putredinis, Alistipes shahii, Clostridium bartlettii	Alistipes putredinis, Alistipes shahii
N1033	CDAD,T2D	3	3	100	66.7	(clade_354 or clade_354e), (clade_444 or clade_444i), (clade_478 or clade_478i)	Clostridium bartlettii, Eubacterium rectale, Subdoligranulum variabile	Eubacterium rectale, Subdoligranulum variabile
N1034	CDAD,T2D	3	3	100	66.7	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h clade_360i)	Ruminococcus gnavus, Ruminococcus obeum, Ruminococcus torques	Ruminococcus obeum, Ruminococcus torques
N1035	CDAD	3	3	66.7	66.7	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_478 or clade_478i), (clade_98 or	Faecalibacterium prausnitzii, Ruminococcus obeum, Streptococcus mitis	Faecalibacterium prausnitzii, Ruminococcus obeum

						clade_98i)		
N1036	CDAD,T2D	3	3	66.7	66.7	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_92 or clade_92e or clade_92i)	Escherichia coli, Ruminococcus obeum, Ruminococcus torques	Ruminococcus obeum, Ruminococcus torques
N1037	CDAD	3	3	66.7	66.7	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_478 or clade_478i), clade_88	Faecalibacterium prausnitzii, Haemophilus parainfluenzae, Ruminococcus obeum	Faecalibacterium prausnitzii, Ruminococcus obeum
N1038	CDAD	3	3	66.7	100	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_478 or clade_478i), (clade_98 or clade_98i)	Faecalibacterium prausnitzii, Ruminococcus obeum, Streptococcus parasanguinis	Faecalibacterium prausnitzii, Ruminococcus obeum, Streptococcus parasanguinis
N1039	CDAD,T2D	2	3	100	66.7	(clade_444 or clade_444i), (clade_516 or clade_516c or clade_516g or clade_516h)	Anaerotruncus colihominis, Roseburia intestinalis, Roseburia inulinivorans	Roseburia intestinalis, Roseburia inulinivorans
N1040	CDAD,T2D	3	3	100	66.7	(clade_444 or clade_444i), (clade_478 or clade_478i), (clade_516 or clade_516c or clade_516g or clade_516h)	Anaerotruncus colihominis, Eubacterium rectale, Subdoligranulum variabile	Eubacterium rectale, Subdoligranulum variabile

N1041	CDAD,T2D	3	3	0	66.7	(clade_172 or clade_172i), clade_466, clade_500	Alistipes putredinis, Bifidobacterium adolescentis, Odoribacter splanchnicus	Alistipes putredinis, Odoribacter splanchnicus
N1042	CDAD,T2D	2	3	66.7	100	clade_170, (clade_444 or clade_444i)	Bacteroides caccae, Roseburia intestinalis, Roseburia inulinivorans	Bacteroides caccae, Roseburia intestinalis, Roseburia inulinivorans
N1043	CDAD,T2D	3	3	66.7	100	clade_396, (clade_444 or clade_444i), (clade_98 or clade_98i)	Eubacterium hallii, Roseburia inulinivorans, Streptococcus parasanguinis	Eubacterium hallii, Roseburia inulinivorans, Streptococcus parasanguinis
N1044	CDAD,T2D	2	3	0	100	(clade_378 or clade_378e), clade_500	Alistipes putredinis, Alistipes shahii, Bacteroides dorei	Alistipes putredinis, Alistipes shahii, Bacteroides dorei
N1045	CDAD,T2D	2	3	66.7	100	clade_110, (clade_444 or clade_444i)	Bacteroides uniformis, Roseburia intestinalis, Roseburia inulinivorans	Bacteroides uniformis, Roseburia intestinalis, Roseburia inulinivorans
N1046	CDAD,T2D	3	3	66.7	66.7	clade_396, (clade_444 or clade_444i), (clade_98 or clade_98i)	Eubacterium hallii, Roseburia inulinivorans, Streptococcus salivarius	Eubacterium hallii, Roseburia inulinivorans
N1047	CDAD	3	3	100	100	(clade_262 or clade_262i), (clade_478 or clade_478i), clade_485	Faecalibacterium prausnitzii, Holdemania filiformis, Ruminococcus torques	Faecalibacterium prausnitzii, Holdemania filiformis, Ruminococcus torques
N1048	CDAD,T2D	3	3	66.7	100	(clade_172 or clade_172i), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i)	Bifidobacterium longum, Ruminococcus obeum, Ruminococcus torques	Bifidobacterium longum, Ruminococcus obeum, Ruminococcus torques
N1049	CDAD,T2D	3	3	100	100	(clade_262 or clade_262i), clade_396, clade_537	Coprococcus comes, Eubacterium hallii, Ruminococcus bromii	Coprococcus comes, Eubacterium hallii, Ruminococcus bromii
N1050	CDAD,T2D	3	3	100	100	(clade_444 or clade_444i), (clade_478 or clade_478i), clade_537	Eubacterium rectale, Ruminococcus bromii, Subdoligranulum variabile	Eubacterium rectale, Ruminococcus bromii, Subdoligranulum variabile

N1051	CDAD	3	3	100	66.7	(clade_262 or clade_262i), (clade_478 or clade_478i), (clade_516 or clade_516c or clade_516g or clade_516h)	Anaerotruncus colihominis, Faecalibacterium prausnitzii, Ruminococcus torques	Faecalibacterium prausnitzii, Ruminococcus torques
N1052	CDAD,T2D	2	3	0	66.7	(clade_378 or clade_378e), clade_500	Alistipes putredinis, Alistipes shahii, Bacteroides vulgatus	Alistipes putredinis, Alistipes shahii
N1053	CDAD,T2D	3	3	66.7	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_500	Alistipes putredinis, Dorea formicigenerans, Ruminococcus lactaris	Alistipes putredinis, Dorea formicigenerans, Ruminococcus lactaris
N1054	CDAD,T2D	2	3	0	100	(clade_38 or clade_38e or clade_38i), clade_500	Alistipes putredinis, Alistipes shahii, Bacteroides xylanisolvens	Alistipes putredinis, Alistipes shahii, Bacteroides xylanisolvens
N1055	CDAD,T2D	3	3	66.7	100	(clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_500, clade_537	Alistipes putredinis, Clostridium leptum, Dorea formicigenerans	Alistipes putredinis, Clostridium leptum, Dorea formicigenerans
N1056	CDAD	2	3	33.3	100	(clade_478 or clade_478i), clade_500	Alistipes putredinis, Alistipes shahii, Faecalibacterium prausnitzii	Alistipes putredinis, Alistipes shahii, Faecalibacterium prausnitzii
N1057	CDAD,T2D	3	3	100	100	clade_393, clade_396, (clade_444 or clade_444i)	Coprococcus catus, Eubacterium hallii, Roseburia inulinivorans	Coprococcus catus, Eubacterium hallii, Roseburia inulinivorans
N1058	CDAD,T2D	3	3	100	100	(clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_393, (clade_478 or clade_478i)	Coprococcus catus, Dorea formicigenerans, Faecalibacterium prausnitzii	Coprococcus catus, Dorea formicigenerans, Faecalibacterium prausnitzii
N1059	CDAD,T2D	2	3	100	100	(clade_444 or clade_444i), (clade_522 or clade_522i)	Eubacterium eligens, Roseburia intestinalis, Roseburia inulinivorans	Eubacterium eligens, Roseburia intestinalis, Roseburia inulinivorans

N1060	CDAD,T2D	3	3	66.7	100	(clade_262 or clade_262i), clade_396, clade_466	Coprococcus comes, Eubacterium hallii, Odoribacter splanchnicus	Coprococcus comes, Eubacterium hallii, Odoribacter splanchnicus
N1061	CDAD	3	3	100	100	(clade_262 or clade_262i), clade_396, (clade_478 or clade_478i)	Eubacterium hallii, Faecalibacterium prausnitzii, Ruminococcus torques	Eubacterium hallii, Faecalibacterium prausnitzii, Ruminococcus torques
N1062	CDAD,T2D	2	3	100	100	(clade_262 or clade_262i), (clade_444 or clade_444i)	Coprococcus comes, Eubacterium rectale, Roseburia inulinivorans	Coprococcus comes, Eubacterium rectale, Roseburia inulinivorans
N1063	CDAD,T2D	2	3	100	100	clade_396, (clade_444 or clade_444i)	Eubacterium hallii, Roseburia intestinalis, Roseburia inulinivorans	Eubacterium hallii, Roseburia intestinalis, Roseburia inulinivorans
N1064	CDAD,T2D	3	3	100	100	clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i)	Eubacterium hallii, Roseburia inulinivorans, Subdoligranulum variabile	Eubacterium hallii, Roseburia inulinivorans, Subdoligranulum variabile
N1065	CDAD,T2D	2	3	33.3	100	(clade_478 or clade_478i), clade_500	Alistipes putredinis, Alistipes shahii, Subdoligranulum variabile	Alistipes putredinis, Alistipes shahii, Subdoligranulum variabile
N1066	CDAD,T2D	3	3	100	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_494	Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques	Pseudoflavonifractor capillosus, Ruminococcus obeum, Ruminococcus torques
N1067	CDAD,T2D	3	3	66.7	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_445	Desulfovibrio desulfuricans, Ruminococcus obeum, Ruminococcus torques	Desulfovibrio desulfuricans, Ruminococcus obeum, Ruminococcus torques
N1068	CDAD,T2D	3	3	66.7	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or	Alistipes shahii, Ruminococcus obeum, Ruminococcus torques	Alistipes shahii, Ruminococcus obeum, Ruminococcus torques

						clade_309h or clade_309i), clade_500		
N1069	CDAD,T2D	3	3	100	100	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i)	Eubacterium rectale, Ruminococcus obeum, Ruminococcus torques	Eubacterium rectale, Ruminococcus obeum, Ruminococcus torques
N1070	CDAD	3	3	66.7	33.3	(clade_262 or clade_262i), clade_299, (clade_516 or clade_516c or clade_516g or clade_516h)	Anaerotruncus colihominis, Coprococcus comes, Propionibacterium acnes	Coprococcus comes
N1071	CDAD,T2D	3	3	100	66.7	(clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_478 or clade_478i), clade_485	Anaerostipes caccae, Faecalibacterium prausnitzii, Holdemania filiformis	Faecalibacterium prausnitzii, Holdemania filiformis
N1072	CDAD,T2D	3	3	100	33.3	clade_368, (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), clade_485	Blautia hydrogenotrophica, Clostridium bolteae, Holdemania filiformis	Holdemania filiformis
N1073	CDAD,T2D	3	3	66.7	66.7	(clade_444 or clade_444i), (clade_478 or clade_478i), clade_556	Acidaminococcus fermentans, Eubacterium rectale, Subdoligranulum variabile	Eubacterium rectale, Subdoligranulum variabile
N1074	CDAD,T2D	3	3	33.3	66.7	(clade_262 or clade_262i), clade_401, clade_466	Lactococcus lactis, Odoribacter splanchnicus, Ruminococcus lactaris	Odoribacter splanchnicus, Ruminococcus lactaris

N1075	CDAD	3	3	33.3	66.7	(clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_445, (clade_98 or clade_98i)	Desulfovibrio desulfuricans, Dorea formicigenerans, Streptococcus infantis	Desulfovibrio desulfuricans, Dorea formicigenerans
N1076	CDAD,T2D	3	3	100	33.3	(clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_516 or clade_516c or clade_516g or clade_516h)	Anaerotruncus colihominis, Clostridium symbiosum, Dorea formicigenerans	Dorea formicigenerans
N1077	CDAD,T2D	3	3	100	66.7	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), clade_396	Blautia hansenii, Coprococcus comes, Eubacterium hallii	Coprococcus comes, Eubacterium hallii
N1078	CDAD	3	3	33.3	66.7	(clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_445, (clade_98 or clade_98i)	Desulfovibrio desulfuricans, Dorea formicigenerans, Streptococcus australis	Desulfovibrio desulfuricans, Dorea formicigenerans
N1079	CDAD,T2D	3	3	100	66.7	(clade_262 or clade_262i), clade_396, (clade_566 or clade_566f)	Coprococcus comes, Eggerthella lenta, Eubacterium hallii	Coprococcus comes, Eubacterium hallii
N1080	CDAD,T2D	3	3	100	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or	Clostridium nexile, Dorea formicigenerans, Subdoligranulum variabile	Clostridium nexile, Dorea formicigenerans, Subdoligranulum variabile

						clade_360h or clade_360i), (clade_478 or clade_478i)		
N1081	CDAD,T2D	3	3	100	100	(clade_262 or clade_262i), (clade_478 or clade_478i), clade_485	Clostridium nexile, Faecalibacterium prausnitzii, Holdemania filiformis	Clostridium nexile, Faecalibacterium prausnitzii, Holdemania filiformis
N1082	CDAD,T2D	3	3	100	66.7	(clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_478 or clade_478i), clade_485	Clostridium hathewayi, Faecalibacterium prausnitzii, Holdemania filiformis	Faecalibacterium prausnitzii, Holdemania filiformis
N1083	CDAD,T2D	3	3	100	66.7	(clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_444 or clade_444i), (clade_478 or clade_478i)	Clostridium asparagiforme, Eubacterium rectale, Subdoligranulum variabile	Eubacterium rectale, Subdoligranulum variabile
N1084	CDAD,T2D	3	3	33.3	100	(clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_500, clade_85	Alistipes putredinis, Bacteroides eggerthii, Dorea formicigenerans	Alistipes putredinis, Bacteroides eggerthii, Dorea formicigenerans
N1085	CDAD,T2D	3	3	33.3	100	clade_286, (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_466	Dorea formicigenerans, Odoribacter splanchnicus, Parabacteroides merdae	Dorea formicigenerans, Odoribacter splanchnicus, Parabacteroides merdae
N1086	CDAD,T2D	3	3	66.7	100	(clade_172 or clade_172i), (clade_262 or clade_262i), clade_396	Bifidobacterium longum, Coprococcus comes, Eubacterium hallii	Bifidobacterium longum, Coprococcus comes, Eubacterium hallii
N1087	CDAD,T2D	3	3	66.7	100	clade_110, (clade_262 or	Bacteroides uniformis, Coprococcus comes,	Bacteroides uniformis, Coprococcus comes,

						clade_262i), clade_396	Eubacterium hallii	Eubacterium hallii
N1088	CDAD	2	2	100	100	clade_393, (clade_444 or clade_444i)	Coprococcus catus, Eubacterium rectale	Coprococcus catus, Eubacterium rectale
N1089	CDAD	2	2	100	100	(clade_478 or clade_478i), clade_576	Clostridium lactatifermentans, Faecalibacterium prausnitzii	Clostridium lactatifermentans, Faecalibacterium prausnitzii
N1090	CDAD	2	2	0	0	clade_293, (clade_378 or clade_378e)	Bacteroides sp. 3_1_40A, Bifidobacterium bifidum	
N1091	CDAD	2	2	50	50	(clade_444 or clade_444i), clade_561	Alistipes indistinctus, Eubacterium rectale	Eubacterium rectale
N1092	CDAD	2	2	100	50	clade_393, (clade_481 or clade_481a or clade_481b or clade_481e or clade_481g or clade_481h or clade_481i)	Clostridium cocleatum, Coprococcus catus	Coprococcus catus
N1093	CDAD	2	2	50	100	(clade_522 or clade_522i), clade_583	Akkermansia muciniphila, Eubacterium eligens	Akkermansia muciniphila, Eubacterium eligens
N1094	CDAD	2	2	0	0	(clade_497 or clade_497e or clade_497f), clade_89	Granulicatella adiacens, Proteus penneri	
N1095	CDAD	2	2	100	100	(clade_444 or clade_444i), (clade_522 or clade_522i)	Eubacterium eligens, Eubacterium rectale	Eubacterium eligens, Eubacterium rectale
N1096	T2D	2	2	50	50	(clade_378 or clade_378e), (clade_522 or clade_522i)	Bacteroides coprocola, Eubacterium eligens	Eubacterium eligens
N1097	T2D	2	2	50	50	clade_543, clade_88	Butyrivibrio crossotus, Haemophilus parainfluenzae	Butyrivibrio crossotus
N1098	T2D	2	2	100	100	(clade_444 or clade_444i), (clade_478 or clade_478i)	Faecalibacterium prausnitzii, Roseburia intestinalis	Faecalibacterium prausnitzii, Roseburia intestinalis

Table 9.

Keystone OTUs that occur in Network Ecologies representing states of health for various disease indications (CDAD = Clostridium difficile associated diarrhea, T2D = Type 2 Diabetes, Obesity = clinical obesity, UC = ulcerative colitis)

OTU	Clade	Family	Genus	Disease Indication for which Health Keystone OTU
Akkermansia muciniphila	clade_583	Verrucomicrobiaceae	Akkermansia	CDAD
Alistipes putredinis	clade_500	Rikenellaceae	Alistipes	CDAD, T2D
Alistipes shahii	clade_500	Rikenellaceae	Alistipes	CDAD, T2D
Bacteroides caccae	clade_170	Bacteroidaceae	Bacteroides	CDAD, Obesity
Bacteroides cellulosilyticus	clade_85	Bacteroidaceae	Bacteroides	CDAD, T2D
Bacteroides dorei	clade_378	Bacteroidaceae	Bacteroides	CDAD, Obesity, T2D
Bacteroides eggerthii	clade_85	Bacteroidaceae	Bacteroides	T2D
Bacteroides finegoldii	clade_170	Bacteroidaceae	Bacteroides	CDAD, UC
Bacteroides intestinalis	clade_171	Bacteroidaceae	Bacteroides	T2D
Bacteroides ovatus	clade_38	Bacteroidaceae	Bacteroides	Obesity, T2D
Bacteroides sp. D20	clade_110	Bacteroidaceae	Bacteroides	CDAD
Bacteroides stercoris	clade_85	Bacteroidaceae	Bacteroides	CDAD, T2D, UC
Bacteroides thetaiotaomicron	clade_65	Bacteroidaceae	Bacteroides	CDAD, Obesity
Bacteroides uniformis	clade_110	Bacteroidaceae	Bacteroides	T2D, UC
Bacteroides xylanisolvens	clade_38	Bacteroidaceae	Bacteroides	Obesity
Bifidobacterium longum	clade_172	Bifidobacteriaceae	Bifidobacterium	CDAD
Bilophila wadsworthia	clade_521	Desulfovibrionaceae	Bilophila	CDAD
Blautia sp. M25	clade_309	Lachnospiraceae	Blautia	CDAD
Butyricicoccus pullicaecorum	clade_572	Clostridiaceae	Butyricicoccus	CDAD
Butyrivibrio crossotus	clade_543	Lachnospiraceae	Butyrivibrio	CDAD
Catenibacterium mitsuokai	clade_469	Erysipelotrichaceae	Catenibacterium	Obesity
Clostridium lactatifermentans	clade_576	Clostridiaceae	Clostridium	CDAD
Clostridium leptum	clade_537	Clostridiaceae	Clostridium	CDAD, Obesity, T2D
Clostridium nexile	clade_262	Clostridiaceae	Clostridium	CDAD
Clostridium sp. NML 04A032	clade_494	Clostridiaceae	Clostridium	CDAD
Coprococcus catus	clade_393	Lachnospiraceae	Coprococcus	CDAD, T2D
Coprococcus comes	clade_262	Lachnospiraceae	Coprococcus	CDAD, T2D
Desulfovibrio desulfuricans	clade_445	Desulfovibrionaceae	Desulfovibrio	T2D
Desulfovibrio piger	clade_445	Desulfovibrionaceae	Desulfovibrio	Obesity
Dorea formicigenerans	clade_360	Lachnospiraceae	Dorea	CDAD, T2D
Dorea longicatena	clade_360	Lachnospiraceae	Dorea	CDAD, T2D
Eubacterium coprostanoligenes	clade_537	Eubacteriaceae	Eubacterium	CDAD
Eubacterium eligens	clade_522	Eubacteriaceae	Eubacterium	T2D

OTU	Clade	Family	Genus	Disease Indication for which Health Recession OTU
Eubacterium hadrum	clade_408	Lachnospiraceae	Anaerostipes	CDAD
Eubacterium hallii	clade_396	Eubacteriaceae	Eubacterium	CDAD, T2D
Eubacterium rectale	clade_444	Eubacteriaceae	Eubacterium	CDAD, T2D
Eubacterium siraeum	clade_538	Eubacteriaceae	Eubacterium	CDAD
Eubacterium ventriosum	clade_519	Eubacteriaceae	Eubacterium	T2D
Faecalibacterium prausnitzii	clade_478	Ruminococcaceae	Faecalibacterium	CDAD, T2D
Gemmiger formicilis	clade_478	Hyphomicrobiaceae	Gemmiger	CDAD
Gordonibacter pamelaeae	clade_566	Coriobacteriaceae	Gordonibacter	Obesity
Holdemania filiformis	clade_485	Erysipelotrichaceae	Holdemania	CDAD, Obesity, T2D
Lachnospiraceae bacterium 1_4_56FAA	clade_262	Lachnospiraceae		CDAD
Lachnospiraceae bacterium 3_1_57FAA_CT1	clade_408	Lachnospiraceae		CDAD
Odoribacter splanchnicus	clade_466	Porphyromonadaceae	Odoribacter	CDAD, T2D
Oscillibacter valericigenes	clade_540	Oscillospiraceae	Oscillibacter	CDAD
Oxalobacter formigenes	clade_357	Oxalobacteraceae	Oxalobacter	T2D
Parabacteroides johnsonii	clade_286	Porphyromonadaceae	Parabacteroides	CDAD, T2D
Parabacteroides merdae	clade_286	Porphyromonadaceae	Parabacteroides	CDAD, Obesity, T2D
Pseudoflavonifractor capillosus	clade_494		Pseudoflavonifractor	T2D
Roseburia hominis	clade_444	Lachnospiraceae	Roseburia	CDAD
Roseburia intestinalis	clade_444	Lachnospiraceae	Roseburia	CDAD, T2D
Roseburia inulinivorans	clade_444	Lachnospiraceae	Roseburia	CDAD, T2D
Ruminococcus bromii	clade_537	Ruminococcaceae	Ruminococcus	CDAD
Ruminococcus lactaris	clade_262	Ruminococcaceae	Ruminococcus	CDAD
Ruminococcus obeum	clade_309	Lachnospiraceae	Blautia	CDAD, T2D
Ruminococcus torques	clade_262	Lachnospiraceae	Blautia	CDAD, T2D
Sporobacter termitidis	clade_572	Ruminococcaceae	Sporobacter	CDAD
Streptococcus parasanguinis	clade_98	Streptococcaceae	Streptococcus	CDAD
Subdoligranulum variabile	clade_478	Ruminococcaceae	Subdoligranulum	CDAD
Veillonella atypica	clade_358	Veillonellaceae	Veillonella	CDAD
Veillonella parvula	clade_358	Veillonellaceae	Veillonella	CDAD
Victivallis vadensis	clade_567	Victivallaceae	Victivallis	UC

Table 10.

Non-Keystone OTUs that occur in Network Ecologies representing states of health


Non Keystone OTUs
Acidaminococcus fermentans
Acinetobacter johnsonii
Alistipes indistinctus
Anaerostipes caccae
Anaerotruncus colihominis
Auritibacter ignavus
Bacteroides coprocola
Bacteroides coprophilus
Bacteroides fragilis
Bacteroides pectinophilus
Bacteroides plebeius
Bacteroides salanitronis
Bacteroides sp. 1_1_30
Bacteroides sp. 20_3
Bacteroides sp. 3_1_40A
Bacteroides sp. D2
Bacteroides vulgatus
Barnesiella viscericola
Bifidobacterium adolescentis
Bifidobacterium bifidum
Bifidobacterium catenulatum
Bifidobacterium dentium
Bifidobacterium pseudocatenulatum
Blautia hansenii
Blautia hydrogenotrophica
Blautia producta
Campylobacter hominis
Campylobacter upsaliensis
Capnocytophaga sp. oral clone ASCH05
Capnocytophaga sp. oral taxon 338
Chlamydiales bacterium NS13
Chromobacterium violaceum
Citrobacter sp. 30_2
Clostridiales bacterium oral clone P4PA
Clostridiales sp. SS3/4
Clostridium asparagiforme
Clostridium bartlettii
Clostridium beijerinckii
Clostridium bifermentans
Clostridium bolteae
Clostridium botulinum

Seq. Accession (NT)
Clostridium butyricum
Clostridium celatum
Clostridium cocleatum
Clostridium glycolicum
Clostridium hathewayi
Clostridium hylemonae
Clostridium innocuum
Clostridium methylpentosum
Clostridium orbiscindens
Clostridium ramosum
Clostridium scindens
Clostridium symbiosum
Clostridium tertium
Clostridium thermocellum
Collinsella aerofaciens
Collinsella tanakaei
Coprobacillus sp. D7
Coprococcus eutactus
Corynebacterium pseudogenitalium
Dialister invisus
Eggerthella lenta
Enhydrobacter aerosaccus
Enterococcus raffinosus
Enterococcus sp. CCRI 16620
Escherichia coli
Eubacterium desmolans
Eubacterium nodatum
Eubacterium sp. WAL 14571
Eubacterium tenue
Gardnerella vaginalis
Granulicatella adiacens
Haemophilus parainfluenzae
Halorubrum lipolyticum
Heliobacterium modesticaldum
Lachnobacterium bovis
Lachnospiraceae bacterium 1_1_57FAA
Lachnospiraceae bacterium 5_1_57FAA
Lactobacillus ruminis
Lactococcus lactis
Marvinbryantia formatexigens
Methanobrevibacter smithii
Mitsuokella multacida
Mycoplasmataceae genomosp P1 oral clone
Neisseria meningitidis


[illegible]
Parabacteroides distasonis
Peptoniphilus sp. gpac077
Phascolarctobacterium sp. YIT 12068
Porphyromonas asaccharolytica
Prevotella buccae
Prevotella buccalis
Prevotella copri
Propionibacterium acnes
Proteus penneri
Psychrobacter pulmonis
Roseburia faecalis
Rothia mucilaginosa
Ruminococcus albus
Ruminococcus gnavus
Ruminococcus sp. ID8
Scardovia inopinata
Solobacterium moorei
Staphylococcus warneri
Streptococcus australis
Streptococcus dysgalactiae
Streptococcus infantis
Streptococcus mitis
Streptococcus peroris
Streptococcus pyogenes
Streptococcus salivarius
Streptococcus sanguinis
Streptococcus sp. oral clone ASCF07
Streptococcus suis
Streptococcus thermophilus
Streptococcus vestibularis
Sutterella wadsworthensis
Synergistetes bacterium oral taxon D48
Tannerella sp. 6_1_58FAA_CT1
Tissierella praeacuta
Veillonella dispar

Table 11.


Exemplary Functional Network Ecologies that are found only in healthy individuals, that contain only Keystone OTUs, and that have OTUs with the functional capacity to form spores.




(c)


Network Ecology ID
Eubacterium_eligens
Roseburia_intestinalis
Ruminococcus_gnavus
Clostridium_symbiosum
Coprococcus_comes
Dorea_longicatena
Subdoligranulum_variabile
Faecalibacterium_prausnitzii
N77
N78
N79
N80
N81
N82
N83
N84
N85
N86
N87
N88
N89
N90
N91
N92
N93
N94
N95
N96
N97
N98
N99
N100
N101
N102
N103
N104
N105
N106
N107
N108
N109
N110
N111
N112
N113
N114

(d)


Network Ecology ID
Eubacterium_eligens
Roseburia_intestinalis
Ruminococcus_gnavus
Clostridium_symbiosum
Coprococcus_comes
Dorea_longicatena
Subdoligranulum_variabile
Faecalibacterium_prausnitzii
N115
N116
N117
N118
N119
N120
N121
N122
N123
N124
N125
N126
N127
N128
N129
N130
N131
N132
N133
N134
N135
N136
N137
N138
N139
N140
N141
N142
N143
N144
N145
N146
N147
N148
N149
N150
N151
N152

(e)


Network Ecology ID
Eubacterium_eligens
Roseburia_intestinalis
Ruminococcus_gnavus
Clostridium_symbiosum
Coprococcus_comes
Dorea_longicatena
Subdoligranulum_variabile
Faecalibacterium_prausnitzii
N153
N154
N155
N156
N157
N158
N159
N160
N161
N162
N163
N164
N165
N166
N167
N168
N169
N170
N171
N172
N173
N174
N175
N176
N177
N178
N179
N180
N181
N182
N183
N184
N185
N186
N187
N188
N189
N190

(f)



Network Ecology ID
Eubacterium_eligens
Roseburia_intestinalis
Ruminococcus_gnavus
Clostridium_symbiosum
Coprococcus_comes
Dorea_longicatena
Subdoligranulum_variabile
Faecalibacterium_prausnitzii
N191
N192
N193
N194
N195
N196
N197
N198
N199
N200
N201
N202
N203
N204
N205
N206
N207
N208
N209
N210
N211
N212
N213
N214
N215
N216
N217
N218
N219
N220
N221
N222
N223

Table 12.

Exemplary Network Ecologies Classes (a.k.a Core) defined from their occurrence in only healthy individuals, the size of the network, and the frequency of occurrence of the networks in individual subjects at or above the 90th percentile for the latter two metrics. OTUs represent diverse taxonomic families (see Table 1). Numbers in each cell represent the percentage of individual observed Network Ecologies within a given Network Class that contain the given OTU. **(a)** OTUs that are observed in at least 80% of a core's networks (dark grey) are primary signature OTUs of a given core. **(b-c)** OTUs observed in 11%-79% (mid grey) ≤10% (light grey) are secondary and tertiary signature OTUs respectively of a given Network Class. Primary signature OTUs are of greater significance than secondary signature OTUs which are of greater significance than tertiary keystone OTUs.

(a)

Core Network ID	Faecalibacterium_prausnitzii	Ruminococcus_obeum	Alistipes_putredinis	Alistipes_shahii	Ruminococcus_torques	Coprococcus_catus	Dorea_longicatena	Eubacterium_rectale	Bifidobacterium_adolescentis	Coprococcus_comes	Roseburia_inulinivorans	Clostridium_leptum	Gordonibacter_pamelaeae
Core1	100	100	15	15	96	99	100	100	99	13	99	13	
Core2	100	100	100	100	14	100	100	100	100	1	14	16	
Core3	100	100	100	100	8	5	100	100	100	100	8	8	
Core4	100	100	100	100	100	11	11	14		94	10	99	99
Core5	100	100	100	100	100	97	20	17		7	13	91	97
Core6	100	100	100	100	100	100	11	11	2	82	100	10	19

(b)

Core Network ID	Dorea_formicigenerans	Eubacterium_eligens	Eubacterium_hallii	Subdoligranulum_variabile	Bacteroides_ovatus	Eubacterium_ventriosum	Anaerotruncus_colihominis	Bacteroides_vulgatus	Bacteroides_xylanisolvens	Roseburia_intestinalis
Core1	13	12	11	13	11	12	9	9	9	11
Core2	16	15	14	16	10	14	10	11	10	9
Core3	8	8	8	8	8	8	8	7	8	8
Core4	13	11	11	11	11	10	10	15	7	6
Core5	19	20	19	12	17	13	16		7	7
Core6	11	9	10	9	9	9	10	10	5	5



(a)
Core Network ID
Bacteroides_uniformis
Holdemania_filiformis
Parabacteroides_merdae
Collinsella_aerofaciens
Bacteroides_dorei
Odoribacter_splanchnicus
Bilophila_wadsworthia
Ruminococcus_lactaris
Bacteroides_finegoldii
Bacteroides_thetaiotaomicron
Ruminococcus_gnavus
Bacteroides_caccae
Bacteroides_stercoris
Akkermansia_muciniphila
Bifidobacterium_longum
Core1 7 7 8 7 8 7 8 8 7 8 3
Core2 7 3 8 6 8 7 8 4 6 8
Core3 7 7 7 7 7 7 7 7 7 7 7 6 6 6
Core4 5 6 6 5 6 3 5 7 5 5 5 4 1 5
Core5 6 10 4 4 4
Core6 4 4 3 4 3 6 4 3 6 3 6 4 3 3

Table 13.

Network Ecologies Classes (a.k.a. Core) encompass specific phylogenetic signature families based on inclusion of OTUs that are observed in at least 80% of a Class' networks.




Table 14a.

Network Ecologies comprised of one or more clades, or two or more OTUs that are observed in the ethanol-treated spore preparation or the combined engrafted and augmented ecologies of at least one patient post-treatment with the bacterial composition. Network Ecologies are defined based on their clade or OTU content. The respective clades and 16S genetic sequences for each OTU are defined in Table 1. Network Ecology IDs with a ".s" indicates that the network is a subset of the computationally determined networks reported in Table 8 with the same Network Ecology ID.

Network Ecology ID	Num. of Clades in Network Ecology	Num. of OTUs in Network Ecology	Percent of OTUs that are Spore Forming	Percent of Key Stone OTUs in Network Ecology	Exemplary Network clades	Exemplary Network OTUs	Exemplary Keystone OTUs
N262.S	10	15	80	93.3	(clade_172 or clade_172i), (clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_485, clade_494, clade_500, (clade_522 or clade_522i)	Alistipes putredinis, Bifidobacterium dentium, Bifidobacterium longum, Coprococcus comes, Dorea longicatena, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Bifidobacterium longum, Coprococcus comes, Dorea longicatena, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques, Subdoligranulum variabile
N290.S	10	14	92.9	92.9	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_393, clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_494, clade_500, (clade_522 or clade_522i), clade_543	Alistipes putredinis, Coprococcus catus, Coprococcus comes, Coprococcus eutactus, Dorea longicatena, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans,	Alistipes putredinis, Coprococcus catus, Coprococcus comes, Dorea longicatena, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques,

						Ruminococcus torques, Subdoligranulum variabile	Subdoligranulum variabile
N284.S	9	13	92.3	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_393, clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500, clade_519, clade_538	Alistipes putredinis, Coprococcus catus, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Eubacterium siraeum, Eubacterium ventriosum, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Coprococcus catus, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Eubacterium siraeum, Eubacterium ventriosum, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques, Subdoligranulum variabile
N271.S	9	13	84.6	92.3	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_485, clade_494, clade_500, (clade_98 or clade_98i)	Alistipes putredinis, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques, Streptococcus salivarius, Subdoligranulum variabile	Alistipes putredinis, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques, Subdoligranulum variabile

N282.S	9	13	84.6	92.3	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, clade_401, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_485, clade_494, clade_500	Alistipes putredinis, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Lactococcus lactis, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques, Subdoligranulum variabile
N288.S	8	12	91.7	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_485, clade_494, clade_500	Alistipes putredinis, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques, Subdoligranulum variabile
N302.S	8	12	91.7	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_393, clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500, clade_519	Alistipes putredinis, Coprococcus catus, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Coprococcus catus, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques, Subdoligranulum variabile

N279.S	9	12	83.3	100	(clade_172 or clade_172i), (clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_485, clade_494, clade_500	Alistipes putredinis, Bifidobacterium longum, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Roseburia inulinivorans, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Bifidobacterium longum, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Roseburia inulinivorans, Ruminococcus torques, Subdoligranulum variabile
N310.S	7	11	90.9	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_494, clade_500	Alistipes putredinis, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques, Subdoligranulum variabile
N323.S	7	11	90.9	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_393, clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500	Alistipes putredinis, Coprococcus catus, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Coprococcus catus, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques, Subdoligranulum variabile

N331.S	7	11	90.9	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500, clade_538	Alistipes putredinis, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Eubacterium siraeum, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Eubacterium siraeum, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques, Subdoligranulum variabile
N332.S	8	11	81.8	90.9	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_485, clade_494, clade_500, (clade_98 or clade_98i)	Alistipes putredinis, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques, Streptococcus thermophilus, Subdoligranulum variabile	Alistipes putredinis, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques, Subdoligranulum variabile
N301.S	7	10	90	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_485, clade_500	Alistipes putredinis, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques	Alistipes putredinis, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques
N312.S	7	10	90	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500, (clade_522 or clade_522i)	Alistipes putredinis, Coprococcus comes, Dorea longicatena, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques	Alistipes putredinis, Coprococcus comes, Dorea longicatena, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques

N339.S	7	10	80	100	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_494, clade_500, (clade_566 or clade_566f)	Alistipes putredinis, Coprococcus comes, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Gordonibacter pamelaeae, Pseudoflavonifractor capillosus, Roseburia inulinivorans, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Coprococcus comes, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Gordonibacter pamelaeae, Pseudoflavonifractor capillosus, Roseburia inulinivorans, Ruminococcus torques, Subdoligranulum variabile
N325.S	8	10	90	90	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_494, clade_500, (clade_516 or clade_516c or clade_516g or clade_516h)	Alistipes putredinis, Anaerotruncus colihominis, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus torques, Subdoligranulum variabile
N340.S	7	10	90	90	(clade_262 or clade_262i), (clade_354 or clade_354e), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_494, clade_500	Alistipes putredinis, Clostridium bartlettii, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques, Subdoligranulum variabile
N341.S	7	10	90	90	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_494, clade_500, (clade_516 or clade_516c or clade_516g or clade_516h)	Alistipes putredinis, Anaerotruncus colihominis, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques, Subdoligranulum variabile

N346.S	7	10	90	90	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_485, clade_500, (clade_516 or clade_516c or clade_516g or clade_516h)	Alistipes putredinis, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus albus, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques, Subdoligranulum variabile
N338.S	7	10	80	90	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500, (clade_522 or clade_522i), (clade_98 or clade_98i)	Alistipes putredinis, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques, Streptococcus australis, Subdoligranulum variabile	Alistipes putredinis, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques, Subdoligranulum variabile
N336.S	6	9	88.9	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500	Alistipes putredinis, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques	Alistipes putredinis, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques
N345.S	7	9	88.9	100	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_485, clade_494, clade_500	Alistipes putredinis, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Roseburia inulinivorans, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Pseudoflavonifractor capillosus, Roseburia inulinivorans, Ruminococcus torques, Subdoligranulum variabile

N355.S	6	9	88.9	100	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500, clade_519	Alistipes putredinis, Eubacterium hallii, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Eubacterium hallii, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques, Subdoligranulum variabile
N356.S	6	9	88.9	100	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500, clade_537	Alistipes putredinis, Coprococcus comes, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus bromii, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Coprococcus comes, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus bromii, Ruminococcus torques, Subdoligranulum variabile
N343.S	7	9	77.8	100	(clade_262 or clade_262i), clade_286, (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500	Alistipes putredinis, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Parabacteroides merdae, Roseburia inulinivorans, Ruminococcus torques	Alistipes putredinis, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Parabacteroides merdae, Roseburia inulinivorans, Ruminococcus torques
N329.S	6	9	88.9	88.9	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500, (clade_553 or clade_553i)	Alistipes putredinis, Collinsella aerofaciens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques, Subdoligranulum variabile
N361.S	6	9	88.9	88.9	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500, (clade_516 or clade_516c or clade_516g or clade_516h)	Alistipes putredinis, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus albus,	Alistipes putredinis, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques,

						Ruminococcus torques, Subdoligranulum variabile	Subdoligranulum variabile
N353.S	7	9	77.8	88.9	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_494, clade_500, clade_506	Alistipes putredinis, Dialister invisus, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Roseburia inulinivorans, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Roseburia inulinivorans, Ruminococcus torques, Subdoligranulum variabile
N381.S	7	9	100	77.8	(clade_262 or clade_262i), (clade_444 or clade_444i), (clade_478 or clade_478i), clade_494, (clade_516 or clade_516c or clade_516g or clade_516h), (clade_522 or clade_522i), clade_537	Anaerotruncus colihominis, Clostridium leptum, Clostridium methylpentosum, Eubacterium eligens, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques	Clostridium leptum, Eubacterium eligens, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques
N344.S	6	8	87.5	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500	Alistipes putredinis, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus torques	Alistipes putredinis, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus torques
N352.S	5	8	87.5	100	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500	Alistipes putredinis, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques, Subdoligranulum variabile

N357.S	6	8	87.5	100	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_485, clade_500	Alistipes putredinis, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques	Alistipes putredinis, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques
N358.S	5	8	87.5	100	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500	Alistipes putredinis, Coprococcus comes, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques	Alistipes putredinis, Coprococcus comes, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques
N369.S	6	8	87.5	100	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500, (clade_522 or clade_522i)	Alistipes putredinis, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques	Alistipes putredinis, Eubacterium eligens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques
N372.S	6	8	87.5	100	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_494, clade_500	Alistipes putredinis, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Roseburia inulinivorans, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Roseburia inulinivorans, Ruminococcus torques, Subdoligranulum variabile
N375.S	6	8	87.5	100	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500, clade_537	Alistipes putredinis, Clostridium leptum, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Clostridium leptum, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus torques, Subdoligranulum variabile

N380.S	7	8	87.5	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_38 or clade_38e or clade_38i), (clade_444 or clade_444i), (clade_478 or clade_478i), clade_519, (clade_522 or clade_522i)	Bacteroides ovatus, Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus torques	Bacteroides ovatus, Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus torques
N374.S	6	8	75	100	(clade_172 or clade_172i), (clade_262 or clade_262i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500	Alistipes putredinis, Bifidobacterium longum, Coprococcus comes, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus torques	Alistipes putredinis, Bifidobacterium longum, Coprococcus comes, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus torques
N377.S	6	8	75	100	clade_170, (clade_262 or clade_262i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500	Alistipes putredinis, Bacteroides caccae, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques	Alistipes putredinis, Bacteroides caccae, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques
N368.S	6	8	75	87.5	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500, (clade_98 or clade_98i)	Alistipes putredinis, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques, Streptococcus salivarius	Alistipes putredinis, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques
N370.S	5	7	85.7	100	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500	Alistipes putredinis, Coprococcus comes, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus torques	Alistipes putredinis, Coprococcus comes, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus torques

N373.S	6	7	85.7	100	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_485, clade_500	Alistipes putredinis, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Roseburia inulinivorans, Ruminococcus torques	Alistipes putredinis, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Roseburia inulinivorans, Ruminococcus torques
N376.S	5	7	85.7	100	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500	Alistipes putredinis, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques	Alistipes putredinis, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans, Ruminococcus torques
N389.S	6	7	85.7	100	(clade_262 or clade_262i), clade_393, clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500	Alistipes putredinis, Coprococcus catus, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus torques	Alistipes putredinis, Coprococcus catus, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus torques
N394.S	5	7	85.7	100	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500	Alistipes putredinis, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus torques, Subdoligranulum variabile
N431.S	6	7	85.7	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_38 or clade_38e or clade_38i), (clade_444 or clade_444i), (clade_478 or clade_478i), clade_519	Bacteroides ovatus, Dorea longicatena, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus torques	Bacteroides ovatus, Dorea longicatena, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus torques
N434.S	6	7	85.7	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_38 or clade_38e or clade_38i), (clade_444 or clade_444i), (clade_478	Bacteroides ovatus, Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus torques	Bacteroides ovatus, Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus torques

					or clade_478i), (clade_522 or clade_522i)		
N390.S	6	7	71.4	100	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500, clade_521	Alistipes putredinis, Bilophila wadsworthia, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus torques	Alistipes putredinis, Bilophila wadsworthia, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus torques
N397.S	6	7	71.4	100	(clade_262 or clade_262i), (clade_38 or clade_38e or clade_38i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500	Alistipes putredinis, Bacteroides ovatus, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus torques	Alistipes putredinis, Bacteroides ovatus, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus torques
N387.S	6	7	85.7	85.7	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500, (clade_553 or clade_553i)	Alistipes putredinis, Collinsella aerofaciens, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus torques	Alistipes putredinis, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus torques
N440.S	7	7	85.7	85.7	(clade_262 or clade_262i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i), clade_494, clade_537	Clostridium leptum, Clostridium symbiosum, Desulfovibrio desulfuricans, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus torques	Clostridium leptum, Desulfovibrio desulfuricans, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus torques
N396.S	6	7	71.4	85.7	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500, (clade_65 or clade_65e)	Alistipes putredinis, Bacteroides fragilis, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus torques	Alistipes putredinis, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus torques

N399.S	6	6	100	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_494	Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus torques	Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus torques
N403.S	4	6	100	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), (clade_478 or clade_478i)	Coprococcus comes, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus torques	Coprococcus comes, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus torques
N414.S	5	6	100	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), (clade_478 or clade_478i), (clade_522 or clade_522i)	Coprococcus comes, Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus torques	Coprococcus comes, Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus torques
N430.S	6	6	100	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), (clade_478 or clade_478i), clade_519, (clade_522 or clade_522i)	Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Ruminococcus torques	Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Ruminococcus torques
N432.S	4	6	100	100	(clade_262 or clade_262i), (clade_444 or clade_444i), (clade_478 or clade_478i), clade_537	Clostridium leptum, Coprococcus comes, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus torques	Clostridium leptum, Coprococcus comes, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus torques
N436.S	4	6	100	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i)	Coprococcus comes, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Roseburia inulinivorans, Ruminococcus torques	Coprococcus comes, Dorea longicatena, Eubacterium hallii, Eubacterium rectale, Roseburia inulinivorans, Ruminococcus torques

N437.S	3	6	100	100	(clade_262 or clade_262i), (clade_444 or clade_444i), (clade_478 or clade_478i)	Coprococcus comes, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus torques, Subdoligranulum variabile	Coprococcus comes, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus torques, Subdoligranulum variabile
N457.S	5	6	100	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), (clade_478 or clade_478i), (clade_522 or clade_522i)	Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus torques	Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus torques
N545	5	6	100	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), clade_538	Coprococcus comes, Dorea longicatena, Eubacterium hallii, Eubacterium siraeum, Roseburia intestinalis, Roseburia inulinivorans	Coprococcus comes, Dorea longicatena, Eubacterium hallii, Eubacterium siraeum, Roseburia intestinalis, Roseburia inulinivorans
N386.S	5	6	83.3	100	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500	Alistipes putredinis, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus torques	Alistipes putredinis, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus torques
N402.S	5	6	83.3	100	(clade_262 or clade_262i), clade_286, (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), (clade_478 or clade_478i)	Coprococcus comes, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Parabacteroides merdae, Ruminococcus torques	Coprococcus comes, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Parabacteroides merdae, Ruminococcus torques
N405.S	4	6	83.3	100	(clade_262 or clade_262i), (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i)	Desulfovibrio desulfuricans, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus torques, Subdoligranulum variabile	Desulfovibrio desulfuricans, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus torques, Subdoligranulum variabile

N415.S	5	6	83.3	100	clade_170, (clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), (clade_478 or clade_478i)	Bacteroides caccae, Coprococcus comes, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus torques	Bacteroides caccae, Coprococcus comes, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus torques
N421.S	6	6	83.3	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500	Alistipes putredinis, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Roseburia inulinivorans, Subdoligranulum variabile	Alistipes putredinis, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Roseburia inulinivorans, Subdoligranulum variabile
N422.S	5	6	83.3	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), clade_494, clade_500	Alistipes putredinis, Dorea longicatena, Eubacterium rectale, Pseudoflavonifractor capillosus, Roseburia intestinalis, Ruminococcus torques	Alistipes putredinis, Dorea longicatena, Eubacterium rectale, Pseudoflavonifractor capillosus, Roseburia intestinalis, Ruminococcus torques
N423.S	5	6	83.3	100	(clade_262 or clade_262i), (clade_444 or clade_444i), (clade_478 or clade_478i), clade_500, clade_538	Alistipes putredinis, Eubacterium rectale, Eubacterium siraeum, Faecalibacterium prausnitzii, Ruminococcus torques, Subdoligranulum variabile	Alistipes putredinis, Eubacterium rectale, Eubacterium siraeum, Faecalibacterium prausnitzii, Ruminococcus torques, Subdoligranulum variabile
N458.S	6	6	83.3	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_38 or clade_38e or clade_38i), (clade_444 or clade_444i), (clade_478 or clade_478i), (clade_522 or clade_522i)	Bacteroides ovatus, Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus torques	Bacteroides ovatus, Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus torques
N459.S	5	6	83.3	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_38 or clade_38e or clade_38i), (clade_444 or clade_444i), (clade_478	Bacteroides ovatus, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus torques	Bacteroides ovatus, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus torques

					or clade_478i)		
N493.S	6	6	100	83.3	(clade_262 or clade_262i), (clade_354 or clade_354e), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_494	Clostridium bartlettii, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus torques	Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus torques
N416.S	6	6	83.3	83.3	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i), clade_494, clade_500, (clade_516 or clade_516c or clade_516g or clade_516h)	Alistipes putredinis, Anaerotruncus colihominis, Eubacterium hallii, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus torques	Alistipes putredinis, Eubacterium hallii, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus torques
N439.S	6	6	83.3	83.3	(clade_262 or clade_262i), clade_293, (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), (clade_478 or clade_478i), clade_494	Bifidobacterium bifidum, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus torques	Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus torques
N447.S	5	6	83.3	83.3	(clade_262 or clade_262i), (clade_444 or clade_444i), (clade_478 or clade_478i), clade_494, clade_506	Dialister invisus, Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus torques, Subdoligranulum variabile	Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus torques, Subdoligranulum variabile
N490.S	5	6	83.3	83.3	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), (clade_98 or clade_98i)	Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus torques, Streptococcus australis	Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus torques
N526	5	6	83.3	83.3	(clade_262 or clade_262i), clade_271, (clade_360 or clade_360c or clade_360g or clade_360h or	Coprococcus comes, Dorea longicatena, Eubacterium hallii, Roseburia intestinalis, Roseburia inulinivorans, Rothia	Coprococcus comes, Dorea longicatena, Eubacterium hallii, Roseburia intestinalis, Roseburia inulinivorans

					clade_360i), clade_396, (clade_444 or clade_444i)	mucilaginosa	
N429.S	4	5	100	100	(clade_444 or clade_444i), (clade_478 or clade_478i), clade_519, (clade_522 or clade_522i)	Eubacterium eligens, Eubacterium ventriosum, Faecalibacterium prausnitzii, Roseburia inulinivorans, Subdoligranulum variabile	Eubacterium eligens, Eubacterium ventriosum, Faecalibacterium prausnitzii, Roseburia inulinivorans, Subdoligranulum variabile
N433.S	4	5	100	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), (clade_478 or clade_478i)	Coprococcus comes, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus torques	Coprococcus comes, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus torques
N448.S	4	5	100	100	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i)	Coprococcus comes, Eubacterium hallii, Faecalibacterium prausnitzii, Roseburia inulinivorans, Subdoligranulum variabile	Coprococcus comes, Eubacterium hallii, Faecalibacterium prausnitzii, Roseburia inulinivorans, Subdoligranulum variabile
N488.S	4	5	100	100	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i)	Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus torques	Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus torques
N508.S	4	5	100	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), (clade_478 or clade_478i)	Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus torques	Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus torques
N509.S	5	5	100	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), (clade_478 or clade_478i), clade_519	Dorea longicatena, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Ruminococcus torques	Dorea longicatena, Eubacterium rectale, Eubacterium ventriosum, Faecalibacterium prausnitzii, Ruminococcus torques

N510.S	5	5	100	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), (clade_478 or clade_478i), (clade_522 or clade_522i)	Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus torques	Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus torques
N511.S	3	5	100	100	(clade_262 or clade_262i), (clade_444 or clade_444i), (clade_478 or clade_478i)	Coprococcus comes, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus torques	Coprococcus comes, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus torques
N408.S	5	5	80	100	(clade_262 or clade_262i), (clade_478 or clade_478i), clade_494, clade_500, (clade_522 or clade_522i)	Alistipes putredinis, Eubacterium eligens, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus torques	Alistipes putredinis, Eubacterium eligens, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus torques
N446.S	5	5	80	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_444 or clade_444i), clade_500	Alistipes putredinis, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Roseburia inulinivorans	Alistipes putredinis, Coprococcus comes, Dorea longicatena, Eubacterium hallii, Roseburia inulinivorans
N451.S	4	5	80	100	(clade_262 or clade_262i), clade_396, (clade_478 or clade_478i), clade_500	Alistipes putredinis, Coprococcus comes, Eubacterium hallii, Faecalibacterium prausnitzii, Ruminococcus torques	Alistipes putredinis, Coprococcus comes, Eubacterium hallii, Faecalibacterium prausnitzii, Ruminococcus torques
N474.S	5	5	80	100	(clade_262 or clade_262i), (clade_444 or clade_444i), (clade_478 or clade_478i), clade_494, (clade_566 or clade_566f)	Eubacterium rectale, Faecalibacterium prausnitzii, Gordonibacter pamelaeae, Pseudoflavonifractor capillosus, Ruminococcus torques	Eubacterium rectale, Faecalibacterium prausnitzii, Gordonibacter pamelaeae, Pseudoflavonifractor capillosus, Ruminococcus torques
N520.S	5	5	80	100	(clade_262 or clade_262i), (clade_478 or clade_478i), clade_494, clade_537, (clade_566 or clade_566f)	Clostridium leptum, Faecalibacterium prausnitzii, Gordonibacter pamelaeae, Pseudoflavonifractor capillosus, Ruminococcus torques	Clostridium leptum, Faecalibacterium prausnitzii, Gordonibacter pamelaeae, Pseudoflavonifractor capillosus, Ruminococcus torques

N521.S	5	5	80	100	(clade_262 or clade_262i), clade_393, (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i)	Coprococcus catus, Desulfovibrio desulfuricans, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus torques	Coprococcus catus, Desulfovibrio desulfuricans, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus torques
N535.S	4	5	80	100	clade_358, clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i)	Eubacterium hallii, Faecalibacterium prausnitzii, Roseburia inulinivorans, Subdoligranulum variabile, Veillonella atypica	Eubacterium hallii, Faecalibacterium prausnitzii, Roseburia inulinivorans, Subdoligranulum variabile, Veillonella atypica
N516.S	5	5	60	100	clade_393, (clade_444 or clade_444i), clade_445, clade_521, (clade_522 or clade_522i)	Bilophila wadsworthia, Coprococcus catus, Desulfovibrio desulfuricans, Eubacterium eligens, Eubacterium rectale	Bilophila wadsworthia, Coprococcus catus, Desulfovibrio desulfuricans, Eubacterium eligens, Eubacterium rectale
N463.S	5	5	100	80	clade_246, (clade_262 or clade_262i), (clade_444 or clade_444i), (clade_478 or clade_478i), clade_576	Clostridiales sp. SS3/4, Clostridium lactatifermentans, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus torques	Clostridium lactatifermentans, Faecalibacterium prausnitzii, Roseburia inulinivorans, Ruminococcus torques
N518.S	5	5	100	80	(clade_262 or clade_262i), (clade_354 or clade_354e), clade_396, (clade_444 or clade_444i), clade_494	Clostridium bartlettii, Eubacterium hallii, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus torques	Eubacterium hallii, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus torques
N586	3	5	100	80	clade_368, (clade_444 or clade_444i), (clade_478 or clade_478i)	Blautia hydrogenotrophica, Eubacterium rectale, Roseburia intestinalis, Roseburia inulinivorans, Subdoligranulum variabile	Eubacterium rectale, Roseburia intestinalis, Roseburia inulinivorans, Subdoligranulum variabile
N450.S	5	5	80	80	(clade_262 or clade_262i), (clade_478 or clade_478i), clade_494, clade_500, (clade_516 or clade_516c or clade_516g or clade_516h)	Alistipes putredinis, Anaerotruncus colihominis, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus torques	Alistipes putredinis, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus torques

N465.S	4	5	80	80	clade_168, (clade_262 or clade_262i), (clade_444 or clade_444i), (clade_478 or clade_478i)	Eubacterium rectale, Faecalibacterium prausnitzii, Prevotella copri, Roseburia intestinalis, Ruminococcus torques	Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus torques
N519.S	5	5	80	80	(clade_262 or clade_262i), clade_401, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_494	Eubacterium rectale, Faecalibacterium prausnitzii, Lactococcus lactis, Pseudoflavonifractor capillosus, Ruminococcus torques	Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus torques
N537.S	5	5	80	80	(clade_260 or clade_260c or clade_260g or clade_260h), (clade_262 or clade_262i), (clade_444 or clade_444i), clade_445, clade_494	Clostridium scindens, Desulfovibrio desulfuricans, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus torques	Desulfovibrio desulfuricans, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus torques
N419.S	5	5	60	80	(clade_262 or clade_262i), (clade_444 or clade_444i), clade_494, clade_500, (clade_98 or clade_98i)	Alistipes putredinis, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus torques, Streptococcus salivarius	Alistipes putredinis, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus torques
N468.S	5	5	60	80	(clade_262 or clade_262i), clade_293, (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, clade_500	Alistipes putredinis, Bifidobacterium bifidum, Coprococcus comes, Dorea longicatena, Eubacterium hallii	Alistipes putredinis, Coprococcus comes, Dorea longicatena, Eubacterium hallii
N477.S	5	5	60	80	(clade_262 or clade_262i), (clade_444 or clade_444i), clade_494, clade_500, (clade_98 or clade_98i)	Alistipes putredinis, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus torques, Streptococcus thermophilus	Alistipes putredinis, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus torques
N514.S	5	5	60	60	clade_393, (clade_420 or clade_420f), (clade_444 or clade_444i), (clade_522 or clade_522i), clade_558	Clostridiales bacterium oral clone P4PA, Coprococcus catus, Eubacterium eligens, Eubacterium rectale, Tannerella sp. 6_1_58FAA_CT1	Coprococcus catus, Eubacterium eligens, Eubacterium rectale

N382.S	5	5	100	40	(clade_260 or clade_260c or clade_260g or clade_260h), (clade_262 or clade_262i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), clade_537, (clade_553 or clade_553i)	Clostridium hylemonae, Clostridium symbiosum, Collinsella aerofaciens, Coprococcus comes, Ruminococcus bromii	Coprococcus comes, Ruminococcus bromii
N460.S	3	4	100	100	(clade_262 or clade_262i), (clade_444 or clade_444i), (clade_478 or clade_478i)	Coprococcus comes, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus torques	Coprococcus comes, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus torques
N462.S	3	4	100	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_478 or clade_478i)	Coprococcus comes, Dorea longicatena, Faecalibacterium prausnitzii, Subdoligranulum variabile	Coprococcus comes, Dorea longicatena, Faecalibacterium prausnitzii, Subdoligranulum variabile
N512.S	3	4	100	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i)	Coprococcus comes, Dorea longicatena, Eubacterium rectale, Ruminococcus torques	Coprococcus comes, Dorea longicatena, Eubacterium rectale, Ruminococcus torques
N517.S	4	4	100	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), (clade_478 or clade_478i)	Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus torques	Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus torques
N523.S	3	4	100	100	(clade_262 or clade_262i), (clade_444 or clade_444i), (clade_478 or clade_478i)	Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus torques	Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus torques
N547.S	3	4	100	100	(clade_262 or clade_262i), (clade_444 or clade_444i), (clade_478 or clade_478i)	Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus torques, Subdoligranulum variabile	Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus torques, Subdoligranulum variabile

N548.S	4	4	100	100	(clade_262 or clade_262i), (clade_444 or clade_444i), (clade_478 or clade_478i), clade_494	Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus torques	Eubacterium rectale, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus torques
N577.S	3	4	100	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_537	Clostridium leptum, Coprococcus comes, Dorea longicatena, Ruminococcus torques	Clostridium leptum, Coprococcus comes, Dorea longicatena, Ruminococcus torques
N581.S	4	4	100	100	(clade_262 or clade_262i), (clade_478 or clade_478i), clade_494, clade_538	Eubacterium siraeum, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus torques	Eubacterium siraeum, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus torques
N585.S	2	4	100	100	(clade_444 or clade_444i), (clade_478 or clade_478i)	Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans	Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Roseburia inulinivorans
N616.S	4	4	100	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, (clade_478 or clade_478i)	Coprococcus comes, Dorea longicatena, Eubacterium hallii, Faecalibacterium prausnitzii	Coprococcus comes, Dorea longicatena, Eubacterium hallii, Faecalibacterium prausnitzii
N466.S	4	4	75	100	(clade_262 or clade_262i), (clade_444 or clade_444i), clade_494, clade_500	Alistipes putredinis, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus torques	Alistipes putredinis, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus torques
N469.S	4	4	75	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396, clade_500	Alistipes putredinis, Coprococcus comes, Dorea longicatena, Eubacterium hallii	Alistipes putredinis, Coprococcus comes, Dorea longicatena, Eubacterium hallii
N480.S	4	4	75	100	(clade_262 or clade_262i), (clade_478 or clade_478i), clade_500, clade_537	Alistipes putredinis, Faecalibacterium prausnitzii, Ruminococcus bromii, Ruminococcus torques	Alistipes putredinis, Faecalibacterium prausnitzii, Ruminococcus bromii, Ruminococcus torques
N482.S	4	4	75	100	(clade_262 or clade_262i), (clade_478 or clade_478i), clade_500, (clade_522 or clade_522i)	Alistipes putredinis, Eubacterium eligens, Faecalibacterium prausnitzii, Ruminococcus torques	Alistipes putredinis, Eubacterium eligens, Faecalibacterium prausnitzii, Ruminococcus torques

N484.S	4	4	75	100	(clade_262 or clade_262i), clade_396, (clade_478 or clade_478i), clade_500	Alistipes putredinis, Eubacterium hallii, Faecalibacterium prausnitzii, Ruminococcus torques	Alistipes putredinis, Eubacterium hallii, Faecalibacterium prausnitzii, Ruminococcus torques
N515.S	4	4	75	100	clade_393, (clade_444 or clade_444i), clade_521, (clade_522 or clade_522i)	Bilophila wadsworthia, Coprococcus catus, Eubacterium eligens, Eubacterium rectale	Bilophila wadsworthia, Coprococcus catus, Eubacterium eligens, Eubacterium rectale
N533.S	4	4	75	100	(clade_262 or clade_262i), (clade_444 or clade_444i), clade_445, clade_494	Desulfovibrio desulfuricans, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus torques	Desulfovibrio desulfuricans, Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus torques
N709	4	4	75	100	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i), (clade_566 or clade_566f)	Coprococcus comes, Eubacterium hallii, Gordonibacter pamelaeae, Roseburia inulinivorans	Coprococcus comes, Eubacterium hallii, Gordonibacter pamelaeae, Roseburia inulinivorans
N730	4	4	75	100	(clade_262 or clade_262i), clade_286, clade_396, (clade_444 or clade_444i)	Coprococcus comes, Eubacterium hallii, Parabacteroides merdae, Roseburia inulinivorans	Coprococcus comes, Eubacterium hallii, Parabacteroides merdae, Roseburia inulinivorans
N478.S	4	4	50	100	clade_170, (clade_262 or clade_262i), (clade_478 or clade_478i), clade_500	Alistipes putredinis, Bacteroides caccae, Faecalibacterium prausnitzii, Ruminococcus torques	Alistipes putredinis, Bacteroides caccae, Faecalibacterium prausnitzii, Ruminococcus torques
N572.S	4	4	50	100	clade_286, (clade_444 or clade_444i), clade_445, (clade_478 or clade_478i)	Desulfovibrio desulfuricans, Eubacterium rectale, Faecalibacterium prausnitzii, Parabacteroides merdae	Desulfovibrio desulfuricans, Eubacterium rectale, Faecalibacterium prausnitzii, Parabacteroides merdae
N400.S	4	4	100	75	(clade_262 or clade_262i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_444 or clade_444i), (clade_478 or clade_478i)	Clostridium symbiosum, Coprococcus comes, Eubacterium rectale, Faecalibacterium prausnitzii	Coprococcus comes, Eubacterium rectale, Faecalibacterium prausnitzii
N543.S	4	4	100	75	(clade_262 or clade_262i), (clade_354 or clade_354e), (clade_478 or clade_478i), clade_494	Clostridium bartlettii, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus torques	Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus torques

N582.S	4	4	100	75	(clade_262 or clade_262i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_444 or clade_444i), (clade_478 or clade_478i)	Clostridium symbiosum, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus torques	Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus torques
N621.S	4	4	100	75	clade_396, (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_444 or clade_444i), (clade_478 or clade_478i)	Anaerostipes caccae, Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii	Eubacterium hallii, Eubacterium rectale, Faecalibacterium prausnitzii
N689	4	4	100	75	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i), (clade_516 or clade_516c or clade_516g or clade_516h)	Clostridium methylpentosum, Coprococcus comes, Eubacterium hallii, Roseburia inulinivorans	Coprococcus comes, Eubacterium hallii, Roseburia inulinivorans
N769	4	4	100	75	(clade_260 or clade_260c or clade_260g or clade_260h), (clade_262 or clade_262i), (clade_478 or clade_478i), clade_494	Clostridium scindens, Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus torques	Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus torques
N481.S	4	4	75	75	(clade_262 or clade_262i), (clade_478 or clade_478i), clade_500, (clade_553 or clade_553i)	Alistipes putredinis, Collinsella aerofaciens, Faecalibacterium prausnitzii, Ruminococcus torques	Alistipes putredinis, Faecalibacterium prausnitzii, Ruminococcus torques
N525.S	4	4	75	75	(clade_262 or clade_262i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), clade_445, clade_494	Anaerostipes caccae, Desulfovibrio desulfuricans, Pseudoflavonifractor capillosus, Ruminococcus torques	Desulfovibrio desulfuricans, Pseudoflavonifractor capillosus, Ruminococcus torques
N528.S	4	4	75	75	(clade_262 or clade_262i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), clade_445, clade_494	Clostridium symbiosum, Desulfovibrio desulfuricans, Pseudoflavonifractor capillosus, Ruminococcus torques	Desulfovibrio desulfuricans, Pseudoflavonifractor capillosus, Ruminococcus torques

N534.S	4	4	75	75	(clade_262 or clade_262i), (clade_444 or clade_444i), (clade_478 or clade_478i), (clade_65 or clade_65e)	Bacteroides fragilis, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus torques	Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus torques
N574.S	4	4	75	75	clade_396, (clade_478 or clade_478i), clade_537, (clade_98 or clade_98i)	Clostridium leptum, Eubacterium hallii, Faecalibacterium prausnitzii, Streptococcus thermophilus	Clostridium leptum, Eubacterium hallii, Faecalibacterium prausnitzii
N580.S	4	4	75	75	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i), (clade_98 or clade_98i)	Eubacterium hallii, Eubacterium rectale, Ruminococcus torques, Streptococcus australis	Eubacterium hallii, Eubacterium rectale, Ruminococcus torques
N590.S	3	4	75	75	clade_401, (clade_478 or clade_478i), clade_485	Faecalibacterium prausnitzii, Holdemania filiformis, Lactococcus lactis, Subdoligranulum variabile	Faecalibacterium prausnitzii, Holdemania filiformis, Subdoligranulum variabile
N591.S	4	4	75	75	(clade_262 or clade_262i), clade_401, (clade_444 or clade_444i), clade_494	Eubacterium rectale, Lactococcus lactis, Pseudoflavonifractor capillosus, Ruminococcus torques	Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus torques
N597.S	3	4	75	75	(clade_478 or clade_478i), (clade_522 or clade_522i), (clade_98 or clade_98i)	Eubacterium eligens, Faecalibacterium prausnitzii, Streptococcus australis, Subdoligranulum variabile	Eubacterium eligens, Faecalibacterium prausnitzii, Subdoligranulum variabile
N664	4	4	75	75	(clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_378 or clade_378e), (clade_516 or clade_516c or clade_516g or clade_516h), clade_519	Bacteroides dorei, Clostridium methylpentosum, Dorea longicatena, Eubacterium ventriosum	Bacteroides dorei, Dorea longicatena, Eubacterium ventriosum
N693	4	4	75	75	(clade_262 or clade_262i), clade_396, clade_401, (clade_444 or clade_444i)	Coprococcus comes, Eubacterium hallii, Lactococcus lactis, Roseburia inulinivorans	Coprococcus comes, Eubacterium hallii, Roseburia inulinivorans
N530.S	4	4	50	75	(clade_262 or clade_262i), (clade_444 or clade_444i), clade_500, (clade_98 or clade_98i)	Alistipes putredinis, Eubacterium rectale, Ruminococcus torques, Streptococcus australis	Alistipes putredinis, Eubacterium rectale, Ruminococcus torques

N687	4	4	100	50	clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i), clade_543	Bacteroides pectinophilus, Coprococcus eutactus, Faecalibacterium prausnitzii, Roseburia intestinalis	Faecalibacterium prausnitzii, Roseburia intestinalis
N470.S	2	3	100	100	(clade_478 or clade_478i), clade_485	Faecalibacterium prausnitzii, Holdemania filiformis, Subdoligranulum variabile	Faecalibacterium prausnitzii, Holdemania filiformis, Subdoligranulum variabile
N529.S	3	3	100	100	(clade_262 or clade_262i), (clade_478 or clade_478i), clade_494	Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus torques	Faecalibacterium prausnitzii, Pseudoflavonifractor capillosus, Ruminococcus torques
N539.S	2	3	100	100	(clade_262 or clade_262i), (clade_444 or clade_444i)	Eubacterium rectale, Roseburia intestinalis, Ruminococcus torques	Eubacterium rectale, Roseburia intestinalis, Ruminococcus torques
N546.S	3	3	100	100	(clade_262 or clade_262i), (clade_444 or clade_444i), (clade_478 or clade_478i)	Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus torques	Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus torques
N570.S	3	3	100	100	(clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), (clade_478 or clade_478i)	Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii	Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii
N579.S	3	3	100	100	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i)	Eubacterium hallii, Eubacterium rectale, Ruminococcus torques	Eubacterium hallii, Eubacterium rectale, Ruminococcus torques
N602.S	3	3	100	100	clade_396, (clade_444 or clade_444i), (clade_478 or clade_478i)	Eubacterium hallii, Roseburia inulinivorans, Subdoligranulum variabile	Eubacterium hallii, Roseburia inulinivorans, Subdoligranulum variabile
N614.S	3	3	100	100	(clade_262 or clade_262i), (clade_478 or clade_478i), clade_537	Clostridium leptum, Faecalibacterium prausnitzii, Ruminococcus torques	Clostridium leptum, Faecalibacterium prausnitzii, Ruminococcus torques
N648.S	3	3	100	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_478 or clade_478i)	Dorea longicatena, Faecalibacterium prausnitzii, Ruminococcus torques	Dorea longicatena, Faecalibacterium prausnitzii, Ruminococcus torques
N652.S	3	3	100	100	clade_393, (clade_444 or clade_444i), (clade_522 or clade_522i)	Coprococcus catus, Eubacterium eligens, Eubacterium rectale	Coprococcus catus, Eubacterium eligens, Eubacterium rectale

N655.S	2	3	100	100	(clade_444 or clade_444i), (clade_478 or clade_478i)	Eubacterium rectale, Faecalibacterium prausnitzii, Subdoligranulum variabile	Eubacterium rectale, Faecalibacterium prausnitzii, Subdoligranulum variabile
N672.S	3	3	100	100	(clade_262 or clade_262i), (clade_444 or clade_444i), clade_494	Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus torques	Eubacterium rectale, Pseudoflavonifractor capillosus, Ruminococcus torques
N681.S	2	3	100	100	(clade_262 or clade_262i), (clade_478 or clade_478i)	Coprococcus comes, Faecalibacterium prausnitzii, Ruminococcus torques	Coprococcus comes, Faecalibacterium prausnitzii, Ruminococcus torques
N690.S	3	3	100	100	(clade_262 or clade_262i), clade_396, (clade_444 or clade_444i)	Coprococcus comes, Eubacterium hallii, Roseburia inulinivorans	Coprococcus comes, Eubacterium hallii, Roseburia inulinivorans
N692.S	3	3	100	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_396	Coprococcus comes, Dorea longicatena, Eubacterium hallii	Coprococcus comes, Dorea longicatena, Eubacterium hallii
N698.S	2	3	100	100	(clade_444 or clade_444i), (clade_478 or clade_478i)	Eubacterium rectale, Roseburia intestinalis, Subdoligranulum variabile	Eubacterium rectale, Roseburia intestinalis, Subdoligranulum variabile
N737.S	3	3	100	100	(clade_262 or clade_262i), clade_393, (clade_444 or clade_444i)	Coprococcus catus, Eubacterium rectale, Ruminococcus torques	Coprococcus catus, Eubacterium rectale, Ruminococcus torques
N738.S	3	3	100	100	(clade_262 or clade_262i), (clade_478 or clade_478i), clade_485	Faecalibacterium prausnitzii, Holdemania filiformis, Ruminococcus torques	Faecalibacterium prausnitzii, Holdemania filiformis, Ruminococcus torques
N785	3	3	100	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_519	Coprococcus comes, Dorea longicatena, Eubacterium ventriosum	Coprococcus comes, Dorea longicatena, Eubacterium ventriosum
N841	3	3	100	100	(clade_262 or clade_262i), (clade_478 or clade_478i), clade_537	Faecalibacterium prausnitzii, Ruminococcus bromii, Ruminococcus torques	Faecalibacterium prausnitzii, Ruminococcus bromii, Ruminococcus torques
N878	2	3	100	100	(clade_444 or clade_444i), (clade_522 or clade_522i)	Eubacterium eligens, Roseburia intestinalis, Roseburia inulinivorans	Eubacterium eligens, Roseburia intestinalis, Roseburia inulinivorans
N880	2	3	100	100	(clade_262 or clade_262i), (clade_444 or clade_444i)	Coprococcus comes, Eubacterium rectale, Roseburia inulinivorans	Coprococcus comes, Eubacterium rectale, Roseburia inulinivorans
N881	2	3	100	100	clade_396, (clade_444 or clade_444i)	Eubacterium hallii, Roseburia intestinalis, Roseburia inulinivorans	Eubacterium hallii, Roseburia intestinalis, Roseburia inulinivorans

N987	3	3	100	100	(clade_262 or clade_262i), clade_396, clade_537	Coprococcus comes, Eubacterium hallii, Ruminococcus bromii	Coprococcus comes, Eubacterium hallii, Ruminococcus bromii
N988	3	3	100	100	(clade_444 or clade_444i), (clade_478 or clade_478i), clade_537	Eubacterium rectale, Ruminococcus bromii, Subdoligranulum variabile	Eubacterium rectale, Ruminococcus bromii, Subdoligranulum variabile
N996	3	3	100	100	clade_393, clade_396, (clade_444 or clade_444i)	Coprococcus catus, Eubacterium hallii, Roseburia inulinivorans	Coprococcus catus, Eubacterium hallii, Roseburia inulinivorans
N1061	3	3	100	100	(clade_262 or clade_262i), clade_396, (clade_478 or clade_478i)	Eubacterium hallii, Faecalibacterium prausnitzii, Ruminococcus torques	Eubacterium hallii, Faecalibacterium prausnitzii, Ruminococcus torques
N479.S	3	3	66.7	100	(clade_262 or clade_262i), (clade_478 or clade_478i), clade_500	Alistipes putredinis, Faecalibacterium prausnitzii, Ruminococcus torques	Alistipes putredinis, Faecalibacterium prausnitzii, Ruminococcus torques
N538.S	3	3	66.7	100	(clade_262 or clade_262i), clade_445, clade_494	Desulfovibrio desulfuricans, Pseudoflavonifractor capillosus, Ruminococcus torques	Desulfovibrio desulfuricans, Pseudoflavonifractor capillosus, Ruminococcus torques
N542.S	3	3	66.7	100	(clade_262 or clade_262i), (clade_444 or clade_444i), clade_500	Alistipes putredinis, Eubacterium rectale, Ruminococcus torques	Alistipes putredinis, Eubacterium rectale, Ruminococcus torques
N578.S	3	3	66.7	100	(clade_262 or clade_262i), clade_445, (clade_478 or clade_478i)	Desulfovibrio desulfuricans, Faecalibacterium prausnitzii, Ruminococcus torques	Desulfovibrio desulfuricans, Faecalibacterium prausnitzii, Ruminococcus torques
N609.S	3	3	66.7	100	(clade_262 or clade_262i), clade_286, (clade_444 or clade_444i)	Eubacterium rectale, Parabacteroides merdae, Ruminococcus torques	Eubacterium rectale, Parabacteroides merdae, Ruminococcus torques
N611.S	3	3	66.7	100	(clade_262 or clade_262i), (clade_378 or clade_378e), (clade_478 or clade_478i)	Bacteroides dorei, Faecalibacterium prausnitzii, Ruminococcus torques	Bacteroides dorei, Faecalibacterium prausnitzii, Ruminococcus torques
N617.S	3	3	66.7	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_500	Alistipes putredinis, Dorea longicatena, Ruminococcus torques	Alistipes putredinis, Dorea longicatena, Ruminococcus torques
N666.S	3	3	66.7	100	(clade_444 or clade_444i), clade_521, (clade_522 or clade_522i)	Bilophila wadsworthia, Eubacterium eligens, Eubacterium rectale	Bilophila wadsworthia, Eubacterium eligens, Eubacterium rectale
N675.S	3	3	66.7	100	(clade_262 or clade_262i), (clade_38 or clade_38e or clade_38i), (clade_478 or clade_478i)	Bacteroides ovatus, Faecalibacterium prausnitzii, Ruminococcus torques	Bacteroides ovatus, Faecalibacterium prausnitzii, Ruminococcus torques

N682.S	3	3	66.7	100	clade_170, (clade_444 or clade_444i), (clade_478 or clade_478i)	Bacteroides caccae, Eubacterium rectale, Faecalibacterium prausnitzii	Bacteroides caccae, Eubacterium rectale, Faecalibacterium prausnitzii
N844	3	3	66.7	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), clade_521	Bilophila wadsworthia, Coprococcus comes, Dorea longicatena	Bilophila wadsworthia, Coprococcus comes, Dorea longicatena
N845	3	3	66.7	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_378 or clade_378e)	Bacteroides dorei, Coprococcus comes, Dorea longicatena	Bacteroides dorei, Coprococcus comes, Dorea longicatena
N846	3	3	66.7	100	clade_170, (clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h clade_360i)	Bacteroides caccae, Coprococcus comes, Dorea longicatena	Bacteroides caccae, Coprococcus comes, Dorea longicatena
N852	3	3	66.7	100	(clade_172 or clade_172i), (clade_262 or clade_262i), (clade_478 or clade_478i)	Bifidobacterium longum, Faecalibacterium prausnitzii, Ruminococcus torques	Bifidobacterium longum, Faecalibacterium prausnitzii, Ruminococcus torques
N876	2	3	66.7	100	clade_170, (clade_444 or clade_444i)	Bacteroides caccae, Roseburia intestinalis, Roseburia inulinivorans	Bacteroides caccae, Roseburia intestinalis, Roseburia inulinivorans
N982	3	3	66.7	100	(clade_172 or clade_172i), (clade_262 or clade_262i), clade_396	Bifidobacterium longum, Coprococcus comes, Eubacterium hallii	Bifidobacterium longum, Coprococcus comes, Eubacterium hallii
N1008	3	3	66.7	100	(clade_262 or clade_262i), (clade_478 or clade_478i), clade_521	Bilophila wadsworthia, Faecalibacterium prausnitzii, Ruminococcus torques	Bilophila wadsworthia, Faecalibacterium prausnitzii, Ruminococcus torques
N649.S	3	3	33.3	100	(clade_378 or clade_378e), (clade_444 or clade_444i), clade_445	Bacteroides dorei, Desulfovibrio desulfuricans, Eubacterium rectale	Bacteroides dorei, Desulfovibrio desulfuricans, Eubacterium rectale
N657.S	3	3	33.3	100	(clade_378 or clade_378e), (clade_38 or clade_38e or clade_38i), (clade_478 or clade_478i)	Bacteroides dorei, Bacteroides ovatus, Faecalibacterium prausnitzii	Bacteroides dorei, Bacteroides ovatus, Faecalibacterium prausnitzii
N678.S	3	3	33.3	100	clade_445, (clade_478 or clade_478i), clade_583	Akkermansia muciniphila, Desulfovibrio desulfuricans, Faecalibacterium prausnitzii	Akkermansia muciniphila, Desulfovibrio desulfuricans, Faecalibacterium prausnitzii

N686.S	3	3	33.3	100	(clade_378 or clade_378e), (clade_38 or clade_38e or clade_38i), clade_485	Bacteroides dorei, Bacteroides ovatus, Holdemania filiformis	Bacteroides dorei, Bacteroides ovatus, Holdemania filiformis
N710.S	3	3	33.3	100	(clade_478 or clade_478i), clade_500, (clade_566 or clade_566f)	Alistipes putredinis, Gordonibacter pamelaeae, Subdoligranulum variabile	Alistipes putredinis, Gordonibacter pamelaeae, Subdoligranulum variabile
N522.S	3	3	100	66.7	(clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), clade_494, clade_538	Clostridium symbiosum, Eubacterium siraeum, Pseudoflavonifractor capillosus	Eubacterium siraeum, Pseudoflavonifractor capillosus
N651.S	3	3	100	66.7	(clade_444 or clade_444i), (clade_516 or clade_516c or clade_516g or clade_516h), (clade_522 or clade_522i)	Anaerotruncus colihominis, Eubacterium eligens, Roseburia inulinivorans	Eubacterium eligens, Roseburia inulinivorans
N653.S	3	3	100	66.7	clade_396, (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_444 or clade_444i)	Anaerostipes caccae, Eubacterium hallii, Eubacterium rectale	Eubacterium hallii, Eubacterium rectale
N654.S	3	3	100	66.7	(clade_444 or clade_444i), (clade_478 or clade_478i), (clade_516 or clade_516c or clade_516g or clade_516h)	Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus albus	Eubacterium rectale, Faecalibacterium prausnitzii
N680.S	3	3	100	66.7	(clade_262 or clade_262i), clade_368, (clade_478 or clade_478i)	Blautia hydrogenotrophica, Faecalibacterium prausnitzii, Ruminococcus torques	Faecalibacterium prausnitzii, Ruminococcus torques
N712.S	2	3	100	66.7	(clade_260 or clade_260c or clade_260g or clade_260h), (clade_478 or clade_478i)	Clostridium scindens, Faecalibacterium prausnitzii, Subdoligranulum variabile	Faecalibacterium prausnitzii, Subdoligranulum variabile
N792	3	3	100	66.7	(clade_444 or clade_444i), (clade_478 or clade_478i), (clade_516 or clade_516c or clade_516g or clade_516h)	Clostridium methylpentosum, Eubacterium rectale, Subdoligranulum variabile	Eubacterium rectale, Subdoligranulum variabile
N802	3	3	100	66.7	(clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), clade_485, clade_537	Anaerostipes caccae, Clostridium leptum, Holdemania filiformis	Clostridium leptum, Holdemania filiformis

N804	3	3	100	66.7	clade_485, clade_494, clade_543	Coprococcus eutactus, Holdemania filiformis, Pseudoflavonifractor capillosus	Holdemania filiformis, Pseudoflavonifractor capillosus
N807	3	3	100	66.7	(clade_262 or clade_262i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_478 or clade_478i)	Anaerostipes caccae, Coprococcus comes, Subdoligranulum variabile	Coprococcus comes, Subdoligranulum variabile
N849	3	3	100	66.7	(clade_444 or clade_444i), (clade_481 or clade_481a or clade_481b or clade_481e or clade_481g or clade_481h or clade_481i), (clade_522 or clade_522i)	Clostridium cocleatum, Eubacterium eligens, Eubacterium rectale	Eubacterium eligens, Eubacterium rectale
N858	3	3	100	66.7	(clade_262 or clade_262i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), clade_494	Anaerostipes caccae, Pseudoflavonifractor capillosus, Ruminococcus torques	Pseudoflavonifractor capillosus, Ruminococcus torques
N859	3	3	100	66.7	(clade_260 or clade_260c or clade_260g or clade_260h), (clade_262 or clade_262i), clade_494	Clostridium scindens, Pseudoflavonifractor capillosus, Ruminococcus torques	Pseudoflavonifractor capillosus, Ruminococcus torques
N875	2	3	100	66.7	(clade_444 or clade_444i), (clade_516 or clade_516c or clade_516g or clade_516h)	Anaerotruncus colihominis, Roseburia intestinalis, Roseburia inulinivorans	Roseburia intestinalis, Roseburia inulinivorans
N885	3	3	100	66.7	(clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_478 or clade_478i), clade_485	Anaerostipes caccae, Faecalibacterium prausnitzii, Holdemania filiformis	Faecalibacterium prausnitzii, Holdemania filiformis
N942	3	3	100	66.7	(clade_260 or clade_260c or clade_260g or clade_260h), clade_396, (clade_444 or clade_444i)	Clostridium scindens, Eubacterium hallii, Roseburia inulinivorans	Eubacterium hallii, Roseburia inulinivorans
N961	3	3	100	66.7	(clade_354 or clade_354e), (clade_444 or clade_444i), (clade_478 or clade_478i)	Clostridium bartlettii, Eubacterium rectale, Subdoligranulum variabile	Eubacterium rectale, Subdoligranulum variabile

N972	3	3	100	66.7	(clade_444 or clade_444i), (clade_478 or clade_478i), (clade_516 or clade_516c or clade_516g or clade_516h)	Anaerotruncus colihominis, Eubacterium rectale, Subdoligranulum variabile	Eubacterium rectale, Subdoligranulum variabile
N1051	3	3	100	66.7	(clade_262 or clade_262i), (clade_478 or clade_478i), (clade_516 or clade_516c or clade_516g or clade_516h)	Anaerotruncus colihominis, Faecalibacterium prausnitzii, Ruminococcus torques	Faecalibacterium prausnitzii, Ruminococcus torques
N587.S	3	3	66.7	66.7	(clade_478 or clade_478i), clade_500, (clade_516 or clade_516c or clade_516g or clade_516h)	Alistipes putredinis, Clostridium methylpentosum, Subdoligranulum variabile	Alistipes putredinis, Subdoligranulum variabile
N589.S	3	3	66.7	66.7	(clade_262 or clade_262i), clade_293, (clade_478 or clade_478i)	Bifidobacterium bifidum, Faecalibacterium prausnitzii, Ruminococcus torques	Faecalibacterium prausnitzii, Ruminococcus torques
N612.S	3	3	66.7	66.7	(clade_262 or clade_262i), (clade_444 or clade_444i), (clade_98 or clade_98i)	Eubacterium rectale, Ruminococcus torques, Streptococcus salivarius	Eubacterium rectale, Ruminococcus torques
N625.S	3	3	66.7	66.7	(clade_444 or clade_444i), (clade_478 or clade_478i), (clade_98 or clade_98i)	Eubacterium rectale, Faecalibacterium prausnitzii, Streptococcus salivarius	Eubacterium rectale, Faecalibacterium prausnitzii
N656.S	3	3	66.7	66.7	clade_170, clade_396, clade_537	Bacteroides caccae, Bacteroides pectinophilus, Clostridium leptum	Bacteroides caccae, Clostridium leptum
N714.S	2	3	66.7	66.7	(clade_478 or clade_478i), (clade_98 or clade_98i)	Faecalibacterium prausnitzii, Streptococcus thermophilus, Subdoligranulum variabile	Faecalibacterium prausnitzii, Subdoligranulum variabile
N779	3	3	66.7	66.7	(clade_444 or clade_444i), (clade_478 or clade_478i), (clade_98 or clade_98i)	Faecalibacterium prausnitzii, Roseburia intestinalis, Streptococcus australis	Faecalibacterium prausnitzii, Roseburia intestinalis
N781	3	3	66.7	66.7	clade_293, clade_393, (clade_444 or clade_444i)	Bifidobacterium bifidum, Coprococcus catus, Eubacterium rectale	Coprococcus catus, Eubacterium rectale
N828	3	3	66.7	66.7	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_98 or clade_98i)	Coprococcus comes, Dorea longicatena, Streptococcus australis	Coprococcus comes, Dorea longicatena

N829	3	3	66.7	66.7	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_65 or clade_65e)	Bacteroides fragilis, Coprococcus comes, Dorea longicatena	Coprococcus comes, Dorea longicatena
N860	3	3	66.7	66.7	(clade_262 or clade_262i), clade_494, (clade_98 or clade_98i)	Pseudoflavonifractor capillosus, Ruminococcus torques, Streptococcus thermophilus	Pseudoflavonifractor capillosus, Ruminococcus torques
N894	3	3	66.7	66.7	clade_293, (clade_444 or clade_444i), (clade_478 or clade_478i)	Bifidobacterium bifidum, Eubacterium rectale, Subdoligranulum variabile	Eubacterium rectale, Subdoligranulum variabile
N925	3	3	66.7	66.7	clade_396, (clade_444 or clade_444i), (clade_98 or clade_98i)	Eubacterium hallii, Roseburia inulinivorans, Streptococcus australis	Eubacterium hallii, Roseburia inulinivorans
N927	3	3	66.7	66.7	clade_396, (clade_444 or clade_444i), clade_506	Dialister invisus, Eubacterium hallii, Roseburia inulinivorans	Eubacterium hallii, Roseburia inulinivorans
N935	3	3	66.7	66.7	clade_396, (clade_444 or clade_444i), (clade_65 or clade_65e)	Bacteroides fragilis, Eubacterium hallii, Roseburia inulinivorans	Eubacterium hallii, Roseburia inulinivorans
N947	3	3	66.7	66.7	clade_396, (clade_444 or clade_444i), (clade_98 or clade_98i)	Eubacterium hallii, Roseburia inulinivorans, Streptococcus thermophilus	Eubacterium hallii, Roseburia inulinivorans
N983	3	3	66.7	66.7	clade_396, (clade_444 or clade_444i), (clade_98 or clade_98i)	Eubacterium hallii, Roseburia inulinivorans, Streptococcus salivarius	Eubacterium hallii, Roseburia inulinivorans
N1023	3	3	66.7	66.7	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_98 or clade_98i)	Dorea longicatena, Ruminococcus torques, Streptococcus salivarius	Dorea longicatena, Ruminococcus torques
N441.S	3	3	100	33.3	clade_252, (clade_262 or clade_262i), (clade_354 or clade_354e)	Clostridium butyricum, Eubacterium tenue, Ruminococcus torques	Ruminococcus torques
N584.S	3	3	100	33.3	(clade_262 or clade_262i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_553 or clade_553i)	Clostridium symbiosum, Collinsella aerofaciens, Coprococcus comes	Coprococcus comes
N794	3	3	100	33.3	(clade_516 or clade_516c or clade_516g or clade_516h), clade_537, clade_543	Anaerotruncus colihominis, Clostridium leptum, Coprococcus eutactus	Clostridium leptum

N788	1	3	100	0	(clade_516 or clade_516c or clade_516g or clade_516h)	Anaerotruncus colihominis, Clostridium methylpentosum, Ruminococcus albus	
N524.S	1	2	100	100	(clade_478 or clade_478i)	Faecalibacterium prausnitzii, Subdoligranulum variabile	Faecalibacterium prausnitzii, Subdoligranulum variabile
N604.S	2	2	100	100	(clade_262 or clade_262i), (clade_478 or clade_478i)	Faecalibacterium prausnitzii, Ruminococcus torques	Faecalibacterium prausnitzii, Ruminococcus torques
N610.S	2	2	100	100	(clade_262 or clade_262i), (clade_444 or clade_444i)	Eubacterium rectale, Ruminococcus torques	Eubacterium rectale, Ruminococcus torques
N623.S	2	2	100	100	(clade_444 or clade_444i), (clade_478 or clade_478i)	Eubacterium rectale, Faecalibacterium prausnitzii	Eubacterium rectale, Faecalibacterium prausnitzii
N663.S	2	2	100	100	(clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i)	Dorea longicatena, Roseburia inulinivorans	Dorea longicatena, Roseburia inulinivorans
N669.S	2	2	100	100	(clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h clade_360i)	Coprococcus comes, Dorea longicatena	Coprococcus comes, Dorea longicatena
N676.S	2	2	100	100	(clade_262 or clade_262i), clade_494	Pseudoflavonifractor capillosus, Ruminococcus torques	Pseudoflavonifractor capillosus, Ruminococcus torques
N703.S	2	2	100	100	(clade_478 or clade_478i), clade_485	Faecalibacterium prausnitzii, Holdemania filiformis	Faecalibacterium prausnitzii, Holdemania filiformis
N775.S	2	2	100	100	(clade_262 or clade_262i), clade_396	Coprococcus comes, Eubacterium hallii	Coprococcus comes, Eubacterium hallii
N777.S	2	2	100	100	(clade_444 or clade_444i), clade_519	Eubacterium ventriosum, Roseburia inulinivorans	Eubacterium ventriosum, Roseburia inulinivorans
N780.S	2	2	100	100	(clade_444 or clade_444i), (clade_478 or clade_478i)	Faecalibacterium prausnitzii, Roseburia intestinalis	Faecalibacterium prausnitzii, Roseburia intestinalis
N817.S	2	2	100	100	clade_519, clade_537	Clostridium leptum, Eubacterium ventriosum	Clostridium leptum, Eubacterium ventriosum
N827.S	2	2	100	100	(clade_444 or clade_444i), (clade_522 or clade_522i)	Eubacterium eligens, Eubacterium rectale	Eubacterium eligens, Eubacterium rectale
N836.S	2	2	100	100	(clade_478 or clade_478i), clade_494	Pseudoflavonifractor capillosus, Subdoligranulum variabile	Pseudoflavonifractor capillosus, Subdoligranulum variabile

N871.S	1	2	100	100	(clade_444 or clade_444i)	Roseburia intestinalis, Roseburia inulinivorans	Roseburia intestinalis, Roseburia inulinivorans
N874.S	2	2	100	100	clade_396, (clade_444 or clade_444i)	Eubacterium hallii, Roseburia inulinivorans	Eubacterium hallii, Roseburia inulinivorans
N898.S	2	2	100	100	(clade_444 or clade_444i), (clade_478 or clade_478i)	Eubacterium rectale, Subdoligranulum variabile	Eubacterium rectale, Subdoligranulum variabile
N907.S	2	2	100	100	(clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i)	Dorea longicatena, Roseburia intestinalis	Dorea longicatena, Roseburia intestinalis
N998.S	2	2	100	100	clade_393, (clade_478 or clade_478i)	Coprococcus catus, Faecalibacterium prausnitzii	Coprococcus catus, Faecalibacterium prausnitzii
N1088	2	2	100	100	clade_393, (clade_444 or clade_444i)	Coprococcus catus, Eubacterium rectale	Coprococcus catus, Eubacterium rectale
N1089	2	2	100	100	(clade_478 or clade_478i), clade_576	Clostridium lactatifermentans, Faecalibacterium prausnitzii	Clostridium lactatifermentans, Faecalibacterium prausnitzii
N660.S	2	2	50	100	(clade_172 or clade_172i), clade_485	Bifidobacterium longum, Holdemania filiformis	Bifidobacterium longum, Holdemania filiformis
N665.S	2	2	50	100	clade_286, (clade_444 or clade_444i)	Parabacteroides merdae, Roseburia intestinalis	Parabacteroides merdae, Roseburia intestinalis
N667.S	2	2	50	100	clade_500, (clade_522 or clade_522i)	Alistipes putredinis, Eubacterium eligens	Alistipes putredinis, Eubacterium eligens
N733.S	2	2	50	100	(clade_262 or clade_262i), (clade_38 or clade_38e or clade_38i)	Bacteroides ovatus, Ruminococcus torques	Bacteroides ovatus, Ruminococcus torques
N734.S	2	2	50	100	(clade_262 or clade_262i), clade_521	Bilophila wadsworthia, Ruminococcus torques	Bilophila wadsworthia, Ruminococcus torques
N739.S	2	2	50	100	(clade_478 or clade_478i), clade_500	Alistipes putredinis, Faecalibacterium prausnitzii	Alistipes putredinis, Faecalibacterium prausnitzii
N741.S	2	2	50	100	(clade_262 or clade_262i), clade_500	Alistipes putredinis, Ruminococcus torques	Alistipes putredinis, Ruminococcus torques
N782.S	2	2	50	100	clade_171, (clade_522 or clade_522i)	Bacteroides intestinalis, Eubacterium eligens	Bacteroides intestinalis, Eubacterium eligens
N789.S	2	2	50	100	clade_357, clade_537	Clostridium leptum, Oxalobacter formigenes	Clostridium leptum, Oxalobacter formigenes
N796.S	2	2	50	100	clade_500, clade_537	Alistipes putredinis, Ruminococcus bromii	Alistipes putredinis, Ruminococcus bromii
N798.S	2	2	50	100	(clade_378 or clade_378e), clade_494	Bacteroides dorei, Pseudoflavonifractor capillosus	Bacteroides dorei, Pseudoflavonifractor capillosus
N800.S	2	2	50	100	clade_445, clade_537	Clostridium leptum, Desulfovibrio desulfuricans	Clostridium leptum, Desulfovibrio desulfuricans

N809.S	2	2	50	100	clade_445, (clade_478 or clade_478i)	Desulfovibrio desulfuricans, Faecalibacterium prausnitzii	Desulfovibrio desulfuricans, Faecalibacterium prausnitzii
N816.S	2	2	50	100	(clade_38 or clade_38e or clade_38i), (clade_522 or clade_522i)	Bacteroides ovatus, Eubacterium eligens	Bacteroides ovatus, Eubacterium eligens
N842.S	2	2	50	100	clade_393, clade_500	Alistipes putredinis, Coprococcus catus	Alistipes putredinis, Coprococcus catus
N843.S	2	2	50	100	(clade_262 or clade_262i), clade_500	Alistipes putredinis, Coprococcus comes	Alistipes putredinis, Coprococcus comes
N869.S	2	2	50	100	clade_537, (clade_566 or clade_566f)	Clostridium leptum, Gordonibacter pamelaeae	Clostridium leptum, Gordonibacter pamelaeae
N986.S	2	2	50	100	(clade_172 or clade_172i), (clade_262 or clade_262i)	Bifidobacterium longum, Ruminococcus torques	Bifidobacterium longum, Ruminococcus torques
N995.S	2	2	50	100	clade_500, clade_537	Alistipes putredinis, Clostridium leptum	Alistipes putredinis, Clostridium leptum
N1002.S	2	2	50	100	(clade_478 or clade_478i), clade_500	Alistipes putredinis, Subdoligranulum variabile	Alistipes putredinis, Subdoligranulum variabile
N1004.S	2	2	50	100	(clade_262 or clade_262i), clade_445	Desulfovibrio desulfuricans, Ruminococcus torques	Desulfovibrio desulfuricans, Ruminococcus torques
N1019.S	2	2	50	100	clade_358, (clade_478 or clade_478i)	Faecalibacterium prausnitzii, Veillonella atypica	Faecalibacterium prausnitzii, Veillonella atypica
N1093	2	2	50	100	(clade_522 or clade_522i), clade_583	Akkermansia muciniphila, Eubacterium eligens	Akkermansia muciniphila, Eubacterium eligens
N668.S	2	2	0	100	(clade_378 or clade_378e), clade_500	Alistipes putredinis, Bacteroides dorei	Alistipes putredinis, Bacteroides dorei
N685.S	2	2	0	100	clade_170, clade_286	Bacteroides caccae, Parabacteroides merdae	Bacteroides caccae, Parabacteroides merdae
N835.S	2	2	0	100	clade_500, (clade_566 or clade_566f)	Alistipes putredinis, Gordonibacter pamelaeae	Alistipes putredinis, Gordonibacter pamelaeae
N851.S	2	2	0	100	clade_445, clade_521	Bilophila wadsworthia, Desulfovibrio desulfuricans	Bilophila wadsworthia, Desulfovibrio desulfuricans
N464.S	2	2	100	50	clade_252, (clade_262 or clade_262i)	Clostridium butyricum, Ruminococcus torques	Ruminococcus torques
N695.S	2	2	100	50	clade_396, (clade_516 or clade_516c or clade_516g or clade_516h)	Eubacterium hallii, Ruminococcus albus	Eubacterium hallii
N776.S	2	2	100	50	(clade_516 or clade_516c or clade_516g or clade_516h), clade_538	Eubacterium siraeum, Ruminococcus albus	Eubacterium siraeum
N793.S	2	2	100	50	(clade_516 or clade_516c or clade_516g or	Anaerotruncus colihominis, Clostridium	Clostridium leptum

					clade_516h), clade_537	leptum	
N815.S	2	2	100	50	(clade_522 or clade_522i), (clade_553 or clade_553i)	Collinsella aerofaciens, Eubacterium eligens	Eubacterium eligens
N833.S	2	2	100	50	(clade_260 or clade_260c or clade_260g or clade_260h), (clade_262 or clade_262i)	Clostridium scindens, Coprococcus comes	Coprococcus comes
N891.S	2	2	100	50	clade_368, clade_485	Blautia hydrogenotrophica, Holdemania filiformis	Holdemania filiformis
N1070.S	2	2	100	50	(clade_262 or clade_262i), (clade_516 or clade_516c or clade_516g or clade_516h)	Anaerotruncus colihominis, Coprococcus comes	Coprococcus comes
N1092	2	2	100	50	clade_393, (clade_481 or clade_481a or clade_481b or clade_481e or clade_481g or clade_481h or clade_481i)	Clostridium cocleatum, Coprococcus catus	Coprococcus catus
N795.S	2	2	50	50	clade_500, (clade_516 or clade_516c or clade_516g or clade_516h)	Alistipes putredinis, Clostridium methylpentosum	Alistipes putredinis
N797.S	2	2	50	50	(clade_478 or clade_478i), (clade_98 or clade_98i)	Faecalibacterium prausnitzii, Streptococcus salivarius	Faecalibacterium prausnitzii
N808.S	2	2	50	50	clade_445, (clade_516 or clade_516c or clade_516g or clade_516h)	Clostridium methylpentosum, Desulfovibrio desulfuricans	Desulfovibrio desulfuricans
N811.S	2	2	50	50	clade_445, (clade_516 or clade_516c or clade_516g or clade_516h)	Desulfovibrio desulfuricans, Ruminococcus albus	Desulfovibrio desulfuricans
N826.S	2	2	50	50	clade_500, clade_543	Alistipes putredinis, Coprococcus eutactus	Alistipes putredinis
N830.S	2	2	50	50	(clade_262 or clade_262i), (clade_98 or clade_98i)	Coprococcus comes, Streptococcus thermophilus	Coprococcus comes
N832.S	2	2	50	50	clade_293, (clade_478 or clade_478i)	Bifidobacterium bifidum, Subdoligranulum variabile	Subdoligranulum variabile
N840.S	2	2	50	50	(clade_444 or clade_444i), (clade_98 or clade_98i)	Eubacterium rectale, Streptococcus salivarius	Eubacterium rectale
N945.S	2	2	50	50	(clade_260 or clade_260c or clade_260g or clade_260h), clade_500	Alistipes putredinis, Clostridium scindens	Alistipes putredinis
N960.S	2	2	50	50	(clade_354 or clade_354e), clade_500	Alistipes putredinis, Clostridium bartlettii	Alistipes putredinis

N968.S	2	2	50	50	(clade_262 or clade_262i), (clade_92 or clade_92e or clade_92i)	Escherichia coli, Ruminococcus torques	Ruminococcus torques
N1091	2	2	50	50	(clade_444 or clade_444i), clade_561	Alistipes indistinctus, Eubacterium rectale	Eubacterium rectale
N805.S	2	2	0	50	clade_293, clade_445	Bifidobacterium bifidum, Desulfovibrio desulfuricans	Desulfovibrio desulfuricans
N822.S	2	2	0	50	clade_401, clade_500	Alistipes putredinis, Lactococcus lactis	Alistipes putredinis
N928.S	2	2	0	50	clade_500, clade_506	Alistipes putredinis, Dialister invisus	Alistipes putredinis
N936.S	2	2	0	50	clade_500, (clade_65 or clade_65e)	Alistipes putredinis, Bacteroides fragilis	Alistipes putredinis
N1078.S	2	2	0	50	clade_445, (clade_98 or clade_98i)	Desulfovibrio desulfuricans, Streptococcus australis	Desulfovibrio desulfuricans
N913.S	2	2	100	0	(clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_516 or clade_516c or clade_516g or clade_516h)	Anaerotruncus colihominis, Clostridium symbiosum	

Table 14b.

Percentage of clinical ethanol-treated spore preparations, or combined engrafted and augmented ecologies of patient's post-treatment with the bacterial composition in which the Network Ecology is observed. Network Ecologies found in doses and patients post treatment comprised 2-15 OTUs. Network Ecology IDs with a ".s" indicates that the network is a subset of the computationally determined networks reported in Table 8 with the same Network Ecology.

Network Ecology ID	Number of OTUs	Percent of Ethanol treated spore Preparations Containing Network	Percent of Combined Augmented & Engrafted Post Treatment Patient Ecologies Containing Network	Number of Clades	Percent of Ethanol treated spore Preparations Containing Network	Percent of Combined Augmented & Engrafted Post Treatment Patient Ecologies Containing Network
N262.S	15	0	0	10	0	10
N290.S	14	0	0	10	20	10
N271.S	13	0	0	9	0	10
N282.S	13	0	0	9	0	10
N284.S	13	0	0	9	0	10
N302.S	12	0	0	8	20	10
N279.S	12	0	0	9	0	10
N288.S	12	0	0	8	0	10
N310.S	11	0	0	7	20	10
N323.S	11	0	0	7	20	10
N331.S	11	0	0	7	0	10
N332.S	11	0	0	8	0	10
N312.S	10	0	0	7	20	10
N325.S	10	0	0	8	20	10
N338.S	10	0	0	7	20	10
N339.S	10	0	0	7	20	10
N340.S	10	0	0	7	20	10
N341.S	10	0	0	7	20	10
N301.S	10	0	0	7	0	10
N346.S	10	0	0	7	0	10
N381.S	9	0	10	7	70	70
N343.S	9	10	0	7	20	0
N336.S	9	0	0	6	20	10
N353.S	9	0	0	7	20	0
N355.S	9	0	0	6	20	10
N356.S	9	0	0	6	20	10
N361.S	9	0	0	6	20	10
N329.S	9	0	0	6	10	0
N345.S	9	0	0	7	0	10
N344.S	8	10	0	6	20	10

Network Ecologic ID	Number of OTUs	Percent of Ethanol treated spore Preparations Containing Network	Percent of Combined Augmented & Engrafted Post Treatment Patient Ecologies Containing Network	Number of Clades	Percent of Ethanol treated spore Preparations Containing Network	Percent of Combined Augmented & Engrafted Post Treatment Patient Ecologies Containing Network
N374.S	8	10	0	6	20	10
N375.S	8	10	0	6	20	10
N352.S	8	0	0	5	20	10
N358.S	8	0	0	5	20	10
N368.S	8	0	0	6	20	10
N369.S	8	0	0	6	20	10
N372.S	8	0	0	6	20	10
N377.S	8	0	0	6	20	0
N380.S	8	0	10	7	10	10
N357.S	8	0	0	6	0	10
N370.S	7	10	0	5	20	10
N389.S	7	10	0	6	20	10
N390.S	7	10	0	6	20	0
N394.S	7	10	0	5	20	10
N396.S	7	10	0	6	20	0
N376.S	7	0	0	5	20	10
N431.S	7	0	10	6	10	10
N434.S	7	0	10	6	10	10
N387.S	7	10	0	6	10	0
N397.S	7	0	0	6	10	0
N440.S	7	0	0	7	10	0
N373.S	7	0	0	6	0	10
N403.S	6	0	50	4	100	80
N432.S	6	0	50	4	100	70
N399.S	6	60	30	6	100	80
N493.S	6	50	30	6	100	70
N436.S	6	20	30	4	100	80
N437.S	6	20	30	3	100	80
N490.S	6	0	0	5	100	40
N414.S	6	40	50	5	70	80
N457.S	6	0	40	5	70	80
N430.S	6	30	40	6	60	50
N402.S	6	50	20	5	60	20
N447.S	6	20	10	5	50	20
N439.S	6	20	0	6	50	0
N415.S	6	20	10	5	30	10
N422.S	6	0	10	5	20	10
N421.S	6	20	0	6	20	10

Network Ecologic ID	Number of OTUs	Percent of Ethanol treated spore Preparations Containing Network	Percent of Combined Augmented & Engrafted Post Treatment Patient Ecologies Containing Network	Number of Clades	Percent of Ethanol treated spore Preparations Containing Network	Percent of Combined Augmented & Engrafted Post Treatment Patient Ecologies Containing Network
N386.S	6	10	0	5	20	10
N416.S	6	0	0	6	20	10
N458.S	6	0	10	6	10	10
N459.S	6	0	10	5	10	10
N405.S	6	0	0	4	10	0
N526	6	0	0	5	10	0
N423.S	6	0	10	5	0	10
N545	6	0	0	5	0	10
N433.S	5	90	60	4	100	80
N508.S	5	0	50	4	100	80
N511.S	5	0	50	3	100	80
N488.S	5	0	40	4	100	80
N518.S	5	50	30	5	100	70
N448.S	5	30	30	4	100	80
N474.S	5	40	10	5	100	60
N520.S	5	20	10	5	100	50
N509.S	5	70	50	5	80	50
N510.S	5	40	50	5	70	80
N519.S	5	40	30	5	60	30
N429.S	5	0	30	4	60	50
N463.S	5	0	30	5	50	50
N382.S	5	20	0	5	50	0
N514.S	5	20	0	5	50	10
N450.S	5	0	10	5	20	10
N477.S	5	0	10	5	20	10
N535.S	5	0	10	4	20	30
N446.S	5	20	0	5	20	10
N468.S	5	20	0	5	20	0
N451.S	5	10	0	4	20	10
N408.S	5	0	0	5	20	10
N419.S	5	0	0	5	20	10
N465.S	5	0	0	4	20	0
N586	5	0	0	3	20	0
N516.S	5	10	0	5	10	0
N521.S	5	10	0	5	10	0
N537.S	5	10	0	5	10	0
N512.S	4	90	70	3	100	80
N460.S	4	90	60	3	100	80

Network Ecologic ID	Number of OTUs	Percent of Ethanol treated spore Preparations Containing Network	Percent of Combined Augmented & Engrafted Post Treatment Patient Ecologies Containing Network	Number of Clades	Percent of Ethanol treated spore Preparations Containing Network	Percent of Combined Augmented & Engrafted Post Treatment Patient Ecologies Containing Network
N517.S	4	90	60	4	100	80
N400.S	4	60	60	4	100	80
N577.S	4	60	60	3	100	70
N582.S	4	50	60	4	100	80
N462.S	4	100	50	3	100	80
N547.S	4	90	50	3	100	80
N548.S	4	70	50	4	100	80
N543.S	4	60	50	4	100	70
N523.S	4	0	50	3	100	80
N616.S	4	90	40	4	100	80
N769	4	40	40	4	100	70
N585.S	4	0	30	2	100	90
N689	4	10	20	4	100	70
N687	4	0	20	4	100	90
N621.S	4	40	10	4	100	90
N574.S	4	60	0	4	100	50
N709	4	30	0	4	100	60
N580.S	4	20	0	4	100	40
N664	4	20	10	4	70	10
N515.S	4	40	0	4	70	0
N597.S	4	0	0	3	70	50
N591.S	4	40	30	4	60	30
N730	4	30	10	4	60	20
N693	4	10	10	4	60	30
N534.S	4	30	40	4	40	40
N590.S	4	30	30	3	30	30
N466.S	4	0	10	4	20	10
N480.S	4	0	10	4	20	10
N469.S	4	20	0	4	20	10
N478.S	4	10	0	4	20	0
N484.S	4	10	0	4	20	10
N482.S	4	0	0	4	20	10
N530.S	4	0	0	4	20	10
N481.S	4	10	0	4	10	0
N533.S	4	10	0	4	10	0
N572.S	4	10	0	4	10	0
N525.S	4	0	0	4	10	0
N528.S	4	0	0	4	10	0

Network Lookup ID	Number of OTUs	Percent of Ethanol treated spore Preparations Containing Network	Percent of Combined Augmented & Engrafted Post Treatment Patient Ecologies Containing Network	Number of Clades	Percent of Ethanol treated spore Preparations Containing Network	Percent of Combined Augmented & Engrafted Post Treatment Patient Ecologies Containing Network
N581.S	4	0	10	4	0	10
N737.S	3	90	70	3	100	80
N672.S	3	70	70	3	100	80
N570.S	3	100	60	3	100	90
N655.S	3	100	60	2	100	90
N546.S	3	90	60	3	100	80
N648.S	3	90	60	3	100	80
N681.S	3	90	60	2	100	80
N961	3	90	60	3	100	80
N579.S	3	80	60	3	100	80
N614.S	3	60	60	3	100	70
N539.S	3	0	60	2	100	80
N698.S	3	0	60	2	100	90
N692.S	3	90	50	3	100	80
N529.S	3	70	50	3	100	80
N859	3	40	50	3	100	70
N1061	3	80	40	3	100	80
N841	3	60	40	3	100	70
N988	3	60	40	3	100	80
N858	3	50	40	3	100	80
N602.S	3	30	40	3	100	90
N792	3	20	40	3	100	70
N1051	3	0	40	3	100	70
N881	3	0	40	2	100	90
N972	3	0	40	3	100	70
N712.S	3	60	30	2	100	80
N807	3	50	30	3	100	80
N653.S	3	40	30	3	100	90
N690.S	3	30	30	3	100	80
N880	3	30	30	2	100	80
N996	3	30	30	3	100	90
N714.S	3	100	20	2	100	50
N987	3	50	20	3	100	70
N942	3	20	20	3	100	80
N875	3	0	20	2	100	70
N860	3	70	10	3	100	40
N1023	3	0	10	3	100	40
N612.S	3	0	10	3	100	40

Network Ecologic ID	Number of OTUs	Percent of Ethanol treated spore Preparations Containing Network	Percent of Combined Augmented & Engrafted Post Treatment Patient Ecologies Containing Network	Number of Clades	Percent of Ethanol treated spore Preparations Containing Network	Percent of Combined Augmented & Engrafted Post Treatment Patient Ecologies Containing Network
N625.S	3	0	10	3	100	50
N794	3	0	10	3	100	70
N844	3	100	0	3	100	0
N1008	3	90	0	3	100	0
N947	3	30	0	3	100	50
N654.S	3	20	0	3	100	70
N828	3	20	0	3	100	40
N982	3	20	0	3	100	50
N852	3	10	0	3	100	50
N779	3	0	0	3	100	50
N788	3	0	0	1	100	80
N925	3	0	0	3	100	50
N983	3	0	0	3	100	50
N785	3	80	50	3	80	50
N845	3	80	20	3	80	30
N611.S	3	70	20	3	80	30
N652.S	3	40	60	3	70	90
N878	3	0	40	2	70	90
N849	3	20	20	3	70	90
N651.S	3	0	20	3	70	70
N666.S	3	40	0	3	70	0
N441.S	3	10	0	3	70	50
N609.S	3	50	20	3	60	20
N781	3	50	0	3	50	0
N894	3	50	0	3	50	0
N589.S	3	40	0	3	50	0
N584.S	3	30	0	3	50	10
N927	3	30	0	3	50	20
N738.S	3	40	60	3	40	70
N470.S	3	40	50	2	40	70
N829	3	40	40	3	40	40
N802	3	30	30	3	40	70
N885	3	30	20	3	40	70
N804	3	20	20	3	40	70
N935	3	20	20	3	40	40
N656.S	3	30	10	3	30	10
N682.S	3	30	10	3	30	10
N846	3	30	10	3	30	10

Network Ecology ID	Number of OTUs	Percent of Ethanol treated spore Preparations Containing Network	Percent of Combined Augmented & Engrafted Post Treatment Patient Ecologies Containing Network	Number of Clades	Percent of Ethanol treated spore Preparations Containing Network	Percent of Combined Augmented & Engrafted Post Treatment Patient Ecologies Containing Network
N876	3	0	10	2	30	10
N710.S	3	20	10	3	20	10
N479.S	3	10	10	3	20	10
N542.S	3	10	10	3	20	10
N587.S	3	10	10	3	20	10
N617.S	3	10	10	3	20	10
N680.S	3	20	0	3	20	0
N657.S	3	10	10	3	10	10
N675.S	3	0	10	3	10	10
N538.S	3	10	0	3	10	0
N578.S	3	10	0	3	10	0
N649.S	3	10	0	3	10	0
N678.S	3	10	0	3	10	0
N522.S	3	0	10	3	0	10
N686.S	3	0	10	3	0	10
N1088	2	100	80	2	100	90
N898.S	2	100	80	2	100	90
N610.S	2	90	80	2	100	80
N623.S	2	100	70	2	100	90
N669.S	2	100	70	2	100	80
N998.S	2	100	70	2	100	90
N836.S	2	80	70	2	100	90
N676.S	2	70	70	2	100	80
N524.S	2	100	60	1	100	90
N604.S	2	90	60	2	100	80
N793.S	2	0	60	2	100	80
N775.S	2	90	50	2	100	80
N780.S	2	0	50	2	100	90
N907.S	2	0	50	2	100	90
N913.S	2	0	50	2	100	80
N833.S	2	60	40	2	100	70
N874.S	2	30	40	2	100	90
N1070.S	2	0	40	2	100	70
N871.S	2	0	40	1	100	90
N663.S	2	30	30	2	100	90
N1092	2	80	20	2	100	90
N830.S	2	100	10	2	100	40
N869.S	2	50	10	2	100	50

Network Ecologic ID	Number of OTUs	Percent of Ethanol treated spore Preparations Containing Network	Percent of Combined Augmented & Engrafted Post Treatment Patient Ecologies Containing Network	Number of Clades	Percent of Ethanol treated spore Preparations Containing Network	Percent of Combined Augmented & Engrafted Post Treatment Patient Ecologies Containing Network
N797.S	2	0	10	2	100	50
N840.S	2	0	10	2	100	50
N734.S	2	90	0	2	100	0
N695.S	2	20	0	2	100	70
N986.S	2	10	0	2	100	50
N817.S	2	60	60	2	80	60
N798.S	2	60	30	2	80	40
N777.S	2	20	30	2	80	50
N968.S	2	70	0	2	80	30
N827.S	2	40	70	2	70	90
N464.S	2	40	40	2	70	50
N665.S	2	0	10	2	60	20
N1089	2	20	60	2	50	60
N832.S	2	50	0	2	50	0
N703.S	2	40	60	2	40	70
N1093	2	40	30	2	40	30
N660.S	2	0	0	2	40	50
N815.S	2	10	0	2	30	10
N1019.S	2	0	30	2	20	30
N1002.S	2	20	10	2	20	10
N685.S	2	20	10	2	20	10
N739.S	2	20	10	2	20	10
N835.S	2	20	10	2	20	10
N842.S	2	20	10	2	20	10
N843.S	2	20	10	2	20	10
N960.S	2	20	10	2	20	10
N995.S	2	20	10	2	20	10
N741.S	2	10	10	2	20	10
N795.S	2	10	10	2	20	10
N945.S	2	10	10	2	20	10
N796.S	2	0	10	2	20	10
N668.S	2	20	0	2	20	0
N891.S	2	20	0	2	20	0
N928.S	2	20	0	2	20	0
N936.S	2	20	0	2	20	0
N667.S	2	0	0	2	20	10
N826.S	2	0	0	2	20	10
N822.S	2	10	10	2	10	10

Network Ecologic ID	Number of OTUs	Percent of Ethanol treated spore Preparations Containing Network	Percent of Combined Augmented & Engrafted Post Treatment Patient Ecologies Containing Network	Number of Clades	Percent of Ethanol treated spore Preparations Containing Network	Percent of Combined Augmented & Engrafted Post Treatment Patient Ecologies Containing Network
N733.S	2	0	10	2	10	10
N816.S	2	0	10	2	10	10
N1004.S	2	10	0	2	10	0
N805.S	2	10	0	2	10	0
N809.S	2	10	0	2	10	0
N851.S	2	10	0	2	10	0
N1078.S	2	0	0	2	10	0
N789.S	2	0	0	2	10	0
N800.S	2	0	0	2	10	0
N808.S	2	0	0	2	10	0
N811.S	2	0	0	2	10	0
N1091	2	0	10	2	0	10
N782.S	2	0	10	2	0	10
N776.S	2	0	0	2	0	10

Table 15.

Presence of Keystone OTU Clades in ethanol-treated spore population treatment and patient's pretreatment, augmented and engrafted microbial ecologies post-treatment.

Keystone clade	Percent of Augmented Ecologies with clade	Percent of Engrafted Ecologies with clade	Percent of EtOH Purified Spore Treatment Ecologies with clade	Percent of Pretreatment Ecologies with clade
clade_65	20	20	40	20
clade_85	0	0	0	0
clade_98	40	30	100	80
clade_110	10	0	10	0
clade_170	10	0	30	0
clade_172	10	50	100	30
clade_262	50	80	100	30
clade_262	50	80	100	30
clade_286	0	20	60	20
clade_286	0	20	60	20
clade_309	40	100	100	40
clade_358	40	0	20	80
clade_360	20	100	100	60
clade_360	20	100	100	60
clade_378	10	30	80	0
clade_393	10	90	100	10
clade_396	70	90	100	10
clade_408	60	100	100	50
clade_444	70	90	100	10
clade_466	10	0	0	0
clade_478	0	90	100	30
clade_485	60	10	40	10
clade_494	50	80	100	30
clade_500	10	0	20	10
clade_521	0	0	100	30
clade_537	50	90	100	20
clade_538	10	0	0	0
clade_540	90	10	30	10
clade_543	10	90	100	0
clade_572	30	80	100	20
clade_576	50	30	50	30
clade_583	20	10	60	50

Table 16.

Efficacy of Network Ecologies screened in *Clostridium difficile* Infection Prevention Mouse Model.

SP Exper.	NE Arm	Test Article	Target Dose (CFU/450 µl inoculum)	Cumulative Mortality (%)	Mean Min. Rel. Weight	Mean Max. Clin. Score (Death = 4)
SP-327	3	Vehicle Control		30	0.89	2.2
SP-327	4	Vanco. Positive Control		0	0.99	1
SP-327	12	N1957	2.0E+07	0	0.87	0
SP-327	13	N1957	2.0E+06	40	0.86	2.2
SP-327	14	N1957	2.0E+05	50	0.80	2.8
SP-338	1	Vehicle Control		60	0.81	3.2
SP-338	2	Vanco. Positive Control		0	1.00	0
SP-338	3	10% fecal suspension		0	0.95	1
SP-338	5	N1957	2.0E+07	10	0.80	2
SP-338	6	N1957	2.0E+06	0	0.97	1
SP-338	7	N1957	2.0E+05	20	0.85	1.7
SP-338	11	N1957	2.0E+07	20	0.86	2
SP-338	12	N1957	2.0E+06	30	0.83	2.5
SP-338	13	N1961	2.0E+07	10	0.93	1.3
SP-338	14	N1955	2.0E+07	0	0.91	1.2
SP-338	15	N1955	2.0E+06	10	0.90	1.5
SP-338	16	N1955	2.0E+05	10	0.89	2.7
SP-338	17	N1967	2.0E+07	10	0.94	1.4
SP-338	18	N1983	2.0E+07	0	0.92	1
SP-338	19	N1989	2.0E+07	10	0.91	1.3
SP-338	20	N1996	2.0E+07	10	0.93	1.3
SP-338	21	Naïve		0	1.00	0
SP-339	1	Vehicle Control		20	0.88	2.2
SP-339	2	Vanco. Positive Control		0	0.99	0
SP-339	3	10% fecal suspension		0	0.97	0
SP-339	4	N1995	2.0E+07	20	0.83	2.1
SP-339	5	N1995	2.0E+06	10	0.91	1.5
SP-339	6	N1995	2.0E+05	0	0.96	1.2
SP-339	7	N1950	2.0E+07	0	0.94	1
SP-339	8	N1994	2.0E+07	20	0.87	1.8
SP-339	9	N1997	2.0E+07	0	0.95	1.2
SP-339	10	N1967	2.0E+07	0	0.93	1.2
SP-339	11	N1983	2.0E+07	10	0.83	2.2
SP-339	12	N1989	2.0E+07	0	0.88	1.5
SP-339	13	N1996	2.0E+07	0	0.97	1
SP-339	14	N2002	2.0E+07	20	0.92	2
SP-339	15	N2000	2.0E+07	0	0.98	1.2
SP-339	21	Naïve		0	0.98	0
SP-342	1	Vehicle Control		40	0.85	2.5
SP-342	2	Vanco. Positive Control		0	1.00	0
SP-342	5	N1957	2.0E+08	0	0.94	0.2

SP Expt.	SP Arm	Test Article	Target Dose (CFU/0.01 mouse)	Cumulative Mortality (%)	Mean Min. Rel. Weight	Mean Max. Clin. Score (Days 1 - 4)
SP-342	6	N1957	2.0E+07	0	0.96	0
SP-342	7	N1957	2.0E+06	10	0.88	1.3
SP-342	8	N1980	2.0E+08	10	0.92	1.8
SP-342	9	N1998	2.0E+08	20	0.83	2.8
SP-342	10	N1976	2.0E+08	10	0.92	1.4
SP-342	11	N1987	2.0E+08	10	0.93	1.6
SP-342	12	N2005	2.0E+08	20	0.86	2.4
SP-342	13	N1958	2.0E+08	0	0.94	1.5
SP-342	14	N2004	2.0E+08	10	0.93	1.4
SP-342	15	N1949	2.0E+08	10	0.87	1.5
SP-342	18	N1970	2.0E+08	50	0.81	3
SP-342	21	Naïve		0	0.99	0
SP-361	1	Vehicle Control		30	0.88	2.6
SP-361	2	10% fecal suspension		0	0.99	0
SP-361	3	N435	1.0E+07	80	0.83	3.6
SP-361	4	N1979	1.0E+07	0	0.97	0
SP-361	5	N414	1.0E+07	0	0.97	0
SP-361	6	N512	1.0E+07	20	0.94	1.6
SP-361	7	N582	1.0E+07	10	0.93	0.9
SP-361	8	N571	1.0E+07	30	0.88	2.1
SP-361	9	N510	1.0E+07	0	0.93	0.3
SP-361	10	N1981	1.0E+07	40	0.83	2.8
SP-361	11	N1969	1.0E+07	80	0.82	3.6
SP-361	12	N461	1.0E+07	10	0.89	1.2
SP-361	13	N460	1.0E+07	0	0.93	1.1
SP-361	14	N1959	1.0E+07	30	0.89	1.9
SP-361	15	N2006	1.0E+07	30	0.89	1.9
SP-361	16	N1953	1.0E+07	10	0.83	2.3
SP-361	17	N1960	1.0E+07	0	0.92	1
SP-361	18	N2007	1.0E+07	10	0.91	0.9
SP-361	19	N1978	1.0E+07	10	0.91	1.3
SP-361	20	N1972	1.0E+07	30	0.83	2.6
SP-361	21	Naïve		0	1.00	0
SP-363	1	Vehicle Control		30	0.85	2.6
SP-363	2	10% fecal suspension		0	0.95	0
SP-363	8	N1974	1.0E+07	60	0.81	3.2
SP-363	9	N582	1.0E+07	60	0.81	3.2
SP-363	10	N435	1.0E+07	30	0.86	2.1
SP-363	11	N414	1.0E+07	40	0.83	2.5
SP-363	12	N457	1.0E+07	30	0.83	2.2
SP-363	13	N511	1.0E+07	20	0.87	2
SP-363	14	N513	1.0E+07	0	0.88	0.2
SP-363	15	N682	1.0E+07	30	0.82	2.6

SP Expt.	SP Arm	Test Article	Target Dose (LCFU/Dose)	Cumulative Mortality (%)	Mean Min. Rel. Weight	Mean Max. Clin. Score (Days 1-4)
SP-363	16	N736	1.0E+07	40	0.82	2.8
SP-363	17	N732	1.0E+07	10	0.86	1.3
SP-363	18	N1948	1.0E+07	60	0.85	3.2
SP-363	19	N853	1.0E+07	10	0.85	2.2
SP-363	20	N1979	1.0E+07	60	0.78	3.2
SP-363	21	N879	1.0E+07	40	0.83	2.8
SP-363	22	N999	1.0E+07	20	0.88	2.4
SP-363	23	N975	1.0E+07	30	0.80	2.6
SP-363	24	N861	1.0E+07	50	0.85	3
SP-363	25	N1095	1.0E+07	80	0.83	3.6
SP-363	26	Naive		0	1.00	0
SP-364	1	Vehicle Control		40	0.83	2.8
SP-364	4	N582	1.0E+07	0	0.81	0.9
SP-364	5	N582	1.0E+06	0	0.84	0.9
SP-364	6	N582	1.0E+05	40	0.76	2.5
SP-364	13	N414	1.0E+07	0	0.84	0
SP-364	14	N414	1.0E+06	30	0.79	2.4
SP-364	15	N414	1.0E+05	10	0.76	2
SP-364	22	10% fecal suspension		0	0.97	0
SP-364	23	Naive		0	0.99	0
SP-365	1	Vehicle Control		40	0.83	2.8
SP-365	4	10% fecal suspension		0	0.98	0
SP-365	13	N582	1.0E+07	60	0.80	3.2
SP-365	14	N582	1.0E+06	10	0.89	1.5
SP-365	15	N414	1.0E+07	20	0.86	1.7
SP-365	16	N414	1.0E+06	80	0.83	3.5
SP-365	21	Naive		0	1.00	0
SP-366	1	Vehicle Control		20	0.82	2.4
SP-366	4	10% fecal suspension		0	0.93	1
SP-366	7	N582	1.0E+07	0	0.86	1
SP-366	10	N414	1.0E+07	20	0.83	2.4
SP-366	13	N402	1.0E+07	30	0.81	2.1
SP-366	16	N1982	1.0E+07	0	0.90	1.1
SP-366	19	N460	1.0E+07	10	0.83	2.2
SP-366	22	N513	6.7E+06	40	0.82	2.8
SP-366	23	N1966	1.0E+07	0	0.90	0.5
SP-366	24	N1977	1.0E+07	20	0.83	1.9
SP-366	25	N1979	1.0E+07	20	0.83	2.4
SP-366	26	N682	1.0E+07	20	0.83	2.3
SP-366	27	N1947	1.0E+07	10	0.82	1.3
SP-366	28	N582	1.0E+07	20	0.82	1.8
SP-366	29	N414	1.0E+07	0	0.85	1.5
SP-366	30	N603	1.0E+07	30	0.82	2.2

SP Expt.	SP Arm	Test Article	Target Dose (CFU/0.0 ml inoculum)	Cumulative Mortality (%)	Mean Min. Rel. Weight	Mean Max. Clin. Score (Days 1 - 4)
SP-366	31	Naïve		0	0.99	0
SP-368	1	Vehicle Control		50	0.85	2.8
SP-368	2	10% fecal suspension		0	0.97	0
SP-368	3	Ethanol-treated fecal spores A		20	0.90	1.8
SP-368	7	N1966	1.0E+07	0	0.89	1
SP-368	8	N1966	1.0E+06	10	0.91	1.5
SP-368	9	N1966	1.0E+05	50	0.82	3.1
SP-368	10	Ethanol-treated fecal spores B		0	0.99	0
SP-368	15	Ethanol-treated fecal spores C		0	0.95	1
SP-368	21	Naïve		0	1.00	0
SP-374	1	Vehicle Control		100	0.83	4
SP-374	4	10% fecal suspension		10	0.89	0.5
SP-374	11	N1966	1.0E+08	0	0.87	1
SP-374	12	N1966	1.0E+08	0	0.91	0.5
SP-374	13	N1966	1.0E+07	10	0.88	1.3
SP-374	14	N1966	1.0E+06	50	0.79	3
SP-374	15	N584	1.0E+08	0	0.89	1
SP-374	16	N584	1.0E+07	30	0.84	2.4
SP-374	17	N1962	1.0E+07	0	0.93	0
SP-374	18	N382	1.0E+07	10	0.85	1.5
SP-374	19	N1964	1.0E+07	20	0.89	1.8
SP-374	20	N1965	1.0E+07	30	0.85	2.1
SP-374	21	N306	1.0E+07	10	0.90	0.4
SP-374	22	N1988	1.0E+07	0	0.89	1
SP-374	23	N2003	1.0E+07	0	0.92	1.2
SP-374	24	N1993	1.0E+07	20	0.77	2.4
SP-374	25	Naïve		0	0.99	0
SP-376	1	Vehicle Control		60	0.83	3.2
SP-376	2	10% fecal suspension		0	0.98	0
SP-376	3	N1966	1.0E+08	30	0.79	2.4
SP-376	4	N1966	1.0E+07	0	0.95	0
SP-376	5	N1966	1.0E+08	30	0.79	2.6
SP-376	6	N1966	1.0E+07	10	0.88	2.2
SP-376	7	N1986	1.0E+07	40	0.80	2.8
SP-376	8	N1962	1.0E+08	0	0.98	0
SP-376	9	N1962	1.0E+07	0	0.95	0
SP-376	10	N1963	1.0E+07	40	0.81	2.6
SP-376	11	N1984	1.0E+08	0	0.97	0
SP-376	12	N1984	1.0E+07	0	0.90	1.1
SP-376	13	N1990	1.0E+08	0	0.92	1
SP-376	14	N1990	1.0E+07	0	0.92	1
SP-376	15	N1999	1.0E+08	10	0.87	1.4
SP-376	16	N1999	1.0E+07	0	0.93	0

SP Expt.	SP Arm	Test Article	Target Dose (CFU/0.01 mouse)	Cumulative Mortality (%)	Mean Min. Rel. Weight	Mean Max. Clin. Score (Days 1 - 4)
SP-376	17	N1968	1.0E+07	50	0.78	3
SP-376	18	N1951	1.0E+07	0	0.93	1
SP-376	19	N1991	1.0E+07	0	0.93	1.1
SP-376	20	N1975	1.0E+07	50	0.78	3
SP-376	21	Naïve		0	0.99	0
SP-383	1	Vehicle Control		100	0.83	4
SP-383	2	10% fecal suspension		0	0.92	0.1
SP-383	9	N1962	1.0E+09	10	0.95	1.3
SP-383	10	N1962	1.0E+08	10	0.93	1.3
SP-383	11	N1962	1.0E+07	0	0.92	1
SP-383	12	N1984	1.0E+09	0	0.89	1
SP-383	13	N1984	1.0E+08	10	0.94	1.3
SP-383	14	N1984	1.0E+07	10	0.90	1.3
SP-383	21	Naïve		0	1.00	0
SP-390	1	Vehicle Control		80	0.82	3.6
SP-390	2	10% fecal suspension		0	0.98	0.1
SP-390	3	N1962	2.0E+07	0	0.97	0
SP-390	4	N1962	2.0E+06	0	0.98	0
SP-390	5	N1984	2.0E+07	0	0.95	1
SP-390	6	N1984	2.0E+06	0	0.95	0.1
SP-390	9	N1962	2.0E+07	0	0.93	1
SP-390	10	N1962	2.0E+06	10	0.93	1.3
SP-390	11	N1984	2.0E+07	20	0.86	2.2
SP-390	12	N1984	2.0E+06	30	0.88	2.1
SP-390	13	N1952	2.0E+07	0	0.89	1
SP-390	14	N2001	2.0E+07	0	0.95	0.2
SP-390	15	N1973	2.0E+07	10	0.90	0.7
SP-390	16	N1954	2.0E+07	0	0.94	1.1
SP-390	17	N1985	2.0E+07	10	0.86	1.8
SP-390	18	N1971	2.0E+07	0	0.89	0.9
SP-390	19	N1956	2.0E+07	0	0.95	0
SP-390	20	N1992	2.0E+07	0	0.95	0
SP-390	31	Naïve		0	0.98	0

Table 17.

Network Ecologies screened *in vivo* in Clostridium difficile Infection Prevention Mouse Model

Network Ecology ID	Exemplary Network Clades	Exemplary Network OTUs	Exemplary Resident OTUs
N306	clade_252, (clade_260 or clade_260c or clade_260g or clade_260h), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_351 or clade_351e), (clade_38 or clade_38e or clade_38i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_444 or clade_444i), (clade_478 or clade_478i), (clade_481 or clade_481a or clade_481b or clade_481e or clade_481g or clade_481h or clade_481i), clade_494, (clade_553 or clade_553i)	Blautia producta, Clostridium hylemonae, Clostridium innocuum, Clostridium orbiscindens, Clostridium symbiosum, Clostridium tertium, Collinsella aerofaciens, Coprobacillus sp. D7, Coprococcus comes, Eubacterium rectale, Eubacterium sp. WAL 14571, Faecalibacterium prausnitzii, Lachnospiraceae bacterium 5_1_57FAA, Roseburia faecalis, Ruminococcus obeum, Ruminococcus torques	Coprococcus comes, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N382	clade_252, (clade_260 or clade_260c or clade_260g or clade_260h), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_351 or clade_351e), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), clade_494, clade_537, (clade_553 or clade_553i)	Blautia producta, Clostridium hylemonae, Clostridium innocuum, Clostridium orbiscindens, Clostridium symbiosum, Clostridium tertium, Collinsella aerofaciens, Coprococcus comes, Lachnospiraceae bacterium 5_1_57FAA, Ruminococcus bromii, Ruminococcus gnavus	Coprococcus comes, Ruminococcus bromii
N402	(clade_262 or clade_262i), clade_286, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), clade_466, (clade_478 or clade_478i), clade_500	Alistipes shahii, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Parabacteroides merdae, Ruminococcus obeum, Ruminococcus torques	Alistipes shahii, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Parabacteroides merdae, Ruminococcus obeum, Ruminococcus torques
N414	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), clade_466, (clade_478 or clade_478i), (clade_522 or clade_522i)	Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Ruminococcus obeum, Ruminococcus torques	Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Ruminococcus obeum, Ruminococcus torques
N435	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or	Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Ruminococcus obeum, Ruminococcus	Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Ruminococcus obeum, Ruminococcus

	clade_444i), clade_466, (clade_478 or clade_478i)	torques	torques
N457	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), (clade_478 or clade_478i), (clade_522 or clade_522i)	Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques	Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques
N460	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), clade_466, (clade_478 or clade_478i)	Coprococcus comes, Dorea formicigenerans, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Ruminococcus obeum, Ruminococcus torques	Coprococcus comes, Dorea formicigenerans, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Ruminococcus obeum, Ruminococcus torques
N461	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), (clade_478 or clade_478i)	Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N510	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), (clade_478 or clade_478i), (clade_522 or clade_522i)	Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N511	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), (clade_478 or clade_478i)	Coprococcus comes, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques	Coprococcus comes, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques
N512	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i)	Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium rectale, Ruminococcus obeum, Ruminococcus torques	Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium rectale, Ruminococcus obeum, Ruminococcus torques
N513	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), (clade_478 or clade_478i)	Coprococcus comes, Dorea formicigenerans, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Coprococcus comes, Dorea formicigenerans, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques

N571	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), (clade_478 or clade_478i)	Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N582	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_444 or clade_444i), (clade_478 or clade_478i)	Clostridium symbiosum, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N584	(clade_260 or clade_260c or clade_260g or clade_260h), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_553 or clade_553i)	Blautia producta, Clostridium symbiosum, Collinsella aerofaciens, Coprococcus comes, Lachnospiraceae bacterium 5_1_57FAA	Coprococcus comes
N603	(clade_172 or clade_172i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), (clade_478 or clade_478i)	Bifidobacterium adolescentis, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum	Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum
N682	clade_170, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), (clade_478 or clade_478i)	Bacteroides caccae, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum	Bacteroides caccae, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum
N732	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_478 or clade_478i)	Coprococcus comes, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Coprococcus comes, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N736	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_478 or clade_478i)	Dorea longicatena, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Dorea longicatena, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N853	(clade_262 or clade_262i), (clade_444 or clade_444i), (clade_478 or clade_478i)	Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus torques	Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus torques
N861	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h)	Clostridium hathewayi, Ruminococcus obeum, Ruminococcus torques	Ruminococcus obeum, Ruminococcus torques

N879	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_444 or clade_444i), (clade_478 or clade_478i)	Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus obeum	Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus obeum
N975	clade_170, (clade_262 or clade_262i), (clade_360 or clade_360c or clade_360g or clade_360h clade_360i)	Bacteroides caccae, Coprococcus comes, Dorea longicatena	Bacteroides caccae, Coprococcus comes, Dorea longicatena
N999	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_478 or clade_478i)	Dorea formicigenerans, Faecalibacterium prausnitzii, Ruminococcus obeum	Dorea formicigenerans, Faecalibacterium prausnitzii, Ruminococcus obeum
N1095	(clade_444 or clade_444i), (clade_522 or clade_522i)	Eubacterium eligens, Eubacterium rectale	Eubacterium eligens, Eubacterium rectale
N1947	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_38 or clade_38e or clade_38i), (clade_444 or clade_444i), (clade_478 or clade_478i), (clade_553 or clade_553i), (clade_92 or clade_92e or clade_92i)	Bacteroides sp. 3_1_23, Collinsella aerofaciens, Dorea longicatena, Escherichia coli, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques	Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques
N1948	(clade_262 or clade_262i), (clade_38 or clade_38e or clade_38i), (clade_478 or clade_478i), (clade_65 or clade_65e)	Bacteroides sp. 1_1_6, Bacteroides sp. 3_1_23, Faecalibacterium prausnitzii, Ruminococcus torques	Faecalibacterium prausnitzii, Ruminococcus torques
N1949	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_378 or clade_378e), (clade_38 or clade_38e or clade_38i), (clade_479 or clade_479c or clade_479g or clade_479h), (clade_497 or clade_497e or clade_497f), (clade_65 or clade_65e), (clade_92 or clade_92e or clade_92i)	Bacteroides sp. 1_1_6, Bacteroides sp. 3_1_23, Bacteroides vulgatus, Blautia producta, Enterococcus faecalis, Erysipelotrichaceae bacterium 3_1_53, Escherichia coli	
N1950	clade_253, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_378 or clade_378e), (clade_38 or clade_38e or clade_38i), (clade_479 or clade_479c or clade_479g or clade_479h), (clade_65 or clade_65e)	Bacteroides sp. 1_1_6, Bacteroides sp. 3_1_23, Bacteroides vulgatus, Blautia producta, Clostridium disporicum, Erysipelotrichaceae bacterium 3_1_53	
N1951	(clade_260 or clade_260c or clade_260g or clade_260h), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_444 or	Blautia producta, Clostridium bolteae, Clostridium hylemonae, Clostridium symbiosum, Coprococcus comes, Eubacterium rectale, Lachnospiraceae bacterium 5_1_57FAA, Ruminococcus gnavus	Coprococcus comes, Eubacterium rectale

	clade_444i)		
N1952	clade_252, clade_253, (clade_260 or clade_260c or clade_260g or clade_260h), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_351 or clade_351e), (clade_354 or clade_354e), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), clade_494, clade_537, (clade_553 or clade_553i)	Blautia producta, Clostridium bolteae, Clostridium butyricum, Clostridium disporicum, Clostridium hylemonae, Clostridium innocuum, Clostridium mayombei, Clostridium orbiscindens, Clostridium symbiosum, Clostridium tertium, Collinsella aerofaciens, Coprococcus comes, Lachnospiraceae bacterium 5_1_57FAA, Ruminococcus bromii, Ruminococcus gnavus	Coprococcus comes, Ruminococcus bromii
N1953	clade_253, (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_354 or clade_354e), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_378 or clade_378e), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_444 or clade_444i), clade_466, (clade_478 or clade_478i), (clade_479 or clade_479c or clade_479g or clade_479h), (clade_481 or clade_481a or clade_481b or clade_481e or clade_481g or clade_481h or clade_481i), (clade_497 or clade_497e or clade_497f), (clade_65 or clade_65e), (clade_92 or clade_92e or clade_92i)	Bacteroides sp. 1_1_6, Bacteroides vulgatus, Clostridium disporicum, Clostridium mayombei, Clostridium symbiosum, Coprobacillus sp. D7, Coprococcus comes, Dorea formicigenerans, Enterococcus faecalis, Erysipelotrichaceae bacterium 3_1_53, Escherichia coli, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Ruminococcus obeum	Coprococcus comes, Dorea formicigenerans, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Ruminococcus obeum
N1954	clade_252, clade_253, (clade_260 or clade_260c or clade_260g or clade_260h), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_351 or clade_351e), (clade_354 or clade_354e), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), clade_494, clade_537, (clade_553 or clade_553i)	Blautia sp. M25, Clostridium bolteae, Clostridium butyricum, Clostridium disporicum, Clostridium hylemonae, Clostridium innocuum, Clostridium mayombei, Clostridium orbiscindens, Clostridium symbiosum, Clostridium tertium, Collinsella aerofaciens, Coprococcus comes, Lachnospiraceae bacterium 5_1_57FAA, Ruminococcus bromii, Ruminococcus gnavus	Blautia sp. M25, Coprococcus comes, Ruminococcus bromii

N1955	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_354 or clade_354e), (clade_378 or clade_378e), (clade_38 or clade_38e or clade_38i), (clade_479 or clade_479c or clade_479g or clade_479h), (clade_481 or clade_481a or clade_481b or clade_481e or clade_481g or clade_481h or clade_481i), (clade_497 or clade_497e or clade_497f), (clade_65 or clade_65e), (clade_92 or clade_92e or clade_92i)	Bacteroides sp. 1_1_6, Bacteroides sp. 2_1_22, Bacteroides sp. 3_1_23, Bacteroides vulgatus, Blautia producta, Citrobacter sp. 30_2, Clostridium sordellii, Coprobacillus sp. D7, Enterococcus faecalis, Enterococcus faecium, Erysipelotrichaceae bacterium 3_1_53, Escherichia coli	
N1956	clade_252, clade_253, (clade_260 or clade_260c or clade_260g or clade_260h), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_351 or clade_351e), (clade_354 or clade_354e), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), clade_494, clade_537, (clade_553 or clade_553i)	Blautia producta, Clostridium bolteae, Clostridium butyricum, Clostridium disporicum, Clostridium hylemonae, Clostridium innocuum, Clostridium mayombei, Clostridium nexile, Clostridium orbiscindens, Clostridium symbiosum, Clostridium tertium, Collinsella aerofaciens, Lachnospiraceae bacterium 5_1_57FAA, Ruminococcus bromii, Ruminococcus gnavus	Clostridium nexile, Ruminococcus bromii
N1957	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_351 or clade_351e), (clade_354 or clade_354e), (clade_378 or clade_378e), (clade_38 or clade_38e or clade_38i), (clade_481 or clade_481a or clade_481b or clade_481e or clade_481g or clade_481h or clade_481i), (clade_497 or clade_497e or clade_497f), (clade_65 or clade_65e), (clade_92 or clade_92e or clade_92i)	Bacteroides sp. 1_1_6, Bacteroides sp. 3_1_23, Bacteroides vulgatus, Blautia producta, Clostridium innocuum, Clostridium sordellii, Coprobacillus sp. D7, Enterococcus faecalis, Escherichia coli	
N1958	(clade_351 or clade_351e), (clade_354 or clade_354e), (clade_481 or clade_481a or clade_481b or clade_481e or clade_481g or clade_481h or clade_481i)	Clostridium innocuum, Clostridium sordellii, Coprobacillus sp. D7	
N1959	clade_253, (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_378 or clade_378e), (clade_38 or clade_38e or clade_38i), (clade_444 or clade_444i), (clade_478 or clade_478i), (clade_479 or clade_479c or clade_479g or clade_479h), (clade_497 or clade_497e or clade_497f), (clade_522 or	Bacteroides sp. 1_1_6, Bacteroides sp. 3_1_23, Bacteroides vulgatus, Blautia producta, Clostridium disporicum, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Enterococcus faecalis, Erysipelotrichaceae bacterium 3_1_53, Escherichia coli, Eubacterium eligens, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques

	clade_522i), (clade_65 or clade_65e), (clade_92 or clade_92e or clade_92i)		
N1960	clade_253, (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_354 or clade_354e), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_444 or clade_444i), (clade_478 or clade_478i), (clade_479 or clade_479c or clade_479g or clade_479h), (clade_481 or clade_481a or clade_481b or clade_481e or clade_481g or clade_481h or clade_481i), (clade_497 or clade_497e or clade_497f), (clade_92 or clade_92e or clade_92i)	Clostridium disporicum, Clostridium mayombei, Clostridium symbiosum, Coprobacillus sp. D7, Coprococcus comes, Dorea formicigenerans, Enterococcus faecalis, Erysipelotrichaceae bacterium 3_1_53, Escherichia coli, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum	Coprococcus comes, Dorea formicigenerans, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum
N1961	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_351 or clade_351e), (clade_378 or clade_378e), (clade_38 or clade_38e or clade_38i), (clade_497 or clade_497e or clade_497f), (clade_65 or clade_65e), (clade_92 or clade_92e or clade_92i)	Bacteroides sp. 1_1_6, Bacteroides sp. 3_1_23, Bacteroides vulgatus, Blautia producta, Clostridium innocuum, Enterococcus faecalis, Escherichia coli	
N1962	clade_252, clade_253, (clade_260 or clade_260c or clade_260g or clade_260h), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_351 or clade_351e), (clade_354 or clade_354e), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), clade_494, clade_537, (clade_553 or clade_553i)	Blautia producta, Clostridium bolteae, Clostridium butyricum, Clostridium disporicum, Clostridium hylemonae, Clostridium innocuum, Clostridium mayombei, Clostridium orbiscindens, Clostridium symbiosum, Clostridium tertium, Collinsella aerofaciens, Coprococcus comes, Lachnospiraceae bacterium 5_1_57FAA, Ruminococcus bromii, Ruminococcus gnavus	Coprococcus comes, Ruminococcus bromii

N1963	clade_252, clade_253, (clade_260 or clade_260c or clade_260g or clade_260h), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_351 or clade_351e), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), clade_494, clade_537, (clade_553 or clade_553i)	Blautia producta, Clostridium disporicum, Clostridium hylemonae, Clostridium innocuum, Clostridium orbiscindens, Clostridium symbiosum, Clostridium tertium, Collinsella aerofaciens, Coprococcus comes, Lachnospiraceae bacterium 5_1_57FAA, Ruminococcus bromii, Ruminococcus gnavus	Coprococcus comes, Ruminococcus bromii
N1964	clade_170, (clade_260 or clade_260c or clade_260g or clade_260h), (clade_262 or clade_262i), clade_286, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_444 or clade_444i), clade_485, clade_500, clade_537, (clade_553 or clade_553i), clade_85	Alistipes shahii, Bacteroides caccae, Bacteroides stercoris, Blautia producta, Clostridium hathewayi, Clostridium symbiosum, Collinsella aerofaciens, Coprococcus comes, Eubacterium rectale, Holdemania filiformis, Lachnospiraceae bacterium 5_1_57FAA, Parabacteroides merdae, Ruminococcus bromii, Ruminococcus obeum, Ruminococcus torques	Alistipes shahii, Bacteroides caccae, Bacteroides stercoris, Coprococcus comes, Eubacterium rectale, Holdemania filiformis, Parabacteroides merdae, Ruminococcus bromii, Ruminococcus obeum, Ruminococcus torques
N1965	clade_252, clade_253, (clade_260 or clade_260c or clade_260g or clade_260h), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_354 or clade_354e), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_444 or clade_444i), (clade_478 or clade_478i), clade_537, (clade_553 or clade_553i)	Blautia producta, Clostridium bolteae, Clostridium butyricum, Clostridium disporicum, Clostridium mayombei, Clostridium symbiosum, Collinsella aerofaciens, Coprococcus comes, Eubacterium rectale, Faecalibacterium prausnitzii, Lachnospiraceae bacterium 5_1_57FAA, Roseburia intestinalis, Ruminococcus bromii, Ruminococcus obeum	Coprococcus comes, Eubacterium rectale, Faecalibacterium prausnitzii, Roseburia intestinalis, Ruminococcus bromii, Ruminococcus obeum
N1966	clade_252, clade_253, (clade_260 or clade_260c or clade_260g or clade_260h), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_354 or clade_354e), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_553 or clade_553i)	Blautia producta, Clostridium bolteae, Clostridium butyricum, Clostridium disporicum, Clostridium mayombei, Clostridium symbiosum, Collinsella aerofaciens, Coprococcus comes, Lachnospiraceae bacterium 5_1_57FAA	Coprococcus comes
N1967	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_378 or clade_378e), (clade_38 or clade_38e or clade_38i), (clade_497 or clade_497e or clade_497f), (clade_65 or clade_65e), (clade_92 or clade_92e or clade_92i)	Bacteroides sp. 1_1_6, Bacteroides sp. 3_1_23, Bacteroides vulgatus, Blautia producta, Enterococcus faecium, Escherichia coli	

N1968	clade_252, clade_253, (clade_351 or clade_351e), (clade_354 or clade_354e), (clade_478 or clade_478i), clade_494, clade_537, (clade_553 or clade_553i)	Clostridium butyricum, Clostridium disporicum, Clostridium innocuum, Clostridium mayombei, Clostridium orbiscindens, Clostridium tertium, Collinsella aerofaciens, Faecalibacterium prausnitzii, Ruminococcus bromii	Faecalibacterium prausnitzii, Ruminococcus bromii
N1969	clade_252, clade_253, (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_354 or clade_354e), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_479 or clade_479c or clade_479g or clade_479h)	Blautia producta, Clostridium butyricum, Clostridium disporicum, Clostridium mayombei, Dorea formicigenerans, Erysipelotrichaceae bacterium 3_1_53, Ruminococcus torques	Dorea formicigenerans, Ruminococcus torques
N1970	(clade_351 or clade_351e), (clade_354 or clade_354e), (clade_378 or clade_378e), (clade_38 or clade_38e or clade_38i), (clade_481 or clade_481a or clade_481b or clade_481e or clade_481g or clade_481h or clade_481i), (clade_497 or clade_497e or clade_497f), (clade_65 or clade_65e), (clade_92 or clade_92e or clade_92i)	Bacteroides sp. 1_1_6, Bacteroides sp. 3_1_23, Bacteroides vulgatus, Clostridium innocuum, Clostridium sordellii, Coprobacillus sp. D7, Enterococcus faecalis, Escherichia coli	
N1971	clade_252, clade_253, (clade_260 or clade_260c or clade_260g or clade_260h), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_351 or clade_351e), (clade_354 or clade_354e), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), clade_494, clade_537, (clade_553 or clade_553i)	Blautia producta, Blautia schinkii, Clostridium bolteae, Clostridium butyricum, Clostridium disporicum, Clostridium hylemonae, Clostridium innocuum, Clostridium mayombei, Clostridium orbiscindens, Clostridium symbiosum, Clostridium tertium, Collinsella aerofaciens, Coprococcus comes, Lachnospiraceae bacterium 5_1_57FAA, Ruminococcus bromii, Ruminococcus gnavus	Coprococcus comes, Ruminococcus bromii
N1972	clade_253, (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_354 or clade_354e), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_444 or clade_444i), (clade_478 or clade_478i), (clade_479 or clade_479c or clade_479g or clade_479h), (clade_481 or clade_481a or clade_481b or clade_481e or clade_481g or clade_481h or clade_481i)	Clostridium disporicum, Clostridium mayombei, Clostridium symbiosum, Coprobacillus sp. D7, Coprococcus comes, Dorea formicigenerans, Erysipelotrichaceae bacterium 3_1_53, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum	Coprococcus comes, Dorea formicigenerans, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum

N1973	clade_252, clade_253, (clade_260 or clade_260c or clade_260g or clade_260h), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_351 or clade_351e), (clade_354 or clade_354e), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), clade_494, clade_537	Blautia producta, Clostridium bolteae, Clostridium butyricum, Clostridium disporicum, Clostridium hylemonae, Clostridium innocuum, Clostridium mayombei, Clostridium orbiscindens, Clostridium symbiosum, Clostridium tertium, Coprococcus comes, Lachnospiraceae bacterium 5_1_57FAA, Ruminococcus bromii, Ruminococcus gnavus	Coprococcus comes, Ruminococcus bromii
N1974	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), clade_466, (clade_478 or clade_478i)	Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques	Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques
N1975	(clade_260 or clade_260c or clade_260g or clade_260h), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_351 or clade_351e), (clade_354 or clade_354e), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_444 or clade_444i), (clade_478 or clade_478i), clade_494, clade_537, (clade_553 or clade_553i)	Blautia producta, Clostridium bolteae, Clostridium hylemonae, Clostridium innocuum, Clostridium mayombei, Clostridium orbiscindens, Clostridium symbiosum, Collinsella aerofaciens, Coprococcus comes, Eubacterium rectale, Faecalibacterium prausnitzii, Lachnospiraceae bacterium 5_1_57FAA, Ruminococcus bromii, Ruminococcus gnavus	Coprococcus comes, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus bromii
N1976	(clade_351 or clade_351e), (clade_378 or clade_378e), (clade_38 or clade_38e or clade_38i), (clade_481 or clade_481a or clade_481b or clade_481e or clade_481g or clade_481h or clade_481i), (clade_497 or clade_497e or clade_497f), (clade_65 or clade_65e)	Bacteroides sp. 1_1_6, Bacteroides sp. 3_1_23, Bacteroides vulgatus, Clostridium innocuum, Coprobacillus sp. D7, Enterococcus faecalis	
N1977	clade_252, clade_253, (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_354 or clade_354e), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_479 or clade_479c or clade_479g or clade_479h)	Blautia producta, Clostridium butyricum, Clostridium disporicum, Clostridium mayombei, Dorea formicigenerans, Erysipelotrichaceae bacterium 3_1_53, Eubacterium tenue, Ruminococcus torques	Dorea formicigenerans, Ruminococcus torques

N1978	clade_253, (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_354 or clade_354e), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_378 or clade_378e), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_444 or clade_444i), clade_466, (clade_478 or clade_478i), (clade_479 or clade_479c or clade_479g or clade_479h), (clade_481 or clade_481a or clade_481b or clade_481e or clade_481g or clade_481h or clade_481i), (clade_65 or clade_65e), (clade_92 or clade_92e or clade_92i)	Bacteroides sp. 1_1_6, Bacteroides vulgatus, Clostridium disporicum, Clostridium mayombei, Clostridium symbiosum, Coprobacillus sp. D7, Coprococcus comes, Dorea formicigenerans, Erysipelotrichaceae bacterium 3_1_53, Escherichia coli, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Ruminococcus obeum	Coprococcus comes, Dorea formicigenerans, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Ruminococcus obeum
N1979	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), (clade_478 or clade_478i), (clade_65 or clade_65e)	Bacteroides sp. 1_1_6, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N1980	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_351 or clade_351e), (clade_354 or clade_354e), (clade_481 or clade_481a or clade_481b or clade_481e or clade_481g or clade_481h or clade_481i), (clade_497 or clade_497e or clade_497f), (clade_92 or clade_92e or clade_92i)	Blautia producta, Clostridium innocuum, Clostridium sordellii, Coprobacillus sp. D7, Enterococcus faecalis, Escherichia coli	
N1981	(clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_38 or clade_38e or clade_38i), (clade_444 or clade_444i), (clade_478 or clade_478i), (clade_522 or clade_522i)	Bacteroides sp. 3_1_23, Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Dorea longicatena, Eubacterium eligens, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques

N1982	clade_252, clade_253, (clade_260 or clade_260c or clade_260g or clade_260h), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_354 or clade_354e), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_444 or clade_444i), (clade_479 or clade_479c or clade_479g or clade_479h), (clade_553 or clade_553i)	Blautia producta, Clostridium bolteae, Clostridium butyricum, Clostridium disporicum, Clostridium mayombei, Clostridium symbiosum, Collinsella aerofaciens, Coprococcus comes, Dorea formicigenerans, Erysipelotrichaceae bacterium 3_1_53, Eubacterium rectale, Lachnospiraceae bacterium 5_1_57FAA, Ruminococcus obeum, Ruminococcus torques	Coprococcus comes, Dorea formicigenerans, Eubacterium rectale, Ruminococcus obeum, Ruminococcus torques
N1983	clade_252, clade_253, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_354 or clade_354e), (clade_378 or clade_378e), (clade_38 or clade_38e or clade_38i), (clade_479 or clade_479c or clade_479g or clade_479h), (clade_497 or clade_497e or clade_497f), (clade_65 or clade_65e), (clade_92 or clade_92e or clade_92i)	Bacteroides sp. 1_1_6, Bacteroides sp. 3_1_23, Bacteroides vulgatus, Blautia producta, Clostridium butyricum, Clostridium disporicum, Clostridium mayombei, Enterococcus faecium, Erysipelotrichaceae bacterium 3_1_53, Escherichia coli	
N1984	clade_253, (clade_260 or clade_260c or clade_260g or clade_260h), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_351 or clade_351e), (clade_354 or clade_354e), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_444 or clade_444i), clade_494, (clade_553 or clade_553i)	Blautia producta, Clostridium disporicum, Clostridium innocuum, Clostridium mayombei, Clostridium orbiscindens, Clostridium symbiosum, Collinsella aerofaciens, Eubacterium rectale, Lachnospiraceae bacterium 5_1_57FAA	Eubacterium rectale
N1985	clade_252, clade_253, (clade_260 or clade_260c or clade_260g or clade_260h), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_351 or clade_351e), (clade_354 or clade_354e), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), clade_494, clade_537, (clade_553 or clade_553i)	Blautia glucerasei, Clostridium bolteae, Clostridium butyricum, Clostridium disporicum, Clostridium hylemonae, Clostridium innocuum, Clostridium mayombei, Clostridium orbiscindens, Clostridium symbiosum, Clostridium tertium, Collinsella aerofaciens, Coprococcus comes, Lachnospiraceae bacterium 5_1_57FAA, Ruminococcus bromii, Ruminococcus gnavus	Coprococcus comes, Ruminococcus bromii

N1986	clade_253, (clade_260 or clade_260c or clade_260g or clade_260h), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_553 or clade_553i)	Blautia producta, Clostridium disporicum, Clostridium symbiosum, Collinsella aerofaciens, Coprococcus comes, Lachnospiraceae bacterium 5_1_57FAA	Coprococcus comes
N1987	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_354 or clade_354e), (clade_92 or clade_92e or clade_92i)	Blautia producta, Clostridium sordellii, Escherichia coli	
N1988	clade_252, clade_253, (clade_260 or clade_260c or clade_260g or clade_260h), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_354 or clade_354e), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_444 or clade_444i), (clade_478 or clade_478i), clade_485, clade_500, (clade_553 or clade_553i)	Alistipes shahii, Blautia producta, Clostridium bolteae, Clostridium butyricum, Clostridium disporicum, Clostridium mayombei, Clostridium symbiosum, Collinsella aerofaciens, Coprococcus comes, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Lachnospiraceae bacterium 5_1_57FAA, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques	Alistipes shahii, Coprococcus comes, Eubacterium rectale, Faecalibacterium prausnitzii, Holdemania filiformis, Roseburia intestinalis, Ruminococcus obeum, Ruminococcus torques
N1989	clade_252, clade_253, (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_354 or clade_354e), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_378 or clade_378e), (clade_38 or clade_38e or clade_38i), (clade_479 or clade_479c or clade_479g or clade_479h), (clade_497 or clade_497e or clade_497f), (clade_65 or clade_65e), (clade_92 or clade_92e or clade_92i)	Bacteroides sp. 1_1_6, Bacteroides sp. 3_1_23, Bacteroides vulgatus, Blautia producta, Clostridium butyricum, Clostridium disporicum, Clostridium mayombei, Dorea formicigenerans, Enterococcus faecium, Erysipelotrichaceae bacterium 3_1_53, Escherichia coli, Eubacterium tenue, Ruminococcus torques	Dorea formicigenerans, Ruminococcus torques
N1990	clade_252, clade_253, (clade_260 or clade_260c or clade_260g or clade_260h), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_351 or clade_351e), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_444 or clade_444i), (clade_478 or clade_478i), clade_494, clade_537, (clade_553 or clade_553i)	Blautia producta, Clostridium disporicum, Clostridium hylemonae, Clostridium innocuum, Clostridium orbiscindens, Clostridium symbiosum, Clostridium tertium, Collinsella aerofaciens, Coprococcus comes, Eubacterium rectale, Faecalibacterium prausnitzii, Lachnospiraceae bacterium 5_1_57FAA, Ruminococcus bromii, Ruminococcus gnavus	Coprococcus comes, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus bromii

N1991	clade_252, clade_253, (clade_260 or clade_260c or clade_260g or clade_260h), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_351 or clade_351e), (clade_354 or clade_354e), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_444 or clade_444i), (clade_553 or clade_553i)	Blautia producta, Clostridium bolteae, Clostridium butyricum, Clostridium disporicum, Clostridium hylemonae, Clostridium innocuum, Clostridium mayombei, Clostridium symbiosum, Clostridium tertium, Collinsella aerofaciens, Coprococcus comes, Eubacterium rectale, Lachnospiraceae bacterium 5_1_57FAA, Ruminococcus gnavus	Coprococcus comes, Eubacterium rectale
N1992	clade_252, clade_253, (clade_260 or clade_260c or clade_260g or clade_260h), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_351 or clade_351e), (clade_354 or clade_354e), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), clade_494, clade_537, (clade_553 or clade_553i)	Blautia producta, Clostridium bolteae, Clostridium butyricum, Clostridium disporicum, Clostridium hylemonae, Clostridium innocuum, Clostridium mayombei, Clostridium orbiscindens, Clostridium symbiosum, Clostridium tertium, Collinsella aerofaciens, Lachnospiraceae bacterium 1_4_56FAA, Lachnospiraceae bacterium 5_1_57FAA, Ruminococcus bromii, Ruminococcus gnavus	Lachnospiraceae bacterium 1_4_56FAA, Ruminococcus bromii
N1993	clade_110, clade_170, (clade_378 or clade_378e), (clade_38 or clade_38e or clade_38i), (clade_65 or clade_65e), clade_85	Bacteroides caccae, Bacteroides eggerthii, Bacteroides sp. 1_1_6, Bacteroides sp. 3_1_23, Bacteroides stercoris, Bacteroides uniformis, Bacteroides vulgatus	Bacteroides caccae, Bacteroides eggerthii, Bacteroides stercoris, Bacteroides uniformis
N1994	clade_253, (clade_378 or clade_378e), (clade_38 or clade_38e or clade_38i), (clade_479 or clade_479c or clade_479g or clade_479h), (clade_497 or clade_497e or clade_497f), (clade_65 or clade_65e), (clade_92 or clade_92e or clade_92i)	Bacteroides sp. 1_1_6, Bacteroides sp. 3_1_23, Bacteroides vulgatus, Clostridium disporicum, Enterococcus faecium, Erysipelotrichaceae bacterium 3_1_53, Escherichia coli	
N1995	clade_253, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_378 or clade_378e), (clade_38 or clade_38e or clade_38i), (clade_479 or clade_479c or clade_479g or clade_479h), (clade_497 or clade_497e or clade_497f), (clade_65 or clade_65e), (clade_92 or clade_92e or clade_92i)	Bacteroides sp. 1_1_6, Bacteroides sp. 3_1_23, Bacteroides vulgatus, Blautia producta, Clostridium disporicum, Enterococcus faecium, Erysipelotrichaceae bacterium 3_1_53, Escherichia coli	
N1996	clade_253, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_479 or clade_479c or clade_479g or clade_479h)	Blautia producta, Clostridium disporicum, Erysipelotrichaceae bacterium 3_1_53	

N1997	clade_253, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_479 or clade_479c or clade_479g or clade_479h), (clade_497 or clade_497e or clade_497f), (clade_92 or clade_92e or clade_92i)	Blautia producta, Clostridium disporicum, Enterococcus faecium, Erysipelotrichaceae bacterium 3_1_53, Escherichia coli	
N1998	(clade_378 or clade_378e), (clade_38 or clade_38e or clade_38i), (clade_65 or clade_65e)	Bacteroides sp. 1_1_6, Bacteroides sp. 3_1_23, Bacteroides vulgatus	
N1999	clade_252, clade_253, (clade_260 or clade_260c or clade_260g or clade_260h), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_354 or clade_354e), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_444 or clade_444i), (clade_478 or clade_478i), (clade_553 or clade_553i)	Blautia producta, Clostridium bolteae, Clostridium butyricum, Clostridium disporicum, Clostridium mayombei, Clostridium symbiosum, Collinsella aerofaciens, Coprococcus comes, Eubacterium rectale, Faecalibacterium prausnitzii, Lachnospiraceae bacterium 5_1_57FAA	Coprococcus comes, Eubacterium rectale, Faecalibacterium prausnitzii
N2000	clade_252, clade_253, (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_354 or clade_354e), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_479 or clade_479c or clade_479g or clade_479h)	Blautia producta, Clostridium butyricum, Clostridium disporicum, Clostridium mayombei, Dorea formicigenerans, Erysipelotrichaceae bacterium 3_1_53, Eubacterium tenue, Ruminococcus torques	Dorea formicigenerans, Ruminococcus torques
N2001	clade_252, clade_253, (clade_260 or clade_260c or clade_260g or clade_260h), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_351 or clade_351e), (clade_354 or clade_354e), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), clade_494, clade_537, (clade_553 or clade_553i)	Blautia producta, Clostridium bolteae, Clostridium disporicum, Clostridium hylemonae, Clostridium innocuum, Clostridium mayombei, Clostridium orbiscindens, Clostridium symbiosum, Clostridium tertium, Collinsella aerofaciens, Coprococcus comes, Lachnospiraceae bacterium 5_1_57FAA, Ruminococcus bromii, Ruminococcus gnavus	Coprococcus comes, Ruminococcus bromii
N2002	clade_252, clade_253, (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_354 or clade_354e), (clade_479 or clade_479c or clade_479g or clade_479h)	Blautia producta, Clostridium butyricum, Clostridium disporicum, Clostridium mayombei, Erysipelotrichaceae bacterium 3_1_53	

N2003	clade_252, clade_253, (clade_260 or clade_260c or clade_260g or clade_260h), (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_354 or clade_354e), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_38 or clade_38e or clade_38i), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_481 or clade_481a or clade_481b or clade_481e or clade_481g or clade_481h or clade_481i), clade_537, (clade_553 or clade_553i)	Blautia producta, Clostridium bolteae, Clostridium butyricum, Clostridium disporicum, Clostridium hylemonae, Clostridium mayombei, Clostridium sordellii, Clostridium symbiosum, Clostridium tertium, Collinsella aerofaciens, Coprobacillus sp. D7, Coprococcus comes, Eubacterium sp. WAL 14571, Lachnospiraceae bacterium 5_1_57FAA, Ruminococcus bromii, Ruminococcus gnavus	Coprococcus comes, Ruminococcus bromii
N2004	(clade_351 or clade_351e), (clade_378 or clade_378e), (clade_38 or clade_38e or clade_38i), (clade_497 or clade_497e or clade_497f), (clade_65 or clade_65e), (clade_92 or clade_92e or clade_92i)	Bacteroides sp. 1_1_6, Bacteroides sp. 3_1_23, Bacteroides vulgatus, Clostridium innocuum, Enterococcus faecalis, Escherichia coli	
N2005	(clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_378 or clade_378e), (clade_38 or clade_38e or clade_38i), (clade_497 or clade_497e or clade_497f), (clade_65 or clade_65e), (clade_92 or clade_92e or clade_92i)	Bacteroides sp. 1_1_6, Bacteroides sp. 3_1_23, Bacteroides vulgatus, Blautia producta, Enterococcus faecalis, Escherichia coli	
N2006	clade_170, (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_444 or clade_444i), (clade_478 or clade_478i), (clade_65 or clade_65e)	Bacteroides caccae, Bacteroides sp. 1_1_6, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques	Bacteroides caccae, Coprococcus comes, Dorea formicigenerans, Dorea longicatena, Eubacterium rectale, Faecalibacterium prausnitzii, Ruminococcus obeum, Ruminococcus torques
N2007	clade_253, (clade_262 or clade_262i), (clade_309 or clade_309c or clade_309e or clade_309g or clade_309h or clade_309i), (clade_354 or clade_354e), (clade_360 or clade_360c or clade_360g or clade_360h or clade_360i), (clade_378 or clade_378e), (clade_408 or clade_408b or clade_408d or clade_408f or clade_408g or clade_408h), (clade_444 or clade_444i), clade_466, (clade_478 or clade_478i), (clade_479 or clade_479c or clade_479g or clade_479h), (clade_481 or clade_481a or clade_481b or clade_481e or clade_481g or clade_481h or clade_481i), (clade_497 or clade_497e or clade_497f), (clade_65 or clade_65e)	Bacteroides sp. 1_1_6, Bacteroides vulgatus, Clostridium disporicum, Clostridium mayombei, Clostridium symbiosum, Coprobacillus sp. D7, Coprococcus comes, Dorea formicigenerans, Enterococcus faecalis, Erysipelotrichaceae bacterium 3_1_53, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Ruminococcus obeum	Coprococcus comes, Dorea formicigenerans, Eubacterium rectale, Faecalibacterium prausnitzii, Odoribacter splanchnicus, Ruminococcus obeum

Table 18

KEGG Orthology Pathway (KO) characterization and F-score of computationally determined network ecologies reported in Table 8 that represent states of health for multiple disease indications.

Net ID	F-Score	KEGG Orthology Pathways
N253	29	KO:K00004, KO:K00023, KO:K00101, KO:K00102, KO:K00116, KO:K00156, KO:K00158, KO:K00163, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01505, KO:K01659, KO:K01720, KO:K01734, KO:K01905, KO:K01907, KO:K01908, KO:K03366, KO:K03416, KO:K03417, KO:K03777, KO:K03778, KO:K03821, KO:K04020, KO:K05973
N250	29	KO:K00004, KO:K00023, KO:K00101, KO:K00102, KO:K00116, KO:K00156, KO:K00158, KO:K00163, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01505, KO:K01659, KO:K01720, KO:K01734, KO:K01905, KO:K01907, KO:K01908, KO:K03366, KO:K03416, KO:K03417, KO:K03777, KO:K03778, KO:K03821, KO:K04020, KO:K05973
N249	29	KO:K00004, KO:K00023, KO:K00101, KO:K00102, KO:K00116, KO:K00156, KO:K00158, KO:K00163, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01505, KO:K01659, KO:K01720, KO:K01734, KO:K01905, KO:K01907, KO:K01908, KO:K03366, KO:K03416, KO:K03417, KO:K03777, KO:K03778, KO:K03821, KO:K04020, KO:K05973
N252	29	KO:K00004, KO:K00023, KO:K00101, KO:K00102, KO:K00116, KO:K00156, KO:K00158, KO:K00163, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01505, KO:K01659, KO:K01720, KO:K01734, KO:K01905, KO:K01907, KO:K01908, KO:K03366, KO:K03416, KO:K03417, KO:K03777, KO:K03778, KO:K03821, KO:K04020, KO:K05973
N251	28	KO:K00023, KO:K00101, KO:K00102, KO:K00116, KO:K00156, KO:K00158, KO:K00163, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01505, KO:K01659, KO:K01720, KO:K01734, KO:K01905, KO:K01907, KO:K01908, KO:K03366, KO:K03416, KO:K03417, KO:K03777, KO:K03778, KO:K03821, KO:K04020, KO:K05973
N257	27	KO:K00023, KO:K00101, KO:K00102, KO:K00116, KO:K00156, KO:K00158, KO:K00163, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01505, KO:K01659, KO:K01720, KO:K01734, KO:K01905, KO:K01907, KO:K03366, KO:K03416, KO:K03417, KO:K03777, KO:K03778, KO:K03821, KO:K04020, KO:K05973
N254	27	KO:K00023, KO:K00101, KO:K00102, KO:K00116, KO:K00156, KO:K00158, KO:K00163, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01505, KO:K01659, KO:K01720, KO:K01734, KO:K01905, KO:K01907, KO:K03366, KO:K03416, KO:K03417, KO:K03777, KO:K03778, KO:K03821, KO:K04020, KO:K05973
N255	27	KO:K00023, KO:K00101, KO:K00102, KO:K00116, KO:K00156, KO:K00158, KO:K00163, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01505, KO:K01659, KO:K01720, KO:K01734, KO:K01905, KO:K01907, KO:K03366, KO:K03416, KO:K03417, KO:K03777, KO:K03778, KO:K03821, KO:K04020, KO:K05973
N1036	17	KO:K00101, KO:K00116, KO:K00156, KO:K00163, KO:K00627, KO:K00656, KO:K00932, KO:K01069, KO:K01442, KO:K01659, KO:K01720, KO:K01734, KO:K01908, KO:K03417, KO:K03777, KO:K03778, KO:K04020
N968	17	KO:K00101, KO:K00116, KO:K00156, KO:K00163, KO:K00627, KO:K00656, KO:K00932, KO:K01069, KO:K01442, KO:K01659, KO:K01720, KO:K01734, KO:K01908, KO:K03417, KO:K03777, KO:K03778, KO:K04020
N335	15	KO:K00102, KO:K00156, KO:K00158, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01067, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03366, KO:K03778, KO:K13923
N329	15	KO:K00102, KO:K00156, KO:K00158, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01067, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03366, KO:K03778, KO:K13923
N365	13	KO:K00004, KO:K00116, KO:K00156, KO:K00163, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778

N363	13	KO:K00004, KO:K00116, KO:K00156, KO:K00163, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N282	13	KO:K00004, KO:K00156, KO:K00158, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03366, KO:K03778
N280	13	KO:K00004, KO:K00116, KO:K00156, KO:K00163, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N306	13	KO:K00102, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K01905, KO:K03417, KO:K03778, KO:K07246
N623	12	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01067, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778, KO:K13923
N350	12	KO:K00102, KO:K00156, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K01905, KO:K03778
N324	12	KO:K00156, KO:K00163, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01067, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N914	12	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01067, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778, KO:K13923
N351	12	KO:K00102, KO:K00156, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K01905, KO:K03778
N296	12	KO:K00156, KO:K00163, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01067, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N917	12	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01067, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778, KO:K13923
N299	12	KO:K00156, KO:K00163, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01067, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N790	12	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01067, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778, KO:K13923
N386	12	KO:K00156, KO:K00158, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03366, KO:K03778
N275	12	KO:K00156, KO:K00163, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01067, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N777	12	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01067, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778, KO:K13923
N318	12	KO:K00156, KO:K00163, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01067, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N271	12	KO:K00156, KO:K00158, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03366, KO:K03778
N816	12	KO:K00156, KO:K00158, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03366, KO:K03778
N256	12	KO:K00102, KO:K00116, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778, KO:K04020
N259	12	KO:K00156, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01067, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778, KO:K07246
N262	12	KO:K00156, KO:K00158, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03366, KO:K03778
N382	12	KO:K00102, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K01905, KO:K03417, KO:K03778, KO:K07246
N424	11	KO:K00156, KO:K00158, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03366, KO:K03778
N640	11	KO:K00102, KO:K00116, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734,

		KO:K03778, KO:K04020
N505	11	KO:K00156, KO:K00158, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03366, KO:K03778
N590	11	KO:K00004, KO:K00158, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03366, KO:K03778
N641	11	KO:K00004, KO:K00158, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03366, KO:K03778
N625	11	KO:K00156, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03366, KO:K03778
N410	11	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01067, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778, KO:K07246
N586	11	KO:K00102, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K01905, KO:K03778
N326	11	KO:K00116, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01505, KO:K01659, KO:K01734, KO:K03778
N522	11	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K01896, KO:K03417, KO:K03778, KO:K07246
N265	11	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01067, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N588	11	KO:K00102, KO:K00116, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778, KO:K04020
N1074	11	KO:K00004, KO:K00156, KO:K00158, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03366, KO:K03778
N610	11	KO:K00156, KO:K00158, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03366, KO:K03778
N408	11	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01067, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778, KO:K07246
N548	11	KO:K00156, KO:K00163, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N383	11	KO:K00156, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778, KO:K10783
N269	11	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01067, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N901	11	KO:K00004, KO:K00156, KO:K00158, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03366, KO:K03778
N419	11	KO:K00156, KO:K00158, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03366, KO:K03778
N443	11	KO:K00116, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01505, KO:K01659, KO:K01734, KO:K03778
N470	11	KO:K00156, KO:K00158, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03366, KO:K03778
N908	11	KO:K00156, KO:K00163, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01067, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N631	11	KO:K00156, KO:K00158, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03366, KO:K03778
N619	11	KO:K00102, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K01905, KO:K03778
N926	11	KO:K00004, KO:K00156, KO:K00158, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03366, KO:K03778

N429	11	KO:K00116, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01505, KO:K01659, KO:K01734, KO:K03778
N390	11	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778, KO:K04020
N368	11	KO:K00156, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03366, KO:K03778
N345	11	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03417, KO:K03778, KO:K07246
N354	11	KO:K00156, KO:K00163, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N825	11	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778, KO:K04020
N822	11	KO:K00004, KO:K00156, KO:K00158, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03366, KO:K03778
N573	11	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778, KO:K04020
N666	11	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778, KO:K04020
N288	11	KO:K00156, KO:K00158, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03366, KO:K03778
N650	11	KO:K00102, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K01905, KO:K03778
N338	11	KO:K00156, KO:K00158, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N381	11	KO:K00156, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778, KO:K10783
N292	11	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03417, KO:K03778, KO:K07246
N818	11	KO:K00156, KO:K00163, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01067, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N516	11	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778, KO:K04020
N515	11	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778, KO:K04020
N276	11	KO:K00156, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778, KO:K10783
N258	11	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01067, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N851	11	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01067, KO:K01069, KO:K01734, KO:K03778, KO:K04020, KO:K07246
N307	11	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03417, KO:K03778, KO:K07246
N400	11	KO:K00634, KO:K00656, KO:K00929, KO:K01067, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03417, KO:K03778, KO:K07246
N361	10	KO:K00116, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N558	10	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01067, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N891	10	KO:K00102, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K01905, KO:K03778,

		KO:K07246
N904	10	KO:K00156, KO:K00158, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N274	10	KO:K00156, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N612	10	KO:K00156, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03366, KO:K03778
N501	10	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N643	10	KO:K00156, KO:K00158, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03366, KO:K03778
N633	10	KO:K00156, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03366, KO:K03778
N866	10	KO:K00102, KO:K00156, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K01905, KO:K03778
N444	10	KO:K00116, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01505, KO:K01734, KO:K03778
N535	10	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01067, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N552	10	KO:K00156, KO:K00158, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N1072	10	KO:K00102, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K01905, KO:K03778, KO:K07246
N597	10	KO:K00158, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N539	10	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01067, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N717	10	KO:K00163, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N471	10	KO:K00156, KO:K00158, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03366, KO:K03778
N268	10	KO:K00156, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N298	10	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N409	10	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778, KO:K10783
N489	10	KO:K00156, KO:K00158, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03366, KO:K03778
N266	10	KO:K00156, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N319	10	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N566	10	KO:K00043, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778, KO:K07246
N542	10	KO:K00156, KO:K00163, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N337	10	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778

N886	10	KO:K00156, KO:K00163, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N528	10	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03417, KO:K03778, KO:K07246
N295	10	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N966	10	KO:K00156, KO:K00158, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03366, KO:K03778
N940	10	KO:K00156, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03366, KO:K03778
N407	10	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778, KO:K10783
N481	10	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N336	10	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N530	10	KO:K00156, KO:K00158, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N567	10	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03417, KO:K03778, KO:K07246
N525	10	KO:K00043, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778, KO:K07246
N771	10	KO:K00163, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N644	10	KO:K00158, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N560	10	KO:K00156, KO:K00163, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N595	10	KO:K00156, KO:K00158, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03366, KO:K03778
N349	10	KO:K00156, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N531	10	KO:K00004, KO:K00158, KO:K00627, KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03366, KO:K03778
N568	10	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01067, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N707	10	KO:K00102, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K01905, KO:K03778
N366	10	KO:K00116, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N797	10	KO:K00156, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03366, KO:K03778
N791	10	KO:K00156, KO:K00163, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N375	10	KO:K00156, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N387	10	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N346	10	KO:K00116, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734,

		KO:K03778
N342	10	KO:K00156, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N834	10	KO:K00156, KO:K00158, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03366, KO:K03778
N314	10	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N332	10	KO:K00156, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N352	10	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01067, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N367	10	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01067, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N333	10	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N519	10	KO:K00004, KO:K00158, KO:K00627, KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03366, KO:K03778
N353	10	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01067, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N680	10	KO:K00102, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K01905, KO:K03778
N283	10	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778, KO:K10783
N264	10	KO:K00156, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N281	10	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N821	10	KO:K00156, KO:K00158, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N273	10	KO:K00156, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N260	10	KO:K00156, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N817	10	KO:K00158, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03366, KO:K03778
N438	10	KO:K00116, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01505, KO:K01734, KO:K03778
N263	10	KO:K00156, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N261	10	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N313	10	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N401	10	KO:K00102, KO:K00156, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778, KO:K04020
N584	10	KO:K00102, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03417, KO:K03778, KO:K07246
N286	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N426	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778

N362	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N270	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N716	9	KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778, KO:K07246
N277	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N614	9	KO:K00156, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N423	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N311	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N546	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N1073	9	KO:K00634, KO:K00656, KO:K00929, KO:K01067, KO:K01069, KO:K01442, KO:K01734, KO:K03778, KO:K07246
N635	9	KO:K00156, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N492	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N770	9	KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778, KO:K07246
N422	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N882	9	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778, KO:K04020
N427	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N700	9	KO:K00158, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N1030	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03417, KO:K03778, KO:K07246
N450	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N322	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N308	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N549	9	KO:K00004, KO:K00116, KO:K00163, KO:K00627, KO:K00634, KO:K00656, KO:K01442, KO:K01659, KO:K01734
N404	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N1070	9	KO:K00156, KO:K00163, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734
N601	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N954	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03417, KO:K03778, KO:K07246
N699	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N884	9	KO:K00156, KO:K00163, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N309	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N488	9	KO:K00158, KO:K00627, KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03366, KO:K03778
N496	9	KO:K00156, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N364	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N502	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N297	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N618	9	KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N310	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N526	9	KO:K00004, KO:K00116, KO:K00163, KO:K00627, KO:K00634, KO:K00656, KO:K01442, KO:K01659, KO:K01734
N1083	9	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03417, KO:K03778, KO:K07246
N749	9	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778, KO:K04020
N608	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N555	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N955	9	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03417, KO:K03778, KO:K07246
N454	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N622	9	KO:K00004, KO:K00158, KO:K00627, KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03366, KO:K03778
N477	9	KO:K00156, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N497	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N325	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N285	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N534	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778

N896	9	KO:K00116, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01505, KO:K01734
N1008	9	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01659, KO:K01734, KO:K03778, KO:K04020
N465	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N328	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N646	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01067, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N449	9	KO:K00627, KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03417, KO:K03778, KO:K07246
N320	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N445	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N1097	9	KO:K00163, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N384	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N898	9	KO:K00634, KO:K00656, KO:K00929, KO:K01067, KO:K01069, KO:K01442, KO:K01734, KO:K03778, KO:K07246
N406	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N536	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01067, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N321	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N563	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N965	9	KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778, KO:K07246
N278	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N734	9	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778, KO:K04020
N453	9	KO:K00634, KO:K00656, KO:K00929, KO:K01067, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N868	9	KO:K00102, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K01905, KO:K03778
N870	9	KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778, KO:K10783
N442	9	KO:K00158, KO:K00627, KO:K00634, KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N323	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N494	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N447	9	KO:K00634, KO:K00656, KO:K00929, KO:K01067, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N591	9	KO:K00004, KO:K00158, KO:K00627, KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03366, KO:K03778
N327	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N417	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N607	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N921	9	KO:K00102, KO:K00156, KO:K00656, KO:K01067, KO:K01069, KO:K01442, KO:K01734, KO:K03778, KO:K13923
N556	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01067, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N482	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N267	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N602	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01067, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N385	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N294	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N474	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N572	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N663	9	KO:K00158, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N799	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01067, KO:K01442, KO:K01734, KO:K03778, KO:K07246
N413	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N394	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N392	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N393	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N371	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N395	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N391	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N372	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778

N370	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N389	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N369	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N388	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N355	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N379	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N356	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N397	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N331	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N358	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N374	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N378	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N343	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N377	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N341	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N344	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N348	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N575	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N340	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N347	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N373	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N376	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N359	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N357	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N302	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N284	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N334	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N576	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N304	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N291	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N290	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N339	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N396	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N316	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N301	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N289	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N440	9	KO:K00627, KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03417, KO:K03778, KO:K07246
N300	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N330	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N360	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N778	9	KO:K00102, KO:K00156, KO:K00656, KO:K01067, KO:K01069, KO:K01442, KO:K01734, KO:K03778, KO:K13923
N303	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N315	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N398	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N432	9	KO:K00158, KO:K00627, KO:K00634, KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N431	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N667	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N439	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778

N312	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N317	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N793	9	KO:K00116, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01505, KO:K01734
N305	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N380	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N293	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N272	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N399	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N823	9	KO:K00156, KO:K00163, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N279	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N824	9	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778, KO:K04020
N789	9	KO:K00156, KO:K00163, KO:K00627, KO:K00656, KO:K01067, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N414	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N435	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N402	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N459	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N460	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N433	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N403	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N458	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N517	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N682	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N434	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N415	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N609	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N639	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778, KO:K10783
N569	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N466	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N1025	8	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N768	8	KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N636	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N726	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N698	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N691	8	KO:K00156, KO:K00163, KO:K00627, KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N869	8	KO:K00156, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N605	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N630	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N718	8	KO:K00156, KO:K00627, KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N448	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N418	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N919	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778, KO:K10783
N714	8	KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N479	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N561	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N411	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N865	8	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N499	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N909	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778, KO:K10783

N543	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N759	8	KO:K00004, KO:K00158, KO:K00627, KO:K00634, KO:K00656, KO:K01442, KO:K01734, KO:K03366
N761	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N1018	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01067, KO:K01442, KO:K01734, KO:K03778
N456	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N735	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N928	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01067, KO:K01442, KO:K01734, KO:K03778
N495	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N500	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N480	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N478	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N701	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N547	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N945	8	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N762	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N493	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N739	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N912	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778, KO:K10783
N484	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N720	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N1014	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778, KO:K10783
N744	8	KO:K00156, KO:K00656, KO:K01067, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N451	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N565	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N498	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N483	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N628	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N889	8	KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N624	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N731	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N1038	8	KO:K00158, KO:K00627, KO:K00656, KO:K01442, KO:K01659, KO:K01734, KO:K03366, KO:K03778
N727	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N615	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N697	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N538	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N688	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N1037	8	KO:K00163, KO:K00627, KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N541	8	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03417, KO:K03778, KO:K07246
N721	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N971	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N1096	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N629	8	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03417, KO:K03778, KO:K07246
N504	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N587	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778, KO:K10783
N476	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N564	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N746	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N490	8	KO:K00158, KO:K00627, KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778

N767	8	KO:K00102, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N693	8	KO:K00004, KO:K00158, KO:K00627, KO:K00634, KO:K00656, KO:K01442, KO:K01734, KO:K03366
N559	8	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03417, KO:K03778, KO:K07246
N712	8	KO:K00102, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N467	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N711	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N938	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N405	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N524	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N593	8	KO:K00158, KO:K00627, KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03366, KO:K03778
N941	8	KO:K00102, KO:K00156, KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N1056	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N752	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N1019	8	KO:K00156, KO:K00656, KO:K01067, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N503	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N455	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N485	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N1042	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N684	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N876	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N657	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N658	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N678	8	KO:K00156, KO:K00627, KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N792	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778, KO:K10783
N661	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N462	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N672	8	KO:K00156, KO:K00163, KO:K00627, KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N664	8	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778, KO:K10783
N656	8	KO:K00156, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N655	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N844	8	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K04020
N674	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N784	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N675	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N463	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N830	8	KO:K00156, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N659	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N839	8	KO:K00102, KO:K00156, KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N833	8	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N782	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N509	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N579	8	KO:K00158, KO:K00627, KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03366, KO:K03778
N795	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778, KO:K10783
N430	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N416	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N794	8	KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N651	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N1091	8	KO:K00156, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734

N1093	8	KO:K00156, KO:K00627, KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N437	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N582	8	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03417, KO:K03778, KO:K07246
N683	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N989	7	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N621	7	KO:K00043, KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N627	7	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N1055	7	KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N922	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N469	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N935	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N1013	7	KO:K00158, KO:K00627, KO:K00656, KO:K01442, KO:K01659, KO:K01734, KO:K03366
N1021	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N958	7	KO:K00156, KO:K00656, KO:K01067, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N907	7	KO:K00158, KO:K00627, KO:K00656, KO:K01442, KO:K01659, KO:K01734, KO:K03366
N937	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N604	7	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N961	7	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N634	7	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N1085	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N900	7	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N592	7	KO:K00627, KO:K00634, KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N452	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N1045	7	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N960	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N979	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N748	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N702	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N972	7	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N906	7	KO:K00102, KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N892	7	KO:K00043, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N745	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N598	7	KO:K00158, KO:K00627, KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N725	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N957	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N527	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N1028	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N1033	7	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N715	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N428	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N872	7	KO:K00158, KO:K00627, KO:K00656, KO:K01442, KO:K01659, KO:K01734, KO:K03366
N686	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N446	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N687	7	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N638	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N1065	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N1011	7	KO:K00656, KO:K01067, KO:K01442, KO:K01659, KO:K01734, KO:K03778, KO:K07246
N733	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778

N1002	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N1076	7	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01734, KO:K03417, KO:K07246
N952	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N1032	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N708	7	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N743	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N1060	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N487	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N632	7	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N980	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N871	7	KO:K00656, KO:K01067, KO:K01442, KO:K01659, KO:K01734, KO:K03778, KO:K07246
N890	7	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N974	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N1022	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N867	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N758	7	KO:K00634, KO:K00656, KO:K01067, KO:K01442, KO:K01734, KO:K03778, KO:K07246
N924	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N981	7	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N473	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N1044	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N723	7	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N611	7	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N875	7	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734
N1005	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N975	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N992	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N936	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N933	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N913	7	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01734, KO:K03417, KO:K07246
N994	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N685	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N1054	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N997	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N760	7	KO:K00158, KO:K00627, KO:K00634, KO:K00656, KO:K01442, KO:K01734, KO:K03366
N532	7	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N1039	7	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734
N1041	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N988	7	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N944	7	KO:K00627, KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03366, KO:K03778
N585	7	KO:K00163, KO:K00627, KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734
N754	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N959	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N696	7	KO:K00158, KO:K00627, KO:K00634, KO:K00656, KO:K01442, KO:K01734, KO:K03366
N887	7	KO:K00156, KO:K00163, KO:K00627, KO:K00656, KO:K01069, KO:K01442, KO:K01734
N550	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N1050	7	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N1051	7	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01659, KO:K01734, KO:K03778
N973	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01659, KO:K01734, KO:K03778

N475	7	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N486	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N910	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N421	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N1068	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N1000	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N1052	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N741	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N491	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N1040	7	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N948	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N540	7	KO:K00627, KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N903	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N888	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N468	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N695	7	KO:K00116, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N976	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N1012	7	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N719	7	KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03417, KO:K03778, KO:K07246
N507	7	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N895	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N692	7	KO:K00634, KO:K00656, KO:K01067, KO:K01442, KO:K01734, KO:K03778, KO:K07246
N894	7	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N995	7	KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N613	7	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N877	7	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N617	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N722	7	KO:K00116, KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N1035	7	KO:K00158, KO:K00656, KO:K01442, KO:K01659, KO:K01734, KO:K03366, KO:K03778
N649	7	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N679	7	KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03417, KO:K03778, KO:K07246
N677	7	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N803	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N660	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N787	7	KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N807	7	KO:K00043, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N804	7	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N800	7	KO:K00156, KO:K00163, KO:K00627, KO:K00656, KO:K01069, KO:K01442, KO:K01734
N788	7	KO:K00116, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01734, KO:K10783
N785	7	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N854	7	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N843	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N846	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N855	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01659, KO:K01734, KO:K03778
N654	7	KO:K00116, KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N842	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N838	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N783	7	KO:K00156, KO:K00656, KO:K01067, KO:K01069, KO:K01442, KO:K01734, KO:K03778

N796	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N836	7	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N670	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N837	7	KO:K00163, KO:K00627, KO:K00634, KO:K00656, KO:K01069, KO:K01442, KO:K01734
N520	7	KO:K00627, KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N669	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N835	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N671	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N840	7	KO:K00627, KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03366, KO:K03778
N829	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N819	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N518	7	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N580	7	KO:K00158, KO:K00627, KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N668	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N780	7	KO:K00158, KO:K00627, KO:K00656, KO:K01442, KO:K01659, KO:K01734, KO:K03366
N831	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N577	7	KO:K00627, KO:K00634, KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N832	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N798	7	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N815	7	KO:K00102, KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N820	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N826	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N441	7	KO:K00634, KO:K00656, KO:K00929, KO:K01067, KO:K01442, KO:K01734, KO:K03778
N583	7	KO:K00634, KO:K00656, KO:K00929, KO:K01067, KO:K01442, KO:K01734, KO:K03778
N464	7	KO:K00634, KO:K00656, KO:K00929, KO:K01067, KO:K01442, KO:K01734, KO:K03778
N461	7	KO:K00634, KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N848	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N513	7	KO:K00634, KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N511	7	KO:K00634, KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N596	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N537	6	KO:K00102, KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N732	6	KO:K00634, KO:K00656, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N506	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N1015	6	KO:K00158, KO:K00656, KO:K01442, KO:K01659, KO:K01734, KO:K03366
N606	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N943	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N946	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734
N915	6	KO:K00634, KO:K00656, KO:K01442, KO:K01734, KO:K03778, KO:K10783
N1059	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N923	6	KO:K00158, KO:K00656, KO:K01442, KO:K01659, KO:K01734, KO:K03366
N1001	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N1064	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N706	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N642	6	KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03778, KO:K10783
N764	6	KO:K00158, KO:K00634, KO:K00656, KO:K01442, KO:K01734, KO:K03366
N874	6	KO:K00163, KO:K00627, KO:K00656, KO:K01069, KO:K01442, KO:K01734
N600	6	KO:K00627, KO:K00656, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N710	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778

N993	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N523	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N626	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N1043	6	KO:K00158, KO:K00627, KO:K00656, KO:K01442, KO:K01734, KO:K03366
N557	6	KO:K00102, KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N916	6	KO:K00656, KO:K01069, KO:K01659, KO:K01734, KO:K03778, KO:K10783
N1077	6	KO:K00634, KO:K00656, KO:K01442, KO:K01734, KO:K03778, KO:K10783
N978	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N990	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N553	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N1082	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734
N529	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N544	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N902	6	KO:K00043, KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N1027	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N694	6	KO:K00043, KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N1029	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N1084	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N931	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N1075	6	KO:K00158, KO:K00627, KO:K00656, KO:K01069, KO:K01734, KO:K03366
N551	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N1087	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N1010	6	KO:K00627, KO:K00656, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N724	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N769	6	KO:K00102, KO:K00656, KO:K01069, KO:K01659, KO:K01734, KO:K03778
N705	6	KO:K00158, KO:K00634, KO:K00656, KO:K01442, KO:K01734, KO:K03366
N603	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N740	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N950	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N420	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N1053	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N977	6	KO:K00158, KO:K00627, KO:K00656, KO:K01442, KO:K01734, KO:K03366
N594	6	KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03778, KO:K10783
N1080	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N953	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N425	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N472	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N878	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N753	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N766	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N873	6	KO:K00158, KO:K00627, KO:K00656, KO:K01442, KO:K01659, KO:K01734
N1023	6	KO:K00627, KO:K00656, KO:K01442, KO:K01734, KO:K03366, KO:K03778
N967	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N956	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N1031	6	KO:K00163, KO:K00627, KO:K00656, KO:K01069, KO:K01442, KO:K01734
N985	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N814	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N812	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778

N662	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N809	6	KO:K00656, KO:K01069, KO:K01659, KO:K01734, KO:K03778, KO:K10783
N858	6	KO:K00043, KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N508	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N681	6	KO:K00634, KO:K00656, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N845	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N673	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N521	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N1095	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N581	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N827	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N570	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N571	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N574	6	KO:K00627, KO:K00656, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N779	6	KO:K00158, KO:K00627, KO:K00656, KO:K01442, KO:K01659, KO:K01734
N578	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N457	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N652	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N828	6	KO:K00158, KO:K00627, KO:K00634, KO:K00656, KO:K01442, KO:K01734
N514	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N653	6	KO:K00043, KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N849	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N436	6	KO:K00634, KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N853	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N786	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N512	6	KO:K00634, KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N510	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N861	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N647	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N1071	5	KO:K00043, KO:K00656, KO:K01442, KO:K01659, KO:K01734
N932	5	KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N750	5	KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N893	5	KO:K00627, KO:K00656, KO:K01069, KO:K01442, KO:K01734
N897	5	KO:K00043, KO:K00627, KO:K00656, KO:K01442, KO:K01734
N729	5	KO:K00656, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N1003	5	KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N1069	5	KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N616	5	KO:K00634, KO:K00656, KO:K01442, KO:K01659, KO:K01734
N964	5	KO:K00656, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N920	5	KO:K00634, KO:K00656, KO:K01442, KO:K01734, KO:K03778
N1061	5	KO:K00656, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N738	5	KO:K00656, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N983	5	KO:K00627, KO:K00656, KO:K01442, KO:K01734, KO:K03366
N757	5	KO:K00634, KO:K00656, KO:K01442, KO:K01734, KO:K03778
N755	5	KO:K00656, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N1004	5	KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N879	5	KO:K00656, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N962	5	KO:K00656, KO:K01442, KO:K01659, KO:K01734, KO:K03778

N1016	5	KO:K00158, KO:K00627, KO:K00656, KO:K01442, KO:K01734
N533	5	KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N645	5	KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N736	5	KO:K00656, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N713	5	KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N1006	5	KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N925	5	KO:K00158, KO:K00627, KO:K00656, KO:K01442, KO:K01734
N620	5	KO:K00656, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N880	5	KO:K00634, KO:K00656, KO:K01069, KO:K01442, KO:K01734
N747	5	KO:K00656, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N885	5	KO:K00043, KO:K00656, KO:K01442, KO:K01659, KO:K01734
N737	5	KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N554	5	KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N951	5	KO:K00102, KO:K00656, KO:K01069, KO:K01734, KO:K03778
N690	5	KO:K00634, KO:K00656, KO:K01442, KO:K01734, KO:K03778
N730	5	KO:K00634, KO:K00656, KO:K01442, KO:K01734, KO:K03778
N999	5	KO:K00656, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N589	5	KO:K00656, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N545	5	KO:K00634, KO:K00656, KO:K01442, KO:K01659, KO:K01734
N763	5	KO:K00656, KO:K01659, KO:K01734, KO:K03778, KO:K10783
N1067	5	KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N703	5	KO:K00656, KO:K01659, KO:K01734, KO:K03778, KO:K10783
N773	5	KO:K00634, KO:K00656, KO:K01442, KO:K01734, KO:K03778
N756	5	KO:K00634, KO:K00656, KO:K01442, KO:K01734, KO:K10783
N1062	5	KO:K00634, KO:K00656, KO:K01069, KO:K01442, KO:K01734
N1046	5	KO:K00627, KO:K00656, KO:K01442, KO:K01734, KO:K03366
N742	5	KO:K00656, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N704	5	KO:K00656, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N751	5	KO:K00656, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N939	5	KO:K00627, KO:K00656, KO:K01069, KO:K01734, KO:K03778
N984	5	KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N599	5	KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N1066	5	KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N689	5	KO:K00634, KO:K00656, KO:K01442, KO:K01734, KO:K10783
N562	5	KO:K00634, KO:K00656, KO:K01442, KO:K01659, KO:K01734
N918	5	KO:K00656, KO:K01069, KO:K01734, KO:K03778, KO:K10783
N1078	5	KO:K00158, KO:K00627, KO:K00656, KO:K01069, KO:K01734
N1007	5	KO:K00656, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N637	5	KO:K00634, KO:K00656, KO:K01442, KO:K01659, KO:K01734
N859	5	KO:K00102, KO:K00656, KO:K01069, KO:K01734, KO:K03778
N676	5	KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N856	5	KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N665	5	KO:K00656, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N775	5	KO:K00634, KO:K00656, KO:K01442, KO:K01734, KO:K03778
N857	5	KO:K00656, KO:K01069, KO:K01734, KO:K03778, KO:K10783
N802	5	KO:K00043, KO:K00627, KO:K00656, KO:K01442, KO:K01734
N801	5	KO:K00627, KO:K00656, KO:K01069, KO:K01442, KO:K01734
N774	5	KO:K00656, KO:K01442, KO:K01659, KO:K01734, KO:K03778

N847	5	KO:K00656, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N648	5	KO:K00656, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N862	5	KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N852	5	KO:K00656, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N841	5	KO:K00656, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N860	5	KO:K00627, KO:K00656, KO:K01069, KO:K01734, KO:K03778
N864	5	KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N863	5	KO:K00656, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N709	4	KO:K00634, KO:K00656, KO:K01442, KO:K01734
N982	4	KO:K00634, KO:K00656, KO:K01442, KO:K01734
N949	4	KO:K00656, KO:K01069, KO:K01442, KO:K01734
N986	4	KO:K00656, KO:K01442, KO:K01734, KO:K03778
N1047	4	KO:K00656, KO:K01659, KO:K01734, KO:K03778
N1086	4	KO:K00634, KO:K00656, KO:K01442, KO:K01734
N1017	4	KO:K00656, KO:K01067, KO:K01442, KO:K01734
N899	4	KO:K00116, KO:K00656, KO:K01442, KO:K01734
N927	4	KO:K00656, KO:K01067, KO:K01442, KO:K01734
N969	4	KO:K00116, KO:K00656, KO:K01069, KO:K01734
N772	4	KO:K00634, KO:K00656, KO:K01442, KO:K01734
N991	4	KO:K00656, KO:K01442, KO:K01734, KO:K03778
N1079	4	KO:K00634, KO:K00656, KO:K01442, KO:K01734
N1058	4	KO:K00656, KO:K01442, KO:K01659, KO:K01734
N987	4	KO:K00634, KO:K00656, KO:K01442, KO:K01734
N1063	4	KO:K00656, KO:K01442, KO:K01659, KO:K01734
N1049	4	KO:K00634, KO:K00656, KO:K01442, KO:K01734
N728	4	KO:K00634, KO:K00656, KO:K01442, KO:K01734
N1009	4	KO:K00656, KO:K01442, KO:K01734, KO:K03778
N1098	4	KO:K00656, KO:K01442, KO:K01659, KO:K01734
N947	4	KO:K00627, KO:K00656, KO:K01442, KO:K01734
N883	4	KO:K00656, KO:K01069, KO:K01442, KO:K01734
N934	4	KO:K00656, KO:K01442, KO:K01659, KO:K01734
N905	4	KO:K00656, KO:K01069, KO:K01442, KO:K01734
N963	4	KO:K00656, KO:K01442, KO:K01734, KO:K03778
N1034	4	KO:K00656, KO:K01442, KO:K01734, KO:K03778
N998	4	KO:K00656, KO:K01442, KO:K01659, KO:K01734
N929	4	KO:K00634, KO:K00656, KO:K01442, KO:K01734
N881	4	KO:K00656, KO:K01442, KO:K01659, KO:K01734
N765	4	KO:K00634, KO:K00656, KO:K01442, KO:K01734
N1081	4	KO:K00656, KO:K01442, KO:K01659, KO:K01734
N1048	4	KO:K00656, KO:K01442, KO:K01734, KO:K03778
N970	4	KO:K00656, KO:K01442, KO:K01734, KO:K03778
N1024	4	KO:K00102, KO:K00656, KO:K01442, KO:K01734
N911	4	KO:K00656, KO:K01069, KO:K01734, KO:K10783
N1026	4	KO:K00627, KO:K00656, KO:K01442, KO:K01734
N942	4	KO:K00102, KO:K00656, KO:K01442, KO:K01734
N813	4	KO:K00656, KO:K01442, KO:K01734, KO:K03778
N811	4	KO:K00116, KO:K00656, KO:K01069, KO:K01734
N810	4	KO:K00656, KO:K01069, KO:K01442, KO:K01734

N808	4	KO:K00656, KO:K01069, KO:K01734, KO:K10783
N805	4	KO:K00656, KO:K01069, KO:K01442, KO:K01734
N806	4	KO:K00656, KO:K01069, KO:K01442, KO:K01734
N1088	4	KO:K00656, KO:K01069, KO:K01442, KO:K01734
N781	4	KO:K00656, KO:K01069, KO:K01442, KO:K01734
N776	4	KO:K00116, KO:K00656, KO:K01442, KO:K01734
N1020	3	KO:K00656, KO:K01442, KO:K01734
N930	3	KO:K00656, KO:K01442, KO:K01734
N996	3	KO:K00656, KO:K01442, KO:K01734
N1057	3	KO:K00656, KO:K01442, KO:K01734
N1089	3	KO:K00656, KO:K01659, KO:K01734
N1094	3	KO:K00627, KO:K00656, KO:K03778
N850	3	KO:K00656, KO:K01734, KO:K03778
N1090	2	KO:K00656, KO:K01442
N1092	2	KO:K01442, KO:K01734
N412	0	
N287	0	

Table 19.

KEGG Orthology Pathway (KO) hierarchical ontology for KOs identified in computationally determined networks characteristic of states of health and reported in Table 18.

KEGG number	KEGG annotation level 1	KEGG annotation level 2	KEGG annotation level 3	Full KEGG annotation level 4
KO:K01442	Metabolism	Lipid metabolism	00121 Secondary bile acid biosynthesis [PATH:ko00121]	E3.5.1.24; choloylglycine hydrolase [EC:3.5.1.24]
KO:K00004	Metabolism	Carbohydrate metabolism	00650 Butanoate metabolism [PATH:ko00650]	BDH, butB; (R,R)-butanediol dehydrogenase / diacetyl reductase [EC:1.1.1.4 1.1.1.303]
KO:K00023	Metabolism	Carbohydrate metabolism	00650 Butanoate metabolism [PATH:ko00650]	E1.1.1.36, phbB; acetoacetyl-CoA reductase [EC:1.1.1.36]
KO:K00043	Metabolism	Carbohydrate metabolism	00650 Butanoate metabolism [PATH:ko00650]	E1.1.1.61; 4-hydroxybutyrate dehydrogenase [EC:1.1.1.61]
KO:K00101	Metabolism	Carbohydrate metabolism	00620 Pyruvate metabolism [PATH:ko00620]	E1.1.2.3, lldD; L-lactate dehydrogenase (cytochrome) [EC:1.1.2.3]
KO:K00102	Metabolism	Carbohydrate metabolism	00620 Pyruvate metabolism [PATH:ko00620]	E1.1.2.4, dld; D-lactate dehydrogenase (cytochrome) [EC:1.1.2.4]
KO:K00116	Metabolism	Carbohydrate metabolism	00620 Pyruvate metabolism [PATH:ko00620]	mqo; malate dehydrogenase (quinone) [EC:1.1.5.4]
KO:K00156	Metabolism	Carbohydrate metabolism	00620 Pyruvate metabolism [PATH:ko00620]	poxB; pyruvate dehydrogenase (quinone) [EC:1.2.5.1]
KO:K00158	Metabolism	Carbohydrate metabolism	00620 Pyruvate metabolism [PATH:ko00620]	E1.2.3.3, poxL; pyruvate oxidase [EC:1.2.3.3]
KO:K00163	Metabolism	Carbohydrate metabolism	00650 Butanoate metabolism [PATH:ko00650]	aceE; pyruvate dehydrogenase E1 component [EC:1.2.4.1]
KO:K00627	Metabolism	Carbohydrate metabolism	00620 Pyruvate metabolism [PATH:ko00620]	DLAT, aceF, pdhC; pyruvate dehydrogenase E2 component (dihydrolipoamide acetyltransferase) [EC:2.3.1.12]
KO:K00634	Metabolism	Carbohydrate metabolism	00650 Butanoate metabolism [PATH:ko00650]	ptb; phosphate butyryltransferase [EC:2.3.1.19]
KO:K00656	Metabolism	Carbohydrate metabolism	00650 Butanoate metabolism [PATH:ko00650]	E2.3.1.54, pflD; formate C-acetyltransferase [EC:2.3.1.54]
KO:K00929	Metabolism	Carbohydrate metabolism	00650 Butanoate metabolism [PATH:ko00650]	E2.7.2.7, buk; butyrate kinase [EC:2.7.2.7]
KO:K00932	Metabolism	Carbohydrate metabolism	00640 Propanoate metabolism [PATH:ko00640]	E2.7.2.15, tdcD, pduW; propionate kinase [EC:2.7.2.15]
KO:K01067	Metabolism	Carbohydrate metabolism	00620 Pyruvate metabolism [PATH:ko00620]	E3.1.2.1, ACH1; acetyl-CoA hydrolase [EC:3.1.2.1]
KO:K01069	Metabolism	Carbohydrate metabolism	00620 Pyruvate metabolism [PATH:ko00620]	E3.1.2.6, gloB; hydroxyacylglutathione hydrolase [EC:3.1.2.6]

KEGG number	KEGG annotation level 1	KEGG annotation level 2	KEGG annotation level 3	Full KEGG annotation level 4
KO:K01505	Metabolism	Carbohydrate metabolism	00640 Propanoate metabolism [PATH:ko00640]	E3.5.99.7; 1-aminocyclopropane-1-carboxylate deaminase [EC:3.5.99.7]
KO:K01659	Metabolism	Carbohydrate metabolism	00640 Propanoate metabolism [PATH:ko00640]	E2.3.3.5, prpC; 2-methylcitrate synthase [EC:2.3.3.5]
KO:K01720	Metabolism	Carbohydrate metabolism	00640 Propanoate metabolism [PATH:ko00640]	E4.2.1.79, prpD; 2-methylcitrate dehydratase [EC:4.2.1.79]
KO:K01734	Metabolism	Carbohydrate metabolism	00620 Pyruvate metabolism [PATH:ko00620]	E4.2.3.3, mgsA; methylglyoxal synthase [EC:4.2.3.3]
KO:K01896	Metabolism	Carbohydrate metabolism	00650 Butanoate metabolism [PATH:ko00650]	ACSM; medium-chain acyl-CoA synthetase [EC:6.2.1.2]
KO:K01905	Metabolism	Carbohydrate metabolism	00640 Propanoate metabolism [PATH:ko00640]	E6.2.1.13; acetyl-CoA synthetase (ADP-forming) [EC:6.2.1.13]
KO:K01907	Metabolism	Carbohydrate metabolism	00650 Butanoate metabolism [PATH:ko00650]	AACS, acsA; acetoacetyl-CoA synthetase [EC:6.2.1.16]
KO:K01908	Metabolism	Carbohydrate metabolism	00640 Propanoate metabolism [PATH:ko00640]	E6.2.1.17, prpE; propionyl-CoA synthetase [EC:6.2.1.17]
KO:K03366	Metabolism	Carbohydrate metabolism	00650 Butanoate metabolism [PATH:ko00650]	butA; (R,R)-butanediol dehydrogenase / diacetyl reductase [EC:1.1.1.4 1.1.1.303]
KO:K03416	Metabolism	Carbohydrate metabolism	00640 Propanoate metabolism [PATH:ko00640]	E2.1.3.1; methylmalonyl-CoA carboxyltransferase [EC:2.1.3.1]
KO:K03417	Metabolism	Carbohydrate metabolism	00640 Propanoate metabolism [PATH:ko00640]	E4.1.3.30, prpB; methylisocitrate lyase [EC:4.1.3.30]
KO:K03777	Metabolism	Carbohydrate metabolism	00620 Pyruvate metabolism [PATH:ko00620]	dld; D-lactate dehydrogenase [EC:1.1.1.28]
KO:K03778	Metabolism	Carbohydrate metabolism	00620 Pyruvate metabolism [PATH:ko00620]	ldhA; D-lactate dehydrogenase [EC:1.1.1.28]
KO:K03821	Metabolism	Carbohydrate metabolism	00650 Butanoate metabolism [PATH:ko00650]	phbC, phaC; polyhydroxyalkanoate synthase [EC:2.3.1.-]
KO:K04020	Metabolism	Carbohydrate metabolism	00620 Pyruvate metabolism [PATH:ko00620]	eutD; phosphotransacetylase
KO:K05973	Metabolism	Carbohydrate metabolism	00650 Butanoate metabolism [PATH:ko00650]	E3.1.1.75, phaZ; poly(3-hydroxybutyrate) depolymerase [EC:3.1.1.75]
KO:K07246	Metabolism	Carbohydrate metabolism	00650 Butanoate metabolism [PATH:ko00650]	ttuC, dmlA; tartrate dehydrogenase/decarboxylase / D-malate dehydrogenase [EC:1.1.1.93 4.1.1.73 1.1.1.83]
KO:K10783	Metabolism	Carbohydrate metabolism	00650 Butanoate metabolism [PATH:ko00650]	E1.3.1.44; trans-2-enoyl-CoA reductase (NAD+) [EC:1.3.1.44]
KO:K13923	Metabolism	Carbohydrate	00640 Propanoate metabolism	pduL; phosphotransacylase

KEGG annotation	KEGG annotation level 1	KEGG annotation level 2	KEGG annotation level 3	Full KEGG annotation level 4
		metabolism	[PATH:ko00640]	

Table 20.

Keystone OTUs inhibit *C. difficile* growth in a competitive in vitro simulation assay

OTU_1	OTU_1 is a Key stone	OTU_2	OTU_2 is a Key stone	% diff Inhibition Score
Bacteroides_caccae	1	Bacteroides_eggerthii		++++
Bacteroides_sp_D20	1	Bacteroides_eggerthii		
Clostridium_nexile	1	Bacteroides_eggerthii		
Coprococcus_catus	1	Bacteroides_eggerthii		+
Dorea_formicigenerans	1	Bacteroides_eggerthii		
Dorea_longicatena	1	Bacteroides_eggerthii		--
Faecalibacterium_prausnitzii	1	Bacteroides_eggerthii		
Odoribacter_splanchnicus	1	Bacteroides_eggerthii		
Parabacteroides_merdae	1	Bacteroides_eggerthii		
Roseburia_intestinalis	1	Bacteroides_eggerthii		
Ruminococcus_obeum	1	Bacteroides_eggerthii		++++
Bacteroides_caccae	1	Bifidobacterium_adolescentis		++++
Bacteroides_sp_D20	1	Bifidobacterium_adolescentis		++++
Clostridium_nexile	1	Bifidobacterium_adolescentis		++++
Coprococcus_catus	1	Bifidobacterium_adolescentis		
Dorea_formicigenerans	1	Bifidobacterium_adolescentis		++++
Dorea_longicatena	1	Bifidobacterium_adolescentis		++++
Faecalibacterium_prausnitzii	1	Bifidobacterium_adolescentis		+
Odoribacter_splanchnicus	1	Bifidobacterium_adolescentis		+++
Parabacteroides_merdae	1	Bifidobacterium_adolescentis		++++
Roseburia_intestinalis	1	Bifidobacterium_adolescentis		+++
Ruminococcus_obeum	1	Bifidobacterium_adolescentis		++++
Ruminococcus_torques	1	Bifidobacterium_adolescentis		++++
Bacteroides_caccae	1	Bifidobacterium_pseudocatenulatum		++++
Bacteroides_sp_D20	1	Bifidobacterium_pseudocatenulatum		--
Clostridium_nexile	1	Bifidobacterium_pseudocatenulatum		++++
Coprococcus_catus	1	Bifidobacterium_pseudocatenulatum		
Dorea_formicigenerans	1	Bifidobacterium_pseudocatenulatum		+++
Dorea_longicatena	1	Bifidobacterium_pseudocatenulatum		++++
Faecalibacterium_prausnitzii	1	Bifidobacterium_pseudocatenulatum		++
Odoribacter_splanchnicus	1	Bifidobacterium_pseudocatenulatum		+
Parabacteroides_merdae	1	Bifidobacterium_pseudocatenulatum		++++
Roseburia_intestinalis	1	Bifidobacterium_pseudocatenulatum		+++
Ruminococcus_obeum	1	Bifidobacterium_pseudocatenulatum		++++
Ruminococcus_torques	1	Bifidobacterium_pseudocatenulatum		++++
Bacteroides_caccae	1	Blautia_schinkii		
Bacteroides_sp_D20	1	Blautia_schinkii		--
Clostridium_nexile	1	Blautia_schinkii		--
Coprococcus_catus	1	Blautia_schinkii		---
Coprococcus_comes	1	Blautia_schinkii		+
Dorea_formicigenerans	1	Blautia_schinkii		
Dorea_longicatena	1	Blautia_schinkii		+++

OTU_1	OTU_1 is a Key Stone	OTU_2	OTU_2 is a Key Stone	C_diff Inhibition Score
Eubacterium_rectale	1	Blautia_schinkii		+
Faecalibacterium_prausnitzii	1	Blautia_schinkii		
Faecalibacterium_prausnitzii	1	Blautia_schinkii		
Odoribacter_splanchnicus	1	Blautia_schinkii		–
Odoribacter_splanchnicus	1	Blautia_schinkii		
Parabacteroides_merdae	1	Blautia_schinkii		
Roseburia_intestinalis	1	Blautia_schinkii		–
Ruminococcus_obeum	1	Blautia_schinkii		
Ruminococcus_torques	1	Blautia_schinkii		
Coprococcus_comes	1	Clostridium butyricum		++++
Coprococcus_comes	1	Clostridium orbiscindens		++++
Faecalibacterium_prausnitzii	1	Clostridium orbiscindens		
Coprococcus_comes	1	Clostridium_bolteae		++++
Coprococcus_comes	1	Clostridium_hylemonae		+
Clostridium_nexile	1	Clostridium_sp_HGF2		++++
Dorea_formicigenerans	1	Clostridium_sp_HGF2		
Clostridium_nexile	1	Erysipelotrichaceae_bacterium		
Coprococcus_catus	1	Erysipelotrichaceae_bacterium		
Dorea_formicigenerans	1	Erysipelotrichaceae_bacterium		----
Dorea_longicatena	1	Erysipelotrichaceae_bacterium		
Faecalibacterium_prausnitzii	1	Erysipelotrichaceae_bacterium		–
Odoribacter_splanchnicus	1	Erysipelotrichaceae_bacterium		
Roseburia_intestinalis	1	Erysipelotrichaceae_bacterium		–
Bacteroides_caccae	1	Lachnospiraceae_bacterium_5_1_57FAA		
Bacteroides_sp_D20	1	Lachnospiraceae_bacterium_5_1_57FAA		----
Clostridium_nexile	1	Lachnospiraceae_bacterium_5_1_57FAA		–
Coprococcus_catus	1	Lachnospiraceae_bacterium_5_1_57FAA		
Coprococcus_comes	1	Lachnospiraceae_bacterium_5_1_57FAA		
Coprococcus_comes	1	Lachnospiraceae_bacterium_5_1_57FAA		++++
Dorea_formicigenerans	1	Lachnospiraceae_bacterium_5_1_57FAA		—
Dorea_longicatena	1	Lachnospiraceae_bacterium_5_1_57FAA		++++
Eubacterium_rectale	1	Lachnospiraceae_bacterium_5_1_57FAA		
Faecalibacterium_prausnitzii	1	Lachnospiraceae_bacterium_5_1_57FAA		
Faecalibacterium_prausnitzii	1	Lachnospiraceae_bacterium_5_1_57FAA		
Faecalibacterium_prausnitzii	1	Lachnospiraceae_bacterium_5_1_57FAA		++++
Odoribacter_splanchnicus	1	Lachnospiraceae_bacterium_5_1_57FAA		----
Odoribacter_splanchnicus	1	Lachnospiraceae_bacterium_5_1_57FAA		
Parabacteroides_merdae	1	Lachnospiraceae_bacterium_5_1_57FAA		–
Roseburia_intestinalis	1	Lachnospiraceae_bacterium_5_1_57FAA		
Ruminococcus_obeum	1	Lachnospiraceae_bacterium_5_1_57FAA		
Ruminococcus_torques	1	Lachnospiraceae_bacterium_5_1_57FAA		
Bacteroides_eggerthii		Alistipes_shahii	1	—
Bacteroides_sp_1_1_6		Alistipes_shahii	1	++++
Bacteroides_sp_3_1_23		Alistipes_shahii	1	+

OTU_1	OTU_1 is a key stone	OTU_2	OTU_2 is a key stone	E. coli Inhibition Score
Bifidobacterium_adolescentis		Alistipes_shahii	1	++++
Bifidobacterium_pseudocatenulatum		Alistipes_shahii	1	
Blautia_schinkii		Alistipes_shahii	1	
Clostridium_sp_HGF2		Alistipes_shahii	1	
Coprobacillus_sp_D7		Alistipes_shahii	1	++++
Enterococcus_faecalis		Alistipes_shahii	1	++++
Erysipelotrichaceae_bacterium		Alistipes_shahii	1	---
Lachnospiraceae_bacterium_5_1_57FAA		Alistipes_shahii	1	
Bacteroides_sp_1_1_6		Bacteroides_caccae	1	++++
Bacteroides_sp_3_1_23		Bacteroides_caccae	1	+++
Clostridium_sp_HGF2		Bacteroides_caccae	1	
Coprobacillus_sp_D7		Bacteroides_caccae	1	+++
Enterococcus_faecalis		Bacteroides_caccae	1	++++
Erysipelotrichaceae_bacterium		Bacteroides_caccae	1	++
Bacteroides_sp_1_1_6		Bacteroides_sp_D20	1	++++
Bacteroides_sp_3_1_23		Bacteroides_sp_D20	1	++++
Clostridium_sp_HGF2		Bacteroides_sp_D20	1	
Coprobacillus_sp_D7		Bacteroides_sp_D20	1	
Enterococcus_faecalis		Bacteroides_sp_D20	1	++++
Erysipelotrichaceae_bacterium		Bacteroides_sp_D20	1	
Bacteroides_sp_1_1_6		Clostridium_nexile	1	++++
Bacteroides_sp_3_1_23		Clostridium_nexile	1	++++
Coprobacillus_sp_D7		Clostridium_nexile	1	
Enterococcus_faecalis		Clostridium_nexile	1	++++
Bacteroides_sp_1_1_6		Coprococcus_catus	1	++++
Bacteroides_sp_3_1_23		Coprococcus_catus	1	
Clostridium_sp_HGF2		Coprococcus_catus	1	---
Coprobacillus_sp_D7		Coprococcus_catus	1	---
Enterococcus_faecalis		Coprococcus_catus	1	++++
Bacteroides_eggerthii		Coprococcus_comes	1	+++
Bacteroides_sp_1_1_6		Coprococcus_comes	1	+++
Bacteroides_sp_3_1_23		Coprococcus_comes	1	++++
Bifidobacterium_adolescentis		Coprococcus_comes	1	++++
Bifidobacterium_pseudocatenulatum		Coprococcus_comes	1	++++
Clostridium butyricum		Coprococcus_comes	1	++++
Clostridium_disporicum		Coprococcus_comes	1	++++
Clostridium_hylemonae		Coprococcus_comes	1	+
Clostridium_innocuum		Coprococcus_comes	1	++++
Clostridium_mayombei		Coprococcus_comes	1	++++
Clostridium_sp_HGF2		Coprococcus_comes	1	
Clostridium_tertium		Coprococcus_comes	1	++++
Coprobacillus_sp_D7		Coprococcus_comes	1	+++
Enterococcus_faecalis		Coprococcus_comes	1	++++
Erysipelotrichaceae_bacterium		Coprococcus_comes	1	-

OTU_1	OTU_1 is a Key Stone	OTU_2	OTU_2 is a Key Stone	E. coli Inhibition Score
Bacteroides_sp_1_1_6		Dorea_formicigenerans	1	+++
Bacteroides_sp_3_1_23		Dorea_formicigenerans	1	
Coprobacillus_sp_D7		Dorea_formicigenerans	1	–
Enterococcus_faecalis		Dorea_formicigenerans	1	++++
Bacteroides_sp_1_1_6		Dorea_longicatena	1	++++
Bacteroides_sp_3_1_23		Dorea_longicatena	1	+++
Clostridium_sp_HGF2		Dorea_longicatena	1	—
Coprobacillus_sp_D7		Dorea_longicatena	1	
Enterococcus_faecalis		Dorea_longicatena	1	++++
Bacteroides_eggerthii		Eubacterium_rectale	1	
Bacteroides_sp_1_1_6		Eubacterium_rectale	1	++++
Bacteroides_sp_3_1_23		Eubacterium_rectale	1	+++
Bifidobacterium_adolescentis		Eubacterium_rectale	1	++++
Bifidobacterium_pseudocatenulatum		Eubacterium_rectale	1	
Clostridium butyricum		Eubacterium_rectale	1	++++
Clostridium orbiscindens		Eubacterium_rectale	1	+
Clostridium_bolteae		Eubacterium_rectale	1	++
Clostridium_disporicum		Eubacterium_rectale	1	++++
Clostridium_hylemonae		Eubacterium_rectale	1	
Clostridium_innocuum		Eubacterium_rectale	1	++++
Clostridium_mayombei		Eubacterium_rectale	1	++++
Clostridium_sp_HGF2		Eubacterium_rectale	1	—
Clostridium_tertium		Eubacterium_rectale	1	++++
Coprobacillus_sp_D7		Eubacterium_rectale	1	+++
Enterococcus_faecalis		Eubacterium_rectale	1	++++
Erysipelotrichaceae_bacterium		Eubacterium_rectale	1	–
Lachnospiraceae_bacterium_5_1_57FAA		Eubacterium_rectale	1	+++
Bacteroides_eggerthii		Faecalibacterium_prausnitzii	1	—
Bacteroides_sp_1_1_6		Faecalibacterium_prausnitzii	1	++++
Bacteroides_sp_1_1_6		Faecalibacterium_prausnitzii	1	+++
Bacteroides_sp_3_1_23		Faecalibacterium_prausnitzii	1	++
Bacteroides_sp_3_1_23		Faecalibacterium_prausnitzii	1	
Bifidobacterium_adolescentis		Faecalibacterium_prausnitzii	1	+
Bifidobacterium_pseudocatenulatum		Faecalibacterium_prausnitzii	1	
Clostridium butyricum		Faecalibacterium_prausnitzii	1	++++
Clostridium orbiscindens		Faecalibacterium_prausnitzii	1	
Clostridium_bolteae		Faecalibacterium_prausnitzii	1	++
Clostridium_disporicum		Faecalibacterium_prausnitzii	1	
Clostridium_hylemonae		Faecalibacterium_prausnitzii	1	
Clostridium_innocuum		Faecalibacterium_prausnitzii	1	++++
Clostridium_mayombei		Faecalibacterium_prausnitzii	1	++++
Clostridium_sp_HGF2		Faecalibacterium_prausnitzii	1	++
Clostridium_sp_HGF2		Faecalibacterium_prausnitzii	1	—
Clostridium_tertium		Faecalibacterium_prausnitzii	1	++++

OTU_1	OTU_1 is a Key Stone	OTU_2	OTU_2 is a Key Stone	C_diff Inhibition Score
Coprobacillus_sp_D7		Faecalibacterium_prausnitzii	1	----
Coprobacillus_sp_D7		Faecalibacterium_prausnitzii	1	
Enterococcus_faecalis		Faecalibacterium_prausnitzii	1	++++
Enterococcus_faecalis		Faecalibacterium_prausnitzii	1	++++
Erysipelotrichaceae_bacterium		Faecalibacterium_prausnitzii	1	--
Lachnospiraceae_bacterium_5_1_57FAA		Faecalibacterium_prausnitzii	1	++++
Bacteroides_eggerthii		Odoribacter_splanchnicus	1	-
Bacteroides_sp_1_1_6		Odoribacter_splanchnicus	1	++++
Bacteroides_sp_1_1_6		Odoribacter_splanchnicus	1	+
Bacteroides_sp_3_1_23		Odoribacter_splanchnicus	1	+
Bacteroides_sp_3_1_23		Odoribacter_splanchnicus	1	
Bifidobacterium_adolescentis		Odoribacter_splanchnicus	1	++++
Bifidobacterium_pseudocatenulatum		Odoribacter_splanchnicus	1	+++
Clostridium_sp_HGF2		Odoribacter_splanchnicus	1	
Clostridium_sp_HGF2		Odoribacter_splanchnicus	1	---
Coprobacillus_sp_D7		Odoribacter_splanchnicus	1	-
Coprobacillus_sp_D7		Odoribacter_splanchnicus	1	+++
Enterococcus_faecalis		Odoribacter_splanchnicus	1	++++
Enterococcus_faecalis		Odoribacter_splanchnicus	1	++++
Erysipelotrichaceae_bacterium		Odoribacter_splanchnicus	1	--
Bacteroides_sp_1_1_6		Parabacteroides_merdae	1	++++
Bacteroides_sp_3_1_23		Parabacteroides_merdae	1	+++
Clostridium_sp_HGF2		Parabacteroides_merdae	1	+++
Coprobacillus_sp_D7		Parabacteroides_merdae	1	-
Enterococcus_faecalis		Parabacteroides_merdae	1	++++
Erysipelotrichaceae_bacterium		Parabacteroides_merdae	1	
Bacteroides_sp_1_1_6		Roseburia_intestinalis	1	++++
Bacteroides_sp_3_1_23		Roseburia_intestinalis	1	+
Clostridium_sp_HGF2		Roseburia_intestinalis	1	---
Coprobacillus_sp_D7		Roseburia_intestinalis	1	-
Enterococcus_faecalis		Roseburia_intestinalis	1	++++
Clostridium butyricum		Ruminococcus_bromii	1	++++
Clostridium orbiscindens		Ruminococcus_bromii	1	
Clostridium_bolteae		Ruminococcus_bromii	1	+++
Clostridium_disporicum		Ruminococcus_bromii	1	
Clostridium_hylemonae		Ruminococcus_bromii	1	
Clostridium_innocuum		Ruminococcus_bromii	1	++++
Clostridium_mayombei		Ruminococcus_bromii	1	++++
Clostridium_tertium		Ruminococcus_bromii	1	++++
Lachnospiraceae_bacterium_5_1_57FAA		Ruminococcus_bromii	1	++++
Bacteroides_sp_1_1_6		Ruminococcus_obeum	1	+++
Bacteroides_sp_3_1_23		Ruminococcus_obeum	1	+++
Clostridium_sp_HGF2		Ruminococcus_obeum	1	---
Coprobacillus_sp_D7		Ruminococcus_obeum	1	+

OTU_1	OTU_1 is a Key Stone	OTU_2	OTU_2 is a Key Stone	1_2diff Inhibition Score
Enterococcus_faecalis		Ruminococcus_obeum	1	++++
Erysipelotrichaceae_bacterium		Ruminococcus_obeum	1	
Bacteroides_eggerthii		Ruminococcus_torques	1	++++
Bacteroides_sp_1_1_6		Ruminococcus_torques	1	++++
Bacteroides_sp_3_1_23		Ruminococcus_torques	1	++++
Clostridium_sp_HGF2		Ruminococcus_torques	1	
Coprobacillus_sp_D7		Ruminococcus_torques	1	++++
Enterococcus_faecalis		Ruminococcus_torques	1	++++
Erysipelotrichaceae_bacterium		Ruminococcus_torques	1	+
Alistipes_shahii	1	Alistipes_shahii	1	
Bacteroides_caccae	1	Alistipes_shahii	1	
Bacteroides_sp_D20	1	Alistipes_shahii	1	–
Clostridium_nexile	1	Alistipes_shahii	1	
Coprococcus_catus	1	Alistipes_shahii	1	–
Coprococcus_comes	1	Alistipes_shahii	1	
Dorea_formicigenerans	1	Alistipes_shahii	1	----
Dorea_longicatena	1	Alistipes_shahii	1	++++
Eubacterium_rectale	1	Alistipes_shahii	1	
Faecalibacterium_prausnitzii	1	Alistipes_shahii	1	
Faecalibacterium_prausnitzii	1	Alistipes_shahii	1	+
Odoribacter_splanchnicus	1	Alistipes_shahii	1	
Odoribacter_splanchnicus	1	Alistipes_shahii	1	
Parabacteroides_merdae	1	Alistipes_shahii	1	
Roseburia_intestinalis	1	Alistipes_shahii	1	–
Ruminococcus_obeum	1	Alistipes_shahii	1	
Ruminococcus_torques	1	Alistipes_shahii	1	
Bacteroides_caccae	1	Bacteroides_caccae	1	++++
Bacteroides_sp_D20	1	Bacteroides_caccae	1	+++
Clostridium_nexile	1	Bacteroides_caccae	1	
Coprococcus_catus	1	Bacteroides_caccae	1	++++
Dorea_formicigenerans	1	Bacteroides_caccae	1	+++
Dorea_longicatena	1	Bacteroides_caccae	1	
Faecalibacterium_prausnitzii	1	Bacteroides_caccae	1	–
Odoribacter_splanchnicus	1	Bacteroides_caccae	1	
Parabacteroides_merdae	1	Bacteroides_caccae	1	+
Roseburia_intestinalis	1	Bacteroides_caccae	1	+
Ruminococcus_obeum	1	Bacteroides_caccae	1	++++
Bacteroides_sp_D20	1	Bacteroides_sp_D20	1	
Clostridium_nexile	1	Bacteroides_sp_D20	1	–
Coprococcus_catus	1	Bacteroides_sp_D20	1	
Dorea_formicigenerans	1	Bacteroides_sp_D20	1	–
Dorea_longicatena	1	Bacteroides_sp_D20	1	
Faecalibacterium_prausnitzii	1	Bacteroides_sp_D20	1	
Odoribacter_splanchnicus	1	Bacteroides_sp_D20	1	

OTU_1	OTU_1 is a key stone	OTU_2	OTU_2 is a key stone	E. coli Inhibition Score
Roseburia_intestinalis	1	Bacteroides_sp_D20	1	–
Clostridium_nexile	1	Clostridium_nexile	1	++
Dorea_formicigenerans	1	Clostridium_nexile	1	
Clostridium_nexile	1	Coprococcus_catus	1	
Coprococcus_catus	1	Coprococcus_catus	1	
Dorea_formicigenerans	1	Coprococcus_catus	1	
Dorea_longicatena	1	Coprococcus_catus	1	
Faecalibacterium_prausnitzii	1	Coprococcus_catus	1	
Odoribacter_splanchnicus	1	Coprococcus_catus	1	
Roseburia_intestinalis	1	Coprococcus_catus	1	
Bacteroides_caccae	1	Coprococcus_comes	1	+++
Bacteroides_sp_D20	1	Coprococcus_comes	1	
Clostridium_nexile	1	Coprococcus_comes	1	
Coprococcus_catus	1	Coprococcus_comes	1	—
Coprococcus_comes	1	Coprococcus_comes	1	
Coprococcus_comes	1	Coprococcus_comes	1	++
Dorea_formicigenerans	1	Coprococcus_comes	1	
Dorea_longicatena	1	Coprococcus_comes	1	
Faecalibacterium_prausnitzii	1	Coprococcus_comes	1	
Odoribacter_splanchnicus	1	Coprococcus_comes	1	
Parabacteroides_merdae	1	Coprococcus_comes	1	–
Roseburia_intestinalis	1	Coprococcus_comes	1	–
Ruminococcus_obeum	1	Coprococcus_comes	1	++++
Ruminococcus_torques	1	Coprococcus_comes	1	++++
Dorea_formicigenerans	1	Dorea_formicigenerans	1	—
Clostridium_nexile	1	Dorea_longicatena	1	
Dorea_formicigenerans	1	Dorea_longicatena	1	++
Dorea_longicatena	1	Dorea_longicatena	1	–
Faecalibacterium_prausnitzii	1	Dorea_longicatena	1	–
Odoribacter_splanchnicus	1	Dorea_longicatena	1	
Bacteroides_caccae	1	Eubacterium_rectale	1	
Bacteroides_sp_D20	1	Eubacterium_rectale	1	—
Clostridium_nexile	1	Eubacterium_rectale	1	–
Coprococcus_catus	1	Eubacterium_rectale	1	—
Coprococcus_comes	1	Eubacterium_rectale	1	+
Coprococcus_comes	1	Eubacterium_rectale	1	++++
Dorea_formicigenerans	1	Eubacterium_rectale	1	–
Dorea_longicatena	1	Eubacterium_rectale	1	++++
Eubacterium_rectale	1	Eubacterium_rectale	1	+++
Eubacterium_rectale	1	Eubacterium_rectale	1	
Faecalibacterium_prausnitzii	1	Eubacterium_rectale	1	—
Faecalibacterium_prausnitzii	1	Eubacterium_rectale	1	
Odoribacter_splanchnicus	1	Eubacterium_rectale	1	–
Parabacteroides_merdae	1	Eubacterium_rectale	1	–

OTU_1	OTU_1 is a Key Stone	OTU_2	OTU_2 is a Key Stone	E. coli Inhibition Score
Roseburia_intestinalis	1	Eubacterium_rectale	1	-------
Ruminococcus_bromii	1	Eubacterium_rectale	1	+
Ruminococcus_obeum	1	Eubacterium_rectale	1	++
Ruminococcus_torques	1	Eubacterium_rectale	1	+
Bacteroides_caccae	1	Faecalibacterium_prausnitzii	1	
Bacteroides_sp_D20	1	Faecalibacterium_prausnitzii	1	—
Clostridium_nexile	1	Faecalibacterium_prausnitzii	1	
Clostridium_nexile	1	Faecalibacterium_prausnitzii	1	–
Coprococcus_catus	1	Faecalibacterium_prausnitzii	1	------
Coprococcus_comes	1	Faecalibacterium_prausnitzii	1	
Coprococcus_comes	1	Faecalibacterium_prausnitzii	1	+++
Dorea_formicigenerans	1	Faecalibacterium_prausnitzii	1	
Dorea_formicigenerans	1	Faecalibacterium_prausnitzii	1	---
Dorea_longicatena	1	Faecalibacterium_prausnitzii	1	+++
Eubacterium_rectale	1	Faecalibacterium_prausnitzii	1	+
Faecalibacterium_prausnitzii	1	Faecalibacterium_prausnitzii	1	+
Faecalibacterium_prausnitzii	1	Faecalibacterium_prausnitzii	1	
Faecalibacterium_prausnitzii	1	Faecalibacterium_prausnitzii	1	+
Faecalibacterium_prausnitzii	1	Faecalibacterium_prausnitzii	1	
Odoribacter_splanchnicus	1	Faecalibacterium_prausnitzii	1	—
Parabacteroides_merdae	1	Faecalibacterium_prausnitzii	1	–
Roseburia_intestinalis	1	Faecalibacterium_prausnitzii	1	
Ruminococcus_obeum	1	Faecalibacterium_prausnitzii	1	
Ruminococcus_torques	1	Faecalibacterium_prausnitzii	1	
Bacteroides_caccae	1	Odoribacter_splanchnicus	1	
Bacteroides_sp_D20	1	Odoribacter_splanchnicus	1	---
Clostridium_nexile	1	Odoribacter_splanchnicus	1	
Clostridium_nexile	1	Odoribacter_splanchnicus	1	------
Coprococcus_catus	1	Odoribacter_splanchnicus	1	—
Coprococcus_comes	1	Odoribacter_splanchnicus	1	
Dorea_formicigenerans	1	Odoribacter_splanchnicus	1	
Dorea_formicigenerans	1	Odoribacter_splanchnicus	1	–
Dorea_longicatena	1	Odoribacter_splanchnicus	1	++++
Eubacterium_rectale	1	Odoribacter_splanchnicus	1	+
Faecalibacterium_prausnitzii	1	Odoribacter_splanchnicus	1	
Faecalibacterium_prausnitzii	1	Odoribacter_splanchnicus	1	--
Faecalibacterium_prausnitzii	1	Odoribacter_splanchnicus	1	+
Odoribacter_splanchnicus	1	Odoribacter_splanchnicus	1	
Odoribacter_splanchnicus	1	Odoribacter_splanchnicus	1	----
Odoribacter_splanchnicus	1	Odoribacter_splanchnicus	1	+
Parabacteroides_merdae	1	Odoribacter_splanchnicus	1	
Roseburia_intestinalis	1	Odoribacter_splanchnicus	1	
Ruminococcus_obeum	1	Odoribacter_splanchnicus	1	+
Ruminococcus_torques	1	Odoribacter_splanchnicus	1	

OTU_1	OTU_1 is a Key Stone	OTU_2	OTU_2 is a Key Stone	E. coli Inhibition Score
Bacteroides_sp_D20	1	Parabacteroides_merdae	1	
Clostridium_nexile	1	Parabacteroides_merdae	1	++
Coprococcus_catus	1	Parabacteroides_merdae	1	+++
Dorea_formicigenerans	1	Parabacteroides_merdae	1	
Dorea_longicatena	1	Parabacteroides_merdae	1	
Faecalibacterium_prausnitzii	1	Parabacteroides_merdae	1	+
Odoribacter_splanchnicus	1	Parabacteroides_merdae	1	
Parabacteroides_merdae	1	Parabacteroides_merdae	1	+++
Roseburia_intestinalis	1	Parabacteroides_merdae	1	
Clostridium_nexile	1	Roseburia_intestinalis	1	--
Dorea_formicigenerans	1	Roseburia_intestinalis	1	
Dorea_longicatena	1	Roseburia_intestinalis	1	-
Faecalibacterium_prausnitzii	1	Roseburia_intestinalis	1	
Odoribacter_splanchnicus	1	Roseburia_intestinalis	1	-
Roseburia_intestinalis	1	Roseburia_intestinalis	1	
Coprococcus_comes	1	Ruminococcus_bromii	1	++++
Eubacterium_rectale	1	Ruminococcus_bromii	1	+
Faecalibacterium_prausnitzii	1	Ruminococcus_bromii	1	
Ruminococcus_bromii	1	Ruminococcus_bromii	1	--
Bacteroides_sp_D20	1	Ruminococcus_obeum	1	
Clostridium_nexile	1	Ruminococcus_obeum	1	-
Coprococcus_catus	1	Ruminococcus_obeum	1	
Dorea_formicigenerans	1	Ruminococcus_obeum	1	++++
Dorea_longicatena	1	Ruminococcus_obeum	1	-
Faecalibacterium_prausnitzii	1	Ruminococcus_obeum	1	
Odoribacter_splanchnicus	1	Ruminococcus_obeum	1	-
Parabacteroides_merdae	1	Ruminococcus_obeum	1	
Roseburia_intestinalis	1	Ruminococcus_obeum	1	
Ruminococcus_obeum	1	Ruminococcus_obeum	1	++++
Bacteroides_caccae	1	Ruminococcus_torques	1	++++
Bacteroides_sp_D20	1	Ruminococcus_torques	1	++
Clostridium_nexile	1	Ruminococcus_torques	1	+
Coprococcus_catus	1	Ruminococcus_torques	1	+
Dorea_formicigenerans	1	Ruminococcus_torques	1	++++
Dorea_longicatena	1	Ruminococcus_torques	1	
Faecalibacterium_prausnitzii	1	Ruminococcus_torques	1	
Odoribacter_splanchnicus	1	Ruminococcus_torques	1	
Parabacteroides_merdae	1	Ruminococcus_torques	1	+
Roseburia_intestinalis	1	Ruminococcus_torques	1	+
Ruminococcus_obeum	1	Ruminococcus_torques	1	++++
Ruminococcus_torques	1	Ruminococcus_torques	1	++++
Bacteroides_ovatus		Alistipes_shahii	1	
Bacteroides_vulgatus		Alistipes_shahii	1	+++
Bacteroides_vulgatus		Alistipes_shahii	1	+

OTU_1	OTU_1 is a Key Stone	OTU_2	OTU_2 is a Key Stone	1_diff Inhibition Score
Blautia_producta		Alistipes_shahii	1	++++
Clostridium_hathewayi		Alistipes_shahii	1	++++
Clostridium_symbiosum		Alistipes_shahii	1	
Collinsella_aerofaciens		Alistipes_shahii	1	++++
Escherichia_coli		Alistipes_shahii	1	++++
Escherichia_coli		Alistipes_shahii	1	++++
Eubacterium_eligens		Alistipes_shahii	1	---
Streptococcus_thermophilus		Alistipes_shahii	1	
Bacteroides_ovatus		Bacteroides_caccae	1	
Bacteroides_vulgatus		Bacteroides_caccae	1	++++
Bacteroides_vulgatus		Bacteroides_caccae	1	+
Blautia_producta		Bacteroides_caccae	1	++++
Collinsella_aerofaciens		Bacteroides_caccae	1	++++
Escherichia_coli		Bacteroides_caccae	1	++++
Escherichia_coli		Bacteroides_caccae	1	++++
Eubacterium_eligens		Bacteroides_caccae	1	++
Streptococcus_thermophilus		Bacteroides_caccae	1	++
Bacteroides_vulgatus		Bacteroides_sp_D20	1	+
Blautia_producta		Bacteroides_sp_D20	1	++++
Escherichia_coli		Bacteroides_sp_D20	1	++++
Eubacterium_eligens		Bacteroides_sp_D20	1	-
Streptococcus_thermophilus		Bacteroides_sp_D20	1	+
Bacteroides_vulgatus		Clostridium_nexile	1	++++
Blautia_producta		Clostridium_nexile	1	++++
Escherichia_coli		Clostridium_nexile	1	++++
Eubacterium_eligens		Clostridium_nexile	1	+
Streptococcus_thermophilus		Clostridium_nexile	1	+
Bacteroides_vulgatus		Coprococcus_catus	1	+
Blautia_producta		Coprococcus_catus	1	++++
Escherichia_coli		Coprococcus_catus	1	++++
Eubacterium_eligens		Coprococcus_catus	1	
Streptococcus_thermophilus		Coprococcus_catus	1	
Bacteroides_ovatus		Coprococcus_comes	1	
Bacteroides_vulgatus		Coprococcus_comes	1	++++
Bacteroides_vulgatus		Coprococcus_comes	1	
Blautia_producta		Coprococcus_comes	1	++++
Clostridium_hathewayi		Coprococcus_comes	1	++++
Collinsella_aerofaciens		Coprococcus_comes	1	++++
Collinsella_aerofaciens		Coprococcus_comes	1	+++
Escherichia_coli		Coprococcus_comes	1	++++
Escherichia_coli		Coprococcus_comes	1	++++
Eubacterium_eligens		Coprococcus_comes	1	++
Streptococcus_thermophilus		Coprococcus_comes	1	++
Bacteroides_vulgatus		Dorea_formicigenerans	1	++

OTU_1	OTU_1 is a key stone	OTU_2	OTU_2 is a key stone	1_2diff Inhibition Score
Escherichia_coli		Dorea_formicigenerans	1	++
Streptococcus_thermophilus		Dorea_formicigenerans	1	
Bacteroides_vulgatus		Dorea_longicatena	1	++++
Blautia_producta		Dorea_longicatena	1	++++
Escherichia_coli		Dorea_longicatena	1	++++
Eubacterium_eligens		Dorea_longicatena	1	++
Streptococcus_thermophilus		Dorea_longicatena	1	+
Bacteroides_ovatus		Eubacterium_rectale	1	
Bacteroides_vulgatus		Eubacterium_rectale	1	++++
Bacteroides_vulgatus		Eubacterium_rectale	1	
Blautia_producta		Eubacterium_rectale	1	++++
Blautia_producta		Eubacterium_rectale	1	++++
Clostridium_hathewayi		Eubacterium_rectale	1	++++
Clostridium_symbiosum		Eubacterium_rectale	1	++
Clostridium_symbiosum		Eubacterium_rectale	1	+
Collinsella_aerofaciens		Eubacterium_rectale	1	++++
Collinsella_aerofaciens		Eubacterium_rectale	1	++++
Escherichia_coli		Eubacterium_rectale	1	++++
Escherichia_coli		Eubacterium_rectale	1	++++
Eubacterium_eligens		Eubacterium_rectale	1	
Ruminococcus_gnavus		Eubacterium_rectale	1	++++
Streptococcus_thermophilus		Eubacterium_rectale	1	
Bacteroides_ovatus		Faecalibacterium_prausnitzii	1	–
Bacteroides_vulgatus		Faecalibacterium_prausnitzii	1	++++
Bacteroides_vulgatus		Faecalibacterium_prausnitzii	1	+++
Bacteroides_vulgatus		Faecalibacterium_prausnitzii	1	–––
Blautia_producta		Faecalibacterium_prausnitzii	1	++++
Blautia_producta		Faecalibacterium_prausnitzii	1	++++
Clostridium_hathewayi		Faecalibacterium_prausnitzii	1	+++
Clostridium_symbiosum		Faecalibacterium_prausnitzii	1	+++
Clostridium_symbiosum		Faecalibacterium_prausnitzii	1	++++
Collinsella_aerofaciens		Faecalibacterium_prausnitzii	1	++++
Collinsella_aerofaciens		Faecalibacterium_prausnitzii	1	++++
Escherichia_coli		Faecalibacterium_prausnitzii	1	++++
Escherichia_coli		Faecalibacterium_prausnitzii	1	++++
Escherichia_coli		Faecalibacterium_prausnitzii	1	++
Eubacterium_eligens		Faecalibacterium_prausnitzii	1	
Eubacterium_eligens		Faecalibacterium_prausnitzii	1	
Streptococcus_thermophilus		Faecalibacterium_prausnitzii	1	
Streptococcus_thermophilus		Faecalibacterium_prausnitzii	1	
Bacteroides_ovatus		Odoribacter_splanchnicus	1	––
Bacteroides_vulgatus		Odoribacter_splanchnicus	1	+++
Bacteroides_vulgatus		Odoribacter_splanchnicus	1	+++
Bacteroides_vulgatus		Odoribacter_splanchnicus	1	–

OTU_1	OTU_1 is a Key Stone	OTU_2	OTU_2 is a Key Stone	E. coli Inhibition Score
Blautia_producta		Odoribacter_splanchnicus	1	++++
Blautia_producta		Odoribacter_splanchnicus	1	++++
Clostridium_hathewayi		Odoribacter_splanchnicus	1	++++
Clostridium_symbiosum		Odoribacter_splanchnicus	1	++
Collinsella_aerofaciens		Odoribacter_splanchnicus	1	++++
Escherichia_coli		Odoribacter_splanchnicus	1	++++
Escherichia_coli		Odoribacter_splanchnicus	1	++++
Escherichia_coli		Odoribacter_splanchnicus	1	++++
Eubacterium_eligens		Odoribacter_splanchnicus	1	
Eubacterium_eligens		Odoribacter_splanchnicus	1	
Streptococcus_thermophilus		Odoribacter_splanchnicus	1	
Streptococcus_thermophilus		Odoribacter_splanchnicus	1	+
Bacteroides_ovatus		Parabacteroides_merdae	1	
Bacteroides_vulgatus		Parabacteroides_merdae	1	++++
Blautia_producta		Parabacteroides_merdae	1	++++
Escherichia_coli		Parabacteroides_merdae	1	++++
Eubacterium_eligens		Parabacteroides_merdae	1	
Streptococcus_thermophilus		Parabacteroides_merdae	1	
Bacteroides_vulgatus		Roseburia_intestinalis	1	+
Blautia_producta		Roseburia_intestinalis	1	++++
Escherichia_coli		Roseburia_intestinalis	1	++++
Eubacterium_eligens		Roseburia_intestinalis	1	
Streptococcus_thermophilus		Roseburia_intestinalis	1	
Blautia_producta		Ruminococcus_bromii	1	++++
Clostridium_symbiosum		Ruminococcus_bromii	1	++++
Collinsella_aerofaciens		Ruminococcus_bromii	1	++++
Ruminococcus_gnavus		Ruminococcus_bromii	1	++++
Bacteroides_ovatus		Ruminococcus_obeum	1	
Bacteroides_vulgatus		Ruminococcus_obeum	1	++++
Bacteroides_vulgatus		Ruminococcus_obeum	1	
Blautia_producta		Ruminococcus_obeum	1	++++
Collinsella_aerofaciens		Ruminococcus_obeum	1	++++
Escherichia_coli		Ruminococcus_obeum	1	+++
Escherichia_coli		Ruminococcus_obeum	1	++++
Eubacterium_eligens		Ruminococcus_obeum	1	+
Streptococcus_thermophilus		Ruminococcus_obeum	1	+++
Bacteroides_ovatus		Ruminococcus_torques	1	++++
Bacteroides_vulgatus		Ruminococcus_torques	1	++++
Bacteroides_vulgatus		Ruminococcus_torques	1	++++
Blautia_producta		Ruminococcus_torques	1	++++
Collinsella_aerofaciens		Ruminococcus_torques	1	++++
Escherichia_coli		Ruminococcus_torques	1	++++
Escherichia_coli		Ruminococcus_torques	1	++++
Eubacterium_eligens		Ruminococcus_torques	1	++

OTU_1	OTU_1 is a Key Stone	OTU_2	OTU_2 is a Key Stone	1_diff Inhibition Score
Streptococcus_thermophilus		Ruminococcus_torques	1	+
Bacteroides_sp_D20	1	Bacteroides_ovatus		–
Clostridium_nexile	1	Bacteroides_ovatus		
Coprococcus_catus	1	Bacteroides_ovatus		
Dorea_formicigenerans	1	Bacteroides_ovatus		
Dorea_longicatena	1	Bacteroides_ovatus		–
Faecalibacterium_prausnitzii	1	Bacteroides_ovatus		
Odoribacter_splanchnicus	1	Bacteroides_ovatus		
Roseburia_intestinalis	1	Bacteroides_ovatus		
Bacteroides_sp_D20	1	Bacteroides_vulgatus		
Clostridium_nexile	1	Bacteroides_vulgatus		
Coprococcus_catus	1	Bacteroides_vulgatus		++
Dorea_formicigenerans	1	Bacteroides_vulgatus		
Dorea_longicatena	1	Bacteroides_vulgatus		
Faecalibacterium_prausnitzii	1	Bacteroides_vulgatus		
Odoribacter_splanchnicus	1	Bacteroides_vulgatus		
Parabacteroides_merdae	1	Bacteroides_vulgatus		+
Roseburia_intestinalis	1	Bacteroides_vulgatus		
Alistipes_shahii	1	Blautia_producta		
Bacteroides_caccae	1	Blautia_producta		+
Bacteroides_sp_D20	1	Blautia_producta		
Clostridium_nexile	1	Blautia_producta		–
Coprococcus_catus	1	Blautia_producta		–––
Coprococcus_comes	1	Blautia_producta		
Coprococcus_comes	1	Blautia_producta		++++
Dorea_formicigenerans	1	Blautia_producta		++++
Dorea_formicigenerans	1	Blautia_producta		----
Dorea_longicatena	1	Blautia_producta		+++
Eubacterium_rectale	1	Blautia_producta		+
Faecalibacterium_prausnitzii	1	Blautia_producta		
Faecalibacterium_prausnitzii	1	Blautia_producta		+
Faecalibacterium_prausnitzii	1	Blautia_producta		++++
Odoribacter_splanchnicus	1	Blautia_producta		–
Odoribacter_splanchnicus	1	Blautia_producta		+
Parabacteroides_merdae	1	Blautia_producta		+++
Roseburia_intestinalis	1	Blautia_producta		----
Ruminococcus_obeum	1	Blautia_producta		
Ruminococcus_torques	1	Blautia_producta		
Bacteroides_caccae	1	Clostridium_hathewayi		++++
Bacteroides_sp_D20	1	Clostridium_hathewayi		++++
Clostridium_nexile	1	Clostridium_hathewayi		
Coprococcus_catus	1	Clostridium_hathewayi		+++
Dorea_formicigenerans	1	Clostridium_hathewayi		++++
Dorea_longicatena	1	Clostridium_hathewayi		+

OTU_1	OTU_1 is a Key Stone	OTU_2	OTU_2 is a Key Stone	E. coli Inhibition Score
Faecalibacterium_prausnitzii	1	Clostridium_hathewayi		
Odoribacter_splanchnicus	1	Clostridium_hathewayi		
Parabacteroides_merdae	1	Clostridium_hathewayi		+
Roseburia_intestinalis	1	Clostridium_hathewayi		+++
Ruminococcus_obeum	1	Clostridium_hathewayi		++++
Ruminococcus_torques	1	Clostridium_hathewayi		++++
Bacteroides_caccae	1	Clostridium_symbiosum		+++
Bacteroides_sp_D20	1	Clostridium_symbiosum		
Clostridium_nexile	1	Clostridium_symbiosum		+
Coprococcus_catus	1	Clostridium_symbiosum		--
Coprococcus_comes	1	Clostridium_symbiosum		
Coprococcus_comes	1	Clostridium_symbiosum		++++
Dorea_formicigenerans	1	Clostridium_symbiosum		
Dorea_longicatena	1	Clostridium_symbiosum		++++
Faecalibacterium_prausnitzii	1	Clostridium_symbiosum		
Odoribacter_splanchnicus	1	Clostridium_symbiosum		
Parabacteroides_merdae	1	Clostridium_symbiosum		-
Roseburia_intestinalis	1	Clostridium_symbiosum		----
Ruminococcus_obeum	1	Clostridium_symbiosum		++++
Ruminococcus_torques	1	Clostridium_symbiosum		++
Bacteroides_sp_D20	1	Collinsella_aerofaciens		++++
Clostridium_nexile	1	Collinsella_aerofaciens		+
Coprococcus_catus	1	Collinsella_aerofaciens		++++
Dorea_formicigenerans	1	Collinsella_aerofaciens		++
Dorea_longicatena	1	Collinsella_aerofaciens		++++
Faecalibacterium_prausnitzii	1	Collinsella_aerofaciens		+++
Odoribacter_splanchnicus	1	Collinsella_aerofaciens		+++
Parabacteroides_merdae	1	Collinsella_aerofaciens		++++
Roseburia_intestinalis	1	Collinsella_aerofaciens		++
Bacteroides_sp_D20	1	Escherichia_coli		++++
Clostridium_nexile	1	Escherichia_coli		++++
Coprococcus_catus	1	Escherichia_coli		++++
Dorea_formicigenerans	1	Escherichia_coli		++++
Dorea_longicatena	1	Escherichia_coli		++++
Faecalibacterium_prausnitzii	1	Escherichia_coli		+++
Odoribacter_splanchnicus	1	Escherichia_coli		+++
Parabacteroides_merdae	1	Escherichia_coli		++++
Roseburia_intestinalis	1	Escherichia_coli		+++
Dorea_formicigenerans	1	Eubacterium_eligens		--
Coprococcus_comes	1	Ruminococcus_gnavus		++++
Faecalibacterium_prausnitzii	1	Ruminococcus_gnavus		++++
Ruminococcus_bromii	1	Ruminococcus_gnavus		++++

Table 21

Functional Network Ecologies comprised of two or more OTUs that are observed in the ethanol-treated spore preparation or the combined engrafted and augmented ecologies of at least one patient post-treatment with the bacterial composition. Network Ecology IDs with a ".s" indicates that the network is a subset of the computationally determined networks reported in Table 8 with the same Network Ecology ID.

Net ID	# Nodes	KEGG Orthology Pathways
N968.S	16	KO:K00101, KO:K00116, KO:K00156, KO:K00163, KO:K00627, KO:K00656, KO:K00932, KO:K01069, KO:K01659, KO:K01720, KO:K01734, KO:K01908, KO:K03417, KO:K03777, KO:K03778, KO:K04020
N282.S	12	KO:K00004, KO:K00158, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03366, KO:K03778
N390.S	11	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778, KO:K04020
N515.S	11	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778, KO:K04020
N516.S	11	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778, KO:K04020
N586	11	KO:K00102, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K01905, KO:K03778
N590.S	11	KO:K00004, KO:K00158, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03366, KO:K03778
N666.S	11	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778, KO:K04020
N271.S	10	KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03366, KO:K03778
N338.S	10	KO:K00158, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N368.S	10	KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03366, KO:K03778
N381.S	10	KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778, KO:K10783
N382.S	10	KO:K00102, KO:K00627, KO:K00634, KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K01905, KO:K03417, KO:K07246
N519.S	10	KO:K00004, KO:K00158, KO:K00627, KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03366, KO:K03778
N535.S	10	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01067, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N597.S	10	KO:K00158, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N680.S	10	KO:K00102, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K01905, KO:K03778
N822.S	10	KO:K00004, KO:K00158, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03366, KO:K03778
N1008	9	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01659, KO:K01734, KO:K03778, KO:K04020
N329.S	9	KO:K00102, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778

N332.S	9	KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N346.S	9	KO:K00116, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N353.S	9	KO:K00634, KO:K00656, KO:K00929, KO:K01067, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N361.S	9	KO:K00116, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N375.S	9	KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N377.S	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N380.S	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N387.S	9	KO:K00102, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N396.S	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N397.S	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N415.S	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N419.S	9	KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03366, KO:K03778
N431.S	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N434.S	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N440.S	9	KO:K00627, KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03417, KO:K03778, KO:K07246
N447.S	9	KO:K00634, KO:K00656, KO:K00929, KO:K01067, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N458.S	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N459.S	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N481.S	9	KO:K00102, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N526	9	KO:K00004, KO:K00116, KO:K00163, KO:K00627, KO:K00634, KO:K00656, KO:K01442, KO:K01659, KO:K01734
N530.S	9	KO:K00158, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N534.S	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N591.S	9	KO:K00004, KO:K00158, KO:K00627, KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03366, KO:K03778
N682.S	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N816.S	9	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734,

		KO:K03778
N891.S	9	KO:K00102, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K01905, KO:K03778
N1091	8	KO:K00156, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734
N1093	8	KO:K00156, KO:K00627, KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N262.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N279.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N284.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N288.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N290.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N301.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N302.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N310.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N312.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N323.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N325.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N331.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N336.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N339.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N340.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N341.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N343.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N344.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N345.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N352.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N355.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N356.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N357.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N358.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N369.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N370.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N372.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N373.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N374.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N376.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N386.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N389.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N394.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N400.S	8	KO:K00634, KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03417, KO:K07246
N405.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N408.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N422.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N423.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N429.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N430.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N432.S	8	KO:K00627, KO:K00634, KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N437.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N450.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778

N477.S	8	KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N478.S	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N482.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N490.S	8	KO:K00158, KO:K00627, KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N493.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N509.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N543.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N547.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N582.S	8	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03417, KO:K03778, KO:K07246
N584.S	8	KO:K00102, KO:K00634, KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03417, KO:K07246
N651.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N655.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N656.S	8	KO:K00156, KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N657.S	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N664	8	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778, KO:K10783
N667.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N675.S	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N693	8	KO:K00004, KO:K00158, KO:K00627, KO:K00634, KO:K00656, KO:K01442, KO:K01734, KO:K03366
N698.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N712.S	8	KO:K00102, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N714.S	8	KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N734.S	8	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01734, KO:K03778, KO:K04020
N782.S	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N789.S	8	KO:K00156, KO:K00163, KO:K00627, KO:K00656, KO:K01067, KO:K01069, KO:K01442, KO:K01734
N792	8	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778, KO:K10783
N794	8	KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N817.S	8	KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N844	8	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K04020
N851.S	8	KO:K00102, KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01734, KO:K04020
N876	8	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N1051	7	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01659, KO:K01734, KO:K03778
N402.S	7	KO:K00634, KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N403.S	7	KO:K00634, KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N414.S	7	KO:K00634, KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N416.S	7	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N433.S	7	KO:K00634, KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N448.S	7	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N451.S	7	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N460.S	7	KO:K00634, KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N462.S	7	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N466.S	7	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N470.S	7	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N479.S	7	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N480.S	7	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N484.S	7	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N511.S	7	KO:K00634, KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N518.S	7	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N520.S	7	KO:K00627, KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778

N524.S	7	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N542.S	7	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N580.S	7	KO:K00158, KO:K00627, KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N587.S	7	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778, KO:K10783
N611.S	7	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N612.S	7	KO:K00627, KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03366, KO:K03778
N625.S	7	KO:K00627, KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03366
N649.S	7	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N685.S	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N686.S	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N687	7	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N733.S	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N739.S	7	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N777.S	7	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N785	7	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N788	7	KO:K00116, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01734, KO:K10783
N793.S	7	KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734
N795.S	7	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778, KO:K10783
N798.S	7	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N804	7	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N807	7	KO:K00043, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N815.S	7	KO:K00102, KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N829	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N836.S	7	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N846	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N875	7	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01659, KO:K01734
N894	7	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N898.S	7	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N913.S	7	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01734, KO:K03417, KO:K07246
N935	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N936.S	7	KO:K00156, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N945.S	7	KO:K00102, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N961	7	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N972	7	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N988	7	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N995.S	7	KO:K00627, KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N1002.S	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N1019.S	6	KO:K00156, KO:K00656, KO:K01067, KO:K01069, KO:K01659, KO:K01734
N1023	6	KO:K00627, KO:K00656, KO:K01442, KO:K01734, KO:K03366, KO:K03778
N1070.S	6	KO:K00634, KO:K00656, KO:K00929, KO:K01069, KO:K01442, KO:K01734
N399.S	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N421.S	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N436.S	6	KO:K00634, KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N439.S	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N441.S	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N446.S	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N457.S	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N464.S	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778

N465.S	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N468.S	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N469.S	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N474.S	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N488.S	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N508.S	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N510.S	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N512.S	6	KO:K00634, KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N514.S	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N517.S	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N521.S	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N522.S	6	KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03417, KO:K07246
N523.S	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N525.S	6	KO:K00043, KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N528.S	6	KO:K00656, KO:K01069, KO:K01734, KO:K03417, KO:K03778, KO:K07246
N537.S	6	KO:K00102, KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N539.S	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N546.S	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N548.S	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N572.S	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N577.S	6	KO:K00627, KO:K00634, KO:K00656, KO:K01442, KO:K01734, KO:K03778
N581.S	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N602.S	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N614.S	6	KO:K00627, KO:K00656, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N617.S	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N621.S	6	KO:K00043, KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734
N652.S	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N654.S	6	KO:K00116, KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734
N668.S	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N678.S	6	KO:K00156, KO:K00627, KO:K00656, KO:K01069, KO:K01659, KO:K01734
N681.S	6	KO:K00634, KO:K00656, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N710.S	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N741.S	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N769	6	KO:K00102, KO:K00656, KO:K01069, KO:K01659, KO:K01734, KO:K03778
N779	6	KO:K00158, KO:K00627, KO:K00656, KO:K01442, KO:K01659, KO:K01734
N796.S	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N826.S	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N827.S	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N828	6	KO:K00158, KO:K00627, KO:K00634, KO:K00656, KO:K01442, KO:K01734
N832.S	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N840.S	6	KO:K00627, KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03366
N843.S	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N845	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N849	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N858	6	KO:K00043, KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N878	6	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N928.S	6	KO:K00634, KO:K00929, KO:K01067, KO:K01442, KO:K01734, KO:K03778
N960.S	6	KO:K00634, KO:K00656, KO:K00929, KO:K01442, KO:K01734, KO:K03778

N1061	5	KO:K00656, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N463.S	5	KO:K00656, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N529.S	5	KO:K00656, KO:K01069, KO:K01659, KO:K01734, KO:K03778
N533.S	5	KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N545	5	KO:K00634, KO:K00656, KO:K01442, KO:K01659, KO:K01734
N570.S	5	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734
N574.S	5	KO:K00627, KO:K00656, KO:K01442, KO:K01659, KO:K01734
N578.S	5	KO:K00656, KO:K01069, KO:K01659, KO:K01734, KO:K03778
N579.S	5	KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N585.S	5	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734
N589.S	5	KO:K00656, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N609.S	5	KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N610.S	5	KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N616.S	5	KO:K00634, KO:K00656, KO:K01442, KO:K01659, KO:K01734
N623.S	5	KO:K00656, KO:K01069, KO:K01442, KO:K01659, KO:K01734
N648.S	5	KO:K00656, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N653.S	5	KO:K00043, KO:K00656, KO:K01069, KO:K01442, KO:K01734
N665.S	5	KO:K00656, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N672.S	5	KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N689	5	KO:K00634, KO:K00656, KO:K01442, KO:K01734, KO:K10783
N730	5	KO:K00634, KO:K00656, KO:K01442, KO:K01734, KO:K03778
N737.S	5	KO:K00656, KO:K01069, KO:K01442, KO:K01734, KO:K03778
N797.S	5	KO:K00627, KO:K00656, KO:K01659, KO:K01734, KO:K03366
N800.S	5	KO:K00627, KO:K00656, KO:K01069, KO:K01442, KO:K01734
N802	5	KO:K00043, KO:K00627, KO:K00656, KO:K01442, KO:K01734
N830.S	5	KO:K00627, KO:K00634, KO:K00656, KO:K01442, KO:K01734
N833.S	5	KO:K00102, KO:K00634, KO:K00656, KO:K01442, KO:K01734
N835.S	5	KO:K00634, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N841	5	KO:K00656, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N842.S	5	KO:K00634, KO:K00929, KO:K01442, KO:K01734, KO:K03778
N852	5	KO:K00656, KO:K01442, KO:K01659, KO:K01734, KO:K03778
N859	5	KO:K00102, KO:K00656, KO:K01069, KO:K01734, KO:K03778
N860	5	KO:K00627, KO:K00656, KO:K01069, KO:K01734, KO:K03778
N880	5	KO:K00634, KO:K00656, KO:K01069, KO:K01442, KO:K01734
N885	5	KO:K00043, KO:K00656, KO:K01442, KO:K01659, KO:K01734
N925	5	KO:K00158, KO:K00627, KO:K00656, KO:K01442, KO:K01734
N983	5	KO:K00627, KO:K00656, KO:K01442, KO:K01734, KO:K03366
N1004.S	4	KO:K00656, KO:K01069, KO:K01734, KO:K03778
N1078.S	4	KO:K00158, KO:K00627, KO:K00656, KO:K01069
N1088	4	KO:K00656, KO:K01069, KO:K01442, KO:K01734
N538.S	4	KO:K00656, KO:K01069, KO:K01734, KO:K03778
N604.S	4	KO:K00656, KO:K01659, KO:K01734, KO:K03778
N669.S	4	KO:K00634, KO:K00656, KO:K01442, KO:K01734
N676.S	4	KO:K00656, KO:K01069, KO:K01734, KO:K03778
N690.S	4	KO:K00634, KO:K00656, KO:K01442, KO:K01734
N692.S	4	KO:K00634, KO:K00656, KO:K01442, KO:K01734
N695.S	4	KO:K00116, KO:K00656, KO:K01442, KO:K01734
N709	4	KO:K00634, KO:K00656, KO:K01442, KO:K01734

N738.S	4	KO:K00656, KO:K01659, KO:K01734, KO:K03778
N775.S	4	KO:K00634, KO:K00656, KO:K01442, KO:K01734
N776.S	4	KO:K00116, KO:K00656, KO:K01442, KO:K01734
N780.S	4	KO:K00656, KO:K01442, KO:K01659, KO:K01734
N781	4	KO:K00656, KO:K01069, KO:K01442, KO:K01734
N808.S	4	KO:K00656, KO:K01069, KO:K01734, KO:K10783
N809.S	4	KO:K00656, KO:K01069, KO:K01659, KO:K01734
N811.S	4	KO:K00116, KO:K00656, KO:K01069, KO:K01734
N869.S	4	KO:K00627, KO:K00656, KO:K01442, KO:K01734
N871.S	4	KO:K00656, KO:K01442, KO:K01659, KO:K01734
N881	4	KO:K00656, KO:K01442, KO:K01659, KO:K01734
N907.S	4	KO:K00656, KO:K01442, KO:K01659, KO:K01734
N927	4	KO:K00656, KO:K01067, KO:K01442, KO:K01734
N942	4	KO:K00102, KO:K00656, KO:K01442, KO:K01734
N947	4	KO:K00627, KO:K00656, KO:K01442, KO:K01734
N982	4	KO:K00634, KO:K00656, KO:K01442, KO:K01734
N986.S	4	KO:K00656, KO:K01442, KO:K01734, KO:K03778
N987	4	KO:K00634, KO:K00656, KO:K01442, KO:K01734
N998.S	4	KO:K00656, KO:K01442, KO:K01659, KO:K01734
N1089	3	KO:K00656, KO:K01659, KO:K01734
N663.S	3	KO:K00656, KO:K01442, KO:K01734
N703.S	3	KO:K00656, KO:K01659, KO:K01734
N805.S	3	KO:K00656, KO:K01069, KO:K01442
N874.S	3	KO:K00656, KO:K01442, KO:K01734
N996	3	KO:K00656, KO:K01442, KO:K01734
N1092	2	KO:K01442, KO:K01734
N660.S	2	KO:K00656, KO:K01442

Table 22

Phylogenetic clades with alternative embodiments

Phylogenetic Clade	OTUs in clade
clade_172	Bifidobacteriaceae genomosp. C1, Bifidobacterium adolescentis, Bifidobacterium angulatum, Bifidobacterium animalis, Bifidobacterium breve, Bifidobacterium catenulatum, Bifidobacterium dentium, Bifidobacterium gallicum, Bifidobacterium infantis, Bifidobacterium kashiwanohense, Bifidobacterium longum, Bifidobacterium pseudocatenulatum, Bifidobacterium pseudolongum, Bifidobacterium scardovii, Bifidobacterium sp. HM2, Bifidobacterium sp. HMLN12, Bifidobacterium sp. M45, Bifidobacterium sp. MSX5B, Bifidobacterium sp. TM_7, Bifidobacterium thermophilum
clade_172i	Bifidobacteriaceae genomosp. C1, Bifidobacterium angulatum, Bifidobacterium animalis, Bifidobacterium breve, Bifidobacterium catenulatum, Bifidobacterium dentium, Bifidobacterium gallicum, Bifidobacterium infantis, Bifidobacterium kashiwanohense, Bifidobacterium pseudocatenulatum, Bifidobacterium pseudolongum, Bifidobacterium scardovii, Bifidobacterium sp. HM2, Bifidobacterium sp. HMLN12, Bifidobacterium sp. M45, Bifidobacterium sp. MSX5B, Bifidobacterium sp. TM_7, Bifidobacterium thermophilum
clade_198	Lactobacillus casei, Lactobacillus paracasei, Lactobacillus zeae
clade_198i	Lactobacillus zeae

clade_260	Clostridium hylemonae, Clostridium scindens, Lachnospiraceae bacterium 5_1_57FAA
clade_260c	Clostridium hylemonae, Lachnospiraceae bacterium 5_1_57FAA
clade_260g	Clostridium hylemonae, Lachnospiraceae bacterium 5_1_57FAA
clade_260h	Clostridium hylemonae, Lachnospiraceae bacterium 5_1_57FAA
clade_262	Clostridium glycyrrhizinilyticum, Clostridium nexile, Coprococcus comes, Lachnospiraceae bacterium 1_1_57FAA, Lachnospiraceae bacterium 1_4_56FAA, Lachnospiraceae bacterium 8_1_57FAA, Ruminococcus lactaris, Ruminococcus torques
clade_262i	Clostridium glycyrrhizinilyticum, Clostridium nexile, Coprococcus comes, Lachnospiraceae bacterium 1_1_57FAA, Lachnospiraceae bacterium 1_4_56FAA, Lachnospiraceae bacterium 8_1_57FAA, Ruminococcus lactaris
clade_309	Blautia coccoides, Blautia glucerasea, Blautia glucerasei, Blautia hansenii, Blautia luti, Blautia producta, Blautia schinkii, Blautia sp. M25, Blautia stercoris, Blautia wexlerae, Bryantella formatexigens, Clostridium coccoides, Eubacterium cellulosolvens, Lachnospiraceae bacterium 6_1_63FAA, Marvinbryantia formatexigens, Ruminococcus hansenii, Ruminococcus obeum, Ruminococcus sp. 5_1_39BFAA, Ruminococcus sp. K_1, Syntrophococcus sucromutans
clade_309c	Blautia coccoides, Blautia glucerasea, Blautia glucerasei, Blautia hansenii, Blautia luti, Blautia schinkii, Blautia sp. M25, Blautia stercoris, Blautia wexlerae, Bryantella formatexigens, Clostridium coccoides, Eubacterium cellulosolvens, Lachnospiraceae bacterium 6_1_63FAA, Marvinbryantia formatexigens, Ruminococcus hansenii, Ruminococcus obeum, Ruminococcus sp. 5_1_39BFAA, Ruminococcus sp. K_1, Syntrophococcus sucromutans
clade_309e	Blautia coccoides, Blautia glucerasea, Blautia glucerasei, Blautia hansenii, Blautia luti, Blautia schinkii, Blautia sp. M25, Blautia stercoris, Blautia wexlerae, Bryantella formatexigens, Clostridium coccoides, Eubacterium cellulosolvens, Lachnospiraceae bacterium 6_1_63FAA, Marvinbryantia formatexigens, Ruminococcus hansenii, Ruminococcus obeum, Ruminococcus sp. 5_1_39BFAA, Ruminococcus sp. K_1, Syntrophococcus sucromutans
clade_309g	Blautia coccoides, Blautia glucerasea, Blautia glucerasei, Blautia hansenii, Blautia luti, Blautia schinkii, Blautia sp. M25, Blautia stercoris, Blautia wexlerae, Bryantella formatexigens, Clostridium coccoides, Eubacterium cellulosolvens, Lachnospiraceae bacterium 6_1_63FAA, Marvinbryantia formatexigens, Ruminococcus hansenii, Ruminococcus obeum, Ruminococcus sp. 5_1_39BFAA, Ruminococcus sp. K_1, Syntrophococcus sucromutans
clade_309h	Blautia coccoides, Blautia glucerasea, Blautia glucerasei, Blautia hansenii, Blautia luti, Blautia schinkii, Blautia sp. M25, Blautia stercoris, Blautia wexlerae, Bryantella formatexigens, Clostridium coccoides, Eubacterium cellulosolvens, Lachnospiraceae bacterium 6_1_63FAA, Marvinbryantia formatexigens, Ruminococcus hansenii, Ruminococcus obeum, Ruminococcus sp. 5_1_39BFAA, Ruminococcus sp. K_1, Syntrophococcus sucromutans
clade_309i	Blautia coccoides, Blautia glucerasea, Blautia glucerasei, Blautia hansenii, Blautia luti, Blautia schinkii, Blautia sp. M25, Blautia stercoris, Blautia wexlerae, Bryantella formatexigens, Clostridium coccoides, Eubacterium cellulosolvens, Lachnospiraceae bacterium 6_1_63FAA, Marvinbryantia formatexigens, Ruminococcus hansenii, Ruminococcus sp. 5_1_39BFAA, Ruminococcus sp. K_1, Syntrophococcus sucromutans
clade_313	Lactobacillus antri, Lactobacillus coleohominis, Lactobacillus fermentum, Lactobacillus gastricus, Lactobacillus mucosae, Lactobacillus oris, Lactobacillus pontis, Lactobacillus reuteri, Lactobacillus sp. KLDS 1.0707, Lactobacillus sp. KLDS 1.0709, Lactobacillus sp. KLDS 1.0711, Lactobacillus sp. KLDS 1.0713, Lactobacillus sp. KLDS 1.0716, Lactobacillus sp. KLDS 1.0718, Lactobacillus sp. oral taxon 052, Lactobacillus vaginalis
clade_313f	Lactobacillus antri, Lactobacillus coleohominis, Lactobacillus fermentum, Lactobacillus gastricus, Lactobacillus mucosae, Lactobacillus oris, Lactobacillus pontis, Lactobacillus sp. KLDS 1.0707, Lactobacillus sp. KLDS 1.0709, Lactobacillus sp. KLDS 1.0711, Lactobacillus sp. KLDS 1.0713, Lactobacillus sp. KLDS 1.0716, Lactobacillus sp. KLDS 1.0718, Lactobacillus sp. oral taxon 052, Lactobacillus vaginalis
clade_325	Staphylococcus aureus, Staphylococcus auricularis, Staphylococcus capitis, Staphylococcus caprae, Staphylococcus carnosus, Staphylococcus cohnii, Staphylococcus condimenti, Staphylococcus epidermidis, Staphylococcus equorum, Staphylococcus haemolyticus, Staphylococcus hominis, Staphylococcus lugdunensis, Staphylococcus pasteuri, Staphylococcus pseudintermedius, Staphylococcus saccharolyticus, Staphylococcus saprophyticus, Staphylococcus sp. H292, Staphylococcus sp. H780, Staphylococcus sp. clone bottae7, Staphylococcus succinus, Staphylococcus warneri, Staphylococcus xylosus

clade_325f	Staphylococcus aureus, Staphylococcus auricularis, Staphylococcus capitis, Staphylococcus caprae, Staphylococcus carnosus, Staphylococcus cohnii, Staphylococcus condimenti, Staphylococcus epidermidis, Staphylococcus equorum, Staphylococcus haemolyticus, Staphylococcus hominis, Staphylococcus lugdunensis, Staphylococcus pseudintermedius, Staphylococcus saccharolyticus, Staphylococcus saprophyticus, Staphylococcus sp. H292, Staphylococcus sp. H780, Staphylococcus sp. clone bottae7, Staphylococcus succinus, Staphylococcus xylosus
clade_335	Bacteroides sp. 20_3, Bacteroides sp. 3_1_19, Bacteroides sp. 3_2_5, Parabacteroides distasonis, Parabacteroides goldsteinii, Parabacteroides gordonii, Parabacteroides sp. D13
clade_335i	Bacteroides sp. 20_3, Bacteroides sp. 3_1_19, Bacteroides sp. 3_2_5, Parabacteroides goldsteinii, Parabacteroides gordonii, Parabacteroides sp. D13
clade_351	Clostridium innocuum, Clostridium sp. HGF2
clade_351e	Clostridium sp. HGF2
clade_354	Clostridium bartlettii, Clostridium bifermentans, Clostridium ghonii, Clostridium glycolicum, Clostridium mayombei, Clostridium sordellii, Clostridium sp. MT4 E, Eubacterium tenue
clade_354e	Clostridium bartlettii, Clostridium ghonii, Clostridium glycolicum, Clostridium mayombei, Clostridium sordellii, Clostridium sp. MT4 E, Eubacterium tenue
clade_360	Dorea formicigenerans, Dorea longicatena, Lachnospiraceae bacterium 2_1_46FAA, Lachnospiraceae bacterium 2_1_58FAA, Lachnospiraceae bacterium 4_1_37FAA, Lachnospiraceae bacterium 9_1_43BFAA, Ruminococcus gnavus, Ruminococcus sp. ID8
clade_360c	Dorea formicigenerans, Dorea longicatena, Lachnospiraceae bacterium 2_1_46FAA, Lachnospiraceae bacterium 2_1_58FAA, Lachnospiraceae bacterium 4_1_37FAA, Lachnospiraceae bacterium 9_1_43BFAA, Ruminococcus gnavus
clade_360g	Dorea formicigenerans, Dorea longicatena, Lachnospiraceae bacterium 2_1_46FAA, Lachnospiraceae bacterium 2_1_58FAA, Lachnospiraceae bacterium 4_1_37FAA, Lachnospiraceae bacterium 9_1_43BFAA, Ruminococcus gnavus
clade_360h	Dorea formicigenerans, Dorea longicatena, Lachnospiraceae bacterium 2_1_46FAA, Lachnospiraceae bacterium 2_1_58FAA, Lachnospiraceae bacterium 4_1_37FAA, Lachnospiraceae bacterium 9_1_43BFAA, Ruminococcus gnavus
clade_360i	Dorea formicigenerans, Lachnospiraceae bacterium 2_1_46FAA, Lachnospiraceae bacterium 2_1_58FAA, Lachnospiraceae bacterium 4_1_37FAA, Lachnospiraceae bacterium 9_1_43BFAA, Ruminococcus gnavus, Ruminococcus sp. ID8
clade_378	Bacteroides barnesiae, Bacteroides coprocola, Bacteroides coprophilus, Bacteroides dorei, Bacteroides massiliensis, Bacteroides plebeius, Bacteroides sp. 3_1_33FAA, Bacteroides sp. 3_1_40A, Bacteroides sp. 4_3_47FAA, Bacteroides sp. 9_1_42FAA, Bacteroides sp. NB_8, Bacteroides vulgatus
clade_378e	Bacteroides barnesiae, Bacteroides coprocola, Bacteroides coprophilus, Bacteroides dorei, Bacteroides massiliensis, Bacteroides plebeius, Bacteroides sp. 3_1_33FAA, Bacteroides sp. 3_1_40A, Bacteroides sp. 4_3_47FAA, Bacteroides sp. 9_1_42FAA, Bacteroides sp. NB_8
clade_38	Bacteroides ovatus, Bacteroides sp. 1_1_30, Bacteroides sp. 2_1_22, Bacteroides sp. 2_2_4, Bacteroides sp. 3_1_23, Bacteroides sp. D1, Bacteroides sp. D2, Bacteroides sp. D22, Bacteroides xylanisolvens
clade_38e	Bacteroides sp. 1_1_30, Bacteroides sp. 2_1_22, Bacteroides sp. 2_2_4, Bacteroides sp. 3_1_23, Bacteroides sp. D1, Bacteroides sp. D2, Bacteroides sp. D22, Bacteroides xylanisolvens
clade_38i	Bacteroides sp. 1_1_30, Bacteroides sp. 2_1_22, Bacteroides sp. 2_2_4, Bacteroides sp. 3_1_23, Bacteroides sp. D1, Bacteroides sp. D2, Bacteroides sp. D22, Bacteroides xylanisolvens
clade_408	Anaerostipes caccae, Anaerostipes sp. 3_2_56FAA, Clostridiales bacterium 1_7_47FAA, Clostridiales sp. SM4_1, Clostridiales sp. SSC_2, Clostridium aerotolerans, Clostridium aldenense, Clostridium algidixylanolyticum, Clostridium amygdalinum, Clostridium asparagiforme, Clostridium bolteae, Clostridium celerecrescens, Clostridium citroniae, Clostridium clostridiiformes, Clostridium clostridioforme, Clostridium hathewayi, Clostridium indolis, Clostridium lavalense, Clostridium saccharolyticum, Clostridium sp. M62_1, Clostridium sp. SS2_1, Clostridium sphenoides, Clostridium symbiosum, Clostridium xylanolyticum, Eubacterium hadrum, Fusobacterium naviforme, Lachnospiraceae bacterium 3_1_57FAA, Lachnospiraceae bacterium 5_1_63FAA, Lachnospiraceae bacterium A4,

	Lachnospiraceae bacterium DJF VP30, Lachnospiraceae genomosp. C1, Moryella indoligenes
clade_408b	Anaerostipes caccae, Anaerostipes sp. 3_2_56FAA, Clostridiales bacterium 1_7_47FAA, Clostridiales sp. SM4_1, Clostridiales sp. SSC_2, Clostridium aerotolerans, Clostridium aldenense, Clostridium algidixylanolyticum, Clostridium amygdalinum, Clostridium asparagiforme, Clostridium bolteae, Clostridium celerecrescens, Clostridium citroniae, Clostridium clostridiiformes, Clostridium clostridioforme, Clostridium indolis, Clostridium lavalense, Clostridium saccharolyticum, Clostridium sp. M62_1, Clostridium sp. SS2_1, Clostridium sphenoides, Clostridium symbiosum, Clostridium xylanolyticum, Eubacterium hadrum, Fusobacterium naviforme, Lachnospiraceae bacterium 5_1_63FAA, Lachnospiraceae bacterium A4, Lachnospiraceae bacterium DJF VP30, Lachnospiraceae genomosp. C1, Moryella indoligenes
clade_408d	Anaerostipes caccae, Anaerostipes sp. 3_2_56FAA, Clostridiales sp. SM4_1, Clostridiales sp. SSC_2, Clostridium aerotolerans, Clostridium aldenense, Clostridium algidixylanolyticum, Clostridium amygdalinum, Clostridium celerecrescens, Clostridium citroniae, Clostridium clostridiiformes, Clostridium clostridioforme, Clostridium hathewayi, Clostridium lavalense, Clostridium saccharolyticum, Clostridium sp. M62_1, Clostridium sp. SS2_1, Clostridium sphenoides, Clostridium symbiosum, Clostridium xylanolyticum, Eubacterium hadrum, Fusobacterium naviforme, Lachnospiraceae bacterium 3_1_57FAA, Lachnospiraceae bacterium 5_1_63FAA, Lachnospiraceae bacterium A4, Lachnospiraceae bacterium DJF VP30, Lachnospiraceae genomosp. C1, Moryella indoligenes
clade_408f	Anaerostipes sp. 3_2_56FAA, Clostridiales bacterium 1_7_47FAA, Clostridiales sp. SM4_1, Clostridiales sp. SSC_2, Clostridium aerotolerans, Clostridium aldenense, Clostridium algidixylanolyticum, Clostridium amygdalinum, Clostridium asparagiforme, Clostridium bolteae, Clostridium celerecrescens, Clostridium citroniae, Clostridium clostridiiformes, Clostridium clostridioforme, Clostridium hathewayi, Clostridium lavalense, Clostridium saccharolyticum, Clostridium sp. M62_1, Clostridium sp. SS2_1, Clostridium sphenoides, Clostridium symbiosum, Clostridium xylanolyticum, Eubacterium hadrum, Fusobacterium naviforme, Lachnospiraceae bacterium 3_1_57FAA, Lachnospiraceae bacterium 5_1_63FAA, Lachnospiraceae bacterium A4, Lachnospiraceae bacterium DJF VP30, Lachnospiraceae genomosp. C1, Moryella indoligenes
clade_408g	Anaerostipes caccae, Anaerostipes sp. 3_2_56FAA, Clostridiales sp. SM4_1, Clostridiales sp. SSC_2, Clostridium aerotolerans, Clostridium aldenense, Clostridium algidixylanolyticum, Clostridium amygdalinum, Clostridium celerecrescens, Clostridium citroniae, Clostridium clostridiiformes, Clostridium clostridioforme, Clostridium lavalense, Clostridium saccharolyticum, Clostridium sp. M62_1, Clostridium sp. SS2_1, Clostridium sphenoides, Clostridium symbiosum, Clostridium xylanolyticum, Eubacterium hadrum, Fusobacterium naviforme, Lachnospiraceae bacterium 5_1_63FAA, Lachnospiraceae bacterium A4, Lachnospiraceae bacterium DJF VP30, Lachnospiraceae genomosp. C1, Moryella indoligenes
clade_408h	Anaerostipes caccae, Anaerostipes sp. 3_2_56FAA, Clostridiales sp. SM4_1, Clostridiales sp. SSC_2, Clostridium aerotolerans, Clostridium aldenense, Clostridium algidixylanolyticum, Clostridium amygdalinum, Clostridium celerecrescens, Clostridium citroniae, Clostridium clostridiiformes, Clostridium clostridioforme, Clostridium lavalense, Clostridium saccharolyticum, Clostridium sp. M62_1, Clostridium sp. SS2_1, Clostridium sphenoides, Clostridium symbiosum, Clostridium xylanolyticum, Eubacterium hadrum, Fusobacterium naviforme, Lachnospiraceae bacterium 5_1_63FAA, Lachnospiraceae bacterium A4, Lachnospiraceae bacterium DJF VP30, Lachnospiraceae genomosp. C1, Moryella indoligenes
clade_420	Barnesiella intestinihominis, Barnesiella viscericola, Parabacteroides sp. NS31_3, Porphyromonadaceae bacterium NML 060648, Tannerella forsythia, Tannerella sp. 6_1_58FAA_CT1
clade_420f	Barnesiella viscericola, Parabacteroides sp. NS31_3, Porphyromonadaceae bacterium NML 060648, Tannerella forsythia, Tannerella sp. 6_1_58FAA_CT1
clade_444	Butyrivibrio fibrisolvens, Eubacterium rectale, Eubacterium sp. oral clone GI038, Lachnobacterium bovis, Roseburia cecicola, Roseburia faecalis, Roseburia faecis, Roseburia hominis, Roseburia intestinalis, Roseburia inulinivorans, Roseburia sp. 11SE37, Roseburia sp. 11SE38, Shuttleworthia satelles, Shuttleworthia sp. MSX8B, Shuttleworthia sp.

	oral taxon G69
clade_444i	Butyrivibrio fibrisolvens, Eubacterium sp. oral clone GI038, Lachnobacterium bovis, Roseburia cecicola, Roseburia faecis, Roseburia hominis, Roseburia inulinivorans, Roseburia sp. 11SE37, Roseburia sp. 11SE38, Shuttleworthia satelles, Shuttleworthia sp. MSX8B, Shuttleworthia sp. oral taxon G69
clade_478	Faecalibacterium prausnitzii, Gemmiger formicilis, Subdoligranulum variabile
clade_478i	Gemmiger formicilis, Subdoligranulum variabile
clade_479	Clostridiaceae bacterium JC13, Clostridium sp. MLG055, Erysipelotrichaceae bacterium 3_1_53
clade_479c	Clostridium sp. MLG055, Erysipelotrichaceae bacterium 3_1_53
clade_479g	Clostridium sp. MLG055, Erysipelotrichaceae bacterium 3_1_53
clade_479h	Clostridium sp. MLG055, Erysipelotrichaceae bacterium 3_1_53
clade_481	Clostridium cocleatum, Clostridium ramosum, Clostridium saccharogumia, Clostridium spiroforme, Coprobacillus sp. D7
clade_481a	Clostridium cocleatum, Clostridium spiroforme, Coprobacillus sp. D7
clade_481b	Clostridium cocleatum, Clostridium ramosum, Clostridium spiroforme, Coprobacillus sp. D7
clade_481e	Clostridium cocleatum, Clostridium saccharogumia, Clostridium spiroforme, Coprobacillus sp. D7
clade_481g	Clostridium cocleatum, Clostridium spiroforme, Coprobacillus sp. D7
clade_481h	Clostridium cocleatum, Clostridium spiroforme, Coprobacillus sp. D7
clade_481i	Clostridium ramosum, Clostridium saccharogumia, Clostridium spiroforme, Coprobacillus sp. D7
clade_497	Abiotrophia para_adiacens, Carnobacterium divergens, Carnobacterium maltaromaticum, Enterococcus avium, Enterococcus caccae, Enterococcus casseliflavus, Enterococcus durans, Enterococcus faecalis, Enterococcus faecium, Enterococcus gallinarum, Enterococcus gilvus, Enterococcus hawaiiensis, Enterococcus hirae, Enterococcus italicus, Enterococcus mundtii, Enterococcus raffinosus, Enterococcus sp. BV2CASA2, Enterococcus sp. CCRI 16620, Enterococcus sp. F95, Enterococcus sp. RfL6, Enterococcus thailandicus, Fusobacterium canifelinum, Fusobacterium genomosp. C1, Fusobacterium genomosp. C2, Fusobacterium nucleatum, Fusobacterium periodonticum, Fusobacterium sp. 11_3_2, Fusobacterium sp. 1_1_41FAA, Fusobacterium sp. 2_1_31, Fusobacterium sp. 3_1_27, Fusobacterium sp. 3_1_33, Fusobacterium sp. 3_1_36A2, Fusobacterium sp. AC18, Fusobacterium sp. ACB2, Fusobacterium sp. AS2, Fusobacterium sp. CM1, Fusobacterium sp. CM21, Fusobacterium sp. CM22, Fusobacterium sp. oral clone ASCF06, Fusobacterium sp. oral clone ASCF11, Granulicatella adiacens, Granulicatella elegans, Granulicatella paradiacens, Granulicatella sp. oral clone ASC02, Granulicatella sp. oral clone ASCA05, Granulicatella sp. oral clone ASCB09, Granulicatella sp. oral clone ASCG05, Tetragenococcus halophilus, Tetragenococcus koreensis, Vagococcus fluvialis
clade_497e	Abiotrophia para_adiacens, Carnobacterium divergens, Carnobacterium maltaromaticum, Enterococcus avium, Enterococcus caccae, Enterococcus casseliflavus, Enterococcus durans, Enterococcus faecium, Enterococcus gallinarum, Enterococcus gilvus, Enterococcus hawaiiensis, Enterococcus hirae, Enterococcus italicus, Enterococcus mundtii, Enterococcus raffinosus, Enterococcus sp. BV2CASA2, Enterococcus sp. CCRI 16620, Enterococcus sp. F95, Enterococcus sp. RfL6, Enterococcus thailandicus, Fusobacterium canifelinum, Fusobacterium genomosp. C1, Fusobacterium genomosp. C2, Fusobacterium nucleatum, Fusobacterium periodonticum, Fusobacterium sp. 11_3_2, Fusobacterium sp. 1_1_41FAA, Fusobacterium sp. 2_1_31, Fusobacterium sp. 3_1_27, Fusobacterium sp. 3_1_33, Fusobacterium sp. 3_1_36A2, Fusobacterium sp. AC18, Fusobacterium sp. ACB2, Fusobacterium sp. AS2, Fusobacterium sp. CM1, Fusobacterium sp. CM21, Fusobacterium sp. CM22, Fusobacterium sp. oral clone ASCF06, Fusobacterium sp. oral clone ASCF11, Granulicatella adiacens, Granulicatella elegans, Granulicatella paradiacens, Granulicatella sp. oral clone ASC02, Granulicatella sp. oral clone ASCA05, Granulicatella sp. oral clone ASCB09, Granulicatella sp. oral clone ASCG05, Tetragenococcus halophilus, Tetragenococcus koreensis, Vagococcus fluvialis

clade_497f	Abiotrophia para_adiacens, Carnobacterium divergens, Carnobacterium maltaromaticum, Enterococcus avium, Enterococcus caccae, Enterococcus casseliflavus, Enterococcus faecalis, Enterococcus gallinarum, Enterococcus gilvus, Enterococcus hawaiiensis, Enterococcus italicus, Enterococcus mundtii, Enterococcus raffinosus, Enterococcus sp. BV2CASA2, Enterococcus sp. CCRI 16620, Enterococcus sp. F95, Enterococcus sp. RfL6, Enterococcus thailandicus, Fusobacterium canifelinum, Fusobacterium genomosp. C1, Fusobacterium genomosp. C2, Fusobacterium nucleatum, Fusobacterium periodonticum, Fusobacterium sp. 11_3_2, Fusobacterium sp. 1_1_41FAA, Fusobacterium sp. 2_1_31, Fusobacterium sp. 3_1_27, Fusobacterium sp. 3_1_33, Fusobacterium sp. 3_1_36A2, Fusobacterium sp. AC18, Fusobacterium sp. ACB2, Fusobacterium sp. AS2, Fusobacterium sp. CM1, Fusobacterium sp. CM21, Fusobacterium sp. CM22, Fusobacterium sp. oral clone ASCF06, Fusobacterium sp. oral clone ASCF11, Granulicatella adiacens, Granulicatella elegans, Granulicatella paradiacens, Granulicatella sp. oral clone ASC02, Granulicatella sp. oral clone ASCA05, Granulicatella sp. oral clone ASCB09, Granulicatella sp. oral clone ASCG05, Tetragenococcus halophilus, Tetragenococcus koreensis, Vagococcus fluvialis
clade_512	Eubacterium barkeri, Eubacterium callanderi, Eubacterium limosum, Pseudoramibacter alactolyticus
clade_512i	Eubacterium barkeri, Eubacterium callanderi, Pseudoramibacter alactolyticus
clade_516	Anaerotruncus colihominis, Clostridium methylpentosum, Clostridium sp. YIT 12070, Hydrogenoanaerobacterium saccharovorans, Ruminococcus albus, Ruminococcus flavefaciens
clade_516c	Clostridium methylpentosum, Clostridium sp. YIT 12070, Hydrogenoanaerobacterium saccharovorans, Ruminococcus albus, Ruminococcus flavefaciens
clade_516g	Clostridium methylpentosum, Clostridium sp. YIT 12070, Hydrogenoanaerobacterium saccharovorans, Ruminococcus albus, Ruminococcus flavefaciens
clade_516h	Clostridium methylpentosum, Clostridium sp. YIT 12070, Hydrogenoanaerobacterium saccharovorans, Ruminococcus albus, Ruminococcus flavefaciens
clade_519	Eubacterium ventriosum
clade_522	Bacteroides galacturonicus, Eubacterium eligens, Lachnospira multipara, Lachnospira pectinoschiza, Lactobacillus rogosae
clade_522i	Bacteroides galacturonicus, Lachnospira multipara, Lachnospira pectinoschiza, Lactobacillus rogosae
clade_553	Collinsella aerofaciens, Collinsella intestinalis, Collinsella stercoris, Collinsella tanakaei
clade_553i	Collinsella intestinalis, Collinsella stercoris, Collinsella tanakaei
clade_566	Adlercreutzia equolifaciens, Coriobacteriaceae bacterium JC110, Coriobacteriaceae bacterium phI, Cryptobacterium curtum, Eggerthella lenta, Eggerthella sinensis, Eggerthella sp. 1_3_56FAA, Eggerthella sp. HGA1, Eggerthella sp. YY7918, Gordonibacter pamelaeae, Slackia equolifaciens, Slackia exigua, Slackia faecicanis, Slackia heliotrinireducens, Slackia isoflavoniconvertens, Slackia piriformis, Slackia sp. NATTS, Streptomyces albus
clade_566f	Coriobacteriaceae bacterium JC110, Coriobacteriaceae bacterium phI, Cryptobacterium curtum, Eggerthella lenta, Eggerthella sinensis, Eggerthella sp. 1_3_56FAA, Eggerthella sp. HGA1, Eggerthella sp. YY7918, Gordonibacter pamelaeae, Slackia equolifaciens, Slackia exigua, Slackia faecicanis, Slackia heliotrinireducens, Slackia isoflavoniconvertens, Slackia piriformis, Slackia sp. NATTS, Streptomyces albus
clade_572	Butyricicoccus pullicaecorum, Eubacterium desmolans, Papillibacter cinnamivorans, Sporobacter termitidis
clade_572i	Butyricicoccus pullicaecorum, Papillibacter cinnamivorans, Sporobacter termitidis
clade_65	Bacteroides faecis, Bacteroides fragilis, Bacteroides nordii, Bacteroides salyersiae, Bacteroides sp. 1_1_14, Bacteroides sp. 1_1_6, Bacteroides sp. 2_1_56FAA, Bacteroides sp. AR29, Bacteroides sp. B2, Bacteroides thetaiotaomicron
clade_65e	Bacteroides faecis, Bacteroides fragilis, Bacteroides nordii, Bacteroides salyersiae, Bacteroides sp. 1_1_14, Bacteroides sp. 1_1_6, Bacteroides sp. 2_1_56FAA, Bacteroides sp. AR29, Bacteroides sp. B2

clade_92	Actinobacillus actinomycetemcomitans, Actinobacillus succinogenes, Aggregatibacter actinomycetemcomitans, Aggregatibacter aphrophilus, Aggregatibacter segnis, Averyella dalhousiensis, Bisgaard Taxon, Buchnera aphidicola, Cedecea davisae, Citrobacter amalonaticus, Citrobacter braakii, Citrobacter farmeri, Citrobacter freundii, Citrobacter gillenii, Citrobacter koseri, Citrobacter murliniae, Citrobacter rodentium, Citrobacter sedlakii, Citrobacter sp. 30_2, Citrobacter sp. KMSI_3, Citrobacter werkmanii, Citrobacter youngae, Cronobacter malonaticus, Cronobacter sakazakii, Cronobacter turicensis, Enterobacter aerogenes, Enterobacter asburiae, Enterobacter cancerogenus, Enterobacter cloacae, Enterobacter cowanii, Enterobacter hormaechei, Enterobacter sp. 247BMC, Enterobacter sp. 638, Enterobacter sp. JC163, Enterobacter sp. SCSS, Enterobacter sp. TSE38, Enterobacteriaceae bacterium 9_2_54FAA, Enterobacteriaceae bacterium CF01Ent_1, Enterobacteriaceae bacterium Smarlab 3302238, Escherichia albertii, Escherichia coli, Escherichia fergusonii, Escherichia hermannii, Escherichia sp. 1_1_43, Escherichia sp. 4_1_40B, Escherichia sp. B4, Escherichia vulneris, Ewingella americana, Haemophilus genomosp. P2 oral clone MB3_C24, Haemophilus genomosp. P3 oral clone MB3_C38, Haemophilus sp. oral clone JM053, Hafnia alvei, Klebsiella oxytoca, Klebsiella pneumoniae, Klebsiella sp. AS10, Klebsiella sp. Co9935, Klebsiella sp. OBRC7, Klebsiella sp. SP_BA, Klebsiella sp. SRC_DSD1, Klebsiella sp. SRC_DSD11, Klebsiella sp. SRC_DSD12, Klebsiella sp. SRC_DSD15, Klebsiella sp. SRC_DSD2, Klebsiella sp. SRC_DSD6, Klebsiella sp. enrichment culture clone SRC_DSD25, Klebsiella variicola, Kluyvera ascorbata, Kluyvera cryocrescens, Leminorella grimontii, Leminorella richardii, Pantoea agglomerans, Pantoea ananatis, Pantoea brenneri, Pantoea citrea, Pantoea conspicua, Pantoea septica, Pasteurella dagmatis, Pasteurella multocida, Plesiomonas shigelloides, Raoultella ornithinolytica, Raoultella planticola, Raoultella terrigena, Salmonella bongori, Salmonella enterica, Salmonella typhimurium, Serratia fonticola, Serratia liquefaciens, Serratia marcescens, Serratia odorifera, Serratia proteamaculans, Shigella boydii, Shigella dysenteriae, Shigella flexneri, Shigella sonnei, Tatumella ptyseos, Trabulsiella guamensis, Yersinia aldovae, Yersinia aleksiciae, Yersinia bercovieri, Yersinia enterocolitica, Yersinia frederiksenii, Yersinia intermedia, Yersinia kristensenii, Yersinia mollaretii, Yersinia pestis, Yersinia pseudotuberculosis, Yersinia rohdei, Yokenella regensburgei
clade_92e	Actinobacillus actinomycetemcomitans, Actinobacillus succinogenes, Aggregatibacter actinomycetemcomitans, Aggregatibacter aphrophilus, Aggregatibacter segnis, Averyella dalhousiensis, Bisgaard Taxon, Buchnera aphidicola, Cedecea davisae, Citrobacter amalonaticus, Citrobacter braakii, Citrobacter farmeri, Citrobacter freundii, Citrobacter gillenii, Citrobacter koseri, Citrobacter murliniae, Citrobacter rodentium, Citrobacter sedlakii, Citrobacter sp. 30_2, Citrobacter sp. KMSI_3, Citrobacter werkmanii, Citrobacter youngae, Cronobacter malonaticus, Cronobacter sakazakii, Cronobacter turicensis, Enterobacter aerogenes, Enterobacter asburiae, Enterobacter cancerogenus, Enterobacter cloacae, Enterobacter cowanii, Enterobacter hormaechei, Enterobacter sp. 247BMC, Enterobacter sp. 638, Enterobacter sp. JC163, Enterobacter sp. SCSS, Enterobacter sp. TSE38, Enterobacteriaceae bacterium 9_2_54FAA, Enterobacteriaceae bacterium CF01Ent_1, Enterobacteriaceae bacterium Smarlab 3302238, Escherichia albertii, Escherichia fergusonii, Escherichia hermannii, Escherichia sp. 1_1_43, Escherichia sp. 4_1_40B, Escherichia sp. B4, Escherichia vulneris, Ewingella americana, Haemophilus genomosp. P2 oral clone MB3_C24, Haemophilus genomosp. P3 oral clone MB3_C38, Haemophilus sp. oral clone JM053, Hafnia alvei, Klebsiella oxytoca, Klebsiella pneumoniae, Klebsiella sp. AS10, Klebsiella sp. Co9935, Klebsiella sp. OBRC7, Klebsiella sp. SP_BA, Klebsiella sp. SRC_DSD1, Klebsiella sp. SRC_DSD11, Klebsiella sp. SRC_DSD12, Klebsiella sp. SRC_DSD15, Klebsiella sp. SRC_DSD2, Klebsiella sp. SRC_DSD6, Klebsiella sp. enrichment culture clone SRC_DSD25, Klebsiella variicola, Kluyvera ascorbata, Kluyvera cryocrescens, Leminorella grimontii, Leminorella richardii, Pantoea agglomerans, Pantoea ananatis, Pantoea brenneri, Pantoea citrea, Pantoea conspicua, Pantoea septica, Pasteurella dagmatis, Pasteurella multocida, Plesiomonas shigelloides, Raoultella ornithinolytica, Raoultella planticola, Raoultella terrigena, Salmonella bongori, Salmonella enterica, Salmonella typhimurium, Serratia fonticola, Serratia liquefaciens, Serratia marcescens, Serratia odorifera, Serratia proteamaculans, Shigella boydii, Shigella dysenteriae, Shigella flexneri, Shigella sonnei, Tatumella ptyseos, Trabulsiella guamensis, Yersinia aldovae, Yersinia aleksiciae, Yersinia bercovieri, Yersinia enterocolitica, Yersinia frederiksenii, Yersinia intermedia, Yersinia kristensenii, Yersinia mollaretii, Yersinia pestis, Yersinia pseudotuberculosis, Yersinia rohdei, Yokenella regensburgei

clade_92i	Actinobacillus actinomycetemcomitans, Actinobacillus succinogenes, Aggregatibacter actinomycetemcomitans, Aggregatibacter aphrophilus, Aggregatibacter segnis, Averyella dalhousiensis, Bisgaard Taxon, Buchnera aphidicola, Cedecea davisae, Citrobacter amalonaticus, Citrobacter braakii, Citrobacter farmeri, Citrobacter freundii, Citrobacter gillenii, Citrobacter koseri, Citrobacter murliniae, Citrobacter rodentium, Citrobacter sedlakii, Citrobacter sp. 30_2, Citrobacter sp. KMSI_3, Citrobacter werkmanii, Citrobacter youngae, Cronobacter malonaticus, Cronobacter sakazakii, Cronobacter turicensis, Enterobacter aerogenes, Enterobacter asburiae, Enterobacter cancerogenus, Enterobacter cloacae, Enterobacter cowanii, Enterobacter hormaechei, Enterobacter sp. 247BMC, Enterobacter sp. 638, Enterobacter sp. JC163, Enterobacter sp. SCSS, Enterobacter sp. TSE38, Enterobacteriaceae bacterium 9_2_54FAA, Enterobacteriaceae bacterium CF01Ent_1, Enterobacteriaceae bacterium Smarlab 3302238, Escherichia albertii, Escherichia fergusonii, Escherichia hermannii, Escherichia sp. 1_1_43, Escherichia sp. 4_1_40B, Escherichia sp. B4, Escherichia vulneris, Ewingella americana, Haemophilus genomosp. P2 oral clone MB3_C24, Haemophilus genomosp. P3 oral clone MB3_C38, Haemophilus sp. oral clone JM053, Hafnia alvei, Klebsiella oxytoca, Klebsiella pneumoniae, Klebsiella sp. AS10, Klebsiella sp. Co9935, Klebsiella sp. OBRC7, Klebsiella sp. SP_BA, Klebsiella sp. SRC_DSD1, Klebsiella sp. SRC_DSD11, Klebsiella sp. SRC_DSD12, Klebsiella sp. SRC_DSD15, Klebsiella sp. SRC_DSD2, Klebsiella sp. SRC_DSD6, Klebsiella sp. enrichment culture clone SRC_DSD25, Klebsiella variicola, Kluyvera ascorbata, Kluyvera cryocrescens, Leminorella grimontii, Leminorella richardii, Pantoea agglomerans, Pantoea ananatis, Pantoea brenneri, Pantoea citrea, Pantoea conspicua, Pantoea septica, Pasteurella dagmatis, Pasteurella multocida, Plesiomonas shigelloides, Raoultella ornithinolytica, Raoultella planticola, Raoultella terrigena, Salmonella bongori, Salmonella enterica, Salmonella typhimurium, Serratia fonticola, Serratia liquefaciens, Serratia marcescens, Serratia odorifera, Serratia proteamaculans, Shigella boydii, Shigella dysenteriae, Shigella flexneri, Shigella sonnei, Tatumella ptyseos, Trabulsiella guamensis, Yersinia aldovae, Yersinia aleksiciae, Yersinia bercovieri, Yersinia enterocolitica, Yersinia frederiksenii, Yersinia intermedia, Yersinia kristensenii, Yersinia mollaretii, Yersinia pestis, Yersinia pseudotuberculosis, Yersinia rohdei, Yokenella regensburgei
clade_96	Clostridium oroticum, Clostridium sp. D5, Eubacterium contortum, Eubacterium fissicatena
clade_96g	Clostridium oroticum, Clostridium sp. D5, Eubacterium fissicatena
clade_96h	Clostridium oroticum, Clostridium sp. D5, Eubacterium fissicatena
clade_98	Okadaella gastrococcus, Streptococcus agalactiae, Streptococcus alactolyticus, Streptococcus australis, Streptococcus bovis, Streptococcus canis, Streptococcus constellatus, Streptococcus cristatus, Streptococcus dysgalactiae, Streptococcus equi, Streptococcus equinus, Streptococcus gallolyticus, Streptococcus genomosp. C1, Streptococcus genomosp. C2, Streptococcus genomosp. C3, Streptococcus genomosp. C4, Streptococcus genomosp. C5, Streptococcus genomosp. C6, Streptococcus genomosp. C7, Streptococcus genomosp. C8, Streptococcus gordonii, Streptococcus infantarius, Streptococcus infantis, Streptococcus intermedius, Streptococcus lutetiensis, Streptococcus massiliensis, Streptococcus mitis, Streptococcus oligofermentans, Streptococcus oralis, Streptococcus parasanguinis, Streptococcus pasteurianus, Streptococcus peroris, Streptococcus pneumoniae, Streptococcus porcinus, Streptococcus pseudopneumoniae, Streptococcus pseudoporcinus, Streptococcus pyogenes, Streptococcus ratti, Streptococcus salivarius, Streptococcus sanguinis, Streptococcus sinensis, Streptococcus sp. 2285_97, Streptococcus sp. 2_1_36FAA, Streptococcus sp. ACS2, Streptococcus sp. AS20, Streptococcus sp. BS35a, Streptococcus sp. C150, Streptococcus sp. CM6, Streptococcus sp. ICM10, Streptococcus sp. ICM12, Streptococcus sp. ICM2, Streptococcus sp. ICM4, Streptococcus sp. ICM45, Streptococcus sp. M143, Streptococcus sp. M334, Streptococcus sp. oral clone ASB02, Streptococcus sp. oral clone ASCA03, Streptococcus sp. oral clone ASCA04, Streptococcus sp. oral clone ASCA09, Streptococcus sp. oral clone ASCB04, Streptococcus sp. oral clone ASCB06, Streptococcus sp. oral clone ASCC04, Streptococcus sp. oral clone ASCC05, Streptococcus sp. oral clone ASCC12, Streptococcus sp. oral clone ASCD01, Streptococcus sp. oral clone ASCD09, Streptococcus sp. oral clone ASCD10, Streptococcus sp. oral clone ASCE03, Streptococcus sp. oral clone ASCE04, Streptococcus sp. oral clone ASCE05, Streptococcus sp. oral clone ASCE06, Streptococcus sp. oral clone ASCE09, Streptococcus sp. oral clone ASCE10, Streptococcus sp. oral clone ASCE12, Streptococcus sp. oral clone ASCF05, Streptococcus sp. oral clone ASCF07, Streptococcus sp. oral clone ASCF09, Streptococcus sp. oral clone ASCG04, Streptococcus sp. oral clone BW009, Streptococcus sp. oral clone CH016, Streptococcus sp. oral clone GK051, Streptococcus sp. oral clone GM006, Streptococcus sp. oral clone P2PA_41 P2, Streptococcus sp. oral clone P4PA_30 P4, Streptococcus sp. oral taxon 071, Streptococcus sp. oral taxon G59, Streptococcus sp. oral taxon G62, Streptococcus sp. oral taxon G63, Streptococcus suis, Streptococcus thermophilus,

	Streptococcus uberis, Streptococcus urinalis, Streptococcus vestibularis, Streptococcus viridans, Synergistetes bacterium oral clone 03 5 D05
clade_98i	Okadaella gastrococcus, Streptococcus agalactiae, Streptococcus alactolyticus, Streptococcus australis, Streptococcus bovis, Streptococcus canis, Streptococcus constellatus, Streptococcus cristatus, Streptococcus dysgalactiae, Streptococcus equi, Streptococcus equinus, Streptococcus gallolyticus, Streptococcus genomosp. C1, Streptococcus genomosp. C2, Streptococcus genomosp. C3, Streptococcus genomosp. C4, Streptococcus genomosp. C5, Streptococcus genomosp. C6, Streptococcus genomosp. C7, Streptococcus genomosp. C8, Streptococcus gordonii, Streptococcus infantarius, Streptococcus infantis, Streptococcus intermedius, Streptococcus lutetiensis, Streptococcus massiliensis, Streptococcus oligofermentans, Streptococcus oralis, Streptococcus parasanguinis, Streptococcus pasteurianus, Streptococcus peroris, Streptococcus pneumoniae, Streptococcus porcinus, Streptococcus pseudopneumoniae, Streptococcus pseudoporcinus, Streptococcus pyogenes, Streptococcus ratti, Streptococcus salivarius, Streptococcus sanguinis, Streptococcus sinensis, Streptococcus sp. 2285_97, Streptococcus sp. 2_1_36FAA, Streptococcus sp. ACS2, Streptococcus sp. AS20, Streptococcus sp. BS35a, Streptococcus sp. C150, Streptococcus sp. CM6, Streptococcus sp. ICM10, Streptococcus sp. ICM12, Streptococcus sp. ICM2, Streptococcus sp. ICM4, Streptococcus sp. ICM45, Streptococcus sp. M143, Streptococcus sp. M334, Streptococcus sp. oral clone ASB02, Streptococcus sp. oral clone ASCA03, Streptococcus sp. oral clone ASCA04, Streptococcus sp. oral clone ASCA09, Streptococcus sp. oral clone ASCB04, Streptococcus sp. oral clone ASCB06, Streptococcus sp. oral clone ASCC04, Streptococcus sp. oral clone ASCC05, Streptococcus sp. oral clone ASCC12, Streptococcus sp. oral clone ASCD01, Streptococcus sp. oral clone ASCD09, Streptococcus sp. oral clone ASCD10, Streptococcus sp. oral clone ASCE03, Streptococcus sp. oral clone ASCE04, Streptococcus sp. oral clone ASCE05, Streptococcus sp. oral clone ASCE06, Streptococcus sp. oral clone ASCE09, Streptococcus sp. oral clone ASCE10, Streptococcus sp. oral clone ASCE12, Streptococcus sp. oral clone ASCF05, Streptococcus sp. oral clone ASCF07, Streptococcus sp. oral clone ASCF09, Streptococcus sp. oral clone ASCG04, Streptococcus sp. oral clone BW009, Streptococcus sp. oral clone CH016, Streptococcus sp. oral clone GK051, Streptococcus sp. oral clone GM006, Streptococcus sp. oral clone P2PA_41 P2, Streptococcus sp. oral clone P4PA_30 P4, Streptococcus sp. oral taxon 071, Streptococcus sp. oral taxon G59, Streptococcus sp. oral taxon G62, Streptococcus sp. oral taxon G63, Streptococcus suis, Streptococcus thermophilus, Streptococcus uberis, Streptococcus urinalis, Streptococcus vestibularis, Streptococcus viridans, Synergistetes bacterium oral clone 03 5 D05

CLAIMS

1. A method for treating, preventing, or reducing the severity of a disorder selected from the group consisting of Clostridium difficile Associated Diarrhea (CDAD), Type 2 Diabetes, Obesity, Irritable Bowel Disease (IBD), colonization with a pathogen or pathobiont, and infection with a drug-resistant pathogen or pathobiont, comprising: administering to a mammalian subject in need thereof an effective amount of a therapeutic bacterial composition, said therapeutic bacterial composition comprising a plurality of isolated bacteria or a purified bacterial preparation, the plurality of isolated bacteria or the purified bacterial preparation capable of forming a network ecology selected from the group consisting of N262.S, N290.S, N284.S, N271.S, N282.S, N288.S, N302.S, N279.S, N310.S, N323.S, N331.S, N332.S, N301.S, N312.S, N339.S, N325.S, N340.S, N341.S, N346.S, N338.S, N336.S, N345.S, N355.S, N356.S, N343.S, N329.S, N361.S, N353.S, N381.S, N344.S, N352.S, N357.S, N358.S, N369.S, N372.S, N375.S, N380.S, N374.S, N377.S, N368.S, N370.S, N373.S, N376.S, N389.S, N394.S, N431.S, N434.S, N390.S, N397.S, N387.S, N440.S, N396.S, N399.S, N403.S, N414.S, N430.S, N432.S, N436.S, N437.S, N457.S, N545, N386.S, N402.S, N405.S, N415.S, N421.S, N422.S, N423.S, N458.S, N459.S, N493.S, N416.S, N439.S, N447.S, N490.S, N526, N429.S, N433.S, N448.S, N488.S, N508.S, N509.S, N510.S, N511.S, N408.S, N446.S, N451.S, N474.S, N520.S, N521.S, N535.S, N516.S, N463.S, N518.S, N586, N450.S, N465.S, N519.S, N537.S, N419.S, N468.S, N477.S, N514.S, N382.S, N460.S, N462.S, N512.S, N517.S, N523.S, N547.S, N548.S, N577.S, N581.S, N585.S, N616.S, N466.S, N469.S, N480.S, N482.S, N484.S, N515.S, N533.S, N709, N730, N478.S, N572.S, N400.S, N543.S, N582.S, N621.S, N689, N769, N481.S, N525.S, N528.S, N534.S, N574.S, N580.S, N590.S, N591.S, N597.S, N664, N693, N530.S, N687, N470.S, N529.S, N539.S, N546.S, N570.S, N579.S, N602.S, N614.S, N648.S, N652.S, N655.S, N672.S, N681.S, N690.S, N692.S, N698.S, N737.S, N738.S, N785, N841, N878, N880, N881, N987, N988, N996, N1061, N479.S, N538.S, N542.S, N578.S, N609.S, N611.S, N617.S, N666.S, N675.S, N682.S, N844, N845, N846, N852, N876, N982, N1008, N649.S, N657.S, N678.S, N686.S, N710.S, N522.S, N651.S, N653.S, N654.S, N680.S, N712.S, N792, N802, N804, N807, N849, N858, N859, N875, N885, N942, N961, N972, N1051, N587.S, N589.S, N612.S, N625.S, N656.S, N714.S, N779, N781, N828, N829, N860, N894, N925, N927, N935, N947, N983, N1023, N441.S, N584.S, N794, N788, N524.S, N604.S, N610.S, N623.S, N663.S, N669.S, N676.S, N703.S, N775.S, N777.S, N780.S, N817.S, N827.S, N836.S, N871.S, N874.S, N898.S, N907.S, N998.S, N1088, N1089, N660.S, N665.S, N667.S, N733.S, N734.S, N739.S, N741.S, N782.S,

N789.S, N796.S, N798.S, N800.S, N809.S, N816.S, N842.S, N843.S, N869.S, N986.S, N995.S, N1002.S, N1004.S, N1019.S, N1093, N668.S, N685.S, N835.S, N851.S, N464.S, N695.S, N776.S, N793.S, N815.S, N833.S, N891.S, N1070.S, N1092, N795.S, N797.S, N808.S, N811.S, N826.S, N830.S, N832.S, N840.S, N945.S, N960.S, N968.S, N1091, N805.S, N822.S, N928.S, N936.S, N1078.S, and N913.S.

2. The method of claim 1, wherein said therapeutic bacterial composition comprises at least one bacterial entity, wherein said bacterial entity is capable of forming the network ecology in combination with one more bacterial entities present in the gastrointestinal tract of the mammalian subject at the time of the administering or thereafter.

3. The method of claim 1, wherein the network ecology is selected from the group consisting of N1008, N1023, N1051, N1061, N1070.S, N1088, N1089, N1092, N381.S, N382.S, N387.S, N399.S, N400.S, N402.S, N403.S, N414.S, N429.S, N430.S, N432.S, N433.S, N436.S, N437.S, N439.S, N441.S, N447.S, N448.S, N457.S, N460.S, N462.S, N463.S, N464.S, N470.S, N474.S, N488.S, N490.S, N493.S, N508.S, N509.S, N510.S, N511.S, N512.S, N514.S, N515.S, N517.S, N518.S, N519.S, N520.S, N523.S, N524.S, N529.S, N539.S, N543.S, N546.S, N547.S, N548.S, N570.S, N574.S, N577.S, N579.S, N580.S, N582.S, N584.S, N585.S, N589.S, N591.S, N597.S, N602.S, N604.S, N609.S, N610.S, N611.S, N612.S, N614.S, N616.S, N621.S, N623.S, N625.S, N648.S, N651.S, N652.S, N653.S, N654.S, N655.S, N660.S, N663.S, N664, N665.S, N666.S, N669.S, N672.S, N676.S, N681.S, N687, N689, N690.S, N692.S, N693, N695.S, N698.S, N703.S, N709, N712.S, N714.S, N730, N734.S, N737.S, N738.S, N769, N775.S, N777.S, N779, N780.S, N781, N785, N788, N792, N793.S, N794, N797.S, N798.S, N802, N804, N807, N817.S, N827.S, N828, N830.S, N832.S, N833.S, N836.S, N840.S, N841, N844, N845, N849, N852, N858, N859, N860, N869.S, N871.S, N874.S, N875, N878, N880, N881, N885, N894, N898.S, N907.S, N913.S, N925, N927, N942, N947, N961, N968.S, N972, N982, N983, N986.S, N987, N988, N996, and N998.S.

4. The method of claim 1, wherein the network ecology consists essentially of N1008, N1023, N1051, N1061, N1070.S, N1088, N1089, N1092, N381.S, N382.S, N387.S, N399.S, N400.S, N402.S, N403.S, N414.S, N429.S, N430.S, N432.S, N433.S, N436.S, N437.S, N439.S, N441.S, N447.S, N448.S, N457.S, N460.S, N462.S, N463.S, N464.S, N470.S, N474.S, N488.S, N490.S, N493.S, N508.S, N509.S, N510.S, N511.S, N512.S, N514.S, N515.S, N517.S, N518.S, N519.S, N520.S, N523.S, N524.S, N529.S, N539.S, N543.S, N546.S, N547.S, N548.S, N570.S, N574.S, N577.S, N579.S, N580.S, N582.S, N584.S, N585.S, N589.S, N591.S, N597.S, N602.S, N604.S, N609.S, N610.S, N611.S, N612.S,

N614.S, N616.S, N621.S, N623.S, N625.S, N648.S, N651.S, N652.S, N653.S, N654.S, N655.S, N660.S, N663.S, N664, N665.S, N666.S, N669.S, N672.S, N676.S, N681.S, N687, N689, N690.S, N692.S, N693, N695.S, N698.S, N703.S, N709, N712.S, N714.S, N730, N734.S, N737.S, N738.S, N769, N775.S, N777.S, N779, N780.S, N781, N785, N788, N792, N793.S, N794, N797.S, N798.S, N802, N804, N807, N817.S, N827.S, N828, N830.S, N832.S, N833.S, N836.S, N840.S, N841, N844, N845, N849, N852, N858, N859, N860, N869.S, N871.S, N874.S, N875, N878, N880, N881, N885, N894, N898.S, N907.S, N913.S, N925, N927, N942, N947, N961, N968.S, N972, N982, N983, N986.S, N987, N988, N996, or N998.S.

5. The method of claim 3, wherein the network ecology is selected from the group consisting of N387.S, N399.S, N512.S, N462.S, N651.S, N982, and N845.

6. The method of claim 5, wherein the network ecology comprises N387.S and the therapeutic bacterial composition comprises at least one bacterium selected from each of clade_262, clade_396, clade_444, clade_478, clade_500, and clade_553.

7. The method of claim 5, wherein the network ecology comprises N387.S and the therapeutic bacterial composition consists essentially of at least one bacterium selected from each of clade_262, clade_396, clade_444, clade_478, clade_500, and clade_553.

8. The method of claim 6 or claim 7, wherein clade_262 comprises one or more bacteria selected from the group consisting Clostridium glycyrrhizinilyticum, Clostridium nexile, Coprococcus comes, Lachnospiraceae bacterium 1_1_57FAA, Lachnospiraceae bacterium 1_4_56FAA, Lachnospiraceae bacterium 8_1_57FAA, Ruminococcus lactaris, and Ruminococcus torques, wherein clade_396 comprises one or more bacteria selected from the group consisting Acetivibrio ethanolgignens, Anaerosporobacter mobilis, Bacteroides pectinophilus, Clostridium aminovalericum, Clostridium phytofermentans, Eubacterium hallii, and Eubacterium xylanophilum, wherein clade_444 comprises one or more bacteria selected from the group consisting Butyrivibrio fibrisolvens, Eubacterium rectale, Eubacterium sp. oral clone GI038, Lachnobacterium bovis, Roseburia cecicola, Roseburia faecalis, Roseburia faecis, Roseburia hominis, Roseburia intestinalis, Roseburia inulinivorans, Roseburia sp. 11SE37, Roseburia sp. 11SE38, Shuttleworthia satelles, Shuttleworthia sp. MSX8B, and Shuttleworthia sp. oral taxon G69, wherein clade_478 comprises one or more bacteria selected from the group consisting Faecalibacterium prausnitzii, Gemmiger formicilis, and Subdoligranulum variabile, wherein clade_500 comprises one or more bacteria selected from the group consisting Alistipes finegoldii, Alistipes onderdonkii, Alistipes putredinis, Alistipes shahii, Alistipes sp. HGB5, Alistipes sp.

JC50, and Alistipes sp. RMA 9912, and wherein clade_553 comprises one or more bacteria selected from the group consisting Collinsella aerofaciens, Collinsella intestinalis, Collinsella stercoris, and Collinsella tanakaei.

9. The method of claim 6 or claim 7, wherein clade_262 comprises one or more bacteria of Ruminococcus torques, wherein clade_396 comprises one or more bacteria of Eubacterium hallii, wherein clade_444 comprises one or more bacteria selected from the group consisting of Eubacterium rectale and Roseburia inulinivorans, wherein clade_478 comprises one or more bacteria of Faecalibacterium prausnitzii, wherein clade_500 comprises one or more bacteria of Alistipes putredinis, and wherein clade_553 comprises one or more bacteria of Collinsella aerofaciens.

10. The method of claim 6 or claim 7, wherein clade_262 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1048, Seq. ID No.: 1049, Seq. ID No.: 1057, Seq. ID No.: 1663, Seq. ID No.: 1670, Seq. ID No.: 588, Seq. ID No.: 607, and Seq. ID No.: 674, wherein clade_396 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 161, Seq. ID No.: 288, Seq. ID No.: 551, Seq. ID No.: 6, Seq. ID No.: 613, Seq. ID No.: 848, and Seq. ID No.: 875, wherein clade_444 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1045, Seq. ID No.: 1634, Seq. ID No.: 1635, Seq. ID No.: 1636, Seq. ID No.: 1637, Seq. ID No.: 1638, Seq. ID No.: 1639, Seq. ID No.: 1640, Seq. ID No.: 1641, Seq. ID No.: 1728, Seq. ID No.: 1729, Seq. ID No.: 1730, Seq. ID No.: 456, Seq. ID No.: 856, and Seq. ID No.: 865, wherein clade_478 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1896, Seq. ID No.: 880, and Seq. ID No.: 932, wherein clade_500 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 129, Seq. ID No.: 131, Seq. ID No.: 132, Seq. ID No.: 133, Seq. ID No.: 134, Seq. ID No.: 135, and Seq. ID No.: 136, and wherein clade_553 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 659, Seq. ID No.: 660, Seq. ID No.: 661, and Seq. ID No.: 662.

11. The method of claim 6 or claim 7, wherein clade_262 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1048, Seq. ID No.: 1049, Seq. ID No.: 1057, Seq. ID No.: 1663, Seq. ID No.: 1670, Seq. ID No.: 588, Seq. ID No.: 607, and Seq. ID No.: 674, wherein clade_396 comprises one more bacteria

selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 161, Seq. ID No.: 288, Seq. ID No.: 551, Seq. ID No.: 6, Seq. ID No.: 613, Seq. ID No.: 848, and Seq. ID No.: 875, wherein clade_444 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1045, Seq. ID No.: 1634, Seq. ID No.: 1635, Seq. ID No.: 1636, Seq. ID No.: 1637, Seq. ID No.: 1638, Seq. ID No.: 1639, Seq. ID No.: 1640, Seq. ID No.: 1641, Seq. ID No.: 1728, Seq. ID No.: 1729, Seq. ID No.: 1730, Seq. ID No.: 456, Seq. ID No.: 856, and Seq. ID No.: 865, wherein clade_478 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1896, Seq. ID No.: 880, and Seq. ID No.: 932, wherein clade_500 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 129, Seq. ID No.: 131, Seq. ID No.: 132, Seq. ID No.: 133, Seq. ID No.: 134, Seq. ID No.: 135, and Seq. ID No.: 136, and wherein clade_553 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 659, Seq. ID No.: 660, Seq. ID No.: 661, and Seq. ID No.: 662.

12. The method of claim 6 or claim 7, wherein clade_262 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1670, wherein clade_396 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 848, wherein clade_444 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1639 and Seq. ID No.: 856, wherein clade_478 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 880, wherein clade_500 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 132, and wherein clade_553 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 659.

13. The method of claim 6 or claim 7, wherein clade_262 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1670, wherein clade_396 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 848, wherein clade_444 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1639 and Seq. ID No.: 856, wherein clade_478 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 880, wherein clade_500

comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 132, and wherein clade_553 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 659.

14. The method of claim 5, wherein the network ecology comprises N399.S and the therapeutic bacterial composition comprises at least one bacterium selected from each of clade_262, clade_360, clade_396, clade_444, clade_478, and clade_494.

15. The method of claim 5, wherein the network ecology comprises N399.S and the therapeutic bacterial composition consists essentially of at least one bacterium selected from each of clade_262, clade_360, clade_396, clade_444, clade_478, and clade_494.

16. The method of claim 14 or claim 15, wherein clade_262 comprises one or more bacteria selected from the group consisting of Clostridium glycyrrhizinilyticum, Clostridium nexile, Coprococcus comes, Lachnospiraceae bacterium 1_1_57FAA, Lachnospiraceae bacterium 1_4_56FAA, Lachnospiraceae bacterium 8_1_57FAA, Ruminococcus lactaris, and Ruminococcus torques, wherein clade_360 comprises one or more bacteria selected from the group consisting of Dorea formicigenerans, Dorea longicatena, Lachnospiraceae bacterium 2_1_46FAA, Lachnospiraceae bacterium 2_1_58FAA, Lachnospiraceae bacterium 4_1_37FAA, Lachnospiraceae bacterium 9_1_43BFAA, Ruminococcus gnavus, and Ruminococcus sp. ID8, wherein clade_396 comprises one or more bacteria selected from the group consisting of Acetivibrio ethanolgignens, Anaerosporobacter mobilis, Bacteroides pectinophilus, Clostridium aminovalericum, Clostridium phytofermentans, Eubacterium hallii, and Eubacterium xylanophilum, wherein clade_444 comprises one or more bacteria selected from the group consisting of Butyrivibrio fibrisolvens, Eubacterium rectale, Eubacterium sp. oral clone GI038, Lachnobacterium bovis, Roseburia cecicola, Roseburia faecalis, Roseburia faecis, Roseburia hominis, Roseburia intestinalis, Roseburia inulinivorans, Roseburia sp. 11SE37, Roseburia sp. 11SE38, Shuttleworthia satelles, Shuttleworthia sp. MSX8B, and Shuttleworthia sp. oral taxon G69, wherein clade_478 comprises one or more bacteria selected from the group consisting of Faecalibacterium prausnitzii, Gemmiger formicilis, and Subdoligranulum variabile, and wherein clade_494 comprises one or more bacteria selected from the group consisting of Clostridium orbiscindens, Clostridium sp. NML 04A032, Flavonifractor plautii, Pseudoflavonifractor capillosus, and Ruminococcaceae bacterium D16.

17. The method of claim 14 or 15, wherein clade_262 comprises one or more bacteria of Ruminococcus torques, wherein clade_360 comprises one or more bacteria of Dorea longicatena, wherein clade_396 comprises one or more bacteria of Eubacterium hallii,

wherein clade_444 comprises one or more bacteria of Eubacterium rectale, wherein clade_478 comprises one or more bacteria of Faecalibacterium prausnitzii, and wherein clade_494 comprises one or more bacteria of Pseudoflavonifractor capillosus.

18. The method of claim 14 or 15, wherein clade_262 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1048, Seq. ID No.: 1049, Seq. ID No.: 1057, Seq. ID No.: 1663, Seq. ID No.: 1670, Seq. ID No.: 588, Seq. ID No.: 607, and Seq. ID No.: 674, wherein clade_360 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1050, Seq. ID No.: 1051, Seq. ID No.: 1053, Seq. ID No.: 1058, Seq. ID No.: 1661, Seq. ID No.: 1668, Seq. ID No.: 773, and Seq. ID No.: 774, wherein clade_396 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 161, Seq. ID No.: 288, Seq. ID No.: 551, Seq. ID No.: 6, Seq. ID No.: 613, Seq. ID No.: 848, and Seq. ID No.: 875, wherein clade_444 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1045, Seq. ID No.: 1634, Seq. ID No.: 1635, Seq. ID No.: 1636, Seq. ID No.: 1637, Seq. ID No.: 1638, Seq. ID No.: 1639, Seq. ID No.: 1640, Seq. ID No.: 1641, Seq. ID No.: 1728, Seq. ID No.: 1729, Seq. ID No.: 1730, Seq. ID No.: 456, Seq. ID No.: 856, and Seq. ID No.: 865, wherein clade_478 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1896, Seq. ID No.: 880, and Seq. ID No.: 932, and wherein clade_494 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1591, Seq. ID No.: 1655, Seq. ID No.: 609, Seq. ID No.: 637, and Seq. ID No.: 886.

19. The method of claim 14 or 15, wherein clade_262 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1048, Seq. ID No.: 1049, Seq. ID No.: 1057, Seq. ID No.: 1663, Seq. ID No.: 1670, Seq. ID No.: 588, Seq. ID No.: 607, and Seq. ID No.: 674, wherein clade_360 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1050, Seq. ID No.: 1051, Seq. ID No.: 1053, Seq. ID No.: 1058, Seq. ID No.: 1661, Seq. ID No.: 1668, Seq. ID No.: 773, and Seq. ID No.: 774, wherein clade_396 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 161, Seq. ID No.: 288, Seq. ID No.: 551, Seq. ID No.: 6, Seq. ID No.: 613, Seq. ID No.: 848, and Seq. ID No.: 875, wherein clade_444 comprises one more bacteria selected from the group

consisting of bacteria having 16S sequences Seq. ID No.: 1045, Seq. ID No.: 1634, Seq. ID No.: 1635, Seq. ID No.: 1636, Seq. ID No.: 1637, Seq. ID No.: 1638, Seq. ID No.: 1639, Seq. ID No.: 1640, Seq. ID No.: 1641, Seq. ID No.: 1728, Seq. ID No.: 1729, Seq. ID No.: 1730, Seq. ID No.: 456, Seq. ID No.: 856, and Seq. ID No.: 865, wherein clade_478 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1896, Seq. ID No.: 880, and Seq. ID No.: 932, and wherein clade_494 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1591, Seq. ID No.: 1655, Seq. ID No.: 609, Seq. ID No.: 637, and Seq. ID No.: 886.

20. The method of claim 14 or 15, wherein clade_262 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1670, wherein clade_360 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 774, wherein clade_396 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 848, wherein clade_444 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 856, wherein clade_478 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 880, and wherein clade_494 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1591.

21. The method of claim 14 or 15, wherein clade_262 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1670, wherein clade_360 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 774, wherein clade_396 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 848, wherein clade_444 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 856, wherein clade_478 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 880, and wherein clade_494 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1591.

22. The method of claim 5, wherein the network ecology comprises N462.S and the therapeutic bacterial composition comprises at least one bacterium selected from each of clade_262, clade_360, and clade_478.

23. The method of claim 5, wherein the network ecology comprises N462.S and the therapeutic bacterial composition consists essentially of at least one bacterium selected from each of clade_262, clade_360, and clade_478.

24. The method of claim 22 or claim 23, wherein clade_262 comprises one or more bacteria selected from the group consisting of Clostridium glycyrrhizinilyticum, Clostridium nexile, Coprococcus comes, Lachnospiraceae bacterium 1_1_57FAA, Lachnospiraceae bacterium 1_4_56FAA, Lachnospiraceae bacterium 8_1_57FAA, Ruminococcus lactaris, and Ruminococcus torques, wherein clade_360 comprises one or more bacteria selected from the group consisting of Dorea formicigenerans, Dorea longicatena, Lachnospiraceae bacterium 2_1_46FAA, Lachnospiraceae bacterium 2_1_58FAA, Lachnospiraceae bacterium 4_1_37FAA, Lachnospiraceae bacterium 9_1_43BFAA, Ruminococcus gnavus, and Ruminococcus sp. ID8, and wherein clade_478 comprises one or more bacteria selected from the group consisting of Faecalibacterium prausnitzii, Gemmiger formicilis, and Subdoligranulum variabile.

25. The method of claim 22 or claim 23, wherein clade_262 comprises one or more bacteria of Coprococcus comes, wherein clade_360 comprises one or more bacteria of Dorea longicatena, and wherein clade_478 comprises one or more bacteria selected from the group consisting Faecalibacterium prausnitzii and Subdoligranulum variabile.

26. The method of claim 22 or claim 23, wherein clade_262 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1048, Seq. ID No.: 1049, Seq. ID No.: 1057, Seq. ID No.: 1663, Seq. ID No.: 1670, Seq. ID No.: 588, Seq. ID No.: 607, and Seq. ID No.: 674, wherein clade_360 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1050, Seq. ID No.: 1051, Seq. ID No.: 1053, Seq. ID No.: 1058, Seq. ID No.: 1661, Seq. ID No.: 1668, Seq. ID No.: 773, and Seq. ID No.: 774, and wherein clade_478 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1896, Seq. ID No.: 880, and Seq. ID No.: 932.

27. The method of claim 22 or claim 23, wherein clade_262 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1048, Seq. ID No.: 1049, Seq. ID No.: 1057, Seq. ID No.: 1663, Seq. ID No.: 1670, Seq. ID No.: 588, Seq. ID No.: 607, and Seq. ID No.: 674, wherein clade_360 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1050, Seq. ID No.: 1051, Seq. ID No.: 1053, Seq. ID No.: 1058, Seq. ID No.: 1661, Seq. ID No.: 1668,

Seq. ID No.: 773, and Seq. ID No.: 774, and wherein clade_478 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1896, Seq. ID No.: 880, and Seq. ID No.: 932.

28. The method of claim 22 or claim 23, wherein clade_262 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 674, wherein clade_360 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 774, and wherein clade_478 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1896 and Seq. ID No.: 880.

29. The method of claim 22 or claim 23, wherein clade_262 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 674, wherein clade_360 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 774, and wherein clade_478 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1896 and Seq. ID No.: 880.

30. The method of claim 5, wherein the network ecology comprises N512.S and the therapeutic bacterial composition comprises at least one bacterium selected from each of clade_262, clade_360, and clade_444.

31. The method of claim 5, wherein the network ecology comprises N512.S and the therapeutic bacterial composition consists essentially of at least one bacterium selected from each of clade_262, clade_360, and clade_444.

32. The method of claim 30 or claim 31, wherein clade_262 comprises one or more bacteria selected from the group consisting of Clostridium glycyrrhizinilyticum, Clostridium nexile, Coprococcus comes, Lachnospiraceae bacterium 1_1_57FAA, Lachnospiraceae bacterium 1_4_56FAA, Lachnospiraceae bacterium 8_1_57FAA, Ruminococcus lactaris, and Ruminococcus torques, wherein clade_360 comprises one or more bacteria selected from the group consisting of Dorea formicigenerans, Dorea longicatena, Lachnospiraceae bacterium 2_1_46FAA, Lachnospiraceae bacterium 2_1_58FAA, Lachnospiraceae bacterium 4_1_37FAA, Lachnospiraceae bacterium 9_1_43BFAA, Ruminococcus gnavus, and Ruminococcus sp. ID8, and wherein clade_444 comprises one or more bacteria selected from the group consisting of Butyrivibrio fibrisolvens, Eubacterium rectale, Eubacterium sp. oral clone GI038, Lachnobacterium bovis, Roseburia cecicola, Roseburia faecalis, Roseburia faecis, Roseburia hominis, Roseburia intestinalis, Roseburia inulinivorans, Roseburia sp.

11SE37, Roseburia sp. 11SE38, Shuttleworthia satelles, Shuttleworthia sp. MSX8B, and Shuttleworthia sp. oral taxon G69.

33. The method of claim 30 or claim 31, wherein clade_262 comprises one or more bacteria selected from the group consisting of Coprococcus comes and Ruminococcus torques, wherein clade_360 comprises one or more bacteria of Dorea longicatena, and wherein clade_444 comprises one or more bacteria of Eubacterium rectale.

34. The method of claim 30 or claim 31, wherein clade_262 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1048, Seq. ID No.: 1049, Seq. ID No.: 1057, Seq. ID No.: 1663, Seq. ID No.: 1670, Seq. ID No.: 588, Seq. ID No.: 607, and Seq. ID No.: 674, wherein clade_360 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1050, Seq. ID No.: 1051, Seq. ID No.: 1053, Seq. ID No.: 1058, Seq. ID No.: 1661, Seq. ID No.: 1668, Seq. ID No.: 773, and Seq. ID No.: 774, and wherein clade_444 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1045, Seq. ID No.: 1634, Seq. ID No.: 1635, Seq. ID No.: 1636, Seq. ID No.: 1637, Seq. ID No.: 1638, Seq. ID No.: 1639, Seq. ID No.: 1640, Seq. ID No.: 1641, Seq. ID No.: 1728, Seq. ID No.: 1729, Seq. ID No.: 1730, Seq. ID No.: 456, Seq. ID No.: 856, and Seq. ID No.: 865.

35. The method of claim 30 or claim 31, wherein clade_262 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1048, Seq. ID No.: 1049, Seq. ID No.: 1057, Seq. ID No.: 1663, Seq. ID No.: 1670, Seq. ID No.: 588, Seq. ID No.: 607, and Seq. ID No.: 674, wherein clade_360 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1050, Seq. ID No.: 1051, Seq. ID No.: 1053, Seq. ID No.: 1058, Seq. ID No.: 1661, Seq. ID No.: 1668, Seq. ID No.: 773, and Seq. ID No.: 774, and wherein clade_444 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1045, Seq. ID No.: 1634, Seq. ID No.: 1635, Seq. ID No.: 1636, Seq. ID No.: 1637, Seq. ID No.: 1638, Seq. ID No.: 1639, Seq. ID No.: 1640, Seq. ID No.: 1641, Seq. ID No.: 1728, Seq. ID No.: 1729, Seq. ID No.: 1730, Seq. ID No.: 456, Seq. ID No.: 856, and Seq. ID No.: 865.

36. The method of claim 30 or claim 31, wherein clade_262 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1670 and Seq. ID No.: 674, wherein clade_360 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having

97% or greater identity to Seq. ID No.: 774, and wherein clade_444 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 856.

37. The method of claim 30 or claim 31, wherein clade_262 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1670 and Seq. ID No.: 674, wherein clade_360 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 774, and wherein clade_444 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 856.

38. The method of claim 5, wherein the network ecology comprises N845 and the therapeutic bacterial composition comprises at least one bacterium selected from each of clade_262, clade_360, and clade_378.

39. The method of claim 5, wherein the network ecology comprises N845 and the therapeutic bacterial composition consists essentially of at least one bacterium selected from each of clade_262, clade_360, and clade_378.

40. The method of claim 38 or claim 39, wherein clade_262 comprises one or more bacteria selected from the group consisting of Clostridium glycyrrhizinilyticum, Clostridium nexile, Coprococcus comes, Lachnospiraceae bacterium 1_1_57FAA, Lachnospiraceae bacterium 1_4_56FAA, Lachnospiraceae bacterium 8_1_57FAA, Ruminococcus lactaris, and Ruminococcus torques, wherein clade_360 comprises one or more bacteria selected from the group consisting of Dorea formicigenerans, Dorea longicatena, Lachnospiraceae bacterium 2_1_46FAA, Lachnospiraceae bacterium 2_1_58FAA, Lachnospiraceae bacterium 4_1_37FAA, Lachnospiraceae bacterium 9_1_43BFAA, Ruminococcus gnavus, and Ruminococcus sp. ID8, and wherein clade_378 comprises one or more bacteria selected from the group consisting of Bacteroides barnesiae, Bacteroides coprocola, Bacteroides coprophilus, Bacteroides dorei, Bacteroides massiliensis, Bacteroides plebeius, Bacteroides sp. 3_1_33FAA, Bacteroides sp. 3_1_40A, Bacteroides sp. 4_3_47FAA, Bacteroides sp. 9_1_42FAA, Bacteroides sp. NB_8, and Bacteroides vulgatus.

41. The method of claim 38 or claim 39, wherein clade_262 comprises one or more bacteria of Coprococcus comes, wherein clade_360 comprises one or more bacteria of Dorea longicatena, and wherein clade_378 comprises one or more bacteria of Bacteroides dorei.

42. The method of claim 38 or claim 39, wherein clade_262 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1048, Seq. ID No.: 1049, Seq. ID No.: 1057, Seq. ID No.: 1663, Seq.

ID No.: 1670, Seq. ID No.: 588, Seq. ID No.: 607, and Seq. ID No.: 674, wherein clade_360 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1050, Seq. ID No.: 1051, Seq. ID No.: 1053, Seq. ID No.: 1058, Seq. ID No.: 1661, Seq. ID No.: 1668, Seq. ID No.: 773, and Seq. ID No.: 774, and wherein clade_378 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 267, Seq. ID No.: 272, Seq. ID No.: 273, Seq. ID No.: 274, Seq. ID No.: 284, Seq. ID No.: 289, Seq. ID No.: 309, Seq. ID No.: 310, Seq. ID No.: 313, Seq. ID No.: 314, Seq. ID No.: 323, and Seq. ID No.: 331.

43. The method of claim 38 or claim 39, wherein clade_262 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1048, Seq. ID No.: 1049, Seq. ID No.: 1057, Seq. ID No.: 1663, Seq. ID No.: 1670, Seq. ID No.: 588, Seq. ID No.: 607, and Seq. ID No.: 674, wherein clade_360 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1050, Seq. ID No.: 1051, Seq. ID No.: 1053, Seq. ID No.: 1058, Seq. ID No.: 1661, Seq. ID No.: 1668, Seq. ID No.: 773, and Seq. ID No.: 774, and wherein clade_378 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 267, Seq. ID No.: 272, Seq. ID No.: 273, Seq. ID No.: 274, Seq. ID No.: 284, Seq. ID No.: 289, Seq. ID No.: 309, Seq. ID No.: 310, Seq. ID No.: 313, Seq. ID No.: 314, Seq. ID No.: 323, and Seq. ID No.: 331.

44. The method of claim 38 or claim 39, wherein clade_262 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 674, wherein clade_360 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 774, and wherein clade_378 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 274.

45. The method of claim 38 or claim 39, wherein clade_262 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 674, wherein clade_360 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 774, and wherein clade_378 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 274.

46. The method of claim 5, wherein the network ecology comprises N982 and the therapeutic bacterial composition comprises at least one bacterium selected from each of clade_172, clade_262, and clade_396.

47. The method of claim 5, wherein the network ecology comprises N982 and the therapeutic bacterial composition consists essentially of at least one bacterium selected from each of clade_172, clade_262, and clade_396.

48. The method of claim 46 or claim 47, wherein clade_172 comprises one or more bacteria selected from the group consisting of Bifidobacteriaceae genomosp. C1, Bifidobacterium adolescentis, Bifidobacterium angulatum, Bifidobacterium animalis, Bifidobacterium breve, Bifidobacterium catenulatum, Bifidobacterium dentium, Bifidobacterium gallicum, Bifidobacterium infantis, Bifidobacterium kashiwanohense, Bifidobacterium longum, Bifidobacterium pseudocatenulatum, Bifidobacterium pseudolongum, Bifidobacterium scardovii, Bifidobacterium sp. HM2, Bifidobacterium sp. HMLN12, Bifidobacterium sp. M45, Bifidobacterium sp. MSX5B, Bifidobacterium sp. TM_7, and Bifidobacterium thermophilum, wherein clade_262 comprises one or more bacteria selected from the group consisting of Clostridium glycyrrhizinilyticum, Clostridium nexile, Coprococcus comes, Lachnospiraceae bacterium 1_1_57FAA, Lachnospiraceae bacterium 1_4_56FAA, Lachnospiraceae bacterium 8_1_57FAA, Ruminococcus lactaris, and Ruminococcus torques, and wherein clade_396 comprises one or more bacteria selected from the group consisting of Acetivibrio ethanolgignens, Anaerosporobacter mobilis, Bacteroides pectinophilus, Clostridium aminovalericum, Clostridium phytofermentans, Eubacterium hallii, and Eubacterium xylanophilum.

49. The method of claim 46 or claim 47, wherein clade_172 comprises one or more bacteria of Bifidobacterium longum, wherein clade_262 comprises one or more bacteria of Coprococcus comes, and wherein clade_396 comprises one or more bacteria of Eubacterium hallii.

50. The method of claim 46 or claim 47, wherein clade_172 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 345, Seq. ID No.: 346, Seq. ID No.: 347, Seq. ID No.: 348, Seq. ID No.: 350, Seq. ID No.: 351, Seq. ID No.: 352, Seq. ID No.: 353, Seq. ID No.: 354, Seq. ID No.: 355, Seq. ID No.: 356, Seq. ID No.: 357, Seq. ID No.: 358, Seq. ID No.: 359, Seq. ID No.: 360, Seq. ID No.: 361, Seq. ID No.: 362, Seq. ID No.: 363, Seq. ID No.: 364, and Seq. ID No.: 365, wherein clade_262 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.:

1048, Seq. ID No.: 1049, Seq. ID No.: 1057, Seq. ID No.: 1663, Seq. ID No.: 1670, Seq. ID No.: 588, Seq. ID No.: 607, and Seq. ID No.: 674, and wherein clade_396 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 161, Seq. ID No.: 288, Seq. ID No.: 551, Seq. ID No.: 6, Seq. ID No.: 613, Seq. ID No.: 848, and Seq. ID No.: 875.

51. The method of claim 46 or claim 47, wherein clade_172 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 345, Seq. ID No.: 346, Seq. ID No.: 347, Seq. ID No.: 348, Seq. ID No.: 350, Seq. ID No.: 351, Seq. ID No.: 352, Seq. ID No.: 353, Seq. ID No.: 354, Seq. ID No.: 355, Seq. ID No.: 356, Seq. ID No.: 357, Seq. ID No.: 358, Seq. ID No.: 359, Seq. ID No.: 360, Seq. ID No.: 361, Seq. ID No.: 362, Seq. ID No.: 363, Seq. ID No.: 364, and Seq. ID No.: 365, wherein clade_262 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1048, Seq. ID No.: 1049, Seq. ID No.: 1057, Seq. ID No.: 1663, Seq. ID No.: 1670, Seq. ID No.: 588, Seq. ID No.: 607, and Seq. ID No.: 674, and wherein clade_396 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 161, Seq. ID No.: 288, Seq. ID No.: 551, Seq. ID No.: 6, Seq. ID No.: 613, Seq. ID No.: 848, and Seq. ID No.: 875.

52. The method of claim 46 or claim 47, wherein clade_172 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 356, wherein clade_262 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 674, and wherein clade_396 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 848.

53. The method of claim 46 or claim 47, wherein clade_172 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 356, wherein clade_262 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 674, and wherein clade_396 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 848.

54. The method of claim 5, wherein the network ecology comprises N651.S and the therapeutic bacterial composition comprises at least one bacterium selected from each of clade_444, clade_516, and clade_522.

55. The method of claim 5, wherein the network ecology comprises N651.S and the therapeutic bacterial composition consists essentially of at least one bacterium selected from each of clade_444, clade_516, and clade_522.

56. The method of claim 54 or claim 55, wherein clade_444 comprises one or more bacteria selected from the group consisting of Butyrivibrio fibrisolvens, Eubacterium rectale, Eubacterium sp. oral clone GI038, Lachnobacterium bovis, Roseburia cecicola, Roseburia faecalis, Roseburia faecis, Roseburia hominis, Roseburia intestinalis, Roseburia inulinivorans, Roseburia sp. 11SE37, Roseburia sp. 11SE38, Shuttleworthia satelles, Shuttleworthia sp. MSX8B, and Shuttleworthia sp. oral taxon G69, wherein clade_516 comprises one or more bacteria selected from the group consisting of Anaerotruncus colihominis, Clostridium methylpentosum, Clostridium sp. YIT 12070, Hydrogenoanaerobacterium saccharovorans, Ruminococcus albus, and Ruminococcus flavefaciens, and wherein clade_522 comprises one or more bacteria selected from the group consisting of Bacteroides galacturonicus, Eubacterium eligens, Lachnospira multipara, Lachnospira pectinoschiza, and Lactobacillus rogosae.

57. The method of claim 54 or claim 55, wherein clade_444 comprises one or more bacteria of Roseburia inulinivorans, wherein clade_516 comprises one or more bacteria of Anaerotruncus colihominis, and wherein clade_522 comprises one or more bacteria of Eubacterium eligens.

58. The method of claim 54 or claim 55, wherein clade_444 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1045, Seq. ID No.: 1634, Seq. ID No.: 1635, Seq. ID No.: 1636, Seq. ID No.: 1637, Seq. ID No.: 1638, Seq. ID No.: 1639, Seq. ID No.: 1640, Seq. ID No.: 1641, Seq. ID No.: 1728, Seq. ID No.: 1729, Seq. ID No.: 1730, Seq. ID No.: 456, Seq. ID No.: 856, and Seq. ID No.: 865, wherein clade_516 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1005, Seq. ID No.: 164, Seq. ID No.: 1656, Seq. ID No.: 1660, Seq. ID No.: 606, and Seq. ID No.: 642, and wherein clade_522 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1046, Seq. ID No.: 1047, Seq. ID No.: 1114, Seq. ID No.: 280, and Seq. ID No.: 845.

59. The method of claim 54 or claim 55, wherein clade_444 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1045, Seq. ID No.: 1634, Seq. ID No.: 1635, Seq. ID No.: 1636, Seq. ID No.: 1637, Seq. ID No.: 1638, Seq. ID No.: 1639, Seq. ID No.: 1640, Seq. ID No.: 1641, Seq. ID No.: 1728, Seq. ID No.:

1729, Seq. ID No.: 1730, Seq. ID No.: 456, Seq. ID No.: 856, and Seq. ID No.: 865, wherein clade_516 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1005, Seq. ID No.: 164, Seq. ID No.: 1656, Seq. ID No.: 1660, Seq. ID No.: 606, and Seq. ID No.: 642, and wherein clade_522 comprises one more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1046, Seq. ID No.: 1047, Seq. ID No.: 1114, Seq. ID No.: 280, and Seq. ID No.: 845.

60. The method of claim 54 or claim 55, wherein clade_444 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 1639, wherein clade_516 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 164, and wherein clade_522 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences having 97% or greater identity to Seq. ID No.: 845.

61. The method of claim 54 or claim 55, wherein clade_444 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 1639, wherein clade_516 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 164, and wherein clade_522 comprises one or more bacteria selected from the group consisting of bacteria having 16S sequences Seq. ID No.: 845.

62. The method of any of claims 0-61 wherein said composition further comprises a pharmaceutically-acceptable excipient.

63. The method of claim 62, wherein the therapeutic bacterial composition is substantially depleted of a residual habitat product of a fecal material.

64. The method of any of claims 1-61, wherein said composition is formulated for oral administration.

65. The method of any of claims 1-63, wherein said composition is capable of inducing the formation of IgA, RegIII-gamma, IL-10, regulatory T cells, TGF-beta, alpha-defensin, beta-defensin, or an antimicrobial peptide in the mammalian subject.

66. The method of any of claims 1-61, wherein said composition is comestible.

67. A composition, comprising any of the compositions administered according to the methods of claims 1-61.

68. A dosage unit comprising predetermined ratios of the isolated bacteria present in the network ecology of any of claims 1-61.

69. A method for producing short chain fatty acids (SCFA) within a mammalian subject,

comprising: administering to said mammalian subject in need thereof an effective amount of a therapeutic bacterial composition, said therapeutic bacterial composition comprising a plurality of isolated bacteria or a purified bacterial preparation, the plurality of isolated bacteria of the purified bacterial preparation capable of forming one or a plurality of bacterial functional pathways, the one or plurality of bacterial functional pathways capable of forming a functional network ecology selected from the group consisting of N262.S, N290.S, N284.S, N271.S, N282.S, N288.S, N302.S, N279.S, N310.S, N323.S, N331.S, N332.S, N301.S, N312.S, N339.S, N325.S, N340.S, N341.S, N346.S, N338.S, N336.S, N345.S, N355.S, N356.S, N343.S, N329.S, N361.S, N353.S, N381.S, N344.S, N352.S, N357.S, N358.S, N369.S, N372.S, N375.S, N380.S, N374.S, N377.S, N368.S, N370.S, N373.S, N376.S, N389.S, N394.S, N431.S, N434.S, N390.S, N397.S, N387.S, N440.S, N396.S, N399.S, N403.S, N414.S, N430.S, N432.S, N436.S, N437.S, N457.S, N545, N386.S, N402.S, N405.S, N415.S, N421.S, N422.S, N423.S, N458.S, N459.S, N493.S, N416.S, N439.S, N447.S, N490.S, N526, N429.S, N433.S, N448.S, N488.S, N508.S, N509.S, N510.S, N511.S, N408.S, N446.S, N451.S, N474.S, N520.S, N521.S, N535.S, N516.S, N463.S, N518.S, N586, N450.S, N465.S, N519.S, N537.S, N419.S, N468.S, N477.S, N514.S, N382.S, N460.S, N462.S, N512.S, N517.S, N523.S, N547.S, N548.S, N577.S, N581.S, N585.S, N616.S, N466.S, N469.S, N480.S, N482.S, N484.S, N515.S, N533.S, N709, N730, N478.S, N572.S, N400.S, N543.S, N582.S, N621.S, N689, N769, N481.S, N525.S, N528.S, N534.S, N574.S, N580.S, N590.S, N591.S, N597.S, N664, N693, N530.S, N687, N470.S, N529.S, N539.S, N546.S, N570.S, N579.S, N602.S, N614.S, N648.S, N652.S, N655.S, N672.S, N681.S, N690.S, N692.S, N698.S, N737.S, N738.S, N785, N841, N878, N880, N881, N987, N988, N996, N1061, N479.S, N538.S, N542.S, N578.S, N609.S, N611.S, N617.S, N666.S, N675.S, N682.S, N844, N845, N846, N852, N876, N982, N1008, N649.S, N657.S, N678.S, N686.S, N710.S, N522.S, N651.S, N653.S, N654.S, N680.S, N712.S, N792, N802, N804, N807, N849, N858, N859, N875, N885, N942, N961, N972, N1051, N587.S, N589.S, N612.S, N625.S, N656.S, N714.S, N779, N781, N828, N829, N860, N894, N925, N927, N935, N947, N983, N1023, N441.S, N584.S, N794, N788, N524.S, N604.S, N610.S, N623.S, N663.S, N669.S, N676.S, N703.S, N775.S, N777.S, N780.S, N817.S, N827.S, N836.S, N871.S, N874.S, N898.S, N907.S, N998.S, N1088, N1089, N660.S, N665.S, N667.S, N733.S, N734.S, N739.S, N741.S, N782.S, N789.S, N796.S, N798.S, N800.S, N809.S, N816.S, N842.S, N843.S, N869.S, N986.S, N995.S, N1002.S, N1004.S, N1019.S, N1093, N668.S, N685.S, N835.S, N851.S, N464.S, N695.S, N776.S, N793.S, N815.S, N833.S, N891.S, N1070.S, N1092, N795.S, N797.S, N808.S, N811.S, N826.S,

N830.S, N832.S, N840.S, N945.S, N960.S, N968.S, N1091, N805.S, N822.S, N928.S, N936.S, N1078.S, and N913.S.

70. The method of claim 69, wherein the functional network ecology is selected from the group consisting of N1008, N1023, N1051, N1061, N1070.S, N1088, N1089, N1092, N381.S, N382.S, N399.S, N400.S, N402.S, N403.S, N414.S, N429.S, N430.S, N432.S, N433.S, N436.S, N437.S, N439.S, N441.S, N447.S, N448.S, N457.S, N460.S, N462.S, N463.S, N464.S, N470.S, N474.S, N488.S, N490.S, N493.S, N508.S, N509.S, N510.S, N511.S, N512.S, N514.S, N515.S, N517.S, N518.S, N519.S, N520.S, N523.S, N524.S, N528.S, N529.S, N539.S, N543.S, N546.S, N547.S, N548.S, N570.S, N574.S, N577.S, N579.S, N580.S, N582.S, N584.S, N585.S, N589.S, N591.S, N597.S, N602.S, N604.S, N609.S, N610.S, N611.S, N612.S, N614.S, N616.S, N621.S, N623.S, N625.S, N648.S, N651.S, N652.S, N653.S, N654.S, N655.S, N660.S, N663.S, N664, N665.S, N666.S, N669.S, N672.S, N676.S, N681.S, N687, N689, N690.S, N692.S, N693, N695.S, N698.S, N703.S, N709, N712.S, N714.S, N730, N734.S, N737.S, N738.S, N769, N775.S, N777.S, N779, N780.S, N781, N785, N788, N792, N793.S, N794, N797.S, N798.S, N802, N804, N807, N817.S, N827.S, N828, N830.S, N832.S, N833.S, N836.S, N840.S, N841, N844, N845, N849, N852, N858, N859, N860, N869.S, N871.S, N874.S, N875, N878, N880, N881, N885, N894, N898.S, N907.S, N913.S, N925, N927, N942, N947, N961, N968.S, N972, N982, N983, N986.S, N987, N988, N996, and N998.S.

71. The method of claim 70, wherein the functional network ecology is N528.S, and the plurality of bacterial functional pathways comprises the functional pathways of of KO:K00656, KO:K01069, KO:K01734, KO:K03417, KO:K03778, KO:K07246.

72. A method for catalyzing secondary metabolism of bile acids within a mammalian subject, comprising: administering to said mammalian subject in need thereof an effective amount of a therapeutic bacterial composition, said therapeutic bacterial composition comprising a plurality of isolated bacteria or a purified bacterial preparation, the plurality of isolated bacteria of the purified bacterial preparation capable of forming one or a plurality of bacterial functional pathways, the one or plurality of bacterial functional pathways capable of forming a functional network ecology selected from the group consisting of N262.S, N290.S, N284.S, N271.S, N282.S, N288.S, N302.S, N279.S, N310.S, N323.S, N331.S, N332.S, N301.S, N312.S, N339.S, N325.S, N340.S, N341.S, N346.S, N338.S, N336.S, N345.S, N355.S, N356.S, N343.S, N329.S, N361.S, N353.S, N381.S, N344.S, N352.S, N357.S, N358.S, N369.S, N372.S, N375.S, N380.S, N374.S, N377.S, N368.S, N370.S, N373.S, N376.S, N389.S, N394.S, N431.S, N434.S, N390.S, N397.S, N387.S, N440.S, N396.S,

N399.S, N403.S, N414.S, N430.S, N432.S, N436.S, N437.S, N457.S, N545, N386.S, N402.S, N405.S, N415.S, N421.S, N422.S, N423.S, N458.S, N459.S, N493.S, N416.S, N439.S, N447.S, N490.S, N526, N429.S, N433.S, N448.S, N488.S, N508.S, N509.S, N510.S, N511.S, N408.S, N446.S, N451.S, N474.S, N520.S, N521.S, N535.S, N516.S, N463.S, N518.S, N586, N450.S, N465.S, N519.S, N537.S, N419.S, N468.S, N477.S, N514.S, N382.S, N460.S, N462.S, N512.S, N517.S, N523.S, N547.S, N548.S, N577.S, N581.S, N585.S, N616.S, N466.S, N469.S, N480.S, N482.S, N484.S, N515.S, N533.S, N709, N730, N478.S, N572.S, N400.S, N543.S, N582.S, N621.S, N689, N769, N481.S, N525.S, N528.S, N534.S, N574.S, N580.S, N590.S, N591.S, N597.S, N664, N693, N530.S, N687, N470.S, N529.S, N539.S, N546.S, N570.S, N579.S, N602.S, N614.S, N648.S, N652.S, N655.S, N672.S, N681.S, N690.S, N692.S, N698.S, N737.S, N738.S, N785, N841, N878, N880, N881, N987, N988, N996, N1061, N479.S, N538.S, N542.S, N578.S, N609.S, N611.S, N617.S, N666.S, N675.S, N682.S, N844, N845, N846, N852, N876, N982, N1008, N649.S, N657.S, N678.S, N686.S, N710.S, N522.S, N651.S, N653.S, N654.S, N680.S, N712.S, N792, N802, N804, N807, N849, N858, N859, N875, N885, N942, N961, N972, N1051, N587.S, N589.S, N612.S, N625.S, N656.S, N714.S, N779, N781, N828, N829, N860, N894, N925, N927, N935, N947, N983, N1023, N441.S, N584.S, N794, N788, N524.S, N604.S, N610.S, N623.S, N663.S, N669.S, N676.S, N703.S, N775.S, N777.S, N780.S, N817.S, N827.S, N836.S, N871.S, N874.S, N898.S, N907.S, N998.S, N1088, N1089, N660.S, N665.S, N667.S, N733.S, N734.S, N739.S, N741.S, N782.S, N789.S, N796.S, N798.S, N800.S, N809.S, N816.S, N842.S, N843.S, N869.S, N986.S, N995.S, N1002.S, N1004.S, N1019.S, N1093, N668.S, N685.S, N835.S, N851.S, N464.S, N695.S, N776.S, N793.S, N815.S, N833.S, N891.S, N1070.S, N1092, N795.S, N797.S, N808.S, N811.S, N826.S, N830.S, N832.S, N840.S, N945.S, N960.S, N968.S, N1091, N805.S, N822.S, N928.S, N936.S, N1078.S, and N913.S.

73. The method of claim 72, wherein the functional network ecology is selected from the group consisting of N1008, N1023, N1051, N1061, N1070.S, N1088, N1089, N1092, N381.S, N382.S, N399.S, N400.S, N402.S, N403.S, N414.S, N429.S, N430.S, N432.S, N433.S, N436.S, N437.S, N439.S, N441.S, N447.S, N448.S, N457.S, N460.S, N462.S, N463.S, N464.S, N470.S, N474.S, N488.S, N490.S, N493.S, N508.S, N509.S, N510.S, N511.S, N512.S, N514.S, N515.S, N517.S, N518.S, N519.S, N520.S, N523.S, N524.S, N529.S, N539.S, N543.S, N546.S, N547.S, N548.S, N570.S, N574.S, N577.S, N579.S, N580.S, N582.S, N584.S, N585.S, N589.S, N591.S, N597.S, N602.S, N604.S, N609.S, N610.S, N611.S, N612.S, N614.S, N616.S, N621.S, N623.S, N625.S, N648.S, N651.S,

N652.S, N653.S, N654.S, N655.S, N660.S, N663.S, N664, N665.S, N666.S, N669.S, N672.S, N676.S, N681.S, N687, N689, N690.S, N692.S, N693, N695.S, N698.S, N703.S, N709, N712.S, N714.S, N730, N734.S, N737.S, N738.S, N769, N775.S, N777.S, N779, N780.S, N781, N785, N788, N792, N793.S, N794, N797.S, N798.S, N802, N804, N807, N817.S, N827.S, N828, N830.S, N832.S, N833.S, N836.S, N840.S, N841, N844, N845, N849, N852, N858, N859, N860, N869.S, N871.S, N874.S, N875, N878, N880, N881, N885, N894, N898.S, N907.S, N913.S, N925, N927, N942, N947, N961, N968.S, N972, N982, N983, N986.S, N987, N988, N996, and N998.S.

74. The method of claim 73, wherein the functional network ecology is N660.S and the plurality of bacterial functional pathways comprises the functional pathways of of KO:K00656, and KO:K01442.

75. The method of any of claims 69-74, wherein said composition further comprises a pharmaceutically-acceptable excipient.

76. The method of any of claims 69-74, wherein said composition is formulated for oral administration.

77. The method of any of claims 69-74, wherein said composition is capable of inducing the formation of butyrate, propionate, acetate, 7-deoxybile acids, deoxycholate acide (DCA) and lithocholic acid (LCA)in the mammalian subject.

78. The method of any of claims 69-74, wherein said composition is capable of inducing the depletion of glucose, pyruvate, lactate, cellulose, fructans, starch, xylans, pectins, taurocholate, glycocholate, ursocholate, cholate, glycochenodeoxycholate, taurochenodeoxycholate, ursodeoxycholate, or chenodeoxycholate; or the formation and depletion of intermediary metabolites acetyl-CoA, butyryl-CoA, propanoyl-CoA, chenodeoxycholoyl-CoA, or ursodeoxycholoyl-CoA in the mammalian subject.

79. The method of any of claims 69-74, wherein the composition is formulated with one or more prebiotic compounds.

80. The method of any of claims 69-74, wherein said composition is comestible.

81. A composition, comprising any of the compositions administered according to the methods of claims 69-74.

82. A dosage unit comprising predetermined ratios of the isolated bacteria present in the network ecology of any of claims 69-74.

83. A pharmaceutical formulation comprising a purified bacterial population consisting essentially of a bacterial network capable of forming germinable bacterial spores, wherein the bacterial network is present in an amount effective to populate the gastrointestinal tract in a

mammalian subject in need thereof to whom the formulation is administered, under conditions such that at least one type of bacteria not detectably present in the bacterial network or in the gastrointestinal tract prior to administration is augmented.

84. A pharmaceutical formulation comprising a purified bacterial population comprising a plurality of bacterial entities, wherein the bacterial entities are present in an amount effective to induce the formation of a functional bacterial network in the gastrointestinal tract in a mammalian subject in need thereof to whom the formulation is administered.

85. The formulation of claim 84, wherein the functional bacterial network comprises bacterial entities present in the formulation.

86. The formulation of claim 84, wherein the functional bacterial network comprises bacterial entities present in the gastrointestinal tract at the time of administration.

87. The formulation of claim 84, wherein the functional bacterial network comprises bacterial entities not present in the formulation or the gastrointestinal tract at the time of administration.

88. The formulation of claim 83 or claim 84, provided as an oral finished pharmaceutical dosage form including at least one pharmaceutically acceptable carrier.

89. The formulation of claim 83 or claim 84, wherein the mammalian subject suffers from a dysbiosis comprising a gastrointestinal disease, disorder or condition selected from the group consisting of *Clostridium difficile* Associated Diarrhea (CDAD), Type 2 Diabetes, Type 1 Diabetes, Obesity, Irritable Bowel Syndrome (IBS), Irritable Bowel Disease (IBD), Ulcerative Colitis, Crohn's Disease, colitis, colonization with a pathogen or pathobiont, and infection with a drug-resistant pathogen or pathobiont.

90. The formulation of claim 83, wherein the bacterial network is purified from a fecal material subjected to a treatment step that comprises depleting or inactivating a pathogenic material.

91. The formulation of claim 90, wherein the bacterial network is substantially depleted of a detectable level of a first pathogenic material.

92. The formulation of claim 90, wherein the bacterial network is substantially depleted of a residual habitat product of the fecal material.

93. A method of treating or preventing a dysbiosis in a human subject, comprising administering to the human subject the formulation of claim 83 or claim 84 in an amount effective to treat or prevent a dysbiosis or to reduce the severity of at least one symptom of the dysbiosis in the human subject to whom the formulation is administered.

94. The method of claim 93, wherein the formulation is provided as an oral finished

pharmaceutical dosage form including at least one pharmaceutically acceptable carrier, the dosage form comprising at least about $1x10^4$ colony forming units of bacterial spores per dose of the composition, wherein the bacterial spores comprise at least two bacterial entities comprising 16S rRNA sequences at least 97% identical to the nucleic acid sequences selected from the group consisting of Seq. ID No.: 674, Seq. ID No.: 1670, Seq. ID No.: 774, Seq. ID No.: 848, Seq. ID No.: 856, Seq. ID No.: 1639, Seq. ID No.: 880, Seq. ID No.: 1896, Seq. ID No.: 1591, Seq. ID No.: 164, Seq. ID No.: 845, and Seq. ID No.: 659.

95. The method of claim 93, wherein the administration of the formulation results in a reduction or an elimination of at least one pathogen and/or pathobiont present in the gastrointestinal tract when the therapeutic composition is administered.

96. The method of claim 93, wherein the administration of the formulation results in engraftment of at least one type of spore-forming bacteria present in the therapeutic composition.

97. The method of claim 93, wherein the administration of the formulation results in augmentation in the gastrointestinal tract of the subject to whom the formulation is administered of at least one type of bacteria not present in the formulation.

98. The method of claim 96, wherein the at least one type of spore-forming bacteria are not detectably present in the gastrointestinal tract of the subject to whom the formulation is administered when the formulation is administered.

99. The method of claim 93, wherein the administration of the formulation results in at least two of: i) reduction or elimination of at least one pathogen and/or pathobiont present in the gastrointestinal tract when the formulation is administered; ii) engraftment of at least one type of spore-forming bacteria present in the therapeutic composition; and iii) augmentation of at least one type of spore-forming or non-spore forming bacteria not present in the therapeutic composition.

100. The method of claim 90, wherein the administration of the therapeutic composition results in at reduction or elimination of at least one pathogen and/or pathobiont present in the gastrointestinal tract when the therapeutic composition is administered and at least one of: i) engraftment of at least one type of spore-forming bacteria present in the therapeutic composition; and ii) augmentation of at least one type of bacteria not present in the therapeutic composition.

101. A method of inducing engraftment of a bacterial population in the gastrointestinal tract of a human subject, comprising the step of administering to the human subject an orally acceptable pharmaceutical formulation comprising a purified bacterial network, under

conditions such that at least i) a subset of the spore-forming bacteria sustainably engraft within the gastrointestinal tract, or ii) at least one type of bacteria not present in the therapeutic composition is augmented within the gastrointestinal tract.

102. A pharmaceutical formulation comprising a purified first bacterial entity and a purified second bacterial entity, wherein the first bacterial entity comprises a first nucleic acid sequence encoding a first polypeptide capable of catalyzing a first chemical reaction, wherein the second bacterial entity comprises a second nucleic acid sequence encoding a second polypeptide capable of catalyzing a second chemical reaction, wherein the pharmaceutical formulation is formulated for oral administration to a mammalian subject in need thereof, wherein the first chemical reaction and the second chemical reaction are capable of occurring in the gastrointestinal tract of the mammalian subject under conditions such that a first product of the first chemical reaction, a substance present within said mammalian subject, or a combination of said first product with the substance is used as a substrate in the second chemical reaction to form a second product, wherein the second product induces a host cell response.

103. The formulation of claim 102, wherein said substance is a mammalian subject protein or a food-derived protein.

104. The pharmaceutical formulation of claim 102, wherein the host cell response comprises production by the host cell of a biological material.

105. The pharmaceutical formulation of claim 102, wherein the biological material comprises a cytokine, growth factor or signaling polypeptide.

106. The pharmaceutical formulation of claim 102, wherein the host cell response comprises an immune response.

107. The pharmaceutical formulation of claim 102, wherein the host cell response comprises decreased gastric motility.

108. The pharmaceutical formulation of claim 102, wherein the host cell response comprises change in host gene expression, increased host metabolism, reduced gut permeability, enhanced epithelial cell junction integrity, reduced lipolysis by the action of Lipoprotein Lipase in adipose tissue, decreased hepatic gluconeogenesis, increased insulin sensitivity, increased production of FGF-19, or change in energy harvesting and/or storage.

109. A pharmaceutical formulation comprising a purified first bacterial entity and a purified second bacterial entity, wherein the first bacterial entity and the second bacterial entity form a functional bacterial network in the gastrointestinal tract of a mammalian subject to whom the pharmaceutical formulation is administered, wherein the functional network

modulates the level and/or activity of a biological material capable of inducing a host cell response.

110. A pharmaceutical formulation comprising a purified first bacterial entity and a purified second bacterial entity, wherein the first bacterial entity and the second bacterial entity form a functional bacterial network in the gastrointestinal tract of a mammalian subject to whom the pharmaceutical formulation is administered, wherein the functional network induces the production of a biological material capable of inducing a host cell response.

111. A therapeutic composition, comprising a network of at least two bacterial entities, wherein the network comprises at least one keystone bacterial entity and at least one non-keystone bacterial entity, wherein the at least two bacterial entities are each provided in amounts effective for the treatment or prevention of a gastrointestinal disease, disorder or condition in a mammalian subject.

112. The composition of claim 111, wherein the network comprises at least three bacterial entities.

113. The composition of claim 111, wherein the network comprises at least three bacterial entities including at least two keystone bacterial entities.

114. A therapeutic composition, comprising a network of at least two keystone bacterial entities capable of forming germination-competent spores, wherein the at least two keystone bacterial entities are each provided in amounts effective for the treatment or prevention of a gastrointestinal disease, disorder or condition in a mammalian subject.

115. The therapeutic composition of claim 114, comprising a network of at least two keystone bacterial entities capable of forming germination-competent spores.

116. A therapeutic composition, comprising:

a first network of at least two bacterial entities, wherein the first network comprises a keystone bacterial entity and a non-keystone bacterial entity; and

a second network of at least two bacterial entities, wherein the second network comprises at least one keystone bacterial entity and at least one non-keystone bacterial entity,

wherein the networks are each provided in amounts effective for the treatment or prevention of a gastrointestinal disease, disorder or condition in a mammalian subject.

117. A therapeutic composition, comprising a network of at least two bacterial entities, wherein the network comprises a first keystone bacterial entity and a second keystone bacterial entity, wherein the two bacterial entities are each provided in amounts effective for

the treatment or prevention of a gastrointestinal disease, disorder or condition in a mammalian subject.

118. The composition of claim 117, wherein the first and second keystone bacterial entities are present in the same network.

119. The composition of claim 117, wherein the first and second keystone bacterial entities are present in different networks.

120. A diagnostic composition for the detection of a dysbiosis, comprising a first detection moiety capable of detecting a first keystone bacterial entity and a second detection moiety capable of detecting a first non-keystone bacterial entity, wherein the keystone bacterial entity and the non-keystone bacterial entity comprise a network, wherein the absence of at least one of the keystone bacterial entity and the non-keystone bacterial entity in a mammalian subject is indicative of a dysbiosis.

121. A method of altering a microbiome population present in a mammalian subject, comprising the steps of determining the presence of an incomplete network of bacterial entities in the gastrointestinal tract of the mammalian subject, and introducing to the gastrointestinal tract of the mammalian subject an effective amount of one or more supplemental bacterial entities not detectable in the gastrointestinal tract of the mammalian subject prior to such administration, under conditions such that the incomplete network is completed, thereby altering the microbiome population.

122. The method of claim 121, wherein the one or more supplemental bacterial entities become part of the incomplete network, thereby forming a complete network.

123. The method of claim 121, wherein the one or more supplemental bacterial entities alter the microbiota of the mammalian subject such that one or more additional bacterial entities complete the incomplete network.

124. The method of claim 121, where the one or more supplemental bacterial entities comprise a network.

125. A method for detection and correction of a dysbiosis in a mammalian subject in need thereof, comprising the steps of: providing a fecal sample from the mammalian subject comprising a plurality of bacterial entities; contacting the fecal sample with a first detection moiety capable of detecting a first bacterial entity present in an network; detecting the absence of the first bacterial entity in the fecal sample, thereby detecting a dysbiosis in the mammalian subject; and administering to the mammalian subject a composition comprising an effective amount of the first bacterial entity.

126. The method of claim 125, further comprising confirming that the dysbiosis in the

mammalian subject has been corrected.

127. A system for predicting a dysbiosis in a subject, the system comprising: a storage memory for storing a dataset associated with a sample obtained from the subject, wherein the dataset comprises content data for at least one network of bacterial entities; and a processor communicatively coupled to the storage memory for determining a score with an interpretation function wherein the score is predictive of dysbiosis in the subject.

128. A kit for diagnosis of a state of dysbiosis in a mammalian subject in need thereof, comprising a plurality of detection means suitable for use in detecting (1) a first bacterial entity comprising a keystone bacterial entity and (2) a second bacterial entity, wherein the first and second bacterial entities comprise a functional network ecology.



V 1 2 3 4 5 6 7 8 9
200 400 600 800 1000 1200 1400
Nucleic Acid Residue

Figure 1

1 AAATTGAAGAGTTTGATCATGGCTCAGATTGAACGCTGGCGGCAGGCCTA

51 ACACATGCAAGTCGAACGGTAACAGGAAGAAGCTTGCTCTTTGCTGACGA

101 GTGGCGGACGGGTGAGTAATGTCTGGGAAACTGCCTGATGGAGGGGGATA

151 ACTACTGGAAACGGTAGCTAATACCGCATAACGTCGCAAGACCAAAGAGG

201 GGGACCTTCGGGCCTCTTGCCATCGGATGTGCCCAGATGGGATTAGCTAG

251 TAGGTGGGGTAACGGCTCACCTAGGCGACGATCCCTAGCTGGTCTGAGAG

301 GATGACCAGCCACACTGGAACTGAGACACGGTCCAGACTCCTACGGGAGG

351 CAGCAGTGGGGAATATTGCACAATGGGCGCAAGCCTGATGCAGCCATGCC

401 GCGTGTATGAAGAAGGCCTTCGGGTTGTAAAGTACTTTCAGCGGGGAGGA

451 AGGGAGTAAAGTTAATACCTTTGCTCATTGACGTTACCCGCAGAAGAAGC

501 ACCGGCTAACTCCGTGCCAGCAGCCGCGGTAATACGGAGGGTGCAAGCGT

551 TAATCGGAATTACTGGGCGTAAAGCGCACGCAGGCGGTTTGTTAAGTCAG

601 ATGTGAAATCCCCGGGCTCAACCTGGGAACTGCATCTGATACTGGCAAGC

651 TTGAGTCTCGTAGAGGGGGGTAGAATTCCAGGTGTAGCGGTGAAATGCGT

701 AGAGATCTGGAGGAATACCGGTGGCGAAGGCGGCCCCCTGGACGAAGACT

751 CACGCTCAGGTGCGAAAGCGTGGGGAGCAAACAGGATTAGATACCCTGGT

801 AGTCCACGCCGTAAACGATGTCGACTTGGAGGTTGTGCCCTTGAGGCGTG

851 GCTTCCGGAGCTAACGCGTTAAGTCGACCGCCTGGGGAGTACGGCCGCAA

901 GGTTAAAACTCAAATGAATTGACGGGGGCCCGCACAAGCGGTGGAGCATG

951 TGGTTTAATTCGATGCAACGCGAAGAACCTTACCTGGTCTTGACATCCAC

1001 GGAAGTTTTCAGAGATGAGAATGTGCCTTCGGGAACCGTGAGACAGGTGC

1051 TGCATGGCTGTCGTCAGCTCGTGTTGTGAAATGTTGGGTTAAGTCCCGCA

1101 ACGAGCGCAACCCTTATCCTTTGTTGCCAGCGGTCCGGCCGGGAACTCAA

1151 AGGAGACTGCCAGTGATAAACTGGAGGAAGGTGGGGATGACGTCAAGTCA

1201 TCATGGCCCTTACGACCAGGGCTACACACGTGCTACAATGGCGCATACAA

1251 AGAGAAGCGACCTCGCGAGAGCAAGCGGACCTCATAAAGTGCGTCGTAGT

1301 CCGGATTGGAGTCTGCAACTCGACTCCATGAAGTCGGAATCGCTAGTAAT

1351 CGTGGATCAGAATGCCACGGTGAATACGTTCCCGGGCCTTGTACACACCG

1401 CCCGTCACACCATGGGAGTGGGTTGCAAAAGAAGTAGGTAGCTTAACCTT

1451 CGGGAGGGCGCTTACCACTTTGTGATTCATGACTGGGGTGAAGTCGTAAC

1501 AAGGTAACCGTAGGGGAACCTGCGGTTGGATCACCTCCTTA

Figure 2



clade_252
clade_253
clade_260
clade_262
clade_309
clade_331
clade_354
clade_360
clade_408
clade_444
clade_478
clade_494
clade_537
clade_553
Clostridium_butyricum
Clostridium_tertium
Clostridium_disporicum
Clostridium_hylemonae
Lachnospiraceae_bacterium_5_1_57FAA
Coprococcus_comes
Blautia_producta
Clostridium_innocuum
Clostridium_mayombei
Ruminococcus_gnavus
Clostridium_bolteae
Clostridium_symbiosum
Eubacterium_rectale
Faecalibacterium_prausnitzii
Clostridium_orbiscindens
Ruminococcus_bromii
Collinsella_aerofaciens

Figure 3




Figure 4



Red
Green
Orange
Blue
Purple
chao1: Sample0
Rarefaction Measure: chao1
Sequences Per Sample
0
1000
2000
3000
4000
5000
6000
7000
8000
9000
10000

Figure 5



PAT1.don1
SER-109
PAT1.pat1d25
D25
PAT1.pat1d14
D14
PAT1.pat1d5
D5
PC2 (31%)
Patient Pretreatment
PAT1.pat1dm1
PC1 (43 %)
PC3 (24 %)

Figure 6



Bacteroides fragilis group species
cfu/g
1.E+10
1.E+09
1.E+08
1.E+07
1.E+06
1.E+05
1.E+04
1.E+03
1.E+02
1.E+01
1.E+00
pre
Wk4
Pt_01
pre
Wk4
Pt_02

Figure 7




Figure 8



Ethanol-treated spores + Vancomycin
Ethanol-treated, gradient purified spores + Vancomycin
Vancomycin control
Vehicle Control
% Survival
100
90
80
70
60
50
40
30
20
10
0
-5 -4 -3 -2 -1 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24
Day

Figure 9



Ethanol-treated spores + Vancomycin
Ethanol-treated, gradient purified spores + Vancomycin
Vancomycin Control
Vehicle Control
% Survival
100
90
80
70
60
50
40
30
20
10
0
-5 -4 -3 -2 -1 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24
Day

Figure 10



Relapse, N1962 + vanco
Relapse, Vanco control
Relapse, Vehicle Control
% Survival
100
90
80
70
60
50
40
30
20
10
0
-5 -4 -3 -2 -1 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24
Day

Figure 11




Figure 12




BUTANOATE METABOLISM
Glycolysis
Pyruvate
Acetyl-CoA
Fatty acid degradation
Diacetyl
(S)-3-Acetoin
(S,S)-Butane-2,3-diol
meso-Butane-2,3-diol
(R,R)-Butane-2,3-diol
(R)-3-Acetoin
Citrate cycle
(R)-Malate
Fumarate
Oxaloacetate
Butanoyl-CoA
Butanol
1-Butanol
Butyrate
Butanoyl-CoA
Crotonoyl-CoA
(R)-3-Hydroxybutanoyl-CoA
(S)-3-Hydroxybutanoyl-CoA
2-Hydroxybutanoyl-CoA
2-Hydroxybutanoate
2-Oxobutanoate
Propanoyl-CoA
Propanoate metabolism
Amino acid metabolism
Alanine, aspartate and glutamate metabolism
Arginine and proline metabolism
Valine, leu and isoleu metabolism
Synthesis and degradation of ketone bodies
3-Butenoyl-CoA
3-Butenoate
3-Butyn-1-ol
3-Butyn-1-al

Figure 13


PROPANOATE METABOLISM
Propanoyl phosphate
Propanoyl CoA
Propanal
Propanol
Propanoic acid
Propanoyl adenylate
Propionaldehyde
Propionate
Propanoyl-CoA
Propan-1-ol
Propan-1-al
Propanoyl-CoA
Propanoyl-CoA
Propanoyl-CoA



PYRUVATE METABOLISM
Glycine, serine and threonine metabolism
Glycolysis
Glycerolipid metabolism
Methylglyoxal
Acetaldehydedecarboxylase
3-Hydroxypalmitoyldecarboxylase
Phenylalanine degradation
Nicotinate and nicotinamide metabolism
Valine, leucine and isoleucine biosynthesis
Pyruvate
Oxaloacetate
Formate
Glycolysate metabolism
2-Hydroxy-3-oxobutanoate
Lipoamide-E
Dihydrolipoamide-E
S-Acetyldihydrolipoamide-E
TPP
Acetyl-CoA
Propanoate metabolism
Glyoxylate metabolism
Citrate cycle
L-Malate
Butanoate metabolism
Synthesis and degradation of ketone bodies
(R)-3-Hydroxybutanoyl-CoA
Acetoacetyl-CoA
2-Propenoate
Leucine biosynthesis
3-Carboxy-3-hydroxy-4-methylpentanoate
Isoleucine biosynthesis
Homocitrate
Fatty acid biosynthesis
Malonyl-CoA
Acetolactate
Acetohydroxybutanoate
Acetoin
Acetolactate
(R)-2,3-Butanediol
(S)-2-Acetolactate
(S)-2,3-Butanediol
Propane-1,2-diol
Lactaldehyde
L-Lactaldehyde
D-Lactaldehyde
D-Lactate
L-Lactate
Acetyl-P
Acetate
Acetaldehyde

Figure 15



Define Disease vs Health Phenotypes
Compute Network Ecologies for Each Phenotype
Define Networks in Intersections Associated with Health
Define Network Ecology BioPriority Score
Define Phylogenetic Network Classes & Keystone OTUs
Define Functional Network Classes & Keystone Pathways
Screen Networks In Vivo & In Vitro based on Desired Biological Characteristics
Network Ecology Computation Detail
Sample Microbiota Taxonomic or Functional Profiles
Compute Binary Co-Occurrence Matrix for Each Sample (0 or 1, unless weighted)
Define all nodes (OTUs) & edges (co-occurrence) across all samples
S1
S2
S3
S4

Figure 16




Figure 17



Define Biologically Relevant Thresholds
Network Size (# of OTUs)
Network Pervasiveness
Cluster Networks Based on OTU content, OTU Phylogenetic Parameters, and Functional Metabolic Properties
Network Relatedness
OTU Phylogenetic Relatedness
Phylogenetic Classes
Functional Classes
Define Class Network Ecologies
e.g. shown Phylogenetic Classes
Class Network Relatedness
OTU Phylogenetic Relatedness

Figure 18



Health General (Hgen)
Disease Donor.fail (DdonF)
Disease pre.treatment (DpreF)
Health donor.success (Hdon)
Health post.treatment (Hpost)
H1
HD5.d
D1
D1.r
H2.d
HD2.d
HD3.d
HD4.d
HD4
H2
HD2
HD3
HD4.r
H2.r
HD2.r
HD3.r

Figure 19



Clade 1
Clade 2
Clade 3
A
B
C
D
E
Node
Statistically Supported Node
A, B, C, D, & E = OTUs (a.k.a leaves of tree)

Figure 20



2100
2102
PROCESSOR
2104
CHIPSET
2106
MEMORY
2108
STORAGE DEVICE
2110
KEYBOARD
2112
GRAPHICS ADAPTER
2114
POINTING DEVICE
2116
NETWORK ADAPTER
2118
DISPLAY
2120
MEMORY CONTROLLER HUB
2122
I/O CONTROLLER HUB

Figure 21

摘要

本發明提供了含有細菌的組合的治療組成，為了維護或恢復哺乳類患者胃腸道中的健康微生物。