



(19) **United States**

(12) **Patent Application Publication**
Patel et al.

(10) **Pub. No.: US 2007/0055209 A1**

(43) **Pub. Date: Mar. 8, 2007**

(54) **SELF CONTAINED WOUND DRESSING APPARATUS**

Publication Classification

(76) Inventors: **Harish A. Patel**, Norfolk, MA (US);
Dianne Acheson, Norwood, MA (US)

(51) **Int. Cl.**
A61M 1/00 (2006.01)
(52) **U.S. Cl.** **604/315; 604/319**

Correspondence Address:
CARTER, DELUCA, FARRELL & SCHMIDT, LLP
445 BROAD HOLLOW ROAD
SUITE 225
MELVILLE, NY 11704 (US)


(57) **ABSTRACT**

(21) Appl. No.: **11/516,216**
(22) Filed: **Sep. 6, 2006**

The composite wound dressing apparatus promotes healing of a wound via the use of an external peristaltic vacuum pump. The external peristaltic pump applies a vacuum pressure to the wound to effectively draw wound fluid or exudate away from the wound bed. The external peristaltic pump is tethered to the wound dressing and is portable, preferably, carried by the patient in a support bag, which permits patient mobility. Moreover, the patient does not need to be constrained for any period of time while exudate is being removed from the wound.

Related U.S. Application Data

(60) Provisional application No. 60/714,912, filed on Sep. 7, 2005.






FIG. 1




FIG. 1A




FIG. 2




FIG. 3




FIG. 4




FIG. 5

SELF CONTAINED WOUND DRESSING APPARATUS

CROSS-REFERENCE TO RELATED APPLICATIONS

[0001] This patent application claims priority to and the benefit of U.S. Provisional Patent Application No. 60/714, 912, filed in the U.S. Patent and Trademark Office on Sep. 7, 2006.

BACKGROUND

[0002] 1. Technical Field

[0003] The present disclosure relates to an apparatus for treating an open wound, and, more specifically, relates to a self contained wound dressing with an external portable pump system which draws wound fluids into a collection canister supported by the patient.

[0004] 2. Description of Related Art

[0005] Wound closure involves the migration of epithelial and subcutaneous tissue adjacent the wound towards the center of the wound until the wound closes. Unfortunately, closure is difficult with large wounds or wounds that have become infected. In such wounds, a zone of stasis (i.e. an area in which localized swelling of tissue restricts the flow of blood to the tissues) forms near the surface of the wound. Without sufficient blood flow, the epithelial and subcutaneous tissues surrounding the wound not only receive diminished oxygen and nutrients, but, are also less able to successfully fight microbial infection and, thus, are less able to close the wound naturally. Such wounds have presented difficulties to medical personnel for many years.

[0006] Wound dressings have been used in the medical industry to protect and/or facilitate healing of open wounds. One popular technique has been to use negative pressure therapy, which is also known as suction or vacuum therapy. A variety of negative pressure devices have been developed to allow excess wound fluids, i.e., exudates to be removed while at the same time isolating the wound to protect the wound and, consequently, effect recovery time. Various wound dressings have been modified to promote the healing of open wounds.

[0007] Issues that continually need to be addressed when using a wound dressing include ease of use, efficiency of healing a wound, portability and negative pressure control capabilities. Thus, there remains a need to constantly improve negative pressure wound dressings for open wounds.

SUMMARY

[0008] In accordance with a preferred embodiment, a wound dressing apparatus includes a wound dressing member dimensioned for positioning relative to a wound bed, a portable vacuum pump in fluid communication with the wound dressing member for applying subatmospheric pressure to facilitate removal of fluid from the wound dressing member, and being carried by the body of a patient, and a collection canister carried by the body of the patient and in fluid communication with the vacuum pump for collecting fluids removed from the wound dressing member. Preferably, the vacuum source includes a peristaltic vacuum pump

and is adapted to produce subatmospheric pressure ranging between about 20 mmHg and about 500 mmHg, more preferably, about 75 mmHg to about 125 mmHg. The collection canister may include an absorbent material to contain the fluid removed from the wound dressing member. Preferably, the apparatus also include a body support bag which is adapted for mounting to the patient. The body support bag may have a pouch for retaining at least one of the collection canister and vacuum pump.

[0009] The vacuum pump preferably includes control means to control operation thereof. A pressure sensor may be incorporated with the control means to detect pressure at a predetermined location relative to the wound dressing member, and send a corresponding signal to the control means. The control means may include a controller adapted to control or vary the output of the vacuum source. The vacuum pump preferably includes a self-contained battery.

[0010] The preferred wound dressing member includes a lower member positionable adjacent the wound bed, an upper absorbent member positionable adjacent the lower member, and a top member. The upper absorbent member comprises a material selected from the group consisting of foams, nonwoven composite fabrics, cellulosic fabrics, super absorbent polymers, and combinations thereof. The upper absorbent member may also include at least one of a medicament, an anti-infective agent, an antimicrobial, polyhexamethylene biguanide (hereinafter, "PHMB"), antibiotics, debridement agents, analgesics, healing factors, vitamins, growth factors and nutrients.

[0011] In another preferred embodiment, a wound dressing apparatus, includes a wound dressing member dimensioned for positioning relative to a wound bed, a portable vacuum pump in fluid communication with the wound dressing member for applying subatmospheric pressure to facilitate removal of fluid from the wound dressing member, and having a self contained battery for operating the vacuum pump, a collection canister in fluid communication with the vacuum pump for collecting fluids removed from the wound dressing member and a body support bag attachable to the body of the patient and having a pouch for retaining at least one of the collection canister and the vacuum pump.

[0012] A method for facilitating healing of a wound is also disclosed. The method includes the steps of positioning a wound dressing member relative to a wound bed, introducing a portable vacuum pump to be in fluid communication with the wound dressing member for applying subatmospheric pressure to facilitate removal of fluid from the wound dressing member, connecting a collection canister in fluid communication with the vacuum pump for collecting fluids removed from the wound dressing member, mounting a body support bag having a retaining pouch and positioning at least one of the collection canister and the vacuum pump into the retaining pouch of the body support bag.

BRIEF DESCRIPTION OF THE DRAWINGS

[0013] Various embodiments of the subject wound dressing are described herein with reference to the drawings wherein:

[0014] FIG. 1 is a partial cross-sectional view of a self contained wound dressing apparatus in accordance with the principles of the present disclosure illustrating the wound dressing member, pump system and collection canister;

[0015] FIG. 1A is a cross-sectional view taken along the lines 1A-1A of FIG. 1 illustrating the vacuum tube of the wound dressing apparatus;

[0016] FIG. 2 is a schematic view of the pump system;

[0017] FIG. 3 is a view illustrating a body support bag for containing the collection canister and/or pump system;

[0018] FIG. 4 is a view illustrating an alternate embodiment of the body support bag of FIG. 3; and

[0019] FIG. 5 is a view illustrating an alternate embodiment of the self contained wound dressing apparatus.

DESCRIPTION OF THE PREFERRED EMBODIMENTS

[0020] The composite wound dressing apparatus of the present disclosure promotes healing of a wound via the use of an external peristaltic vacuum pump. The external peristaltic pump applies a vacuum pressure to the wound to effectively draw wound fluid or exudate away from the wound bed. The external peristaltic pump is tethered to the wound dressing and is portable, preferably, carried by the patient, which permits patient mobility. Moreover, the patient does not need to be constrained for any period of time during therapy and while exudates is being removed from the wound.

[0021] Referring now to FIG. 1, the wound dressing apparatus 100 in accordance with a preferred embodiment of the present disclosure is illustrated. Wound dressing apparatus 100 includes composite wound dressing 102 and pump system 104 tethered to the wound dressing 102. Wound dressing 102 is in the form of an article with multiple layers arranged in juxtaposed or superposed relation. The multiple layers include, but are not limited to a base layer 106, a packing/absorbent layer 108, and a non-porous adherent top layer 110.

[0022] The base layer 106 is in direct contact with the wound bed "w". The base layer 106 is typically porous and non-adherent. "Non-adherent" as used herein refers to a material that does not adhere to tissues in and around the wound bed. "Porous" as used herein refers to a material which contains numerous small perforations or pores which allow wound fluids of all kinds to pass through the material to the dressing layers above. The passage of wound fluid through the porous material is preferably unidirectional such that wound exudate does not flow back to the wound bed. This direction flow feature could be in the form of directional apertures imparted into the material layer, a lamination of materials of different absorption to the base layer 106 or specific material selection that encourages directional flow. Exemplary materials used as the base layer 106 include a contact layer sold under the trademark XEROFLO® by Kendall Corp, a division of TycoHealthcare.

[0023] In addition, agents such as hydrogels and medicaments could be bonded or coated to the base layer 106 to reduce bioburden in the wound, promote healing and reduce pain associated with dressing changes or removal. Medicaments include, for example, antimicrobial agents, growth factors, antibiotics, analgesics, and the like. Furthermore, when an analgesic is used, the analgesic could include a mechanism that would allow the release of that agent prior to dressing removal or change.

[0024] The layer proximal to the base layer 106 is the packing/absorbent layer 108. The packing/absorbent layer 108 is intended to absorb and capture wound fluid and exudates. Exemplary materials used as the packing/absorbent layer 108 include the antimicrobial dressing sold under the trademark KERLIX® by Kendall Corp., a division of TycoHealthcare. Those skilled in the art will recognize that the packing/absorbent layer 108 can be formed into any suitable shape. The only requirement as to shape is that the packing/absorbent layer 108 is suitable to conform to a particular shape of the wound.

[0025] A further use for the packing/absorbent layer 108 is to decrease the incidence of infection in the wound bed. Hence, the packing/absorbent layer 108 may be treated with medicaments. Medicaments include, for example, an anti-infective agent such as an antiseptic or other suitable antimicrobial or combination of antimicrobials, polyhexamethylene biguanide (hereinafter, "PHMB"), antibiotics, analgesics, healing factors such as vitamins, growth factors, nutrients and the like, as well as a simple flushing with isotonic saline solution.

[0026] With continued reference still to FIG. 1, the top layer 110 encompasses the perimeter of the wound dressing 102 to surround the wound bed "w" to provide an occlusive seal around the perimeter of the wound bed "w". The top layer 110 may include an adhesive bonded to an area that surrounds the wound bed "w" or may incorporate an additional layer which has the adhesive. The adhesive must provide acceptable adhesion to the tissue "t" surrounding the wound bed "w" skin, e.g., the periwound area, and be acceptable for use on skin without contact deterioration (for example, the adhesive should preferably be non-irritating and non-sensitizing.) The adhesive may be semi-permeable to permit the contacted skin to breathe and transmit moisture. Alternatively, the adhesive may be impermeable. Additionally, the adhesive could be activated or de-activated by an external stimulus such as heat or a given fluid solution or chemical reaction. Adhesives include, for example, the ULTEC Hydrocolloid Dressing, by Kendall Corp., a division of TycoHealthcare.

[0027] The top layer 110 is preferably in the form of a sheet mounted proximal to the packing/absorbent layer 108. In a preferred embodiment, the peripheral portions 110P of the top layer 110 includes an adhesive and is secured to the tissue "t" about the wound bed "w". The peripheral portions 110P may be secured to the periphery of base layer 102 if desired. It is anticipated that removable liners may also be used to protect the adhesive surface of the top layer 110 prior to use.

[0028] The top layer 110 may incorporate a flexible material, e.g., resilient or elastomeric, that seals the top of the wound dressing 102. In one embodiment, the top layer 110 includes the transparent dressing manufactured under the trademark Polyskin II® by Kendall Corp, a division of TycoHealthcare. POLYSKIN® II is a transparent, semi-permeable material which permits moisture and oxygen exchange with the wound site, and provides a barrier to microbes and fluid containment. In the alternative, the top layer 110 may be impermeable. The transparency of the top layer 110 provides a visual indication of the status of the wound dressing and more particularly, the status of the saturation level of the layers of the wound dressing. The top

layer 110 further includes a vacuum port or connector 112 in fluid communication with the interior of the wound dressing 102. The vacuum port 112 may be a separate component attached to the top layer 110 and connected thereto by conventional means or integrally formed with the top layer 110. The vacuum port 112 may have a valve built therein, e.g., a one way valve, to permit exudates to flow in one direction only, i.e., away from the wound dressing 102 toward the pump system 104. Vacuum port 112 is adapted to be releasably connected to the pump system 104 as will be discussed and may or may not include structure for releasable connection to the pump system.

[0029] Referring still to FIG. 1, the pump system 104 will be discussed. The pump system 104 includes a vacuum source 114, inlet tubing 116 connecting the inlet side of the vacuum source 114 to the vacuum port 112 of the wound dressing 102 and a collector canister 118 connected to the outlet side of the vacuum source 114 by outlet tubing 120. In the alternative, the collection canister 118 may be disposed "in-line" between the vacuum source 114 and the wound dressing 102. Vacuum source 114 may be any type of pump that is biocompatible and maintains or draws adequate and therapeutic vacuum levels. Preferably, the vacuum level to be achieved is in a range between about 20 mmHg and about 500 mmHg, more preferably, about 75 mmHg and about 125 mmHg. The pump 114 may be removable, reusable, and/or rechargeable. Typically, the pump 114 is a pump of the diaphragmatic or peristaltic type, or the like, in which the moving part(s) draw exudate out of the wound bed into the wound dressing by creating areas or zones of decreased pressure e.g., vacuum zones with the wound dressing 102. This area of decreased pressure preferably communicates with the wound bed "w" to facilitate removal of the fluids therefrom and into the packing/absorbent layer 108. The pump 114 may be actuated by any means known by those skilled in the art. In a preferred embodiment of the present disclosure, the pump 114 is a peristaltic pump. One suitable peristaltic pump is the Kangaroo PET External Feeding Pump manufactured by Kendall Corp., a division of Tyco-Healthcare. Another suitable peristaltic pump may be the model 101 V/R pmy MK2 manufactured by Watson Marlow LTD of England. Preferably, the peristaltic pump produces subatmospheric pressure ranging from about 20 mmHg to about 500 mmHg. A suitable diaphragm pump includes model NMP 850 KNDC manufactured by KNF Neuberger of Germany.

[0030] The inlet and outlet tubings 116,120 may be any suitable flexible tubing fabricated from elastomeric and/or polymeric materials. The inlet tubing 116 is preferably releasably connected to the vacuum port 112 through conventional means including a friction fit, bayonet coupling, snap fit or the like. The collection canister 118 may be any flexible disposable pouch or the like. The collection canister 118 may include a super absorbent material such as super-absorbent polymers (SAP), silica gel, sodium polyacrylate, potassium polyacrylamide and related compounds to consolidate or contain wound drainage or debris. The collection canister 118 is preferably transparent to permit viewing into the interior of the canister 118 to assist the patient in determining the remaining capacity of the collection canister 118 and quality of exudates.

[0031] Referring to FIG. 2, the pump system 104 preferably includes an internal self contained battery source 122,

a pressure sensor or transducer 124 to monitor pressure within the wound dressing, and self-contained regulation or control means 126. The pressure sensor 124 is preferably disposed within the interior of the wound dressing 102 and is in electrical connection with the control means 126 through an electrical wiring 128. (FIG. 1) One suitable pressure sensor is the Dynamic ICP Pressure Sensor of the Pressure Division of PCB Piezotronics, Inc. The pressure sensor 124 would also provide information to assist in detecting a leak in the wound dressing 102. The electrical wiring 128 may be passed through the vacuum port 112 and through inlet tubing 116 or on the exterior surface of the inlet tubing 116. Alternatively, the electrical wiring 128 may pass through a conduit or channel in the wall of the vacuum port 112 and/or the inlet tubing 116. FIG. 1A illustrates the various arrangements where the electrical wiring 128 passes through the channel of the tubing 116 or the central lumen of the tubing 116. The control means 126 is preferably incorporated within the pump housing of the pump 114. The control means 126 may incorporate a motor controller/driver 130 including processing and drive software or circuitry to control or vary the drive voltage to the motor of the pump 114 responsive to the pressure sensed by the pressure sensor 124 and/or other operational parameters including operational time constraints etc. For example, the motor controller/driver may be programmed to run only for a predetermined period of time after start-up. The output of the motor of the pump 114 may be increased or decreased, or initiated or discontinued, as controlled by the control means 126. The regulation or control means 126 may also have an alarm such as a visual, audio or tactile sensory alarm (e.g., vibratory etc.) to indicate to the patient when specific conditions have been met (e.g., the desired vacuum level, loss of vacuum or leak). An override switch 130 may also be incorporated within the pump system to permit the patient to optionally initiate or terminate operation of the pump as desired without input from the control means 126. Wireless means are also envisioned to operate the pump 114 through the control means 126.

[0032] With reference now to FIG. 3, there is illustrated a body support bag 134 for supporting at least the canister and/or the pump 114. As discussed, the pump system 104 is adapted for mounting to the body of the patient to be a self contained portal unit. In this regard, the pump system 104 may be at least partially carried or supported by the body support bag 134. The body support bag 134 generally includes a pouch 136 and at least one strap 138, preferably two straps, for securing the pouch 136 to the body of the patient. The body support bag 134 is intended to receive and store at least the collection canister 118 and/or the pump 114. The body support bag 134 may be worn about the waist of the patient. This is desirable in that it may reduce the length of tubing needed depending on the location of the wound. In addition, the pouch 136 may be located adjacent the abdomen of the patient which may present a significantly enhanced ability to conceal the system. The inlet and outlet tubings 116,120 may be secured to the body with tape or the like, or, optionally, may be unsecured and disposed beneath the patient's clothing. Thus, the body support bag 134 permits the patient to move without restrictions or limitations, and provides an entirely portable capability to the patient during wound drainage and healing.

[0033] FIG. 4 illustrates an alternate embodiment of the body support bag. In accordance with this embodiment, the

body support bag **140** is adapted for mounting to the shoulder of the patient and has a pouch **142**. In other respects, the body support bag **140** functions in a similar manner to the body support bag of FIG. 3.

[0034] In use, the wound dressing apparatus **100** is positioned within the wound bed “w” as shown in FIG. 1 and secured about the wound “w” in the manner discussed hereinabove. The pump **114** and/or collection canister **118** are positioned within the pouch **136** of the body support bag **134** (or support bag **140**). The body support bag **134, 140** is mounted to the patient either about the waist, shoulder, leg, etc . . . with the straps **134**. The inlet and outlet tubings **114,120** may be secured to the patient’s body with tape or the like. Thereafter, the pump **114** is initiated to create a zone of subatmospheric pressure (i.e., a state of vacuum) within the wound dressing **100**. The pump **114** may be initiated via the manual override switch **130**, or may be started via the pressure sensor **124** which detects the lack of subatmospheric pressure within the wound dressing apparatus **100** and sends a corresponding signal to the control means **126**. The control means **126**, in turn, activates the pump **114**. As the subatmospheric pressure within the wound dressing **102** increases, the top layer **110** and packing/absorbent layer **108** may collapse. Fluids are drawn away from the wound bed “w” and into the packing/absorbent layer **106** of the wound dressing **102**. These fluids and/or exudates may be removed from the packing/absorbent layer **106** under the negative pumping energy of the pump **114**. The fluids are delivered through the inlet and outlet tubings **116,120** to be collected within the collection canister **118**. Once the desired level of subatmospheric pressure is achieved as detected by, e.g., the pressure sensor **124**, the pressure sensor **124** sends a signal to the control means **126**. The control means **126** may either terminate operation of the pump **114** or alternatively vary the speed or output (e.g., decrease) of the pump **114**. In this vacuum state, wound fluid and exudates are continually drawn into the packing/absorbent layer **106**. After a period of time, the wound dressing **102** may lose its vacuum state as detected by the pressure sensor **124** or detected visually by the patient. When the loss of a desired vacuum level is achieved, the pressure sensor **124** sends a signal to the control means **126** to activate or increase the output of the pump **114**. The pump **114** removes the fluid from the packing/absorbent layer **108** and reestablishes the vacuum state within the wound dressing **102**. As indicated hereinabove, in the alternative, the pump **114** may be initiated via the manual override switch **130** when e.g., the patient sees that the collection canister **118** is full. This process may continue several times during wound healing during one application or a series of applications.

[0035] Once the wound is fully healed, the wound closure apparatus and pump system may be disposed. The body support bag may also be disposed or cleaned for subsequent use. The pump may be sterilized and reused as well.

[0036] FIG. 5 illustrates another embodiment of the present disclosure. In accordance with this embodiment, wound dressing apparatus **200** includes micropump **202** which is adapted for mounting within absorbent layer **204**. Micropump **202** has a length ranging from about 1 to 3 inches and a relatively small diameter, preferably, no greater than about one inch. The micropump **202** may be any type of pump that is biocompatible and maintains or draws adequate and therapeutic vacuum levels. The micropump

202 may be removable, reusable, and/or rechargeable. The micropump **202** may be a pump of the diaphragmatic, peristaltic or rotary type, or the like, in which the moving part(s) draw exudates out of the wound bed into the wound dressing by creating areas or zones of decreased pressure e.g., vacuum zones with the wound dressing apparatus **200**. This area of decreased pressure preferably communicates with the wound bed “w” to facilitate removal of the fluids therefrom and into the absorbent layer **204**. The micropump **202** may be actuated by any means known by those skilled in the art. In a preferred embodiment of the present disclosure, the micropump **202** is a peristaltic pump. One suitable micropump is manufactured by Piab Vacuum Products in Hingham, MA. Preferably, the peristaltic pump produces subatmospheric pressure ranging from about 20 mmHg to about 500 mmHg.

[0037] Absorbent layer **204** is preferably a foam filled dressing which is transparent. The foam may be a resilient, liquid absorbent, porous, polymer-based foam. The foam may be a dispensable liquid which at least partially solidifies to a crystal-like arrangement defining hollow tubes to allow exudates drainage. The foam is dispensed within the wound bed and is potentially collapsible to expel air from the foam channels. The foam may be an expandable hydrophilic foam which is capable of absorbing fluid from a wound and maintain the wound bed moist. The hollow tubes or voids defined by the foam also provide a means to conduct electricity, heat, cold, and ultrasound. The hollow tubes or voids also provide a bioactive scaffold for tissue growth. A thin film transparent top layer **205** is secured about the wound area to enclose the wound.

[0038] The self contained battery source and control circuitry may be mounted within housing **206** which is connected to belt **208**. Belt **208** is adapted for mounting to the body of a patient, e.g., around the waist area and may include VELCRO® means for securing about the patient. Belt **208** may further support canister **210** which receives the fluid exudates from pump **202** through tube **212**. Tube **214** extends from housing **206** to pump **202** and may incorporate electronic wires etc. for operating the pump. In the alternative, tube **212** may incorporate the electrical wires within, e.g., a lumen, and extend from the housing to pump **202** and canister **210**.

[0039] It is further contemplated that the wound dressing apparatus may incorporate external means or applications to stimulate tissue growth and/or healing. For example, an auxiliary treatment apparatus may be incorporated into the wound dressing apparatus to impart electrical or mechanical energy for the treatment of the tissue such as, for instance, directing electrical, thermal or vibratory energy on the wound area and/or introducing various drugs into the human body through the skin. The auxiliary treatment apparatus may be incorporated into the housing of the pump **202** as shown schematically as reference numeral **216** and operated via a control means discussed hereinabove. One suitable auxiliary treatment apparatus may include an ultrasonic transducer. Other sensor types are also contemplated for incorporation into the wound dressing apparatus including oxygen, chemical, microbial and/or temperature sensors. The detection of oxygen adjacent the wound area would assist the clinician in determining the status of wound healing. The presence of an elevated temperature may be indicative of an infection. The pump system may incorporate

circuitry to communicate with a computer, e.g., a hand-held PALM® device through wireless means.

[0040] While the disclosure has been illustrated and described, it is not intended to be limited to the details shown, since various modifications and substitutions can be made without departing in any way from the spirit of the present disclosure. For example, it is envisioned the subject matter of the commonly assigned patent application filed concurrently herewith under Express Mail Certificate No. EL 985194511 US, and which claims priority to provisional application No. 60/714,812, filed on Sep. 6, 2006, and the subject matter of the commonly assigned patent application filed concurrently herewith under Express Mail Certificate No. EL 985194499, and which claims priority to provisional application No. 60/714,805, filed on Sep. 7, 2006, (the entire contents of each application being incorporated herein) may be incorporated into the present disclosure. As such, further modifications and equivalents of the invention herein disclosed can occur to persons skilled in the art using no more than routine experimentation, and all such modifications and equivalents are believed to be within the spirit and scope of the disclosure as defined by the following claims.

What is claimed is:

- 1. A wound dressing apparatus, which comprises:
 - a wound dressing member dimensioned for positioning relative to a wound bed;
 - a portable vacuum pump in fluid communication with the wound dressing member for applying subatmospheric pressure to facilitate removal of fluid from the wound dressing member, the vacuum pump adapted to be carried by the body of a patient; and
 - a collection canister carried by the body of the patient and in fluid communication with the vacuum pump for collecting fluids removed from the wound dressing member.
- 2. The wound dressing apparatus according to claim 1 wherein the vacuum source includes a peristaltic vacuum pump.
- 3. The wound dressing apparatus according to claim 2 wherein the vacuum pump is adapted to produce subatmospheric pressure ranging between about 20 mmHg and about 500 mmHg.
- 4. The wound dressing apparatus according to claim 1 wherein the collection canister includes an absorbent material to contain the fluid removed from the wound dressing member.
- 5. The wound dressing apparatus according to claim 1 including a body support bag, the body support bag adapted for mounting to the patient and having a pouch for retaining at least one of the collection canister and vacuum pump.
- 6. The wound dressing apparatus according to claim 1 wherein the vacuum pump includes control means to control operation thereof.
- 7. The wound dressing apparatus according to claim 6 including a pressure sensor adapted to detect pressure at a predetermined location relative to the wound dressing member, and send a corresponding signal to the control means.

8. The wound dressing apparatus according to claim 6 wherein the control means includes a controller adapted to control or vary the output of the vacuum source.

9. The wound dressing apparatus according to claim 1 wherein the vacuum pump includes a self-contained battery.

10. The wound dressing apparatus according to claim 1 wherein the wound dressing member includes a lower member positionable adjacent the wound bed, an upper absorbent member positionable adjacent the lower member, and a top member.

11. The wound dressing apparatus according to claim 10 wherein the upper absorbent member comprises a material selected from the group consisting of foams, nonwoven composite fabrics, cellulosic fabrics, super absorbent polymers, and combinations thereof.

12. The wound dressing apparatus according to claim 11 wherein the upper absorbent member includes at least one of a medicament, an anti-infective agent, an antimicrobial, polyhexamethylene biguanide (hereinafter, "PHMB"), antibiotics, analgesics, healing factors, vitamins, growth factors and nutrients.

13. A wound dressing apparatus, which comprises:

- a wound dressing member dimensioned for positioning relative to a wound bed;
- a portable vacuum pump in fluid communication with the wound dressing member for applying subatmospheric pressure to facilitate removal of fluid from the wound dressing member, the vacuum pump having a self contained battery for operating the vacuum pump;
- a collection canister in fluid communication with the vacuum pump for collecting fluids removed from the wound dressing member; and
- a body support bag attachable to the body of the patient, the body support bag including a pouch for retaining at least one of the collection canister and the vacuum pump.

14. A method for facilitating healing of a wound, comprising the steps of:

- positioning a wound dressing member relative to a wound bed;
- introducing a portable vacuum pump to be in fluid communication with the wound dressing member for applying subatmospheric pressure to facilitate removal of fluid from the wound dressing member;
- connecting a collection canister in fluid communication with the vacuum pump for collecting fluids removed from the wound dressing member;
- mounting a body support bag to the body of the patient, the body support bag including a retaining pouch; and
- positioning at least one of the collection canister and the vacuum pump into the retaining pouch of the body support bag.

* * * * *